PostgreSQL 7.3.21 Documentation

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

PostgreSQL 7.3.21 Tutorial xi
Preface xiv
1. What's In This Book xiv
1. Getting Started 1
1.1. Installation 1
1.2. Architectural Fundamentals 1
1.3. Creating a Database 1
1.4. Accessing a Database 3
2. The SQL Language 5
2.1. Introduction 5
2.2. Concepts 5
2.3. Creating a New Table 5
2.4. Populating a Table With Rows 6
2.5. Querying a Table 7
2.6. Joins Between Tables 8
2.7. Aggregate Functions 10
2.8. Updates 11
2.9. Deletions 12
3. Advanced Features 13
3.1. Introduction 13
3.2. Views 13
3.3. Foreign Keys 13
3.4. Transactions 14
3.5. Inheritance 15
3.6. Conclusion 16
PostgreSQL 7.3.21 User's Guide xvii
Preface xxvi
1. What is PostgreSQL? xxvi
2. A Short History of PostgreSQL xxvi
3. What's In This Book xxviii
4. Overview of Documentation Resources xxviii
5. Terminology and Notation xxx
6. Bug Reporting Guidelines xxx
1. SQL Syntax 1
1.1. Lexical Structure 1
1.2. Value Expressions 7
2. Data Definition 11
2.1. Table Basics 11
2.2. System Columns 12
2.3. Default Values 13
2.4. Constraints 13
2.5. Inheritance 19
2.6. Modifying Tables 21
2.7. Privileges 23
2.8. Schemas 23
2.9. Other Database Objects 27
2.10. Dependency Tracking 27
3. Data Manipulation 29
3.1. Inserting Data 29
3.2. Updating Data 30
3.3. Deleting Data 30
4. Queries 32
4.1. Overview 32
4.2. Table Expressions 32
4.3. Select Lists 40

4.4. Combining Queries 41
4.5. Sorting Rows 42
4.6. LIMIT and OFFSET 42
5. Data Types 44
5.1. Numeric Types 45
5.2. Monetary Type 48
5.3. Character Types 49
5.4. Binary Strings 50
5.5. Date/Time Types 52
5.6. Boolean Type 58
5.7. Geometric Types 58
5.8. Network Address Data Types 61
5.9. Bit String Types 62
5.10. Object Identifier Types 63
5.11. Pseudo-Types 64
5.12. Arrays 65
6. Functions and Operators 69
6.1. Logical Operators 69
6.2. Comparison Operators 69
6.3. Mathematical Functions and Operators 71
6.4. String Functions and Operators 73
6.5. Binary String Functions and Operators 80
6.6. Pattern Matching 82
6.7. Data Type Formatting Functions 86
6.8. Date/Time Functions and Operators 91
6.9. Geometric Functions and Operators 98
6.10. Network Address Type Functions 101
6.11. Sequence-Manipulation Functions 102
6.12. Conditional Expressions 104
6.13. Miscellaneous Functions 105
6.14. Aggregate Functions 109
6.15. Subquery Expressions 110
7. Type Conversion 115
7.1. Overview 115
7.2. Operators 116
7.3. Functions 119
7.4. Query Targets 121
7.5. UNION and CASE Constructs 122
8. Indexes 124
8.1. Introduction 124
8.2. Index Types 124
8.3. Multicolumn Indexes 125
8.4. Unique Indexes 126
8.5. Functional Indexes 126
8.6. Operator Classes 126
8.7. Partial Indexes 127
8.8. Examining Index Usage 129
9. Concurrency Control 131
9.1. Introduction 131
9.2. Transaction Isolation 131
9.3. Explicit Locking 133
9.4. Data Consistency Checks at the Application Level 135
9.5. Locking and Indexes 136
10. Performance Tips 138
10.1. Using EXPLAIN 138
10.2. Statistics Used by the Planner 141
10.3. Controlling the Planner with Explicit JOIN Clauses 143
10.4. Populating a Database 145

A. Date/Time Support 146
A.1. Date/Time Input Interpretation 146
A.2. Date/Time Key Words 147
A.3. History of Units 151
B. SQL Key Words 153
C. SQL Conformance 168
C.1. Supported Features 168
C.2. Unsupported Features 176
Bibliography 183
PostgreSQL 7.3.21 Administrator's Guide clxxxv
Preface cxcv
1. What's In This Book cxcv
1. Installation Instructions 1
1.1. Short Version 1
1.2. Requirements 1
1.3. Getting The Source 3
1.4. If You Are Upgrading 3
1.5. Installation Procedure 4
1.6. Post-Installation Setup 10
1.7. Supported Platforms 11
2. Installation on Windows 15
3. Server Run-time Environment 16
3.1. The PostgreSQL User Account 16
3.2. Creating a Database Cluster 16
3.3. Starting the Database Server 17
3.4. Run-time Configuration 20
3.5. Managing Kernel Resources 34
3.6. Shutting Down the Server 39
3.7. Secure TCP/IP Connections with SSL 39
3.8. Secure TCP/IP Connections with SSH Tunnels 40
4. Database Users and Privileges 42
4.1. Database Users 42
4.2. User Attributes 42
4.3. Groups 43
4.4. Privileges 43
4.5. Functions and Triggers 44
5. Managing Databases 45
5.1. Overview 45
5.2. Creating a Database 45
5.3. Template Databases 46
5.4. Database Configuration 47
5.5. Alternative Locations 47
5.6. Destroying a Database 48
6. Client Authentication 50
6.1. The `pg_hba.conf` file 50
6.2. Authentication methods 54
6.3. Authentication problems 58
7. Localization 59
7.1. Locale Support 59
7.2. Multibyte Support 61
7.3. Single-byte character set recoding 67
8. Routine Database Maintenance Tasks 69
8.1. General Discussion 69
8.2. Routine Vacuuming 69
8.3. Routine Reindexing 72
8.4. Log File Maintenance 72
9. Backup and Restore 74
9.1. SQL Dump 74

9.2. File system level backup 76
9.3. Migration between releases 77
10. Monitoring Database Activity 78
10.1. Standard Unix Tools 78
10.2. Statistics Collector 79
10.3. Viewing Locks 82
11. Monitoring Disk Usage 85
11.1. Determining Disk Usage 85
11.2. Disk Full Failure 86
12. Write-Ahead Logging (WAL) 87
12.1. General Description 87
12.2. Implementation 88
12.3. WAL Configuration 88
13. Regression Tests 91
13.1. Introduction 91
13.2. Running the Tests 91
13.3. Test Evaluation 92
13.4. Platform-specific comparison files 94
A. Release Notes 95
A.1. Release 7.3.21 95
A.2. Release 7.3.20 96
A.3. Release 7.3.19 96
A.4. Release 7.3.18 96
A.5. Release 7.3.17 97
A.6. Release 7.3.16 97
A.7. Release 7.3.15 98
A.8. Release 7.3.14 99
A.9. Release 7.3.13 99
A.10. Release 7.3.12 100
A.11. Release 7.3.11 100
A.12. Release 7.3.10 101
A.13. Release 7.3.9 103
A.14. Release 7.3.8 103
A.15. Release 7.3.7 104
A.16. Release 7.3.6 104
A.17. Release 7.3.5 105
A.18. Release 7.3.4 106
A.19. Release 7.3.3 107
A.20. Release 7.3.2 109
A.21. Release 7.3.1 110
A.22. Release 7.3 111
A.23. Release 7.2.8 123
A.24. Release 7.2.7 123
A.25. Release 7.2.6 124
A.26. Release 7.2.5 125
A.27. Release 7.2.4 125
A.28. Release 7.2.3 126
A.29. Release 7.2.2 126
A.30. Release 7.2.1 127
A.31. Release 7.2 128
A.32. Release 7.1.3 137
A.33. Release 7.1.2 138
A.34. Release 7.1.1 138
A.35. Release 7.1 139
A.36. Release 7.0.3 143
A.37. Release 7.0.2 144
A.38. Release 7.0.1 145
A.39. Release 7.0 145

A.40. Release 6.5.3 153
A.41. Release 6.5.2 153
A.42. Release 6.5.1 154
A.43. Release 6.5 155
A.44. Release 6.4.2 160
A.45. Release 6.4.1 160
A.46. Release 6.4 161
A.47. Release 6.3.2 165
A.48. Release 6.3.1 166
A.49. Release 6.3 167
A.50. Release 6.2.1 172
A.51. Release 6.2 173
A.52. Release 6.1.1 175
A.53. Release 6.1 176
A.54. Release 6.0 178
A.55. Release 1.09 181
A.56. Release 1.02 181
A.57. Release 1.01 182
A.58. Release 1.0 185
A.59. Postgres95 Release 0.03 186
A.60. Postgres95 Release 0.02 189
A.61. Postgres95 Release 0.01 190
PostgreSQL 7.3.21 Programmer's Guide cxci
Preface cxcix
1. What's In This Book cxcix
I. Client Interfaces 1
1. libpq - C Library 4
2. Large Objects 34
3. pgtcl - Tcl Binding Library 42
4. ECPG - Embedded SQL in C 65
5. JDBC Interface 75
6. PyGreSQL - Python Interface 107
II. Server Programming 159
7. Architecture 162
8. Extending SQL: An Overview 165
9. Extending SQL: Functions 168
10. Extending SQL: Types 196
11. Extending SQL: Operators 198
12. Extending SQL: Aggregates 203
13. The Rule System 205
14. Interfacing Extensions To Indexes 227
15. Index Cost Estimation Functions 233
16. Triggers 236
17. Server Programming Interface 243
III. Procedural Languages 278
18. Procedural Languages 281
19. PL/pgSQL - SQL Procedural Language 283
20. PL/Tcl - Tcl Procedural Language 316
21. PL/Perl - Perl Procedural Language 323
22. PL/Python - Python Procedural Language 326
PostgreSQL 7.3.21 Reference Manual cccxxix
Preface cccxxxiii
I. SQL Commands 334
ABORT 336
ALTER DATABASE 337
ALTER GROUP 339
ALTER TABLE 340
ALTER TRIGGER 345

ALTER USER 346
ANALYZE 348
BEGIN 350
CHECKPOINT 352
CLOSE 353
CLUSTER 354
COMMENT 356
COMMIT 358
COPY 359
CREATE AGGREGATE 365
CREATE CAST 368
CREATE CONSTRAINT TRIGGER 371
CREATE CONVERSION 372
CREATE DATABASE 374
CREATE DOMAIN 377
CREATE FUNCTION 379
CREATE GROUP 384
CREATE INDEX 385
CREATE LANGUAGE 389
CREATE OPERATOR 392
CREATE OPERATOR CLASS 397
CREATE RULE 400
CREATE SCHEMA 403
CREATE SEQUENCE 405
CREATE TABLE 408
CREATE TABLE AS 416
CREATE TRIGGER 418
CREATE TYPE 421
CREATE USER 425
CREATE VIEW 428
DEALLOCATE 431
DECLARE 432
DELETE 435
DROP AGGREGATE 437
DROP CAST 438
DROP CONVERSION 439
DROP DATABASE 440
DROP DOMAIN 441
DROP FUNCTION 442
DROP GROUP 444
DROP INDEX 445
DROP LANGUAGE 446
DROP OPERATOR 447
DROP OPERATOR CLASS 449
DROP RULE 450
DROP SCHEMA 451
DROP SEQUENCE 452
DROP TABLE 453
DROP TRIGGER 454
DROP TYPE 456
DROP USER 457
DROP VIEW 458
END 459
EXECUTE 460
EXPLAIN 461
FETCH 463
GRANT 466
INSERT 470

LISTEN 472
LOAD 474
LOCK 475
MOVE 479
NOTIFY 480
PREPARE 482
REINDEX 484
RESET 486
REVOKE 487
ROLLBACK 489
SELECT 490
SELECT INTO 502
SET 503
SET CONSTRAINTS 507
SET SESSION AUTHORIZATION 508
SET TRANSACTION 510
SHOW 511
START TRANSACTION 513
TRUNCATE 514
UNLISTEN 515
UPDATE 517
VACUUM 519
II. PostgreSQL Client Applications 522
clusterdb 523
createdb 525
createlang 528
createuser 530
dropdb 533
droplang 535
dropuser 537
ecpg 539
pg_config 541
pg_dump 543
pg_dumpall 549
pg_restore 552
psql 558
pgtclsh 579
pgtksh 580
vacuumdb 581
III. PostgreSQL Server Applications 584
initdb 585
initlocation 587
ipcclean 588
pg_ctl 589
pg_controldata 592
pg_resetxlog 593
postgres 594
postmaster 597
PostgreSQL 7.3.21 Developer's Guide ..... dcii
1. PostgreSQL Source Code 1
1.1. Formatting 1
2. Overview of PostgreSQL Internals 2
2.1. The Path of a Query 2
2.2. How Connections are Established 2
2.3. The Parser Stage 3
2.4. The PostgreSQL Rule System 4
2.5. Planner/Optimizer 6
2.6. Executor 7

3. System Catalogs 8
3.1. Overview 8
3.2. pg_aggregate 9
3.3. pg_am 9
3.4. pg_amop 11
3.5. pg_amproc 11
3.6. pg_attrdef 11
3.7. pg_attribute 12
3.8. pg_cast 14
3.9. pg_class 15
3.10. pg_constraint 17
3.11. pg_conversion 18
3.12. pg_database 19
3.13. pg_depend 20
3.14. pg_description 21
3.15. pg_group 22
3.16. pg_index 22
3.17. pg_inherits 23
3.18. pg_language 23
3.19. pg_largeobject 24
3.20. pg_listener 25
3.21. pg_namespace 25
3.22. pg_opclass 26
3.23. pg_operator 26
3.24. pg_proc 27
3.25. pg_rewrite 29
3.26. pg_shadow 30
3.27. pg_statistic 30
3.28. pg_trigger 32
3.29. pg_type 33
4. Frontend/Backend Protocol 39
4.1. Overview 39
4.2. Protocol 39
4.3. Message Data Types 44
4.4. Message Formats 45
5. gcc Default Optimizations 52
6. BKI Backend Interface 53
6.1. BKI File Format 53
6.2. BKI Commands 53
6.3. Example 54
7. Page Files 55
8. Genetic Query Optimization 58
8.1. Query Handling as a Complex Optimization Problem 58
8.2. Genetic Algorithms 58
8.3. Genetic Query Optimization (GEQO) in PostgreSQL 59
8.4. Further Readings 60
9. GiST Indexes 61
10. Native Language Support 63
10.1. For the Translator 63
10.2. For the Programmer 65
A. The CVS Repository 68
A.1. Getting The Source Via Anonymous CVS 68
A.2. CVS Tree Organization 69
A.3. Getting The Source Via CVSup 70
B. Documentation 75
B.1. DocBook 75
B.2. Tool Sets 75
B.3. Building The Documentation 79

B.4. Documentation Authoring 82
B.5. Style Guide 84

PostgreSQL 7.3.21 Tutorial

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 Tutorial

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

Preface xiv
1. What's In This Book xiv
1. Getting Started 1
1.1. Installation 1
1.2. Architectural Fundamentals 1
1.3. Creating a Database 1
1.4. Accessing a Database 3
2. The SQL Language 5
2.1. Introduction 5
2.2. Concepts 5
2.3. Creating a New Table 5
2.4. Populating a Table With Rows 6
2.5. Querying a Table 7
2.6. Joins Between Tables 8
2.7. Aggregate Functions 10
2.8. Updates 11
2.9. Deletions 12
3. Advanced Features 13
3.1. Introduction 13
3.2. Views 13
3.3. Foreign Keys 13
3.4. Transactions 14
3.5. Inheritance 15
3.6. Conclusion 16

Preface

1. What's In This Book

Welcome to PostgreSQL and the *PostgreSQL Tutorial*. The following few chapters are intended to give a simple introduction to PostgreSQL, relational database concepts, and the SQL language to those who are new to any one of these aspects. We only assume some general knowledge about how to use computers. No particular Unix or programming experience is required. This book is mainly intended to give you a hands-on experience with important aspects of the PostgreSQL system. It makes no attempt to be a complete or thorough treatment of the topics it covers.

After you have worked through this tutorial you might want to move on to reading the PostgreSQL 7.3.21 User's Guide to gain a more formal knowledge of the SQL language, or the PostgreSQL 7.3.21 Programmer's Guide for information about developing applications for PostgreSQL. Those who set up and manage their own server should also read the PostgreSQL 7.3.21 Administrator's Guide.

Chapter 1. Getting Started

1.1. Installation

Before you can use PostgreSQL you need to install it, of course. It is possible that PostgreSQL is already installed at your site, either because it was included in your operating system distribution or because the system administrator already installed it. If that is the case, you should obtain information from the operating system documentation or your system administrator about how to access PostgreSQL.

If you are not sure whether PostgreSQL is already available or whether you can use it for your experimentation then you can install it yourself. Doing so is not hard and it can be a good exercise. PostgreSQL can be installed by any unprivileged user, no superuser (root) access is required.

If you are installing PostgreSQL yourself, then refer to the PostgreSQL 7.3.21 Administrator's Guide for instructions on installation, and return to this guide when the installation is complete. Be sure to follow closely the section about setting up the appropriate environment variables.

If your site administrator has not set things up in the default way, you may have some more work to do. For example, if the database server machine is a remote machine, you will need to set the `PGHOST` environment variable to the name of the database server machine. The environment variable `PGPORT` may also have to be set. The bottom line is this: if you try to start an application program and it complains that it cannot connect to the database, you should consult your site administrator or, if that is you, the documentation to make sure that your environment is properly set up. If you did not understand the preceding paragraph then read the next section.

1.2. Architectural Fundamentals

Before we proceed, you should understand the basic PostgreSQL system architecture. Understanding how the parts of PostgreSQL interact will make this chapter somewhat clearer.

In database jargon, PostgreSQL uses a client/server model. A PostgreSQL session consists of the following cooperating processes (programs):

- A server process, which manages the database files, accepts connections to the database from client applications, and performs actions on the database on behalf of the clients. The database server program is called `postmaster`.
- The user's client (frontend) application that wants to perform database operations. Client applications can be very diverse in nature: a client could be a text-oriented tool, a graphical application, a web server that accesses the database to display web pages, or a specialized database maintenance tool. Some client applications are supplied with the PostgreSQL distribution, most are developed by users.

As is typical of client/server applications, the client and the server can be on different hosts. In that case they communicate over a TCP/IP network connection. You should keep this in mind, because the files that can be accessed on a client machine might not be accessible (or might only be accessible using a different file name) on the database server machine.

The PostgreSQL server can handle multiple concurrent connections from clients. For that purpose it starts (“forks”) a new process for each connection. From that point on, the client and the new server process communicate without intervention by the original `postmaster` process. Thus, the `postmaster` is always running, waiting for client connections, whereas client and associated server processes come and go. (All of this is of course invisible to the user. We only mention it here for completeness.)

1.3. Creating a Database

The first test to see whether you can access the database server is to try to create a database. A running PostgreSQL server can manage many databases. Typically, a separate database is used for each project or for each user.

Possibly, your site administrator has already created a database for your use. He should have told you what the name of your database is. In this case you can omit this step and skip ahead to the next section.

To create a new database, in this example named `mydb`, you use the following command:

```
$ createdb mydb
```

This should produce as response:

```
CREATE DATABASE
```

If so, this step was successful and you can skip over the remainder of this section.

If you see a message similar to

```
createdb: command not found
```

then PostgreSQL was not installed properly. Either it was not installed at all or the search path was not set correctly. Try calling the command with an absolute path instead:

```
$ /usr/local/pgsql/bin/createdb mydb
```

The path at your site might be different. Contact your site administrator or check back in the installation instructions to correct the situation.

Another response could be this:

```
psql: could not connect to server: Connection refused
        Is the server running locally and accepting
        connections on Unix domain socket "/tmp/.s.PGSQL.5432"?
createdb: database creation failed
```

This means that the server was not started, or it was not started where `createdb` expected it. Again, check the installation instructions or consult the administrator.

If you do not have the privileges required to create a database, you will see the following:

```
ERROR:  CREATE DATABASE: permission denied
createdb: database creation failed
```

Not every user has authorization to create new databases. If PostgreSQL refuses to create databases for you then the site administrator needs to grant you permission to create databases. Consult your site administrator if this occurs. If you installed PostgreSQL yourself then you should log in for the purposes of this tutorial under the user account that you started the server as. [1]

You can also create databases with other names. PostgreSQL allows you to create any number of databases at a given site. Database names must have an alphabetic first character and are limited to 63 characters in length. A convenient choice is to create a database with the same name as your current user name. Many tools assume that database name as the default, so it can save you some typing. To create that database, simply type

```
$ createdb
```

[1] As an explanation for why this works: PostgreSQL user names are separate from operating system user accounts. If you connect to a database, you can choose what PostgreSQL user name to connect as; if you don't, it will default to the same name as your current operating system account. As it happens, there will always be a PostgreSQL user account that has the same name as the operating system user that started the server, and it also happens that that user always has permission to create databases. Instead of logging in as that user you can also specify the `-U` option everywhere to select a PostgreSQL user name to connect as.

If you don't want to use your database anymore you can remove it. For example, if you are the owner (creator) of the database `mydb`, you can destroy it using the following command:

```
$ dropdb mydb
```

(For this command, the database name does not default to the user account name. You always need to specify it.) This action physically removes all files associated with the database and cannot be undone, so this should only be done with a great deal of forethought.

1.4. Accessing a Database

Once you have created a database, you can access it by:

- Running the PostgreSQL interactive terminal program, called *psql*, which allows you to interactively enter, edit, and execute SQL commands.
- Using an existing graphical frontend tool like PgAccess or an office suite with ODBC support to create and manipulate a database. These possibilities are not covered in this tutorial.
- Writing a custom application, using one of the several available language bindings. These possibilities are discussed further in the PostgreSQL 7.3.21 Programmer's Guide.

You probably want to start up `psql`, to try out the examples in this tutorial. It can be activated for the `mydb` database by typing the command:

```
$ psql mydb
```

If you leave off the database name then it will default to your user account name. You already discovered this scheme in the previous section.

In `psql`, you will be greeted with the following message:

```
Welcome to psql 7.3.21, the PostgreSQL interactive terminal.

Type:  \copyright for distribution terms
       \h for help with SQL commands
       \? for help on internal slash commands
       \g or terminate with semicolon to execute query
       \q to quit

mydb=>
```

The last line could also be

```
mydb=#
```

That would mean you are a database superuser, which is most likely the case if you installed PostgreSQL yourself. Being a superuser means that you are not subject to access controls. For the purpose of this tutorial this is not of importance.

If you have encountered problems starting `psql` then go back to the previous section. The diagnostics of `psql` and `createdb` are similar, and if the latter worked the former should work as well.

The last line printed out by `psql` is the prompt, and it indicates that `psql` is listening to you and that you can type SQL queries into a work space maintained by `psql`. Try out these commands:

```
mydb=> SELECT version();
                              version
---------------------------------------------------------------
 PostgreSQL 7.3devel on i586-pc-linux-gnu, compiled by GCC 2.96
(1 row)
```

```
mydb=> SELECT current_date;
    date
------------
 2002-08-31
(1 row)

mydb=> SELECT 2 + 2;
 ?column?
----------
        4
(1 row)
```

The `psql` program has a number of internal commands that are not SQL commands. They begin with the backslash character, "\". Some of these commands were listed in the welcome message. For example, you can get help on the syntax of various PostgreSQL SQL commands by typing:

```
mydb=> \h
```

To get out of `psql`, type

```
mydb=> \q
```

and `psql` will quit and return you to your command shell. (For more internal commands, type `\?` at the `psql` prompt.) The full capabilities of `psql` are documented in the PostgreSQL 7.3.21 Reference Manual. If PostgreSQL is installed correctly you can also type `man psql` at the operating system shell prompt to see the documentation. In this tutorial we will not use these features explicitly, but you can use them yourself when you see fit.

Chapter 2. The SQL Language

2.1. Introduction

This chapter provides an overview of how to use SQL to perform simple operations. This tutorial is only intended to give you an introduction and is in no way a complete tutorial on SQL. Numerous books have been written on SQL, including [melt93] and [date97]. You should be aware that some PostgreSQL language features are extensions to the standard.

In the examples that follow, we assume that you have created a database named `mydb`, as described in the previous chapter, and have started psql.

Examples in this manual can also be found in the PostgreSQL source distribution in the directory `src/tutorial/`. Refer to the `README` file in that directory for how to use them. To start the tutorial, do the following:

```
$ cd ..../src/tutorial
$ psql -s mydb
...

mydb=> \i basics.sql
```

The `\i` command reads in commands from the specified file. The `-s` option puts you in single step mode which pauses before sending each statement to the server. The commands used in this section are in the file `basics.sql`.

2.2. Concepts

PostgreSQL is a *relational database management system* (RDBMS). That means it is a system for managing data stored in *relations*. Relation is essentially a mathematical term for *table*. The notion of storing data in tables is so commonplace today that it might seem inherently obvious, but there are a number of other ways of organizing databases. Files and directories on Unix-like operating systems form an example of a hierarchical database. A more modern development is the object-oriented database.

Each table is a named collection of *rows*. Each row of a given table has the same set of named *columns*, and each column is of a specific data type. Whereas columns have a fixed order in each row, it is important to remember that SQL does not guarantee the order of the rows within the table in any way (although they can be explicitly sorted for display).

Tables are grouped into databases, and a collection of databases managed by a single PostgreSQL server instance constitutes a database *cluster*.

2.3. Creating a New Table

You can create a new table by specifying the table name, along with all column names and their types:

```
CREATE TABLE weather (
    city            varchar(80),
    temp_lo         int,           -- low temperature
    temp_hi         int,           -- high temperature
    prcp            real,          -- precipitation
    date            date
);
```

You can enter this into `psql` with the line breaks. `psql` will recognize that the command is not terminated until the semicolon.

White space (i.e., spaces, tabs, and newlines) may be used freely in SQL commands. That means you can type the command aligned differently than above, or even all on one line. Two dashes ("--") introduce comments. Whatever follows them is ignored up to the end of the line. SQL is case insensitive about key words and identifiers, except when identifiers are double-quoted to preserve the case (not done above).

`varchar(80)` specifies a data type that can store arbitrary character strings up to 80 characters in length. `int` is the normal integer type. `real` is a type for storing single precision floating-point numbers. `date` should be self-explanatory. (Yes, the column of type `date` is also named `date`. This may be convenient or confusing -- you choose.)

PostgreSQL supports the usual SQL types `int`, `smallint`, `real`, `double precision`, `char(`*N*`)`, `varchar(`*N*`)`, `date`, `time`, `timestamp`, and `interval`, as well as other types of general utility and a rich set of geometric types. PostgreSQL can be customized with an arbitrary number of user-defined data types. Consequently, type names are not syntactical keywords, except where required to support special cases in the SQL standard.

The second example will store cities and their associated geographical location:

```
CREATE TABLE cities (
    name            varchar(80),
    location        point
);
```

The `point` type is an example of a PostgreSQL-specific data type.

Finally, it should be mentioned that if you don't need a table any longer or want to recreate it differently you can remove it using the following command:

```
DROP TABLE tablename;
```

2.4. Populating a Table With Rows

The `INSERT` statement is used to populate a table with rows:

```
INSERT INTO weather VALUES ('San Francisco', 46, 50, 0.25,
 '1994-11-27');
```

Note that all data types use rather obvious input formats. Constants that are not simple numeric values usually must be surrounded by single quotes (`'`), as in the example. The `date` type is actually quite flexible in what it accepts, but for this tutorial we will stick to the unambiguous format shown here.

The `point` type requires a coordinate pair as input, as shown here:

```
INSERT INTO cities  VALUES ('San Francisco', '(-194.0, 53.0)');
```

The syntax used so far requires you to remember the order of the columns. An alternative syntax allows you to list the columns explicitly:

```
INSERT INTO weather (city, temp_lo, temp_hi, prcp, date)
    VALUES ('San Francisco', 43, 57, 0.0, '1994-11-29');
```

You can list the columns in a different order if you wish or even omit some columns, e.g., if the precipitation is unknown:

```
INSERT INTO weather (date, city, temp_hi, temp_lo)
    VALUES ('1994-11-29', 'Hayward', 54, 37);
```

Many developers consider explicitly listing the columns better style than relying on the order implicitly.

Please enter all the commands shown above so you have some data to work with in the following sections.

You could also have used `COPY` to load large amounts of data from flat-text files. This is usually faster because the `COPY` command is optimized for this application while allowing less flexibility than `INSERT`. An example would be:

```
COPY weather FROM '/home/user/weather.txt';
```

where the file name for the source file must be available to the backend server machine, not the client, since the backend server reads the file directly. You can read more about the `COPY` command in the PostgreSQL 7.3.21 Reference Manual.

2.5. Querying a Table

To retrieve data from a table, the table is *queried*. An SQL `SELECT` statement is used to do this. The statement is divided into a select list (the part that lists the columns to be returned), a table list (the part that lists the tables from which to retrieve the data), and an optional qualification (the part that specifies any restrictions). For example, to retrieve all the rows of table `weather`, type:

```
SELECT * FROM weather;
```

(here `*` means "all columns") and the output should be:

```
     city      | temp_lo | temp_hi | prcp |    date
---------------+---------+---------+------+------------
 San Francisco |      46 |      50 | 0.25 | 1994-11-27
 San Francisco |      43 |      57 |    0 | 1994-11-29
 Hayward       |      37 |      54 |      | 1994-11-29
(3 rows)
```

You may specify any arbitrary expressions in the target list. For example, you can do:

```
SELECT city, (temp_hi+temp_lo)/2 AS temp_avg, date FROM weather;
```

This should give:

```
     city      | temp_avg |    date
---------------+----------+------------
 San Francisco |       48 | 1994-11-27
 San Francisco |       50 | 1994-11-29
 Hayward       |       45 | 1994-11-29
(3 rows)
```

Notice how the `AS` clause is used to relabel the output column. (It is optional.)

Arbitrary Boolean operators (`AND`, `OR`, and `NOT`) are allowed in the qualification of a query. For example, the following retrieves the weather of San Francisco on rainy days:

```
SELECT * FROM weather
    WHERE city = 'San Francisco'
    AND prcp > 0.0;
```

Result:

```
     city      | temp_lo | temp_hi | prcp |    date
---------------+---------+---------+------+------------
 San Francisco |      46 |      50 | 0.25 | 1994-11-27
(1 row)
```

As a final note, you can request that the results of a select can be returned in sorted order or with duplicate rows removed:

```
SELECT DISTINCT city
    FROM weather
    ORDER BY city;

     city
---------------
 Hayward
 San Francisco
(2 rows)
```

`DISTINCT` and `ORDER BY` can be used separately, of course.

2.6. Joins Between Tables

Thus far, our queries have only accessed one table at a time. Queries can access multiple tables at once, or access the same table in such a way that multiple rows of the table are being processed at the same time. A query that accesses multiple rows of the same or different tables at one time is called a *join* query. As an example, say you wish to list all the weather records together with the location of the associated city. To do that, we need to compare the city column of each row of the weather table with the name column of all rows in the cities table, and select the pairs of rows where these values match.

Note

This is only a conceptual model. The actual join may be performed in a more efficient manner, but this is invisible to the user.

This would be accomplished by the following query:

```
SELECT *
    FROM weather, cities
    WHERE city = name;

     city      | temp_lo | temp_hi | prcp |    date    |     name
    | location
---------------+---------+---------+------+------------
+---------------+-----------
 San Francisco |      46 |      50 | 0.25 | 1994-11-27 | San
 Francisco | (-194,53)
 San Francisco |      43 |      57 |    0 | 1994-11-29 | San
 Francisco | (-194,53)
(2 rows)
```

Observe two things about the result set:

- There is no result row for the city of Hayward. This is because there is no matching entry in the `cities` table for Hayward, so the join ignores the unmatched rows in the weather table. We will see shortly how this can be fixed.
- There are two columns containing the city name. This is correct because the lists of columns of the `weather` and the `cities` table are concatenated. In practice this is undesirable, though, so you will probably want to list the output columns explicitly rather than using `*`:

  ```
  SELECT city, temp_lo, temp_hi, prcp, date, location
      FROM weather, cities
      WHERE city = name;
  ```

Exercise: Attempt to find out the semantics of this query when the `WHERE` clause is omitted.

Since the columns all had different names, the parser automatically found out which table they belong to, but it is good style to fully qualify column names in join queries:

```
SELECT weather.city, weather.temp_lo, weather.temp_hi,
       weather.prcp, weather.date, cities.location
    FROM weather, cities
    WHERE cities.name = weather.city;
```

Join queries of the kind seen thus far can also be written in this alternative form:

```
SELECT *
    FROM weather INNER JOIN cities ON (weather.city = cities.name);
```

This syntax is not as commonly used as the one above, but we show it here to help you understand the following topics.

Now we will figure out how we can get the Hayward records back in. What we want the query to do is to scan the `weather` table and for each row to find the matching `cities` row. If no matching row is found we want some “empty values” to be substituted for the `cities` table's columns. This kind of query is called an *outer join*. (The joins we have seen so far are inner joins.) The command looks like this:

```
SELECT *
    FROM weather LEFT OUTER JOIN cities ON (weather.city =
 cities.name);

     city      | temp_lo | temp_hi | prcp |    date    |     name
    | location
---------------+---------+---------+------+------------
+---------------+-----------
 Hayward       |      37 |      54 |      | 1994-11-29 |
    |
 San Francisco |      46 |      50 | 0.25 | 1994-11-27 | San
 Francisco | (-194,53)
 San Francisco |      43 |      57 |    0 | 1994-11-29 | San
 Francisco | (-194,53)
(3 rows)
```

This query is called a *left outer join* because the table mentioned on the left of the join operator will have each of its rows in the output at least once, whereas the table on the right will only have those rows output that match some row of the left table. When outputting a left-table row for which there is no right-table match, empty (null) values are substituted for the right-table columns.

Exercise: There are also right outer joins and full outer joins. Try to find out what those do.

We can also join a table against itself. This is called a *self join*. As an example, suppose we wish to find all the weather records that are in the temperature range of other weather records. So we need to compare the `temp_lo` and `temp_hi` columns of each `weather` row to the `temp_lo` and `temp_hi` columns of all other `weather` rows. We can do this with the following query:

```
SELECT W1.city, W1.temp_lo AS low, W1.temp_hi AS high,
    W2.city, W2.temp_lo AS low, W2.temp_hi AS high
    FROM weather W1, weather W2
    WHERE W1.temp_lo < W2.temp_lo
    AND W1.temp_hi > W2.temp_hi;

     city      | low | high |     city      | low | high
---------------+-----+------+---------------+-----+------
 San Francisco |  43 |   57 | San Francisco |  46 |   50
```

```
 Hayward       |  37 |   54 | San Francisco |  46 |   50
(2 rows)
```

Here we have relabeled the weather table as `W1` and `W2` to be able to distinguish the left and right side of the join. You can also use these kinds of aliases in other queries to save some typing, e.g.:

```
SELECT *
    FROM weather w, cities c
    WHERE w.city = c.name;
```

You will encounter this style of abbreviating quite frequently.

2.7. Aggregate Functions

Like most other relational database products, PostgreSQL supports aggregate functions. An aggregate function computes a single result from multiple input rows. For example, there are aggregates to compute the `count`, `sum`, `avg` (average), `max` (maximum) and `min` (minimum) over a set of rows.

As an example, we can find the highest low-temperature reading anywhere with

```
SELECT max(temp_lo) FROM weather;

 max
-----
  46
(1 row)
```

If we wanted to know what city (or cities) that reading occurred in, we might try

```
SELECT city FROM weather WHERE temp_lo = max(temp_lo);      WRONG
```

but this will not work since the aggregate `max` cannot be used in the `WHERE` clause. (This restriction exists because the `WHERE` clause determines the rows that will go into the aggregation stage; so it has to be evaluated before aggregate functions are computed.) However, as is often the case the query can be restated to accomplish the intended result, here by using a *subquery*:

```
SELECT city FROM weather
    WHERE temp_lo = (SELECT max(temp_lo) FROM weather);

     city
---------------
 San Francisco
(1 row)
```

This is OK because the subquery is an independent computation that computes its own aggregate separately from what is happening in the outer query.

Aggregates are also very useful in combination with `GROUP BY` clauses. For example, we can get the maximum low temperature observed in each city with

```
SELECT city, max(temp_lo)
    FROM weather
    GROUP BY city;

     city      | max
---------------+-----
 Hayward       |  37
 San Francisco |  46
```

```
(2 rows)
```

which gives us one output row per city. Each aggregate result is computed over the table rows matching that city. We can filter these grouped rows using HAVING:

```
SELECT city, max(temp_lo)
    FROM weather
    GROUP BY city
    HAVING max(temp_lo) < 40;

  city   | max
---------+-----
 Hayward |  37
(1 row)
```

which gives us the same results for only the cities that have all temp_lo values below 40. Finally, if we only care about cities whose names begin with "S", we might do

```
SELECT city, max(temp_lo)
    FROM weather
    WHERE city LIKE 'S%'[1]
    GROUP BY city
    HAVING max(temp_lo) < 40;
```

[1] The LIKE operator does pattern matching and is explained in the PostgreSQL 7.3.21 User's Guide.

It is important to understand the interaction between aggregates and SQL's WHERE and HAVING clauses. The fundamental difference between WHERE and HAVING is this: WHERE selects input rows before groups and aggregates are computed (thus, it controls which rows go into the aggregate computation), whereas HAVING selects group rows after groups and aggregates are computed. Thus, the WHERE clause must not contain aggregate functions; it makes no sense to try to use an aggregate to determine which rows will be inputs to the aggregates. On the other hand, HAVING clauses always contain aggregate functions. (Strictly speaking, you are allowed to write a HAVING clause that doesn't use aggregates, but it's wasteful: The same condition could be used more efficiently at the WHERE stage.)

Observe that we can apply the city name restriction in WHERE, since it needs no aggregate. This is more efficient than adding the restriction to HAVING, because we avoid doing the grouping and aggregate calculations for all rows that fail the WHERE check.

2.8. Updates

You can update existing rows using the UPDATE command. Suppose you discover the temperature readings are all off by 2 degrees as of November 28. You may update the data as follows:

```
UPDATE weather
    SET temp_hi = temp_hi - 2,  temp_lo = temp_lo - 2
    WHERE date > '1994-11-28';
```

Look at the new state of the data:

```
SELECT * FROM weather;

     city      | temp_lo | temp_hi | prcp |    date
---------------+---------+---------+------+------------
 San Francisco |      46 |      50 | 0.25 | 1994-11-27
 San Francisco |      41 |      55 |    0 | 1994-11-29
 Hayward       |      35 |      52 |      | 1994-11-29
```

```
(3 rows)
```

2.9. Deletions

Suppose you are no longer interested in the weather of Hayward. Then you can do the following to delete those rows from the table. Deletions are performed using the `DELETE` command:

```
DELETE FROM weather WHERE city = 'Hayward';
```

All weather records belonging to Hayward are removed.

```
SELECT * FROM weather;
```

```
     city      | temp_lo | temp_hi | prcp |    date
---------------+---------+---------+------+------------
 San Francisco |      46 |      50 | 0.25 | 1994-11-27
 San Francisco |      41 |      55 |    0 | 1994-11-29
(2 rows)
```

One should be wary of statements of the form

```
DELETE FROM tablename;
```

Without a qualification, `DELETE` will remove *all* rows from the given table, leaving it empty. The system will not request confirmation before doing this!

Chapter 3. Advanced Features

3.1. Introduction

In the previous chapter we have covered the basics of using SQL to store and access your data in PostgreSQL. We will now discuss some more advanced features of SQL that simplify management and prevent loss or corruption of your data. Finally, we will look at some PostgreSQL extensions.

This chapter will on occasion refer to examples found in Chapter 2, *The SQL Language* to change or improve them, so it will be of advantage if you have read that chapter. Some examples from this chapter can also be found in `advanced.sql` in the tutorial directory. This file also contains some example data to load, which is not repeated here. (Refer to Section 2.1, “Introduction” for how to use the file.)

3.2. Views

Refer back to the queries in Section 2.6, “Joins Between Tables”. Suppose the combined listing of weather records and city location is of particular interest to your application, but you don't want to type the query each time you need it. You can create a *view* over the query, which gives a name to the query that you can refer to like an ordinary table.

```
CREATE VIEW myview AS
    SELECT city, temp_lo, temp_hi, prcp, date, location
        FROM weather, cities
        WHERE city = name;

SELECT * FROM myview;
```

Making liberal use of views is a key aspect of good SQL database design. Views allow you to encapsulate the details of the structure of your tables, which may change as your application evolves, behind consistent interfaces.

Views can be used in almost any place a real table can be used. Building views upon other views is not uncommon.

3.3. Foreign Keys

Recall the `weather` and `cities` tables from Chapter 2, *The SQL Language*. Consider the following problem: You want to make sure that no one can insert rows in the `weather` table that do not have a matching entry in the `cities` table. This is called maintaining the *referential integrity* of your data. In simplistic database systems this would be implemented (if at all) by first looking at the `cities` table to check if a matching record exists, and then inserting or rejecting the new `weather` records. This approach has a number of problems and is very inconvenient, so PostgreSQL can do this for you.

The new declaration of the tables would look like this:

```
CREATE TABLE cities (
  city     varchar(80) primary key,
  location point
);

CREATE TABLE weather (
 city      varchar(80) references cities,
 temp_lo   int,
 temp_hi   int,
 prcp      real,
```

```
 date      date
);
```

Now try inserting an invalid record:

```
INSERT INTO weather VALUES ('Berkeley', 45, 53, 0.0, '1994-11-28');

ERROR:  <unnamed> referential integrity violation - key referenced
 from weather not found in cities
```

The behavior of foreign keys can be finely tuned to your application. We will not go beyond this simple example in this tutorial, but just refer you to the PostgreSQL 7.3.21 User's Guide for more information. Making correct use of foreign keys will definitely improve the quality of your database applications, so you are strongly encouraged to learn about them.

3.4. Transactions

Transactions are a fundamental concept of all database systems. The essential point of a transaction is that it bundles multiple steps into a single, all-or-nothing operation. The intermediate states between the steps are not visible to other concurrent transactions, and if some failure occurs that prevents the transaction from completing, then none of the steps affect the database at all.

For example, consider a bank database that contains balances for various customer accounts, as well as total deposit balances for branches. Suppose that we want to record a payment of $100.00 from Alice's account to Bob's account. Simplifying outrageously, the SQL commands for this might look like

```
UPDATE accounts SET balance = balance - 100.00
    WHERE name = 'Alice';
UPDATE branches SET balance = balance - 100.00
    WHERE name = (SELECT branch_name FROM accounts WHERE name =
 'Alice');
UPDATE accounts SET balance = balance + 100.00
    WHERE name = 'Bob';
UPDATE branches SET balance = balance + 100.00
    WHERE name = (SELECT branch_name FROM accounts WHERE name =
 'Bob');
```

The details of these commands are not important here; the important point is that there are several separate updates involved to accomplish this rather simple operation. Our bank's officers will want to be assured that either all these updates happen, or none of them happen. It would certainly not do for a system failure to result in Bob receiving $100.00 that was not debited from Alice. Nor would Alice long remain a happy customer if she was debited without Bob being credited. We need a guarantee that if something goes wrong partway through the operation, none of the steps executed so far will take effect. Grouping the updates into a *transaction* gives us this guarantee. A transaction is said to be *atomic*: from the point of view of other transactions, it either happens completely or not at all.

We also want a guarantee that once a transaction is completed and acknowledged by the database system, it has indeed been permanently recorded and won't be lost even if a crash ensues shortly thereafter. For example, if we are recording a cash withdrawal by Bob, we do not want any chance that the debit to his account will disappear in a crash just as he walks out the bank door. A transactional database guarantees that all the updates made by a transaction are logged in permanent storage (i.e., on disk) before the transaction is reported complete.

Another important property of transactional databases is closely related to the notion of atomic updates: when multiple transactions are running concurrently, each one should not be able to see the incomplete changes made by others. For example, if one transaction is busy totalling all the branch balances, it would not do for it to include the debit from Alice's branch but not the credit to Bob's branch, nor vice versa. So transactions must be all-or-nothing not only in terms of their permanent effect on the database, but also in terms of their visibility as they happen. The updates made so far by an open

transaction are invisible to other transactions until the transaction completes, whereupon all the updates become visible simultaneously.

In PostgreSQL, a transaction is set up by surrounding the SQL commands of the transaction with `BEGIN` and `COMMIT` commands. So our banking transaction would actually look like

```
BEGIN;
UPDATE accounts SET balance = balance - 100.00
    WHERE name = 'Alice';
-- etc etc
COMMIT;
```

If, partway through the transaction, we decide we don't want to commit (perhaps we just noticed that Alice's balance went negative), we can issue the command `ROLLBACK` instead of `COMMIT`, and all our updates so far will be canceled.

PostgreSQL actually treats every SQL statement as being executed within a transaction. If you don't issue a `BEGIN` command, then each individual statement has an implicit `BEGIN` and (if successful) `COMMIT` wrapped around it. A group of statements surrounded by `BEGIN` and `COMMIT` is sometimes called a *transaction block*.

Note

Some client libraries issue `BEGIN` and `COMMIT` commands automatically, so that you may get the effect of transaction blocks without asking. Check the documentation for the interface you are using.

3.5. Inheritance

Inheritance is a concept from object-oriented databases. It opens up interesting new possibilities of database design.

Let's create two tables: A table `cities` and a table `capitals`. Naturally, capitals are also cities, so you want some way to show the capitals implicitly when you list all cities. If you're really clever you might invent some scheme like this:

```
CREATE TABLE capitals (
  name       text,
  population real,
  altitude   int,    -- (in ft)
  state      char(2)
);

CREATE TABLE non_capitals (
  name       text,
  population real,
  altitude   int     -- (in ft)
);

CREATE VIEW cities AS
  SELECT name, population, altitude FROM capitals
    UNION
  SELECT name, population, altitude FROM non_capitals;
```

This works OK as far as querying goes, but it gets ugly when you need to update several rows, to name one thing.

A better solution is this:

```
CREATE TABLE cities (
  name       text,
  population real,
  altitude   int     -- (in ft)
);

CREATE TABLE capitals (
  state      char(2)
) INHERITS (cities);
```

In this case, a row of `capitals` *inherits* all columns (`name`, `population`, and `altitude`) from its *parent*, `cities`. The type of the column `name` is `text`, a native PostgreSQL type for variable length character strings. State capitals have an extra column, state, that shows their state. In PostgreSQL, a table can inherit from zero or more other tables.

For example, the following query finds the names of all cities, including state capitals, that are located at an altitude over 500 ft.:

```
SELECT name, altitude
  FROM cities
  WHERE altitude > 500;
```

which returns:

```
   name    | altitude
-----------+----------
 Las Vegas |     2174
 Mariposa  |     1953
 Madison   |      845
(3 rows)
```

On the other hand, the following query finds all the cities that are not state capitals and are situated at an altitude of 500 ft. or higher:

```
SELECT name, altitude
    FROM ONLY cities
    WHERE altitude > 500;

   name    | altitude
-----------+----------
 Las Vegas |     2174
 Mariposa  |     1953
(2 rows)
```

Here the `ONLY` before `cities` indicates that the query should be run over only the `cities` table, and not tables below `cities` in the inheritance hierarchy. Many of the commands that we have already discussed -- `SELECT`, `UPDATE`, and `DELETE` -- support this `ONLY` notation.

3.6. Conclusion

PostgreSQL has many features not touched upon in this tutorial introduction, which has been oriented toward newer users of SQL. These features are discussed in more detail in both the PostgreSQL 7.3.21 User's Guide and the PostgreSQL 7.3.21 Programmer's Guide.

If you feel you need more introductory material, please visit the PostgreSQL web site[1] for links to more resources.

[1] http://www.postgresql.org

PostgreSQL 7.3.21 User's Guide

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 User's Guide

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

Preface xxvi
1. What is PostgreSQL? xxvi
2. A Short History of PostgreSQL xxvi
2.1. The Berkeley POSTGRES Project xxvi
2.2. Postgres95 xxvii
2.3. PostgreSQL xxviii
3. What's In This Book xxviii
4. Overview of Documentation Resources xxviii
5. Terminology and Notation xxx
6. Bug Reporting Guidelines xxx
6.1. Identifying Bugs xxx
6.2. What to report xxxi
6.3. Where to report bugs xxxii
1. SQL Syntax 1
1.1. Lexical Structure 1
1.1.1. Identifiers and Key Words 1
1.1.2. Constants 2
1.1.3. Operators 4
1.1.4. Special Characters 5
1.1.5. Comments 5
1.1.6. Lexical Precedence 6
1.2. Value Expressions 7
1.2.1. Column References 7
1.2.2. Positional Parameters 8
1.2.3. Operator Invocations 8
1.2.4. Function Calls 8
1.2.5. Aggregate Expressions 8
1.2.6. Type Casts 9
1.2.7. Scalar Subqueries 10
1.2.8. Expression Evaluation 10
2. Data Definition 11
2.1. Table Basics 11
2.2. System Columns 12
2.3. Default Values 13
2.4. Constraints 13
2.4.1. Check Constraints 13
2.4.2. Not-Null Constraints 15
2.4.3. Unique Constraints 15
2.4.4. Primary Keys 16
2.4.5. Foreign Keys 17
2.5. Inheritance 19
2.6. Modifying Tables 21
2.6.1. Adding a Column 21
2.6.2. Removing a Column 21
2.6.3. Adding a Constraint 22
2.6.4. Removing a Constraint 22
2.6.5. Changing the Default 22
2.6.6. Renaming a Column 22
2.6.7. Renaming a Table 22
2.7. Privileges 23
2.8. Schemas 23
2.8.1. Creating a Schema 24
2.8.2. The Public Schema 24
2.8.3. The Schema Search Path 25
2.8.4. Schemas and Privileges 26

2.8.5. The System Catalog Schema 26
2.8.6. Usage Patterns 26
2.8.7. Portability 27
2.9. Other Database Objects 27
2.10. Dependency Tracking 27
3. Data Manipulation 29
3.1. Inserting Data 29
3.2. Updating Data 30
3.3. Deleting Data 30
4. Queries 32
4.1. Overview 32
4.2. Table Expressions 32
4.2.1. The FROM Clause 32
4.2.2. The WHERE Clause 37
4.2.3. The GROUP BY and HAVING Clauses 38
4.3. Select Lists 40
4.3.1. Select-List Items 40
4.3.2. Column Labels 40
4.3.3. DISTINCT 41
4.4. Combining Queries 41
4.5. Sorting Rows 42
4.6. LIMIT and OFFSET 42
5. Data Types 44
5.1. Numeric Types 45
5.1.1. The Integer Types 46
5.1.2. Arbitrary Precision Numbers 46
5.1.3. Floating-Point Types 47
5.1.4. The Serial Types 47
5.2. Monetary Type 48
5.3. Character Types 49
5.4. Binary Strings 50
5.5. Date/Time Types 52
5.5.1. Date/Time Input 53
5.5.2. Date/Time Output 56
5.5.3. Time Zones 57
5.5.4. Internals 57
5.6. Boolean Type 58
5.7. Geometric Types 58
5.7.1. Point 59
5.7.2. Line Segment 59
5.7.3. Box 59
5.7.4. Path 60
5.7.5. Polygon 60
5.7.6. Circle 61
5.8. Network Address Data Types 61
5.8.1. `inet` 61
5.8.2. `cidr` 61
5.8.3. `inet` vs `cidr` 62
5.8.4. `macaddr` 62
5.9. Bit String Types 62
5.10. Object Identifier Types 63
5.11. Pseudo-Types 64
5.12. Arrays 65
6. Functions and Operators 69
6.1. Logical Operators 69
6.2. Comparison Operators 69
6.3. Mathematical Functions and Operators 71
6.4. String Functions and Operators 73

6.5. Binary String Functions and Operators 80
6.6. Pattern Matching 82
6.6.1. LIKE 82
6.6.2. SIMILAR TO and SQL99 Regular Expressions 82
6.6.3. POSIX Regular Expressions 83
6.7. Data Type Formatting Functions 86
6.8. Date/Time Functions and Operators 91
6.8.1. EXTRACT, date_part 93
6.8.2. date_trunc 95
6.8.3. AT TIME ZONE 96
6.8.4. Current Date/Time 96
6.9. Geometric Functions and Operators 98
6.10. Network Address Type Functions 101
6.11. Sequence-Manipulation Functions 102
6.12. Conditional Expressions 104
6.12.1. CASE 104
6.12.2. COALESCE 105
6.12.3. NULLIF 105
6.13. Miscellaneous Functions 105
6.14. Aggregate Functions 109
6.15. Subquery Expressions 110
6.15.1. EXISTS 110
6.15.2. IN (scalar form) 111
6.15.3. IN (subquery form) 111
6.15.4. NOT IN (scalar form) 112
6.15.5. NOT IN (subquery form) 112
6.15.6. ANY/SOME 113
6.15.7. ALL 113
6.15.8. Row-wise Comparison 114
7. Type Conversion 115
7.1. Overview 115
7.2. Operators 116
7.3. Functions 119
7.4. Query Targets 121
7.5. UNION and CASE Constructs 122
8. Indexes 124
8.1. Introduction 124
8.2. Index Types 124
8.3. Multicolumn Indexes 125
8.4. Unique Indexes 126
8.5. Functional Indexes 126
8.6. Operator Classes 126
8.7. Partial Indexes 127
8.8. Examining Index Usage 129
9. Concurrency Control 131
9.1. Introduction 131
9.2. Transaction Isolation 131
9.2.1. Read Committed Isolation Level 132
9.2.2. Serializable Isolation Level 132
9.3. Explicit Locking 133
9.3.1. Table-Level Locks 133
9.3.2. Row-Level Locks 135
9.3.3. Deadlocks 135
9.4. Data Consistency Checks at the Application Level 135
9.5. Locking and Indexes 136
10. Performance Tips 138
10.1. Using EXPLAIN 138
10.2. Statistics Used by the Planner 141

10.3. Controlling the Planner with Explicit JOIN Clauses 143
10.4. Populating a Database 145
10.4.1. Disable Autocommit 145
10.4.2. Use COPY FROM 145
10.4.3. Remove Indexes 145
10.4.4. Run ANALYZE Afterwards 145
A. Date/Time Support 146
A.1. Date/Time Input Interpretation 146
A.2. Date/Time Key Words 147
A.3. History of Units 151
B. SQL Key Words 153
C. SQL Conformance 168
C.1. Supported Features 168
C.2. Unsupported Features 176
Bibliography 183

List of Tables

1.1. Operator Precedence (decreasing) 6
5.1. Data Types 44
5.2. Numeric Types 45
5.3. Monetary Types 49
5.4. Character Types 49
5.5. Specialty Character Types 50
5.6. Binary String Types 50
5.7. `bytea` Literal Escaped Octets 51
5.8. `bytea` Output Escaped Octets 51
5.9. Date/Time Types 52
5.10. Date Input 53
5.11. Time Input 54
5.12. Time With Time Zone Input 54
5.13. Time Zone Input 55
5.14. Special Date/Time Inputs 56
5.15. Date/Time Output Styles 56
5.16. Date Order Conventions 56
5.17. Geometric Types 59
5.18. Network Address Data Types 61
5.19. `cidr` Type Input Examples 62
5.20. Object Identifier Types 63
5.21. Pseudo-Types 64
6.1. Comparison Operators 69
6.2. Mathematical Operators 71
6.3. Bit String Binary Operators 71
6.4. Mathematical Functions 72
6.5. Trigonometric Functions 73
6.6. SQL String Functions and Operators 73
6.7. Other String Functions 74
6.8. Built-in Conversions 77
6.9. SQL Binary String Functions and Operators 80
6.10. Other Binary String Functions 81
6.11. Regular Expression Match Operators 83
6.12. Formatting Functions 86
6.13. Template patterns for date/time conversions 87
6.14. Template pattern modifiers for date/time conversions 88
6.15. Template patterns for numeric conversions 89
6.16. `to_char` Examples 90
6.17. Date/Time Operators 91
6.18. Date/Time Functions 91
6.19. AT TIME ZONE Variants 96
6.20. Geometric Operators 98
6.21. Geometric Functions 99
6.22. Geometric Type Conversion Functions 100
6.23. `cidr` and `inet` Operators 101
6.24. `cidr` and `inet` Functions 102
6.25. `macaddr` Functions 102
6.26. Sequence Functions 102
6.27. Session Information Functions 105
6.28. Configuration Settings Information Functions 106
6.29. Access Privilege Inquiry Functions 107
6.30. Schema Visibility Inquiry Functions 108
6.31. Catalog Information Functions 108
6.32. Comment Information Functions 109
6.33. Aggregate Functions 109

9.1. Isolation Levels 131
10.1. pg_stats Columns 142
A.1. Month Abbreviations 147
A.2. Day of the Week Abbreviations 147
A.3. Date/Time Field Modifiers 148
A.4. Time Zone Abbreviations 148
A.5. Australian Time Zone Abbreviations 151
B.1. SQL Key Words 153

List of Examples

5.1. Using the character types 50
5.2. Using the `boolean` type 58
5.3. Using the bit string types 63
7.1. Exponentiation Operator Type Resolution 117
7.2. String Concatenation Operator Type Resolution 118
7.3. Absolute-Value and Factorial Operator Type Resolution 118
7.4. Factorial Function Argument Type Resolution 120
7.5. Substring Function Type Resolution 120
7.6. `character` Storage Type Conversion 122
7.7. Underspecified Types in a Union 122
7.8. Type Conversion in a Simple Union 123
7.9. Type Conversion in a Transposed Union 123
8.1. Setting up a Partial Index to Exclude Common Values 127
8.2. Setting up a Partial Index to Exclude Uninteresting Values 128
8.3. Setting up a Partial Unique Index 129

Preface

1. What is PostgreSQL?

PostgreSQL is an object-relational database management system (ORDBMS) based on POSTGRES, Version 4.2[1], developed at the University of California at Berkeley Computer Science Department. The POSTGRES project, led by Professor Michael Stonebraker, was sponsored by the Defense Advanced Research Projects Agency (DARPA), the Army Research Office (ARO), the National Science Foundation (NSF), and ESL, Inc.

PostgreSQL is an open-source descendant of this original Berkeley code. It provides SQL92/SQL99 language support and other modern features.

POSTGRES pioneered many of the object-relational concepts now becoming available in some commercial databases. Traditional relational database management systems (RDBMS) support a data model consisting of a collection of named relations, containing attributes of a specific type. In current commercial systems, possible types include floating point numbers, integers, character strings, money, and dates. It is commonly recognized that this model is inadequate for future data-processing applications. The relational model successfully replaced previous models in part because of its "Spartan simplicity". However, this simplicity makes the implementation of certain applications very difficult. PostgreSQL offers substantial additional power by incorporating the following additional concepts in such a way that users can easily extend the system:

- inheritance
- data types
- functions

Other features provide additional power and flexibility:

- constraints
- triggers
- rules
- transactional integrity

These features put PostgreSQL into the category of databases referred to as *object-relational*. Note that this is distinct from those referred to as *object-oriented*, which in general are not as well suited to supporting traditional relational database languages. So, although PostgreSQL has some object-oriented features, it is firmly in the relational database world. In fact, some commercial databases have recently incorporated features pioneered by PostgreSQL.

2. A Short History of PostgreSQL

The object-relational database management system now known as PostgreSQL (and briefly called Postgres95) is derived from the POSTGRES package written at the University of California at Berkeley. With over a decade of development behind it, PostgreSQL is the most advanced open-source database available anywhere, offering multiversion concurrency control, supporting almost all SQL constructs (including subselects, transactions, and user-defined types and functions), and having a wide range of language bindings available (including C, C++, Java, Perl, Tcl, and Python).

2.1. The Berkeley POSTGRES Project

Implementation of the POSTGRES DBMS began in 1986. The initial concepts for the system were presented in [ston86] and the definition of the initial data model appeared in [rowe87]. The design of

[1] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/postgres.html

the rule system at that time was described in [ston87a]. The rationale and architecture of the storage manager were detailed in [ston87b].

Postgres has undergone several major releases since then. The first "demoware" system became operational in 1987 and was shown at the 1988 ACM-SIGMOD Conference. Version 1, described in [ston90a], was released to a few external users in June 1989. In response to a critique of the first rule system ([ston89]), the rule system was redesigned ([ston90b]) and Version 2 was released in June 1990 with the new rule system. Version 3 appeared in 1991 and added support for multiple storage managers, an improved query executor, and a rewritten rewrite rule system. For the most part, subsequent releases until Postgres95 (see below) focused on portability and reliability.

POSTGRES has been used to implement many different research and production applications. These include: a financial data analysis system, a jet engine performance monitoring package, an asteroid tracking database, a medical information database, and several geographic information systems. POSTGRES has also been used as an educational tool at several universities. Finally, Illustra Information Technologies (later merged into Informix[2], which is now owned by IBM[3].) picked up the code and commercialized it. POSTGRES became the primary data manager for the Sequoia 2000[4] scientific computing project in late 1992.

The size of the external user community nearly doubled during 1993. It became increasingly obvious that maintenance of the prototype code and support was taking up large amounts of time that should have been devoted to database research. In an effort to reduce this support burden, the Berkeley POSTGRES project officially ended with Version 4.2.

2.2. Postgres95

In 1994, Andrew Yu and Jolly Chen added a SQL language interpreter to POSTGRES. Postgres95 was subsequently released to the Web to find its own way in the world as an open-source descendant of the original POSTGRES Berkeley code.

Postgres95 code was completely ANSI C and trimmed in size by 25%. Many internal changes improved performance and maintainability. Postgres95 release 1.0.x ran about 30-50% faster on the Wisconsin Benchmark compared to POSTGRES, Version 4.2. Apart from bug fixes, the following were the major enhancements:

- The query language PostQUEL was replaced with SQL (implemented in the server). Subqueries were not supported until PostgreSQL (see below), but they could be imitated in Postgres95 with user-defined SQL functions. Aggregates were re-implemented. Support for the GROUP BY query clause was also added. The `libpq` interface remained available for C programs.

- In addition to the monitor program, a new program (psql) was provided for interactive SQL queries using GNU Readline.

- A new front-end library, `libpgtcl`, supported Tcl-based clients. A sample shell, `pgtclsh`, provided new Tcl commands to interface Tcl programs with the Postgres95 backend.

- The large-object interface was overhauled. The Inversion large objects were the only mechanism for storing large objects. (The Inversion file system was removed.)

- The instance-level rule system was removed. Rules were still available as rewrite rules.

- A short tutorial introducing regular SQL features as well as those of Postgres95 was distributed with the source code

- GNU make (instead of BSD make) was used for the build. Also, Postgres95 could be compiled with an unpatched GCC (data alignment of doubles was fixed).

[2] http://www.informix.com/
[3] http://www.ibm.com/
[4] http://meteora.ucsd.edu/s2k/s2k_home.html

2.3. PostgreSQL

By 1996, it became clear that the name “Postgres95” would not stand the test of time. We chose a new name, PostgreSQL, to reflect the relationship between the original POSTGRES and the more recent versions with SQL capability. At the same time, we set the version numbering to start at 6.0, putting the numbers back into the sequence originally begun by the Berkeley POSTGRES project.

The emphasis during development of Postgres95 was on identifying and understanding existing problems in the backend code. With PostgreSQL, the emphasis has shifted to augmenting features and capabilities, although work continues in all areas.

Major enhancements in PostgreSQL include:

- Table-level locking has been replaced by multiversion concurrency control, which allows readers to continue reading consistent data during writer activity and enables hot backups from pg_dump while the database stays available for queries.
- Important backend features, including subselects, defaults, constraints, and triggers, have been implemented.
- Additional SQL92-compliant language features have been added, including primary keys, quoted identifiers, literal string type coercion, type casting, and binary and hexadecimal integer input.
- Built-in types have been improved, including new wide-range date/time types and additional geometric type support.
- Overall backend code speed has been increased by approximately 20-40%, and backend start-up time has decreased by 80% since version 6.0 was released.

3. What's In This Book

This book describes the use of the SQL language in PostgreSQL. We start with describing the general syntax of SQL, then explain how to create the structures to hold data, how to populate the database, and how to query it. The middle part lists the available data types and functions for use in SQL data commands. The rest of the book treats several aspects that are important for tuning a database for optimal performance.

The information in this book is arranged so that a novice user can follow it start to end to gain a full understanding of the topics without having to refer forward too many times. The chapters are intended to be self-contained, so that advanced users can read the chapters individually as they choose. The information in this book is presented in a narrative fashion in topical units. Readers looking for a complete description of a particular command should look into the PostgreSQL 7.3.21 Reference Manual.

Readers of this book should know how to connect to a PostgreSQL database and issue SQL commands. Readers that are unfamiliar with these issues are encouraged to read the PostgreSQL 7.3.21 Tutorial first. SQL commands are typically entered using the PostgreSQL interactive terminal psql, but other programs that have similar functionality can be used as well.

This book covers PostgreSQL 7.3.21 only. For information on other versions, please read the documentation that accompanies that release.

4. Overview of Documentation Resources

The PostgreSQL documentation is organized into several books:

PostgreSQL 7.3.21 Tutorial

An informal introduction for new users.

PostgreSQL 7.3.21 User's Guide

Documents the SQL query language environment, including data types and functions, as well as user-level performance tuning. Every PostgreSQL user should read this.

PostgreSQL 7.3.21 Administrator's Guide

Installation and server management information. Everyone who runs a PostgreSQL server, either for personal use or for other users, needs to read this.

PostgreSQL 7.3.21 Programmer's Guide

Advanced information for application programmers. Topics include type and function extensibility, library interfaces, and application design issues.

PostgreSQL 7.3.21 Reference Manual

Reference pages for SQL command syntax, and client and server programs. This book is auxiliary to the User's, Administrator's, and Programmer's Guides.

PostgreSQL 7.3.21 Developer's Guide

Information for PostgreSQL developers. This is intended for those who are contributing to the PostgreSQL project; application development information appears in the *Programmer's Guide*.

In addition to this manual set, there are other resources to help you with PostgreSQL installation and use:

man pages

The *Reference Manual*'s pages in the traditional Unix man format. There is no difference in content.

FAQs

Frequently Asked Questions (FAQ) lists document both general issues and some platform-specific issues.

READMEs

README files are available for some contributed packages.

Web Site

The PostgreSQL web site[5] carries details on the latest release, upcoming features, and other information to make your work or play with PostgreSQL more productive.

Mailing Lists

The mailing lists are a good place to have your questions answered, to share experiences with other users, and to contact the developers. Consult the User's Lounge[6] section of the PostgreSQL web site for details.

Yourself!

PostgreSQL is an open-source effort. As such, it depends on the user community for ongoing support. As you begin to use PostgreSQL, you will rely on others for help, either through the documentation or through the mailing lists. Consider contributing your knowledge back. If you learn something which is not in the documentation, write it up and contribute it. If you add features to the code, contribute them.

[5] http://www.postgresql.org
[6] http://www.postgresql.org/users-lounge/

Even those without a lot of experience can provide corrections and minor changes in the documentation, and that is a good way to start. The <pgsql-docs@postgresql.org> mailing list is the place to get going.

5. Terminology and Notation

An *administrator* is generally a person who is in charge of installing and running the server. A *user* could be anyone who is using, or wants to use, any part of the PostgreSQL system. These terms should not be interpreted too narrowly; this documentation set does not have fixed presumptions about system administration procedures.

We use `/usr/local/pgsql/` as the root directory of the installation and `/usr/local/pgsql/data` as the directory with the database files. These directories may vary on your site, details can be derived in the *Administrator's Guide*.

In a command synopsis, brackets (`[` and `]`) indicate an optional phrase or keyword. Anything in braces (`{` and `}`) and containing vertical bars (`|`) indicates that you must choose one alternative.

Examples will show commands executed from various accounts and programs. Commands executed from a Unix shell may be preceded with a dollar sign ("`$`"). Commands executed from particular user accounts such as root or postgres are specially flagged and explained. SQL commands may be preceded with "=>" or will have no leading prompt, depending on the context.

Note

The notation for flagging commands is not universally consistent throughout the documentation set. Please report problems to the documentation mailing list <pgsql-docs@postgresql.org>.

6. Bug Reporting Guidelines

When you find a bug in PostgreSQL we want to hear about it. Your bug reports play an important part in making PostgreSQL more reliable because even the utmost care cannot guarantee that every part of PostgreSQL will work on every platform under every circumstance.

The following suggestions are intended to assist you in forming bug reports that can be handled in an effective fashion. No one is required to follow them but it tends to be to everyone's advantage.

We cannot promise to fix every bug right away. If the bug is obvious, critical, or affects a lot of users, chances are good that someone will look into it. It could also happen that we tell you to update to a newer version to see if the bug happens there. Or we might decide that the bug cannot be fixed before some major rewrite we might be planning is done. Or perhaps it is simply too hard and there are more important things on the agenda. If you need help immediately, consider obtaining a commercial support contract.

6.1. Identifying Bugs

Before you report a bug, please read and re-read the documentation to verify that you can really do whatever it is you are trying. If it is not clear from the documentation whether you can do something or not, please report that too; it is a bug in the documentation. If it turns out that the program does something different from what the documentation says, that is a bug. That might include, but is not limited to, the following circumstances:

- A program terminates with a fatal signal or an operating system error message that would point to a problem in the program. (A counterexample might be a "disk full" message, since you have to fix that yourself.)
- A program produces the wrong output for any given input.

- A program refuses to accept valid input (as defined in the documentation).
- A program accepts invalid input without a notice or error message. But keep in mind that your idea of invalid input might be our idea of an extension or compatibility with traditional practice.
- PostgreSQL fails to compile, build, or install according to the instructions on supported platforms.

Here “program” refers to any executable, not only the backend server.

Being slow or resource-hogging is not necessarily a bug. Read the documentation or ask on one of the mailing lists for help in tuning your applications. Failing to comply to the SQL standard is not necessarily a bug either, unless compliance for the specific feature is explicitly claimed.

Before you continue, check on the TODO list and in the FAQ to see if your bug is already known. If you cannot decode the information on the TODO list, report your problem. The least we can do is make the TODO list clearer.

6.2. What to report

The most important thing to remember about bug reporting is to state all the facts and only facts. Do not speculate what you think went wrong, what “it seemed to do”, or which part of the program has a fault. If you are not familiar with the implementation you would probably guess wrong and not help us a bit. And even if you are, educated explanations are a great supplement to but no substitute for facts. If we are going to fix the bug we still have to see it happen for ourselves first. Reporting the bare facts is relatively straightforward (you can probably copy and paste them from the screen) but all too often important details are left out because someone thought it does not matter or the report would be understood anyway.

The following items should be contained in every bug report:

- The exact sequence of steps *from program start-up* necessary to reproduce the problem. This should be self-contained; it is not enough to send in a bare select statement without the preceding create table and insert statements, if the output should depend on the data in the tables. We do not have the time to reverse-engineer your database schema, and if we are supposed to make up our own data we would probably miss the problem. The best format for a test case for query-language related problems is a file that can be run through the psql frontend that shows the problem. (Be sure to not have anything in your `~/.psqlrc` start-up file.) An easy start at this file is to use pg_dump to dump out the table declarations and data needed to set the scene, then add the problem query. You are encouraged to minimize the size of your example, but this is not absolutely necessary. If the bug is reproducible, we will find it either way.

  If your application uses some other client interface, such as PHP, then please try to isolate the offending queries. We will probably not set up a web server to reproduce your problem. In any case remember to provide the exact input files, do not guess that the problem happens for “large files” or “mid-size databases”, etc. since this information is too inexact to be of use.

- The output you got. Please do not say that it “didn't work” or “crashed”. If there is an error message, show it, even if you do not understand it. If the program terminates with an operating system error, say which. If nothing at all happens, say so. Even if the result of your test case is a program crash or otherwise obvious it might not happen on our platform. The easiest thing is to copy the output from the terminal, if possible.

  > **Note**
  >
  > In case of fatal errors, the error message reported by the client might not contain all the information available. Please also look at the log output of the database server. If you do not keep your server's log output, this would be a good time to start doing so.

- The output you expected is very important to state. If you just write “This command gives me that output.” or “This is not what I expected.”, we might run it ourselves, scan the output, and think it

looks OK and is exactly what we expected. We should not have to spend the time to decode the exact semantics behind your commands. Especially refrain from merely saying that "This is not what SQL says/Oracle does." Digging out the correct behavior from SQL is not a fun undertaking, nor do we all know how all the other relational databases out there behave. (If your problem is a program crash, you can obviously omit this item.)

- Any command line options and other start-up options, including concerned environment variables or configuration files that you changed from the default. Again, be exact. If you are using a prepackaged distribution that starts the database server at boot time, you should try to find out how that is done.

- Anything you did at all differently from the installation instructions.

- The PostgreSQL version. You can run the command `SELECT version();` to find out the version of the server you are connected to. Most executable programs also support a `--version` option; at least `postmaster --version` and `psql --version` should work. If the function or the options do not exist then your version is more than old enough to warrant an upgrade. You can also look into the `README` file in the source directory or at the name of your distribution file or package name. If you run a prepackaged version, such as RPMs, say so, including any subversion the package may have. If you are talking about a CVS snapshot, mention that, including its date and time.

  If your version is older than 7.3.21 we will almost certainly tell you to upgrade. There are tons of bug fixes in each new release, that is why we make new releases.

- Platform information. This includes the kernel name and version, C library, processor, memory information. In most cases it is sufficient to report the vendor and version, but do not assume everyone knows what exactly "Debian" contains or that everyone runs on Pentiums. If you have installation problems then information about compilers, make, etc. is also necessary.

Do not be afraid if your bug report becomes rather lengthy. That is a fact of life. It is better to report everything the first time than us having to squeeze the facts out of you. On the other hand, if your input files are huge, it is fair to ask first whether somebody is interested in looking into it.

Do not spend all your time to figure out which changes in the input make the problem go away. This will probably not help solving it. If it turns out that the bug cannot be fixed right away, you will still have time to find and share your work-around. Also, once again, do not waste your time guessing why the bug exists. We will find that out soon enough.

When writing a bug report, please choose non-confusing terminology. The software package in total is called "PostgreSQL", sometimes "Postgres" for short. If you are specifically talking about the backend server, mention that, do not just say "PostgreSQL crashes". A crash of a single backend server process is quite different from crash of the parent "postmaster" process; please don't say "the postmaster crashed" when you mean a single backend went down, nor vice versa. Also, client programs such as the interactive frontend "psql" are completely separate from the backend. Please try to be specific about whether the problem is on the client or server side.

6.3. Where to report bugs

In general, send bug reports to the bug report mailing list at <pgsql-bugs@postgresql.org>. You are requested to use a descriptive subject for your email message, perhaps parts of the error message.

Another method is to fill in the bug report web-form available at the project's web site http://www.postgresql.org/. Entering a bug report this way causes it to be mailed to the <pgsql-bugs@postgresql.org> mailing list.

If your bug report has security implications and you'd prefer that it not become immediately visible in public archives, don't send it to `pgsql-bugs`. Security issues can be reported privately to <security@postgresql.org>.

Do not send bug reports to any of the user mailing lists, such as <pgsql-sql@postgresql.org> or <pgsql-general@postgresql.org>. These mailing lists are for answering user questions and their subscribers normally do not wish to receive bug reports. More importantly, they are unlikely to fix them.

Also, please do *not* send reports to the developers' mailing list <pgsql-hackers@postgresql.org>. This list is for discussing the development of PostgreSQL and it would be nice if we could keep the bug reports separate. We might choose to take up a discussion about your bug report on pgsql-hackers, if the problem needs more review.

If you have a problem with the documentation, the best place to report it is the documentation mailing list <pgsql-docs@postgresql.org>. Please be specific about what part of the documentation you are unhappy with.

If your bug is a portability problem on a non-supported platform, send mail to <pgsql-ports@postgresql.org>, so we (and you) can work on porting PostgreSQL to your platform.

Note

Due to the unfortunate amount of spam going around, all of the above email addresses are closed mailing lists. That is, you need to be subscribed to a list to be allowed to post on it. (You need not be subscribed to use the bug report web-form, however.) If you would like to send mail but do not want to receive list traffic, you can subscribe and set your subscription option to nomail. For more information send mail to <majordomo@postgresql.org> with the single word help in the body of the message.

Chapter 1. SQL Syntax

This chapter describes the syntax of SQL. It forms the foundation for understanding the following chapters which will go into detail about how the SQL commands are applied to define and modify data.

We also advise users who are already familiar with SQL to read this chapter carefully because there are several rules and concepts that are implemented inconsistently among SQL databases or that are specific to PostgreSQL.

1.1. Lexical Structure

SQL input consists of a sequence of *commands*. A command is composed of a sequence of *tokens*, terminated by a semicolon (";"). The end of the input stream also terminates a command. Which tokens are valid depends on the syntax of the particular command.

A token can be a *key word*, an *identifier*, a *quoted identifier*, a *literal* (or constant), or a special character symbol. Tokens are normally separated by whitespace (space, tab, newline), but need not be if there is no ambiguity (which is generally only the case if a special character is adjacent to some other token type).

Additionally, *comments* can occur in SQL input. They are not tokens, they are effectively equivalent to whitespace.

For example, the following is (syntactically) valid SQL input:

```
SELECT * FROM MY_TABLE;
UPDATE MY_TABLE SET A = 5;
INSERT INTO MY_TABLE VALUES (3, 'hi there');
```

This is a sequence of three commands, one per line (although this is not required; more than one command can be on a line, and commands can usefully be split across lines).

The SQL syntax is not very consistent regarding what tokens identify commands and which are operands or parameters. The first few tokens are generally the command name, so in the above example we would usually speak of a "SELECT", an "UPDATE", and an "INSERT" command. But for instance the `UPDATE` command always requires a `SET` token to appear in a certain position, and this particular variation of `INSERT` also requires a `VALUES` in order to be complete. The precise syntax rules for each command are described in the PostgreSQL 7.3.21 Reference Manual.

1.1.1. Identifiers and Key Words

Tokens such as `SELECT`, `UPDATE`, or `VALUES` in the example above are examples of *key words*, that is, words that have a fixed meaning in the SQL language. The tokens `MY_TABLE` and `A` are examples of *identifiers*. They identify names of tables, columns, or other database objects, depending on the command they are used in. Therefore they are sometimes simply called "names". Key words and identifiers have the same lexical structure, meaning that one cannot know whether a token is an identifier or a key word without knowing the language. A complete list of key words can be found in Appendix B, *SQL Key Words*.

SQL identifiers and key words must begin with a letter (`a-z`, but also letters with diacritical marks and non-Latin letters) or an underscore (_). Subsequent characters in an identifier or key word can be letters, digits (`0-9`), or underscores, although the SQL standard will not define a key word that contains digits or starts or ends with an underscore.

The system uses no more than `NAMEDATALEN`-1 characters of an identifier; longer names can be written in commands, but they will be truncated. By default, `NAMEDATALEN` is 64 so the maximum identifier length is 63 (but at the time PostgreSQL is built, `NAMEDATALEN` can be changed in `src/include/postgres_ext.h`).

Identifier and key word names are case insensitive. Therefore

```
UPDATE MY_TABLE SET A = 5;
```

can equivalently be written as

```
uPDaTE my_TabLE SeT a = 5;
```

A convention often used is to write key words in upper case and names in lower case, e.g.,

```
UPDATE my_table SET a = 5;
```

There is a second kind of identifier: the *delimited identifier* or *quoted identifier*. It is formed by enclosing an arbitrary sequence of characters in double-quotes (`"`). A delimited identifier is always an identifier, never a key word. So `"select"` could be used to refer to a column or table named "select", whereas an unquoted `select` would be taken as a key word and would therefore provoke a parse error when used where a table or column name is expected. The example can be written with quoted identifiers like this:

```
UPDATE "my_table" SET "a" = 5;
```

Quoted identifiers can contain any character other than a double quote itself. To include a double quote, write two double quotes. This allows constructing table or column names that would otherwise not be possible, such as ones containing spaces or ampersands. The length limitation still applies.

Quoting an identifier also makes it case-sensitive, whereas unquoted names are always folded to lower case. For example, the identifiers `FOO`, `foo` and `"foo"` are considered the same by PostgreSQL, but `"Foo"` and `"FOO"` are different from these three and each other. [1]

1.1.2. Constants

There are three kinds of *implicitly-typed constants* in PostgreSQL: strings, bit strings, and numbers. Constants can also be specified with explicit types, which can enable more accurate representation and more efficient handling by the system. The implicit constants are described below; explicit constants are discussed afterwards.

1.1.2.1. String Constants

A string constant in SQL is an arbitrary sequence of characters bounded by single quotes ("'"), e.g., `'This is a string'`. SQL allows single quotes to be embedded in strings by typing two adjacent single quotes (e.g., `'Dianne''s horse'`). In PostgreSQL single quotes may alternatively be escaped with a backslash ("\", e.g., `'Dianne\'s horse'`).

C-style backslash escapes are also available: `\b` is a backspace, `\f` is a form feed, `\n` is a newline, `\r` is a carriage return, `\t` is a tab, and `\`*xxx*, where *xxx* is an octal number, is the character with the corresponding ASCII code. Any other character following a backslash is taken literally. Thus, to include a backslash in a string constant, type two backslashes.

The character with the code zero cannot be in a string constant.

Two string constants that are only separated by whitespace *with at least one newline* are concatenated and effectively treated as if the string had been written in one constant. For example:

```
SELECT 'foo'
'bar';
```

is equivalent to

[1] The folding of unquoted names to lower case in PostgreSQL is incompatible with the SQL standard, which says that unquoted names should be folded to upper case. Thus, `foo` should be equivalent to `"FOO"` not `"foo"` according to the standard. If you want to write portable applications you are advised to always quote a particular name or never quote it.

```
SELECT 'foobar';
```

but

```
SELECT 'foo'      'bar';
```

is not valid syntax. (This slightly bizarre behavior is specified by SQL; PostgreSQL is following the standard.)

1.1.2.2. Bit-String Constants

Bit-string constants look like string constants with a `B` (upper or lower case) immediately before the opening quote (no intervening whitespace), e.g., `B'1001'`. The only characters allowed within bit-string constants are `0` and `1`.

Alternatively, bit-string constants can be specified in hexadecimal notation, using a leading `X` (upper or lower case), e.g., `X'1FF'`. This notation is equivalent to a bit-string constant with four binary digits for each hexadecimal digit.

Both forms of bit-string constant can be continued across lines in the same way as regular string constants.

1.1.2.3. Numeric Constants

Numeric constants are accepted in these general forms:

digits
digits.[*digits*][e[+-]*digits*]
[*digits*].*digits*[e[+-]*digits*]
*digits*e[+-]*digits*

where *digits* is one or more decimal digits (0 through 9). At least one digit must be before or after the decimal point, if one is used. At least one digit must follow the exponent marker (`e`), if one is present. There may not be any spaces or other characters embedded in the constant. Note that any leading plus or minus sign is not actually considered part of the constant; it is an operator applied to the constant.

These are some examples of valid numeric constants:

42
3.5
4.
.001
5e2
1.925e-3

A numeric constant that contains neither a decimal point nor an exponent is initially presumed to be type `integer` if its value fits in type `integer` (32 bits); otherwise it is presumed to be type `bigint` if its value fits in type `bigint` (64 bits); otherwise it is taken to be type `numeric`. Constants that contain decimal points and/or exponents are always initially presumed to be type `numeric`.

The initially assigned data type of a numeric constant is just a starting point for the type resolution algorithms. In most cases the constant will be automatically coerced to the most appropriate type depending on context. When necessary, you can force a numeric value to be interpreted as a specific data type by casting it. For example, you can force a numeric value to be treated as type `real` (`float4`) by writing

```
REAL '1.23'  -- string style
1.23::REAL   -- PostgreSQL (historical) style
```

1.1.2.4. Constants of Other Types

A constant of an *arbitrary* type can be entered using any one of the following notations:

```
type 'string'
'string'::type
CAST ( 'string' AS type )
```

The string's text is passed to the input conversion routine for the type called *type*. The result is a constant of the indicated type. The explicit type cast may be omitted if there is no ambiguity as to the type the constant must be (for example, when it is passed as an argument to a non-overloaded function), in which case it is automatically coerced.

It is also possible to specify a type coercion using a function-like syntax:

```
typename ( 'string' )
```

but not all type names may be used in this way; see Section 1.2.6, “Type Casts” for details.

The `::`, `CAST()`, and function-call syntaxes can also be used to specify run-time type conversions of arbitrary expressions, as discussed in Section 1.2.6, “Type Casts”. But the form *type* '*string*' can only be used to specify the type of a literal constant. Another restriction on *type* '*string*' is that it does not work for array types; use `::` or `CAST()` to specify the type of an array constant.

1.1.2.5. Array constants

The general format of an array constant is the following:

```
'{ val1 delim val2 delim ... }'
```

where *delim* is the delimiter character for the type, as recorded in its `pg_type` entry. (For all built-in types, this is the comma character “`,`”.) Each *val* is either a constant of the array element type, or a subarray. An example of an array constant is

```
'{{1,2,3},{4,5,6},{7,8,9}}'
```

This constant is a two-dimensional, 3-by-3 array consisting of three subarrays of integers.

Individual array elements can be placed between double-quote marks (`"`) to avoid ambiguity problems with respect to whitespace. Without quote marks, the array-value parser will skip leading whitespace.

(Array constants are actually only a special case of the generic type constants discussed in the previous section. The constant is initially treated as a string and passed to the array input conversion routine. An explicit type specification might be necessary.)

1.1.3. Operators

An operator is a sequence of up to `NAMEDATALEN`-1 (63 by default) characters from the following list:

+ - * / < > = ~ ! @ # % ^ & | ` ? $

There are a few restrictions on operator names, however:

- `$` (dollar) cannot be a single-character operator, although it can be part of a multiple-character operator name.
- `--` and `/*` cannot appear anywhere in an operator name, since they will be taken as the start of a comment.
- A multiple-character operator name cannot end in + or −, unless the name also contains at least one of these characters:

~ ! @ # % ^ & | ` ? $

For example, `@-` is an allowed operator name, but `*-` is not. This restriction allows PostgreSQL to parse SQL-compliant queries without requiring spaces between tokens.

When working with non-SQL-standard operator names, you will usually need to separate adjacent operators with spaces to avoid ambiguity. For example, if you have defined a left unary operator named `@`, you cannot write `X*@Y`; you must write `X* @Y` to ensure that PostgreSQL reads it as two operator names not one.

1.1.4. Special Characters

Some characters that are not alphanumeric have a special meaning that is different from being an operator. Details on the usage can be found at the location where the respective syntax element is described. This section only exists to advise the existence and summarize the purposes of these characters.

- A dollar sign (`$`) followed by digits is used to represent the positional parameters in the body of a function definition. In other contexts the dollar sign may be part of an operator name.
- Parentheses (`()`) have their usual meaning to group expressions and enforce precedence. In some cases parentheses are required as part of the fixed syntax of a particular SQL command.
- Brackets (`[]`) are used to select the elements of an array. See Section 5.12, “Arrays” for more information on arrays.
- Commas (`,`) are used in some syntactical constructs to separate the elements of a list.
- The semicolon (`;`) terminates an SQL command. It cannot appear anywhere within a command, except within a string constant or quoted identifier.
- The colon (`:`) is used to select “slices” from arrays. (See Section 5.12, “Arrays”.) In certain SQL dialects (such as Embedded SQL), the colon is used to prefix variable names.
- The asterisk (`*`) has a special meaning when used in the `SELECT` command or with the `COUNT` aggregate function.
- The period (`.`) is used in floating-point constants, and to separate schema, table, and column names.

1.1.5. Comments

A comment is an arbitrary sequence of characters beginning with double dashes and extending to the end of the line, e.g.:

```
-- This is a standard SQL92 comment
```

Alternatively, C-style block comments can be used:

```
/* multiline comment
 * with nesting: /* nested block comment */
 */
```

where the comment begins with `/*` and extends to the matching occurrence of `*/`. These block comments nest, as specified in SQL99 but unlike C, so that one can comment out larger blocks of code that may contain existing block comments.

A comment is removed from the input stream before further syntax analysis and is effectively replaced by whitespace.

1.1.6. Lexical Precedence

Table 1.1, “Operator Precedence (decreasing)” shows the precedence and associativity of the operators in PostgreSQL. Most operators have the same precedence and are left-associative. The precedence and associativity of the operators is hard-wired into the parser. This may lead to non-intuitive behavior; for example the Boolean operators < and > have a different precedence than the Boolean operators <= and >=. Also, you will sometimes need to add parentheses when using combinations of binary and unary operators. For instance

```
SELECT 5 ! - 6;
```

will be parsed as

```
SELECT 5 ! (- 6);
```

because the parser has no idea -- until it is too late -- that `!` is defined as a postfix operator, not an infix one. To get the desired behavior in this case, you must write

```
SELECT (5 !) - 6;
```

This is the price one pays for extensibility.

Table 1.1. Operator Precedence (decreasing)

Operator/Element	Associativity	Description
`.`	left	table/column name separator
`::`	left	PostgreSQL-style typecast
`[ ]`	left	array element selection
`-`	right	unary minus
`^`	left	exponentiation
`* / %`	left	multiplication, division, modulo
`+ -`	left	addition, subtraction
`IS`		`IS TRUE, IS FALSE, IS UNKNOWN, IS NULL`
`ISNULL`		test for null
`NOTNULL`		test for not null
(any other)	left	all other native and user-defined operators
`IN`		set membership
`BETWEEN`		containment
`OVERLAPS`		time interval overlap
`LIKE ILIKE SIMILAR`		string pattern matching
`< >`		less than, greater than
`=`	right	equality, assignment
`NOT`	right	logical negation
`AND`	left	logical conjunction
`OR`	left	logical disjunction

Note that the operator precedence rules also apply to user-defined operators that have the same names as the built-in operators mentioned above. For example, if you define a “+” operator for some custom data type it will have the same precedence as the built-in “+” operator, no matter what yours does.

When a schema-qualified operator name is used in the OPERATOR syntax, as for example in

```
SELECT 3 OPERATOR(pg_catalog.+) 4;
```

the OPERATOR construct is taken to have the default precedence shown in Table 1.1, “Operator Precedence (decreasing)” for “any other” operator. This is true no matter which specific operator name appears inside OPERATOR().

1.2. Value Expressions

Value expressions are used in a variety of contexts, such as in the target list of the SELECT command, as new column values in INSERT or UPDATE, or in search conditions in a number of commands. The result of a value expression is sometimes called a *scalar*, to distinguish it from the result of a table expression (which is a table). Value expressions are therefore also called *scalar expressions* (or even simply *expressions*). The expression syntax allows the calculation of values from primitive parts using arithmetic, logical, set, and other operations.

A value expression is one of the following:

- A constant or literal value; see Section 1.1.2, “Constants”.
- A column reference.
- A positional parameter reference, in the body of a function declaration.
- An operator invocation.
- A function call.
- An aggregate expression.
- A type cast.
- A scalar subquery.
- Another value expression in parentheses, useful to group subexpressions and override precedence.

In addition to this list, there are a number of constructs that can be classified as an expression but do not follow any general syntax rules. These generally have the semantics of a function or operator and are explained in the appropriate location in Chapter 6, *Functions and Operators*. An example is the IS NULL clause.

We have already discussed constants in Section 1.1.2, “Constants”. The following sections discuss the remaining options.

1.2.1. Column References

A column can be referenced in the form

correlation.*columnname*

or

correlation.*columnname*[*subscript*]

(Here, the brackets [ ] are meant to appear literally.)

correlation is the name of a table (possibly qualified), or an alias for a table defined by means of a FROM clause, or the key words NEW or OLD. (NEW and OLD can only appear in rewrite rules, while other correlation names can be used in any SQL statement.) The correlation name and separating dot

may be omitted if the column name is unique across all the tables being used in the current query. (See also Chapter 4, *Queries*.)

If *column* is of an array type, then the optional *subscript* selects a specific element or elements in the array. If no subscript is provided, then the whole array is selected. (See Section 5.12, "Arrays" for more about arrays.)

1.2.2. Positional Parameters

A positional parameter reference is used to indicate a parameter that is supplied externally to an SQL statement. Parameters are used in SQL function definitions and in prepared queries. The form of a parameter reference is:

```
$number
```

For example, consider the definition of a function, dept, as

```
CREATE FUNCTION dept(text) RETURNS dept
    AS 'SELECT * FROM dept WHERE name = $1'
    LANGUAGE SQL;
```

Here the $1 will be replaced by the first function argument when the function is invoked.

1.2.3. Operator Invocations

There are three possible syntaxes for an operator invocation:

expression operator expression (binary infix operator)
operator expression (unary prefix operator)
expression operator (unary postfix operator)
where the *operator* token follows the syntax rules of Section 1.1.3, "Operators", or is one of the keywords AND, OR, and NOT, or is a qualified operator name

```
OPERATOR(schema.operatorname)
```

Which particular operators exist and whether they are unary or binary depends on what operators have been defined by the system or the user. Chapter 6, *Functions and Operators* describes the built-in operators.

1.2.4. Function Calls

The syntax for a function call is the name of a function (possibly qualified with a schema name), followed by its argument list enclosed in parentheses:

```
function ([expression [, expression ... ]] )
```

For example, the following computes the square root of 2:

```
sqrt(2)
```

The list of built-in functions is in Chapter 6, *Functions and Operators*. Other functions may be added by the user.

1.2.5. Aggregate Expressions

An *aggregate expression* represents the application of an aggregate function across the rows selected by a query. An aggregate function reduces multiple inputs to a single output value, such as the sum or average of the inputs. The syntax of an aggregate expression is one of the following:

```
aggregate_name (expression)
aggregate_name (ALL expression)
aggregate_name (DISTINCT expression)
aggregate_name ( * )
```

where *aggregate_name* is a previously defined aggregate (possibly a qualified name), and *expression* is any value expression that does not itself contain an aggregate expression.

The first form of aggregate expression invokes the aggregate across all input rows for which the given expression yields a non-null value. (Actually, it is up to the aggregate function whether to ignore null values or not --- but all the standard ones do.) The second form is the same as the first, since `ALL` is the default. The third form invokes the aggregate for all distinct non-null values of the expression found in the input rows. The last form invokes the aggregate once for each input row regardless of null or non-null values; since no particular input value is specified, it is generally only useful for the `count()` aggregate function.

For example, `count(*)` yields the total number of input rows; `count(f1)` yields the number of input rows in which `f1` is non-null; `count(distinct f1)` yields the number of distinct non-null values of `f1`.

The predefined aggregate functions are described in Section 6.14, “Aggregate Functions”. Other aggregate functions may be added by the user.

1.2.6. Type Casts

A type cast specifies a conversion from one data type to another. PostgreSQL accepts two equivalent syntaxes for type casts:

```
CAST ( expression AS type )
expression::type
```

The `CAST` syntax conforms to SQL; the syntax with `::` is historical PostgreSQL usage.

When a cast is applied to a value expression of a known type, it represents a run-time type conversion. The cast will succeed only if a suitable type conversion function is available. Notice that this is subtly different from the use of casts with constants, as shown in Section 1.1.2.4, “Constants of Other Types”. A cast applied to an unadorned string literal represents the initial assignment of a type to a literal constant value, and so it will succeed for any type (if the contents of the string literal are acceptable input syntax for the data type).

An explicit type cast may usually be omitted if there is no ambiguity as to the type that a value expression must produce (for example, when it is assigned to a table column); the system will automatically apply a type cast in such cases. However, automatic casting is only done for casts that are marked “OK to apply implicitly” in the system catalogs. Other casts must be invoked with explicit casting syntax. This restriction is intended to prevent surprising conversions from being applied silently.

It is also possible to specify a type cast using a function-like syntax:

```
typename ( expression )
```

However, this only works for types whose names are also valid as function names. For example, `double precision` can't be used this way, but the equivalent `float8` can. Also, the names `interval`, `time`, and `timestamp` can only be used in this fashion if they are double-quoted, because of syntactic conflicts. Therefore, the use of the function-like cast syntax leads to inconsistencies and should probably be avoided in new applications. (The function-like syntax is in fact just a function call. When one of the two standard cast syntaxes is used to do a run-time conversion, it will internally invoke a registered function to perform the conversion. By convention, these conversion functions have the same name as their output type, but this is not something that a portable application should rely on.)

1.2.7. Scalar Subqueries

A scalar subquery is an ordinary `SELECT` query in parentheses that returns exactly one row with one column. (See Chapter 4, *Queries* for information about writing queries.) The `SELECT` query is executed and the single returned value is used in the surrounding value expression. It is an error to use a query that returns more than one row or more than one column as a scalar subquery. (But if, during a particular execution, the subquery returns no rows, there is no error; the scalar result is taken to be null.) The subquery can refer to variables from the surrounding query, which will act as constants during any one evaluation of the subquery. See also Section 6.15, “Subquery Expressions”.

For example, the following finds the largest city population in each state:

```
SELECT name, (SELECT max(pop) FROM cities WHERE cities.state =
 states.name)
    FROM states;
```

1.2.8. Expression Evaluation

The order of evaluation of subexpressions is not defined. In particular, the inputs of an operator or function are not necessarily evaluated left-to-right or in any other fixed order.

Furthermore, if the result of an expression can be determined by evaluating only some parts of it, then other subexpressions might not be evaluated at all. For instance, if one wrote

```
SELECT true OR somefunc();
```

then `somefunc()` would (probably) not be called at all. The same would be the case if one wrote

```
SELECT somefunc() OR true;
```

Note that this is not the same as the left-to-right “short-circuiting” of Boolean operators that is found in some programming languages.

As a consequence, it is unwise to use functions with side effects as part of complex expressions. It is particularly dangerous to rely on side effects or evaluation order in `WHERE` and `HAVING` clauses, since those clauses are extensively reprocessed as part of developing an execution plan. Boolean expressions (`AND`/`OR`/`NOT` combinations) in those clauses may be reorganized in any manner allowed by the laws of Boolean algebra.

When it is essential to force evaluation order, a `CASE` construct (see Section 6.12, “Conditional Expressions”) may be used. For example, this is an untrustworthy way of trying to avoid division by zero in a `WHERE` clause:

```
SELECT ... WHERE x <> 0 AND y/x > 1.5;
```

But this is safe:

```
SELECT ... WHERE CASE WHEN x <> 0 THEN y/x > 1.5 ELSE false END;
```

A `CASE` construct used in this fashion will defeat optimization attempts, so it should only be done when necessary.

Chapter 2. Data Definition

This chapter covers how one creates the database structures that will hold one's data. In a relational database, the raw data is stored in tables, so the majority of this chapter is devoted to explaining how tables are created and modified and what features are available to control what data is stored in the tables. Subsequently, we discuss how tables can be organized into schemas, and how privileges can be assigned to tables. Finally, we will briefly look at other features that affect the data storage, such as views, functions, and triggers. Detailed information on these topics is found in the PostgreSQL 7.3.21 Programmer's Guide.

2.1. Table Basics

A table in a relational database is much like a table on paper: It consists of rows and columns. The number and order of the columns is fixed, and each column has a name. The number of rows is variable -- it reflects how much data is stored at a given moment. SQL does not make any guarantees about the order of the rows in a table. When a table is read, the rows will appear in random order, unless sorting is explicitly requested. This is covered in Chapter 4, *Queries*. Furthermore, SQL does not assign unique identifiers to rows, so it is possible to have several completely identical rows in a table. This is a consequence of the mathematical model that underlies SQL but is usually not desirable. Later in this chapter we will see how to deal with this issue.

Each column has a data type. The data type constrains the set of possible values that can be assigned to a column and assigns semantics to the data stored in the column so that it can be used for computations. For instance, a column declared to be of a numerical type will not accept arbitrary text strings, and the data stored in such a column can be used for mathematical computations. By contrast, a column declared to be of a character string type will accept almost any kind of data but it does not lend itself to mathematical calculations, although other operations such as string concatenation are available.

PostgreSQL includes a sizable set of built-in data types that fit many applications. Users can also define their own data types. Most built-in data types have obvious names and semantics, so we defer a detailed explanation to Chapter 5, *Data Types*. Some of the frequently used data types are `integer` for whole numbers, `numeric` for possibly fractional numbers, `text` for character strings, `date` for dates, `time` for time-of-day values, and `timestamp` for values containing both date and time.

To create a table, you use the aptly named `CREATE TABLE` command. In this command you specify at least a name for the new table, the names of the columns and the data type of each column. For example:

```
CREATE TABLE my_first_table (
    first_column text,
    second_column integer
);
```

This creates a table named `my_first_table` with two columns. The first column is named `first_column` and has a data type of `text`; the second column has the name `second_column` and the type `integer`. The table and column names follow the identifier syntax explained in Section 1.1.1, “Identifiers and Key Words”. The type names are usually also identifiers, but there are some exceptions. Note that the column list is comma-separated and surrounded by parentheses.

Of course, the previous example was heavily contrived. Normally, you would give names to your tables and columns that convey what kind of data they store. So let's look at a more realistic example:

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric
);
```

(The `numeric` type can store fractional components, as would be typical of monetary amounts.)

Tip

When you create many interrelated tables it is wise to choose a consistent naming pattern for the tables and columns. For instance, there is a choice of using singular or plural nouns for table names, both of which are favored by some theorist or other.

There is a limit on how many columns a table can contain. Depending on the column types, it is between 250 and 1600. However, defining a table with anywhere near this many columns is highly unusual and often a questionable design.

If you don't need a table anymore, you can remove it using the `DROP TABLE` command. For example:

```
DROP TABLE my_first_table;
DROP TABLE products;
```

Attempting to drop a table that does not exist is an error. Nevertheless, it is common in SQL script files to unconditionally try to drop each table before creating it, ignoring the error messages.

If you need to modify a table that already exists look into Section 2.6, “Modifying Tables” later in this chapter.

With the tools discussed so far you can create fully functional tables. The remainder of this chapter is concerned with adding features to the table definition to ensure data integrity, security, or convenience. If you are eager to fill your tables with data now you can skip ahead to Chapter 3, *Data Manipulation* and read the rest of this chapter later.

2.2. System Columns

Every table has several *system columns* that are implicitly defined by the system. Therefore, these names cannot be used as names of user-defined columns. (Note that these restrictions are separate from whether the name is a key word or not; quoting a name will not allow you to escape these restrictions.) You do not really need to be concerned about these columns, just know they exist.

`oid`

The object identifier (object ID) of a row. This is a serial number that is automatically added by PostgreSQL to all table rows (unless the table was created `WITHOUT OIDS`, in which case this column is not present). This column is of type `oid` (same name as the column); see Section 5.10, “Object Identifier Types” for more information about the type.

`tableoid`

The OID of the table containing this row. This attribute is particularly handy for queries that select from inheritance hierarchies, since without it, it's difficult to tell which individual table a row came from. The `tableoid` can be joined against the `oid` column of `pg_class` to obtain the table name.

`xmin`

The identity (transaction ID) of the inserting transaction for this tuple. (Note: In this context, a tuple is an individual state of a row; each update of a row creates a new tuple for the same logical row.)

`cmin`

The command identifier (starting at zero) within the inserting transaction.

`xmax`

The identity (transaction ID) of the deleting transaction, or zero for an undeleted tuple. It is possible for this field to be nonzero in a visible tuple: That usually indicates that the deleting transaction hasn't committed yet, or that an attempted deletion was rolled back.

`cmax`

The command identifier within the deleting transaction, or zero.

`ctid`

The physical location of the tuple within its table. Note that although the `ctid` can be used to locate the tuple very quickly, a row's `ctid` will change each time it is updated or moved by `VACUUM FULL`. Therefore `ctid` is useless as a long-term row identifier. The OID, or even better a user-defined serial number, should be used to identify logical rows.

2.3. Default Values

A column can be assigned a default value. When a new row is created and no values are specified for some of the columns, the columns will be filled with their respective default values. A data manipulation command can also request explicitly that a column be set to its default value, without knowing what this value is. (Details about data manipulation commands are in Chapter 3, *Data Manipulation*.)

If no default value is declared explicitly, the null value is the default value. This usually makes sense because a null value can be thought to represent unknown data.

In a table definition, default values are listed after the column data type. For example:

```
CREATE TABLE products (
    product_no integer PRIMARY KEY,
    name text,
    price numeric DEFAULT 9.99
);
```

The default value may be a scalar expression, which will be evaluated whenever the default value is inserted (*not* when the table is created).

2.4. Constraints

Data types are a way to limit the kind of data that can be stored in a table. For many applications, however, the constraint they provide is too coarse. For example, a column containing a product price should probably only accept positive values. But there is no data type that accepts only positive numbers. Another issue is that you might want to constrain column data with respect to other columns or rows. For example, in a table containing product information, there should only be one row for each product number.

To that end, SQL allows you to define constraints on columns and tables. Constraints give you as much control over the data in your tables as you wish. If a user attempts to store data in a column that would violate a constraint, an error is raised. This applies even if the value came from the default value definition.

2.4.1. Check Constraints

A check constraint is the most generic constraint type. It allows you to specify that the value in a certain column must satisfy an arbitrary expression. For instance, to require positive product prices, you could use:

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric CHECK (price > 0)
);
```

As you see, the constraint definition comes after the data type, just like default value definitions. Default values and constraints can be listed in any order. A check constraint consists of the key word `CHECK` followed by an expression in parentheses. The check constraint expression should involve the column thus constrained, otherwise the constraint would not make too much sense.

You can also give the constraint a separate name. This clarifies error messages and allows you to refer to the constraint when you need to change it. The syntax is:

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric CONSTRAINT positive_price CHECK (price > 0)
);
```

So, to specify a named constraint, use the key word `CONSTRAINT` followed by an identifier followed by the constraint definition.

A check constraint can also refer to several columns. Say you store a regular price and a discounted price, and you want to ensure that the discounted price is lower than the regular price.

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric CHECK (price > 0),
    discounted_price numeric CHECK (discounted_price > 0),
    CHECK (price > discounted_price)
);
```

The first two constraints should look familiar. The third one uses a new syntax. It is not attached to a particular column, instead it appears as a separate item in the comma-separated column list. Column definitions and these constraint definitions can be listed in mixed order.

We say that the first two constraints are column constraints, whereas the third one is a table constraint because it is written separately from the column definitions. Column constraints can also be written as table constraints, while the reverse is not necessarily possible. The above example could also be written as

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric,
    CHECK (price > 0),
    discounted_price numeric,
    CHECK (discounted_price > 0),
    CHECK (price > discounted_price)
);
```

or even

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric CHECK (price > 0),
    discounted_price numeric,
```

```
    CHECK (discounted_price > 0 AND price > discounted_price)
);
```

It's a matter of taste.

It should be noted that a check constraint is satisfied if the check expression evaluates to true or the null value. Since most expressions will evaluate to the null value if one operand is null they will not prevent null values in the constrained columns. To ensure that a column does not contain null values, the not-null constraint described in the next section should be used.

2.4.2. Not-Null Constraints

A not-null constraint simply specifies that a column must not assume the null value. A syntax example:

```
CREATE TABLE products (
    product_no integer NOT NULL,
    name text NOT NULL,
    price numeric
);
```

A not-null constraint is always written as a column constraint. A not-null constraint is functionally equivalent to creating a check constraint `CHECK (column_name IS NOT NULL)`, but in PostgreSQL creating an explicit not-null constraint is more efficient. The drawback is that you cannot give explicit names to not-null constraints created that way.

Of course, a column can have more than one constraint. Just write the constraints after one another:

```
CREATE TABLE products (
    product_no integer NOT NULL,
    name text NOT NULL,
    price numeric NOT NULL CHECK (price > 0)
);
```

The order doesn't matter. It does not necessarily affect in which order the constraints are checked.

The `NOT NULL` constraint has an inverse: the `NULL` constraint. This does not mean that the column must be null, which would surely be useless. Instead, this simply defines the default behavior that the column may be null. The `NULL` constraint is not defined in the SQL standard and should not be used in portable applications. (It was only added to PostgreSQL to be compatible with other database systems.) Some users, however, like it because it makes it easy to toggle the constraint in a script file. For example, you could start with

```
CREATE TABLE products (
    product_no integer NULL,
    name text NULL,
    price numeric NULL
);
```

and then insert the `NOT` key word where desired.

Tip

In most database designs the majority of columns should be marked not null.

2.4.3. Unique Constraints

Unique constraints ensure that the data contained in a column or a group of columns is unique with respect to all the rows in the table. The syntax is

```
CREATE TABLE products (
```

```
    product_no integer UNIQUE,
    name text,
    price numeric
);
```

when written as a column constraint, and

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric,
    UNIQUE (product_no)
);
```

when written as a table constraint.

If a unique constraint refers to a group of columns, the columns are listed separated by commas:

```
CREATE TABLE example (
    a integer,
    b integer,
    c integer,
    UNIQUE (a, c)
);
```

It is also possible to assign names to unique constraints:

```
CREATE TABLE products (
    product_no integer CONSTRAINT must_be_different UNIQUE,
    name text,
    price numeric
);
```

In general, a unique constraint is violated when there are (at least) two rows in the table where the values of each of the corresponding columns that are part of the constraint are equal. However, null values are not considered equal in this consideration. That means, in the presence of a multicolumn unique constraint it is possible to store an unlimited number of rows that contain a null value in at least one of the constrained columns. This behavior conforms to the SQL standard, but we have heard that other SQL databases may not follow this rule. So be careful when developing applications that are intended to be portable.

2.4.4. Primary Keys

Technically, a primary key constraint is simply a combination of a unique constraint and a not-null constraint. So, the following two table definitions accept the same data:

```
CREATE TABLE products (
    product_no integer UNIQUE NOT NULL,
    name text,
    price numeric
);

CREATE TABLE products (
    product_no integer PRIMARY KEY,
    name text,
    price numeric
);
```

Primary keys can also constrain more than one column; the syntax is similar to unique constraints:

```
CREATE TABLE example (
    a integer,
    b integer,
    c integer,
    PRIMARY KEY (a, c)
);
```

A primary key indicates that a column or group of columns can be used as a unique identifier for rows in the table. (This is a direct consequence of the definition of a primary key. Note that a unique constraint does not, in fact, provide a unique identifier because it does not exclude null values.) This is useful both for documentation purposes and for client applications. For example, a GUI application that allows modifying row values probably needs to know the primary key of a table to be able to identify rows uniquely.

A table can have at most one primary key (while it can have many unique and not-null constraints). Relational database theory dictates that every table must have a primary key. This rule is not enforced by PostgreSQL, but it is usually best to follow it.

2.4.5. Foreign Keys

A foreign key constraint specifies that the values in a column (or a group of columns) must match the values appearing in some row of another table. We say this maintains the *referential integrity* between two related tables.

Say you have the product table that we have used several times already:

```
CREATE TABLE products (
    product_no integer PRIMARY KEY,
    name text,
    price numeric
);
```

Let's also assume you have a table storing orders of those products. We want to ensure that the orders table only contains orders of products that actually exist. So we define a foreign key constraint in the orders table that references the products table:

```
CREATE TABLE orders (
    order_id integer PRIMARY KEY,
    product_no integer REFERENCES products (product_no),
    quantity integer
);
```

Now it is impossible to create orders with `product_no` entries that do not appear in the products table.

We say that in this situation the orders table is the *referencing* table and the products table is the *referenced* table. Similarly, there are referencing and referenced columns.

You can also shorten the above command to

```
CREATE TABLE orders (
    order_id integer PRIMARY KEY,
    product_no integer REFERENCES products,
    quantity integer
);
```

because in absence of a column list the primary key of the referenced table is used as referenced column.

A foreign key can also constrain and reference a group of columns. As usual, it then needs to be written in table constraint form. Here is a contrived syntax example:

```
CREATE TABLE t1 (
  a integer PRIMARY KEY,
  b integer,
  c integer,
  FOREIGN KEY (b, c) REFERENCES other_table (c1, c2)
);
```

Of course, the number and type of the constrained columns needs to match the number and type of the referenced columns.

A table can contain more than one foreign key constraint. This is used to implement many-to-many relationships between tables. Say you have tables about products and orders, but now you want to allow one order to contain possibly many products (which the structure above did not allow). You could use this table structure:

```
CREATE TABLE products (
    product_no integer PRIMARY KEY,
    name text,
    price numeric
);

CREATE TABLE orders (
    order_id integer PRIMARY KEY,
    shipping_address text,
    ...
);

CREATE TABLE order_items (
    product_no integer REFERENCES products,
    order_id integer REFERENCES orders,
    quantity integer,
    PRIMARY KEY (product_no, order_id)
);
```

Note also that the primary key overlaps with the foreign keys in the last table.

We know that the foreign keys disallow creation of orders that don't relate to any products. But what if a product is removed after an order is created that references it? SQL allows you to specify that as well. Intuitively, we have a few options:

- Disallow deleting a referenced product
- Delete the orders as well
- Something else?

To illustrate this, let's implement the following policy on the many-to-many relationship example above: When someone wants to remove a product that is still referenced by an order (via `order_items`), we disallow it. If someone removes an order, the order items are removed as well.

```
CREATE TABLE products (
    product_no integer PRIMARY KEY,
    name text,
    price numeric
);

CREATE TABLE orders (
    order_id integer PRIMARY KEY,
    shipping_address text,
    ...
);
```

```
CREATE TABLE order_items (
    product_no integer REFERENCES products ON DELETE RESTRICT,
    order_id integer REFERENCES orders ON DELETE CASCADE,
    quantity integer,
    PRIMARY KEY (product_no, order_id)
);
```

Restricting and cascading deletes are the two most common options. `RESTRICT` can also be written as `NO ACTION` and it's also the default if you don't specify anything. There are two other options for what should happen with the foreign key columns when a primary key is deleted: `SET NULL` and `SET DEFAULT`. Note that these do not excuse you from observing any constraints. For example, if an action specifies `SET DEFAULT` but the default value would not satisfy the foreign key, the deletion of the primary key will fail.

Analogous to `ON DELETE` there is also `ON UPDATE` which is invoked when a primary key is changed (updated). The possible actions are the same.

More information about updating and deleting data is in Chapter 3, *Data Manipulation*.

Finally, we should mention that a foreign key must reference columns that are either a primary key or form a unique constraint. If the foreign key references a unique constraint, there are some additional possibilities regarding how null values are matched. These are explained in the `CREATE TABLE` entry in the PostgreSQL 7.3.21 Reference Manual.

2.5. Inheritance

Let's create two tables. The capitals table contains state capitals which are also cities. Naturally, the capitals table should inherit from cities.

```
CREATE TABLE cities (
    name            text,
    population      float,
    altitude        int     -- (in ft)
);

CREATE TABLE capitals (
    state           char(2)
) INHERITS (cities);
```

In this case, a row of capitals *inherits* all attributes (name, population, and altitude) from its parent, cities. The type of the attribute name is `text`, a native PostgreSQL type for variable length ASCII strings. The type of the attribute population is `float`, a native PostgreSQL type for double precision floating-point numbers. State capitals have an extra attribute, state, that shows their state. In PostgreSQL, a table can inherit from zero or more other tables, and a query can reference either all rows of a table or all rows of a table plus all of its descendants.

Note

The inheritance hierarchy is actually a directed acyclic graph.

For example, the following query finds the names of all cities, including state capitals, that are located at an altitude over 500ft:

```
SELECT name, altitude
    FROM cities
    WHERE altitude > 500;
```

which returns:

```
   name    | altitude
-----------+----------
 Las Vegas |     2174
 Mariposa  |     1953
 Madison   |      845
```

On the other hand, the following query finds all the cities that are not state capitals and are situated at an altitude over 500ft:

```
SELECT name, altitude
    FROM ONLY cities
    WHERE altitude > 500;

   name    | altitude
-----------+----------
 Las Vegas |     2174
 Mariposa  |     1953
```

Here the "ONLY" before cities indicates that the query should be run over only cities and not tables below cities in the inheritance hierarchy. Many of the commands that we have already discussed -- `SELECT`, `UPDATE` and `DELETE` -- support this "ONLY" notation.

In some cases you may wish to know which table a particular tuple originated from. There is a system column called `TABLEOID` in each table which can tell you the originating table:

```
SELECT c.tableoid, c.name, c.altitude
FROM cities c
WHERE c.altitude > 500;
```

which returns:

```
 tableoid |   name    | altitude
----------+-----------+----------
   139793 | Las Vegas |     2174
   139793 | Mariposa  |     1953
   139798 | Madison   |      845
```

(If you try to reproduce this example, you will probably get different numeric OIDs.) By doing a join with pg_class you can see the actual table names:

```
SELECT p.relname, c.name, c.altitude
FROM cities c, pg_class p
WHERE c.altitude > 500 and c.tableoid = p.oid;
```

which returns:

```
 relname  |   name    | altitude
----------+-----------+----------
 cities   | Las Vegas |     2174
 cities   | Mariposa  |     1953
 capitals | Madison   |      845
```

Deprecated

In previous versions of PostgreSQL, the default was not to get access to child tables. This was found to be error prone and is also in violation of the SQL standard. Under the old syntax, to get the sub-tables you append `*` to the table name. For example

```
SELECT * from cities*;
```

You can still explicitly specify scanning child tables by appending `*`, as well as explicitly specify not scanning child tables by writing "ONLY". But beginning in version 7.1, the default behavior for an undecorated table name is to scan its child tables too, whereas before the default was not to do so. To get the old default behavior, set the configuration option `SQL_Inheritance` to off, e.g.,

```
SET SQL_Inheritance TO OFF;
```

or add a line in your `postgresql.conf` file.

A limitation of the inheritance feature is that indexes (including unique constraints) and foreign key constraints only apply to single tables, not to their inheritance children. Thus, in the above example, specifying that another table's column `REFERENCES cities(name)` would allow the other table to contain city names but not capital names. This deficiency will probably be fixed in some future release.

2.6. Modifying Tables

When you create a table and you realize that you made a mistake, or the requirements of the application changed, then you can drop the table and create it again. But this is not a convenient option if the table is already filled with data, or if the table is referenced by other database objects (for instance a foreign key constraint). Therefore PostgreSQL provides a family of commands to make modifications on existing tables.

You can

- Add columns,
- Remove columns,
- Add constraints,
- Remove constraints,
- Change default values,
- Rename columns,
- Rename tables.

All these actions are performed using the `ALTER TABLE` command.

2.6.1. Adding a Column

To add a column, use this command:

```
ALTER TABLE products ADD COLUMN description text;
```

The new column will initially be filled with null values in the existing rows of the table.

You can also define a constraint on the column at the same time, using the usual syntax:

```
ALTER TABLE products ADD COLUMN description text CHECK (description
 <> '');
```

A new column cannot have a not-null constraint since the column initially has to contain null values. But you can add a not-null constraint later. Also, you cannot define a default value on a new column. According to the SQL standard, this would have to fill the new columns in the existing rows with the default value, which is not implemented yet. But you can adjust the column default later on.

2.6.2. Removing a Column

To remove a column, use this command:

```
ALTER TABLE products DROP COLUMN description;
```

2.6.3. Adding a Constraint

To add a constraint, the table constraint syntax is used. For example:

```
ALTER TABLE products ADD CHECK (name <> '');
ALTER TABLE products ADD CONSTRAINT some_name UNIQUE (product_no);
ALTER TABLE products ADD FOREIGN KEY (product_group_id) REFERENCES
 product_groups;
```

To add a not-null constraint, which cannot be written as a table constraint, use this syntax:

```
ALTER TABLE products ALTER COLUMN product_no SET NOT NULL;
```

The constraint will be checked immediately, so the table data must satisfy the constraint before it can be added.

2.6.4. Removing a Constraint

To remove a constraint you need to know its name. If you gave it a name then that's easy. Otherwise the system assigned a generated name, which you need to find out. The psql command `\d` *`tablename`* can be helpful here; other interfaces might also provide a way to inspect table details. Then the command is:

```
ALTER TABLE products DROP CONSTRAINT some_name;
```

This works the same for all constraint types except not-null constraints. To drop a not null constraint use

```
ALTER TABLE products ALTER COLUMN product_no DROP NOT NULL;
```

(Recall that not-null constraints do not have names.)

2.6.5. Changing the Default

To set a new default for a column, use a command like this:

```
ALTER TABLE products ALTER COLUMN price SET DEFAULT 7.77;
```

To remove any default value, use

```
ALTER TABLE products ALTER COLUMN price DROP DEFAULT;
```

This is equivalent to setting the default to null, at least in PostgreSQL. As a consequence, it is not an error to drop a default where one hadn't been defined, because the default is implicitly the null value.

2.6.6. Renaming a Column

To rename a column:

```
ALTER TABLE products RENAME COLUMN product_no TO product_number;
```

2.6.7. Renaming a Table

To rename a table:

```
ALTER TABLE products RENAME TO items;
```

2.7. Privileges

When you create a database object, you become its owner. By default, only the owner of an object can do anything with the object. In order to allow other users to use it, *privileges* must be granted. (There are also users that have the superuser privilege. Those users can always access any object.)

Note

To change the owner of a table, index, sequence, or view, use the `ALTER TABLE` command.

There are several different privileges: `SELECT`, `INSERT`, `UPDATE`, `DELETE`, `RULE`, `REFERENCES`, `TRIGGER`, `CREATE`, `TEMPORARY`, `EXECUTE`, `USAGE`, and `ALL PRIVILEGES`. For complete information on the different types of privileges supported by PostgreSQL, refer to the `GRANT` reference page. The following sections and chapters will also show you how those privileges are used.

The right to modify or destroy an object is always the privilege of the owner only.

To assign privileges, the `GRANT` command is used. So, if `joe` is an existing user, and `accounts` is an existing table, the privilege to update the table can be granted with

```
GRANT UPDATE ON accounts TO joe;
```

The user executing this command must be the owner of the table. To grant a privilege to a group, use

```
GRANT SELECT ON accounts TO GROUP staff;
```

The special "user" name `PUBLIC` can be used to grant a privilege to every user on the system. Writing `ALL` in place of a specific privilege specifies that all privileges will be granted.

To revoke a privilege, use the fittingly named `REVOKE` command:

```
REVOKE ALL ON accounts FROM PUBLIC;
```

The special privileges of the table owner (i.e., the right to do `DROP`, `GRANT`, `REVOKE`, etc) are always implicit in being the owner, and cannot be granted or revoked. But the table owner can choose to revoke his own ordinary privileges, for example to make a table read-only for himself as well as others.

2.8. Schemas

A PostgreSQL database cluster (installation) contains one or more named databases. Users and groups of users are shared across the entire cluster, but no other data is shared across databases. Any given client connection to the server can access only the data in a single database, the one specified in the connection request.

Note

Users of a cluster do not necessarily have the privilege to access every database in the cluster. Sharing of user names means that there cannot be different users named, say, `joe` in two databases in the same cluster; but the system can be configured to allow `joe` access to only some of the databases.

A database contains one or more named *schemas*, which in turn contain tables. Schemas also contain other kinds of named objects, including data types, functions, and operators. The same object name can be used in different schemas without conflict; for example, both `schema1` and `myschema` may contain tables named `mytable`. Unlike databases, schemas are not rigidly separated: a user may access objects in any of the schemas in the database he is connected to, if he has privileges to do so.

There are several reasons why one might want to use schemas:

- To allow many users to use one database without interfering with each other.

- To organize database objects into logical groups to make them more manageable.
- Third-party applications can be put into separate schemas so they cannot collide with the names of other objects.

Schemas are analogous to directories at the operating system level, except that schemas cannot be nested.

2.8.1. Creating a Schema

To create a separate schema, use the command `CREATE SCHEMA`. Give the schema a name of your choice. For example:

```
CREATE SCHEMA myschema;
```

To create or access objects in a schema, write a *qualified name* consisting of the schema name and table name separated by a dot:

`schema.table`

Actually, the even more general syntax

`database.schema.table`

can be used too, but at present this is just for pro-forma compliance with the SQL standard; if you write a database name it must be the same as the database you are connected to.

So to create a table in the new schema, use

```
CREATE TABLE myschema.mytable (
 ...
);
```

This works anywhere a table name is expected, including the table modification commands and the data access commands discussed in the following chapters.

To drop a schema if it's empty (all objects in it have been dropped), use

```
DROP SCHEMA myschema;
```

To drop a schema including all contained objects, use

```
DROP SCHEMA myschema CASCADE;
```

See Section 2.10, “Dependency Tracking” for a description of the general mechanism behind this.

Often you will want to create a schema owned by someone else (since this is one of the ways to restrict the activities of your users to well-defined namespaces). The syntax for that is:

`CREATE SCHEMA` *`schemaname`* `AUTHORIZATION` *`username`*`;`

You can even omit the schema name, in which case the schema name will be the same as the user name. See Section 2.8.6, “Usage Patterns” for how this can be useful.

Schema names beginning with `pg_` are reserved for system purposes and may not be created by users.

2.8.2. The Public Schema

In the previous sections we created tables without specifying any schema names. By default, such tables (and other objects) are automatically put into a schema named “public”. Every new database contains such a schema. Thus, the following are equivalent:

```
CREATE TABLE products ( ... );
```

and

```
CREATE TABLE public.products ( ... );
```

2.8.3. The Schema Search Path

Qualified names are tedious to write, and it's often best not to wire a particular schema name into applications anyway. Therefore tables are often referred to by *unqualified names*, which consist of just the table name. The system determines which table is meant by following a *search path*, which is a list of schemas to look in. The first matching table in the search path is taken to be the one wanted. If there is no match in the search path, an error is reported, even if matching table names exist in other schemas in the database.

The first schema named in the search path is called the current schema. Aside from being the first schema searched, it is also the schema in which new tables will be created if the `CREATE TABLE` command does not specify a schema name.

To show the current search path, use the following command:

```
SHOW search_path;
```

In the default setup this returns:

```
 search_path
--------------
 $user,public
```

The first element specifies that a schema with the same name as the current user is to be searched. Since no such schema exists yet, this entry is ignored. The second element refers to the public schema that we have seen already.

The first schema in the search path that exists is the default location for creating new objects. That is the reason that by default objects are created in the public schema. When objects are referenced in any other context without schema qualification (table modification, data modification, or query commands) the search path is traversed until a matching object is found. Therefore, in the default configuration, any unqualified access again can only refer to the public schema.

To put our new schema in the path, we use

```
SET search_path TO myschema,public;
```

(We omit the `$user` here because we have no immediate need for it.) And then we can access the table without schema qualification:

```
DROP TABLE mytable;
```

Also, since `myschema` is the first element in the path, new objects would by default be created in it.

We could also have written

```
SET search_path TO myschema;
```

Then we no longer have access to the public schema without explicit qualification. There is nothing special about the public schema except that it exists by default. It can be dropped, too.

See also Section 6.13, “Miscellaneous Functions” for other ways to access the schema search path.

The search path works in the same way for data type names, function names, and operator names as it does for table names. Data type and function names can be qualified in exactly the same way as table

names. If you need to write a qualified operator name in an expression, there is a special provision: you must write

```
OPERATOR(schema.operator)
```

This is needed to avoid syntactic ambiguity. An example is

```
SELECT 3 OPERATOR(pg_catalog.+) 4;
```

In practice one usually relies on the search path for operators, so as not to have to write anything so ugly as that.

2.8.4. Schemas and Privileges

By default, users cannot see the objects in schemas they do not own. To allow that, the owner of the schema needs to grant the `USAGE` privilege on the schema. To allow users to make use of the objects in the schema, additional privileges may need to be granted, as appropriate for the object.

A user can also be allowed to create objects in someone else's schema. To allow that, the `CREATE` privilege on the schema needs to be granted. Note that by default, everyone has the `CREATE` privilege on the schema `public`. This allows all users that manage to connect to a given database to create objects there. If you do not want to allow that, you can revoke that privilege:

```
REVOKE CREATE ON public FROM PUBLIC;
```

(The first “public” is the schema, the second “public” means “every user”. In the first sense it is an identifier, in the second sense it is a reserved word, hence the different capitalization; recall the guidelines from Section 1.1.1, “Identifiers and Key Words”.)

2.8.5. The System Catalog Schema

In addition to `public` and user-created schemas, each database contains a `pg_catalog` schema, which contains the system tables and all the built-in data types, functions, and operators. `pg_catalog` is always effectively part of the search path. If it is not named explicitly in the path then it is implicitly searched *before* searching the path's schemas. This ensures that built-in names will always be findable. However, you may explicitly place `pg_catalog` at the end of your search path if you prefer to have user-defined names override built-in names.

In PostgreSQL versions before 7.3, table names beginning with `pg_` were reserved. This is no longer true: you may create such a table name if you wish, in any non-system schema. However, it's best to continue to avoid such names, to ensure that you won't suffer a conflict if some future version defines a system catalog named the same as your table. (With the default search path, an unqualified reference to your table name would be resolved as the system catalog instead.) System catalogs will continue to follow the convention of having names beginning with `pg_`, so that they will not conflict with unqualified user-table names so long as users avoid the `pg_` prefix.

2.8.6. Usage Patterns

Schemas can be used to organize your data in many ways. There are a few usage patterns that are recommended and are easily supported by the default configuration:

- If you do not create any schemas then all users access the public schema implicitly. This simulates the situation where schemas are not available at all. This setup is mainly recommended when there is only a single user or a few cooperating users in a database. This setup also allows smooth transition from the non-schema-aware world.
- You can create a schema for each user with the same name as that user. Recall that the default search path starts with `$user`, which resolves to the user name. Therefore, if each user has a separate schema, they access their own schemas by default.

If you use this setup then you might also want to revoke access to the public schema (or drop it altogether), so users are truly constrained to their own schemas.

- To install shared applications (tables to be used by everyone, additional functions provided by third parties, etc.), put them into separate schemas. Remember to grant appropriate privileges to allow the other users to access them. Users can then refer to these additional objects by qualifying the names with a schema name, or they can put the additional schemas into their path, as they choose.

2.8.7. Portability

In the SQL standard, the notion of objects in the same schema being owned by different users does not exist. Moreover, some implementations don't allow you to create schemas that have a different name than their owner. In fact, the concepts of schema and user are nearly equivalent in a database system that implements only the basic schema support specified in the standard. Therefore, many users consider qualified names to really consist of *`username`*`.`*`tablename`*. This is how PostgreSQL will effectively behave if you create a per-user schema for every user.

Also, there is no concept of a `public` schema in the SQL standard. For maximum conformance to the standard, you should not use (perhaps even remove) the `public` schema.

Of course, some SQL database systems might not implement schemas at all, or provide namespace support by allowing (possibly limited) cross-database access. If you need to work with those systems, then maximum portability would be achieved by not using schemas at all.

2.9. Other Database Objects

Tables are the central objects in a relational database structure, because they hold your data. But they are not the only objects that exist in a database. Many other kinds of objects can be created to make the use and management of the data more efficient or convenient. They are not discussed in this chapter, but we give you a list here so that you are aware of what is possible.

- Views
- Functions, operators, data types, domains
- Triggers and rewrite rules

2.10. Dependency Tracking

When you create complex database structures involving many tables with foreign key constraints, views, triggers, functions, etc. you will implicitly create a net of dependencies between the objects. For instance, a table with a foreign key constraint depends on the table it references.

To ensure the integrity of the entire database structure, PostgreSQL makes sure that you cannot drop objects that other objects still depend on. For example, attempting to drop the products table we had considered in Section 2.4.5, “Foreign Keys”, with the orders table depending on it, would result in an error message such as this:

```
DROP TABLE products;
NOTICE:  constraint $1 on table orders depends on table products
ERROR:  Cannot drop table products because other objects depend on
 it
        Use DROP ... CASCADE to drop the dependent objects too
```

The error message contains a useful hint: If you don't want to bother deleting all the dependent objects individually, you can run

```
DROP TABLE products CASCADE;
```

and all the dependent objects will be removed. In this case, it doesn't remove the orders table, it only removes the foreign key constraint. (If you want to check what `DROP ... CASCADE` will do, run `DROP` without `CASCADE` and read the `NOTICE` messages.)

All drop commands in PostgreSQL support specifying `CASCADE`. Of course, the nature of the possible dependencies varies with the type of the object. You can also write `RESTRICT` instead of `CASCADE` to get the default behavior which is to restrict drops of objects that other objects depend on.

Note

According to the SQL standard, specifying either `RESTRICT` or `CASCADE` is required. No database system actually implements it that way, but whether the default behavior is `RESTRICT` or `CASCADE` varies across systems.

Note

Foreign key constraint dependencies and serial column dependencies from PostgreSQL versions prior to 7.3 are *not* maintained or created during the upgrade process. All other dependency types will be properly created during an upgrade.

Chapter 3. Data Manipulation

The previous chapter discussed how to create tables and other structures to hold your data. Now it is time to fill the tables with data. This chapter covers how to insert, update, and delete table data. We also introduce ways to effect automatic data changes when certain events occur: triggers and rewrite rules. The chapter after this will finally explain how to extract your long-lost data back out of the database.

3.1. Inserting Data

When a table is created, it contains no data. The first thing to do before a database can be of much use is to insert data. Data is conceptually inserted one row at a time. Of course you can also insert more than one row, but there is no way to insert less than one row at a time. Even if you know only some column values, a complete row must be created.

To create a new row, use the `INSERT` command. The command requires the table name and a value for each of the columns of the table. For example, consider the products table from Chapter 2, *Data Definition*:

```
CREATE TABLE products (
    product_no integer,
    name text,
    price numeric
);
```

An example command to insert a row would be:

```
INSERT INTO products VALUES (1, 'Cheese', 9.99);
```

The data values are listed in the order in which the columns appear in the table, separated by commas. Usually, the data values will be literals (constants), but scalar expressions are also allowed.

The above syntax has the drawback that you need to know the order of the columns in the table. To avoid that you can also list the columns explicitly. For example, both of the following commands have the same effect as the one above:

```
INSERT INTO products (product_no, name, price) VALUES (1, 'Cheese',
 9.99);
INSERT INTO products (name, price, product_no) VALUES ('Cheese',
 9.99, 1);
```

Many users consider it good practice to always list the column names.

If you don't have values for all the columns, you can omit some of them. In that case, the columns will be filled with their default values. For example,

```
INSERT INTO products (product_no, name) VALUES (1, 'Cheese');
INSERT INTO products VALUES (1, 'Cheese');
```

The second form is a PostgreSQL extension. It fills the columns from the left with as many values as are given, and the rest will be defaulted.

For clarity, you can also request default values explicitly, for individual columns or for the entire row:

```
INSERT INTO products (product_no, name, price) VALUES (1, 'Cheese',
 DEFAULT);
INSERT INTO products DEFAULT VALUES;
```

Tip

To do “bulk loads”, that is, inserting a lot of data, take a look at the `COPY` command (see PostgreSQL 7.3.21 Reference Manual). It is not as flexible as the `INSERT` command, but more efficient.

3.2. Updating Data

The modification of data that is already in the database is referred to as updating. You can update individual rows, all the rows in a table, or a subset of all rows. Each column can be updated separately; the other columns are not affected.

To perform an update, you need three pieces of information:

1. The name of the table and column to update,
2. The new value of the column,
3. Which row(s) to update.

Recall from Chapter 2, *Data Definition* that SQL does not, in general, provide a unique identifier for rows. Therefore it is not necessarily possible to directly specify which row to update. Instead, you specify which conditions a row must meet in order to be updated. Only if you have a primary key in the table (no matter whether you declared it or not) can you reliably address individual rows, by choosing a condition that matches the primary key. Graphical database access tools rely on this fact to allow you to update rows individually.

For example, this command updates all products that have a price of 5 to have a price of 10:

```
UPDATE products SET price = 10 WHERE price = 5;
```

This may cause zero, one, or many rows to be updated. It is not an error to attempt an update that does not match any rows.

Let's look at that command in detail: First is the key word `UPDATE` followed by the table name. As usual, the table name may be schema-qualified, otherwise it is looked up in the path. Next is the key word `SET` followed by the column name, an equals sign and the new column value. The new column value can be any scalar expression, not just a constant. For example, if you want to raise the price of all products by 10% you could use:

```
UPDATE products SET price = price * 1.10;
```

As you see, the expression for the new value can also refer to the old value. We also left out the `WHERE` clause. If it is omitted, it means that all rows in the table are updated. If it is present, only those rows that match the condition after the `WHERE` are updated. Note that the equals sign in the `SET` clause is an assignment while the one in the `WHERE` clause is a comparison, but this does not create any ambiguity. Of course, the condition does not have to be an equality test. Many other operators are available (see Chapter 6, *Functions and Operators*). But the expression needs to evaluate to a Boolean result.

You can also update more than one column in an `UPDATE` command by listing more than one assignment in the `SET` clause. For example:

```
UPDATE mytable SET a = 5, b = 3, c = 1 WHERE a > 0;
```

3.3. Deleting Data

So far we have explained how to add data to tables and how to change data. What remains is to discuss how to remove data that is no longer needed. Just as adding data is only possible in whole rows, you can only remove entire rows from a table. In the previous section we discussed that SQL does not provide a way to directly address individual rows. Therefore, removing rows can only be done by

specifying conditions that the rows to be removed have to match. If you have a primary key in the table then you can specify the exact row. But you can also remove groups of rows matching a condition, or you can remove all rows in the table at once.

You use the `DELETE` command to remove rows; the syntax is very similar to the `UPDATE` command. For instance, to remove all rows from the products table that have a price of 10, use

```
DELETE FROM products WHERE price = 10;
```

If you simply write

```
DELETE FROM products;
```

then all rows in the table will be deleted! Caveat programmer.

Chapter 4. Queries

The previous chapters explained how to create tables, how to fill them with data, and how to manipulate that data. Now we finally discuss how to retrieve the data out of the database.

4.1. Overview

The process of retrieving or the command to retrieve data from a database is called a *query*. In SQL the `SELECT` command is used to specify queries. The general syntax of the `SELECT` command is

```
SELECT select_list FROM table_expression [sort_specification]
```

The following sections describe the details of the select list, the table expression, and the sort specification.

The simplest kind of query has the form

```
SELECT * FROM table1;
```

Assuming that there is a table called `table1`, this command would retrieve all rows and all columns from `table1`. (The method of retrieval depends on the client application. For example, the psql program will display an ASCII-art table on the screen, while client libraries will offer functions to retrieve individual rows and columns.) The select list specification `*` means all columns that the table expression happens to provide. A select list can also select a subset of the available columns or make calculations using the columns. For example, if `table1` has columns named `a`, `b`, and `c` (and perhaps others) you can make the following query:

```
SELECT a, b + c FROM table1;
```

(assuming that `b` and `c` are of a numerical data type). See Section 4.3, “Select Lists” for more details.

`FROM table1` is a particularly simple kind of table expression: it reads just one table. In general, table expressions can be complex constructs of base tables, joins, and subqueries. But you can also omit the table expression entirely and use the `SELECT` command as a calculator:

```
SELECT 3 * 4;
```

This is more useful if the expressions in the select list return varying results. For example, you could call a function this way:

```
SELECT random();
```

4.2. Table Expressions

A *table expression* computes a table. The table expression contains a `FROM` clause that is optionally followed by `WHERE`, `GROUP BY`, and `HAVING` clauses. Trivial table expressions simply refer to a table on disk, a so-called base table, but more complex expressions can be used to modify or combine base tables in various ways.

The optional `WHERE`, `GROUP BY`, and `HAVING` clauses in the table expression specify a pipeline of successive transformations performed on the table derived in the `FROM` clause. All these transformations produce a virtual table that provides the rows that are passed to the select list to compute the output rows of the query.

4.2.1. The FROM Clause

The `FROM` clause derives a table from one or more other tables given in a comma-separated table reference list.

```
FROM table_reference [, table_reference [, ...]]
```

A table reference may be a table name (possibly schema-qualified), or a derived table such as a subquery, a table join, or complex combinations of these. If more than one table reference is listed in the FROM clause they are cross-joined (see below) to form the intermediate virtual table that may then be subject to transformations by the WHERE, GROUP BY, and HAVING clauses and is finally the result of the overall table expression.

When a table reference names a table that is the supertable of a table inheritance hierarchy, the table reference produces rows of not only that table but all of its subtable successors, unless the keyword ONLY precedes the table name. However, the reference produces only the columns that appear in the named table --- any columns added in subtables are ignored.

4.2.1.1. Joined Tables

A joined table is a table derived from two other (real or derived) tables according to the rules of the particular join type. Inner, outer, and cross-joins are available.

Join Types

Cross join

```
T1 CROSS JOIN T2
```

For each combination of rows from *T1* and *T2*, the derived table will contain a row consisting of all columns in *T1* followed by all columns in *T2*. If the tables have N and M rows respectively, the joined table will have N * M rows. A cross join is equivalent to an INNER JOIN ON TRUE.

Tip

FROM *T1* CROSS JOIN *T2* is equivalent to FROM *T1*, *T2*.

Qualified joins

```
T1 { [INNER] | { LEFT | RIGHT | FULL } [OUTER] } JOIN T2
 ON boolean_expression
T1 { [INNER] | { LEFT | RIGHT | FULL } [OUTER] } JOIN T2 USING
 ( join column list )
T1 NATURAL { [INNER] | { LEFT | RIGHT | FULL } [OUTER] } JOIN T2
```

The words INNER and OUTER are optional in all forms. INNER is the default; LEFT, RIGHT, and FULL imply an outer join.

The *join condition* is specified in the ON or USING clause, or implicitly by the word NATURAL. The join condition determines which rows from the two source tables are considered to “match”, as explained in detail below.

The ON clause is the most general kind of join condition: it takes a Boolean value expression of the same kind as is used in a WHERE clause. A pair of rows from *T1* and *T2* match if the ON expression evaluates to true for them.

USING is a shorthand notation: it takes a comma-separated list of column names, which the joined tables must have in common, and forms a join condition specifying equality of each of these pairs of columns. Furthermore, the output of a JOIN USING has one column for each of the equated pairs of input columns, followed by all of the other columns from each table. Thus, USING (a, b, c) is equivalent to ON (t1.a = t2.a AND t1.b = t2.b AND t1.c = t2.c) with the exception that if ON is used there will be two columns a, b, and c in the result, whereas with USING there will be only one of each.

Finally, NATURAL is a shorthand form of USING: it forms a USING list consisting of exactly those column names that appear in both input tables. As with USING, these columns appear only once in the output table.

The possible types of qualified join are:

`INNER JOIN`

For each row R1 of T1, the joined table has a row for each row in T2 that satisfies the join condition with R1.

`LEFT OUTER JOIN`

First, an inner join is performed. Then, for each row in T1 that does not satisfy the join condition with any row in T2, a joined row is added with null values in columns of T2. Thus, the joined table unconditionally has at least one row for each row in T1.

`RIGHT OUTER JOIN`

First, an inner join is performed. Then, for each row in T2 that does not satisfy the join condition with any row in T1, a joined row is added with null values in columns of T1. This is the converse of a left join: the result table will unconditionally have a row for each row in T2.

`FULL OUTER JOIN`

First, an inner join is performed. Then, for each row in T1 that does not satisfy the join condition with any row in T2, a joined row is added with null values in columns of T2. Also, for each row of T2 that does not satisfy the join condition with any row in T1, a joined row with null values in the columns of T1 is added.

Joins of all types can be chained together or nested: either or both of *`T1`* and *`T2`* may be joined tables. Parentheses may be used around `JOIN` clauses to control the join order. In the absence of parentheses, `JOIN` clauses nest left-to-right.

To put this together, assume we have tables `t1`

```
 num | name
-----+------
   1 | a
   2 | b
   3 | c
```

and `t2`

```
 num | value
-----+-------
   1 | xxx
   3 | yyy
   5 | zzz
```

then we get the following results for the various joins:

```
=> SELECT * FROM t1 CROSS JOIN t2;
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   1 | a    |   3 | yyy
   1 | a    |   5 | zzz
   2 | b    |   1 | xxx
   2 | b    |   3 | yyy
   2 | b    |   5 | zzz
   3 | c    |   1 | xxx
   3 | c    |   3 | yyy
   3 | c    |   5 | zzz
```

```
(9 rows)

=> SELECT * FROM t1 INNER JOIN t2 ON t1.num = t2.num;
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   3 | c    |   3 | yyy
(2 rows)

=> SELECT * FROM t1 INNER JOIN t2 USING (num);
 num | name | value
-----+------+-------
   1 | a    | xxx
   3 | c    | yyy
(2 rows)

=> SELECT * FROM t1 NATURAL INNER JOIN t2;
 num | name | value
-----+------+-------
   1 | a    | xxx
   3 | c    | yyy
(2 rows)

=> SELECT * FROM t1 LEFT JOIN t2 ON t1.num = t2.num;
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   2 | b    |     |
   3 | c    |   3 | yyy
(3 rows)

=> SELECT * FROM t1 LEFT JOIN t2 USING (num);
 num | name | value
-----+------+-------
   1 | a    | xxx
   2 | b    |
   3 | c    | yyy
(3 rows)

=> SELECT * FROM t1 RIGHT JOIN t2 ON t1.num = t2.num;
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   3 | c    |   3 | yyy
     |      |   5 | zzz
(3 rows)

=> SELECT * FROM t1 FULL JOIN t2 ON t1.num = t2.num;
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   2 | b    |     |
   3 | c    |   3 | yyy
     |      |   5 | zzz
(4 rows)
```

The join condition specified with `ON` can also contain conditions that do not relate directly to the join. This can prove useful for some queries but needs to be thought out carefully. For example:

```
=> SELECT * FROM t1 LEFT JOIN t2 ON t1.num = t2.num AND t2.value =
 'xxx';
 num | name | num | value
-----+------+-----+-------
   1 | a    |   1 | xxx
   2 | b    |     |
   3 | c    |     |
(3 rows)
```

4.2.1.2. Table and Column Aliases

A temporary name can be given to tables and complex table references to be used for references to the derived table in further processing. This is called a *table alias*.

To create a table alias, write

```
FROM table_reference AS alias
```

or

```
FROM table_reference alias
```

The `AS` key word is noise. *`alias`* can be any identifier.

A typical application of table aliases is to assign short identifiers to long table names to keep the join clauses readable. For example:

```
SELECT * FROM some_very_long_table_name s JOIN
 another_fairly_long_name a ON s.id = a.num;
```

The alias becomes the new name of the table reference for the current query -- it is no longer possible to refer to the table by the original name. Thus

```
SELECT * FROM my_table AS m WHERE my_table.a > 5;
```

is not valid SQL syntax. What will actually happen (this is a PostgreSQL extension to the standard) is that an implicit table reference is added to the `FROM` clause, so the query is processed as if it were written as

```
SELECT * FROM my_table AS m, my_table AS my_table WHERE my_table.a
 > 5;
```

which will result in a cross join, which is usually not what you want.

Table aliases are mainly for notational convenience, but it is necessary to use them when joining a table to itself, e.g.,

```
SELECT * FROM my_table AS a CROSS JOIN my_table AS b ...
```

Additionally, an alias is required if the table reference is a subquery (see Section 4.2.1.3, “Subqueries”).

Parentheses are used to resolve ambiguities. The following statement will assign the alias `b` to the result of the join, unlike the previous example:

```
SELECT * FROM (my_table AS a CROSS JOIN my_table) AS b ...
```

Another form of table aliasing also gives temporary names to the columns of the table:

```
FROM table_reference [AS] alias ( column1 [, column2 [, ...]] )
```

If fewer column aliases are specified than the actual table has columns, the remaining columns are not renamed. This syntax is especially useful for self-joins or subqueries.

When an alias is applied to the output of a JOIN clause, using any of these forms, the alias hides the original names within the JOIN. For example,

```
SELECT a.* FROM my_table AS a JOIN your_table AS b ON ...
```

is valid SQL, but

```
SELECT a.* FROM (my_table AS a JOIN your_table AS b ON ...) AS c
```

is not valid: the table alias a is not visible outside the alias c.

4.2.1.3. Subqueries

Subqueries specifying a derived table must be enclosed in parentheses and *must* be assigned a table alias name. (See Section 4.2.1.2, “Table and Column Aliases”.) For example:

```
FROM (SELECT * FROM table1) AS alias_name
```

This example is equivalent to FROM table1 AS alias_name. More interesting cases, which can't be reduced to a plain join, arise when the subquery involves grouping or aggregation.

4.2.2. The WHERE Clause

The syntax of the WHERE clause is

```
WHERE search_condition
```

where *search_condition* is any value expression as defined in Section 1.2, “Value Expressions” that returns a value of type boolean.

After the processing of the FROM clause is done, each row of the derived virtual table is checked against the search condition. If the result of the condition is true, the row is kept in the output table, otherwise (that is, if the result is false or null) it is discarded. The search condition typically references at least some column in the table generated in the FROM clause; this is not required, but otherwise the WHERE clause will be fairly useless.

Note

Before the implementation of the JOIN syntax, it was necessary to put the join condition of an inner join in the WHERE clause. For example, these table expressions are equivalent:

```
FROM a, b WHERE a.id = b.id AND b.val > 5
```

and

```
FROM a INNER JOIN b ON (a.id = b.id) WHERE b.val > 5
```

or perhaps even

```
FROM a NATURAL JOIN b WHERE b.val > 5
```

Which one of these you use is mainly a matter of style. The JOIN syntax in the FROM clause is probably not as portable to other SQL database products. For outer joins there is no choice in any case: they must be done in the FROM clause. An ON/USING clause of an outer join is *not* equivalent to a WHERE condition, because it determines the addition of rows (for unmatched input rows) as well as the removal of rows from the final result.

Here are some examples of WHERE clauses:

```
SELECT ... FROM fdt WHERE c1 > 5

SELECT ... FROM fdt WHERE c1 IN (1, 2, 3)
```

```
SELECT ... FROM fdt WHERE c1 IN (SELECT c1 FROM t2)

SELECT ... FROM fdt WHERE c1 IN (SELECT c3 FROM t2 WHERE c2 =
 fdt.c1 + 10)

SELECT ... FROM fdt WHERE c1 BETWEEN (SELECT c3 FROM t2 WHERE c2 =
 fdt.c1 + 10) AND 100

SELECT ... FROM fdt WHERE EXISTS (SELECT c1 FROM t2 WHERE c2 >
 fdt.c1)
```

`fdt` is the table derived in the `FROM` clause. Rows that do not meet the search condition of the `WHERE` clause are eliminated from `fdt`. Notice the use of scalar subqueries as value expressions. Just like any other query, the subqueries can employ complex table expressions. Notice how `fdt` is referenced in the subqueries. Qualifying `c1` as `fdt.c1` is only necessary if `c1` is also the name of a column in the derived input table of the subquery. Qualifying the column name adds clarity even when it is not needed. This shows how the column naming scope of an outer query extends into its inner queries.

4.2.3. The GROUP BY and HAVING Clauses

After passing the `WHERE` filter, the derived input table may be subject to grouping, using the `GROUP BY` clause, and elimination of group rows using the `HAVING` clause.

```
SELECT select_list
    FROM ...
    [WHERE ...]
    GROUP BY grouping_column_reference
 [, grouping_column_reference]...
```

The `GROUP BY` clause is used to group together rows in a table that share the same values in all the columns listed. The order in which the columns are listed does not matter. The purpose is to reduce each group of rows sharing common values into one group row that is representative of all rows in the group. This is done to eliminate redundancy in the output and/or compute aggregates that apply to these groups. For instance:

```
=> SELECT * FROM test1;
 x | y
---+---
 a | 3
 c | 2
 b | 5
 a | 1
(4 rows)

=> SELECT x FROM test1 GROUP BY x;
 x
---
 a
 b
 c
(3 rows)
```

In the second query, we could not have written `SELECT * FROM test1 GROUP BY x`, because there is no single value for the column `y` that could be associated with each group. The grouped-by columns can be referenced in the select list since they have a known constant value per group.

In general, if a table is grouped, columns that are not used in the grouping cannot be referenced except in aggregate expressions. An example with aggregate expressions is:

```
=> SELECT x, sum(y) FROM test1 GROUP BY x;
 x | sum
---+-----
 a |   4
 b |   5
 c |   2
(3 rows)
```

Here `sum()` is an aggregate function that computes a single value over the entire group. More information about the available aggregate functions can be found in Section 6.14, "Aggregate Functions".

Tip

Grouping without aggregate expressions effectively calculates the set of distinct values in a column. This can also be achieved using the `DISTINCT` clause (see Section 4.3.3, "DISTINCT").

Here is another example: `sum(sales)` on a table grouped by product code gives the total sales for each product, not the total sales on all products.

```
SELECT product_id, p.name, (sum(s.units) * p.price) AS sales
    FROM products p LEFT JOIN sales s USING (product_id)
    GROUP BY product_id, p.name, p.price;
```

In this example, the columns `product_id`, `p.name`, and `p.price` must be in the `GROUP BY` clause since they are referenced in the query select list. (Depending on how exactly the products table is set up, name and price may be fully dependent on the product ID, so the additional groupings could theoretically be unnecessary, but this is not implemented yet.) The column `s.units` does not have to be in the `GROUP BY` list since it is only used in an aggregate expression (`sum()`), which represents the group of sales of a product. For each product, a summary row is returned about all sales of the product.

In strict SQL, `GROUP BY` can only group by columns of the source table but PostgreSQL extends this to also allow `GROUP BY` to group by columns in the select list. Grouping by value expressions instead of simple column names is also allowed.

If a table has been grouped using a `GROUP BY` clause, but then only certain groups are of interest, the `HAVING` clause can be used, much like a `WHERE` clause, to eliminate groups from a grouped table. The syntax is:

```
SELECT select_list FROM ... [WHERE ...] GROUP BY ...
 HAVING boolean_expression
```

Expressions in the `HAVING` clause can refer both to grouped expressions and to ungrouped expressions (which necessarily involve an aggregate function).

Example:

```
=> SELECT x, sum(y) FROM test1 GROUP BY x HAVING sum(y) > 3;
 x | sum
---+-----
 a |   4
 b |   5
(2 rows)

=> SELECT x, sum(y) FROM test1 GROUP BY x HAVING x < 'c';
 x | sum
---+-----
 a |   4
 b |   5
```

```
(2 rows)
```

Again, a more realistic example:

```
SELECT product_id, p.name, (sum(s.units) * (p.price - p.cost)) AS
 profit
    FROM products p LEFT JOIN sales s USING (product_id)
    WHERE s.date > CURRENT_DATE - INTERVAL '4 weeks'
    GROUP BY product_id, p.name, p.price, p.cost
    HAVING sum(p.price * s.units) > 5000;
```

In the example above, the `WHERE` clause is selecting rows by a column that is not grouped, while the `HAVING` clause restricts the output to groups with total gross sales over 5000. Note that the aggregate expressions do not necessarily need to be the same everywhere.

4.3. Select Lists

As shown in the previous section, the table expression in the `SELECT` command constructs an intermediate virtual table by possibly combining tables, views, eliminating rows, grouping, etc. This table is finally passed on to processing by the *select list*. The select list determines which *columns* of the intermediate table are actually output.

4.3.1. Select-List Items

The simplest kind of select list is `*` which emits all columns that the table expression produces. Otherwise, a select list is a comma-separated list of value expressions (as defined in Section 1.2, “Value Expressions”). For instance, it could be a list of column names:

```
SELECT a, b, c FROM ...
```

The columns names `a`, `b`, and `c` are either the actual names of the columns of tables referenced in the `FROM` clause, or the aliases given to them as explained in Section 4.2.1.2, “Table and Column Aliases”. The name space available in the select list is the same as in the `WHERE` clause, unless grouping is used, in which case it is the same as in the `HAVING` clause.

If more than one table has a column of the same name, the table name must also be given, as in

```
SELECT tbl1.a, tbl2.b, tbl1.c FROM ...
```

(See also Section 4.2.2, “The WHERE Clause”.)

If an arbitrary value expression is used in the select list, it conceptually adds a new virtual column to the returned table. The value expression is evaluated once for each retrieved row, with the row's values substituted for any column references. But the expressions in the select list do not have to reference any columns in the table expression of the `FROM` clause; they could be constant arithmetic expressions as well, for instance.

4.3.2. Column Labels

The entries in the select list can be assigned names for further processing. The “further processing” in this case is an optional sort specification and the client application (e.g., column headers for display). For example:

```
SELECT a AS value, b + c AS sum FROM ...
```

If no output column name is specified via AS, the system assigns a default name. For simple column references, this is the name of the referenced column. For function calls, this is the name of the function. For complex expressions, the system will generate a generic name.

Note

The naming of output columns here is different from that done in the FROM clause (see Section 4.2.1.2, “Table and Column Aliases”). This pipeline will in fact allow you to rename the same column twice, but the name chosen in the select list is the one that will be passed on.

4.3.3. DISTINCT

After the select list has been processed, the result table may optionally be subject to the elimination of duplicates. The DISTINCT key word is written directly after the SELECT to enable this:

```
SELECT DISTINCT select_list ...
```

(Instead of DISTINCT the word ALL can be used to select the default behavior of retaining all rows.)

Obviously, two rows are considered distinct if they differ in at least one column value. Null values are considered equal in this comparison.

Alternatively, an arbitrary expression can determine what rows are to be considered distinct:

```
SELECT DISTINCT ON (expression [, expression ...]) select_list ...
```

Here *expression* is an arbitrary value expression that is evaluated for all rows. A set of rows for which all the expressions are equal are considered duplicates, and only the first row of the set is kept in the output. Note that the “first row” of a set is unpredictable unless the query is sorted on enough columns to guarantee a unique ordering of the rows arriving at the DISTINCT filter. (DISTINCT ON processing occurs after ORDER BY sorting.)

The DISTINCT ON clause is not part of the SQL standard and is sometimes considered bad style because of the potentially indeterminate nature of its results. With judicious use of GROUP BY and subselects in FROM the construct can be avoided, but it is often the most convenient alternative.

4.4. Combining Queries

The results of two queries can be combined using the set operations union, intersection, and difference. The syntax is

```
query1 UNION [ALL] query2
query1 INTERSECT [ALL] query2
query1 EXCEPT [ALL] query2
```

query1 and *query2* are queries that can use any of the features discussed up to this point. Set operations can also be nested and chained, for example

```
query1 UNION query2 UNION query3
```

which really says

```
(query1 UNION query2) UNION query3
```

UNION effectively appends the result of *query2* to the result of *query1* (although there is no guarantee that this is the order in which the rows are actually returned). Furthermore, it eliminates all duplicate rows, in the sense of DISTINCT, unless UNION ALL is used.

INTERSECT returns all rows that are both in the result of *query1* and in the result of *query2*. Duplicate rows are eliminated unless INTERSECT ALL is used.

EXCEPT returns all rows that are in the result of *query1* but not in the result of *query2*. (This is sometimes called the *difference* between two queries.) Again, duplicates are eliminated unless EXCEPT ALL is used.

In order to calculate the union, intersection, or difference of two queries, the two queries must be "union compatible", which means that they both return the same number of columns, and that the corresponding columns have compatible data types, as described in Section 7.5, "UNION and CASE Constructs".

4.5. Sorting Rows

After a query has produced an output table (after the select list has been processed) it can optionally be sorted. If sorting is not chosen, the rows will be returned in random order. The actual order in that case will depend on the scan and join plan types and the order on disk, but it must not be relied on. A particular output ordering can only be guaranteed if the sort step is explicitly chosen.

The ORDER BY clause specifies the sort order:

```
SELECT select_list
    FROM table_expression
    ORDER BY column1 [ASC | DESC] [, column2 [ASC | DESC] ...]
```

column1, etc., refer to select list columns. These can be either the output name of a column (see Section 4.3.2, "Column Labels") or the number of a column. Some examples:

```
SELECT a, b FROM table1 ORDER BY a;
SELECT a + b AS sum, c FROM table1 ORDER BY sum;
SELECT a, sum(b) FROM table1 GROUP BY a ORDER BY 1;
```

As an extension to the SQL standard, PostgreSQL also allows ordering by arbitrary expressions:

```
SELECT a, b FROM table1 ORDER BY a + b;
```

References to column names in the FROM clause that are renamed in the select list are also allowed:

```
SELECT a AS b FROM table1 ORDER BY a;
```

But these extensions do not work in queries involving UNION, INTERSECT, or EXCEPT, and are not portable to other SQL databases.

Each column specification may be followed by an optional ASC or DESC to set the sort direction to ascending or descending. ASC order is the default. Ascending order puts smaller values first, where "smaller" is defined in terms of the < operator. Similarly, descending order is determined with the > operator.

If more than one sort column is specified, the later entries are used to sort rows that are equal under the order imposed by the earlier sort columns.

4.6. LIMIT and OFFSET

LIMIT and OFFSET allow you to retrieve just a portion of the rows that are generated by the rest of the query:

```
SELECT select_list
    FROM table_expression
    [LIMIT { number | ALL }] [OFFSET number]
```

If a limit count is given, no more than that many rows will be returned (but possibly less, if the query itself yields less rows). LIMIT ALL is the same as omitting the LIMIT clause.

OFFSET says to skip that many rows before beginning to return rows to the client. OFFSET 0 is the same as omitting the OFFSET clause. If both OFFSET and LIMIT appear, then OFFSET rows are skipped before starting to count the LIMIT rows that are returned.

When using `LIMIT`, it is a good idea to use an `ORDER BY` clause that constrains the result rows into a unique order. Otherwise you will get an unpredictable subset of the query's rows---you may be asking for the tenth through twentieth rows, but tenth through twentieth in what ordering? The ordering is unknown, unless you specified `ORDER BY`.

The query optimizer takes `LIMIT` into account when generating a query plan, so you are very likely to get different plans (yielding different row orders) depending on what you give for `LIMIT` and `OFFSET`. Thus, using different `LIMIT`/`OFFSET` values to select different subsets of a query result *will give inconsistent results* unless you enforce a predictable result ordering with `ORDER BY`. This is not a bug; it is an inherent consequence of the fact that SQL does not promise to deliver the results of a query in any particular order unless `ORDER BY` is used to constrain the order.

Chapter 5. Data Types

PostgreSQL has a rich set of native data types available to users. Users may add new types to PostgreSQL using the `CREATE TYPE` command.

Table 5.1, “Data Types” shows all general-purpose data types included in the standard distribution. Most of the alternative names listed in the “Aliases” column are the names used internally by PostgreSQL for historical reasons. In addition, some internally used or deprecated types are available, but they are not listed here.

Table 5.1. Data Types

Type Name	Aliases	Description
`bigint`	`int8`	signed eight-byte integer
`bigserial`	`serial8`	autoincrementing eight-byte integer
`bit`		fixed-length bit string
`bit varying(`*n*`)`	`varbit(`*n*`)`	variable-length bit string
`boolean`	`bool`	logical Boolean (true/false)
`box`		rectangular box in 2D plane
`bytea`		binary data
`character varying(`*n*`)`	`varchar(`*n*`)`	variable-length character string
`character(`*n*`)`	`char(`*n*`)`	fixed-length character string
`cidr`		IP network address
`circle`		circle in 2D plane
`date`		calendar date (year, month, day)
`double precision`	`float8`	double precision floating-point number
`inet`		IP host address
`integer`	`int`, `int4`	signed four-byte integer
`interval(`*p*`)`		general-use time span
`line`		infinite line in 2D plane (not implemented)
`lseg`		line segment in 2D plane
`macaddr`		MAC address
`money`		currency amount
`numeric [ (`*p*`, `*s*`) ]`	`decimal [ (`*p*`, `*s*`) ]`	exact numeric with selectable precision
`path`		open and closed geometric path in 2D plane
`point`		geometric point in 2D plane
`polygon`		closed geometric path in 2D plane
`real`	`float4`	single precision floating-point number
`smallint`	`int2`	signed two-byte integer

Type Name	Aliases	Description
serial	serial4	autoincrementing four-byte integer
text		variable-length character string
time [(*p*)] [without time zone]		time of day
time [(*p*)] with time zone	timetz	time of day, including time zone
timestamp [(*p*)] without time zone	timestamp	date and time
timestamp [(*p*)] [with time zone]	timestamptz	date and time, including time zone

Compatibility

The following types (or spellings thereof) are specified by SQL: bit, bit varying, boolean, char, character varying, character, varchar, date, double precision, integer, interval, numeric, decimal, real, smallint, time, timestamp (both with or without time zone).

Each data type has an external representation determined by its input and output functions. Many of the built-in types have obvious external formats. However, several types are either unique to PostgreSQL, such as open and closed paths, or have several possibilities for formats, such as the date and time types. Most of the input and output functions corresponding to the base types (e.g., integers and floating-point numbers) do some error-checking. Some of the input and output functions are not invertible. That is, the result of an output function may lose precision when compared to the original input.

Some of the operators and functions (e.g., addition and multiplication) do not perform run-time error-checking in the interests of improving execution speed. On some systems, for example, the numeric operators for some data types may silently underflow or overflow.

5.1. Numeric Types

Numeric types consist of two-, four-, and eight-byte integers, four- and eight-byte floating-point numbers, and fixed-precision decimals. Table 5.2, “Numeric Types” lists the available types.

Table 5.2. Numeric Types

Type name	Storage size	Description	Range
smallint	2 bytes	small range fixed-precision	-32768 to +32767
integer	4 bytes	usual choice for fixed-precision	-2147483648 to +2147483647
bigint	8 bytes	large range fixed-precision	-9223372036854775808 to 9223372036854775807
decimal	variable	user-specified precision, exact	no limit
numeric	variable	user-specified precision, exact	no limit
real	4 bytes	variable-precision, inexact	6 decimal digits precision

Type name	Storage size	Description	Range
`double precision`	8 bytes	variable-precision, inexact	15 decimal digits precision
`serial`	4 bytes	autoincrementing integer	1 to 2147483647
`bigserial`	8 bytes	large autoincrementing integer	1 to 9223372036854775807

The syntax of constants for the numeric types is described in Section 1.1.2, “Constants”. The numeric types have a full set of corresponding arithmetic operators and functions. Refer to Chapter 6, *Functions and Operators* for more information. The following sections describe the types in detail.

5.1.1. The Integer Types

The types `smallint`, `integer`, `bigint` store whole numbers, that is, numbers without fractional components, of various ranges. Attempts to store values outside of the allowed range will result in an error.

The type `integer` is the usual choice, as it offers the best balance between range, storage size, and performance. The `smallint` type is generally only used if disk space is at a premium. The `bigint` type should only be used if the `integer` range is not sufficient, because the latter is definitely faster.

The `bigint` type may not function correctly on all platforms, since it relies on compiler support for eight-byte integers. On a machine without such support, `bigint` acts the same as `integer` (but still takes up eight bytes of storage). However, we are not aware of any reasonable platform where this is actually the case.

SQL only specifies the integer types `integer` (or `int`) and `smallint`. The type `bigint`, and the type names `int2`, `int4`, and `int8` are extensions, which are shared with various other SQL database systems.

Note

If you have a column of type `smallint` or `bigint` with an index, you may encounter problems getting the system to use that index. For instance, a clause of the form

```
... WHERE smallint_column = 42
```

will not use an index, because the system assigns type `integer` to the constant 42, and PostgreSQL currently cannot use an index when two different data types are involved. A workaround is to single-quote the constant, thus:

```
... WHERE smallint_column = '42'
```

This will cause the system to delay type resolution and will assign the right type to the constant.

5.1.2. Arbitrary Precision Numbers

The type `numeric` can store numbers with up to 1,000 digits of precision and perform calculations exactly. It is especially recommended for storing monetary amounts and other quantities where exactness is required. However, the `numeric` type is very slow compared to the floating-point types described in the next section.

In what follows we use these terms: The *scale* of a `numeric` is the count of decimal digits in the fractional part, to the right of the decimal point. The *precision* of a `numeric` is the total count of

significant digits in the whole number, that is, the number of digits to both sides of the decimal point. So the number 23.5141 has a precision of 6 and a scale of 4. Integers can be considered to have a scale of zero.

Both the precision and the scale of the numeric type can be configured. To declare a column of type `numeric` use the syntax

```
NUMERIC(precision, scale)
```

The precision must be positive, the scale zero or positive. Alternatively,

```
NUMERIC(precision)
```

selects a scale of 0. Specifying

```
NUMERIC
```

without any precision or scale creates a column in which numeric values of any precision and scale can be stored, up to the implementation limit on precision. A column of this kind will not coerce input values to any particular scale, whereas `numeric` columns with a declared scale will coerce input values to that scale. (The SQL standard requires a default scale of 0, i.e., coercion to integer precision. We find this a bit useless. If you're concerned about portability, always specify the precision and scale explicitly.)

If the precision or scale of a value is greater than the declared precision or scale of a column, the system will attempt to round the value. If the value cannot be rounded so as to satisfy the declared limits, an error is raised.

The types `decimal` and `numeric` are equivalent. Both types are part of the SQL standard.

5.1.3. Floating-Point Types

The data types `real` and `double precision` are inexact, variable-precision numeric types. In practice, these types are usually implementations of IEEE Standard 754 for Binary Floating-Point Arithmetic (single and double precision, respectively), to the extent that the underlying processor, operating system, and compiler support it.

Inexact means that some values cannot be converted exactly to the internal format and are stored as approximations, so that storing and printing back out a value may show slight discrepancies. Managing these errors and how they propagate through calculations is the subject of an entire branch of mathematics and computer science and will not be discussed further here, except for the following points:

- If you require exact storage and calculations (such as for monetary amounts), use the `numeric` type instead.
- If you want to do complicated calculations with these types for anything important, especially if you rely on certain behavior in boundary cases (infinity, underflow), you should evaluate the implementation carefully.
- Comparing two floating-point values for equality may or may not work as expected.

Normally, the `real` type has a range of at least -1E+37 to +1E+37 with a precision of at least 6 decimal digits. The `double precision` type normally has a range of around -1E+308 to +1E+308 with a precision of at least 15 digits. Values that are too large or too small will cause an error. Rounding may take place if the precision of an input number is too high. Numbers too close to zero that are not representable as distinct from zero will cause an underflow error.

5.1.4. The Serial Types

The serial data type is not a true type, but merely a notational convenience for setting up identifier columns (similar to the AUTO_INCREMENT property supported by some other databases). In the current implementation, specifying

```
CREATE TABLE tablename (
    colname SERIAL
);
```

is equivalent to specifying:

```
CREATE SEQUENCE tablename_colname_seq;
CREATE TABLE tablename (
    colname integer DEFAULT nextval('tablename_colname_seq') NOT
 NULL
);
```

Thus, we have created an integer column and arranged for its default values to be assigned from a sequence generator. A NOT NULL constraint is applied to ensure that a null value cannot be explicitly inserted, either. In most cases you would also want to attach a UNIQUE or PRIMARY KEY constraint to prevent duplicate values from being inserted by accident, but this is not automatic.

To use a serial column to insert the next value of the sequence into the table, specify that the serial column should be assigned the default value. This can be done either be excluding from the column from the list of columns in the INSERT statement, or through the use of the DEFAULT keyword.

The type names serial and serial4 are equivalent: both create integer columns. The type names bigserial and serial8 work just the same way, except that they create a bigint column. bigserial should be used if you anticipate the use of more than 2^{31} identifiers over the lifetime of the table.

The sequence created by a serial type is automatically dropped when the owning column is dropped, and cannot be dropped otherwise. (This was not true in PostgreSQL releases before 7.3. Note that this automatic drop linkage will not occur for a sequence created by reloading a dump from a pre-7.3 database; the dump file does not contain the information needed to establish the dependency link.) Furthermore, this dependency between sequence and column is made only for the serial column itself; if any other columns reference the sequence (perhaps by manually calling the nextval() function), they may be broken if the sequence is removed. Using serial columns in fashion is considered bad form.

Note

Prior to PostgreSQL 7.3, serial implied UNIQUE. This is no longer automatic. If you wish a serial column to be UNIQUE or a PRIMARY KEY it must now be specified, just as with any other data type.

5.2. Monetary Type

Note

The money type is deprecated. Use numeric or decimal instead, in combination with the to_char function. The money type may become a locale-aware layer over the numeric type in a future release.

The money type stores a currency amount with fixed decimal point representation; see Table 5.3, “Monetary Types”. The output format is locale-specific.

Input is accepted in a variety of formats, including integer and floating-point literals, as well as “typical” currency formatting, such as '$1,000.00'. Output is in the latter form.

Table 5.3. Monetary Types

Type Name	Storage	Description	Range
money	4 bytes	currency amount	-21474836.48 to +21474836.47

5.3. Character Types

Table 5.4. Character Types

Type name	Description
`character varying(n)`, `varchar(n)`	variable-length with limit
`character(n)`, `char(n)`	fixed-length, blank padded
`text`	variable unlimited length

Table 5.4, “Character Types” shows the general-purpose character types available in PostgreSQL.

SQL defines two primary character types: `character varying(n)` and `character(n)`, where *n* is a positive integer. Both of these types can store strings up to *n* characters in length. An attempt to store a longer string into a column of these types will result in an error, unless the excess characters are all spaces, in which case the string will be truncated to the maximum length. (This somewhat bizarre exception is required by the SQL standard.) If the string to be stored is shorter than the declared length, values of type `character` will be space-padded; values of type `character varying` will simply store the shorter string.

Note

If one explicitly casts a value to `character varying(n)` or `character(n)`, then an over-length value will be truncated to *n* characters without raising an error. (This too is required by the SQL standard.)

Note

Prior to PostgreSQL 7.2, strings that were too long were always truncated without raising an error, in either explicit or implicit casting contexts.

The notations `varchar(n)` and `char(n)` are aliases for `character varying(n)` and `character(n)`, respectively. `character` without length specifier is equivalent to `character(1)`; if `character varying` is used without length specifier, the type accepts strings of any size. The latter is a PostgreSQL extension.

In addition, PostgreSQL supports the more general `text` type, which stores strings of any length. Unlike `character varying`, `text` does not require an explicit declared upper limit on the size of the string. Although the type `text` is not in the SQL standard, many other RDBMS packages have it as well.

The storage requirement for data of these types is 4 bytes plus the actual string, and in case of `character` plus the padding. Long strings are compressed by the system automatically, so the physical requirement on disk may be less. Long values are also stored in background tables so they don't interfere with rapid access to the shorter column values. In any case, the longest possible character string that can be stored is about 1 GB. (The maximum value that will be allowed for *n* in the data type declaration is less than that. It wouldn't be very useful to change this because with multibyte character encodings the number of characters and bytes can be quite different anyway. If you desire to store long strings with no specific upper limit, use `text` or `character varying` without a length specifier, rather than making up an arbitrary length limit.)

Tip

There are no performance differences between these three types, apart from the increased storage size when using the blank-padded type.

Refer to Section 1.1.2.1, “String Constants” for information about the syntax of string literals, and to Chapter 6, *Functions and Operators* for information about available operators and functions.

Example 5.1. Using the character types

```
CREATE TABLE test1 (a character(4));
INSERT INTO test1 VALUES ('ok');
SELECT a, char_length(a) FROM test1; -- 1
  a   | char_length
------+-------------
 ok   |           4

CREATE TABLE test2 (b varchar(5));
INSERT INTO test2 VALUES ('ok');
INSERT INTO test2 VALUES ('good      ');
INSERT INTO test2 VALUES ('too long');
ERROR:  value too long for type character varying(5)
INSERT INTO test2 VALUES ('too long'::varchar(5)); -- explicit
 truncation
SELECT b, char_length(b) FROM test2;
   b   | char_length
-------+-------------
 ok    |           2
 good  |           5
 too l |           5
```

1 The `char_length` function is discussed in Section 6.4, “String Functions and Operators”.

There are two other fixed-length character types in PostgreSQL, shown in Table 5.5, “Specialty Character Types”. The `name` type exists *only* for storage of internal catalog names and is not intended for use by the general user. Its length is currently defined as 64 bytes (63 usable characters plus terminator) but should be referenced using the constant `NAMEDATALEN`. The length is set at compile time (and is therefore adjustable for special uses); the default maximum length may change in a future release. The type `"char"` (note the quotes) is different from `char(1)` in that it only uses one byte of storage. It is internally used in the system catalogs as a poor-man's enumeration type.

Table 5.5. Specialty Character Types

Type Name	Storage	Description
`"char"`	1 byte	single character internal type
`name`	64 bytes	sixty-three character internal type

5.4. Binary Strings

The `bytea` data type allows storage of binary strings; see Table 5.6, “Binary String Types”.

Table 5.6. Binary String Types

Type Name	Storage	Description
`bytea`	4 bytes plus the actual binary string	Variable (not specifically limited) length binary string

A binary string is a sequence of octets (or bytes). Binary strings are distinguished from characters strings by two characteristics: First, binary strings specifically allow storing octets of zero value and other "non-printable" octets (defined as octets outside the range 32 to 126). Second, operations on binary strings process the actual bytes, whereas the encoding and processing of character strings depends on locale settings.

When entering `bytea` values, octets of certain values *must* be escaped (but all octet values *may* be escaped) when used as part of a string literal in an SQL statement. In general, to escape an octet, it is converted into the three-digit octal number equivalent of its decimal octet value, and preceded by two backslashes. Some octet values have alternate escape sequences, as shown in Table 5.7, "`bytea` Literal Escaped Octets".

Table 5.7. `bytea` Literal Escaped Octets

Decimal Octet Value	Description	Input Escaped Representation	Example	Printed Result
0	zero octet	`'\\000'`	`SELECT '\\000'::bytea;`	`\000`
39	single quote	`'\''` or `'\047'`	`SELECT '\''::bytea;`	`'`
92	backslash	`'\\\\'` or `'\134'`	`SELECT '\\\\'::bytea;`	`\\`
0 to 31 and 127 to 255	"non-printable" octets	`'\\`*xxx*`'` (octal value)	`SELECT '\001'::bytea;`	`\001`

The requirement to escape "non-printable" octets actually varies depending on locale settings. In some instances you can get away with leaving them unescaped. Note that the result in each of the examples in Table 5.7, "`bytea` Literal Escaped Octets" was exactly one octet in length, even though the output representation of the zero octet and backslash are more than one character. `Bytea` output octets are also escaped. In general, each "non-printable" octet decimal value is converted into its equivalent three digit octal value, and preceded by one backslash. Most "printable" octets are represented by their standard representation in the client character set. The octet with decimal value 92 (backslash) has a special alternate output representation. Details are in Table 5.8, "`bytea` Output Escaped Octets".

Table 5.8. `bytea` Output Escaped Octets

Decimal Octet Value	Description	Output Escaped Representation	Example	Printed Result
92	backslash	`\\`	`SELECT '\134'::bytea;`	`\\`
0 to 31 and 127 to 255	"non-printable" octets	`\###` (octal value)	`SELECT '\001'::bytea;`	`\001`
32 to 126	"printable" octets	client character set representation	`SELECT '\176'::bytea;`	`~`

To use the `bytea` escaped octet notation, string literals (input strings) must contain two backslashes because they must pass through two parsers in the PostgreSQL server. The first backslash is interpreted as an escape character by the string-literal parser, and therefore is consumed, leaving the characters that follow. The remaining backslash is recognized by the `bytea` input function as the prefix of a three digit octal value. For example, a string literal passed to the backend as `'\\001'` becomes `'\001'` after passing through the string-literal parser. The `'\001'` is then sent to the `bytea` input function, where it is converted to a single octet with a decimal value of 1.

For a similar reason, a backslash must be input as `'\\\\'` (or `'\\134'`). The first and third backslashes are interpreted as escape characters by the string-literal parser, and therefore are consumed, leaving two backslashes in the string passed to the `bytea` input function, which interprets

them as representing a single backslash. For example, a string literal passed to the server as '\\\\' becomes '\\' after passing through the string-literal parser. The '\\' is then sent to the bytea input function, where it is converted to a single octet with a decimal value of 92.

A single quote is a bit different in that it must be input as '\'' (or '\\047'), *not* as '\\''. This is because, while the literal parser interprets the single quote as a special character, and will consume the single backslash, the bytea input function does *not* recognize a single quote as a special octet. Therefore a string literal passed to the backend as '\'' becomes ''' after passing through the string-literal parser. The ''' is then sent to the bytea input function, where it is retains its single octet decimal value of 39.

Depending on the front end to PostgreSQL you use, you may have additional work to do in terms of escaping and unescaping bytea strings. For example, you may also have to escape line feeds and carriage returns if your interface automatically translates these. Or you may have to double up on backslashes if the parser for your language or choice also treats them as an escape character.

The SQL standard defines a different binary string type, called BLOB or BINARY LARGE OBJECT. The input format is different compared to bytea, but the provided functions and operators are mostly the same.

5.5. Date/Time Types

PostgreSQL supports the full set of SQL date and time types, shown in Table 5.9, “Date/Time Types”.

Table 5.9. Date/Time Types

Type	Description	Storage	Earliest	Latest	Resolution
timestamp [(*p*)] [without time zone]	both date and time	8 bytes	4713 BC	AD 1465001	1 microsecond / 14 digits
timestamp [(*p*)] with time zone	both date and time	8 bytes	4713 BC	AD 1465001	1 microsecond / 14 digits
interval [(*p*)]	time intervals	12 bytes	-178000000 years	178000000 years	1 microsecond
date	dates only	4 bytes	4713 BC	32767 AD	1 day
time [(*p*)] [without time zone]	times of day only	8 bytes	00:00:00.00	23:59:59.99	1 microsecond
time [(*p*)] with time zone	times of day only	12 bytes	00:00:00.00+12	23:59:59.99-12	1 microsecond

time, timestamp, and interval accept an optional precision value *p* which specifies the number of fractional digits retained in the seconds field. By default, there is no explicit bound on precision. The allowed range of *p* is from 0 to 6 for the timestamp and interval types.

Note

When timestamp values are stored as double precision floating-point numbers (currently the default), the effective limit of precision may be less than 6, since timestamp values are stored as seconds since 2000-01-01. Microsecond precision is achieved for dates within a few

years of 2000-01-01, but the precision degrades for dates further away. When timestamps are stored as eight-byte integers (a compile-time option), microsecond precision is available over the full range of values.

For the `time` types, the allowed range of *p* is from 0 to 6 when eight-byte integer storage is used, or from 0 to 10 when floating-point storage is used.

Time zones, and time-zone conventions, are influenced by political decisions, not just earth geometry. Time zones around the world became somewhat standardized during the 1900's, but continue to be prone to arbitrary changes. PostgreSQL uses your operating system's underlying features to provide output time-zone support, and these systems usually contain information for only the time period 1902 through 2038 (corresponding to the full range of conventional Unix system time). `timestamp with time zone` and `time with time zone` will use time zone information only within that year range, and assume that times outside that range are in UTC.

The type `time with time zone` is defined by the SQL standard, but the definition exhibits properties which lead to questionable usefulness. In most cases, a combination of `date`, `time`, `timestamp without time zone` and `timestamp with time zone` should provide a complete range of date/time functionality required by any application.

The types `abstime` and `reltime` are lower precision types which are used internally. You are discouraged from using these types in new applications and are encouraged to move any old ones over when appropriate. Any or all of these internal types might disappear in a future release.

5.5.1. Date/Time Input

Date and time input is accepted in almost any reasonable format, including ISO 8601, SQL-compatible, traditional PostgreSQL, and others. For some formats, ordering of month and day in date input can be ambiguous and there is support for specifying the expected ordering of these fields. The command `SET DateStyle TO 'US'` or `SET DateStyle TO 'NonEuropean'` specifies the variant "month before day", the command `SET DateStyle TO 'European'` sets the variant "day before month".

PostgreSQL is more flexible in handling date/time than the SQL standard requires. See Appendix A, *Date/Time Support* for the exact parsing rules of date/time input and for the recognized text fields including months, days of the week, and time zones.

Remember that any date or time literal input needs to be enclosed in single quotes, like text strings. Refer to Section 1.1.2.4, "Constants of Other Types" for more information. SQL requires the following syntax

type [(*p*)] '*value*'

where *p* in the optional precision specification is an integer corresponding to the number of fractional digits in the seconds field. Precision can be specified for `time`, `timestamp`, and `interval` types.

5.5.1.1. Dates

Table 5.10, "Date Input" shows some possible inputs for the `date` type.

Table 5.10. Date Input

Example	Description
January 8, 1999	unambiguous
1999-01-08	ISO-8601 format, preferred
1/8/1999	U.S.; read as August 1 in European mode
8/1/1999	European; read as August 1 in U.S. mode
1/18/1999	U.S.; read as January 18 in any mode

Example	Description
19990108	ISO-8601 year, month, day
990108	ISO-8601 year, month, day
1999.008	year and day of year
99008	year and day of year
J2451187	Julian day
January 8, 99 BC	year 99 before the Common Era

5.5.1.2. Times

The `time` type can be specified as `time` or as `time without time zone`. The optional precision *p* should be between 0 and 6, and defaults to the precision of the input time literal.

Table 5.11, "Time Input" shows the valid `time` inputs.

Table 5.11. Time Input

Example	Description
`04:05:06.789`	ISO 8601
`04:05:06`	ISO 8601
`04:05`	ISO 8601
`040506`	ISO 8601
`04:05 AM`	same as 04:05; AM does not affect value
`04:05 PM`	same as 16:05; input hour must be <= 12
`allballs`	same as 00:00:00

The type `time with time zone` accepts all input also legal for the `time` type, appended with a legal time zone, as shown in Table 5.12, "Time With Time Zone Input".

Table 5.12. Time With Time Zone Input

Example	Description
04:05:06.789-8	ISO 8601
04:05:06-08:00	ISO 8601
04:05-08:00	ISO 8601
040506-08	ISO 8601

Refer to Table 5.13, "Time Zone Input" for more examples of time zones.

5.5.1.3. Time stamps

The time stamp types are `timestamp [ (p) ] without time zone` and `timestamp [ (p) ] with time zone`. Writing just `timestamp` is equivalent to `timestamp without time zone`.

> ### Note
>
> Prior to PostgreSQL 7.3, writing just `timestamp` was equivalent to `timestamp with time zone`. This was changed for SQL spec compliance.

Valid input for the time stamp types consists of a concatenation of a date and a time, followed by an optional `AD` or `BC`, followed by an optional time zone. (See Table 5.13, "Time Zone Input".) Thus

```
1999-01-08 04:05:06
```

and

```
1999-01-08 04:05:06 -8:00
```

are valid values, which follow the ISO 8601 standard. In addition, the wide-spread format

```
January 8 04:05:06 1999 PST
```

is supported.

The optional precision *p* should be between 0 and 6, and defaults to the precision of the input `timestamp` literal.

For `timestamp without time zone`, any explicit time zone specified in the input is silently ignored. That is, the resulting date/time value is derived from the explicit date/time fields in the input value, and is not adjusted for time zone.

For `timestamp with time zone`, the internally stored value is always in UTC (GMT). An input value that has an explicit time zone specified is converted to UTC using the appropriate offset for that time zone. If no time zone is stated in the input string, then it is assumed to be in the time zone indicated by the system's `TimeZone` parameter, and is converted to UTC using the offset for the `TimeZone` zone.

When a `timestamp with time zone` value is output, it is always converted from UTC to the current `TimeZone` zone, and displayed as local time in that zone. To see the time in another time zone, either change `TimeZone` or use the `AT TIME ZONE` construct (see Section 6.8.3, "`AT TIME ZONE`").

Conversions between `timestamp without time zone` and `timestamp with time zone` normally assume that the `timestamp without time zone` value should be taken or given as `TimeZone` local time. A different zone reference can be specified for the conversion using `AT TIME ZONE`.

Table 5.13. Time Zone Input

Time Zone	Description
PST	Pacific Standard Time
-8:00	ISO-8601 offset for PST
-800	ISO-8601 offset for PST
-8	ISO-8601 offset for PST

5.5.1.4. Intervals

`interval` values can be written with the following syntax:

```
  Quantity Unit [Quantity Unit...] [Direction]
@ Quantity Unit [Quantity Unit...] [Direction]
```

where: `Quantity` is a number (possibly signed), `Unit` is `second`, `minute`, `hour`, `day`, `week`, `month`, `year`, `decade`, `century`, `millennium`, or abbreviations or plurals of these units; `Direction` can be `ago` or empty. The at sign (`@`) is optional noise. The amounts of different units are implicitly added up with appropriate sign accounting.

Quantities of days, hours, minutes, and seconds can be specified without explicit unit markings. For example, `'1 12:59:10'` is read the same as `'1 day 12 hours 59 min 10 sec'`.

The optional precision *p* should be between 0 and 6, and defaults to the precision of the input literal.

5.5.1.5. Special values

The following SQL-compatible functions can be used as date or time values for the corresponding data type: `CURRENT_DATE`, `CURRENT_TIME`, `CURRENT_TIMESTAMP`. The latter two accept an optional precision specification. (See also Section 6.8.4, "Current Date/Time".)

PostgreSQL also supports several special date/time input values for convenience, as shown in Table 5.14, "Special Date/Time Inputs". The values `infinity` and `-infinity` are specially represented inside the system and will be displayed the same way; but the others are simply notational shorthands that will be converted to ordinary date/time values when read.

Table 5.14. Special Date/Time Inputs

Input string	Description
`epoch`	1970-01-01 00:00:00+00 (Unix system time zero)
`infinity`	later than all other timestamps (not available for type `date`)
`-infinity`	earlier than all other timestamps (not available for type `date`)
`now`	current transaction time
`today`	midnight today
`tomorrow`	midnight tomorrow
`yesterday`	midnight yesterday
`zulu`, `allballs`, `z`	00:00:00.00 GMT

5.5.2. Date/Time Output

Output formats can be set to one of the four styles ISO 8601, SQL (Ingres), traditional PostgreSQL, and German, using the `SET DateStyle`. The default is the ISO format. (The SQL standard requires the use of the ISO 8601 format. The name of the "SQL" output format is a historical accident.) Table 5.15, "Date/Time Output Styles" shows examples of each output style. The output of the `date` and `time` types is of course only the date or time part in accordance with the given examples.

Table 5.15. Date/Time Output Styles

Style Specification	Description	Example
ISO	ISO 8601/SQL standard	1997-12-17 07:37:16-08
SQL	traditional style	12/17/1997 07:37:16.00 PST
PostgreSQL	original style	Wed Dec 17 07:37:16 1997 PST
German	regional style	17.12.1997 07:37:16.00 PST

The SQL style has European and non-European (U.S.) variants, which determines whether month follows day or vice versa. (See Section 5.5.1, "Date/Time Input" for how this setting also affects interpretation of input values.) Table 5.16, "Date Order Conventions" shows an example.

Table 5.16. Date Order Conventions

Style Specification	Description	Example
European	*day*/*month*/*year*	17/12/1997 15:37:16.00 MET
US	*month*/*day*/*year*	12/17/1997 07:37:16.00 PST

`interval` output looks like the input format, except that units like `week` or `century` are converted to years and days. In ISO mode the output looks like

```
[ Quantity Units [ ... ] ] [ Days ] Hours:Minutes [ ago ]
```

The date/time styles can be selected by the user using the `SET DATESTYLE` command, the `datestyle` parameter in the `postgresql.conf` configuration file, and the `PGDATESTYLE` environment variable on the server or client. The formatting function `to_char` (see Section 6.7, "Data Type Formatting Functions") is also available as a more flexible way to format the date/time output.

5.5.3. Time Zones

PostgreSQL endeavors to be compatible with the SQL standard definitions for typical usage. However, the SQL standard has an odd mix of date and time types and capabilities. Two obvious problems are:

- Although the `date` type does not have an associated time zone, the `time` type can. Time zones in the real world can have no meaning unless associated with a date as well as a time since the offset may vary through the year with daylight-saving time boundaries.
- The default time zone is specified as a constant integer offset from GMT/UTC. It is not possible to adapt to daylight-saving time when doing date/time arithmetic across DST boundaries.

To address these difficulties, we recommend using date/time types that contain both date and time when using time zones. We recommend *not* using the type `time with time zone` (though it is supported by PostgreSQL for legacy applications and for compatibility with other SQL implementations). PostgreSQL assumes your local time zone for any type containing only date or time. Further, time zone support is derived from the underlying operating system time-zone capabilities, and hence can handle daylight-saving time and other expected behavior.

PostgreSQL obtains time-zone support from the underlying operating system for dates between 1902 and 2038 (near the typical date limits for Unix-style systems). Outside of this range, all dates are assumed to be specified and used in Universal Coordinated Time (UTC).

All dates and times are stored internally in UTC, traditionally known as Greenwich Mean Time (GMT). Times are converted to local time on the database server before being sent to the client frontend, hence by default are in the server time zone.

There are several ways to select the time zone used by the server:

- The `TZ` environment variable on the server host is used by the server as the default time zone, if no other is specified.
- The `timezone` configuration parameter can be set in `postgresql.conf`.
- The `PGTZ` environment variable, if set at the client, is used by libpq applications to send a `SET TIME ZONE` command to the server upon connection.
- The SQL command `SET TIME ZONE` sets the time zone for the session.

Note

If an invalid time zone is specified, the time zone becomes UTC (on most systems anyway).

Refer to Appendix A, *Date/Time Support* for a list of available time zones.

5.5.4. Internals

PostgreSQL uses Julian dates for all date/time calculations. They have the nice property of correctly predicting/calculating any date more recent than 4713 BC to far into the future, using the assumption that the length of the year is 365.2425 days.

Date conventions before the 19th century make for interesting reading, but are not consistent enough to warrant coding into a date/time handler.

5.6. Boolean Type

PostgreSQL provides the standard SQL type `boolean`. `boolean` can have one of only two states: “true” or “false”. A third state, “unknown”, is represented by the SQL null value.

Valid literal values for the “true” state are:

```
TRUE
't'
'true'
'y'
'yes'
'1'
```

For the “false” state, the following values can be used:

```
FALSE
'f'
'false'
'n'
'no'
'0'
```

Using the key words `TRUE` and `FALSE` is preferred (and SQL-compliant).

Example 5.2. Using the `boolean` type

```
CREATE TABLE test1 (a boolean, b text);
INSERT INTO test1 VALUES (TRUE, 'sic est');
INSERT INTO test1 VALUES (FALSE, 'non est');
SELECT * FROM test1;
 a |    b
---+---------
 t | sic est
 f | non est

SELECT * FROM test1 WHERE a;
 a |    b
---+---------
 t | sic est
```

Example 5.2, “Using the `boolean` type” shows that `boolean` values are output using the letters `t` and `f`.

> **Tip**
>
> Values of the `boolean` type cannot be cast directly to other types (e.g., `CAST (`*`boolval`*` AS integer)` does not work). This can be accomplished using the `CASE` expression: `CASE WHEN `*`boolval`*` THEN 'value if true' ELSE 'value if false' END`. See also Section 6.12, “Conditional Expressions”.

`boolean` uses 1 byte of storage.

5.7. Geometric Types

Geometric data types represent two-dimensional spatial objects. Table 5.17, “Geometric Types” shows the geometric types available in PostgreSQL. The most fundamental type, the point, forms the basis for all of the other types.

Table 5.17. Geometric Types

Geometric Type	Storage	Representation	Description
`point`	16 bytes	(x,y)	Point in space
`line`	32 bytes	((x1,y1),(x2,y2))	Infinite line (not fully implemented)
`lseg`	32 bytes	((x1,y1),(x2,y2))	Finite line segment
`box`	32 bytes	((x1,y1),(x2,y2))	Rectangular box
`path`	16+16n bytes	((x1,y1),...)	Closed path (similar to polygon)
`path`	16+16n bytes	[(x1,y1),...]	Open path
`polygon`	40+16n bytes	((x1,y1),...)	Polygon (similar to closed path)
`circle`	24 bytes	<(x,y),r>	Circle (center and radius)

A rich set of functions and operators is available to perform various geometric operations such as scaling, translation, rotation, and determining intersections. They are explained in Section 6.9, “Geometric Functions and Operators”.

5.7.1. Point

Points are the fundamental two-dimensional building block for geometric types. `point` is specified using the following syntax:

```
( x , y )
  x , y
```

where the arguments are

x

the x-axis coordinate as a floating-point number

y

the y-axis coordinate as a floating-point number

5.7.2. Line Segment

Line segments (`lseg`) are represented by pairs of points. `lseg` is specified using the following syntax:

```
( ( x1 , y1 ) , ( x2 , y2 ) )
  ( x1 , y1 ) , ( x2 , y2 )
    x1 , y1   ,   x2 , y2
```

where the arguments are

(*x1*,*y1*)
(*x2*,*y2*)

the end points of the line segment

5.7.3. Box

Boxes are represented by pairs of points that are opposite corners of the box. `box` is specified using the following syntax:

```
( ( x1 , y1 ) , ( x2 , y2 ) )
  ( x1 , y1 ) , ( x2 , y2 )
    x1 , y1   ,   x2 , y2
```

where the arguments are

(*x1*,*y1*)
(*x2*,*y2*)

opposite corners of the box

Boxes are output using the first syntax. The corners are reordered on input to store the upper right corner, then the lower left corner. Other corners of the box can be entered, but the lower left and upper right corners are determined from the input and stored corners.

5.7.4. Path

Paths are represented by connected sets of points. Paths can be *open*, where the first and last points in the set are not connected, and *closed*, where the first and last point are connected. Functions `popen(p)` and `pclose(p)` are supplied to force a path to be open or closed, and functions `isopen(p)` and `isclosed(p)` are supplied to test for either type in a query.

`path` is specified using the following syntax:

```
( ( x1 , y1 ) , ... , ( xn , yn ) )
[ ( x1 , y1 ) , ... , ( xn , yn ) ]
  ( x1 , y1 ) , ... , ( xn , yn )
  ( x1 , y1   , ... ,   xn , yn )
    x1 , y1   , ... ,   xn , yn
```

where the arguments are

(*x*,*y*)

End points of the line segments comprising the path. A leading square bracket (`[`) indicates an open path, while a leading parenthesis (`(`) indicates a closed path.

Paths are output using the first syntax.

5.7.5. Polygon

Polygons are represented by sets of points. Polygons should probably be considered equivalent to closed paths, but are stored differently and have their own set of support routines.

`polygon` is specified using the following syntax:

```
( ( x1 , y1 ) , ... , ( xn , yn ) )
  ( x1 , y1 ) , ... , ( xn , yn )
  ( x1 , y1   , ... ,   xn , yn )
    x1 , y1   , ... ,   xn , yn
```

where the arguments are

(*x*,*y*)

End points of the line segments comprising the boundary of the polygon

Polygons are output using the first syntax.

5.7.6. Circle

Circles are represented by a center point and a radius. `circle` is specified using the following syntax:

```
< ( x , y ) , r >
( ( x , y ) , r )
  ( x , y ) , r
    x , y   , r
```

where the arguments are

(*x*,*y*)

center of the circle

r

radius of the circle

Circles are output using the first syntax.

5.8. Network Address Data Types

PostgreSQL offers data types to store IP and MAC addresses, shown in Table 5.18, "Network Address Data Types". It is preferable to use these types over plain text types, because these types offer input error checking and several specialized operators and functions.

Table 5.18. Network Address Data Types

Name	Storage	Description	Range
`cidr`	12 bytes	IP networks	valid IPv4 networks
`inet`	12 bytes	IP hosts and networks	valid IPv4 hosts or networks
`macaddr`	6 bytes	MAC addresses	customary formats

IPv6 is not yet supported.

5.8.1. `inet`

The `inet` type holds an IP host address, and optionally the identity of the subnet it is in, all in one field. The subnet identity is represented by the number of bits in the network part of the address (the "netmask"). If the netmask is 32, then the value does not indicate a subnet, only a single host. Note that if you want to accept networks only, you should use the `cidr` type rather than `inet`.

The input format for this type is *x*`.`*x*`.`*x*`.`*x*`/`*y* where *x*`.`*x*`.`*x*`.`*x* is an IP address and *y* is the number of bits in the netmask. If the `/`*y* part is left off, then the netmask is 32, and the value represents just a single host. On display, the `/`*y* portion is suppressed if the netmask is 32.

5.8.2. `cidr`

The `cidr` type holds an IP network specification. Input and output formats follow Classless Internet Domain Routing conventions. The format for specifying classless networks is *x*`.`*x*`.`*x*`.`*x*`/`*y* where *x*`.`*x*`.`*x*`.`*x* is the network and *y* is the number of bits in the netmask. If *y* is omitted, it is calculated using assumptions from the older classful numbering system, except that it will be at least large enough to include all of the octets written in the input.

Table 5.19, "`cidr` Type Input Examples" shows some examples.

Table 5.19. `cidr` Type Input Examples

`CIDR` Input	`CIDR` Displayed	`abbrev(CIDR)`
192.168.100.128/25	192.168.100.128/25	192.168.100.128/25
192.168/24	192.168.0.0/24	192.168.0/24
192.168/25	192.168.0.0/25	192.168.0.0/25
192.168.1	192.168.1.0/24	192.168.1/24
192.168	192.168.0.0/24	192.168.0/24
128.1	128.1.0.0/16	128.1/16
128	128.0.0.0/16	128.0/16
128.1.2	128.1.2.0/24	128.1.2/24
10.1.2	10.1.2.0/24	10.1.2/24
10.1	10.1.0.0/16	10.1/16
10	10.0.0.0/8	10/8

5.8.3. `inet` vs `cidr`

The essential difference between `inet` and `cidr` data types is that `inet` accepts values with nonzero bits to the right of the netmask, whereas `cidr` does not.

Tip

If you do not like the output format for `inet` or `cidr` values, try the `host`(), `text`(), and `abbrev`() functions.

5.8.4. `macaddr`

The `macaddr` type stores MAC addresses, i.e., Ethernet card hardware addresses (although MAC addresses are used for other purposes as well). Input is accepted in various customary formats, including

```
'08002b:010203'
'08002b-010203'
'0800.2b01.0203'
'08-00-2b-01-02-03'
'08:00:2b:01:02:03'
```

which would all specify the same address. Upper and lower case is accepted for the digits `a` through `f`. Output is always in the last of the shown forms.

The directory `contrib/mac` in the PostgreSQL source distribution contains tools that can be used to map MAC addresses to hardware manufacturer names.

5.9. Bit String Types

Bit strings are strings of 1's and 0's. They can be used to store or visualize bit masks. There are two SQL bit types: `BIT(`*n*`)` and `BIT VARYING(`*n*`)`, where *n* is a positive integer.

`BIT` type data must match the length *n* exactly; it is an error to attempt to store shorter or longer bit strings. `BIT VARYING` data is of variable length up to the maximum length *n*; longer strings will be rejected. Writing `BIT` without a length is equivalent to `BIT(1)`, while `BIT VARYING` without a length specification means unlimited length.

Note

If one explicitly casts a bit-string value to `BIT(n)`, it will be truncated or zero-padded on the right to be exactly *n* bits, without raising an error. Similarly, if one explicitly casts a bit-string value to `BIT VARYING(n)`, it will be truncated on the right if it is more than *n* bits.

Note

Prior to PostgreSQL 7.2, `BIT` data was always silently truncated or zero-padded on the right, with or without an explicit cast. This was changed to comply with the SQL standard.

Refer to Section 1.1.2.2, "Bit-String Constants" for information about the syntax of bit string constants. Bit-logical operators and string manipulation functions are available; see Chapter 6, *Functions and Operators*.

Example 5.3. Using the bit string types

```
CREATE TABLE test (a BIT(3), b BIT VARYING(5));
INSERT INTO test VALUES (B'101', B'00');
INSERT INTO test VALUES (B'10', B'101');
ERROR:  Bit string length 2 does not match type BIT(3)
INSERT INTO test VALUES (B'10'::bit(3), B'101');
SELECT * FROM test;
  a  |  b
-----+-----
 101 | 00
 100 | 101
```

5.10. Object Identifier Types

Object identifiers (OIDs) are used internally by PostgreSQL as primary keys for various system tables. Also, an OID system column is added to user-created tables (unless `WITHOUT OIDS` is specified at table creation time). Type `oid` represents an object identifier. There are also several aliases for `oid`: `regproc`, `regprocedure`, `regoper`, `regoperator`, `regclass`, and `regtype`. Table 5.20, "Object Identifier Types" shows an overview.

The `oid` type is currently implemented as an unsigned four-byte integer. Therefore, it is not large enough to provide database-wide uniqueness in large databases, or even in large individual tables. So, using a user-created table's OID column as a primary key is discouraged. OIDs are best used only for references to system tables.

The `oid` type itself has few operations beyond comparison (which is implemented as unsigned comparison). It can be cast to integer, however, and then manipulated using the standard integer operators. (Beware of possible signed-versus-unsigned confusion if you do this.)

The `oid` alias types have no operations of their own except for specialized input and output routines. These routines are able to accept and display symbolic names for system objects, rather than the raw numeric value that type `oid` would use. The alias types allow simplified lookup of OID values for objects: for example, one may write `'mytable'::regclass` to get the OID of table `mytable`, rather than `SELECT oid FROM pg_class WHERE relname = 'mytable'`. (In reality, a much more complicated `SELECT` would be needed to deal with selecting the right OID when there are multiple tables named `mytable` in different schemas.)

Table 5.20. Object Identifier Types

Type name	References	Description	Value example
`oid`	any	numeric object identifier	`564182`

Type name	References	Description	Value example
regproc	pg_proc	function name	sum
regprocedure	pg_proc	function with argument types	sum(int4)
regoper	pg_operator	operator name	+
regoperator	pg_operator	operator with argument types	*(integer,integer) or -(NONE,integer)
regclass	pg_class	relation name	pg_type
regtype	pg_type	type name	integer

All of the OID alias types accept schema-qualified names, and will display schema-qualified names on output if the object would not be found in the current search path without being qualified. The regproc and regoper alias types will only accept input names that are unique (not overloaded), so they are of limited use; for most uses regprocedure or regoperator is more appropriate. For regoperator, unary operators are identified by writing NONE for the unused operand.

OIDs are 32-bit quantities and are assigned from a single cluster-wide counter. In a large or long-lived database, it is possible for the counter to wrap around. Hence, it is bad practice to assume that OIDs are unique, unless you take steps to ensure that they are unique. Recommended practice when using OIDs for row identification is to create a unique constraint on the OID column of each table for which the OID will be used. Never assume that OIDs are unique across tables; use the combination of tableoid and row OID if you need a database-wide identifier. (Future releases of PostgreSQL are likely to use a separate OID counter for each table, so that tableoid *must* be included to arrive at a globally unique identifier.)

Another identifier type used by the system is xid, or transaction (abbreviated xact) identifier. This is the data type of the system columns xmin and xmax. Transaction identifiers are 32-bit quantities. In a long-lived database it is possible for transaction IDs to wrap around. This is not a fatal problem given appropriate maintenance procedures; see the PostgreSQL 7.3.21 Administrator's Guide for details. However, it is unwise to depend on uniqueness of transaction IDs over the long term (more than one billion transactions).

A third identifier type used by the system is cid, or command identifier. This is the data type of the system columns cmin and cmax. Command identifiers are also 32-bit quantities. This creates a hard limit of 2^{32} (4 billion) SQL commands within a single transaction. In practice this limit is not a problem --- note that the limit is on number of SQL commands, not number of tuples processed.

A final identifier type used by the system is tid, or tuple identifier. This is the data type of the system column ctid. A tuple ID is a pair (block number, tuple index within block) that identifies the physical location of the tuple within its table.

5.11. Pseudo-Types

The PostgreSQL type system contains a number of special-purpose entries that are collectively called *pseudo-types*. A pseudo-type cannot be used as a column data type, but it can be used to declare a function's argument or result type. Each of the available pseudo-types is useful in situations where a function's behavior does not correspond to simply taking or returning a value of a specific SQL data type. Table 5.21, “Pseudo-Types” lists the existing pseudo-types.

Table 5.21. Pseudo-Types

Type name	Description
record	Identifies a function returning an unspecified row type

Type name	Description
any	Indicates that a function accepts any input data type whatever
anyarray	Indicates that a function accepts any array data type
void	Indicates that a function returns no value
trigger	A trigger function is declared to return trigger
language_handler	A procedural language call handler is declared to return language_handler
cstring	Indicates that a function accepts or returns a null-terminated C string
internal	Indicates that a function accepts or returns a server-internal data type
opaque	An obsolete type name that formerly served all the above purposes

Functions coded in C (whether built-in or dynamically loaded) may be declared to accept or return any of these pseudo data types. It is up to the function author to ensure that the function will behave safely when a pseudo-type is used as an argument type.

Functions coded in procedural languages may use pseudo-types only as allowed by their implementation languages. At present the procedural languages all forbid use of a pseudo-type as argument type, and allow only void as a result type (plus trigger when the function is used as a trigger).

The internal pseudo-type is used to declare functions that are meant only to be called internally by the database system, and not by direct invocation in a SQL query. If a function has at least one internal-type argument then it cannot be called from SQL. To preserve the type safety of this restriction it is important to follow this coding rule: do not create any function that is declared to return internal unless it has at least one internal argument.

5.12. Arrays

PostgreSQL allows columns of a table to be defined as variable-length multidimensional arrays. Arrays of any built-in type or user-defined type can be created. To illustrate their use, we create this table:

```
CREATE TABLE sal_emp (
    name            text,
    pay_by_quarter  integer[],
    schedule        text[][]
);
```

As shown, an array data type is named by appending square brackets ([]) to the data type name of the array elements. The above command will create a table named sal_emp with columns including a text string (name), a one-dimensional array of type integer (pay_by_quarter), which represents the employee's salary by quarter, and a two-dimensional array of text (schedule), which represents the employee's weekly schedule.

Now we do some INSERTs. Observe that to write an array value, we enclose the element values within curly braces and separate them by commas. If you know C, this is not unlike the syntax for initializing structures. (More details appear below.)

```
INSERT INTO sal_emp
    VALUES ('Bill',
    '{10000, 10000, 10000, 10000}',
```

```
    '{{"meeting", "lunch"}, {}}');

INSERT INTO sal_emp
    VALUES ('Carol',
    '{20000, 25000, 25000, 25000}',
    '{{"talk", "consult"}, {"meeting"}}');
```

Now, we can run some queries on `sal_emp`. First, we show how to access a single element of an array at a time. This query retrieves the names of the employees whose pay changed in the second quarter:

```
SELECT name FROM sal_emp WHERE pay_by_quarter[1] <>
 pay_by_quarter[2];

 name
-------
 Carol
(1 row)
```

The array subscript numbers are written within square brackets. By default PostgreSQL uses the one-based numbering convention for arrays, that is, an array of *n* elements starts with `array[1]` and ends with `array[`*n*`]`.

This query retrieves the third quarter pay of all employees:

```
SELECT pay_by_quarter[3] FROM sal_emp;

 pay_by_quarter
----------------
          10000
          25000
(2 rows)
```

We can also access arbitrary rectangular slices of an array, or subarrays. An array slice is denoted by writing *`lower-bound`*`:`*`upper-bound`* for one or more array dimensions. This query retrieves the first item on Bill's schedule for the first two days of the week:

```
SELECT schedule[1:2][1:1] FROM sal_emp WHERE name = 'Bill';

      schedule
--------------------
 {{meeting},{""}}
(1 row)
```

We could also have written

```
SELECT schedule[1:2][1] FROM sal_emp WHERE name = 'Bill';
```

with the same result. An array subscripting operation is taken to represent an array slice if any of the subscripts are written in the form *`lower`*`:`*`upper`*. A lower bound of 1 is assumed for any subscript where only one value is specified.

An array value can be replaced completely:

```
UPDATE sal_emp SET pay_by_quarter = '{25000,25000,27000,27000}'
    WHERE name = 'Carol';
```

or updated at a single element:

```
UPDATE sal_emp SET pay_by_quarter[4] = 15000
    WHERE name = 'Bill';
```

or updated in a slice:

```
UPDATE sal_emp SET pay_by_quarter[1:2] = '{27000,27000}'
    WHERE name = 'Carol';
```

An array can be enlarged by assigning to an element adjacent to those already present, or by assigning to a slice that is adjacent to or overlaps the data already present. For example, if an array value currently has 4 elements, it will have five elements after an update that assigns to `array[5]`. Currently, enlargement in this fashion is only allowed for one-dimensional arrays, not multidimensional arrays.

Array slice assignment allows creation of arrays that do not use one-based subscripts. For example one might assign to `array[-2:7]` to create an array with subscript values running from -2 to 7.

The syntax for `CREATE TABLE` allows fixed-length arrays to be defined:

```
CREATE TABLE tictactoe (
    squares   integer[3][3]
);
```

However, the current implementation does not enforce the array size limits --- the behavior is the same as for arrays of unspecified length.

Actually, the current implementation does not enforce the declared number of dimensions either. Arrays of a particular element type are all considered to be of the same type, regardless of size or number of dimensions. So, declaring number of dimensions or sizes in `CREATE TABLE` is simply documentation, it does not affect runtime behavior.

The current dimensions of any array value can be retrieved with the `array_dims` function:

```
SELECT array_dims(schedule) FROM sal_emp WHERE name = 'Carol';

 array_dims
------------
 [1:2][1:1]
(1 row)
```

`array_dims` produces a `text` result, which is convenient for people to read but perhaps not so convenient for programs.

To search for a value in an array, you must check each value of the array. This can be done by hand (if you know the size of the array):

```
SELECT * FROM sal_emp WHERE pay_by_quarter[1] = 10000 OR
                            pay_by_quarter[2] = 10000 OR
                            pay_by_quarter[3] = 10000 OR
                            pay_by_quarter[4] = 10000;
```

However, this quickly becomes tedious for large arrays, and is not helpful if the size of the array is unknown. Although it is not part of the primary PostgreSQL distribution, there is an extension available that defines new functions and operators for iterating over array values. Using this, the above query could be:

```
SELECT * FROM sal_emp WHERE pay_by_quarter[1:4] *= 10000;
```

To search the entire array (not just specified columns), you could use:

```
SELECT * FROM sal_emp WHERE pay_by_quarter *= 10000;
```

In addition, you could find rows where the array had all values equal to 10 000 with:

```
SELECT * FROM sal_emp WHERE pay_by_quarter **= 10000;
```

To install this optional module, look in the `contrib/array` directory of the PostgreSQL source distribution.

Tip

Arrays are not sets; using arrays in the manner described in the previous paragraph is often a sign of database misdesign. The array field should generally be split off into a separate table. Tables can obviously be searched easily.

Note

A limitation of the present array implementation is that individual elements of an array cannot be SQL null values. The entire array can be set to null, but you can't have an array with some elements null and some not. Fixing this is on the to-do list.

Array input and output syntax. The external representation of an array value consists of items that are interpreted according to the I/O conversion rules for the array's element type, plus decoration that indicates the array structure. The decoration consists of curly braces (`{` and `}`) around the array value plus delimiter characters between adjacent items. The delimiter character is usually a comma (`,`) but can be something else: it is determined by the `typdelim` setting for the array's element type. (Among the standard data types provided in the PostgreSQL distribution, type `box` uses a semicolon (`;`) but all the others use comma.) In a multidimensional array, each dimension (row, plane, cube, etc.) gets its own level of curly braces, and delimiters must be written between adjacent curly-braced entities of the same level. You may write whitespace before a left brace, after a right brace, or before any individual item string. Whitespace after an item is not ignored, however: after skipping leading whitespace, everything up to the next right brace or delimiter is taken as the item value.

Quoting array elements. As shown above, when writing an array value you may write double quotes around any individual array element. You *must* do so if the element value would otherwise confuse the array-value parser. For example, elements containing curly braces, commas (or whatever the delimiter character is), double quotes, backslashes, or leading white space must be double-quoted. To put a double quote or backslash in an array element value, precede it with a backslash. Alternatively, you can use backslash-escaping to protect all data characters that would otherwise be taken as array syntax or ignorable white space.

The array output routine will put double quotes around element values if they are empty strings or contain curly braces, delimiter characters, double quotes, backslashes, or white space. Double quotes and backslashes embedded in element values will be backslash-escaped. For numeric data types it is safe to assume that double quotes will never appear, but for textual data types one should be prepared to cope with either presence or absence of quotes. (This is a change in behavior from pre-7.2 PostgreSQL releases.)

Tip

Remember that what you write in an SQL command will first be interpreted as a string literal, and then as an array. This doubles the number of backslashes you need. For example, to insert a `text` array value containing a backslash and a double quote, you'd need to write

```
INSERT ... VALUES ('{"\\\\","\\""}');
```

The string-literal processor removes one level of backslashes, so that what arrives at the array-value parser looks like `{"\\","\""}`. In turn, the strings fed to the `text` data type's input routine become `\` and `"` respectively. (If we were working with a data type whose input routine also treated backslashes specially, `bytea` for example, we might need as many as eight backslashes in the command to get one backslash into the stored array element.)

Chapter 6. Functions and Operators

PostgreSQL provides a large number of functions and operators for the built-in data types. Users can also define their own functions and operators, as described in the PostgreSQL 7.3.21 Programmer's Guide. The psql commands `\df` and `\do` can be used to show the list of all actually available functions and operators, respectively.

If you are concerned about portability then take note that most of the functions and operators described in this chapter, with the exception of the most trivial arithmetic and comparison operators and some explicitly marked functions, are not specified by the SQL standard. Some of this extended functionality is present in other SQL implementations, and in many cases this functionality is compatible and consistent between various products.

6.1. Logical Operators

The usual logical operators are available:

AND
OR
NOT
SQL uses a three-valued Boolean logic where the null value represents “unknown”. Observe the following truth tables:

a	*b*	*a* AND *b*	*a* OR *b*
TRUE	TRUE	TRUE	TRUE
TRUE	FALSE	FALSE	TRUE
TRUE	NULL	NULL	TRUE
FALSE	FALSE	FALSE	FALSE
FALSE	NULL	FALSE	NULL
NULL	NULL	NULL	NULL

a	NOT *a*
TRUE	FALSE
FALSE	TRUE
NULL	NULL

6.2. Comparison Operators

The usual comparison operators are available, shown in Table 6.1, “Comparison Operators”.

Table 6.1. Comparison Operators

Operator	Description
<	less than
>	greater than
<=	less than or equal to
>=	greater than or equal to
=	equal

Operator	Description
<> or !=	not equal

Note

The != operator is converted to <> in the parser stage. It is not possible to implement != and <> operators that do different things.

Comparison operators are available for all data types where this makes sense. All comparison operators are binary operators that return values of type `boolean`; expressions like `1 < 2 < 3` are not valid (because there is no < operator to compare a Boolean value with `3`).

In addition to the comparison operators, the special `BETWEEN` construct is available.

a `BETWEEN` *x* `AND` *y*

is equivalent to

a `>=` *x* `AND` *a* `<=` *y*

Similarly,

a `NOT BETWEEN` *x* `AND` *y*

is equivalent to

a `<` *x* `OR` *a* `>` *y*

There is no difference between the two respective forms apart from the CPU cycles required to rewrite the first one into the second one internally.

To check whether a value is or is not null, use the constructs

expression `IS NULL`
expression `IS NOT NULL`

or the equivalent, but nonstandard, constructs

expression `ISNULL`
expression `NOTNULL`

Do *not* write *expression* `= NULL` because `NULL` is not "equal to" `NULL`. (The null value represents an unknown value, and it is not known whether two unknown values are equal.)

Some applications may (incorrectly) require that *expression* `= NULL` returns true if *expression* evaluates to the null value. To support these applications, the run-time option `transform_null_equals` can be turned on (e.g., `SET transform_null_equals TO ON;`). PostgreSQL will then convert `x = NULL` clauses to `x IS NULL`. This was the default behavior in releases 6.5 through 7.1.

Boolean values can also be tested using the constructs

expression `IS TRUE`
expression `IS NOT TRUE`
expression `IS FALSE`
expression `IS NOT FALSE`
expression `IS UNKNOWN`
expression `IS NOT UNKNOWN`

These are similar to `IS NULL` in that they will always return true or false, never a null value, even when the operand is null. A null input is treated as the logical value "unknown".

6.3. Mathematical Functions and Operators

Mathematical operators are provided for many PostgreSQL types. For types without common mathematical conventions for all possible permutations (e.g., date/time types) we describe the actual behavior in subsequent sections.

Table 6.2, “Mathematical Operators” shows the available mathematical operators.

Table 6.2. Mathematical Operators

Name	Description	Example	Result
+	addition	2 + 3	5
−	subtraction	2 - 3	-1
*	multiplication	2 * 3	6
/	division (integer division truncates results)	4 / 2	2
%	modulo (remainder)	5 % 4	1
^	exponentiation	2.0 ^ 3.0	8
|/	square root	|/ 25.0	5
||/	cube root	||/ 27.0	3
!	factorial	5 !	120
!!	factorial (prefix operator)	!! 5	120
@	absolute value	@ -5.0	5
&	binary AND	91 & 15	11
|	binary OR	32 | 3	35
#	binary XOR	17 # 5	20
~	binary NOT	~1	-2
<<	binary shift left	1 << 4	16
>>	binary shift right	8 >> 2	2

The “binary” operators are also available for the bit string types `BIT` and `BIT VARYING`, as shown in Table 6.3, “Bit String Binary Operators”. Bit string arguments to `&`, `|`, and `#` must be of equal length. When bit shifting, the original length of the string is preserved, as shown in the table.

Table 6.3. Bit String Binary Operators

Example	Result
B'10001' & B'01101'	00001
B'10001' | B'01101'	11101
B'10001' # B'01101'	11110
~ B'10001'	01110
B'10001' << 3	01000
B'10001' >> 2	00100

Table 6.4, “Mathematical Functions” shows the available mathematical functions. In the table, `dp` indicates `double precision`. Many of these functions are provided in multiple forms with different argument types. Except where noted, any given form of a function returns the same datatype

as its argument. The functions working with `double precision` data are mostly implemented on top of the host system's C library; accuracy and behavior in boundary cases may therefore vary depending on the host system.

Table 6.4. Mathematical Functions

Function	Return Type	Description	Example	Result
`abs(`*x*`)`	(same as *x*)	absolute value	`abs(-17.4)`	17.4
`cbrt(dp)`	`dp`	cube root	`cbrt(27.0)`	3
`ceil(dp` or `numeric)`	(same as input)	smallest integer not less than argument	`ceil(-42.8)`	-42
`degrees(dp)`	`dp`	radians to degrees	`degrees(0.5)`	28.6478897565412
`exp(dp` or `numeric)`	(same as input)	exponential	`exp(1.0)`	2.71828182845905
`floor(dp` or `numeric)`	(same as input)	largest integer not greater than argument	`floor(-42.8)`	-43
`ln(dp` or `numeric)`	(same as input)	natural logarithm	`ln(2.0)`	0.693147180559945
`log(dp` or `numeric)`	(same as input)	base 10 logarithm	`log(100.0)`	2
`log(`*b* `numeric,` *x* `numeric)`	`numeric`	logarithm to base *b*	`log(2.0, 64.0)`	6.0000000000
`mod(`*y*, *x*`)`	(same as argument types)	remainder of *y*/*x*	`mod(9,4)`	1
`pi()`	`dp`	“Pi” constant	`pi()`	3.14159265358979
`pow(`*x* `dp,` *e* `dp)`	`dp`	raise a number to exponent *e*	`pow(9.0, 3.0)`	729
`pow(`*x* `numeric,` *e* `numeric)`	`numeric`	raise a number to exponent *e*	`pow(9.0, 3.0)`	729
`radians(dp)`	`dp`	degrees to radians	`radians(45.0)`	0.785398163397448
`random()`	`dp`	random value between 0.0 and 1.0	`random()`	
`round(dp` or `numeric)`	(same as input)	round to nearest integer	`round(42.4)`	42
`round(`*v* `numeric,` *s* `integer)`	`numeric`	round to *s* decimal places	`round(42.4382, 2)`	42.44
`sign(dp` or `numeric)`	(same as input)	sign of the argument (-1, 0, +1)	`sign(-8.4)`	-1
`sqrt(dp` or `numeric)`	(same as input)	square root	`sqrt(2.0)`	1.4142135623731
`trunc(dp` or `numeric)`	(same as input)	truncate toward zero	`trunc(42.8)`	42
`trunc(`*v* `numeric,` *s* `integer)`	`numeric`	truncate to *s* decimal places	`trunc(42.4382, 2)`	42.43

Finally, Table 6.5, “Trigonometric Functions” shows the available trigonometric functions. All trigonometric functions take arguments and return values of type `double precision`.

Table 6.5. Trigonometric Functions

Function	Description
`acos(`*x*`)`	inverse cosine
`asin(`*x*`)`	inverse sine
`atan(`*x*`)`	inverse tangent
`atan2(`*x*`, `*y*`)`	inverse tangent of *x*/*y*
`cos(`*x*`)`	cosine
`cot(`*x*`)`	cotangent
`sin(`*x*`)`	sine
`tan(`*x*`)`	tangent

6.4. String Functions and Operators

This section describes functions and operators for examining and manipulating string values. Strings in this context include values of all the types `CHARACTER`, `CHARACTER VARYING`, and `TEXT`. Unless otherwise noted, all of the functions listed below work on all of these types, but be wary of potential effects of the automatic padding when using the `CHARACTER` type. Generally, the functions described here also work on data of non-string types by converting that data to a string representation first. Some functions also exist natively for bit-string types.

SQL defines some string functions with a special syntax where certain key words rather than commas are used to separate the arguments. Details are in Table 6.6, “SQL String Functions and Operators”. These functions are also implemented using the regular syntax for function invocation. (See Table 6.7, “Other String Functions”.)

Table 6.6. SQL String Functions and Operators

Function	Return Type	Description	Example	Result
string `||` *string*	`text`	String concatenation	`'Post' || 'greSQL'`	`PostgreSQL`
`bit_length(`*string*`)`	`integer`	Number of bits in string	`bit_length('jose')`	`32`
`char_length(`*string*`)` or `character_length(`*string*`)`	`integer`	Number of characters in string	`char_length('jose')`	`4`
`convert(`*string* using *conversion_name*`)`	`text`	Change encoding using specified conversion name. Conversions can be defined by `CREATE CONVERSION`. Also there are some pre-defined conversion names. See Table 6.8, “Built-in Conversions” for	`convert('PostgreSQL' using iso_8859_1_to_utf_8)`	`'PostgreSQL'` in Unicode (UTF-8) encoding

Function	Return Type	Description	Example	Result
		available conversion names.		
lower(*string*)	text	Convert string to lower case	lower('TOM')	tom
octet_length(*string*)	integer	Number of bytes in string	octet_length('jose')	5
overlay(*string* placing *string* from integer [for integer])	text	Insert substring	overlay('Txxxxas' placing 'hom' from 2 for 4)	Thomas
position(*substring* in *string*)	integer	Location of specified substring	position('om' in 'Thomas')	3
substring(*string* [from integer] [for integer])	text	Extract substring	substring('Thomas' from 2 for 3)	hom
substring(*string* from *pattern*)	text	Extract substring matching POSIX regular expression	substring('Thomas' from '...$')	mas
substring(*string* from *pattern* for *escape*)	text	Extract substring matching SQL regular expression	substring('Thomas' from '%#"o_a#"_' for '#')	oma
trim([leading | trailing | both] [*characters*] from *string*)	text	Remove the longest string containing only the *characters* (a space by default) from the beginning/end/ both ends of the *string*	trim(both 'x' from 'xTomxx')	Tom
upper(*string*)	text	Convert string to upper case	upper('tom')	TOM

Additional string manipulation functions are available and are listed in Table 6.7, “Other String Functions”. Some of them are used internally to implement the SQL-standard string functions listed in Table 6.6, “SQL String Functions and Operators”.

Table 6.7. Other String Functions

Function	Return Type	Description	Example	Result
ascii(text)	integer	ASCII code of the first character of the argument.	ascii('x')	120
btrim(*string* text, *trim* text)	text	Remove (trim) the longest string consisting only of characters in *trim* from the start and end of *string*	btrim('xyxtrimyyx','xy')	trim
chr(integer)	text	Character with the given ASCII code	chr(65)	A

Function	Return Type	Description	Example	Result
convert(*string* text, [*src_encoding* name,] *dest_encoding* name)	text	Convert string to *dest_encoding*. The original encoding is specified by *src_encoding*. If *src_encoding* is omitted, database encoding is assumed.	convert('text_in_unicode', 'UNICODE', 'LATIN1')	text_in_unicode represented in ISO 8859-1
decode(*string* text, *type* text)	bytea	Decode binary data from *string* previously encoded with encode(). Parameter type is same as in encode().	decode('MTIzAAE=', 'base64')	123\000\001
encode(*data* bytea, *type* text)	text	Encode binary data to ASCII-only representation. Supported types are: base64, hex, escape.	encode('123\\000\\001', 'base64')	MTIzAAE=
initcap(text)	text	Convert first letter of each word (whitespace separated) to upper case	initcap('hi thomas')	Hi Thomas
length(*string*)	integer	Length of string	length('jose')	4
lpad(*string* text, *length* integer [, *fill* text])	text	Fill up the *string* to length *length* by prepending the characters *fill* (a space by default). If the *string* is already longer than *length* then it is truncated (on the right).	lpad('hi', 5, 'xy')	xyxhi
ltrim(*string* text, *text* text)	text	Remove the longest string containing only characters from *trim* from the start of the string.	ltrim('zzzytrim', 'xyz')	trim
pg_client_encoding()	name	Current client encoding name.	pg_client_encoding()	SQL_ASCII
quote_ident(*string* text)	text	Return the given string suitably quoted to be	quote_ident('Foo')	"Foo"

Function	Return Type	Description	Example	Result
		used as an identifier in an SQL query string. Quotes are added only if necessary (i.e., if the string contains non-identifier characters or would be case-folded). Embedded quotes are properly doubled.		
quote_literal(*string* text)	text	Return the given string suitably quoted to be used as a literal in an SQL query string. Embedded quotes and backslashes are properly doubled.	quote_literal('O'Reilly')	'O''Reilly'
repeat(text, integer)	text	Repeat text a number of times	repeat('Pg', 4)	PgPgPgPg
replace(*string* text, *from* text, *to* text)	text	Replace all occurrences in *string* of substring *from* with substring *to*	replace('abcdefabcdef', 'cd', 'XX')	abXXefabXXef
rpad(*string* text, *length* integer [, *fill* text])	text	Fill up the *string* to length *length* by appending the characters *fill* (a space by default). If the *string* is already longer than *length* then it is truncated.	rpad('hi', 5, 'xy')	hixyx
rtrim(*string* text, *trim* text)	text	Remove the longest string containing only characters from *trim* from the end of the string.	rtrim('trimxxxx', 'x')	trim
split_part(*string* text, *delimiter* text, *column* integer)	text	Split *string* on *delimiter* returning the resulting (one based) *column* number.	split_part('abc~@~def~@~ghi', '~@~', 2)	def
strpos(*string*, *substring*)	int	Locate specified substring (same as position(*substring*	strpos('high', 'ig')	2

Function	Return Type	Description	Example	Result
		`in string`), but note the reversed argument order)		
`substr(string, from [, count])`	`text`	Extract specified substring (same as `substring(string from from for count)`)	`substr('alphabet', 3, 2)`	`ph`
`to_ascii(text [, encoding])`	`text`	Convert text to ASCII from other encoding [a]	`to_ascii('Karel')`	`Karel`
`to_hex(number integer or bigint)`	`text`	Convert *number* to its equivalent hexadecimal representation	`to_hex(9223372036854775807::bigint)`	`7fffffffffffffff`
`translate(string text, from text, to text)`	`text`	Any character in *string* that matches a character in the *from* set is replaced by the corresponding character in the *to* set.	`translate('12345', '14', 'ax')`	`a23x5`

[a] The `to_ascii` function supports conversion from `LATIN1`, `LATIN2`, and `WIN1250` only.

Table 6.8. Built-in Conversions

Conversion Name [a]	Source Encoding	Destination Encoding
`ascii_to_mic`	`SQL_ASCII`	`MULE_INTERNAL`
`ascii_to_utf_8`	`SQL_ASCII`	`UNICODE`
`big5_to_euc_tw`	`BIG5`	`EUC_TW`
`big5_to_mic`	`BIG5`	`MULE_INTERNAL`
`big5_to_utf_8`	`BIG5`	`UNICODE`
`euc_cn_to_mic`	`EUC_CN`	`MULE_INTERNAL`
`euc_cn_to_utf_8`	`EUC_CN`	`UNICODE`
`euc_jp_to_mic`	`EUC_JP`	`MULE_INTERNAL`
`euc_jp_to_sjis`	`EUC_JP`	`SJIS`
`euc_jp_to_utf_8`	`EUC_JP`	`UNICODE`
`euc_kr_to_mic`	`EUC_KR`	`MULE_INTERNAL`
`euc_kr_to_utf_8`	`EUC_KR`	`UNICODE`
`euc_tw_to_big5`	`EUC_TW`	`BIG5`
`euc_tw_to_mic`	`EUC_TW`	`MULE_INTERNAL`
`euc_tw_to_utf_8`	`EUC_TW`	`UNICODE`
`gb18030_to_utf_8`	`GB18030`	`UNICODE`
`gbk_to_utf_8`	`GBK`	`UNICODE`
`iso_8859_10_to_utf_8`	`LATIN6`	`UNICODE`
`iso_8859_13_to_utf_8`	`LATIN7`	`UNICODE`

Conversion Name [a]	Source Encoding	Destination Encoding
iso_8859_14_to_utf_8	LATIN8	UNICODE
iso_8859_15_to_utf_8	LATIN9	UNICODE
iso_8859_16_to_utf_8	LATIN10	UNICODE
iso_8859_1_to_mic	LATIN1	MULE_INTERNAL
iso_8859_1_to_utf_8	LATIN1	UNICODE
iso_8859_2_to_mic	LATIN2	MULE_INTERNAL
iso_8859_2_to_utf_8	LATIN2	UNICODE
iso_8859_2_to_windows_1250	LATIN2	WIN1250
iso_8859_3_to_mic	LATIN3	MULE_INTERNAL
iso_8859_3_to_utf_8	LATIN3	UNICODE
iso_8859_4_to_mic	LATIN4	MULE_INTERNAL
iso_8859_4_to_utf_8	LATIN4	UNICODE
iso_8859_5_to_koi8_r	ISO_8859_5	KOI8
iso_8859_5_to_mic	ISO_8859_5	MULE_INTERNAL
iso_8859_5_to_utf_8	ISO_8859_5	UNICODE
iso_8859_5_to_windows_1251	ISO_8859_5	WIN
iso_8859_5_to_windows_866	ISO_8859_5	ALT
iso_8859_6_to_utf_8	ISO_8859_6	UNICODE
iso_8859_7_to_utf_8	ISO_8859_7	UNICODE
iso_8859_8_to_utf_8	ISO_8859_8	UNICODE
iso_8859_9_to_utf_8	LATIN5	UNICODE
johab_to_utf_8	JOHAB	UNICODE
koi8_r_to_iso_8859_5	KOI8	ISO_8859_5
koi8_r_to_mic	KOI8	MULE_INTERNAL
koi8_r_to_utf_8	KOI8	UNICODE
koi8_r_to_windows_1251	KOI8	WIN
koi8_r_to_windows_866	KOI8	ALT
mic_to_ascii	MULE_INTERNAL	SQL_ASCII
mic_to_big5	MULE_INTERNAL	BIG5
mic_to_euc_cn	MULE_INTERNAL	EUC_CN
mic_to_euc_jp	MULE_INTERNAL	EUC_JP
mic_to_euc_kr	MULE_INTERNAL	EUC_KR
mic_to_euc_tw	MULE_INTERNAL	EUC_TW
mic_to_iso_8859_1	MULE_INTERNAL	LATIN1
mic_to_iso_8859_2	MULE_INTERNAL	LATIN2
mic_to_iso_8859_3	MULE_INTERNAL	LATIN3
mic_to_iso_8859_4	MULE_INTERNAL	LATIN4
mic_to_iso_8859_5	MULE_INTERNAL	ISO_8859_5
mic_to_koi8_r	MULE_INTERNAL	KOI8
mic_to_sjis	MULE_INTERNAL	SJIS
mic_to_windows_1250	MULE_INTERNAL	WIN1250

Conversion Name [a]	Source Encoding	Destination Encoding
mic_to_windows_1251	MULE_INTERNAL	WIN
mic_to_windows_866	MULE_INTERNAL	ALT
sjis_to_euc_jp	SJIS	EUC_JP
sjis_to_mic	SJIS	MULE_INTERNAL
sjis_to_utf_8	SJIS	UNICODE
tcvn_to_utf_8	TCVN	UNICODE
uhc_to_utf_8	UHC	UNICODE
utf_8_to_ascii	UNICODE	SQL_ASCII
utf_8_to_big5	UNICODE	BIG5
utf_8_to_euc_cn	UNICODE	EUC_CN
utf_8_to_euc_jp	UNICODE	EUC_JP
utf_8_to_euc_kr	UNICODE	EUC_KR
utf_8_to_euc_tw	UNICODE	EUC_TW
utf_8_to_gb18030	UNICODE	GB18030
utf_8_to_gbk	UNICODE	GBK
utf_8_to_iso_8859_1	UNICODE	LATIN1
utf_8_to_iso_8859_10	UNICODE	LATIN6
utf_8_to_iso_8859_13	UNICODE	LATIN7
utf_8_to_iso_8859_14	UNICODE	LATIN8
utf_8_to_iso_8859_15	UNICODE	LATIN9
utf_8_to_iso_8859_16	UNICODE	LATIN10
utf_8_to_iso_8859_2	UNICODE	LATIN2
utf_8_to_iso_8859_3	UNICODE	LATIN3
utf_8_to_iso_8859_4	UNICODE	LATIN4
utf_8_to_iso_8859_5	UNICODE	ISO_8859_5
utf_8_to_iso_8859_6	UNICODE	ISO_8859_6
utf_8_to_iso_8859_7	UNICODE	ISO_8859_7
utf_8_to_iso_8859_8	UNICODE	ISO_8859_8
utf_8_to_iso_8859_9	UNICODE	LATIN5
utf_8_to_johab	UNICODE	JOHAB
utf_8_to_koi8_r	UNICODE	KOI8
utf_8_to_sjis	UNICODE	SJIS
utf_8_to_tcvn	UNICODE	TCVN
utf_8_to_uhc	UNICODE	UHC
utf_8_to_windows_1250	UNICODE	WIN1250
utf_8_to_windows_1251	UNICODE	WIN
utf_8_to_windows_1256	UNICODE	WIN1256
utf_8_to_windows_866	UNICODE	ALT
utf_8_to_windows_874	UNICODE	WIN874
windows_1250_to_iso_8859_2	WIN1250	LATIN2
windows_1250_to_mic	WIN1250	MULE_INTERNAL

Conversion Name [a]	Source Encoding	Destination Encoding
windows_1250_to_utf_8	WIN1250	UNICODE
windows_1251_to_iso_8859_5	WIN	ISO_8859_5
windows_1251_to_koi8_r	WIN	KOI8
windows_1251_to_mic	WIN	MULE_INTERNAL
windows_1251_to_utf_8	WIN	UNICODE
windows_1251_to_windows_866	WIN	ALT
windows_1256_to_utf_8	WIN1256	UNICODE
windows_866_to_iso_8859_5	ALT	ISO_8859_5
windows_866_to_koi8_r	ALT	KOI8
windows_866_to_mic	ALT	MULE_INTERNAL
windows_866_to_utf_8	ALT	UNICODE
windows_866_to_windows_1251	ALT	WIN
windows_874_to_utf_8	WIN874	UNICODE

[a] The conversion names follow a standard naming scheme: The official name of the source encoding with all non-alphanumeric characters replaced by underscores followed by `_to_` followed by the equally processed destination encoding name. Therefore the names might deviate from the customary encoding names.

6.5. Binary String Functions and Operators

This section describes functions and operators for examining and manipulating binary string values. Strings in this context mean values of the type `BYTEA`.

SQL defines some string functions with a special syntax where certain key words rather than commas are used to separate the arguments. Details are in Table 6.9, “SQL Binary String Functions and Operators”. Some functions are also implemented using the regular syntax for function invocation. (See Table 6.10, “Other Binary String Functions”.)

Table 6.9. SQL Binary String Functions and Operators

Function	Return Type	Description	Example	Result
string `||` *string*	bytea	String concatenation	`'\\\\Post'::bytea || '\047greSQL\000'::bytea`	`\\Post'greSQL\000`
`octet_length(`*string*`)`	integer	Number of bytes in binary string	`octet_length('jo\000se'::bytea)`	5
`position(`*substring* `in` *string*`)`	integer	Location of specified substring	`position('om'::bytea in 'Th\000omas'::bytea)`	3
`substring(`*string* [from integer] [for integer]`)`	bytea	Extract substring	`substring('Th\000omas'::bytea from 2 for 3)`	`h\000o`
`trim(`[both] *characters* from *string*`)`	bytea	Remove the longest string containing only the *characters*	`trim('\000'::bytea from '\`	Tom

Function	Return Type	Description	Example	Result
		from the beginning/end/ both ends of the *string*	`\000Tom\ \000'::bytea)`	
`get_byte(`*string*, *offset*`)`	integer	Extract byte from string.	`get_byte('Th\ \000omas'::bytea, 4)`	109
`set_byte(`*string*, *offset*, *newvalue*`)`	bytea	Set byte in string.	`set_byte('Th\ \000omas'::bytea, 4, 64)`	Th\000o@as
`get_bit(`*string*, *offset*`)`	integer	Extract bit from string.	`get_bit('Th\ \000omas'::bytea, 45)`	1
`set_bit(`*string*, *offset*, *newvalue*`)`	bytea	Set bit in string.	`set_bit('Th\ \000omas'::bytea, 45, 0)`	Th\000omAs

Additional binary string manipulation functions are available and are listed in Table 6.10, “Other Binary String Functions”. Some of them are used internally to implement the SQL-standard string functions listed in Table 6.9, “SQL Binary String Functions and Operators”.

Table 6.10. Other Binary String Functions

Function	Return Type	Description	Example	Result
`btrim(`*string* bytea, *trim* bytea`)`	bytea	Remove (trim) the longest string consisting only of characters in *trim* from the start and end of *string*.	`btrim('\ \000trim\ \000'::bytea, '\ \000'::bytea)`	trim
`length(`*string*`)`	integer	Length of binary string	`length('jo\ \000se'::bytea)`	5
`encode(`*string* bytea, *type* text`)`	text	Encode binary string to ASCII-only representation. Supported types are: base64, hex, escape.	`encode('123\ \000456'::bytea, 'escape')`	123\000456
`decode(`*string* text, *type* text`)`	bytea	Decode binary string from *string* previously encoded with `encode()`. Parameter type is same as in `encode()`.	`decode('123\ \000456', 'escape')`	123\000456

6.6. Pattern Matching

There are three separate approaches to pattern matching provided by PostgreSQL: the traditional SQL `LIKE` operator, the more recent SQL99 `SIMILAR TO` operator, and POSIX-style regular expressions. Additionally, a pattern matching function, `SUBSTRING`, is available, using either SQL99-style or POSIX-style regular expressions.

Tip

If you have pattern matching needs that go beyond this, consider writing a user-defined function in Perl or Tcl.

6.6.1. `LIKE`

string `LIKE` *pattern* `[ESCAPE` *escape-character*`]`
string `NOT LIKE` *pattern* `[ESCAPE` *escape-character*`]`

Every *pattern* defines a set of strings. The `LIKE` expression returns true if the *string* is contained in the set of strings represented by *pattern*. (As expected, the `NOT LIKE` expression returns false if `LIKE` returns true, and vice versa. An equivalent expression is `NOT (`*string* `LIKE` *pattern*`)`.)

If *pattern* does not contain percent signs or underscore, then the pattern only represents the string itself; in that case `LIKE` acts like the equals operator. An underscore (`_`) in *pattern* stands for (matches) any single character; a percent sign (`%`) matches any string of zero or more characters.

Some examples:

```
'abc' LIKE 'abc'    true
'abc' LIKE 'a%'     true
'abc' LIKE '_b_'    true
'abc' LIKE 'c'      false
```

`LIKE` pattern matches always cover the entire string. To match a pattern anywhere within a string, the pattern must therefore start and end with a percent sign.

To match a literal underscore or percent sign without matching other characters, the respective character in *pattern* must be preceded by the escape character. The default escape character is the backslash but a different one may be selected by using the `ESCAPE` clause. To match the escape character itself, write two escape characters.

Note that the backslash already has a special meaning in string literals, so to write a pattern constant that contains a backslash you must write two backslashes in the query. Thus, writing a pattern that actually matches a literal backslash means writing four backslashes in the query. You can avoid this by selecting a different escape character with `ESCAPE`; then backslash is not special to `LIKE` anymore. (But it is still special to the string literal parser, so you still need two of them.)

It's also possible to select no escape character by writing `ESCAPE ''`. This effectively disables the escape mechanism, which makes it impossible to turn off the special meaning of underscore and percent signs in the pattern.

The keyword `ILIKE` can be used instead of `LIKE` to make the match case insensitive according to the active locale. This is not in the SQL standard but is a PostgreSQL extension.

The operator `~~` is equivalent to `LIKE`, and `~~*` corresponds to `ILIKE`. There are also `!~~` and `!~~*` operators that represent `NOT LIKE` and `NOT ILIKE`. All of these operators are PostgreSQL-specific.

6.6.2. `SIMILAR TO` and SQL99 Regular Expressions

string `SIMILAR TO` *pattern* `[ESCAPE` *escape-character*`]`

string NOT SIMILAR TO *pattern* [ESCAPE *escape-character*]

The SIMILAR TO operator returns true or false depending on whether its pattern matches the given string. It is much like LIKE, except that it interprets the pattern using SQL99's definition of a regular expression. SQL99's regular expressions are a curious cross between LIKE notation and common regular expression notation.

Like LIKE, the SIMILAR TO operator succeeds only if its pattern matches the entire string; this is unlike common regular expression practice, wherein the pattern may match any part of the string. Also like LIKE, SIMILAR TO uses % and _ as wildcard characters denoting any string and any single character, respectively (these are comparable to .* and . in POSIX regular expressions).

In addition to these facilities borrowed from LIKE, SIMILAR TO supports these pattern-matching metacharacters borrowed from POSIX regular expressions:

- | denotes alternation (either of two alternatives).
- * denotes repetition of the previous item zero or more times.
- + denotes repetition of the previous item one or more times.
- Parentheses () may be used to group items into a single logical item.
- A bracket expression [...] specifies a character class, just as in POSIX regular expressions.

Notice that bounded repetition (? and {...}) are not provided, though they exist in POSIX. Also, dot (.) is not a metacharacter.

As with LIKE, a backslash disables the special meaning of any of these metacharacters; or a different escape character can be specified with ESCAPE.

Some examples:

```
'abc' SIMILAR TO 'abc'      true
'abc' SIMILAR TO 'a'        false
'abc' SIMILAR TO '%(b|d)%'  true
'abc' SIMILAR TO '(b|c)%'   false
```

The SUBSTRING function with three parameters, SUBSTRING(*string* FROM *pattern* FOR *escape*), provides extraction of a substring that matches a SQL99 regular expression pattern. As with SIMILAR TO, the specified pattern must match to the entire data string, else the function fails and returns null. To indicate the part of the pattern that should be returned on success, SQL99 specifies that the pattern must contain two occurrences of the escape character followed by double quote ("). The text matching the portion of the pattern between these markers is returned.

Some examples:

```
SUBSTRING('foobar' FROM '%#"o_b#"%' FOR '#')    oob
SUBSTRING('foobar' FROM '#"o_b#"%' FOR '#')     NULL
```

6.6.3. POSIX Regular Expressions

Table 6.11, “Regular Expression Match Operators” lists the available operators for pattern matching using POSIX regular expressions.

Table 6.11. Regular Expression Match Operators

Operator	Description	Example
~	Matches regular expression, case sensitive	'thomas' ~ '.*thomas.*'

Operator	Description	Example
~*	Matches regular expression, case insensitive	'thomas' ~* '.*Thomas.*'
!~	Does not match regular expression, case sensitive	'thomas' !~ '.*Thomas.*'
!~*	Does not match regular expression, case insensitive	'thomas' !~* '.*vadim.*'

POSIX regular expressions provide a more powerful means for pattern matching than the LIKE and SIMILAR TO operators. Many Unix tools such as egrep, sed, or awk use a pattern matching language that is similar to the one described here.

A regular expression is a character sequence that is an abbreviated definition of a set of strings (a *regular set*). A string is said to match a regular expression if it is a member of the regular set described by the regular expression. As with LIKE, pattern characters match string characters exactly unless they are special characters in the regular expression language --- but regular expressions use different special characters than LIKE does. Unlike LIKE patterns, a regular expression is allowed to match anywhere within a string, unless the regular expression is explicitly anchored to the beginning or end of the string.

Some examples:

```
'abc' ~ 'abc'    true
'abc' ~ '^a'     true
'abc' ~ '(b|d)'  true
'abc' ~ '^(b|c)' false
```

The SUBSTRING function with two parameters, SUBSTRING(*string* FROM *pattern*), provides extraction of a substring that matches a POSIX regular expression pattern. It returns null if there is no match, otherwise the portion of the text that matched the pattern. But if the pattern contains any parentheses, the portion of the text that matched the first parenthesized subexpression (the one whose left parenthesis comes first) is returned. You can always put parentheses around the whole expression if you want to use parentheses within it without triggering this exception.

Some examples:

```
SUBSTRING('foobar' FROM 'o.b')     oob
SUBSTRING('foobar' FROM 'o(.)b')   o
```

Regular expressions (REs), as defined in POSIX 1003.2, come in two forms: modern REs (roughly those of egrep; 1003.2 calls these “extended” REs) and obsolete REs (roughly those of ed; 1003.2 “basic” REs). PostgreSQL implements the modern form.

A (modern) RE is one or more non-empty *branches*, separated by |. It matches anything that matches one of the branches.

A branch is one or more *pieces*, concatenated. It matches a match for the first, followed by a match for the second, etc.

A piece is an *atom* possibly followed by a single *, +, ?, or *bound*. An atom followed by * matches a sequence of 0 or more matches of the atom. An atom followed by + matches a sequence of 1 or more matches of the atom. An atom followed by ? matches a sequence of 0 or 1 matches of the atom.

A *bound* is { followed by an unsigned decimal integer, possibly followed by , possibly followed by another unsigned decimal integer, always followed by }. The integers must lie between 0 and RE_DUP_MAX (255) inclusive, and if there are two of them, the first may not exceed the second. An atom followed by a bound containing one integer *i* and no comma matches a sequence of exactly *i* matches of the atom. An atom followed by a bound containing one integer *i* and a comma matches a sequence of *i* or more matches of the atom. An atom followed by a bound containing two integers *i* and *j* matches a sequence of *i* through *j* (inclusive) matches of the atom.

Note

A repetition operator (`?`, `*`, `+`, or bounds) cannot follow another repetition operator. A repetition operator cannot begin an expression or subexpression or follow `^` or `|`.

An *atom* is a regular expression enclosed in `()` (matching a match for the regular expression), an empty set of `()` (matching the null string), a *bracket expression* (see below), `.` (matching any single character), `^` (matching the null string at the beginning of the input string), `$` (matching the null string at the end of the input string), a `\` followed by one of the characters `^.[$()|*+?{\` (matching that character taken as an ordinary character), a `\` followed by any other character (matching that character taken as an ordinary character, as if the `\` had not been present), or a single character with no other significance (matching that character). A `{` followed by a character other than a digit is an ordinary character, not the beginning of a bound. It is illegal to end an RE with `\`.

Note that the backslash (`\`) already has a special meaning in string literals, so to write a pattern constant that contains a backslash you must write two backslashes in the query.

A *bracket expression* is a list of characters enclosed in `[]`. It normally matches any single character from the list (but see below). If the list begins with `^`, it matches any single character (but see below) not from the rest of the list. If two characters in the list are separated by `-`, this is shorthand for the full range of characters between those two (inclusive) in the collating sequence, e.g. `[0-9]` in ASCII matches any decimal digit. It is illegal for two ranges to share an endpoint, e.g. `a-c-e`. Ranges are very collating-sequence-dependent, and portable programs should avoid relying on them.

To include a literal `]` in the list, make it the first character (following a possible `^`). To include a literal `-`, make it the first or last character, or the second endpoint of a range. To use a literal `-` as the first endpoint of a range, enclose it in `[.` and `.]` to make it a collating element (see below). With the exception of these and some combinations using `[` (see next paragraphs), all other special characters, including `\`, lose their special significance within a bracket expression.

Within a bracket expression, a collating element (a character, a multiple-character sequence that collates as if it were a single character, or a collating-sequence name for either) enclosed in `[.` and `.]` stands for the sequence of characters of that collating element. The sequence is a single element of the bracket expression's list. A bracket expression containing a multiple-character collating element can thus match more than one character, e.g. if the collating sequence includes a `ch` collating element, then the RE `[[.ch.]]*c` matches the first five characters of `chchcc`.

Within a bracket expression, a collating element enclosed in `[=` and `=]` is an equivalence class, standing for the sequences of characters of all collating elements equivalent to that one, including itself. (If there are no other equivalent collating elements, the treatment is as if the enclosing delimiters were `[.` and `.]`.) For example, if `o` and `^` are the members of an equivalence class, then `[[=o=]]`, `[[=^=]]`, and `[o^]` are all synonymous. An equivalence class may not be an endpoint of a range.

Within a bracket expression, the name of a character class enclosed in `[:` and `:]` stands for the list of all characters belonging to that class. Standard character class names are: `alnum`, `alpha`, `blank`, `cntrl`, `digit`, `graph`, `lower`, `print`, `punct`, `space`, `upper`, `xdigit`. These stand for the character classes defined in ctype. A locale may provide others. A character class may not be used as an endpoint of a range.

There are two special cases of bracket expressions: the bracket expressions `[[:<:]]` and `[[:>:]]` match the null string at the beginning and end of a word respectively. A word is defined as a sequence of word characters which is neither preceded nor followed by word characters. A word character is an alnum character (as defined by ctype) or an underscore. This is an extension, compatible with but not specified by POSIX 1003.2, and should be used with caution in software intended to be portable to other systems.

In the event that an RE could match more than one substring of a given string, the RE matches the one starting earliest in the string. If the RE could match more than one substring starting at that point, it matches the longest. Subexpressions also match the longest possible substrings, subject to the constraint that the whole match be as long as possible, with subexpressions starting earlier in the RE

taking priority over ones starting later. Note that higher-level subexpressions thus take priority over their lower-level component subexpressions.

Match lengths are measured in characters, not collating elements. A null string is considered longer than no match at all. For example, `bb*` matches the three middle characters of `abbbc`, `(wee|week)(knights|nights)` matches all ten characters of `weeknights`, when `(.*).*` is matched against `abc` the parenthesized subexpression matches all three characters, and when `(a*)*` is matched against `bc` both the whole RE and the parenthesized subexpression match the null string.

If case-independent matching is specified, the effect is much as if all case distinctions had vanished from the alphabet. When an alphabetic that exists in multiple cases appears as an ordinary character outside a bracket expression, it is effectively transformed into a bracket expression containing both cases, e.g. `x` becomes `[xX]`. When it appears inside a bracket expression, all case counterparts of it are added to the bracket expression, so that (e.g.) `[x]` becomes `[xX]` and `[^x]` becomes `[^xX]`.

There is no particular limit on the length of REs, except insofar as memory is limited. Memory usage is approximately linear in RE size, and largely insensitive to RE complexity, except for bounded repetitions. Bounded repetitions are implemented by macro expansion, which is costly in time and space if counts are large or bounded repetitions are nested. An RE like, say, `((((a{1,100}){1,100}){1,100}){1,100}){1,100}` will (eventually) run almost any existing machine out of swap space. [1]

6.7. Data Type Formatting Functions

The PostgreSQL formatting functions provide a powerful set of tools for converting various data types (date/time, integer, floating point, numeric) to formatted strings and for converting from formatted strings to specific data types. Table 6.12, “Formatting Functions” lists them. These functions all follow a common calling convention: the first argument is the value to be formatted and the second argument is a template that defines the output or input format.

Table 6.12. Formatting Functions

Function	Returns	Description	Example
`to_char(timestamp, text)`	`text`	convert time stamp to string	`to_char(timestamp 'now','HH12:MI:SS')`
`to_char(interval, text)`	`text`	convert interval to string	`to_char(interval '15h 2m 12s','HH24:MI:SS')`
`to_char(int, text)`	`text`	convert integer to string	`to_char(125, '999')`
`to_char(double precision, text)`	`text`	convert real/double precision to string	`to_char(125.8, '999D9')`
`to_char(numeric, text)`	`text`	convert numeric to string	`to_char(numeric '-125.8', '999D99S')`
`to_date(text, text)`	`date`	convert string to date	`to_date('05 Dec 2000', 'DD Mon YYYY')`
`to_timestamp(text, text)`	`timestamp`	convert string to time stamp	`to_timestamp('05 Dec 2000', 'DD Mon YYYY')`
`to_number(text, text)`	`numeric`	convert string to numeric	`to_number('12,454.8-', '99G999D9S')`

[1] This was written in 1994, mind you. The numbers have probably changed, but the problem persists.

In an output template string, there are certain patterns that are recognized and replaced with appropriately-formatted data from the value to be formatted. Any text that is not a template pattern is simply copied verbatim. Similarly, in an input template string, template patterns identify the parts of the input data string to be looked at and the values to be found there.

Table 6.13, “Template patterns for date/time conversions” shows the template patterns available for formatting date and time values.

Table 6.13. Template patterns for date/time conversions

Pattern	Description
HH	hour of day (01-12)
HH12	hour of day (01-12)
HH24	hour of day (00-23)
MI	minute (00-59)
SS	second (00-59)
MS	millisecond (000-999)
US	microsecond (000000-999999)
SSSS	seconds past midnight (0-86399)
AM or A.M. or PM or P.M.	meridian indicator (upper case)
am or a.m. or pm or p.m.	meridian indicator (lower case)
Y,YYY	year (4 and more digits) with comma
YYYY	year (4 and more digits)
YYY	last 3 digits of year
YY	last 2 digits of year
Y	last digit of year
BC or B.C. or AD or A.D.	era indicator (upper case)
bc or b.c. or ad or a.d.	era indicator (lower case)
MONTH	full upper case month name (blank-padded to 9 chars)
Month	full mixed case month name (blank-padded to 9 chars)
month	full lower case month name (blank-padded to 9 chars)
MON	abbreviated upper case month name (3 chars)
Mon	abbreviated mixed case month name (3 chars)
mon	abbreviated lower case month name (3 chars)
MM	month number (01-12)
DAY	full upper case day name (blank-padded to 9 chars)
Day	full mixed case day name (blank-padded to 9 chars)
day	full lower case day name (blank-padded to 9 chars)
DY	abbreviated upper case day name (3 chars)
Dy	abbreviated mixed case day name (3 chars)
dy	abbreviated lower case day name (3 chars)

Pattern	Description
DDD	day of year (001-366)
DD	day of month (01-31)
D	day of week (1-7; SUN=1)
W	week of month (1-5) where first week start on the first day of the month
WW	week number of year (1-53) where first week start on the first day of the year
IW	ISO week number of year (The first Thursday of the new year is in week 1.)
CC	century (2 digits)
J	Julian Day (days since January 1, 4712 BC)
Q	quarter
RM	month in Roman Numerals (I-XII; I=January) - upper case
rm	month in Roman Numerals (I-XII; I=January) - lower case
TZ	time-zone name - upper case
tz	time-zone name - lower case

Certain modifiers may be applied to any template pattern to alter its behavior. For example, "FMMonth" is the "Month" pattern with the "FM" prefix. Table 6.14, "Template pattern modifiers for date/time conversions" shows the modifier patterns for date/time formatting.

Table 6.14. Template pattern modifiers for date/time conversions

Modifier	Description	Example
FM prefix	fill mode (suppress padding blanks and zeroes)	FMMonth
TH suffix	add upper-case ordinal number suffix	DDTH
th suffix	add lower-case ordinal number suffix	DDth
FX prefix	fixed format global option (see usage notes)	FX Month DD Day
SP suffix	spell mode (not yet implemented)	DDSP

Usage notes for the date/time formatting:

- FM suppresses leading zeroes and trailing blanks that would otherwise be added to make the output of a pattern be fixed-width.
- to_timestamp and to_date skip multiple blank spaces in the input string if the FX option is not used. FX must be specified as the first item in the template; for example to_timestamp('2000 JUN','YYYY MON') is right, but to_timestamp('2000 JUN','FXYYYY MON') returns an error, because to_timestamp expects one blank space only.
- If a backslash ("\") is desired in a string constant, a double backslash ("\\") must be entered; for example '\\HH\\MI\\SS'. This is true for any string constant in PostgreSQL.
- Ordinary text is allowed in to_char templates and will be output literally. You can put a substring in double quotes to force it to be interpreted as literal text even if it contains pattern keywords. For

example, in `'"Hello Year "YYYY'`, the `YYYY` will be replaced by the year data, but the single `Y` in "Year" will not be.

- If you want to have a double quote in the output you must precede it with a backslash, for example `'\\"YYYY Month\\"'`.

- `YYYY` conversion from string to `timestamp` or `date` is restricted if you use a year with more than 4 digits. You must use some non-digit character or template after `YYYY`, otherwise the year is always interpreted as 4 digits. For example (with year 20000): `to_date('200001131', 'YYYYMMDD')` will be interpreted as a 4-digit year; better is to use a non-digit separator after the year, like `to_date('20000-1131', 'YYYY-MMDD')` or `to_date('20000Nov31', 'YYYYMonDD')`.

- Millisecond `MS` and microsecond `US` values in a conversion from string to time stamp are used as part of the seconds after the decimal point. For example `to_timestamp('12:3', 'SS:MS')` is not 3 milliseconds, but 300, because the conversion counts it as 12 + 0.3. This means for the format `SS:MS`, the input values `12:3`, `12:30`, and `12:300` specify the same number of milliseconds. To get three milliseconds, one must use `12:003`, which the conversion counts as 12 + 0.003 = 12.003 seconds.

  Here is a more complex example: `to_timestamp('15:12:02.020.001230','HH:MI:SS.MS.US')` is 15 hours, 12 minutes, and 2 seconds + 20 milliseconds + 1230 microseconds = 2.021230 seconds.

Table 6.15, "Template patterns for numeric conversions" shows the template patterns available for formatting numeric values.

Table 6.15. Template patterns for numeric conversions

Pattern	Description
`9`	value with the specified number of digits
`0`	value with leading zeros
`.` (period)	decimal point
`,` (comma)	group (thousand) separator
`PR`	negative value in angle brackets
`S`	negative value with minus sign (uses locale)
`L`	currency symbol (uses locale)
`D`	decimal point (uses locale)
`G`	group separator (uses locale)
`MI`	minus sign in specified position (if number < 0)
`PL`	plus sign in specified position (if number > 0)
`SG`	plus/minus sign in specified position
`RN`	roman numeral (input between 1 and 3999)
`TH` or `th`	convert to ordinal number
`V`	shift *n* digits (see notes)
`EEEE`	scientific notation (not implemented yet)

Usage notes for the numeric formatting:

- A sign formatted using `SG`, `PL`, or `MI` is not an anchor in the number; for example, `to_char(-12, 'S9999')` produces `' -12'`, but `to_char(-12, 'MI9999')` produces `'- 12'`. The Oracle implementation does not allow the use of `MI` ahead of `9`, but rather requires that `9` precede `MI`.

- `9` specifies a value with the same number of digits as there are `9`s. If a digit is not available it outputs a space.
- `TH` does not convert values less than zero and does not convert decimal numbers.
- `PL`, `SG`, and `TH` are PostgreSQL extensions.
- `V` effectively multiplies the input values by `10^n`, where *n* is the number of digits following `V`. `to_char` does not support the use of `V` combined with a decimal point. (E.g., `99.9V99` is not allowed.)

Table 6.16, "`to_char` Examples" shows some examples of the use of the `to_char` function.

Table 6.16. `to_char` Examples

Input	Output
`to_char(now(),'Day, DD HH12:MI:SS')`	`'Tuesday , 06 05:39:18'`
`to_char(now(),'FMDay, FMDD HH12:MI:SS')`	`'Tuesday, 6 05:39:18'`
`to_char(-0.1,'99.99')`	`' -.10'`
`to_char(-0.1,'FM9.99')`	`'-.1'`
`to_char(0.1,'0.9')`	`' 0.1'`
`to_char(12,'9990999.9')`	`' 0012.0'`
`to_char(12,'FM9990999.9')`	`'0012'`
`to_char(485,'999')`	`' 485'`
`to_char(-485,'999')`	`'-485'`
`to_char(485,'9 9 9')`	`' 4 8 5'`
`to_char(1485,'9,999')`	`' 1,485'`
`to_char(1485,'9G999')`	`' 1 485'`
`to_char(148.5,'999.999')`	`' 148.500'`
`to_char(148.5,'999D999')`	`' 148,500'`
`to_char(3148.5,'9G999D999')`	`' 3 148,500'`
`to_char(-485,'999S')`	`'485-'`
`to_char(-485,'999MI')`	`'485-'`
`to_char(485,'999MI')`	`'485'`
`to_char(485,'PL999')`	`'+485'`
`to_char(485,'SG999')`	`'+485'`
`to_char(-485,'SG999')`	`'-485'`
`to_char(-485,'9SG99')`	`'4-85'`
`to_char(-485,'999PR')`	`'<485>'`
`to_char(485,'L999')`	`'DM 485`
`to_char(485,'RN')`	`' CDLXXXV'`
`to_char(485,'FMRN')`	`'CDLXXXV'`
`to_char(5.2,'FMRN')`	`V`
`to_char(482,'999th')`	`' 482nd'`
`to_char(485, '"Good number:"999')`	`'Good number: 485'`

Input	Output
`to_char(485.8,'"Pre:"999" Post:" .999')`	`'Pre: 485 Post: .800'`
`to_char(12,'99V999')`	`' 12000'`
`to_char(12.4,'99V999')`	`' 12400'`
`to_char(12.45, '99V9')`	`' 125'`

6.8. Date/Time Functions and Operators

Table 6.18, “Date/Time Functions” shows the available functions for date/time value processing, with details appearing in the following subsections. Table 6.17, “Date/Time Operators” illustrates the behaviors of the basic arithmetic operators (+, *, etc.). For formatting functions, refer to Section 6.7, “Data Type Formatting Functions”. You should be familiar with the background information on date/time data types (see Section 5.5, “Date/Time Types”).

All the functions and operators described below that take time or timestamp inputs actually come in two variants: one that takes time or timestamp with time zone, and one that takes time or timestamp without time zone. For brevity, these variants are not shown separately.

Table 6.17. Date/Time Operators

Name	Example	Result
+	`timestamp '2001-09-28 01:00' + interval '23 hours'`	`timestamp '2001-09-29 00:00'`
+	`date '2001-09-28' + interval '1 hour'`	`timestamp '2001-09-28 01:00'`
+	`time '01:00' + interval '3 hours'`	`time '04:00'`
-	`timestamp '2001-09-28 23:00' - interval '23 hours'`	`timestamp '2001-09-28'`
-	`date '2001-09-28' - interval '1 hour'`	`timestamp '2001-09-27 23:00'`
-	`time '05:00' - interval '2 hours'`	`time '03:00'`
-	`interval '2 hours' - time '05:00'`	`time '03:00:00'`
*	`interval '1 hour' * int '3'`	`interval '03:00'`
/	`interval '1 hour' / int '3'`	`interval '00:20'`

Table 6.18. Date/Time Functions

Name	Return Type	Description	Example	Result
`age(timestamp)`	`interval`	Subtract from today	`age(timestamp '1957-06-13')`	`43 years 8 mons 3 days`
`age(timestamp, timestamp)`	`interval`	Subtract arguments	`age('2001-04-10' timestamp '1957-06-13')`	`43 years 9 mons 27 days`

Name	Return Type	Description	Example	Result
current_date	date	Today's date; see Section 6.8.4, “Current Date/Time”		
current_time	time with time zone	Time of day; see Section 6.8.4, “Current Date/Time”		
current_timestamp	timestamp with time zone	Date and time; see Section 6.8.4, “Current Date/Time”		
date_part(text, timestamp)	double precision	Get subfield (equivalent to extract); see also below	date_part('hour', timestamp '2001-02-16 20:38:40')	20
date_part(text, interval)	double precision	Get subfield (equivalent to extract); see also below	date_part('month', interval '2 years 3 months')	3
date_trunc(text, timestamp)	timestamp	Truncate to specified precision; see also Section 6.8.2, “date_trunc”	date_trunc('hour', timestamp '2001-02-16 20:38:40')	2001-02-16 20:00:00+00
extract(*field* from timestamp)	double precision	Get subfield; see also Section 6.8.1, “EXTRACT, date_part”	extract(hour from timestamp '2001-02-16 20:38:40')	20
extract(*field* from interval)	double precision	Get subfield; see also Section 6.8.1, “EXTRACT, date_part”	extract(month from interval '2 years 3 months')	3
isfinite(timestamp)	boolean	Test for finite time stamp (neither invalid nor infinity)	isfinite(timestamp '2001-02-16 21:28:30')	true
isfinite(interval)	boolean	Test for finite interval	isfinite(interval '4 hours')	true
localtime	time	Time of day; see Section 6.8.4, “Current Date/Time”		
localtimestamp	timestamp	Date and time; see Section 6.8.4, “Current Date/Time”		
now()	timestamp with time zone	Current date and time (equivalent to current_timestamp); see Section 6.8.4,		

Name	Return Type	Description	Example	Result
		"Current Date/Time"		
timeofday()	text	Current date and time; see Section 6.8.4, "Current Date/Time"	timeofday()	Wed Feb 21 17:01:13.000126 2001 EST

6.8.1. EXTRACT, date_part

EXTRACT (*field* FROM *source*)

The extract function retrieves subfields from date/time values, such as year or hour. *source* is a value expression that evaluates to type timestamp or interval. (Expressions of type date or time will be cast to timestamp and can therefore be used as well.) *field* is an identifier or string that selects what field to extract from the source value. The extract function returns values of type double precision. The following are valid values:

century

The year field divided by 100

```
SELECT EXTRACT(CENTURY FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 20
```

Note that the result for the century field is simply the year field divided by 100, and not the conventional definition which puts most years in the 1900's in the twentieth century.

day

The day (of the month) field (1 - 31)

```
SELECT EXTRACT(DAY FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 16
```

decade

The year field divided by 10

```
SELECT EXTRACT(DECADE FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 200
```

dow

The day of the week (0 - 6; Sunday is 0) (for timestamp values only)

```
SELECT EXTRACT(DOW FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 5
```

doy

The day of the year (1 - 365/366) (for timestamp values only)

```
SELECT EXTRACT(DOY FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 47
```

epoch

For date and timestamp values, the number of seconds since 1970-01-01 00:00:00-00 (can be negative); for interval values, the total number of seconds in the interval

```
SELECT EXTRACT(EPOCH FROM TIMESTAMP '2001-02-16 20:38:40');
```

```
Result: 982352320

SELECT EXTRACT(EPOCH FROM INTERVAL '5 days 3 hours');
Result: 442800
```

`hour`

The hour field (0 - 23)

```
SELECT EXTRACT(HOUR FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 20
```

`microseconds`

The seconds field, including fractional parts, multiplied by 1 000 000. Note that this includes full seconds.

```
SELECT EXTRACT(MICROSECONDS FROM TIME '17:12:28.5');
Result: 28500000
```

`millennium`

The year field divided by 1000

```
SELECT EXTRACT(MILLENNIUM FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 2
```

Note that the result for the millennium field is simply the year field divided by 1000, and not the conventional definition which puts years in the 1900's in the second millennium.

`milliseconds`

The seconds field, including fractional parts, multiplied by 1000. Note that this includes full seconds.

```
SELECT EXTRACT(MILLISECONDS FROM TIME '17:12:28.5');
Result: 28500
```

`minute`

The minutes field (0 - 59)

```
SELECT EXTRACT(MINUTE FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 38
```

`month`

For `timestamp` values, the number of the month within the year (1 - 12) ; for `interval` values the number of months, modulo 12 (0 - 11)

```
SELECT EXTRACT(MONTH FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 2

SELECT EXTRACT(MONTH FROM INTERVAL '2 years 3 months');
Result: 3

SELECT EXTRACT(MONTH FROM INTERVAL '2 years 13 months');
Result: 1
```

`quarter`

The quarter of the year (1 - 4) that the day is in (for `timestamp` values only)

```
SELECT EXTRACT(QUARTER FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 1
```

second

The seconds field, including fractional parts (0 - 59[2])

```
SELECT EXTRACT(SECOND FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 40

SELECT EXTRACT(SECOND FROM TIME '17:12:28.5');
Result: 28.5
```

timezone_hour

The hour component of the time zone offset.

timezone_minute

The minute component of the time zone offset.

week

From a timestamp value, calculate the number of the week of the year that the day is in. By definition (ISO 8601), the first week of a year contains January 4 of that year. (The ISO week starts on Monday.) In other words, the first Thursday of a year is in week 1 of that year.

```
SELECT EXTRACT(WEEK FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 7
```

year

The year field

```
SELECT EXTRACT(YEAR FROM TIMESTAMP '2001-02-16 20:38:40');
Result: 2001
```

The extract function is primarily intended for computational processing. For formatting date/time values for display, see Section 6.7, “Data Type Formatting Functions”.

The date_part function is modeled on the traditional Ingres equivalent to the SQL-standard function extract:

```
date_part('field', source)
```

Note that here the *field* parameter needs to be a string value, not a name. The valid field values for date_part are the same as for extract.

```
SELECT date_part('day', TIMESTAMP '2001-02-16 20:38:40');
Result: 16

SELECT date_part('hour', INTERVAL '4 hours 3 minutes');
Result: 4
```

6.8.2. date_trunc

The function date_trunc is conceptually similar to the trunc function for numbers.

```
date_trunc('field', source)
```

source is a value expression of type timestamp (values of type date and time are cast automatically). *field* selects to which precision to truncate the time stamp value. The return value is of type timestamp with all fields that are less than the selected one set to zero (or one, for day and month).

[2] 60 if leap seconds are implemented by the operating system

Valid values for *field* are:

microseconds
milliseconds
second
minute
hour
day
month
year
decade
century
millennium

Examples:

```
SELECT date_trunc('hour', TIMESTAMP '2001-02-16 20:38:40');
Result: 2001-02-16 20:00:00+00

SELECT date_trunc('year', TIMESTAMP '2001-02-16 20:38:40');
Result: 2001-01-01 00:00:00+00
```

6.8.3. AT TIME ZONE

The AT TIME ZONE construct allows conversions of timestamps to different timezones.

Table 6.19. AT TIME ZONE Variants

Expression	Returns	Description
timestamp without time zone AT TIME ZONE *zone*	timestamp with time zone	Convert local time in given timezone to UTC
timestamp with time zone AT TIME ZONE *zone*	timestamp without time zone	Convert UTC to local time in given timezone
time with time zone AT TIME ZONE *zone*	time with time zone	Convert local time across timezones

In these expressions, the desired time *zone* can be specified either as a text string (e.g., 'PST') or as an interval (e.g., INTERVAL '-08:00').

Examples (supposing that TimeZone is PST8PDT):

```
SELECT TIMESTAMP '2001-02-16 20:38:40' AT TIME ZONE 'MST';
Result: 2001-02-16 19:38:40-08

SELECT TIMESTAMP WITH TIME ZONE '2001-02-16 20:38:40-05' AT TIME
 ZONE 'MST';
Result: 2001-02-16 18:38:40
```

The first example takes a zone-less timestamp and interprets it as MST time (GMT-7) to produce a UTC timestamp, which is then rotated to PST (GMT-8) for display. The second example takes a timestamp specified in EST (GMT-5) and converts it to local time in MST (GMT-7).

The function timezone(*zone*, *timestamp*) is equivalent to the SQL-compliant construct *timestamp* AT TIME ZONE *zone*.

6.8.4. Current Date/Time

The following functions are available to obtain the current date and/or time:

```
CURRENT_DATE
CURRENT_TIME
CURRENT_TIMESTAMP
CURRENT_TIME ( precision )
CURRENT_TIMESTAMP ( precision )
LOCALTIME
LOCALTIMESTAMP
LOCALTIME ( precision )
LOCALTIMESTAMP ( precision )
```

`CURRENT_TIME` and `CURRENT_TIMESTAMP` deliver values with time zone; `LOCALTIME` and `LOCALTIMESTAMP` deliver values without time zone.

`CURRENT_TIME`, `CURRENT_TIMESTAMP`, `LOCALTIME`, and `LOCALTIMESTAMP` can optionally be given a precision parameter, which causes the result to be rounded to that many fractional digits. Without a precision parameter, the result is given to the full available precision.

Note

Prior to PostgreSQL 7.2, the precision parameters were unimplemented, and the result was always given in integer seconds.

Some examples:

```
SELECT CURRENT_TIME;
14:39:53.662522-05

SELECT CURRENT_DATE;
2001-12-23

SELECT CURRENT_TIMESTAMP;
2001-12-23 14:39:53.662522-05

SELECT CURRENT_TIMESTAMP(2);
2001-12-23 14:39:53.66-05

SELECT LOCALTIMESTAMP;
2001-12-23 14:39:53.662522
```

The function `now()` is the traditional PostgreSQL equivalent to `CURRENT_TIMESTAMP`.

There is also `timeofday()`, which for historical reasons returns a text string rather than a `timestamp` value:

```
SELECT timeofday();
 Sat Feb 17 19:07:32.000126 2001 EST
```

It is important to realize that `CURRENT_TIMESTAMP` and related functions return the start time of the current transaction; their values do not change during the transaction. `timeofday()` returns the wall clock time and does advance during transactions.

Note

Many other database systems advance these values more frequently.

All the date/time data types also accept the special literal value `now` to specify the current date and time. Thus, the following three all return the same result:

```
SELECT CURRENT_TIMESTAMP;
SELECT now();
SELECT TIMESTAMP 'now';
```

Note

You do not want to use the third form when specifying a `DEFAULT` clause while creating a table. The system will convert `now` to a `timestamp` as soon as the constant is parsed, so that when the default value is needed, the time of the table creation would be used! The first two forms will not be evaluated until the default value is used, because they are function calls. Thus they will give the desired behavior of defaulting to the time of row insertion.

6.9. Geometric Functions and Operators

The geometric types `point`, `box`, `lseg`, `line`, `path`, `polygon`, and `circle` have a large set of native support functions and operators, shown in Table 6.20, “Geometric Operators”, Table 6.21, “Geometric Functions”, and Table 6.22, “Geometric Type Conversion Functions”.

Table 6.20. Geometric Operators

Operator	Description	Usage
+	Translation	`box '((0,0),(1,1))' + point '(2.0,0)'`
-	Translation	`box '((0,0),(1,1))' - point '(2.0,0)'`
*	Scaling/rotation	`box '((0,0),(1,1))' * point '(2.0,0)'`
/	Scaling/rotation	`box '((0,0),(2,2))' / point '(2.0,0)'`
#	Intersection	`'((1,-1),(-1,1))' # '((1,1),(-1,-1))'`
#	Number of points in path or polygon	`# '((1,0),(0,1),(-1,0))'`
##	Point of closest proximity	`point '(0,0)' ## lseg '((2,0),(0,2))'`
&&	Overlaps?	`box '((0,0),(1,1))' && box '((0,0),(2,2))'`
&<	Overlaps to left?	`box '((0,0),(1,1))' &< box '((0,0),(2,2))'`
&>	Overlaps to right?	`box '((0,0),(3,3))' &> box '((0,0),(2,2))'`
<->	Distance between	`circle '((0,0),1)' <-> circle '((5,0),1)'`
<<	Left of?	`circle '((0,0),1)' << circle '((5,0),1)'`
<^	Is below?	`circle '((0,0),1)' <^ circle '((0,5),1)'`
>>	Is right of?	`circle '((5,0),1)' >> circle '((0,0),1)'`
>^	Is above?	`circle '((0,5),1)' >^ circle '((0,0),1)'`
?#	Intersects or overlaps	`lseg '((-1,0),(1,0))' ?# box '((-2,-2),(2,2))'`

Operator	Description	Usage
?-	Is horizontal?	`point '(1,0)' ?- point '(0,0)'`
?-|	Is perpendicular?	`lseg '((0,0),(0,1))' ?-| lseg '((0,0),(1,0))'`
@-@	Length or circumference	`@-@ path '((0,0),(1,0))'`
?|	Is vertical?	`point '(0,1)' ?| point '(0,0)'`
?||	Is parallel?	`lseg '((-1,0),(1,0))' ?|| lseg '((-1,2),(1,2))'`
@	Contained or on	`point '(1,1)' @ circle '((0,0),2)'`
@@	Center of	`@@ circle '((0,0),10)'`
~=	Same as	`polygon '((0,0),(1,1))' ~= polygon '((1,1),(0,0))'`

Table 6.21. Geometric Functions

Function	Returns	Description	Example
`area`(object)	`double precision`	area of item	`area(box '((0,0),(1,1))')`
`box`(box, box)	`box`	intersection box	`box(box '((0,0),(1,1))',box '((0.5,0.5),(2,2))')`
`center`(object)	`point`	center of item	`center(box '((0,0),(1,2))')`
`diameter`(circle)	`double precision`	diameter of circle	`diameter(circle '((0,0),2.0)')`
`height`(box)	`double precision`	vertical size of box	`height(box '((0,0),(1,1))')`
`isclosed`(path)	`boolean`	a closed path?	`isclosed(path '((0,0),(1,1),(2,0))')`
`isopen`(path)	`boolean`	an open path?	`isopen(path '[(0,0),(1,1),(2,0)]')`
`length`(object)	`double precision`	length of item	`length(path '((-1,0),(1,0))')`
`npoints`(path)	`integer`	number of points	`npoints(path '[(0,0),(1,1),(2,0)]')`
`npoints`(polygon)	`integer`	number of points	`npoints(polygon '((1,1),(0,0))')`

Function	Returns	Description	Example
pclose(path)	path	convert path to closed	popen(path '[(0,0),(1,1),(2,0)]')
popen(path)	path	convert path to open path	popen(path '((0,0),(1,1),(2,0))')
radius(circle)	double precision	radius of circle	radius(circle '((0,0),2.0)')
width(box)	double precision	horizontal size	width(box '((0,0),(1,1))')

Table 6.22. Geometric Type Conversion Functions

Function	Returns	Description	Example
box(circle)	box	circle to box	box(circle '((0,0),2.0)')
box(point, point)	box	points to box	box(point '(0,0)', point '(1,1)')
box(polygon)	box	polygon to box	box(polygon '((0,0),(1,1),(2,0))')
circle(box)	circle	to circle	circle(box '((0,0),(1,1))')
circle(point, double precision)	circle	point to circle	circle(point '(0,0)', 2.0)
lseg(box)	lseg	box diagonal to lseg	lseg(box '((-1,0),(1,0))')
lseg(point, point)	lseg	points to lseg	lseg(point '(-1,0)', point '(1,0)')
path(polygon)	point	polygon to path	path(polygon '((0,0),(1,1),(2,0))')
point(circle)	point	center	point(circle '((0,0),2.0)')
point(lseg, lseg)	point	intersection	point(lseg '((-1,0),(1,0))', lseg '((-2,-2),(2,2))')
point(polygon)	point	center	point(polygon '((0,0),(1,1),(2,0))')
polygon(box)	polygon	4-point polygon	polygon(box '((0,0),(1,1))')
polygon(circle)	polygon	12-point polygon	polygon(circle '((0,0),2.0)')

Function	Returns	Description	Example
polygon(*npts*, circle)	polygon	*npts* polygon	polygon(12, circle '((0,0),2.0)')
polygon(path)	polygon	path to polygon	polygon(path '((0,0),(1,1),(2,0))')

It is possible to access the two component numbers of a point as though it were an array with subscripts 0, 1. For example, if t.p is a point column then SELECT p[0] FROM t retrieves the X coordinate; UPDATE t SET p[1] = ... changes the Y coordinate. In the same way, a box or an lseg may be treated as an array of two points.

6.10. Network Address Type Functions

Table 6.23, "cidr and inet Operators" shows the operators available for the inet and cidr types. The operators <<, <<=, >>, >>= test for subnet inclusion: they consider only the network parts of the two addresses, ignoring any host part, and determine whether one network part is identical to or a subnet of the other.

Table 6.23. cidr and inet Operators

Operator	Description	Usage
<	Less than	inet '192.168.1.5' < inet '192.168.1.6'
<=	Less than or equal	inet '192.168.1.5' <= inet '192.168.1.5'
=	Equals	inet '192.168.1.5' = inet '192.168.1.5'
>=	Greater or equal	inet '192.168.1.5' >= inet '192.168.1.5'
>	Greater	inet '192.168.1.5' > inet '192.168.1.4'
<>	Not equal	inet '192.168.1.5' <> inet '192.168.1.4'
<<	is contained within	inet '192.168.1.5' << inet '192.168.1/24'
<<=	is contained within or equals	inet '192.168.1/24' <<= inet '192.168.1/24'
>>	contains	inet'192.168.1/24' >> inet '192.168.1.5'
>>=	contains or equals	inet '192.168.1/24' >>= inet '192.168.1/24'

Table 6.24, "cidr and inet Functions" shows the functions available for use with the inet and cidr types. The host(), text(), and abbrev() functions are primarily intended to offer alternative display formats. You can cast a text field to inet using normal casting syntax: inet(expression) or colname::inet.

Table 6.24. `cidr` and `inet` Functions

Function	Returns	Description	Example	Result
`broadcast(inet)`	`inet`	broadcast address for network	`broadcast('192.168.1.5/24')`	`192.168.1.255/24`
`host(inet)`	`text`	extract IP address as text	`host('192.168.1.5/24')`	`192.168.1.5`
`masklen(inet)`	`integer`	extract netmask length	`masklen('192.168.1.5/24')`	`24`
`set_masklen(inet,integer)`	`inet`	set netmask length for `inet` value	`set_masklen('192.168.1.5/24',16)`	`192.168.1.5/16`
`netmask(inet)`	`inet`	construct netmask for network	`netmask('192.168.1.5/24')`	`255.255.255.0`
`network(inet)`	`cidr`	extract network part of address	`network('192.168.1.5/24')`	`192.168.1.0/24`
`text(inet)`	`text`	extract IP address and masklen as text	`text(inet '192.168.1.5')`	`192.168.1.5/32`
`abbrev(inet)`	`text`	extract abbreviated display as text	`abbrev(cidr '10.1.0.0/16')`	`10.1/16`

Table 6.25, "`macaddr` Functions" shows the functions available for use with the `mac` type. The function `trunc(macaddr)` returns a MAC address with the last 3 bytes set to 0. This can be used to associate the remaining prefix with a manufacturer. The directory `contrib/mac` in the source distribution contains some utilities to create and maintain such an association table.

Table 6.25. `macaddr` Functions

Function	Returns	Description	Example	Result
`trunc(macaddr)`	`macaddr`	set last 3 bytes to zero	`trunc(macaddr '12:34:56:78:90:ab')`	`12:34:56:00:00:00`

The `macaddr` type also supports the standard relational operators (>, <=, etc.) for lexicographical ordering.

6.11. Sequence-Manipulation Functions

This section describes PostgreSQL's functions for operating on *sequence objects*. Sequence objects (also called sequence generators or just sequences) are special single-row tables created with `CREATE SEQUENCE`. A sequence object is usually used to generate unique identifiers for rows of a table. The sequence functions, listed in Table 6.26, "Sequence Functions", provide simple, multiuser-safe methods for obtaining successive sequence values from sequence objects.

Table 6.26. Sequence Functions

Function	Returns	Description
`nextval(text)`	`bigint`	Advance sequence and return new value
`currval(text)`	`bigint`	Return value most recently obtained with `nextval`
`setval(text,bigint)`	`bigint`	Set sequence's current value
`setval(text,bigint,boolean)`	`bigint`	Set sequence's current value and `is_called` flag

For largely historical reasons, the sequence to be operated on by a sequence-function call is specified by a text-string argument. To achieve some compatibility with the handling of ordinary SQL names, the sequence functions convert their argument to lower case unless the string is double-quoted. Thus

```
nextval('foo')      operates on sequence foo
nextval('FOO')      operates on sequence foo
nextval('"Foo"')    operates on sequence Foo
```

The sequence name can be schema-qualified if necessary:

```
nextval('myschema.foo')     operates on myschema.foo
nextval('"myschema".foo')   same as above
nextval('foo')              searches search path for foo
```

Of course, the text argument can be the result of an expression, not only a simple literal, which is occasionally useful.

The available sequence functions are:

`nextval`

Advance the sequence object to its next value and return that value. This is done atomically: even if multiple sessions execute `nextval` concurrently, each will safely receive a distinct sequence value.

`currval`

Return the value most recently obtained by `nextval` for this sequence in the current session. (An error is reported if `nextval` has never been called for this sequence in this session.) Notice that because this is returning a session-local value, it gives a predictable answer even if other sessions are executing `nextval` meanwhile.

`setval`

Reset the sequence object's counter value. The two-parameter form sets the sequence's `last_value` field to the specified value and sets its `is_called` field to `true`, meaning that the next `nextval` will advance the sequence before returning a value. In the three-parameter form, `is_called` may be set either `true` or `false`. If it's set to `false`, the next `nextval` will return exactly the specified value, and sequence advancement commences with the following `nextval`. For example,

```
SELECT setval('foo', 42);           Next nextval() will return
 43
SELECT setval('foo', 42, true);     Same as above
SELECT setval('foo', 42, false);    Next nextval() will return
 42
```

The result returned by `setval` is just the value of its second argument.

Important

To avoid blocking of concurrent transactions that obtain numbers from the same sequence, a `nextval` operation is never rolled back; that is, once a value has been fetched it is considered used, even if the transaction that did the `nextval` later aborts. This means that aborted transactions may leave unused “holes” in the sequence of assigned values. `setval` operations are never rolled back, either.

If a sequence object has been created with default parameters, `nextval()` calls on it will return successive values beginning with one. Other behaviors can be obtained by using special parameters in the `CREATE SEQUENCE` command; see its command reference page for more information.

6.12. Conditional Expressions

This section describes the SQL-compliant conditional expressions available in PostgreSQL.

Tip

If your needs go beyond the capabilities of these conditional expressions you might want to consider writing a stored procedure in a more expressive programming language.

6.12.1. CASE

```
CASE WHEN condition THEN result
     [WHEN ...]
     [ELSE result]
END
```

The SQL `CASE` expression is a generic conditional expression, similar to if/else statements in other languages. `CASE` clauses can be used wherever an expression is valid. *`condition`* is an expression that returns a `boolean` result. If the result is true then the value of the `CASE` expression is *`result`*. If the result is false any subsequent `WHEN` clauses are searched in the same manner. If no `WHEN` *`condition`* is true then the value of the case expression is the *`result`* in the `ELSE` clause. If the `ELSE` clause is omitted and no condition matches, the result is null.

An example:

```
=> SELECT * FROM test;
 a
---
 1
 2
 3

=> SELECT a,
          CASE WHEN a=1 THEN 'one'
               WHEN a=2 THEN 'two'
               ELSE 'other'
          END
    FROM test;
 a | case
---+-------
 1 | one
 2 | two
 3 | other
```

The data types of all the *`result`* expressions must be coercible to a single output type. See Section 7.5, "`UNION` and `CASE` Constructs" for more detail.

```
CASE expression
    WHEN value THEN result
    [WHEN ...]
    [ELSE result]
END
```

This "simple" `CASE` expression is a specialized variant of the general form above. The *`expression`* is computed and compared to all the *`value`*s in the `WHEN` clauses until one is found that is equal. If no match is found, the *`result`* in the `ELSE` clause (or a null value) is returned. This is similar to the `switch` statement in C.

The example above can be written using the simple CASE syntax:

```
=> SELECT a,
          CASE a WHEN 1 THEN 'one'
                 WHEN 2 THEN 'two'
                 ELSE 'other'
          END
    FROM test;
 a | case
---+-------
 1 | one
 2 | two
 3 | other
```

6.12.2. COALESCE

```
COALESCE(value [, ...])
```

The COALESCE function returns the first of its arguments that is not null. This is often useful to substitute a default value for null values when data is retrieved for display, for example:

```
SELECT COALESCE(description, short_description, '(none)') ...
```

6.12.3. NULLIF

```
NULLIF(value1, value2)
```

The NULLIF function returns a null value if and only if *value1* and *value2* are equal. Otherwise it returns *value1*. This can be used to perform the inverse operation of the COALESCE example given above:

```
SELECT NULLIF(value, '(none)') ...
```

Tip

COALESCE and NULLIF are just shorthand for CASE expressions. They are actually converted into CASE expressions at a very early stage of processing, and subsequent processing thinks it is dealing with CASE. Thus an incorrect COALESCE or NULLIF usage may draw an error message that refers to CASE.

6.13. Miscellaneous Functions

Table 6.27, “Session Information Functions” shows several functions that extract session and system information.

Table 6.27. Session Information Functions

Name	Return Type	Description
current_database()	name	name of current database
current_schema()	name	name of current schema
current_schemas(boolean)	name[]	names of schemas in search path optionally including implicit schemas
current_user	name	user name of current execution context
session_user	name	session user name

Name	Return Type	Description
user	name	equivalent to current_user
version()	text	PostgreSQL version information

The session_user is the user that initiated a database connection; it is fixed for the duration of that connection. The current_user is the user identifier that is applicable for permission checking. Normally, it is equal to the session user, but it changes during the execution of functions with the attribute SECURITY DEFINER. In Unix parlance, the session user is the "real user" and the current user is the "effective user".

Note

current_user, session_user, and user have special syntactic status in SQL: they must be called without trailing parentheses.

current_schema returns the name of the schema that is at the front of the search path (or a null value if the search path is empty). This is the schema that will be used for any tables or other named objects that are created without specifying a target schema. current_schemas(boolean) returns an array of the names of all schemas presently in the search path. The boolean option determines whether or not implicitly included system schemas such as pg_catalog are included in the search path returned.

The search path may be altered by a run-time setting. The command to use is SET SEARCH_PATH 'schema'[,'schema']...

version() returns a string describing the PostgreSQL server's version.

Table 6.28, "Configuration Settings Information Functions" shows the functions available to query and alter run-time configuration parameters.

Table 6.28. Configuration Settings Information Functions

Name	Return Type	Description
current_setting(*setting_name*)	text	value of current setting
set_config(*setting_name*, *new_value*, *is_local*)	text	new value of current setting

The current_setting is used to obtain the current value of the *setting_name* setting, as a query result. It is the equivalent to the SQL SHOW command. For example:

```
select current_setting('DateStyle');
            current_setting
-----------------------------------------
 ISO with US (NonEuropean) conventions
(1 row)
```

set_config allows the *setting_name* setting to be changed to *new_value*. If *is_local* is set to true, the new value will only apply to the current transaction. If you want the new value to apply for the current session, use false instead. It is the equivalent to the SQL SET command. For example:

```
select set_config('show_statement_stats','off','f');
 set_config
------------
 off
(1 row)
```

Table 6.29, “Access Privilege Inquiry Functions” lists functions that allow the user to query object access privileges programmatically. See Section 2.7, “Privileges” for more information about privileges.

Table 6.29. Access Privilege Inquiry Functions

Name	Return Type	Description
has_table_privilege(*user*, *table*, *access*)	boolean	does user have access to table
has_table_privilege(*table*, *access*)	boolean	does current user have access to table
has_database_privilege(*user*, *database*, *access*)	boolean	does user have access to database
has_database_privilege(*database*, *access*)	boolean	does current user have access to database
has_function_privilege(*user*, *function*, *access*)	boolean	does user have access to function
has_function_privilege(*function*, *access*)	boolean	does current user have access to function
has_language_privilege(*user*, *language*, *access*)	boolean	does user have access to language
has_language_privilege(*language*, *access*)	boolean	does current user have access to language
has_schema_privilege(*user*, *schema*, *access*)	boolean	does user have access to schema
has_schema_privilege(*schema*, *access*)	boolean	does current user have access to schema

has_table_privilege checks whether a user can access a table in a particular way. The user can be specified by name or by ID (pg_user.usesysid), or if the argument is omitted current_user is assumed. The table can be specified by name or by OID. (Thus, there are actually six variants of has_table_privilege, which can be distinguished by the number and types of their arguments.) When specifying by name, the name can be schema-qualified if necessary. The desired access type is specified by a text string, which must evaluate to one of the values SELECT, INSERT, UPDATE, DELETE, RULE, REFERENCES, or TRIGGER. (Case of the string is not significant, however.) An example is:

```
SELECT has_table_privilege('myschema.mytable', 'select');
```

has_database_privilege checks whether a user can access a database in a particular way. The possibilities for its arguments are analogous to has_table_privilege. The desired access type must evaluate to CREATE, TEMPORARY, or TEMP (which is equivalent to TEMPORARY).

has_function_privilege checks whether a user can access a function in a particular way. The possibilities for its arguments are analogous to has_table_privilege. When specifying a function by a text string rather than by OID, the allowed input is the same as for the regprocedure data type. The desired access type must currently evaluate to EXECUTE.

has_language_privilege checks whether a user can access a procedural language in a particular way. The possibilities for its arguments are analogous to has_table_privilege. The desired access type must currently evaluate to USAGE.

has_schema_privilege checks whether a user can access a schema in a particular way. The possibilities for its arguments are analogous to has_table_privilege. The desired access type must evaluate to CREATE or USAGE.

Table 6.30, “Schema Visibility Inquiry Functions” shows functions that determine whether a certain object is *visible* in the current schema search path. A table is said to be visible if its containing schema is in the search path and no table of the same name appears earlier in the search path. This is equivalent to the statement that the table can be referenced by name without explicit schema qualification. For example, to list the names of all visible tables:

```
SELECT relname FROM pg_class WHERE pg_table_is_visible(oid);
```

Table 6.30. Schema Visibility Inquiry Functions

Name	Return Type	Description
`pg_table_is_visible(`*tableOID*`)`	`boolean`	is table visible in search path
`pg_type_is_visible(`*typeOID*`)`	`boolean`	is type visible in search path
`pg_function_is_visible(`*functionOID*`)`	`boolean`	is function visible in search path
`pg_operator_is_visible(`*operatorOID*`)`	`boolean`	is operator visible in search path
`pg_opclass_is_visible(`*opclassOID*`)`	`boolean`	is operator class visible in search path

`pg_table_is_visible` performs the check for tables (or views, or any other kind of `pg_class` entry). `pg_type_is_visible`, `pg_function_is_visible`, `pg_operator_is_visible`, and `pg_opclass_is_visible` perform the same sort of visibility check for types, functions, operators, and operator classes, respectively. For functions and operators, an object in the search path is visible if there is no object of the same name *and argument data type(s)* earlier in the path. For operator classes, both name and associated index access method are considered.

All these functions require object OIDs to identify the object to be checked. If you want to test an object by name, it is convenient to use the OID alias types (`regclass`, `regtype`, `regprocedure`, or `regoperator`), for example

```
SELECT pg_type_is_visible('myschema.widget'::regtype);
```

Note that it would not make much sense to test an unqualified name in this way --- if the name can be recognized at all, it must be visible.

Table 6.31, “Catalog Information Functions” lists functions that extract information from the system catalogs. `pg_get_viewdef()`, `pg_get_ruledef()`, `pg_get_indexdef()`, and `pg_get_constraintdef()` respectively reconstruct the creating command for a view, rule, index, or constraint. (Note that this is a decompiled reconstruction, not the verbatim text of the command.) At present `pg_get_constraintdef()` only works for foreign-key constraints. `pg_get_userbyid()` extracts a user's name given a `usesysid` value.

Table 6.31. Catalog Information Functions

Name	Return Type	Description
`pg_get_viewdef(`*viewname*`)`	`text`	Get `CREATE VIEW` command for view (*deprecated*)
`pg_get_viewdef(`*viewOID*`)`	`text`	Get `CREATE VIEW` command for view
`pg_get_ruledef(`*ruleOID*`)`	`text`	Get `CREATE RULE` command for rule
`pg_get_indexdef(`*indexOID*`)`	`text`	Get `CREATE INDEX` command for index

Name	Return Type	Description
pg_get_constraintdef(*constraintOID*)	text	Get definition of a constraint
pg_get_userbyid(*userid*)	name	Get user name with given ID

The function shown in Table 6.32, “Comment Information Functions” extract comments previously stored with the COMMENT command. A null value is returned if no comment can be found matching the specified parameters.

Table 6.32. Comment Information Functions

Name	Return Type	Description
obj_description(*objectOID*, *tablename*)	text	Get comment for a database object
obj_description(*objectOID*)	text	Get comment for a database object (*deprecated*)
col_description(*tableOID*, *columnnumber*)	text	Get comment for a table column

The two-parameter form of obj_description() returns the comment for a database object specified by its OID and the name of the containing system catalog. For example, obj_description(123456,'pg_class') would retrieve the comment for a table with OID 123456. The one-parameter form of obj_description() requires only the object OID. It is now deprecated since there is no guarantee that OIDs are unique across different system catalogs; therefore, the wrong comment could be returned.

col_description() returns the comment for a table column, which is specified by the OID of its table and its column number. obj_description() cannot be used for table columns since columns do not have OIDs of their own.

6.14. Aggregate Functions

Aggregate functions compute a single result value from a set of input values. Table 6.33, “Aggregate Functions” show the built-in aggregate functions. The special syntax considerations for aggregate functions are explained in Section 1.2.5, “Aggregate Expressions”. Consult the PostgreSQL 7.3.21 Tutorial for additional introductory information.

Table 6.33. Aggregate Functions

Function	Argument Type	Return Type	Description	
avg(*expression*)	smallint, integer, bigint, real, double precision, numeric, or interval.	numeric for any integer type argument, double precision for a floating-point argument, otherwise the same as the argument data type	the average (arithmetic mean) of all input values	
count(*)		bigint	number of input values	
count(*expression*)	any	bigint	number of input values for which	

Function	Argument Type	Return Type	Description	
			the value of *expression* is not null	
max(*expression*)	any numeric, string, or date/time type	same as argument type	maximum value of *expression* across all input values	
min(*expression*)	any numeric, string, or date/time type	same as argument type	minimum value of *expression* across all input values	
stddev(*expression*)	smallint, integer, bigint, real, double precision, or numeric.	double precision for floating-point arguments, otherwise numeric.	sample standard deviation of the input values	
sum(*expression*)	smallint, integer, bigint, real, double precision, numeric, or interval	bigint for smallint or integer arguments, numeric for bigint arguments, double precision for floating-point arguments, otherwise the same as the argument data type	sum of *expression* across all input values	
variance(*expression*)	smallint, integer, bigint, real, double precision, or numeric.	double precision for floating-point arguments, otherwise numeric.	sample variance of the input values (square of the sample standard deviation)	

It should be noted that except for count, these functions return a null value when no rows are selected. In particular, sum of no rows returns null, not zero as one might expect. The function coalesce may be used to substitute zero for null when necessary.

6.15. Subquery Expressions

This section describes the SQL-compliant subquery expressions available in PostgreSQL. All of the expression forms documented in this section return Boolean (true/false) results.

6.15.1. EXISTS

```
EXISTS ( subquery )
```

The argument of EXISTS is an arbitrary SELECT statement, or *subquery*. The subquery is evaluated to determine whether it returns any rows. If it returns at least one row, the result of EXISTS is “true”; if the subquery returns no rows, the result of EXISTS is “false”.

The subquery can refer to variables from the surrounding query, which will act as constants during any one evaluation of the subquery.

The subquery will generally only be executed far enough to determine whether at least one row is returned, not all the way to completion. It is unwise to write a subquery that has any side effects (such as calling sequence functions); whether the side effects occur or not may be difficult to predict.

Since the result depends only on whether any rows are returned, and not on the contents of those rows, the output list of the subquery is normally uninteresting. A common coding convention is to write all `EXISTS` tests in the form `EXISTS(SELECT 1 WHERE ...)`. There are exceptions to this rule however, such as subqueries that use `INTERSECT`.

This simple example is like an inner join on `col2`, but it produces at most one output row for each `tab1` row, even if there are multiple matching `tab2` rows:

```
SELECT col1 FROM tab1
    WHERE EXISTS(SELECT 1 FROM tab2 WHERE col2 = tab1.col2);
```

6.15.2. IN (scalar form)

expression `IN (`*value*`[, ...])`

The right-hand side of this form of `IN` is a parenthesized list of scalar expressions. The result is “true” if the left-hand expression's result is equal to any of the right-hand expressions. This is a shorthand notation for

```
expression = value1
OR
expression = value2
OR
...
```

Note that if the left-hand expression yields null, or if there are no equal right-hand values and at least one right-hand expression yields null, the result of the `IN` construct will be null, not false. This is in accordance with SQL's normal rules for Boolean combinations of null values.

Note

This form of `IN` is not truly a subquery expression, but it seems best to document it in the same place as subquery `IN`.

6.15.3. IN (subquery form)

expression `IN (`*subquery*`)`

The right-hand side of this form of `IN` is a parenthesized subquery, which must return exactly one column. The left-hand expression is evaluated and compared to each row of the subquery result. The result of `IN` is “true” if any equal subquery row is found. The result is “false” if no equal row is found (including the special case where the subquery returns no rows).

Note that if the left-hand expression yields null, or if there are no equal right-hand values and at least one right-hand row yields null, the result of the `IN` construct will be null, not false. This is in accordance with SQL's normal rules for Boolean combinations of null values.

As with `EXISTS`, it's unwise to assume that the subquery will be evaluated completely.

`(`*expression* `[, `*expression* `...]) IN (`*subquery*`)`

The right-hand side of this form of `IN` is a parenthesized subquery, which must return exactly as many columns as there are expressions in the left-hand list. The left-hand expressions are evaluated

and compared row-wise to each row of the subquery result. The result of IN is “true” if any equal subquery row is found. The result is “false” if no equal row is found (including the special case where the subquery returns no rows).

As usual, null values in the expressions or subquery rows are combined per the normal rules of SQL Boolean expressions. Two rows are considered equal if all their corresponding members are non-null and equal; the rows are unequal if any corresponding members are non-null and unequal; otherwise the result of that row comparison is unknown (null). If all the row results are either unequal or null, with at least one null, then the result of IN is null.

6.15.4. NOT IN (scalar form)

```
expression NOT IN (value[, ...])
```

The right-hand side of this form of NOT IN is a parenthesized list of scalar expressions. The result is “true” if the left-hand expression's result is unequal to all of the right-hand expressions. This is a shorthand notation for

```
expression <> value1
AND
expression <> value2
AND
...
```

Note that if the left-hand expression yields null, or if there are no equal right-hand values and at least one right-hand expression yields null, the result of the NOT IN construct will be null, not true as one might naively expect. This is in accordance with SQL's normal rules for Boolean combinations of null values.

Tip

x NOT IN y is equivalent to NOT (x IN y) in all cases. However, null values are much more likely to trip up the novice when working with NOT IN than when working with IN. It's best to express your condition positively if possible.

6.15.5. NOT IN (subquery form)

```
expression NOT IN (subquery)
```

The right-hand side of this form of NOT IN is a parenthesized subquery, which must return exactly one column. The left-hand expression is evaluated and compared to each row of the subquery result. The result of NOT IN is “true” if only unequal subquery rows are found (including the special case where the subquery returns no rows). The result is “false” if any equal row is found.

Note that if the left-hand expression yields null, or if there are no equal right-hand values and at least one right-hand row yields null, the result of the NOT IN construct will be null, not true. This is in accordance with SQL's normal rules for Boolean combinations of null values.

As with EXISTS, it's unwise to assume that the subquery will be evaluated completely.

```
(expression [, expression ...]) NOT IN (subquery)
```

The right-hand side of this form of NOT IN is a parenthesized subquery, which must return exactly as many columns as there are expressions in the left-hand list. The left-hand expressions are evaluated and compared row-wise to each row of the subquery result. The result of NOT IN is “true” if only unequal subquery rows are found (including the special case where the subquery returns no rows). The result is “false” if any equal row is found.

As usual, null values in the expressions or subquery rows are combined per the normal rules of SQL Boolean expressions. Two rows are considered equal if all their corresponding members are non-null

and equal; the rows are unequal if any corresponding members are non-null and unequal; otherwise the result of that row comparison is unknown (null). If all the row results are either unequal or null, with at least one null, then the result of NOT IN is null.

6.15.6. ANY/SOME

```
expression operator ANY (subquery)
expression operator SOME (subquery)
```

The right-hand side of this form of ANY is a parenthesized subquery, which must return exactly one column. The left-hand expression is evaluated and compared to each row of the subquery result using the given *operator*, which must yield a Boolean result. The result of ANY is “true” if any true result is obtained. The result is “false” if no true result is found (including the special case where the subquery returns no rows).

SOME is a synonym for ANY. IN is equivalent to = ANY.

Note that if there are no successes and at least one right-hand row yields null for the operator's result, the result of the ANY construct will be null, not false. This is in accordance with SQL's normal rules for Boolean combinations of null values.

As with EXISTS, it's unwise to assume that the subquery will be evaluated completely.

```
(expression [, expression ...]) operator ANY (subquery)
(expression [, expression ...]) operator SOME (subquery)
```

The right-hand side of this form of ANY is a parenthesized subquery, which must return exactly as many columns as there are expressions in the left-hand list. The left-hand expressions are evaluated and compared row-wise to each row of the subquery result, using the given *operator*. Presently, only = and <> operators are allowed in row-wise ANY queries. The result of ANY is “true” if any equal or unequal row is found, respectively. The result is “false” if no such row is found (including the special case where the subquery returns no rows).

As usual, null values in the expressions or subquery rows are combined per the normal rules of SQL Boolean expressions. Two rows are considered equal if all their corresponding members are non-null and equal; the rows are unequal if any corresponding members are non-null and unequal; otherwise the result of that row comparison is unknown (null). If there is at least one null row result, then the result of ANY cannot be false; it will be true or null.

6.15.7. ALL

```
expression operator ALL (subquery)
```

The right-hand side of this form of ALL is a parenthesized subquery, which must return exactly one column. The left-hand expression is evaluated and compared to each row of the subquery result using the given *operator*, which must yield a Boolean result. The result of ALL is “true” if all rows yield true (including the special case where the subquery returns no rows). The result is “false” if any false result is found.

NOT IN is equivalent to <> ALL.

Note that if there are no failures but at least one right-hand row yields null for the operator's result, the result of the ALL construct will be null, not true. This is in accordance with SQL's normal rules for Boolean combinations of null values.

As with EXISTS, it's unwise to assume that the subquery will be evaluated completely.

```
(expression [, expression ...]) operator ALL (subquery)
```

The right-hand side of this form of `ALL` is a parenthesized subquery, which must return exactly as many columns as there are expressions in the left-hand list. The left-hand expressions are evaluated and compared row-wise to each row of the subquery result, using the given *`operator`*. Presently, only = and <> operators are allowed in row-wise `ALL` queries. The result of `ALL` is "true" if all subquery rows are equal or unequal, respectively (including the special case where the subquery returns no rows). The result is "false" if any row is found to be unequal or equal, respectively.

As usual, null values in the expressions or subquery rows are combined per the normal rules of SQL Boolean expressions. Two rows are considered equal if all their corresponding members are non-null and equal; the rows are unequal if any corresponding members are non-null and unequal; otherwise the result of that row comparison is unknown (null). If there is at least one null row result, then the result of `ALL` cannot be true; it will be false or null.

6.15.8. Row-wise Comparison

```
(expression [, expression ...]) operator (subquery)
(expression [, expression ...]) operator (expression [, expression
 ...])
```

The left-hand side is a list of scalar expressions. The right-hand side can be either a list of scalar expressions of the same length, or a parenthesized subquery, which must return exactly as many columns as there are expressions on the left-hand side. Furthermore, the subquery cannot return more than one row. (If it returns zero rows, the result is taken to be null.) The left-hand side is evaluated and compared row-wise to the single subquery result row, or to the right-hand expression list. Presently, only = and <> operators are allowed in row-wise comparisons. The result is "true" if the two rows are equal or unequal, respectively.

As usual, null values in the expressions or subquery rows are combined per the normal rules of SQL Boolean expressions. Two rows are considered equal if all their corresponding members are non-null and equal; the rows are unequal if any corresponding members are non-null and unequal; otherwise the result of the row comparison is unknown (null).

Chapter 7. Type Conversion

SQL queries can, intentionally or not, require mixing of different data types in the same expression. PostgreSQL has extensive facilities for evaluating mixed-type expressions.

In many cases a user will not need to understand the details of the type conversion mechanism. However, the implicit conversions done by PostgreSQL can affect the results of a query. When necessary, these results can be tailored by a user or programmer using *explicit* type coercion.

This chapter introduces the PostgreSQL type conversion mechanisms and conventions. Refer to the relevant sections in Chapter 5, *Data Types* and Chapter 6, *Functions and Operators* for more information on specific data types and allowed functions and operators.

The PostgreSQL 7.3.21 Programmer's Guide has more details on the exact algorithms used for implicit type conversion and coercion.

7.1. Overview

SQL is a strongly typed language. That is, every data item has an associated data type which determines its behavior and allowed usage. PostgreSQL has an extensible type system that is much more general and flexible than other SQL implementations. Hence, most type conversion behavior in PostgreSQL should be governed by general rules rather than by *ad hoc* heuristics, to allow mixed-type expressions to be meaningful even with user-defined types.

The PostgreSQL scanner/parser decodes lexical elements into only five fundamental categories: integers, floating-point numbers, strings, names, and key words. Most extended types are first tokenized into strings. The SQL language definition allows specifying type names with strings, and this mechanism can be used in PostgreSQL to start the parser down the correct path. For example, the query

```
tgl=> SELECT text 'Origin' AS "Label", point '(0,0)' AS "Value";
 Label  | Value
--------+-------
 Origin | (0,0)
(1 row)
```

has two literal constants, of type `text` and `point`. If a type is not specified for a string literal, then the placeholder type *unknown* is assigned initially, to be resolved in later stages as described below.

There are four fundamental SQL constructs requiring distinct type conversion rules in the PostgreSQL parser:

Operators

PostgreSQL allows expressions with prefix and postfix unary (one-argument) operators, as well as binary (two-argument) operators.

Function calls

Much of the PostgreSQL type system is built around a rich set of functions. Function calls have one or more arguments which, for any specific query, must be matched to the functions available in the system catalog. Since PostgreSQL permits function overloading, the function name alone does not uniquely identify the function to be called; the parser must select the right function based on the data types of the supplied arguments.

Query targets

SQL `INSERT` and `UPDATE` statements place the results of expressions into a table. The expressions in the query must be matched up with, and perhaps converted to, the types of the target columns.

`UNION` and `CASE` constructs

Since all select results from a unionized `SELECT` statement must appear in a single set of columns, the types of the results of each `SELECT` clause must be matched up and converted to a uniform set. Similarly, the result expressions of a `CASE` construct must be coerced to a common type so that the `CASE` expression as a whole has a known output type.

Many of the general type conversion rules use simple conventions built on the PostgreSQL function and operator system tables. There are some heuristics included in the conversion rules to better support conventions for the SQL standard native types such as `smallint`, `integer`, and `real`.

The system catalogs store information about which conversions, called *casts*, between data types are valid, and how to perform those conversions. Additional casts can be added by the user with the `CREATE CAST` command. (This is usually done in conjunction with defining new data types. The set of casts between the built-in types has been carefully crafted and should not be altered.)

An additional heuristic is provided in the parser to allow better guesses at proper behavior for SQL standard types. There are several basic *type categories* defined: `boolean`, `numeric`, `string`, `bitstring`, `datetime`, `timespan`, `geometric`, `network`, and user-defined. Each category, with the exception of user-defined, has a *preferred type* which is preferentially selected when there is ambiguity. In the user-defined category, each type is its own preferred type. Ambiguous expressions (those with multiple candidate parsing solutions) can often be resolved when there are multiple possible built-in types, but they will raise an error when there are multiple choices for user-defined types.

All type conversion rules are designed with several principles in mind:

- Implicit conversions should never have surprising or unpredictable outcomes.
- User-defined types, of which the parser has no *a priori* knowledge, should be "higher" in the type hierarchy. In mixed-type expressions, native types shall always be converted to a user-defined type (of course, only if conversion is necessary).
- User-defined types are not related. Currently, PostgreSQL does not have information available to it on relationships between types, other than hardcoded heuristics for built-in types and implicit relationships based on available functions in the catalog.
- There should be no extra overhead from the parser or executor if a query does not need implicit type conversion. That is, if a query is well formulated and the types already match up, then the query should proceed without spending extra time in the parser and without introducing unnecessary implicit conversion functions into the query.

  Additionally, if a query usually requires an implicit conversion for a function, and if then the user defines an explicit function with the correct argument types, the parser should use this new function and will no longer do the implicit conversion using the old function.

7.2. Operators

The operand types of an operator invocation are resolved following the procedure below. Note that this procedure is indirectly affected by the precedence of the involved operators. See Section 1.1.6, "Lexical Precedence" for more information.

Operand Type Resolution

1. Select the operators to be considered from the `pg_operator` system catalog. If an unqualified operator name is used (the usual case), the operators considered are those of the right name and argument count that are visible in the current search path (see Section 2.8.3, "The Schema Search Path"). If a qualified operator name was given, only operators in the specified schema are considered.

- (Optional) If the search path finds multiple operators of identical argument types, only the one appearing earliest in the path is considered. But operators of different argument types are considered on an equal footing regardless of search path position.

2. Check for an operator accepting exactly the input argument types. If one exists (there can be only one exact match in the set of operators considered), use it.

   - (Optional) If one argument of a binary operator is `unknown` type, then assume it is the same type as the other argument for this check. Other cases involving `unknown` will never find a match at this step.

3. Look for the best match.

   a. Discard candidate operators for which the input types do not match and cannot be coerced (using an implicit coercion function) to match. `unknown` literals are assumed to be coercible to anything for this purpose. If only one candidate remains, use it; else continue to the next step.

   b. Run through all candidates and keep those with the most exact matches on input types. Keep all candidates if none have any exact matches. If only one candidate remains, use it; else continue to the next step.

   c. Run through all candidates and keep those with the most exact or binary-compatible matches on input types. Keep all candidates if none have any exact or binary-compatible matches. If only one candidate remains, use it; else continue to the next step.

   d. Run through all candidates and keep those that accept preferred types at the most positions where type coercion will be required. Keep all candidates if none accept preferred types. If only one candidate remains, use it; else continue to the next step.

   e. If any input arguments are “unknown”, check the type categories accepted at those argument positions by the remaining candidates. At each position, select the "string" category if any candidate accepts that category (this bias towards string is appropriate since an unknown-type literal does look like a string). Otherwise, if all the remaining candidates accept the same type category, select that category; otherwise fail because the correct choice cannot be deduced without more clues. Also note whether any of the candidates accept a preferred data type within the selected category. Now discard operator candidates that do not accept the selected type category; furthermore, if any candidate accepts a preferred type at a given argument position, discard candidates that accept non-preferred types for that argument.

   f. If only one candidate remains, use it. If no candidate or more than one candidate remains, then fail.

Examples

Example 7.1. Exponentiation Operator Type Resolution

There is only one exponentiation operator defined in the catalog, and it takes arguments of type `double precision`. The scanner assigns an initial type of `integer` to both arguments of this query expression:

```
tgl=> SELECT 2 ^ 3 AS "Exp";
 Exp
-----
   8
(1 row)
```

So the parser does a type conversion on both operands and the query is equivalent to

```
tgl=> SELECT CAST(2 AS double precision) ^ CAST(3 AS double
 precision) AS "Exp";
 Exp
-----
   8
(1 row)
```

or

```
tgl=> SELECT 2.0 ^ 3.0 AS "Exp";
 Exp
-----
   8
(1 row)
```

Note

This last form has the least overhead, since no functions are called to do implicit type conversion. This is not an issue for small queries, but may have an impact on the performance of queries involving large tables.

Example 7.2. String Concatenation Operator Type Resolution

A string-like syntax is used for working with string types as well as for working with complex extended types. Strings with unspecified type are matched with likely operator candidates.

An example with one unspecified argument:

```
tgl=> SELECT text 'abc' || 'def' AS "Text and Unknown";
 Text and Unknown
------------------
 abcdef
(1 row)
```

In this case the parser looks to see if there is an operator taking `text` for both arguments. Since there is, it assumes that the second argument should be interpreted as of type `text`.

Concatenation on unspecified types:

```
tgl=> SELECT 'abc' || 'def' AS "Unspecified";
 Unspecified
-------------
 abcdef
(1 row)
```

In this case there is no initial hint for which type to use, since no types are specified in the query. So, the parser looks for all candidate operators and finds that there are candidates accepting both string-category and bit-string-category inputs. Since string category is preferred when available, that category is selected, and then the “preferred type” for strings, `text`, is used as the specific type to resolve the unknown literals to.

Example 7.3. Absolute-Value and Factorial Operator Type Resolution

The PostgreSQL operator catalog has several entries for the prefix operator `@`, all of which implement absolute-value operations for various numeric data types. One of these entries is for type `float8`, which is the preferred type in the numeric category. Therefore, PostgreSQL will use that entry when faced with a non-numeric input:

```
tgl=> select @ text '-4.5' as "abs";
```

```
 abs
-----
 4.5
(1 row)
```

Here the system has performed an implicit text-to-float8 conversion before applying the chosen operator. We can verify that float8 and not some other type was used:

```
tgl=> select @ text '-4.5e500' as "abs";
ERROR:  Input '-4.5e500' is out of range for float8
```

On the other hand, the postfix operator `!` (factorial) is defined only for integer data types, not for float8. So, if we try a similar case with `!`, we get:

```
tgl=> select text '20' ! as "factorial";
ERROR:  Unable to identify a postfix operator '!' for type 'text'
        You may need to add parentheses or an explicit cast
```

This happens because the system can't decide which of the several possible `!` operators should be preferred. We can help it out with an explicit cast:

```
tgl=> select cast(text '20' as int8) ! as "factorial";
      factorial
---------------------
 2432902008176640000
(1 row)
```

7.3. Functions

The argument types of function calls are resolved according to the following steps.

Function Argument Type Resolution

1. Select the functions to be considered from the `pg_proc` system catalog. If an unqualified function name is used, the functions considered are those of the right name and argument count that are visible in the current search path (see Section 2.8.3, “The Schema Search Path”). If a qualified function name was given, only functions in the specified schema are considered.

    - (Optional) If the search path finds multiple functions of identical argument types, only the one appearing earliest in the path is considered. But functions of different argument types are considered on an equal footing regardless of search path position.

2. Check for a function accepting exactly the input argument types. If one exists (there can be only one exact match in the set of functions considered), use it. (Cases involving `unknown` will never find a match at this step.)

3. If no exact match is found, see whether the function call appears to be a trivial type coercion request. This happens if the function call has just one argument and the function name is the same as the (internal) name of some data type. Furthermore, the function argument must be either an unknown-type literal or a type that is binary-compatible with the named data type. When these conditions are met, the function argument is coerced to the named data type without any explicit function call.

4. Look for the best match.

    a. Discard candidate functions for which the input types do not match and cannot be coerced (using an implicit coercion function) to match. `unknown` literals are assumed to be coercible to anything for this purpose. If only one candidate remains, use it; else continue to the next step.

b. Run through all candidates and keep those with the most exact matches on input types. Keep all candidates if none have any exact matches. If only one candidate remains, use it; else continue to the next step.

c. Run through all candidates and keep those with the most exact or binary-compatible matches on input types. Keep all candidates if none have any exact or binary-compatible matches. If only one candidate remains, use it; else continue to the next step.

d. Run through all candidates and keep those that accept preferred types at the most positions where type coercion will be required. Keep all candidates if none accept preferred types. If only one candidate remains, use it; else continue to the next step.

e. If any input arguments are `unknown`, check the type categories accepted at those argument positions by the remaining candidates. At each position, select the `string` category if any candidate accepts that category (this bias towards string is appropriate since an unknown-type literal does look like a string). Otherwise, if all the remaining candidates accept the same type category, select that category; otherwise fail because the correct choice cannot be deduced without more clues. Also note whether any of the candidates accept a preferred data type within the selected category. Now discard candidates that do not accept the selected type category; furthermore, if any candidate accepts a preferred type at a given argument position, discard candidates that accept non-preferred types for that argument.

f. If only one candidate remains, use it. If no candidate or more than one candidate remains, then fail.

Examples

Example 7.4. Factorial Function Argument Type Resolution

There is only one `int4fac` function defined in the `pg_proc` catalog. So the following query automatically converts the `int2` argument to `int4`:

```
tgl=> SELECT int4fac(int2 '4');
 int4fac
---------
      24
(1 row)
```

and is actually transformed by the parser to

```
tgl=> SELECT int4fac(int4(int2 '4'));
 int4fac
---------
      24
(1 row)
```

Example 7.5. Substring Function Type Resolution

There are two `substr` functions declared in `pg_proc`. However, only one takes two arguments, of types `text` and `int4`.

If called with a string constant of unspecified type, the type is matched up directly with the only candidate function type:

```
tgl=> SELECT substr('1234', 3);
 substr
--------
     34
```

```
(1 row)
```

If the string is declared to be of type `varchar`, as might be the case if it comes from a table, then the parser will try to coerce it to become `text`:

```
tgl=> SELECT substr(varchar '1234', 3);
 substr
--------
     34
(1 row)
```

which is transformed by the parser to become

```
tgl=> SELECT substr(text(varchar '1234'), 3);
 substr
--------
     34
(1 row)
```

Note

Actually, the parser is aware that `text` and `varchar` are *binary-compatible*, meaning that one can be passed to a function that accepts the other without doing any physical conversion. Therefore, no explicit type conversion call is really inserted in this case.

And, if the function is called with an `int4`, the parser will try to convert that to `text`:

```
tgl=> SELECT substr(1234, 3);
 substr
--------
     34
(1 row)
```

which actually executes as

```
tgl=> SELECT substr(text(1234), 3);
 substr
--------
     34
(1 row)
```

This succeeds because there is a conversion function text(int4) in the system catalog.

7.4. Query Targets

Values to be inserted into a table are coerced to the destination column's data type according to the following steps.

Query Target Type Resolution

1. Check for an exact match with the target.

2. Otherwise, try to coerce the expression to the target type. This will succeed if the two types are known binary-compatible, or if there is a conversion function. If the expression is an unknown-type literal, the contents of the literal string will be fed to the input conversion routine for the target type.

3. If the target is a fixed-length type (e.g. `char` or `varchar` declared with a length) then try to find a sizing function for the target type. A sizing function is a function of the same name as

the type, taking two arguments of which the first is that type and the second is an integer, and returning the same type. If one is found, it is applied, passing the column's declared length as the second parameter.

Example 7.6. `character` Storage Type Conversion

For a target column declared as `character(20)` the following query ensures that the target is sized correctly:

```
tgl=> CREATE TABLE vv (v character(20));
CREATE
tgl=> INSERT INTO vv SELECT 'abc' || 'def';
INSERT 392905 1
tgl=> SELECT v, length(v) FROM vv;
          v           | length
----------------------+--------
 abcdef               |     20
(1 row)
```

What has really happened here is that the two unknown literals are resolved to `text` by default, allowing the `||` operator to be resolved as `text` concatenation. Then the `text` result of the operator is coerced to `bpchar` ("blank-padded char", the internal name of the character data type) to match the target column type. (Since the parser knows that `text` and `bpchar` are binary-compatible, this coercion is implicit and does not insert any real function call.) Finally, the sizing function `bpchar(bpchar, integer)` is found in the system catalogs and applied to the operator's result and the stored column length. This type-specific function performs the required length check and addition of padding spaces.

7.5. `UNION` and `CASE` Constructs

SQL `UNION` constructs must match up possibly dissimilar types to become a single result set. The resolution algorithm is applied separately to each output column of a union query. The `INTERSECT` and `EXCEPT` constructs resolve dissimilar types in the same way as `UNION`. A `CASE` construct also uses the identical algorithm to match up its component expressions and select a result data type.

`UNION` and `CASE` Type Resolution

1. If all inputs are of type `unknown`, resolve as type `text` (the preferred type for string category). Otherwise, ignore the `unknown` inputs while choosing the type.

2. If the non-unknown inputs are not all of the same type category, fail.

3. Choose the first non-unknown input type which is a preferred type in that category or allows all the non-unknown inputs to be implicitly coerced to it.

4. Coerce all inputs to the selected type.

Examples

Example 7.7. Underspecified Types in a Union

```
tgl=> SELECT text 'a' AS "Text" UNION SELECT 'b';
 Text
------
 a
 b
(2 rows)
```

Here, the unknown-type literal `'b'` will be resolved as type text.

Example 7.8. Type Conversion in a Simple Union

```
tgl=> SELECT 1.2 AS "Numeric" UNION SELECT 1;
 Numeric
---------
       1
     1.2
(2 rows)
```

The literal `1.2` is of type `numeric`, and the integer value `1` can be cast implicitly to `numeric`, so that type is used.

Example 7.9. Type Conversion in a Transposed Union

```
tgl=> SELECT 1 AS "Real"
tgl-> UNION SELECT CAST('2.2' AS REAL);
 Real
------
    1
  2.2
(2 rows)
```

Here, since type `real` cannot be implicitly cast to `integer`, but `integer` can be implicitly cast to `real`, the union result type is resolved as `real`.

Chapter 8. Indexes

Indexes are a common way to enhance database performance. An index allows the database server to find and retrieve specific rows much faster than it could do without an index. But indexes also add overhead to the database system as a whole, so they should be used sensibly.

8.1. Introduction

The classical example for the need of an index is if there is a table similar to this:

```
CREATE TABLE test1 (
    id integer,
    content varchar
);
```

and the application requires a lot of queries of the form

```
SELECT content FROM test1 WHERE id = constant;
```

Ordinarily, the system would have to scan the entire `test1` table row by row to find all matching entries. If there are a lot of rows in `test1` and only a few rows (possibly zero or one) returned by the query, then this is clearly an inefficient method. If the system were instructed to maintain an index on the `id` column, then it could use a more efficient method for locating matching rows. For instance, it might only have to walk a few levels deep into a search tree.

A similar approach is used in most books of non-fiction: Terms and concepts that are frequently looked up by readers are collected in an alphabetic index at the end of the book. The interested reader can scan the index relatively quickly and flip to the appropriate page, and would not have to read the entire book to find the interesting location. As it is the task of the author to anticipate the items that the readers are most likely to look up, it is the task of the database programmer to foresee which indexes would be of advantage.

The following command would be used to create the index on the `id` column, as discussed:

```
CREATE INDEX test1_id_index ON test1 (id);
```

The name `test1_id_index` can be chosen freely, but you should pick something that enables you to remember later what the index was for.

To remove an index, use the `DROP INDEX` command. Indexes can be added to and removed from tables at any time.

Once the index is created, no further intervention is required: the system will use the index when it thinks it would be more efficient than a sequential table scan. But you may have to run the `ANALYZE` command regularly to update statistics to allow the query planner to make educated decisions. Also read Chapter 10, *Performance Tips* for information about how to find out whether an index is used and when and why the planner may choose to *not* use an index.

Indexes can benefit `UPDATE`s and `DELETE`s with search conditions. Indexes can also be used in join queries. Thus, an index defined on a column that is part of a join condition can significantly speed up queries with joins.

When an index is created, the system has to keep it synchronized with the table. This adds overhead to data manipulation operations. Therefore indexes that are non-essential or do not get used at all should be removed. Note that a query or data manipulation command can use at most one index per table.

8.2. Index Types

PostgreSQL provides several index types: B-tree, R-tree, GiST, and Hash. Each index type is more appropriate for a particular query type because of the algorithm it uses. By default, the `CREATE`

INDEX command will create a B-tree index, which fits the most common situations. In particular, the PostgreSQL query optimizer will consider using a B-tree index whenever an indexed column is involved in a comparison using one of these operators: <, <=, =, >=, >

R-tree indexes are especially suited for spatial data. To create an R-tree index, use a command of the form

```
CREATE INDEX name ON table USING RTREE (column);
```

The PostgreSQL query optimizer will consider using an R-tree index whenever an indexed column is involved in a comparison using one of these operators: <<, &<, &>, >>, @, ~=, && (Refer to Section 6.9, "Geometric Functions and Operators" about the meaning of these operators.)

The query optimizer will consider using a hash index whenever an indexed column is involved in a comparison using the = operator. The following command is used to create a hash index:

```
CREATE INDEX name ON table USING HASH (column);
```

Note

Testing has shown PostgreSQL's hash indexes to be similar or slower than B-tree indexes, and the index size and build time for hash indexes is much worse. Hash indexes also suffer poor performance under high concurrency. For these reasons, hash index use is discouraged.

The B-tree index is an implementation of Lehman-Yao high-concurrency B-trees. The R-tree index method implements standard R-trees using Guttman's quadratic split algorithm. The hash index is an implementation of Litwin's linear hashing. We mention the algorithms used solely to indicate that all of these access methods are fully dynamic and do not have to be optimized periodically (as is the case with, for example, static hash access methods).

8.3. Multicolumn Indexes

An index can be defined on more than one column. For example, if you have a table of this form:

```
CREATE TABLE test2 (
  major int,
  minor int,
  name varchar
);
```

(Say, you keep your /dev directory in a database...) and you frequently make queries like

```
SELECT name FROM test2 WHERE major = constant AND minor = constant;
```

then it may be appropriate to define an index on the columns major and minor together, e.g.,

```
CREATE INDEX test2_mm_idx ON test2 (major, minor);
```

Currently, only the B-tree and GiST implementations support multicolumn indexes. Up to 32 columns may be specified. (This limit can be altered when building PostgreSQL; see the file pg_config.h.)

The query optimizer can use a multicolumn index for queries that involve the first *n* consecutive columns in the index (when used with appropriate operators), up to the total number of columns specified in the index definition. For example, an index on (a, b, c) can be used in queries involving all of a, b, and c, or in queries involving both a and b, or in queries involving only a, but not in other combinations. (In a query involving a and c the optimizer might choose to use the index for a only and treat c like an ordinary unindexed column.)

Multicolumn indexes can only be used if the clauses involving the indexed columns are joined with AND. For instance,

```
SELECT name FROM test2 WHERE major = constant OR minor = constant;
```

cannot make use of the index `test2_mm_idx` defined above to look up both columns. (It can be used to look up only the `major` column, however.)

Multicolumn indexes should be used sparingly. Most of the time, an index on a single column is sufficient and saves space and time. Indexes with more than three columns are almost certainly inappropriate.

8.4. Unique Indexes

Indexes may also be used to enforce uniqueness of a column's value, or the uniqueness of the combined values of more than one column.

```
CREATE UNIQUE INDEX name ON table (column [, ...]);
```

Currently, only B-tree indexes can be declared unique.

When an index is declared unique, multiple table rows with equal indexed values will not be allowed. NULL values are not considered equal.

PostgreSQL automatically creates unique indexes when a table is declared with a unique constraint or a primary key, on the columns that make up the primary key or unique columns (a multicolumn index, if appropriate), to enforce that constraint. A unique index can be added to a table at any later time, to add a unique constraint.

Note

The preferred way to add a unique constraint to a table is `ALTER TABLE ... ADD CONSTRAINT`. The use of indexes to enforce unique constraints could be considered an implementation detail that should not be accessed directly.

8.5. Functional Indexes

For a *functional index*, an index is defined on the result of a function applied to one or more columns of a single table. Functional indexes can be used to obtain fast access to data based on the result of function calls.

For example, a common way to do case-insensitive comparisons is to use the `lower` function:

```
SELECT * FROM test1 WHERE lower(col1) = 'value';
```

This query can use an index, if one has been defined on the result of the `lower(column)` operation:

```
CREATE INDEX test1_lower_col1_idx ON test1 (lower(col1));
```

The function in the index definition can take more than one argument, but they must be table columns, not constants. Functional indexes are always single-column (namely, the function result) even if the function uses more than one input field; there cannot be multicolumn indexes that contain function calls.

Tip

The restrictions mentioned in the previous paragraph can easily be worked around by defining a custom function to use in the index definition that computes any desired result internally.

8.6. Operator Classes

An index definition may specify an *operator class* for each column of an index.

```
CREATE INDEX name ON table (column opclass [, ...]);
```

The operator class identifies the operators to be used by the index for that column. For example, a B-tree index on four-byte integers would use the `int4_ops` class; this operator class includes comparison functions for four-byte integers. In practice the default operator class for the column's data type is usually sufficient. The main point of having operator classes is that for some data types, there could be more than one meaningful ordering. For example, we might want to sort a complex-number data type either by absolute value or by real part. We could do this by defining two operator classes for the data type and then selecting the proper class when making an index. There are also some operator classes with special purposes:

- The operator classes `box_ops` and `bigbox_ops` both support R-tree indexes on the `box` data type. The difference between them is that `bigbox_ops` scales box coordinates down, to avoid floating-point exceptions from doing multiplication, addition, and subtraction on very large floating-point coordinates. If the field on which your rectangles lie is about 20 000 units square or larger, you should use `bigbox_ops`.

The following query shows all defined operator classes:

```
SELECT am.amname AS acc_method,
       opc.opcname AS ops_name
    FROM pg_am am, pg_opclass opc
    WHERE opc.opcamid = am.oid
    ORDER BY acc_method, ops_name;
```

It can be extended to show all the operators included in each class:

```
SELECT am.amname AS acc_method,
       opc.opcname AS ops_name,
       opr.oprname AS ops_comp
    FROM pg_am am, pg_opclass opc, pg_amop amop, pg_operator opr
    WHERE opc.opcamid = am.oid AND
          amop.amopclaid = opc.oid AND
          amop.amopopr = opr.oid
    ORDER BY acc_method, ops_name, ops_comp;
```

8.7. Partial Indexes

A *partial index* is an index built over a subset of a table; the subset is defined by a conditional expression (called the *predicate* of the partial index). The index contains entries for only those table rows that satisfy the predicate.

A major motivation for partial indexes is to avoid indexing common values. Since a query searching for a common value (one that accounts for more than a few percent of all the table rows) will not use the index anyway, there is no point in keeping those rows in the index at all. This reduces the size of the index, which will speed up queries that do use the index. It will also speed up many table update operations because the index does not need to be updated in all cases. Example 8.1, “Setting up a Partial Index to Exclude Common Values” shows a possible application of this idea.

Example 8.1. Setting up a Partial Index to Exclude Common Values

Suppose you are storing web server access logs in a database. Most accesses originate from the IP range of your organization but some are from elsewhere (say, employees on dial-up connections). If your searches by IP are primarily for outside accesses, you probably do not need to index the IP range that corresponds to your organization's subnet.

Assume a table like this:

```
CREATE TABLE access_log (
    url varchar,
    client_ip inet,
    ...
);
```

To create a partial index that suits our example, use a command such as this:

```
CREATE INDEX access_log_client_ip_ix ON access_log (client_ip)
    WHERE NOT (client_ip > inet '192.168.100.0' AND client_ip <
 inet '192.168.100.255');
```

A typical query that can use this index would be:

```
SELECT * FROM access_log WHERE url = '/index.html' AND client_ip =
 inet '212.78.10.32';
```

A query that cannot use this index is:

```
SELECT * FROM access_log WHERE client_ip = inet '192.168.100.23';
```

Observe that this kind of partial index requires that the common values be predetermined. If the distribution of values is inherent (due to the nature of the application) and static (not changing over time), this is not difficult, but if the common values are merely due to the coincidental data load this can require a lot of maintenance work.

Another possibility is to exclude values from the index that the typical query workload is not interested in; this is shown in Example 8.2, “Setting up a Partial Index to Exclude Uninteresting Values”. This results in the same advantages as listed above, but it prevents the “uninteresting” values from being accessed via that index at all, even if an index scan might be profitable in that case. Obviously, setting up partial indexes for this kind of scenario will require a lot of care and experimentation.

Example 8.2. Setting up a Partial Index to Exclude Uninteresting Values

If you have a table that contains both billed and unbilled orders, where the unbilled orders take up a small fraction of the total table and yet those are the most-accessed rows, you can improve performance by creating an index on just the unbilled rows. The command to create the index would look like this:

```
CREATE INDEX orders_unbilled_index ON orders (order_nr)
    WHERE billed is not true;
```

A possible query to use this index would be

```
SELECT * FROM orders WHERE billed is not true AND order_nr < 10000;
```

However, the index can also be used in queries that do not involve `order_nr` at all, e.g.,

```
SELECT * FROM orders WHERE billed is not true AND amount > 5000.00;
```

This is not as efficient as a partial index on the `amount` column would be, since the system has to scan the entire index. Yet, if there are relatively few unbilled orders, using this partial index just to find the unbilled orders could be a win.

Note that this query cannot use this index:

```
SELECT * FROM orders WHERE order_nr = 3501;
```

The order 3501 may be among the billed or among the unbilled orders.

Example 8.2, “Setting up a Partial Index to Exclude Uninteresting Values” also illustrates that the indexed column and the column used in the predicate do not need to match. PostgreSQL supports

partial indexes with arbitrary predicates, so long as only columns of the table being indexed are involved. However, keep in mind that the predicate must match the conditions used in the queries that are supposed to benefit from the index. To be precise, a partial index can be used in a query only if the system can recognize that the query's WHERE condition mathematically *implies* the index's predicate. PostgreSQL does not have a sophisticated theorem prover that can recognize mathematically equivalent predicates that are written in different forms. (Not only is such a general theorem prover extremely difficult to create, it would probably be too slow to be of any real use.) The system can recognize simple inequality implications, for example "x < 1" implies "x < 2"; otherwise the predicate condition must exactly match the query's WHERE condition or the index will not be recognized to be usable.

A third possible use for partial indexes does not require the index to be used in queries at all. The idea here is to create a unique index over a subset of a table, as in Example 8.3, "Setting up a Partial Unique Index". This enforces uniqueness among the rows that satisfy the index predicate, without constraining those that do not.

Example 8.3. Setting up a Partial Unique Index

Suppose that we have a table describing test outcomes. We wish to ensure that there is only one "successful" entry for a given subject and target combination, but there might be any number of "unsuccessful" entries. Here is one way to do it:

```
CREATE TABLE tests (subject text,
                    target text,
                    success bool,
                    ...);
CREATE UNIQUE INDEX tests_success_constraint ON tests (subject,
 target)
    WHERE success;
```

This is a particularly efficient way of doing it when there are few successful trials and many unsuccessful ones.

Finally, a partial index can also be used to override the system's query plan choices. It may occur that data sets with peculiar distributions will cause the system to use an index when it really should not. In that case the index can be set up so that it is not available for the offending query. Normally, PostgreSQL makes reasonable choices about index usage (e.g., it avoids them when retrieving common values, so the earlier example really only saves index size, it is not required to avoid index usage), and grossly incorrect plan choices are cause for a bug report.

Keep in mind that setting up a partial index indicates that you know at least as much as the query planner knows, in particular you know when an index might be profitable. Forming this knowledge requires experience and understanding of how indexes in PostgreSQL work. In most cases, the advantage of a partial index over a regular index will not be much.

More information about partial indexes can be found in [ston89b], [olson93], and [seshadri95].

8.8. Examining Index Usage

Although indexes in PostgreSQL do not need maintenance and tuning, it is still important to check which indexes are actually used by the real-life query workload. Examining index usage is done with the `EXPLAIN` command; its application for this purpose is illustrated in Section 10.1, "Using `EXPLAIN`".

It is difficult to formulate a general procedure for determining which indexes to set up. There are a number of typical cases that have been shown in the examples throughout the previous sections. A good deal of experimentation will be necessary in most cases. The rest of this section gives some tips for that.

- Always run `ANALYZE` first. This command collects statistics about the distribution of the values in the table. This information is required to guess the number of rows returned by a query, which is needed by the planner to assign realistic costs to each possible query plan. In absence of any real statistics, some default values are assumed, which are almost certain to be inaccurate. Examining an application's index usage without having run `ANALYZE` is therefore a lost cause.

- Use real data for experimentation. Using test data for setting up indexes will tell you what indexes you need for the test data, but that is all.

  It is especially fatal to use proportionally reduced data sets. While selecting 1000 out of 100000 rows could be a candidate for an index, selecting 1 out of 100 rows will hardly be, because the 100 rows will probably fit within a single disk page, and there is no plan that can beat sequentially fetching 1 disk page.

  Also be careful when making up test data, which is often unavoidable when the application is not in production use yet. Values that are very similar, completely random, or inserted in sorted order will skew the statistics away from the distribution that real data would have.

- When indexes are not used, it can be useful for testing to force their use. There are run-time parameters that can turn off various plan types (described in the PostgreSQL 7.3.21 Administrator's Guide). For instance, turning off sequential scans (`enable_seqscan`) and nested-loop joins (`enable_nestloop`), which are the most basic plans, will force the system to use a different plan. If the system still chooses a sequential scan or nested-loop join then there is probably a more fundamental problem for why the index is not used, for example, the query condition does not match the index. (What kind of query can use what kind of index is explained in the previous sections.)

- If forcing index usage does use the index, then there are two possibilities: Either the system is right and using the index is indeed not appropriate, or the cost estimates of the query plans are not reflecting reality. So you should time your query with and without indexes. The `EXPLAIN ANALYZE` command can be useful here.

- If it turns out that the cost estimates are wrong, there are, again, two possibilities. The total cost is computed from the per-row costs of each plan node times the selectivity estimate of the plan node. The costs of the plan nodes can be tuned with run-time parameters (described in the PostgreSQL 7.3.21 Administrator's Guide). An inaccurate selectivity estimate is due to insufficient statistics. It may be possible to help this by tuning the statistics-gathering parameters (see `ALTER TABLE` reference).

  If you do not succeed in adjusting the costs to be more appropriate, then you may have to resort to forcing index usage explicitly. You may also want to contact the PostgreSQL developers to examine the issue.

Chapter 9. Concurrency Control

This chapter describes the behavior of the PostgreSQL database system when two or more sessions try to access the same data at the same time. The goals in that situation are to allow efficient access for all sessions while maintaining strict data integrity. Every developer of database applications should be familiar with the topics covered in this chapter.

9.1. Introduction

Unlike traditional database systems which use locks for concurrency control, PostgreSQL maintains data consistency by using a multiversion model (Multiversion Concurrency Control, MVCC). This means that while querying a database each transaction sees a snapshot of data (a *database version*) as it was some time ago, regardless of the current state of the underlying data. This protects the transaction from viewing inconsistent data that could be caused by (other) concurrent transaction updates on the same data rows, providing *transaction isolation* for each database session.

The main difference between multiversion and lock models is that in MVCC locks acquired for querying (reading) data don't conflict with locks acquired for writing data, and so reading never blocks writing and writing never blocks reading.

Table- and row-level locking facilities are also available in PostgreSQL for applications that cannot adapt easily to MVCC behavior. However, proper use of MVCC will generally provide better performance than locks.

9.2. Transaction Isolation

The SQL standard defines four levels of transaction isolation in terms of three phenomena that must be prevented between concurrent transactions. These undesirable phenomena are:

dirty read

A transaction reads data written by a concurrent uncommitted transaction.

nonrepeatable read

A transaction re-reads data it has previously read and finds that data has been modified by another transaction (that committed since the initial read).

phantom read

A transaction re-executes a query returning a set of rows that satisfy a search condition and finds that the set of rows satisfying the condition has changed due to another recently-committed transaction.

The four transaction isolation levels and the corresponding behaviors are described in Table 9.1, “Isolation Levels”.

Table 9.1. SQL Transaction Isolation Levels

Isolation Level	Dirty Read	Nonrepeatable Read	Phantom Read
Read uncommitted	Possible	Possible	Possible
Read committed	Not possible	Possible	Possible
Repeatable read	Not possible	Not possible	Possible
Serializable	Not possible	Not possible	Not possible

PostgreSQL offers the read committed and serializable isolation levels.

9.2.1. Read Committed Isolation Level

Read Committed is the default isolation level in PostgreSQL. When a transaction runs on this isolation level, a `SELECT` query sees only data committed before the query began; it never sees either uncommitted data or changes committed during query execution by concurrent transactions. (However, the `SELECT` does see the effects of previous updates executed within its own transaction, even though they are not yet committed.) In effect, a `SELECT` query sees a snapshot of the database as of the instant that that query begins to run. Notice that two successive `SELECT`s can see different data, even though they are within a single transaction, if other transactions commit changes during execution of the first `SELECT`.

`UPDATE`, `DELETE`, and `SELECT FOR UPDATE` commands behave the same as `SELECT` in terms of searching for target rows: they will only find target rows that were committed as of the query start time. However, such a target row may have already been updated (or deleted or marked for update) by another concurrent transaction by the time it is found. In this case, the would-be updater will wait for the first updating transaction to commit or roll back (if it is still in progress). If the first updater rolls back, then its effects are negated and the second updater can proceed with updating the originally found row. If the first updater commits, the second updater will ignore the row if the first updater deleted it, otherwise it will attempt to apply its operation to the updated version of the row. The query search condition (`WHERE` clause) is re-evaluated to see if the updated version of the row still matches the search condition. If so, the second updater proceeds with its operation, starting from the updated version of the row.

Because of the above rule, it is possible for updating queries to see inconsistent snapshots --- they can see the effects of concurrent updating queries that affected the same rows they are trying to update, but they do not see effects of those queries on other rows in the database. This behavior makes Read Committed mode unsuitable for queries that involve complex search conditions. However, it is just right for simpler cases. For example, consider updating bank balances with transactions like

```
BEGIN;
UPDATE accounts SET balance = balance + 100.00 WHERE acctnum =
 12345;
UPDATE accounts SET balance = balance - 100.00 WHERE acctnum =
 7534;
COMMIT;
```

If two such transactions concurrently try to change the balance of account 12345, we clearly want the second transaction to start from the updated version of the account's row. Because each query is affecting only a predetermined row, letting it see the updated version of the row does not create any troublesome inconsistency.

Since in Read Committed mode each new query starts with a new snapshot that includes all transactions committed up to that instant, subsequent queries in the same transaction will see the effects of the committed concurrent transaction in any case. The point at issue here is whether or not within a *single* query we see an absolutely consistent view of the database.

The partial transaction isolation provided by Read Committed mode is adequate for many applications, and this mode is fast and simple to use. However, for applications that do complex queries and updates, it may be necessary to guarantee a more rigorously consistent view of the database than the Read Committed mode provides.

9.2.2. Serializable Isolation Level

Serializable provides the strictest transaction isolation. This level emulates serial transaction execution, as if transactions had been executed one after another, serially, rather than concurrently. However, applications using this level must be prepared to retry transactions due to serialization failures.

When a transaction is on the serializable level, a SELECT query sees only data committed before the transaction began; it never sees either uncommitted data or changes committed during transaction execution by concurrent transactions. (However, the SELECT does see the effects of previous updates executed within its own transaction, even though they are not yet committed.) This is different from Read Committed in that the SELECT sees a snapshot as of the start of the transaction, not as of the start of the current query within the transaction. Thus, successive SELECTs within a single transaction always see the same data.

UPDATE, DELETE, and SELECT FOR UPDATE commands behave the same as SELECT in terms of searching for target rows: they will only find target rows that were committed as of the transaction start time. However, such a target row may have already been updated (or deleted or marked for update) by another concurrent transaction by the time it is found. In this case, the serializable transaction will wait for the first updating transaction to commit or roll back (if it is still in progress). If the first updater rolls back, then its effects are negated and the serializable transaction can proceed with updating the originally found row. But if the first updater commits (and actually updated or deleted the row, not just selected it for update) then the serializable transaction will be rolled back with the message

```
ERROR:  Can't serialize access due to concurrent update
```

because a serializable transaction cannot modify rows changed by other transactions after the serializable transaction began.

When the application receives this error message, it should abort the current transaction and then retry the whole transaction from the beginning. The second time through, the transaction sees the previously-committed change as part of its initial view of the database, so there is no logical conflict in using the new version of the row as the starting point for the new transaction's update.

Note that only updating transactions may need to be retried --- read-only transactions will never have serialization conflicts.

The Serializable mode provides a rigorous guarantee that each transaction sees a wholly consistent view of the database. However, the application has to be prepared to retry transactions when concurrent updates make it impossible to sustain the illusion of serial execution. Since the cost of redoing complex transactions may be significant, this mode is recommended only when updating transactions contain logic sufficiently complex that they may give wrong answers in Read Committed mode. Most commonly, Serializable mode is necessary when a transaction performs several successive queries that must see identical views of the database.

9.3. Explicit Locking

PostgreSQL provides various lock modes to control concurrent access to data in tables. These modes can be used for application-controlled locking in situations where MVCC does not give the desired behavior. Also, most PostgreSQL commands automatically acquire locks of appropriate modes to ensure that referenced tables are not dropped or modified in incompatible ways while the command executes. (For example, ALTER TABLE cannot be executed concurrently with other operations on the same table.)

9.3.1. Table-Level Locks

The list below shows the available lock modes and the contexts in which they are used automatically by PostgreSQL. Remember that all of these lock modes are table-level locks, even if the name contains the word “row”. The names of the lock modes are historical. To some extent the names reflect the typical usage of each lock mode --- but the semantics are all the same. The only real difference between one lock mode and another is the set of lock modes with which each conflicts. Two transactions cannot hold locks of conflicting modes on the same table at the same time. (However, a transaction never conflicts with itself --- for example, it may acquire ACCESS EXCLUSIVE lock and later acquire ACCESS SHARE lock on the same table.) Non-conflicting lock modes may be held concurrently by many transactions. Notice in particular that some lock modes are self-conflicting (for example, ACCESS EXCLUSIVE cannot be held by more than one transaction at a time) while others are not

self-conflicting (for example, ACCESS SHARE can be held by multiple transactions). Once acquired, a lock mode is held till end of transaction.

To examine a list of the currently outstanding locks in a database server, use the pg_locks system view. For more information on monitoring the status of the lock manager subsystem, refer to the PostgreSQL 7.3.21 Administrator's Guide.

Table-level lock modes

ACCESS SHARE

Conflicts with the ACCESS EXCLUSIVE lock mode only.

The SELECT command acquires a lock of this mode on referenced tables. In general, any query that only reads a table and does not modify it will acquire this lock mode.

ROW SHARE

Conflicts with the EXCLUSIVE and ACCESS EXCLUSIVE lock modes.

The SELECT FOR UPDATE command acquires a lock of this mode on the target table(s) (in addition to ACCESS SHARE locks on any other tables that are referenced but not selected FOR UPDATE).

ROW EXCLUSIVE

Conflicts with the SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE, and ACCESS EXCLUSIVE lock modes.

The commands UPDATE, DELETE, and INSERT acquire this lock mode on the target table (in addition to ACCESS SHARE locks on any other referenced tables). In general, this lock mode will be acquired by any query that modifies the data in a table.

SHARE UPDATE EXCLUSIVE

Conflicts with the SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE, and ACCESS EXCLUSIVE lock modes. This mode protects a table against concurrent schema changes and VACUUM runs.

Acquired by VACUUM (without FULL).

SHARE

Conflicts with the ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE ROW EXCLUSIVE, EXCLUSIVE, and ACCESS EXCLUSIVE lock modes. This mode protects a table against concurrent data changes.

Acquired by CREATE INDEX.

SHARE ROW EXCLUSIVE

Conflicts with the ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE, and ACCESS EXCLUSIVE lock modes.

This lock mode is not automatically acquired by any PostgreSQL command.

EXCLUSIVE

Conflicts with the ROW SHARE, ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE, and ACCESS EXCLUSIVE lock modes. This mode allows only concurrent ACCESS SHARE, i.e., only reads from the table can proceed in parallel with a transaction holding this lock mode.

This lock mode is not automatically acquired by any PostgreSQL command.

`ACCESS EXCLUSIVE`

Conflicts with locks of all modes (`ACCESS SHARE`, `ROW SHARE`, `ROW EXCLUSIVE`, `SHARE UPDATE EXCLUSIVE`, `SHARE`, `SHARE ROW EXCLUSIVE`, `EXCLUSIVE`, and `ACCESS EXCLUSIVE`). This mode guarantees that the holder is the only transaction accessing the table in any way.

Acquired by the `ALTER TABLE`, `DROP TABLE`, and `VACUUM FULL` commands. This is also the default lock mode for `LOCK TABLE` statements that do not specify a mode explicitly.

Note

Only an `ACCESS EXCLUSIVE` lock blocks a `SELECT` (without `FOR UPDATE`) statement.

9.3.2. Row-Level Locks

In addition to table-level locks, there are row-level locks. A row-level lock on a specific row is automatically acquired when the row is updated (or deleted or marked for update). The lock is held until the transaction commits or rolls back. Row-level locks don't affect data querying; they block *writers to the same row* only. To acquire a row-level lock on a row without actually modifying the row, select the row with `SELECT FOR UPDATE`. Note that once a particular row-level lock is acquired, the transaction may update the row multiple times without fear of conflicts.

PostgreSQL doesn't remember any information about modified rows in memory, so it has no limit to the number of rows locked at one time. However, locking a row may cause a disk write; thus, for example, `SELECT FOR UPDATE` will modify selected rows to mark them and so will result in disk writes.

In addition to table and row locks, page-level share/exclusive locks are used to control read/write access to table pages in the shared buffer pool. These locks are released immediately after a tuple is fetched or updated. Application writers normally need not be concerned with page-level locks, but we mention them for completeness.

9.3.3. Deadlocks

Use of explicit locking can cause *deadlocks*, wherein two (or more) transactions each hold locks that the other wants. For example, if transaction 1 acquires an exclusive lock on table A and then tries to acquire an exclusive lock on table B, while transaction 2 has already exclusive-locked table B and now wants an exclusive lock on table A, then neither one can proceed. PostgreSQL automatically detects deadlock situations and resolves them by aborting one of the transactions involved, allowing the other(s) to complete. (Exactly which transaction will be aborted is difficult to predict and should not be relied on.)

The best defense against deadlocks is generally to avoid them by being certain that all applications using a database acquire locks on multiple objects in a consistent order. One should also ensure that the first lock acquired on an object in a transaction is the highest mode that will be needed for that object. If it is not feasible to verify this in advance, then deadlocks may be handled on-the-fly by retrying transactions that are aborted due to deadlock.

So long as no deadlock situation is detected, a transaction seeking either a table-level or row-level lock will wait indefinitely for conflicting locks to be released. This means it is a bad idea for applications to hold transactions open for long periods of time (e.g., while waiting for user input).

9.4. Data Consistency Checks at the Application Level

Because readers in PostgreSQL don't lock data, regardless of transaction isolation level, data read by one transaction can be overwritten by another concurrent transaction. In other words, if a row

is returned by SELECT it doesn't mean that the row is still current at the instant it is returned (i.e., sometime after the current query began). The row might have been modified or deleted by an already-committed transaction that committed after this one started. Even if the row is still valid "now", it could be changed or deleted before the current transaction does a commit or rollback.

Another way to think about it is that each transaction sees a snapshot of the database contents, and concurrently executing transactions may very well see different snapshots. So the whole concept of "now" is somewhat suspect anyway. This is not normally a big problem if the client applications are isolated from each other, but if the clients can communicate via channels outside the database then serious confusion may ensue.

To ensure the current validity of a row and protect it against concurrent updates one must use SELECT FOR UPDATE or an appropriate LOCK TABLE statement. (SELECT FOR UPDATE locks just the returned rows against concurrent updates, while LOCK TABLE locks the whole table.) This should be taken into account when porting applications to PostgreSQL from other environments.

Note

Before version 6.5 PostgreSQL used read locks, and so the above consideration is also the case when upgrading from PostgreSQL versions prior to 6.5.

Global validity checks require extra thought under MVCC. For example, a banking application might wish to check that the sum of all credits in one table equals the sum of debits in another table, when both tables are being actively updated. Comparing the results of two successive SELECT SUM(...) commands will not work reliably under Read Committed mode, since the second query will likely include the results of transactions not counted by the first. Doing the two sums in a single serializable transaction will give an accurate picture of the effects of transactions that committed before the serializable transaction started --- but one might legitimately wonder whether the answer is still relevant by the time it is delivered. If the serializable transaction itself applied some changes before trying to make the consistency check, the usefulness of the check becomes even more debatable, since now it includes some but not all post-transaction-start changes. In such cases a careful person might wish to lock all tables needed for the check, in order to get an indisputable picture of current reality. A SHARE mode (or higher) lock guarantees that there are no uncommitted changes in the locked table, other than those of the current transaction.

Note also that if one is relying on explicit locks to prevent concurrent changes, one should use Read Committed mode, or in Serializable mode be careful to obtain the lock(s) before performing queries. An explicit lock obtained in a serializable transaction guarantees that no other transactions modifying the table are still running --- but if the snapshot seen by the transaction predates obtaining the lock, it may predate some now-committed changes in the table. A serializable transaction's snapshot is actually frozen at the start of its first query (SELECT, INSERT, UPDATE, or DELETE), so it's possible to obtain explicit locks before the snapshot is frozen.

9.5. Locking and Indexes

Though PostgreSQL provides nonblocking read/write access to table data, nonblocking read/write access is not currently offered for every index access method implemented in PostgreSQL.

The various index types are handled as follows:

B-tree indexes

Short-term share/exclusive page-level locks are used for read/write access. Locks are released immediately after each index tuple is fetched or inserted. B-tree indexes provide the highest concurrency without deadlock conditions.

GiST and R-tree indexes

Share/exclusive index-level locks are used for read/write access. Locks are released after the statement (command) is done.

Hash indexes

Share/exclusive page-level locks are used for read/write access. Locks are released after the page is processed. Page-level locks provide better concurrency than index-level ones but are liable to deadlocks.

In short, B-tree indexes are the recommended index type for concurrent applications.

Chapter 10. Performance Tips

Query performance can be affected by many things. Some of these can be manipulated by the user, while others are fundamental to the underlying design of the system. This chapter provides some hints about understanding and tuning PostgreSQL performance.

10.1. Using `EXPLAIN`

PostgreSQL devises a *query plan* for each query it is given. Choosing the right plan to match the query structure and the properties of the data is absolutely critical for good performance. You can use the `EXPLAIN` command to see what query plan the system creates for any query. Plan-reading is an art that deserves an extensive tutorial, which this is not; but here is some basic information.

The numbers that are currently quoted by `EXPLAIN` are:

- Estimated start-up cost (Time expended before output scan can start, e.g., time to do the sorting in a sort node.)
- Estimated total cost (If all rows are retrieved, which they may not be --- a query with a `LIMIT` clause will stop short of paying the total cost, for example.)
- Estimated number of rows output by this plan node (Again, only if executed to completion.)
- Estimated average width (in bytes) of rows output by this plan node

The costs are measured in units of disk page fetches. (CPU effort estimates are converted into disk-page units using some fairly arbitrary fudge factors. If you want to experiment with these factors, see the list of run-time configuration parameters in the PostgreSQL 7.3.21 Administrator's Guide.)

It's important to note that the cost of an upper-level node includes the cost of all its child nodes. It's also important to realize that the cost only reflects things that the planner/optimizer cares about. In particular, the cost does not consider the time spent transmitting result rows to the frontend --- which could be a pretty dominant factor in the true elapsed time, but the planner ignores it because it cannot change it by altering the plan. (Every correct plan will output the same row set, we trust.)

Rows output is a little tricky because it is *not* the number of rows processed/scanned by the query --- it is usually less, reflecting the estimated selectivity of any `WHERE`-clause constraints that are being applied at this node. Ideally the top-level rows estimate will approximate the number of rows actually returned, updated, or deleted by the query.

Here are some examples (using the regress test database after a `VACUUM ANALYZE`, and 7.3 development sources):

```
regression=# EXPLAIN SELECT * FROM tenk1;
                         QUERY PLAN
-------------------------------------------------------------
 Seq Scan on tenk1  (cost=0.00..333.00 rows=10000 width=148)
```

This is about as straightforward as it gets. If you do

```
SELECT * FROM pg_class WHERE relname = 'tenk1';
```

you will find out that `tenk1` has 233 disk pages and 10000 rows. So the cost is estimated at 233 page reads, defined as costing 1.0 apiece, plus 10000 * `cpu_tuple_cost` which is currently 0.01 (try `SHOW cpu_tuple_cost`).

Now let's modify the query to add a `WHERE` condition:

```
regression=# EXPLAIN SELECT * FROM tenk1 WHERE unique1 < 1000;
                         QUERY PLAN
-------------------------------------------------------------
```

```
 Seq Scan on tenk1  (cost=0.00..358.00 rows=1033 width=148)
   Filter: (unique1 < 1000)
```

The estimate of output rows has gone down because of the `WHERE` clause. However, the scan will still have to visit all 10000 rows, so the cost hasn't decreased; in fact it has gone up a bit to reflect the extra CPU time spent checking the `WHERE` condition.

The actual number of rows this query would select is 1000, but the estimate is only approximate. If you try to duplicate this experiment, you will probably get a slightly different estimate; moreover, it will change after each `ANALYZE` command, because the statistics produced by `ANALYZE` are taken from a randomized sample of the table.

Modify the query to restrict the condition even more:

```
regression=# EXPLAIN SELECT * FROM tenk1 WHERE unique1 < 50;
                                  QUERY PLAN
------------------------------------------------------------------------------
 Index Scan using tenk1_unique1 on tenk1  (cost=0.00..179.33
 rows=49 width=148)
   Index Cond: (unique1 < 50)
```

and you will see that if we make the `WHERE` condition selective enough, the planner will eventually decide that an index scan is cheaper than a sequential scan. This plan will only have to visit 50 rows because of the index, so it wins despite the fact that each individual fetch is more expensive than reading a whole disk page sequentially.

Add another clause to the `WHERE` condition:

```
regression=# EXPLAIN SELECT * FROM tenk1 WHERE unique1 < 50 AND
regression-# stringu1 = 'xxx';
                                   QUERY PLAN
------------------------------------------------------------------------------
 Index Scan using tenk1_unique1 on tenk1  (cost=0.00..179.45 rows=1
 width=148)
   Index Cond: (unique1 < 50)
   Filter: (stringu1 = 'xxx'::name)
```

The added clause `stringu1 = 'xxx'` reduces the output-rows estimate, but not the cost because we still have to visit the same set of rows. Notice that the `stringu1` clause cannot be applied as an index condition (since this index is only on the `unique1` column). Instead it is applied as a filter on the rows retrieved by the index. Thus the cost has actually gone up a little bit to reflect this extra checking.

Let's try joining two tables, using the fields we have been discussing:

```
regression=# EXPLAIN SELECT * FROM tenk1 t1, tenk2 t2 WHERE
 t1.unique1 < 50
regression-# AND t1.unique2 = t2.unique2;
                                  QUERY PLAN
------------------------------------------------------------------------------
 Nested Loop  (cost=0.00..327.02 rows=49 width=296)
   ->  Index Scan using tenk1_unique1 on tenk1 t1
                                       (cost=0.00..179.33 rows=49
 width=148)
         Index Cond: (unique1 < 50)
   ->  Index Scan using tenk2_unique2 on tenk2 t2
                                       (cost=0.00..3.01 rows=1
 width=148)
         Index Cond: ("outer".unique2 = t2.unique2)
```

In this nested-loop join, the outer scan is the same index scan we had in the example before last, and so its cost and row count are the same because we are applying the `unique1 < 50` `WHERE` clause

at that node. The `t1.unique2 = t2.unique2` clause is not relevant yet, so it doesn't affect row count of the outer scan. For the inner scan, the `unique2` value of the current outer-scan row is plugged into the inner index scan to produce an index condition like `t2.unique2 = constant`. So we get the same inner-scan plan and costs that we'd get from, say, `EXPLAIN SELECT * FROM tenk2 WHERE unique2 = 42`. The costs of the loop node are then set on the basis of the cost of the outer scan, plus one repetition of the inner scan for each outer row (49 * 3.01, here), plus a little CPU time for join processing.

In this example the loop's output row count is the same as the product of the two scans' row counts, but that's not true in general, because in general you can have `WHERE` clauses that mention both relations and so can only be applied at the join point, not to either input scan. For example, if we added `WHERE ... AND t1.hundred < t2.hundred`, that would decrease the output row count of the join node, but not change either input scan.

One way to look at variant plans is to force the planner to disregard whatever strategy it thought was the winner, using the enable/disable flags for each plan type. (This is a crude tool, but useful. See also Section 10.3, “Controlling the Planner with Explicit `JOIN` Clauses”.)

```
regression=# SET enable_nestloop = off;
SET
regression=# EXPLAIN SELECT * FROM tenk1 t1, tenk2 t2 WHERE
 t1.unique1 < 50
regression-# AND t1.unique2 = t2.unique2;
                                 QUERY PLAN
------------------------------------------------------------------------------
 Hash Join  (cost=179.45..563.06 rows=49 width=296)
   Hash Cond: ("outer".unique2 = "inner".unique2)
   ->  Seq Scan on tenk2 t2  (cost=0.00..333.00 rows=10000
 width=148)
   ->  Hash  (cost=179.33..179.33 rows=49 width=148)
         ->  Index Scan using tenk1_unique1 on tenk1 t1
                                    (cost=0.00..179.33 rows=49
 width=148)
               Index Cond: (unique1 < 50)
```

This plan proposes to extract the 50 interesting rows of `tenk1` using ye same olde index scan, stash them into an in-memory hash table, and then do a sequential scan of `tenk2`, probing into the hash table for possible matches of `t1.unique2 = t2.unique2` at each `tenk2` row. The cost to read `tenk1` and set up the hash table is entirely start-up cost for the hash join, since we won't get any rows out until we can start reading `tenk2`. The total time estimate for the join also includes a hefty charge for the CPU time to probe the hash table 10000 times. Note, however, that we are *not* charging 10000 times 179.33; the hash table setup is only done once in this plan type.

It is possible to check on the accuracy of the planner's estimated costs by using `EXPLAIN ANALYZE`. This command actually executes the query, and then displays the true run time accumulated within each plan node along with the same estimated costs that a plain `EXPLAIN` shows. For example, we might get a result like this:

```
regression=# EXPLAIN ANALYZE
regression-# SELECT * FROM tenk1 t1, tenk2 t2
regression-# WHERE t1.unique1 < 50 AND t1.unique2 = t2.unique2;
                                      QUERY PLAN
------------------------------------------------------------------------------
 Nested Loop  (cost=0.00..327.02 rows=49 width=296)
                                    (actual time=1.18..29.82 rows=50
 loops=1)
   ->  Index Scan using tenk1_unique1 on tenk1 t1
                  (cost=0.00..179.33 rows=49 width=148)
                                    (actual time=0.63..8.91 rows=50
 loops=1)
```

```
        Index Cond: (unique1 < 50)
   ->  Index Scan using tenk2_unique2 on tenk2 t2
                 (cost=0.00..3.01 rows=1 width=148)
                                 (actual time=0.29..0.32 rows=1
 loops=50)
        Index Cond: ("outer".unique2 = t2.unique2)
 Total runtime: 31.60 msec
```

Note that the “actual time” values are in milliseconds of real time, whereas the “cost” estimates are expressed in arbitrary units of disk fetches; so they are unlikely to match up. The thing to pay attention to is the ratios.

In some query plans, it is possible for a subplan node to be executed more than once. For example, the inner index scan is executed once per outer row in the above nested-loop plan. In such cases, the “loops” value reports the total number of executions of the node, and the actual time and rows values shown are averages per-execution. This is done to make the numbers comparable with the way that the cost estimates are shown. Multiply by the “loops” value to get the total time actually spent in the node.

The `Total runtime` shown by `EXPLAIN ANALYZE` includes executor start-up and shut-down time, as well as time spent processing the result rows. It does not include parsing, rewriting, or planning time. For a `SELECT` query, the total run time will normally be just a little larger than the total time reported for the top-level plan node. For `INSERT`, `UPDATE`, and `DELETE` commands, the total run time may be considerably larger, because it includes the time spent processing the result rows. In these commands, the time for the top plan node essentially is the time spent computing the new rows and/or locating the old ones, but it doesn't include the time spent making the changes.

It is worth noting that `EXPLAIN` results should not be extrapolated to situations other than the one you are actually testing; for example, results on a toy-sized table can't be assumed to apply to large tables. The planner's cost estimates are not linear and so it may well choose a different plan for a larger or smaller table. An extreme example is that on a table that only occupies one disk page, you'll nearly always get a sequential scan plan whether indexes are available or not. The planner realizes that it's going to take one disk page read to process the table in any case, so there's no value in expending additional page reads to look at an index.

10.2. Statistics Used by the Planner

As we saw in the previous section, the query planner needs to estimate the number of rows retrieved by a query in order to make good choices of query plans. This section provides a quick look at the statistics that the system uses for these estimates.

One component of the statistics is the total number of entries in each table and index, as well as the number of disk blocks occupied by each table and index. This information is kept in `pg_class`'s `reltuples` and `relpages` columns. We can look at it with queries similar to this one:

```
regression=# SELECT relname, relkind, reltuples, relpages FROM
 pg_class
regression-# WHERE relname LIKE 'tenk1%';
    relname    | relkind | reltuples | relpages
---------------+---------+-----------+----------
 tenk1         | r       |     10000 |      233
 tenk1_hundred | i       |     10000 |       30
 tenk1_unique1 | i       |     10000 |       30
 tenk1_unique2 | i       |     10000 |       30
(4 rows)
```

Here we can see that `tenk1` contains 10000 rows, as do its indexes, but the indexes are (unsurprisingly) much smaller than the table.

For efficiency reasons, `reltuples` and `relpages` are not updated on-the-fly, and so they usually contain only approximate values (which is good enough for the planner's purposes). They are

initialized with dummy values (presently 1000 and 10 respectively) when a table is created. They are updated by certain commands, presently VACUUM, ANALYZE, and CREATE INDEX. A stand-alone ANALYZE, that is one not part of VACUUM, generates an approximate reltuples value since it does not read every row of the table.

Most queries retrieve only a fraction of the rows in a table, due to having WHERE clauses that restrict the rows to be examined. The planner thus needs to make an estimate of the *selectivity* of WHERE clauses, that is, the fraction of rows that match each clause of the WHERE condition. The information used for this task is stored in the pg_statistic system catalog. Entries in pg_statistic are updated by ANALYZE and VACUUM ANALYZE commands, and are always approximate even when freshly updated.

Rather than look at pg_statistic directly, it's better to look at its view pg_stats when examining the statistics manually. pg_stats is designed to be more easily readable. Furthermore, pg_stats is readable by all, whereas pg_statistic is only readable by the superuser. (This prevents unprivileged users from learning something about the contents of other people's tables from the statistics. The pg_stats view is restricted to show only rows about tables that the current user can read.) For example, we might do:

```
regression=# SELECT attname, n_distinct, most_common_vals FROM
 pg_stats WHERE tablename = 'road';
 attname | n_distinct |


 most_common_vals


---------+------------
+--------------------------------------------------------------------------------
 name    |  -0.467008 | {"I- 580                          Ramp","I-
 880                       Ramp","Sp Railroad
  ","I- 580                             ","I- 680
     Ramp","I- 80                          Ramp","14th
            St  ","5th                             St  ","Mission
                   Blvd","I- 880                              "}
 thepath |         20 | {"[(-122.089,37.71),(-122.0886,37.711)]"}
(2 rows)
regression=#
```

Table 10.1, “pg_stats Columns” shows the columns that exist in pg_stats.

Table 10.1. pg_stats Columns

Name	Type	Description
tablename	name	Name of the table containing the column
attname	name	Column described by this row
null_frac	real	Fraction of column's entries that are null
avg_width	integer	Average width in bytes of the column's entries
n_distinct	real	If greater than zero, the estimated number of distinct values in the column. If less than zero, the negative of the number of distinct values divided by the number of rows. (The negated form is used when ANALYZE

Name	Type	Description
		believes that the number of distinct values is likely to increase as the table grows; the positive form is used when the column seems to have a fixed number of possible values.) For example, -1 indicates a unique column in which the number of distinct values is the same as the number of rows.
most_common_vals	text[]	A list of the most common values in the column. (Omitted if no values seem to be more common than any others.)
most_common_freqs	real[]	A list of the frequencies of the most common values, i.e., number of occurrences of each divided by total number of rows.
histogram_bounds	text[]	A list of values that divide the column's values into groups of approximately equal population. The most_common_vals, if present, are omitted from the histogram calculation. (Omitted if column data type does not have a < operator, or if the most_common_vals list accounts for the entire population.)
correlation	real	Statistical correlation between physical row ordering and logical ordering of the column values. This ranges from -1 to +1. When the value is near -1 or +1, an index scan on the column will be estimated to be cheaper than when it is near zero, due to reduction of random access to the disk. (Omitted if column data type does not have a < operator.)

The maximum number of entries in the most_common_vals and histogram_bounds arrays can be set on a column-by-column basis using the ALTER TABLE SET STATISTICS command. The default limit is presently 10 entries. Raising the limit may allow more accurate planner estimates to be made, particularly for columns with irregular data distributions, at the price of consuming more space in pg_statistic and slightly more time to compute the estimates. Conversely, a lower limit may be appropriate for columns with simple data distributions.

10.3. Controlling the Planner with Explicit JOIN Clauses

Beginning with PostgreSQL 7.1 it has been possible to control the query planner to some extent by using the explicit JOIN syntax. To see why this matters, we first need some background.

In a simple join query, such as

```
SELECT * FROM a, b, c WHERE a.id = b.id AND b.ref = c.id;
```

the planner is free to join the given tables in any order. For example, it could generate a query plan that joins A to B, using the `WHERE` condition `a.id = b.id`, and then joins C to this joined table, using the other `WHERE` condition. Or it could join B to C and then join A to that result. Or it could join A to C and then join them with B --- but that would be inefficient, since the full Cartesian product of A and C would have to be formed, there being no applicable condition in the `WHERE` clause to allow optimization of the join. (All joins in the PostgreSQL executor happen between two input tables, so it's necessary to build up the result in one or another of these fashions.) The important point is that these different join possibilities give semantically equivalent results but may have hugely different execution costs. Therefore, the planner will explore all of them to try to find the most efficient query plan.

When a query only involves two or three tables, there aren't many join orders to worry about. But the number of possible join orders grows exponentially as the number of tables expands. Beyond ten or so input tables it's no longer practical to do an exhaustive search of all the possibilities, and even for six or seven tables planning may take an annoyingly long time. When there are too many input tables, the PostgreSQL planner will switch from exhaustive search to a *genetic* probabilistic search through a limited number of possibilities. (The switch-over threshold is set by the `GEQO_THRESHOLD` run-time parameter described in the PostgreSQL 7.3.21 Administrator's Guide.) The genetic search takes less time, but it won't necessarily find the best possible plan.

When the query involves outer joins, the planner has much less freedom than it does for plain (inner) joins. For example, consider

```
SELECT * FROM a LEFT JOIN (b JOIN c ON (b.ref = c.id)) ON (a.id =
 b.id);
```

Although this query's restrictions are superficially similar to the previous example, the semantics are different because a row must be emitted for each row of A that has no matching row in the join of B and C. Therefore the planner has no choice of join order here: it must join B to C and then join A to that result. Accordingly, this query takes less time to plan than the previous query.

The PostgreSQL query planner treats all explicit `JOIN` syntaxes as constraining the join order, even though it is not logically necessary to make such a constraint for inner joins. Therefore, although all of these queries give the same result:

```
SELECT * FROM a, b, c WHERE a.id = b.id AND b.ref = c.id;
SELECT * FROM a CROSS JOIN b CROSS JOIN c WHERE a.id = b.id AND
 b.ref = c.id;
SELECT * FROM a JOIN (b JOIN c ON (b.ref = c.id)) ON (a.id = b.id);
```

but the second and third take less time to plan than the first. This effect is not worth worrying about for only three tables, but it can be a lifesaver with many tables.

You do not need to constrain the join order completely in order to cut search time, because it's OK to use `JOIN` operators in a plain `FROM` list. For example,

```
SELECT * FROM a CROSS JOIN b, c, d, e WHERE ...;
```

forces the planner to join A to B before joining them to other tables, but doesn't constrain its choices otherwise. In this example, the number of possible join orders is reduced by a factor of 5.

If you have a mix of outer and inner joins in a complex query, you might not want to constrain the planner's search for a good ordering of inner joins inside an outer join. You can't do that directly in the `JOIN` syntax, but you can get around the syntactic limitation by using subselects. For example,

```
SELECT * FROM d LEFT JOIN
        (SELECT * FROM a, b, c WHERE ...) AS ss
```

```
ON (...);
```

Here, joining D must be the last step in the query plan, but the planner is free to consider various join orders for A, B, C.

Constraining the planner's search in this way is a useful technique both for reducing planning time and for directing the planner to a good query plan. If the planner chooses a bad join order by default, you can force it to choose a better order via `JOIN` syntax --- assuming that you know of a better order, that is. Experimentation is recommended.

10.4. Populating a Database

One may need to do a large number of table insertions when first populating a database. Here are some tips and techniques for making that as efficient as possible.

10.4.1. Disable Autocommit

Turn off autocommit and just do one commit at the end. (In plain SQL, this means issuing `BEGIN` at the start and `COMMIT` at the end. Some client libraries may do this behind your back, in which case you need to make sure the library does it when you want it done.) If you allow each insertion to be committed separately, PostgreSQL is doing a lot of work for each record added. An additional benefit of doing all insertions in one transaction is that if the insertion of one record were to fail then the insertion of all records inserted up to that point would be rolled back, so you won't be stuck with partially loaded data.

10.4.2. Use COPY FROM

Use `COPY FROM STDIN` to load all the records in one command, instead of using a series of `INSERT` commands. This reduces parsing, planning, etc. overhead a great deal. If you do this then it is not necessary to turn off autocommit, since it is only one command anyway.

10.4.3. Remove Indexes

If you are loading a freshly created table, the fastest way is to create the table, bulk-load with `COPY`, then create any indexes needed for the table. Creating an index on pre-existing data is quicker than updating it incrementally as each record is loaded.

If you are augmenting an existing table, you can `DROP INDEX`, load the table, then recreate the index. Of course, the database performance for other users may be adversely affected during the time that the index is missing. One should also think twice before dropping unique indexes, since the error checking afforded by the unique constraint will be lost while the index is missing.

10.4.4. Run ANALYZE Afterwards

It's a good idea to run `ANALYZE` or `VACUUM ANALYZE` anytime you've added or updated a lot of data, including just after initially populating a table. This ensures that the planner has up-to-date statistics about the table. With no statistics or obsolete statistics, the planner may make poor choices of query plans, leading to bad performance on queries that use your table.

Appendix A. Date/Time Support

PostgreSQL uses an internal heuristic parser for all date/time input support. Dates and times are input as strings, and are broken up into distinct fields with a preliminary determination of what kind of information may be in the field. Each field is interpreted and either assigned a numeric value, ignored, or rejected. The parser contains internal lookup tables for all textual fields, including months, days of the week, and time zones.

This appendix includes information on the content of these lookup tables and describes the steps used by the parser to decode dates and times.

A.1. Date/Time Input Interpretation

The date/time types are all decoded using a common set of routines.

Date/Time Input Interpretation

1. Break the input string into tokens and categorize each token as a string, time, time zone, or number.
   a. If the numeric token contains a colon (`:`), this is a time string. Include all subsequent digits and colons.
   b. If the numeric token contains a dash (`-`), slash (`/`), or two or more dots (`.`), this is a date string which may have a text month.
   c. If the token is numeric only, then it is either a single field or an ISO 8601 concatenated date (e.g., `19990113` for January 13, 1999) or time (e.g. `141516` for 14:15:16).
   d. If the token starts with a plus (`+`) or minus (`-`), then it is either a time zone or a special field.
2. If the token is a text string, match up with possible strings.
   a. Do a binary-search table lookup for the token as either a special string (e.g., `today`), day (e.g., `Thursday`), month (e.g., `January`), or noise word (e.g., `at`, `on`).

      Set field values and bit mask for fields. For example, set year, month, day for `today`, and additionally hour, minute, second for `now`.
   b. If not found, do a similar binary-search table lookup to match the token with a time zone.
   c. If not found, throw an error.
3. The token is a number or number field.
   a. If there are more than 4 digits, and if no other date fields have been previously read, then interpret as a "concatenated date" (e.g., `19990118`). 8 and 6 digits are interpreted as year, month, and day, while 7 and 5 digits are interpreted as year, day of year, respectively.
   b. If the token is three digits and a year has already been decoded, then interpret as day of year.
   c. If four or six digits and a year has already been read, then interpret as a time.
   d. If four or more digits, then interpret as a year.
   e. If in European date mode, and if the day field has not yet been read, and if the value is less than or equal to 31, then interpret as a day.
   f. If the month field has not yet been read, and if the value is less than or equal to 12, then interpret as a month.

g. If the day field has not yet been read, and if the value is less than or equal to 31, then interpret as a day.

h. If two digits or four or more digits, then interpret as a year.

i. Otherwise, throw an error.

4. If BC has been specified, negate the year and add one for internal storage. (There is no year zero in the Gregorian calendar, so numerically `1BC` becomes year zero.)

5. If BC was not specified, and if the year field was two digits in length, then adjust the year to 4 digits. If the field was less than 70, then add 2000; otherwise, add 1900.

Tip

Gregorian years AD 1-99 may be entered by using 4 digits with leading zeros (e.g., `0099` is AD 99). Previous versions of PostgreSQL accepted years with three digits and with single digits, but as of version 7.0 the rules have been tightened up to reduce the possibility of ambiguity.

A.2. Date/Time Key Words

Table A.1, “Month Abbreviations” shows the tokens that are permissible as abbreviations for the names of the month.

Table A.1. Month Abbreviations

Month	Abbreviations
April	Apr
August	Aug
December	Dec
February	Feb
January	Jan
July	Jul
June	Jun
March	Mar
November	Nov
October	Oct
September	Sep, Sept

Note

The month May has no explicit abbreviation, for obvious reasons.

Table A.2, “Day of the Week Abbreviations” shows the tokens that are permissible as abbreviations for the names of the days of the week.

Table A.2. Day of the Week Abbreviations

Day	Abbreviation
Sunday	Sun
Monday	Mon
Tuesday	Tue, Tues

Day	Abbreviation
Wednesday	Wed, Weds
Thursday	Thu, Thur, Thurs
Friday	Fri
Saturday	Sat

Table A.3, “Date/Time Field Modifiers” shows the tokens that serve various modifier purposes.

Table A.3. Date/Time Field Modifiers

Identifier	Description
`ABSTIME`	Key word ignored
`AM`	Time is before 12:00
`AT`	Key word ignored
`JULIAN`, `JD`, `J`	Next field is Julian Day
`ON`	Key word ignored
`PM`	Time is on or after after 12:00
`T`	Next field is time

The key word `ABSTIME` is ignored for historical reasons; in very old releases of PostgreSQL invalid fields of type `abstime` were emitted as `Invalid Abstime`. This is no longer the case however and this key word will likely be dropped in a future release.

Table A.4, “Time Zone Abbreviations” shows the time zone abbreviations recognized by PostgreSQL. PostgreSQL contains internal tabular information for time zone decoding, since there is no standard operating system interface to provide access to general, cross-time zone information. The underlying operating system *is* used to provide time zone information for *output*, however.

The table is organized by time zone offset from UTC, rather than alphabetically; this is intended to facilitate matching local usage with recognized abbreviations for cases where these might differ.

Table A.4. Time Zone Abbreviations

Time Zone	Offset from UTC	Description
NZDT	+13:00	New Zealand Daylight Time
IDLE	+12:00	International Date Line, East
NZST	+12:00	New Zealand Standard Time
NZT	+12:00	New Zealand Time
AESST	+11:00	Australia Eastern Summer Standard Time
ACSST	+10:30	Central Australia Summer Standard Time
CADT	+10:30	Central Australia Daylight Savings Time
SADT	+10:30	South Australian Daylight Time
AEST	+10:00	Australia Eastern Standard Time
EAST	+10:00	East Australian Standard Time
GST	+10:00	Guam Standard Time, USSR Zone 9
LIGT	+10:00	Melbourne, Australia

Time Zone	Offset from UTC	Description
SAST	+09:30	South Australia Standard Time
CAST	+09:30	Central Australia Standard Time
AWSST	+09:00	Australia Western Summer Standard Time
JST	+09:00	Japan Standard Time,USSR Zone 8
KST	+09:00	Korea Standard Time
MHT	+09:00	Kwajalein Time
WDT	+09:00	West Australian Daylight Time
MT	+08:30	Moluccas Time
AWST	+08:00	Australia Western Standard Time
CCT	+08:00	China Coastal Time
WADT	+08:00	West Australian Daylight Time
WST	+08:00	West Australian Standard Time
JT	+07:30	Java Time
ALMST	+07:00	Almaty Summer Time
WAST	+07:00	West Australian Standard Time
CXT	+07:00	Christmas (Island) Time
MMT	+06:30	Myannar Time
ALMT	+06:00	Almaty Time
MAWT	+06:00	Mawson (Antarctica) Time
IOT	+05:00	Indian Chagos Time
MVT	+05:00	Maldives Island Time
TFT	+05:00	Kerguelen Time
AFT	+04:30	Afganistan Time
EAST	+04:00	Antananarivo Savings Time
MUT	+04:00	Mauritius Island Time
RET	+04:00	Reunion Island Time
SCT	+04:00	Mahe Island Time
IRT, IT	+03:30	Iran Time
EAT	+03:00	Antananarivo, Comoro Time
BT	+03:00	Baghdad Time
EETDST	+03:00	Eastern Europe Daylight Savings Time
HMT	+03:00	Hellas Mediterranean Time (?)
BDST	+02:00	British Double Standard Time
CEST	+02:00	Central European Savings Time
CETDST	+02:00	Central European Daylight Savings Time
EET	+02:00	Eastern Europe, USSR Zone 1
FWT	+02:00	French Winter Time

Time Zone	Offset from UTC	Description
IST	+02:00	Israel Standard Time
MEST	+02:00	Middle Europe Summer Time
METDST	+02:00	Middle Europe Daylight Time
SST	+02:00	Swedish Summer Time
BST	+01:00	British Summer Time
CET	+01:00	Central European Time
DNT	+01:00	*Dansk Normal Tid*
FST	+01:00	French Summer Time
MET	+01:00	Middle Europe Time
MEWT	+01:00	Middle Europe Winter Time
MEZ	+01:00	Middle Europe Zone
NOR	+01:00	Norway Standard Time
SET	+01:00	Seychelles Time
SWT	+01:00	Swedish Winter Time
WETDST	+01:00	Western Europe Daylight Savings Time
GMT	+00:00	Greenwich Mean Time
UT	+00:00	Universal Time
UTC	+00:00	Universal Time, Coordinated
Z	+00:00	Same as UTC
ZULU	+00:00	Same as UTC
WET	+00:00	Western Europe
WAT	-01:00	West Africa Time
NDT	-02:30	Newfoundland Daylight Time
ADT	-03:00	Atlantic Daylight Time
AWT	-03:00	(unknown)
NFT	-03:30	Newfoundland Standard Time
NST	-03:30	Newfoundland Standard Time
AST	-04:00	Atlantic Standard Time (Canada)
ACST	-04:00	Atlantic/Porto Acre Summer Time
ACT	-05:00	Atlantic/Porto Acre Standard Time
EDT	-04:00	Eastern Daylight Time
CDT	-05:00	Central Daylight Time
EST	-05:00	Eastern Standard Time
CST	-06:00	Central Standard Time
MDT	-06:00	Mountain Daylight Time
MST	-07:00	Mountain Standard Time
PDT	-07:00	Pacific Daylight Time
AKDT	-08:00	Alaska Daylight Time

Time Zone	Offset from UTC	Description
PST	-08:00	Pacific Standard Time
YDT	-08:00	Yukon Daylight Time
AKST	-09:00	Alaska Standard Time
HDT	-09:00	Hawaii/Alaska Daylight Time
YST	-09:00	Yukon Standard Time
MART	-09:30	Marquesas Time
AHST	-10:00	Alaska-Hawaii Standard Time
HST	-10:00	Hawaii Standard Time
CAT	-10:00	Central Alaska Time
NT	-11:00	Nome Time
IDLW	-12:00	International Date Line, West

Australian Time Zones. There are three naming conflicts between Australian time zone names with time zones commonly used in North and South America: `ACST`, `CST`, and `EST`. If the run-time option `AUSTRALIAN_TIMEZONES` is set to true then `ACST`, `CST`, `EST`, and `SAT` are interpreted as Australian time zone names, as shown in Table A.5, “Australian Time Zone Abbreviations”. If it is false (which is the default), then `ACST`, `CST`, and `EST` are taken as American time zone names, and `SAT` is interpreted as a noise word indicating Saturday.

Table A.5. Australian Time Zone Abbreviations

Time Zone	Offset from UTC	Description
ACST	+09:30	Central Australia Standard Time
CST	+10:30	Australian Central Standard Time
EST	+10:00	Australian Eastern Standard Time
SAT	+09:30	South Australian Standard Time

A.3. History of Units

Note

Contributed by José Soares (<jose@sferacarta.com>)

The Julian Day was invented by the French scholar Joseph Justus Scaliger (1540-1609) and probably takes its name from the Scaliger's father, the Italian scholar Julius Caesar Scaliger (1484-1558). Astronomers have used the Julian period to assign a unique number to every day since 1 January 4713 BC. This is the so-called Julian Day (JD). JD 0 designates the 24 hours from noon UTC on 1 January 4713 BC to noon UTC on 2 January 4713 BC.

The “Julian Day” is different from the “Julian Date”. The Julian date refers to the Julian calendar, which was introduced by Julius Caesar in 45 BC. It was in common use until the 1582, when countries started changing to the Gregorian calendar. In the Julian calendar, the tropical year is approximated as 365 1/4 days = 365.25 days. This gives an error of about 1 day in 128 years.

The accumulating calendar error prompted Pope Gregory XIII to reform the calendar in accordance with instructions from the Council of Trent. In the Gregorian calendar, the tropical year is approximated as 365 + 97 / 400 days = 365.2425 days. Thus it takes approximately 3300 years for the tropical year to shift one day with respect to the Gregorian calendar.

The approximation 365+97/400 is achieved by having 97 leap years every 400 years, using the following rules:

Every year divisible by 4 is a leap year.
However, every year divisible by 100 is not a leap year.
However, every year divisible by 400 is a leap year after all.
So, 1700, 1800, 1900, 2100, and 2200 are not leap years. But 1600, 2000, and 2400 are leap years. By contrast, in the older Julian calendar only years divisible by 4 are leap years.

The papal bull of February 1582 decreed that 10 days should be dropped from October 1582 so that 15 October should follow immediately after 4 October. This was observed in Italy, Poland, Portugal, and Spain. Other Catholic countries followed shortly after, but Protestant countries were reluctant to change, and the Greek orthodox countries didn't change until the start of the 20th century. The reform was observed by Great Britain and Dominions (including what is now the USA) in 1752. Thus 2 September 1752 was followed by 14 September 1752. This is why Unix systems have the `cal` program produce the following:

```
$ cal 9 1752
   September 1752
 S  M Tu  W Th  F  S
       1  2 14 15 16
17 18 19 20 21 22 23
24 25 26 27 28 29 30
```

Note

The SQL standard states that “Within the definition of a ‘datetime literal’, the ‘datetime value’s are constrained by the natural rules for dates and times according to the Gregorian calendar”. Dates between 1752-09-03 and 1752-09-13, although eliminated in some countries by Papal fiat, conform to “natural rules” and are hence valid dates.

Different calendars have been developed in various parts of the world, many predating the Gregorian system. For example, the beginnings of the Chinese calendar can be traced back to the 14th century BC. Legend has it that the Emperor Huangdi invented the calendar in 2637 BC. The People's Republic of China uses the Gregorian calendar for civil purposes. The Chinese calendar is used for determining festivals.

Appendix B. SQL Key Words

Table B.1, “SQL Key Words” lists all tokens that are key words in the SQL standard and in PostgreSQL 7.3.21. Background information can be found in Section 1.1.1, “Identifiers and Key Words”.

SQL distinguishes between *reserved* and *non-reserved* key words. According to the standard, reserved key words are the only real key words; they are never allowed as identifiers. Non-reserved key words only have a special meaning in particular contexts and can be used as identifiers in other contexts. Most non-reserved key words are actually the names of built-in tables and functions specified by SQL. The concept of non-reserved key words essentially only exists to declare that some predefined meaning is attached to a word in some contexts.

In the PostgreSQL parser life is a bit more complicated. There are several different classes of tokens ranging from those that can never be used as an identifier to those that have absolutely no special status in the parser as compared to an ordinary identifier. (The latter is usually the case for functions specified by SQL.) Even reserved key words are not completely reserved in PostgreSQL, but can be used as column labels (for example, `SELECT 55 AS CHECK`, even though `CHECK` is a reserved key word).

In Table B.1, “SQL Key Words” in the column for PostgreSQL we classify as “non-reserved” those key words that are explicitly known to the parser but are allowed in most or all contexts where an identifier is expected. Some key words that are otherwise non-reserved cannot be used as function or data type names and are marked accordingly. (Most of these words represent built-in functions or data types with special syntax. The function or type is still available but it cannot be redefined by the user.) Labeled “reserved” are those tokens that are only allowed as “AS” column label names (and perhaps in very few other contexts). Some reserved key words are allowable as names for functions; this is also shown in the table.

As a general rule, if you get spurious parser errors for commands that contain any of the listed key words as an identifier you should try to quote the identifier to see if the problem goes away.

It is important to understand before studying Table B.1, “SQL Key Words” that the fact that a key word is not reserved in PostgreSQL does not mean that the feature related to the word is not implemented. Conversely, the presence of a key word does not indicate the existence of a feature.

Table B.1. SQL Key Words

Key Word	PostgreSQL	SQL 99	SQL 92
ABORT	non-reserved		
ABS		non-reserved	
ABSOLUTE	non-reserved	reserved	reserved
ACCESS	non-reserved		
ACTION	non-reserved	reserved	reserved
ADA		non-reserved	non-reserved
ADD	non-reserved	reserved	reserved
ADMIN		reserved	
AFTER	non-reserved	reserved	
AGGREGATE	non-reserved	reserved	
ALIAS		reserved	
ALL	reserved	reserved	reserved
ALLOCATE		reserved	reserved
ALTER	non-reserved	reserved	reserved
ANALYSE	reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
ANALYZE	reserved		
AND	reserved	reserved	reserved
ANY	reserved	reserved	reserved
ARE		reserved	reserved
ARRAY		reserved	
AS	reserved	reserved	reserved
ASC	reserved	reserved	reserved
ASENSITIVE		non-reserved	
ASSERTION	non-reserved	reserved	reserved
ASSIGNMENT	non-reserved	non-reserved	
ASYMMETRIC		non-reserved	
AT	non-reserved	reserved	reserved
ATOMIC		non-reserved	
AUTHORIZATION	reserved (can be function)	reserved	reserved
AVG		non-reserved	reserved
BACKWARD	non-reserved		
BEFORE	non-reserved	reserved	
BEGIN	non-reserved	reserved	reserved
BETWEEN	reserved (can be function)	non-reserved	reserved
BIGINT	non-reserved (cannot be function or type)		
BINARY	reserved (can be function)	reserved	
BIT	non-reserved (cannot be function or type)	reserved	reserved
BITVAR		non-reserved	
BIT_LENGTH		non-reserved	reserved
BLOB		reserved	
BOOLEAN	non-reserved (cannot be function or type)	reserved	
BOTH	reserved	reserved	reserved
BREADTH		reserved	
BY	non-reserved	reserved	reserved
C		non-reserved	non-reserved
CACHE	non-reserved		
CALL		reserved	
CALLED	non-reserved	non-reserved	
CARDINALITY		non-reserved	
CASCADE	non-reserved	reserved	reserved
CASCADED		reserved	reserved

Key Word	PostgreSQL	SQL 99	SQL 92
CASE	reserved	reserved	reserved
CAST	reserved	reserved	reserved
CATALOG		reserved	reserved
CATALOG_NAME		non-reserved	non-reserved
CHAIN	non-reserved	non-reserved	
CHAR	non-reserved (cannot be function or type)	reserved	reserved
CHARACTER	non-reserved (cannot be function or type)	reserved	reserved
CHARACTERISTICS	non-reserved		
CHARACTER_LENGTH		non-reserved	reserved
CHARACTER_SET_CATALOG		non-reserved	non-reserved
CHARACTER_SET_NAME		non-reserved	non-reserved
CHARACTER_SET_SCHEMA		non-reserved	non-reserved
CHAR_LENGTH		non-reserved	reserved
CHECK	reserved	reserved	reserved
CHECKED		non-reserved	
CHECKPOINT	non-reserved		
CLASS	non-reserved	reserved	
CLASS_ORIGIN		non-reserved	non-reserved
CLOB		reserved	
CLOSE	non-reserved	reserved	reserved
CLUSTER	non-reserved		
COALESCE	non-reserved (cannot be function or type)	non-reserved	reserved
COBOL		non-reserved	non-reserved
COLLATE	reserved	reserved	reserved
COLLATION		reserved	reserved
COLLATION_CATALOG		non-reserved	non-reserved
COLLATION_NAME		non-reserved	non-reserved
COLLATION_SCHEMA		non-reserved	non-reserved
COLUMN	reserved	reserved	reserved
COLUMN_NAME		non-reserved	non-reserved
COMMAND_FUNCTION		non-reserved	non-reserved
COMMAND_FUNCTION_CODE		non-reserved	
COMMENT	non-reserved		
COMMIT	non-reserved	reserved	reserved
COMMITTED	non-reserved	non-reserved	non-reserved
COMPLETION		reserved	
CONDITION_NUMBER		non-reserved	non-reserved
CONNECT		reserved	reserved
CONNECTION		reserved	reserved

Key Word	PostgreSQL	SQL 99	SQL 92
CONNECTION_NAME		non-reserved	non-reserved
CONSTRAINT	reserved	reserved	reserved
CONSTRAINTS	non-reserved	reserved	reserved
CONSTRAINT_CATALOG		non-reserved	non-reserved
CONSTRAINT_NAME		non-reserved	non-reserved
CONSTRAINT_SCHEMA		non-reserved	non-reserved
CONSTRUCTOR		reserved	
CONTAINS		non-reserved	
CONTINUE		reserved	reserved
CONVERSION	non-reserved		
CONVERT	non-reserved (cannot be function or type)	non-reserved	reserved
COPY	non-reserved		
CORRESPONDING		reserved	reserved
COUNT		non-reserved	reserved
CREATE	reserved	reserved	reserved
CREATEDB	non-reserved		
CREATEUSER	non-reserved		
CROSS	reserved (can be function)	reserved	reserved
CUBE		reserved	
CURRENT		reserved	reserved
CURRENT_DATE	reserved	reserved	reserved
CURRENT_PATH		reserved	
CURRENT_ROLE		reserved	
CURRENT_TIME	reserved	reserved	reserved
CURRENT_TIMESTAMP	reserved	reserved	reserved
CURRENT_USER	reserved	reserved	reserved
CURSOR	non-reserved	reserved	reserved
CURSOR_NAME		non-reserved	non-reserved
CYCLE	non-reserved	reserved	
DATA		reserved	non-reserved
DATABASE	non-reserved		
DATE		reserved	reserved
DATETIME_INTERVAL_CODE		non-reserved	non-reserved
DATETIME_INTERVAL_PRECISION		non-reserved	non-reserved
DAY	non-reserved	reserved	reserved
DEALLOCATE	non-reserved	reserved	reserved
DEC	non-reserved (cannot be function or type)	reserved	reserved
DECIMAL	non-reserved (cannot be function or type)	reserved	reserved

Key Word	PostgreSQL	SQL 99	SQL 92
DECLARE	non-reserved	reserved	reserved
DEFAULT	reserved	reserved	reserved
DEFERRABLE	reserved	reserved	reserved
DEFERRED	non-reserved	reserved	reserved
DEFINED		non-reserved	
DEFINER	non-reserved	non-reserved	
DELETE	non-reserved	reserved	reserved
DELIMITER	non-reserved		
DELIMITERS	non-reserved		
DEPTH		reserved	
DEREF		reserved	
DESC	reserved	reserved	reserved
DESCRIBE		reserved	reserved
DESCRIPTOR		reserved	reserved
DESTROY		reserved	
DESTRUCTOR		reserved	
DETERMINISTIC		reserved	
DIAGNOSTICS		reserved	reserved
DICTIONARY		reserved	
DISCONNECT		reserved	reserved
DISPATCH		non-reserved	
DISTINCT	reserved	reserved	reserved
DO	reserved		
DOMAIN	non-reserved	reserved	reserved
DOUBLE	non-reserved	reserved	reserved
DROP	non-reserved	reserved	reserved
DYNAMIC		reserved	
DYNAMIC_FUNCTION		non-reserved	non-reserved
DYNAMIC_FUNCTION_CODE		non-reserved	
EACH	non-reserved	reserved	
ELSE	reserved	reserved	reserved
ENCODING	non-reserved		
ENCRYPTED	non-reserved		
END	reserved	reserved	reserved
END-EXEC		reserved	reserved
EQUALS		reserved	
ESCAPE	non-reserved	reserved	reserved
EVERY		reserved	
EXCEPT	reserved	reserved	reserved
EXCEPTION		reserved	reserved
EXCLUSIVE	non-reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
EXEC		reserved	reserved
EXECUTE	non-reserved	reserved	reserved
EXISTING		non-reserved	
EXISTS	non-reserved (cannot be function or type)	non-reserved	reserved
EXPLAIN	non-reserved		
EXTERNAL	non-reserved	reserved	reserved
EXTRACT	non-reserved (cannot be function or type)	non-reserved	reserved
FALSE	reserved	reserved	reserved
FETCH	non-reserved	reserved	reserved
FINAL		non-reserved	
FIRST		reserved	reserved
FLOAT	non-reserved (cannot be function or type)	reserved	reserved
FOR	reserved	reserved	reserved
FORCE	non-reserved		
FOREIGN	reserved	reserved	reserved
FORTRAN		non-reserved	non-reserved
FORWARD	non-reserved		
FOUND		reserved	reserved
FREE		reserved	
FREEZE	reserved (can be function)		
FROM	reserved	reserved	reserved
FULL	reserved (can be function)	reserved	reserved
FUNCTION	non-reserved	reserved	
G		non-reserved	
GENERAL		reserved	
GENERATED		non-reserved	
GET	non-reserved	reserved	reserved
GLOBAL	non-reserved	reserved	reserved
GO		reserved	reserved
GOTO		reserved	reserved
GRANT	reserved	reserved	reserved
GRANTED		non-reserved	
GROUP	reserved	reserved	reserved
GROUPING		reserved	
HANDLER	non-reserved		
HAVING	reserved	reserved	reserved
HIERARCHY		non-reserved	

Key Word	PostgreSQL	SQL 99	SQL 92
HOLD		non-reserved	
HOST		reserved	
HOUR	non-reserved	reserved	reserved
IDENTITY		reserved	reserved
IGNORE		reserved	
ILIKE	reserved (can be function)		
IMMEDIATE	non-reserved	reserved	reserved
IMMUTABLE	non-reserved		
IMPLEMENTATION		non-reserved	
IMPLICIT	non-reserved		
IN	reserved (can be function)	reserved	reserved
INCREMENT	non-reserved		
INDEX	non-reserved		
INDICATOR		reserved	reserved
INFIX		non-reserved	
INHERITS	non-reserved		
INITIALIZE		reserved	
INITIALLY	reserved	reserved	reserved
INNER	reserved (can be function)	reserved	reserved
INOUT	non-reserved	reserved	
INPUT	non-reserved	reserved	reserved
INSENSITIVE	non-reserved	non-reserved	reserved
INSERT	non-reserved	reserved	reserved
INSTANCE		non-reserved	
INSTANTIABLE		non-reserved	
INSTEAD	non-reserved		
INT	non-reserved (cannot be function or type)	reserved	reserved
INTEGER	non-reserved (cannot be function or type)	reserved	reserved
INTERSECT	reserved	reserved	reserved
INTERVAL	non-reserved (cannot be function or type)	reserved	reserved
INTO	reserved	reserved	reserved
INVOKER	non-reserved	non-reserved	
IS	reserved (can be function)	reserved	reserved
ISNULL	reserved (can be function)		
ISOLATION	non-reserved	reserved	reserved

Key Word	PostgreSQL	SQL 99	SQL 92
ITERATE		reserved	
JOIN	reserved (can be function)	reserved	reserved
K		non-reserved	
KEY	non-reserved	reserved	reserved
KEY_MEMBER		non-reserved	
KEY_TYPE		non-reserved	
LANCOMPILER	non-reserved		
LANGUAGE	non-reserved	reserved	reserved
LARGE		reserved	
LAST		reserved	reserved
LATERAL		reserved	
LEADING	reserved	reserved	reserved
LEFT	reserved (can be function)	reserved	reserved
LENGTH		non-reserved	non-reserved
LESS		reserved	
LEVEL	non-reserved	reserved	reserved
LIKE	reserved (can be function)	reserved	reserved
LIMIT	reserved	reserved	
LISTEN	non-reserved		
LOAD	non-reserved		
LOCAL	non-reserved	reserved	reserved
LOCALTIME	reserved	reserved	
LOCALTIMESTAMP	reserved	reserved	
LOCATION	non-reserved		
LOCATOR		reserved	
LOCK	non-reserved		
LOWER		non-reserved	reserved
M		non-reserved	
MAP		reserved	
MATCH	non-reserved	reserved	reserved
MAX		non-reserved	reserved
MAXVALUE	non-reserved		
MESSAGE_LENGTH		non-reserved	non-reserved
MESSAGE_OCTET_LENGTH		non-reserved	non-reserved
MESSAGE_TEXT		non-reserved	non-reserved
METHOD		non-reserved	
MIN		non-reserved	reserved
MINUTE	non-reserved	reserved	reserved
MINVALUE	non-reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
MOD		non-reserved	
MODE	non-reserved		
MODIFIES		reserved	
MODIFY		reserved	
MODULE		reserved	reserved
MONTH	non-reserved	reserved	reserved
MORE		non-reserved	non-reserved
MOVE	non-reserved		
MUMPS		non-reserved	non-reserved
NAME		non-reserved	non-reserved
NAMES	non-reserved	reserved	reserved
NATIONAL	non-reserved	reserved	reserved
NATURAL	reserved (can be function)	reserved	reserved
NCHAR	non-reserved (cannot be function or type)	reserved	reserved
NCLOB		reserved	
NEW	reserved	reserved	
NEXT	non-reserved	reserved	reserved
NO	non-reserved	reserved	reserved
NOCREATEDB	non-reserved		
NOCREATEUSER	non-reserved		
NONE	non-reserved (cannot be function or type)	reserved	
NOT	reserved	reserved	reserved
NOTHING	non-reserved		
NOTIFY	non-reserved		
NOTNULL	reserved (can be function)		
NULL	reserved	reserved	reserved
NULLABLE		non-reserved	non-reserved
NULLIF	non-reserved (cannot be function or type)	non-reserved	reserved
NUMBER		non-reserved	non-reserved
NUMERIC	non-reserved (cannot be function or type)	reserved	reserved
OBJECT		reserved	
OCTET_LENGTH		non-reserved	reserved
OF	non-reserved	reserved	reserved
OFF	reserved	reserved	
OFFSET	reserved		
OIDS	non-reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
OLD	reserved	reserved	
ON	reserved	reserved	reserved
ONLY	reserved	reserved	reserved
OPEN		reserved	reserved
OPERATION		reserved	
OPERATOR	non-reserved		
OPTION	non-reserved	reserved	reserved
OPTIONS		non-reserved	
OR	reserved	reserved	reserved
ORDER	reserved	reserved	reserved
ORDINALITY		reserved	
OUT	non-reserved	reserved	
OUTER	reserved (can be function)	reserved	reserved
OUTPUT		reserved	reserved
OVERLAPS	reserved (can be function)	non-reserved	reserved
OVERLAY	non-reserved (cannot be function or type)	non-reserved	
OVERRIDING		non-reserved	
OWNER	non-reserved		
PAD		reserved	reserved
PARAMETER		reserved	
PARAMETERS		reserved	
PARAMETER_MODE		non-reserved	
PARAMETER_NAME		non-reserved	
PARAMETER_ORDINAL_POSITION		non-reserved	
PARAMETER_SPECIFIC_CATALOG		non-reserved	
PARAMETER_SPECIFIC_NAME		non-reserved	
PARAMETER_SPECIFIC_SCHEMA		non-reserved	
PARTIAL	non-reserved	reserved	reserved
PASCAL		non-reserved	non-reserved
PASSWORD	non-reserved		
PATH	non-reserved	reserved	
PENDANT	non-reserved		
PLACING	reserved		
PLI		non-reserved	non-reserved
POSITION	non-reserved (cannot be function or type)	non-reserved	reserved
POSTFIX		reserved	
PRECISION	non-reserved	reserved	reserved
PREFIX		reserved	

Key Word	PostgreSQL	SQL 99	SQL 92
PREORDER		reserved	
PREPARE	non-reserved	reserved	reserved
PRESERVE		reserved	reserved
PRIMARY	reserved	reserved	reserved
PRIOR	non-reserved	reserved	reserved
PRIVILEGES	non-reserved	reserved	reserved
PROCEDURAL	non-reserved		
PROCEDURE	non-reserved	reserved	reserved
PUBLIC		reserved	reserved
READ	non-reserved	reserved	reserved
READS		reserved	
REAL	non-reserved (cannot be function or type)	reserved	reserved
RECHECK	non-reserved		
RECURSIVE		reserved	
REF		reserved	
REFERENCES	reserved	reserved	reserved
REFERENCING		reserved	
REINDEX	non-reserved		
RELATIVE	non-reserved	reserved	reserved
RENAME	non-reserved		
REPEATABLE		non-reserved	non-reserved
REPLACE	non-reserved		
RESET	non-reserved		
RESTRICT	non-reserved	reserved	reserved
RESULT		reserved	
RETURN		reserved	
RETURNED_LENGTH		non-reserved	non-reserved
RETURNED_OCTET_LENGTH		non-reserved	non-reserved
RETURNED_SQLSTATE		non-reserved	non-reserved
RETURNS	non-reserved	reserved	
REVOKE	non-reserved	reserved	reserved
RIGHT	reserved (can be function)	reserved	reserved
ROLE		reserved	
ROLLBACK	non-reserved	reserved	reserved
ROLLUP		reserved	
ROUTINE		reserved	
ROUTINE_CATALOG		non-reserved	
ROUTINE_NAME		non-reserved	
ROUTINE_SCHEMA		non-reserved	

Key Word	PostgreSQL	SQL 99	SQL 92
ROW	non-reserved (cannot be function or type)	reserved	
ROWS		reserved	reserved
ROW_COUNT		non-reserved	non-reserved
RULE	non-reserved		
SAVEPOINT		reserved	
SCALE		non-reserved	non-reserved
SCHEMA	non-reserved	reserved	reserved
SCHEMA_NAME		non-reserved	non-reserved
SCOPE		reserved	
SCROLL	non-reserved	reserved	reserved
SEARCH		reserved	
SECOND	non-reserved	reserved	reserved
SECTION		reserved	reserved
SECURITY	non-reserved	non-reserved	
SELECT	reserved	reserved	reserved
SELF		non-reserved	
SENSITIVE		non-reserved	
SEQUENCE	non-reserved	reserved	
SERIALIZABLE	non-reserved	non-reserved	non-reserved
SERVER_NAME		non-reserved	non-reserved
SESSION	non-reserved	reserved	reserved
SESSION_USER	reserved	reserved	reserved
SET	non-reserved	reserved	reserved
SETOF	non-reserved (cannot be function or type)		
SETS		reserved	
SHARE	non-reserved		
SHOW	non-reserved		
SIMILAR	reserved (can be function)	non-reserved	
SIMPLE	non-reserved	non-reserved	
SIZE		reserved	reserved
SMALLINT	non-reserved (cannot be function or type)	reserved	reserved
SOME	reserved	reserved	reserved
SOURCE		non-reserved	
SPACE		reserved	reserved
SPECIFIC		reserved	
SPECIFICTYPE		reserved	
SPECIFIC_NAME		non-reserved	
SQL		reserved	reserved

Key Word	PostgreSQL	SQL 99	SQL 92
SQLCODE			reserved
SQLERROR			reserved
SQLEXCEPTION		reserved	
SQLSTATE		reserved	reserved
SQLWARNING		reserved	
STABLE	non-reserved		
START	non-reserved	reserved	
STATE		reserved	
STATEMENT	non-reserved	reserved	
STATIC		reserved	
STATISTICS	non-reserved		
STDIN	non-reserved		
STDOUT	non-reserved		
STORAGE	non-reserved		
STRICT	non-reserved		
STRUCTURE		reserved	
STYLE		non-reserved	
SUBCLASS_ORIGIN		non-reserved	non-reserved
SUBLIST		non-reserved	
SUBSTRING	non-reserved (cannot be function or type)	non-reserved	reserved
SUM		non-reserved	reserved
SYMMETRIC		non-reserved	
SYSID	non-reserved		
SYSTEM		non-reserved	
SYSTEM_USER		reserved	reserved
TABLE	reserved	reserved	reserved
TABLE_NAME		non-reserved	non-reserved
TEMP	non-reserved		
TEMPLATE	non-reserved		
TEMPORARY	non-reserved	reserved	reserved
TERMINATE		reserved	
THAN		reserved	
THEN	reserved	reserved	reserved
TIME	non-reserved (cannot be function or type)	reserved	reserved
TIMESTAMP	non-reserved (cannot be function or type)	reserved	reserved
TIMEZONE_HOUR		reserved	reserved
TIMEZONE_MINUTE		reserved	reserved
TO	reserved	reserved	reserved
TOAST	non-reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
TRAILING	reserved	reserved	reserved
TRANSACTION	non-reserved	reserved	reserved
TRANSACTIONS_COMMITTED		non-reserved	
TRANSACTIONS_ROLLED_BACK		non-reserved	
TRANSACTION_ACTIVE		non-reserved	
TRANSFORM		non-reserved	
TRANSFORMS		non-reserved	
TRANSLATE		non-reserved	reserved
TRANSLATION		reserved	reserved
TREAT	non-reserved (cannot be function or type)	reserved	
TRIGGER	non-reserved	reserved	
TRIGGER_CATALOG		non-reserved	
TRIGGER_NAME		non-reserved	
TRIGGER_SCHEMA		non-reserved	
TRIM	non-reserved (cannot be function or type)	non-reserved	reserved
TRUE	reserved	reserved	reserved
TRUNCATE	non-reserved		
TRUSTED	non-reserved		
TYPE	non-reserved	non-reserved	non-reserved
UNCOMMITTED		non-reserved	non-reserved
UNDER		reserved	
UNENCRYPTED	non-reserved		
UNION	reserved	reserved	reserved
UNIQUE	reserved	reserved	reserved
UNKNOWN	non-reserved	reserved	reserved
UNLISTEN	non-reserved		
UNNAMED		non-reserved	non-reserved
UNNEST		reserved	
UNTIL	non-reserved		
UPDATE	non-reserved	reserved	reserved
UPPER		non-reserved	reserved
USAGE	non-reserved	reserved	reserved
USER	reserved	reserved	reserved
USER_DEFINED_TYPE_CATALOG		non-reserved	
USER_DEFINED_TYPE_NAME		non-reserved	
USER_DEFINED_TYPE_SCHEMA		non-reserved	
USING	reserved	reserved	reserved
VACUUM	non-reserved		
VALID	non-reserved		

Key Word	PostgreSQL	SQL 99	SQL 92
VALIDATOR	non-reserved		
VALUE		reserved	reserved
VALUES	non-reserved	reserved	reserved
VARCHAR	non-reserved (cannot be function or type)	reserved	reserved
VARIABLE		reserved	
VARYING	non-reserved	reserved	reserved
VERBOSE	reserved (can be function)		
VERSION	non-reserved		
VIEW	non-reserved	reserved	reserved
VOLATILE	non-reserved		
WHEN	reserved	reserved	reserved
WHENEVER		reserved	reserved
WHERE	reserved	reserved	reserved
WITH	non-reserved	reserved	reserved
WITHOUT	non-reserved	reserved	
WORK	non-reserved	reserved	reserved
WRITE	non-reserved	reserved	reserved
YEAR	non-reserved	reserved	reserved
ZONE	non-reserved	reserved	reserved

Appendix C. SQL Conformance

This section attempts to outline to what extent PostgreSQL conforms to the SQL standard. Full compliance to the standard or a complete statement about the compliance to the standard is complicated and not particularly useful, so this section can only give an overview.

The formal name of the SQL standard is ISO/IEC 9075 “Database Language SQL”. A revised version of the standard is released from time to time; the most recent one appearing in 1999. That version is refered to as ISO/IEC 9075:1999, or informally as SQL99. The version prior to that was SQL92. PostgreSQL development tends to aim for conformance with the latest official version of the standard where such conformance does not contradict traditional features or common sense. At the time of this writing, ballotting is under way for a new revision of the standard, which, if approved, will eventually become the conformance target for future PostgreSQL development.

SQL92 defined three feature sets for conformance: Entry, Intermediate, and Full. Most database products claiming SQL standard conformance were conforming at only the Entry level, since the entire set of features in the Intermediate and Full levels was either too voluminous or in conflict with legacy behaviors.

SQL99 defines a large set of individual features rather than the ineffectively broad three levels found in SQL92. A large subset of these features represents the “core” features, which every conforming SQL implementation must supply. The rest of the features are purely optional. Some optional features are grouped together to form “packages”, which SQL implementations can claim conformance to, thus claiming conformance to particular groups of features.

The SQL99 standard is also split into 5 parts: Framework, Foundation, Call Level Interface, Persistent Stored Modules, and Host Language Bindings. PostgreSQL only covers parts 1, 2, and 5. Part 3 is similar to the ODBC interface, and part 4 is similar to the PL/pgSQL programming language, but exact conformance is not specifically intended in either case.

In the following two sections, we provide a list of those features that PostgreSQL supports, followed by a list of the features defined in SQL99 which are not yet supported in PostgreSQL. Both of these lists are approximate: There may be minor details that are nonconforming for a feature that is listed as supported, and large parts of an unsupported feature may in fact be implemented. The main body of the documentation always contains the most accurate information about what does and does not work.

Note

Feature codes containing a hyphen are subfeatures. Therefore, if a particular subfeature is not supported, the main feature is listed as unsupported even if some other subfeatures are supported.

C.1. Supported Features

Identifier	Package	Description	Comment
B012	Core	Embedded C	
B021		Direct SQL	
E011	Core	Numeric data types	
E011-01	Core	INTEGER and SMALLINT data types	
E011-02	Core	REAL, DOUBLE PRECISON, and FLOAT data types	
E011-03	Core	DECIMAL and NUMERIC data types	

Identifier	Package	Description	Comment
E011-04	Core	Arithmetic operators	
E011-05	Core	Numeric comparison	
E011-06	Core	Implicit casting among the numeric data types	
E021	Core	Character data types	
E021-01	Core	CHARACTER data type	
E021-02	Core	CHARACTER VARYING data type	
E021-03	Core	Character literals	
E021-04	Core	CHARACTER_LENGTH function	
E021-05	Core	OCTET_LENGTH function	
E021-06	Core	SUBSTRING function	
E021-07	Core	Character concatenation	
E021-08	Core	UPPER and LOWER functions	
E021-09	Core	TRIM function	
E021-10	Core	Implicit casting among the character data types	
E021-11	Core	POSITION function	
E011-12	Core	Character comparison	
E031	Core	Identifiers	
E031-01	Core	Delimited identifiers	
E031-02	Core	Lower case identifiers	
E031-03	Core	Trailing underscore	
E051	Core	Basic query specification	
E051-01	Core	SELECT DISTINCT	
E051-02	Core	GROUP BY clause	
E051-04	Core	GROUP BY can contain columns not in <select list>	
E051-05	Core	Select list items can be renamed	AS is required
E051-06	Core	HAVING clause	
E051-07	Core	Qualified * in select list	
E051-08	Core	Correlation names in the FROM clause	
E051-09	Core	Rename columns in the FROM clause	
E061	Core	Basic predicates and search conditions	
E061-01	Core	Comparison predicate	

Identifier	Package	Description	Comment
E061-02	Core	BETWEEN predicate	
E061-03	Core	IN predicate with list of values	
E061-04	Core	LIKE predicate	
E061-05	Core	LIKE predicate ESCAPE clause	
E061-06	Core	NULL predicate	
E061-07	Core	Quantified comparison predicate	
E061-08	Core	EXISTS predicate	
E061-09	Core	Subqueries in comparison predicate	
E061-11	Core	Subqueries in IN predicate	
E061-12	Core	Subqueries in quantified comparison predicate	
E061-13	Core	Correlated subqueries	
E061-14	Core	Search condition	
E071	Core	Basic query expressions	
E071-01	Core	UNION DISTINCT table operator	
E071-02	Core	UNION ALL table operator	
E071-03	Core	EXCEPT DISTINCT table operator	
E071-05	Core	Columns combined via table operators need not have exactly the same data type	
E071-06	Core	Table operators in subqueries	
E081-01	Core	SELECT privilege	
E081-02	Core	DELETE privilege	
E081-03	Core	INSERT privilege at the table level	
E081-04	Core	UPDATE privilege at the table level	
E081-06	Core	REFERENCES privilege at the table level	
E091	Core	Set functions	
E091-01	Core	AVG	
E091-02	Core	COUNT	
E091-03	Core	MAX	
E091-04	Core	MIN	

Identifier	Package	Description	Comment
E091-05	Core	SUM	
E091-06	Core	ALL quantifier	
E091-07	Core	DISTINCT quantifier	
E101	Core	Basic data manipulation	
E101-01	Core	INSERT statement	
E101-03	Core	Searched UPDATE statement	
E101-04	Core	Searched DELETE statement	
E111	Core	Single row SELECT statement	
E121-01	Core	DECLARE CURSOR	
E121-02	Core	ORDER BY columns need not be in select list	
E121-03	Core	Value expressions in ORDER BY clause	
E121-08	Core	CLOSE statement	(cursor)
E121-10	Core	FETCH statement implicit NEXT	
E131	Core	Null value support (nulls in lieu of values)	
E141	Core	Basic integrity constraints	
E141-01	Core	NOT NULL constraints	
E141-02	Core	UNIQUE constraints of NOT NULL columns	
E141-03	Core	PRIMARY KEY constraints	
E141-04	Core	Basic FOREIGN KEY constraint with the NO ACTION default for both referential delete action and referential update action	
E141-06	Core	CHECK constraints	
E141-07	Core	Column defaults	
E141-08	Core	NOT NULL inferred on PRIMARY KEY	
E141-10	Core	Names in a foreign key can be specified in any order	
E151	Core	Transaction support	
E151-01	Core	COMMIT statement	
E151-02	Core	ROLLBACK statement	
E152-01	Core	SET TRANSACTION statement: ISOLATION	

Identifier	Package	Description	Comment
		LEVEL SERIALIZABLE clause	
E161	Core	SQL comments using leading double minus	
F031	Core	Basic schema manipulation	
F031-01	Core	CREATE TABLE statement to create persistent base tables	
F031-02	Core	CREATE VIEW statement	
F031-03	Core	GRANT statement	
F031-04	Core	ALTER TABLE statement: ADD COLUMN clause	
F031-13	Core	DROP TABLE statement: RESTRICT clause	
F031-16	Core	DROP VIEW statement: RESTRICT clause	
F032		CASCADE drop behavior	
F033		ALTER TABLE statement: DROP COLUMN clause	
F041	Core	Basic joined table	
F041-01	Core	Inner join (but not necessarily the INNER keyword)	
F041-02	Core	INNER keyword	
F041-03	Core	LEFT OUTER JOIN	
F041-04	Core	RIGHT OUTER JOIN	
F041-05	Core	Outer joins can be nested	
F041-07	Core	The inner table in a left or right outer join can also be used in an inner join	
F041-08	Core	All comparison operators are supported (rather than just =)	
F051	Core	Basic date and time	
F051-01	Core	DATE data type (including support of DATE literal)	

Identifier	Package	Description	Comment
F051-02	Core	TIME data type (including support of TIME literal) with fractional seconds precision of at least 0	
F051-03	Core	TIMESTAMP data type (including support of TIMESTAMP literal) with fractional seconds precision of at least 0 and 6	
F051-04	Core	Comparison predicate on DATE, TIME, and TIMESTAMP data types	
F051-05	Core	Explicit CAST between datetime types and character types	
F051-06	Core	CURRENT_DATE	
F051-07	Core	LOCALTIME	
F051-08	Core	LOCALTIMESTAMP	
F052	Enhanced datetime facilities	Intervals and datetime arithmetic	
F081	Core	UNION and EXCEPT in views	
F111-02		READ COMMITTED isolation level	
F131	Core	Grouped operations	
F131-01	Core	WHERE, GROUP BY, and HAVING clauses supported in queries with grouped views	
F131-02	Core	Multiple tables supported in queries with grouped views	
F131-03	Core	Set functions supported in queries with grouped views	
F131-04	Core	Subqueries with GROUP BY and HAVING clauses and grouped views	
F131-05	Core	Single row SELECT with GROUP BY and HAVING clauses and grouped views	
F171		Multiple schemas per user	
F191	Enhanced integrity management	Referential delete actions	

Identifier	Package	Description	Comment
F201	Core	CAST function	
F221	Core	Explicit defaults	
F222		INSERT statement: DEFAULT VALUES clause	
F251		Domain support	
F261	Core	CASE expression	
F261-01	Core	Simple CASE	
F261-02	Core	Searched CASE	
F261-03	Core	NULLIF	
F261-04	Core	COALESCE	
F271		Compound character literals	
F281		LIKE enhancements	
F302	OLAP facilities	INTERSECT table operator	
F302-01	OLAP facilities	INTERSECT DISTINCT table operator	
F302-02	OLAP facilities	INTERSECT ALL table operator	
F304	OLAP facilities	EXCEPT ALL table operator	
F311	Core	Schema definition statement	
F311-01	Core	CREATE SCHEMA	
F311-02	Core	CREATE TABLE for persistent base tables	
F311-03	Core	CREATE VIEW	
F311-05	Core	GRANT statement	
F321		User authorization	
F361		Subprogram support	
F381		Extended schema manipulation	
F381-01		ALTER TABLE statement: ALTER COLUMN clause	
F381-02		ALTER TABLE statement: ADD CONSTRAINT clause	
F381-03		ALTER TABLE statement: DROP CONSTRAINT clause	
F391		Long identifiers	
F401	OLAP facilities	Extended joined table	

Identifier	Package	Description	Comment
F401-01	OLAP facilities	NATURAL JOIN	
F401-02	OLAP facilities	FULL OUTER JOIN	
F401-03	OLAP facilities	UNION JOIN	
F401-04	OLAP facilities	CROSS JOIN	
F411	Enhanced datetime facilities	Time zone specification	
F421		National character	
F431-01		FETCH with explicit NEXT	
F431-04		FETCH PRIOR	
F431-06		FETCH RELATIVE	
F441		Extended set function support	
F471	Core	Scalar subquery values	
F481	Core	Expanded NULL predicate	
F491	Enhanced integrity management	Constraint management	
F511		BIT data type	
F531		Temporary tables	
F555	Enhanced datetime facilities	Enhanced seconds precision	
F561		Full value expressions	
F571		Truth value tests	
F591	OLAP facilities	Derived tables	
F611		Indicator data types	
F651		Catalog name qualifiers	
F701	Enhanced integrity management	Referential update actions	
F761		Session management	
F791		Insensitive cursors	
F801		Full set function	
S071	Enhanced object support	SQL paths in function and type name resolution	
S111	Enhanced object support	ONLY in query expressions	
S211	Enhanced object support, SQL/MM support	User-defined cast functions	
T031		BOOLEAN data type	
T141		SIMILAR predicate	
T151		DISTINCT predicate	

Identifier	Package	Description	Comment
T191	Enhanced integrity management	Referential action RESTRICT	
T201	Enhanced integrity management	Comparable data types for referential constraints	
T211-01	Enhanced integrity management	Triggers activated on UPDATE, INSERT, or DELETE of one base table	
T211-02	Enhanced integrity management	BEFORE triggers	
T211-03	Enhanced integrity management	AFTER triggers	
T211-04	Enhanced integrity management	FOR EACH ROW triggers	
T211-07	Enhanced integrity management	TRIGGER privilege	
T231		SENSITIVE cursors	
T241		START TRANSACTION statement	
T312		OVERLAY function	
T321-01	Core	User-defined functions with no overloading	
T321-03	Core	Function invocation	
T322	PSM, SQL/MM support	Overloading of SQL-invoked functions and procedures	
T323		Explicit security for external routines	
T351		Bracketed SQL comments (/*...*/ comments)	
T441		ABS and MOD functions	
T501		Enhanced EXISTS predicate	
T551		Optional key words for default syntax	
T581		Regular expression substring function	
T591		UNIQUE constraints of possibly null columns	

C.2. Unsupported Features

The following features defined in SQL99 are not implemented in the current release of PostgreSQL. In a few cases, equivalent functionality is available.

Identifier	Package	Description	Comment
B011	Core	Embedded Ada	
B013	Core	Embedded COBOL	
B014	Core	Embedded Fortran	
B015	Core	Embedded MUMPS	
B016	Core	Embedded Pascal	
B017	Core	Embedded PL/I	
B031		Basic dynamic SQL	
B032		Extended dynamic SQL	
B032-1		<describe input> statement	
B041		Extensions to embedded SQL exception declarations	
B051		Enhanced execution rights	
E081	Core	Basic Privileges	
E081-05	Core	UPDATE privilege at the column level	
E081-07	Core	REFERENCES privilege at the column level	
E081-08	Core	WITH GRANT OPTION	
E121	Core	Basic cursor support	
E121-04	Core	OPEN statement	(cursor)
E121-06	Core	Positioned UPDATE statement	(cursor)
E121-07	Core	Positioned DELETE statement	(cursor)
E121-17	Core	WITH HOLD cursors	Cursor to stay open across transactions
E152	Core	Basic SET TRANSACTION statement	
E152-02	Core	SET TRANSACTION statement: READ ONLY and READ WRITE clauses	Syntax accepted; READ ONLY not supported
E153	Core	Updatable queries with subqueries	
E171	Core	SQLSTATE support	
F181		Multiple module support	
E182	Core	Module language	
F021	Core	Basic information schema	

Identifier	Package	Description	Comment
F021-01	Core	COLUMNS view	
F021-02	Core	TABLES view	
F021-03	Core	VIEWS view	
F021-04	Core	TABLE_CONSTRAINTS view	
F021-05	Core	REFERENTIAL_CONSTRAINTS view	
F021-06	Core	CHECK_CONSTRAINTS view	
F031-19	Core	REVOKE statement: RESTRICT clause	
F034		Extended REVOKE statement	
F034-01		REVOKE statement performed by other than the owner of a schema object	
F034-02		REVOKE statement: GRANT OPTION FOR clause	
F034-03		REVOKE statement to revoke a privilege that the grantee has WITH GRANT OPTION	
F111		Isolation levels other than SERIALIZABLE	
F111-01		READ UNCOMMITTED isolation level	
F111-03		REPEATABLE READ isolation level	
F121		Basic diagnostics management	
F121-01		GET DIAGNOSTICS statement	
F121-02		SET TRANSACTION statement: DIAGNOSTICS SIZE clause	
F231		Privilege Tables	
F231-01		TABLE_PRIVILEGES view	
F231-02		COLUMN_PRIVILEGES view	
F231-03		USAGE_PRIVILEGES view	
F291		UNIQUE predicate	

Identifier	Package	Description	Comment
F301		CORRESPONDING in query expressions	
F311-04	Core	CREATE VIEW: WITH CHECK OPTION	
F341		Usage tables	
F431		Read-only scrollable cursors	
F431-02		FETCH FIRST	
F431-03		FETCH LAST	
F431-05		FETCH ABSOLUTE	
F451		Character set definition	
F461		Named character sets	
F501	Core	Features and conformance views	
F501-01	Core	SQL_FEATURES view	
F501-02	Core	SQL_SIZING view	
F501-03	Core	SQL_LANGUAGES view	
F502		Enhanced documentation tables	
F502-01		SQL_SIZING_PROFILES view	
F502-02		SQL_IMPLEMENTATION_INFO view	
F502-03		SQL_PACKAGES view	
F521	Enhanced integrity management	Assertions	
F641	OLAP facilities	Row and table constructors	
F661		Simple tables	
F671	Enhanced integrity management	Subqueries in CHECK	intentionally omitted
F691		Collation and translation	
F711		ALTER domain	
F721		Deferrable constraints	foreign keys only
F731		INSERT column privileges	
F741		Referential MATCH types	no partial match yet
F751		View CHECK enhancements	
F771		Connection management	

Identifier	Package	Description	Comment
F781		Self-referencing operations	
F811		Extended flagging	
F812	Core	Basic flagging	
F813		Extended flagging for "Core SQL Flagging" and "Catalog Lookup" only	
F821		Local table references	
F831		Full cursor update	
F831-01		Updatable scrollable cursors	
F831-02		Updatable ordered cursors	
S011	Core	Distinct data types	
S011-01	Core	USER_DEFINED_TYPES view	
S023	Basic object support, SQL/MM support	Basic structured types	
S024, SQL/MM support	Enhanced object support	Enhanced structured types	
S041	Basic object support	Basic reference types	
S043	Enhanced object support	Enhanced reference types	
S051	Basic object support	Create table of type	
S081	Enhanced object support	Subtables	
S091	SQL/MM support	Basic array support	PostgreSQL arrays are different
S091-01	SQL/MM support	Arrays of built-in data types	
S091-02	SQL/MM support	Arrays of distinct types	
S091-03	SQL/MM support	Array expressions	
S092	SQL/MM support	Arrays of user-defined types	
S094		Arrays of reference types	
S151	Basic object support	Type predicate	IS OF
S161	Enhanced object support	Subtype treatment	TREAT(expr AS type)
S201		SQL routines on arrays	
S201-01		Array parameters	
S201-02		Array as result type of functions	
S231	Enhanced object support	Structured type locators	

Identifier	Package	Description	Comment
S232		Array locators	
S241	Enhanced object support	Transform functions	
S251		User-defined orderings	CREATE ORDERING FOR
S261		Specific type method	
T011		Timestamp in Information Schema	
T041	Basic object support	Basic LOB data type support	
T041-01	Basic object support	BLOB data type	
T041-02	Basic object support	CLOB data type	
T041-03	Basic object support	POSITION, LENGTH, LOWER, TRIM, UPPER, and SUBSTRING functions for LOB data types	
T041-04	Basic object support	Concatenation of LOB data types	
T041-05	Basic object support	LOB locator: non-holdable	
T042		Extended LOB data type support	
T051		Row types	
T111		Updatable joins, unions, and columns	
T121		WITH (excluding RECURSIVE) in query expression	
T131		Recursive query	
T171		LIKE clause in table definition	CREATE TABLE T1 (LIKE T2)
T211	Enhanced integrity management, Active database	Basic trigger capability	
T211-05	Enhanced integrity management	Ability to specify a search condition that must be true before the trigger is invoked	
T211-06	Enhanced integrity management	Support for run-time rules for the interaction of triggers and constraints	
T211-08	Enhanced integrity management	Multiple triggers for the same the event are executed in the order in which they were created	

Identifier	Package	Description	Comment
T212	Enhanced integrity management	Enhanced trigger capability	
T251		SET TRANSACTION statement: LOCAL option	
T261		Chained transactions	
T271		Savepoints	
T281		SELECT privilege with column granularity	
T301		Functional Dependencies	
T321	Core	Basic SQL-invoked routines	
T321-02	Core	User-defined stored procedures with no overloading	
T321-04	Core	CALL statement	
T321-05	Core	RETURN statement	
T321-06	Core	ROUTINES view	
T321-07	Core	PARAMETERS view	
T331		Basic roles	
T332		Extended roles	
T401		INSERT into a cursor	
T411		UPDATE statement: SET ROW option	
T431	OLAP facilities	CUBE and ROLLUP operations	
T461		Symmetric BETWEEN predicate	
T471		Result sets return value	
T491		LATERAL derived table	
T511		Transaction counts	
T541		Updatable table references	
T561		Holdable locators	
T571		Array-returning external SQL-invoked functions	
T601		Local cursor references	

Bibliography

Selected references and readings for SQL and PostgreSQL.

Some white papers and technical reports from the original POSTGRES development team are available at the University of California, Berkeley, Computer Science Department web site[1]

SQL Reference Books

Reference texts for SQL features.

[bowman93] *The Practical SQL Handbook*. Bowman et al, 1996. Using Structured Query Language. Third Edition. Judith Bowman, Sandra Emerson, and Marcy Darnovsky. 0-201-44787-8. 1996. Addison-Wesley. Copyright © 1996 Addison-Wesley Longman, Inc..

[date97] *A Guide to the SQL Standard*. Date and Darwen, 1997. A user's guide to the standard database language SQL. Fourth Edition. C. J. Date and Hugh Darwen. 0-201-96426-0. 1997. Addison-Wesley. Copyright © 1997 Addison-Wesley Longman, Inc..

[date94] *An Introduction to Database Systems*. Date, 1994. Sixth Edition. C. J. Date. Volume 1. 1994. Addison-Wesley. Copyright © 1994 Addison-Wesley Longman, Inc..

[elma99] *Fundamentals of Database Systems*. 3rd Edition. Ramez Elmasri and Shamkant Navathe. 0-805-31755-4. August 1999. Addison-Wesley.

[melt93] *Understanding the New SQL*. Melton and Simon, 1993. A complete guide. Jim Melton and Alan R. Simon. 1-55860-245-3. 1993. Morgan Kaufmann. Copyright © 1993 Morgan Kaufmann Publishers, Inc..

[ull88] *Principles of Database and Knowledge*. Base Systems. Ullman, 1988. Jeffrey D. Ullman. Volume 1. Computer Science Press. 1988.

PostgreSQL-Specific Documentation

This section is for related documentation.

[sim98] *Enhancement of the ANSI SQL Implementation of PostgreSQL*. Simkovics, 1998. Stefan Simkovics. November 29, 1998. Department of Information Systems, Vienna University of Technology. Vienna, Austria.

[yu95] *The Postgres95. User Manual*. Yu and Chen, 1995. A. Yu and J. Chen. . Sept. 5, 1995. University of California. Berkeley, California.

[fong] *The design and implementation of the POSTGRES query optimizer*[2]. Zelaine Fong. University of California, Berkeley, Computer Science Department.

Proceedings and Articles

This section is for articles and newsletters.

[olson93] *Partial indexing in POSTGRES: research project*. Olson, 1993. Nels Olson. 1993. UCB Engin T7.49.1993 O676. University of California. Berkeley, California.

[ong90] “A Unified Framework for Version Modeling Using Production Rules in a Database System”. Ong and Goh, 1990. L. Ong and J. Goh. *ERL Technical Memorandum M90/33*. April, 1990. University of California. Berkely, California.

[1] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/
[2] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/UCB-MS-zfong.pdf

[rowe87] “The POSTGRES data model[3]”. Rowe and Stonebraker, 1987. L. Rowe and M. Stonebraker. VLDB Conference. Sept. 1987. Brighton, England. .

[seshadri95] “Generalized Partial Indexes[4] ”. Seshardri, 1995. P. Seshadri and A. Swami. Eleventh International Conference on Data Engineering. 6-10 March 1995. Taipeh, Taiwan. . 1995. Cat. No.95CH35724. IEEE Computer Society Press. Los Alamitos, California. 420-7.

[ston86] “The design of POSTGRES[5]”. Stonebraker and Rowe, 1986. M. Stonebraker and L. Rowe. ACM-SIGMOD Conference on Management of Data. May 1986. Washington, DC. .

[ston87a] “The design of the POSTGRES. rules system”. Stonebraker, Hanson, Hong, 1987. M. Stonebraker, E. Hanson, and C. H. Hong. IEEE Conference on Data Engineering. Feb. 1987. Los Angeles, California. .

[ston87b] “The design of the POSTGRES storage system[6]”. Stonebraker, 1987. M. Stonebraker. VLDB Conference. Sept. 1987. Brighton, England. .

[ston89] “A commentary on the POSTGRES rules system[7]”. Stonebraker et al, 1989. M. Stonebraker, M. Hearst, and S. Potamianos. *SIGMOD Record 18(3)*. Sept. 1989.

[ston89b] “The case for partial indexes[8]”. Stonebraker, M, 1989b. M. Stonebraker. *SIGMOD Record 18(4)*. 4-11. Dec. 1989.

[ston90a] “The implementation of POSTGRES[9]”. Stonebraker, Rowe, Hirohama, 1990. M. Stonebraker, L. A. Rowe, and M. Hirohama. *Transactions on Knowledge and Data Engineering 2(1)*. IEEE. March 1990.

[ston90b] “On Rules, Procedures, Caching and Views in Database Systems[10]”. Stonebraker et al, ACM, 1990. M. Stonebraker, A. Jhingran, J. Goh, and S. Potamianos. ACM-SIGMOD Conference on Management of Data. June 1990. .

[3] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M87-13.pdf
[4] http://simon.cs.cornell.edu/home/praveen/papers/partindex.de95.ps.Z
[5] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M85-95.pdf
[6] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M87-06.pdf
[7] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M89-82.pdf
[8] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M89-17.pdf
[9] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M90-34.pdf
[10] http://s2k-ftp.CS.Berkeley.EDU:8000/postgres/papers/ERL-M90-36.pdf

PostgreSQL 7.3.21
Administrator's Guide

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 Administrator's Guide

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

Preface cxcv
1. What's In This Book cxcv
1. Installation Instructions 1
1.1. Short Version 1
1.2. Requirements 1
1.3. Getting The Source 3
1.4. If You Are Upgrading 3
1.5. Installation Procedure 4
1.6. Post-Installation Setup 10
1.6.1. Shared Libraries 10
1.6.2. Environment Variables 11
1.7. Supported Platforms 11
2. Installation on Windows 15
3. Server Run-time Environment 16
3.1. The PostgreSQL User Account 16
3.2. Creating a Database Cluster 16
3.3. Starting the Database Server 17
3.3.1. Server Start-up Failures 18
3.3.2. Client Connection Problems 19
3.4. Run-time Configuration 20
3.4.1. pg_settings 21
3.4.2. Planner and Optimizer Tuning 21
3.4.3. Logging and Debugging 23
3.4.4. General Operation 26
3.4.5. WAL 32
3.4.6. Short Options 33
3.5. Managing Kernel Resources 34
3.5.1. Shared Memory and Semaphores 34
3.5.2. Resource Limits 38
3.6. Shutting Down the Server 39
3.7. Secure TCP/IP Connections with SSL 39
3.8. Secure TCP/IP Connections with SSH Tunnels 40
4. Database Users and Privileges 42
4.1. Database Users 42
4.2. User Attributes 42
4.3. Groups 43
4.4. Privileges 43
4.5. Functions and Triggers 44
5. Managing Databases 45
5.1. Overview 45
5.2. Creating a Database 45
5.3. Template Databases 46
5.4. Database Configuration 47
5.5. Alternative Locations 47
5.6. Destroying a Database 48
6. Client Authentication 50
6.1. The `pg_hba.conf` file 50
6.2. Authentication methods 54
6.2.1. Trust authentication 54
6.2.2. Password authentication 55
6.2.3. Kerberos authentication 55
6.2.4. Ident-based authentication 56
6.2.5. PAM Authentication 57
6.3. Authentication problems 58
7. Localization 59

7.1. Locale Support 59
7.1.1. Overview 59
7.1.2. Benefits 60
7.1.3. Problems 60
7.2. Multibyte Support 61
7.2.1. Supported character set encodings 61
7.2.2. Setting the Encoding 62
7.2.3. Automatic encoding conversion between server and client 63
7.2.4. What happens if the translation is not possible? 65
7.2.5. References 65
7.2.6. History 65
7.2.7. WIN1250 on Windows/ODBC 67
7.3. Single-byte character set recoding 67
8. Routine Database Maintenance Tasks 69
8.1. General Discussion 69
8.2. Routine Vacuuming 69
8.2.1. Recovering disk space 69
8.2.2. Updating planner statistics 70
8.2.3. Preventing transaction ID wraparound failures 71
8.3. Routine Reindexing 72
8.4. Log File Maintenance 72
9. Backup and Restore 74
9.1. SQL Dump 74
9.1.1. Restoring the dump 74
9.1.2. Using `pg_dumpall` 75
9.1.3. Large Databases 75
9.1.4. Caveats 76
9.2. File system level backup 76
9.3. Migration between releases 77
10. Monitoring Database Activity 78
10.1. Standard Unix Tools 78
10.2. Statistics Collector 79
10.2.1. Statistics Collection Configuration 79
10.2.2. Viewing Collected Statistics 79
10.3. Viewing Locks 82
11. Monitoring Disk Usage 85
11.1. Determining Disk Usage 85
11.2. Disk Full Failure 86
12. Write-Ahead Logging (WAL) 87
12.1. General Description 87
12.1.1. Immediate Benefits of WAL 87
12.1.2. Future Benefits 87
12.2. Implementation 88
12.2.1. Database Recovery with WAL 88
12.3. WAL Configuration 88
13. Regression Tests 91
13.1. Introduction 91
13.2. Running the Tests 91
13.3. Test Evaluation 92
13.3.1. Error message differences 92
13.3.2. Locale differences 92
13.3.3. Date and time differences 93
13.3.4. Floating-point differences 93
13.3.5. Polygon differences 93
13.3.6. Row ordering differences 94
13.3.7. The “random” test 94
13.4. Platform-specific comparison files 94
A. Release Notes 95

A.1. Release 7.3.21 95
A.1.1. Migration to Version 7.3.21 95
A.1.2. Changes 95
A.2. Release 7.3.20 96
A.2.1. Migration to Version 7.3.20 96
A.2.2. Changes 96
A.3. Release 7.3.19 96
A.3.1. Migration to Version 7.3.19 96
A.3.2. Changes 96
A.4. Release 7.3.18 96
A.4.1. Migration to Version 7.3.18 97
A.4.2. Changes 97
A.5. Release 7.3.17 97
A.5.1. Migration to Version 7.3.17 97
A.5.2. Changes 97
A.6. Release 7.3.16 97
A.6.1. Migration to Version 7.3.16 97
A.6.2. Changes 98
A.7. Release 7.3.15 98
A.7.1. Migration to Version 7.3.15 98
A.7.2. Changes 98
A.8. Release 7.3.14 99
A.8.1. Migration to Version 7.3.14 99
A.8.2. Changes 99
A.9. Release 7.3.13 99
A.9.1. Migration to Version 7.3.13 99
A.9.2. Changes 100
A.10. Release 7.3.12 100
A.10.1. Migration to Version 7.3.12 100
A.10.2. Changes 100
A.11. Release 7.3.11 100
A.11.1. Migration to Version 7.3.11 101
A.11.2. Changes 101
A.12. Release 7.3.10 101
A.12.1. Migration to Version 7.3.10 101
A.12.2. Changes 102
A.13. Release 7.3.9 103
A.13.1. Migration to Version 7.3.9 103
A.13.2. Changes 103
A.14. Release 7.3.8 103
A.14.1. Migration to Version 7.3.8 103
A.14.2. Changes 103
A.15. Release 7.3.7 104
A.15.1. Migration to Version 7.3.7 104
A.15.2. Changes 104
A.16. Release 7.3.6 104
A.16.1. Migration to Version 7.3.6 104
A.16.2. Changes 104
A.17. Release 7.3.5 105
A.17.1. Migration to Version 7.3.5 105
A.17.2. Changes 105
A.18. Release 7.3.4 106
A.18.1. Migration to Version 7.3.4 106
A.18.2. Changes 106
A.19. Release 7.3.3 107
A.19.1. Migration to Version 7.3.3 107
A.19.2. Changes 107
A.20. Release 7.3.2 109

A.20.1. Migration to Version 7.3.2 109
A.20.2. Changes 109
A.21. Release 7.3.1 110
A.21.1. Migration to Version 7.3.1 110
A.21.2. Changes 110
A.22. Release 7.3 111
A.22.1. Overview 111
A.22.2. Migration to Version 7.3 112
A.22.3. Changes 113
A.23. Release 7.2.8 123
A.23.1. Migration to Version 7.2.8 123
A.23.2. Changes 123
A.24. Release 7.2.7 123
A.24.1. Migration to Version 7.2.7 124
A.24.2. Changes 124
A.25. Release 7.2.6 124
A.25.1. Migration to Version 7.2.6 124
A.25.2. Changes 124
A.26. Release 7.2.5 125
A.26.1. Migration to Version 7.2.5 125
A.26.2. Changes 125
A.27. Release 7.2.4 125
A.27.1. Migration to Version 7.2.4 125
A.27.2. Changes 125
A.28. Release 7.2.3 126
A.28.1. Migration to Version 7.2.3 126
A.28.2. Changes 126
A.29. Release 7.2.2 126
A.29.1. Migration to Version 7.2.2 126
A.29.2. Changes 126
A.30. Release 7.2.1 127
A.30.1. Migration to Version 7.2.1 127
A.30.2. Changes 127
A.31. Release 7.2 128
A.31.1. Overview 128
A.31.2. Migration to Version 7.2 128
A.31.3. Changes 129
A.32. Release 7.1.3 137
A.32.1. Migration to Version 7.1.3 138
A.32.2. Changes 138
A.33. Release 7.1.2 138
A.33.1. Migration to Version 7.1.2 138
A.33.2. Changes 138
A.34. Release 7.1.1 138
A.34.1. Migration to Version 7.1.1 138
A.34.2. Changes 138
A.35. Release 7.1 139
A.35.1. Migration to Version 7.1 139
A.35.2. Changes 140
A.36. Release 7.0.3 143
A.36.1. Migration to Version 7.0.3 143
A.36.2. Changes 143
A.37. Release 7.0.2 144
A.37.1. Migration to Version 7.0.2 144
A.37.2. Changes 144
A.38. Release 7.0.1 145
A.38.1. Migration to Version 7.0.1 145
A.38.2. Changes 145

A.39. Release 7.0 145
A.39.1. Migration to Version 7.0 146
A.39.2. Changes 146
A.40. Release 6.5.3 153
A.40.1. Migration to Version 6.5.3 153
A.40.2. Changes 153
A.41. Release 6.5.2 153
A.41.1. Migration to Version 6.5.2 153
A.41.2. Changes 153
A.42. Release 6.5.1 154
A.42.1. Migration to Version 6.5.1 154
A.42.2. Changes 154
A.43. Release 6.5 155
A.43.1. Migration to Version 6.5 156
A.43.2. Changes 156
A.44. Release 6.4.2 160
A.44.1. Migration to Version 6.4.2 160
A.44.2. Changes 160
A.45. Release 6.4.1 160
A.45.1. Migration to Version 6.4.1 160
A.45.2. Changes 160
A.46. Release 6.4 161
A.46.1. Migration to Version 6.4 161
A.46.2. Changes 161
A.47. Release 6.3.2 165
A.47.1. Changes 166
A.48. Release 6.3.1 166
A.48.1. Changes 166
A.49. Release 6.3 167
A.49.1. Migration to Version 6.3 168
A.49.2. Changes 168
A.50. Release 6.2.1 172
A.50.1. Migration from version 6.2 to version 6.2.1 172
A.50.2. Changes 172
A.51. Release 6.2 173
A.51.1. Migration from version 6.1 to version 6.2 173
A.51.2. Migration from version 1.*x* to version 6.2 173
A.51.3. Changes 173
A.52. Release 6.1.1 175
A.52.1. Migration from version 6.1 to version 6.1.1 175
A.52.2. Changes 175
A.53. Release 6.1 176
A.53.1. Migration to Version 6.1 176
A.53.2. Changes 177
A.54. Release 6.0 178
A.54.1. Migration from version 1.09 to version 6.0 178
A.54.2. Migration from pre-1.09 to version 6.0 179
A.54.3. Changes 179
A.55. Release 1.09 181
A.56. Release 1.02 181
A.56.1. Migration from version 1.02 to version 1.02.1 181
A.56.2. Dump/Reload Procedure 181
A.56.3. Changes 182
A.57. Release 1.01 182
A.57.1. Migration from version 1.0 to version 1.01 183
A.57.2. Changes 184
A.58. Release 1.0 185
A.58.1. Changes 185

A.59. Postgres95 Release 0.03 186
A.59.1. Changes 186
A.60. Postgres95 Release 0.02 189
A.60.1. Changes 189
A.61. Postgres95 Release 0.01 190

List of Tables

3.1. pg_settings Columns 21
3.2. Short option key 33
3.3. System V IPC parameters 34
7.1. Encodings 61
7.2. Communication Encodings 63
10.1. Standard Statistics Views 80
10.2. Statistics Access Functions 81
10.3. Lock Status System View 83

List of Examples

6.1. An example pg_hba.conf file 53
6.2. An example pg_ident.conf file 57

Preface

1. What's In This Book

This book covers topics that are of interest to a PostgreSQL database administrator. This includes installation of the software, set up and configuration of the server, management of users and databases, and maintenance tasks. Anyone who runs a PostgreSQL server, either for personal use, but especially in production, should be familiar with the topics covered in this book.

The information in this book is arranged approximately in the order in which a new user should read it. But the chapters are self-contained and can be read individually as desired. The information in this book is presented in a narrative fashion in topical units. Readers looking for a complete description of a particular command should look into the PostgreSQL 7.3.21 Reference Manual.

The first few chapters are written so that they can be understood without prerequisite knowledge, so that new users who need to set up their own server can begin their exploration with this book. The rest of this book which is about tuning and management presupposes that the reader is familiar with the general use of the PostgreSQL database system. Readers are encouraged to look at the PostgreSQL 7.3.21 Tutorial and the PostgreSQL 7.3.21 User's Guide for additional information.

This book covers PostgreSQL 7.3.21 only. For information on other versions, please read the documentation that accompanies that release.

Chapter 1. Installation Instructions

This chapter describes the installation of PostgreSQL from the source code distribution.

1.1. Short Version

```
./configure
gmake
su
gmake install
adduser postgres
mkdir /usr/local/pgsql/data
chown postgres /usr/local/pgsql/data
su - postgres
/usr/local/pgsql/bin/initdb -D /usr/local/pgsql/data
/usr/local/pgsql/bin/postmaster -D /usr/local/pgsql/data >logfile
 2>&1 &
/usr/local/pgsql/bin/createdb test
/usr/local/pgsql/bin/psql test
```

The long version is the rest of this chapter.

1.2. Requirements

In general, a modern Unix-compatible platform should be able to run PostgreSQL. The platforms that had received specific testing at the time of release are listed in Section 1.7, “Supported Platforms” below. In the `doc` subdirectory of the distribution there are several platform-specific FAQ documents you might wish to consult if you are having trouble.

The following software packages are required for building PostgreSQL:

- GNU make is required; other make programs will *not* work. GNU make is often installed under the name `gmake`; this document will always refer to it by that name. (On some systems GNU make is the default tool with the name `make`.) To test for GNU make enter

  `gmake --version`

  It is recommended to use version 3.76.1 or later.

- You need an ISO/ANSI C compiler. Recent versions of GCC are recommendable, but PostgreSQL is known to build with a wide variety of compilers from different vendors.

- gzip is needed to unpack the distribution in the first place. If you are reading this, you probably already got past that hurdle.

- The GNU Readline library (for comfortable line editing and command history retrieval) will be used by default. If you don't want to use it then you must specify the `--without-readline` option for `configure`. (On NetBSD, the `libedit` library is readline-compatible and is used if `libreadline` is not found.)

- To build on Windows NT or Windows 2000 you need the Cygwin and cygipc packages. See the file `doc/FAQ_MSWIN` for details.

The following packages are optional. They are not required in the default configuration, but they are needed when certain build options are enabled, as explained below.

- To build the server programming language PL/Perl you need a full Perl installation, including the `libperl` library and the header files. Since PL/Perl will be a shared library, the `libperl` library

must be a shared library also on most platforms. This appears to be the default in recent Perl versions, but it was not in earlier versions, and in general it is the choice of whomever installed Perl at your site.

If you don't have the shared library but you need one, a message like this will appear during the build to point out this fact:

```
*** Cannot build PL/Perl because libperl is not a shared library.
*** You might have to rebuild your Perl installation.  Refer to
*** the documentation for details.
```

(If you don't follow the on-screen output you will merely notice that the PL/Perl library object, `plperl.so` or similar, will not be installed.) If you see this, you will have to rebuild and install Perl manually to be able to build PL/Perl. During the configuration process for Perl, request a shared library.

- To build the Python interface module or the PL/Python server programming language, you need a Python installation, including the header files. Since PL/Python will be a shared library, the `libpython` library must be a shared library also on most platforms. This is not the case in a default Python installation.

  If after building and installing you have a file called `plpython.so` (possibly a different extension), then everything went well. Otherwise you should have seen a notice like this flying by:

  ```
  *** Cannot build PL/Python because libpython is not a shared
   library.
  *** You might have to rebuild your Python installation.  Refer to
  *** the documentation for details.
  ```

  That means you have to rebuild (part of) your Python installation to supply this shared library.

  The catch is that the Python distribution or the Python maintainers do not provide any direct way to do this. The closest thing we can offer you is the information in Python FAQ 3.30[1]. On some operating systems you don't really have to build a shared library, but then you will have to convince the PostgreSQL build system of this. Consult the `Makefile` in the `src/pl/plpython` directory for details.

- If you want to build Tcl or Tk components (clients and the PL/Tcl language) you of course need a Tcl installation.

- To build the JDBC driver, you need Ant 1.5 or higher and a JDK. Ant is a special tool for building Java-based packages. It can be downloaded from the Ant web site[2].

  If you have several Java compilers installed, it depends on the Ant configuration which one gets used. Precompiled Ant distributions are typically set up to read a file `.antrc` in the current user's home directory for configuration. For example, to use a different JDK than the default, this may work:

  ```
  JAVA_HOME=/usr/local/sun-jdk1.3
  JAVACMD=$JAVA_HOME/bin/java
  ```

  ### Note

  Do not try to build the driver by calling `ant` or even `javac` directly. This will not work. Run `gmake` normally as described below.

- To enable Native Language Support (NLS), that is, the ability to display a program's messages in a language other than English, you need an implementation of the Gettext API. Some operating

[1] http://www.python.org/doc/FAQ.html#3.30
[2] http://jakarta.apache.org/ant/index.html

systems have this built-in (e.g., Linux, NetBSD, Solaris), for other systems you can download an add-on package from here: http://www.postgresql.org/~petere/gettext.html. If you are using the gettext implementation in the GNU C library then you will additionally need the GNU Gettext package for some utility programs. For any of the other implementations you will not need it.

- Kerberos, OpenSSL, or PAM, if you want to support authentication using these services.

If you are build from a CVS tree instead of using a released source package, or if you want to do development, you also need the following packages:

- Flex and Bison are needed to build a CVS checkout or if you changed the actual scanner and parser definition files. If you need them, be sure to get Flex 2.5.4 or later and Bison 1.50 or later. Other yacc programs can sometimes be used, but doing so requires extra effort and is not recommended. Other lex programs will definitely not work.

If you need to get a GNU package, you can find it at your local GNU mirror site (see http://www.gnu.org/order/ftp.html for a list) or at ftp://ftp.gnu.org/gnu/.

Also check that you have sufficient disk space. You will need about 65 MB for the source tree during compilation and about 15 MB for the installation directory. An empty database cluster takes about 25 MB, databases take about five times the amount of space that a flat text file with the same data would take. If you are going to run the regression tests you will temporarily need up to an extra 90 MB. Use the `df` command to check for disk space.

1.3. Getting The Source

The PostgreSQL 7.3.21 sources can be obtained by anonymous FTP from ftp://ftp.postgresql.org/pub/postgresql-7.3.21.tar.gz. Use a mirror if possible. After you have obtained the file, unpack it:

```
gunzip postgresql-7.3.21.tar.gz
tar xf postgresql-7.3.21.tar
```

This will create a directory `postgresql-7.3.21` under the current directory with the PostgreSQL sources. Change into that directory for the rest of the installation procedure.

1.4. If You Are Upgrading

The internal data storage format changes with new releases of PostgreSQL. Therefore, if you are upgrading an existing installation that does not have a version number “7.3.x”, you must back up and restore your data as shown here. These instructions assume that your existing installation is under the `/usr/local/pgsql` directory, and that the data area is in `/usr/local/pgsql/data`. Substitute your paths appropriately.

1. Make sure that your database is not updated during or after the backup. This does not affect the integrity of the backup, but the changed data would of course not be included. If necessary, edit the permissions in the file `/usr/local/pgsql/data/pg_hba.conf` (or equivalent) to disallow access from everyone except you.

2. To back up your database installation, type:

   ```
   pg_dumpall > outputfile
   ```

   If you need to preserve OIDs (such as when using them as foreign keys), then use the `-o` option when running `pg_dumpall`.

   `pg_dumpall` does not save large objects. Check Section 9.1.4, “Caveats” if you need to do this.

   To make the backup, you can use the `pg_dumpall` command from the version you are currently running. For best results, however, try to use the `pg_dumpall` command from PostgreSQL 7.3.21, since this version contains bug fixes and improvements over older versions. While this

advice might seem idiosyncratic since you haven't installed the new version yet, it is advisable to follow it if you plan to install the new version in parallel with the old version. In that case you can complete the installation normally and transfer the data later. This will also decrease the downtime.

3. If you are installing the new version at the same location as the old one then shut down the old server, at the latest before you install the new files:

   ```
   kill -INT `cat /usr/local/pgsql/data/postmaster.pid`
   ```

   Versions prior to 7.0 do not have this `postmaster.pid` file. If you are using such a version you must find out the process id of the server yourself, for example by typing **ps ax | grep postmaster**, and supply it to the `kill` command.

   On systems that have PostgreSQL started at boot time, there is probably a start-up file that will accomplish the same thing. For example, on a Red Hat Linux system one might find that

   ```
   /etc/rc.d/init.d/postgresql stop
   ```

   works. Another possibility is **pg_ctl stop**.

4. If you are installing in the same place as the old version then it is also a good idea to move the old installation out of the way, in case you have trouble and need to revert to it. Use a command like this:

   ```
   mv /usr/local/pgsql /usr/local/pgsql.old
   ```

After you have installed PostgreSQL 7.3.21, create a new database directory and start the new server. Remember that you must execute these commands while logged in to the special database user account (which you already have if you are upgrading).

```
/usr/local/pgsql/bin/initdb -D /usr/local/pgsql/data
/usr/local/pgsql/bin/postmaster -D /usr/local/pgsql/data
```

Finally, restore your data with

```
/usr/local/pgsql/bin/psql -d template1 -f outputfile
```

using the *new* psql.

These topics are discussed at length in Section 9.3, “Migration between releases”, which you are encouraged to read in any case.

1.5. Installation Procedure

1. **Configuration**

   The first step of the installation procedure is to configure the source tree for your system and choose the options you would like. This is done by running the `configure` script. For a default installation simply enter

   ```
   ./configure
   ```

   This script will run a number of tests to guess values for various system dependent variables and detect some quirks of your operating system, and finally will create several files in the build tree to record what it found. (You can also run `configure` in a directory outside the source tree if you want to keep the build directory separate.)

   The default configuration will build the server and utilities, as well as all client applications and interfaces that require only a C compiler. All files will be installed under `/usr/local/pgsql` by default.

You can customize the build and installation process by supplying one or more of the following command line options to `configure`:

`--prefix=`*`PREFIX`*

Install all files under the directory *`PREFIX`* instead of `/usr/local/pgsql`. The actual files will be installed into various subdirectories; no files will ever be installed directly into the *`PREFIX`* directory.

If you have special needs, you can also customize the individual subdirectories with the following options.

`--exec-prefix=`*`EXEC-PREFIX`*

You can install architecture-dependent files under a different prefix, *`EXEC-PREFIX`*, than what *`PREFIX`* was set to. This can be useful to share architecture-independent files between hosts. If you omit this, then *`EXEC-PREFIX`* is set equal to *`PREFIX`* and both architecture-dependent and independent files will be installed under the same tree, which is probably what you want.

`--bindir=`*`DIRECTORY`*

Specifies the directory for executable programs. The default is *`EXEC-PREFIX`*`/bin`, which normally means `/usr/local/pgsql/bin`.

`--datadir=`*`DIRECTORY`*

Sets the directory for read-only data files used by the installed programs. The default is *`PREFIX`*`/share`. Note that this has nothing to do with where your database files will be placed.

`--sysconfdir=`*`DIRECTORY`*

The directory for various configuration files, *`PREFIX`*`/etc` by default.

`--libdir=`*`DIRECTORY`*

The location to install libraries and dynamically loadable modules. The default is *`EXEC-PREFIX`*`/lib`.

`--includedir=`*`DIRECTORY`*

The directory for installing C and C++ header files. The default is *`PREFIX`*`/include`.

`--docdir=`*`DIRECTORY`*

Documentation files, except “man” pages, will be installed into this directory. The default is *`PREFIX`*`/doc`.

`--mandir=`*`DIRECTORY`*

The man pages that come with PostgreSQL will be installed under this directory, in their respective `man`*`x`* subdirectories. The default is *`PREFIX`*`/man`.

Note

Care has been taken to make it possible to install PostgreSQL into shared installation locations (such as `/usr/local/include`) without interfering with the namespace of the rest of the system. First, the string “`/postgresql`” is automatically appended to `datadir`, `sysconfdir`, and `docdir`, unless the fully expanded directory name

already contains the string "postgres" or "pgsql". For example, if you choose /usr/local as prefix, the documentation will be installed in /usr/local/doc/postgresql, but if the prefix is /opt/postgres, then it will be in /opt/postgres/doc. The public C header files of the client interfaces are installed into includedir and are namespace-clean. The internal header files and the server header files are installed into private directories under includedir. See the *Programmer's Guide* for information about how to get at the header files for each interface. Finally, a private subdirectory will also be created, if appropriate, under libdir for dynamically loadable modules.

--with-includes=*DIRECTORIES*

DIRECTORIES is a colon-separated list of directories that will be added to the list the compiler searches for header files. If you have optional packages (such as GNU Readline) installed in a non-standard location, you have to use this option and probably also the corresponding --with-libraries option.

Example: --with-includes=/opt/gnu/include:/usr/sup/include.

--with-libraries=*DIRECTORIES*

DIRECTORIES is a colon-separated list of directories to search for libraries. You will probably have to use this option (and the corresponding --with-includes option) if you have packages installed in non-standard locations.

Example: --with-libraries=/opt/gnu/lib:/usr/sup/lib.

--enable-recode

Enables single-byte character set recode support. See Section 7.3, "Single-byte character set recoding" about this feature. Note that a more general form of character set conversion is supported in the default configuration; this feature is obsolete.

--enable-nls[=*LANGUAGES*]

Enables Native Language Support (NLS), that is, the ability to display a program's messages in a language other than English. *LANGUAGES* is a space separated list of codes of the languages that you want supported, for example --enable-nls='de fr'. (The intersection between your list and the set of actually provided translations will be computed automatically.) If you do not specify a list, then all available translations are installed.

To use this option, you will need an implementation of the gettext API; see above.

--with-pgport=*NUMBER*

Set *NUMBER* as the default port number for server and clients. The default is 5432. The port can always be changed later on, but if you specify it here then both server and clients will have the same default compiled in, which can be very convenient. Usually the only good reason to select a non-default value is if you intend to run multiple PostgreSQL servers on the same machine.

--with-perl

Build the PL/Perl server-side language.

--with-python

Build the Python interface module and the PL/Python server-side language. You need to have root access to be able to install the Python module at its default place (/usr/lib/python*x.y*).

`--with-tcl`

Build components that require Tcl/Tk, which are libpgtcl, pgtclsh, pgtksh, and PL/Tcl. But see below about `--without-tk`.

`--without-tk`

If you specify `--with-tcl` and this option, then the program that requires Tk (pgtksh) will be excluded.

`--with-tclconfig=`*`DIRECTORY`*
`--with-tkconfig=`*`DIRECTORY`*

Tcl/Tk installs the files `tclConfig.sh` and `tkConfig.sh`, which contain configuration information needed to build modules interfacing to Tcl or Tk. These files are normally found automatically at their well-known locations, but if you want to use a different version of Tcl or Tk you can specify the directory in which to find them.

`--with-java`

Build the JDBC driver and associated Java packages.

`--with-krb4[=`*`DIRECTORY`*`]`
`--with-krb5[=`*`DIRECTORY`*`]`

Build with support for Kerberos authentication. You can use either Kerberos version 4 or 5, but not both. The *`DIRECTORY`* argument specifies the root directory of the Kerberos installation; `/usr/athena` is assumed as default. If the relevant header files and libraries are not under a common parent directory, then you must use the `--with-includes` and `--with-libraries` options in addition to this option. If, on the other hand, the required files are in a location that is searched by default (e.g., `/usr/lib`), then you can leave off the argument.

`configure` will check for the required header files and libraries to make sure that your Kerberos installation is sufficient before proceeding.

`--with-krb-srvnam=`*`NAME`*

The name of the Kerberos service principal. `postgres` is the default. There's probably no reason to change this.

`--with-openssl[=`*`DIRECTORY`*`]`

Build with support for SSL (encrypted) connections. This requires the OpenSSL package to be installed. The *`DIRECTORY`* argument specifies the root directory of the OpenSSL installation; the default is `/usr/local/ssl`.

`configure` will check for the required header files and libraries to make sure that your OpenSSL installation is sufficient before proceeding.

`--with-pam`

Build with PAM (Pluggable Authentication Modules) support.

`--without-readline`

Prevents the use of the Readline library. This disables command-line editing and history in psql, so it is not recommended.

`--without-zlib`

Prevents the use of the Zlib library. This disables compression support in pg_dump. This option is only intended for those rare systems where this library is not available.

`--enable-debug`

Compiles all programs and libraries with debugging symbols. This means that you can run the programs through a debugger to analyze problems. This enlarges the size of the installed executables considerably, and on non-GCC compilers it usually also disables compiler optimization, causing slowdowns. However, having the symbols available is extremely helpful for dealing with any problems that may arise. Currently, this option is recommended for production installations only if you use GCC. But you should always have it on if you are doing development work or running a beta version.

`--enable-cassert`

Enables *assertion* checks in the server, which test for many "can't happen" conditions. This is invaluable for code development purposes, but the tests slow things down a little. Also, having the tests turned on won't necessarily enhance the stability of your server! The assertion checks are not categorized for severity, and so what might be a relatively harmless bug will still lead to server restarts if it triggers an assertion failure. Currently, this option is not recommended for production use, but you should have it on for development work or when running a beta version.

`--enable-depend`

Enables automatic dependency tracking. With this option, the makefiles are set up so that all affected object files will be rebuilt when any header file is changed. This is useful if you are doing development work, but is just wasted overhead if you intend only to compile once and install. At present, this option will work only if you use GCC.

If you prefer a C compiler different from the one `configure` picks then you can set the environment variable `CC` to the program of your choice. By default, `configure` will pick `gcc` unless this is inappropriate for the platform. Similarly, you can override the default compiler flags with the `CFLAGS` variable.

You can specify environment variables on the `configure` command line, for example:

```
./configure CC=/opt/bin/gcc CFLAGS='-O2 -pipe'
```

2. **Build**

To start the build, type

```
gmake
```

(Remember to use GNU make.) The build may take anywhere from 5 minutes to half an hour depending on your hardware. The last line displayed should be

```
All of PostgreSQL is successfully made. Ready to install.
```

3. **Regression Tests**

If you want to test the newly built server before you install it, you can run the regression tests at this point. The regression tests are a test suite to verify that PostgreSQL runs on your machine in the way the developers expected it to. Type

```
gmake check
```

(This won't work as root; do it as an unprivileged user.) It is possible that some tests fail, due to differences in error message wording or floating point results. Chapter 13, *Regression Tests* contains detailed information about interpreting the test results. You can repeat this test at any later time by issuing the same command.

4. **Installing The Files**

Note

If you are upgrading an existing system and are going to install the new files over the old ones, then you should have backed up your data and shut down the old server by now, as explained in Section 1.4, “If You Are Upgrading” above.

To install PostgreSQL enter

```
gmake install
```

This will install files into the directories that were specified in Step 1. Make sure that you have appropriate permissions to write into that area. Normally you need to do this step as root. Alternatively, you could create the target directories in advance and arrange for appropriate permissions to be granted.

You can use `gmake install-strip` instead of `gmake install` to strip the executable files and libraries as they are installed. This will save some space. If you built with debugging support, stripping will effectively remove the debugging support, so it should only be done if debugging is no longer needed. `install-strip` tries to do a reasonable job saving space, but it does not have perfect knowledge of how to strip every unneeded byte from an executable file, so if you want to save all the disk space you possibly can, you will have to do manual work.

If you built the Python interfaces and you were not the root user when you executed the above command then that part of the installation probably failed. In that case you should become the root user and then do

```
gmake -C src/interfaces/python install
```

If you do not have superuser access you are on your own: you can still take the required files and place them in other directories where Python can find them, but how to do that is left as an exercise.

The standard installation provides only the header files needed for client application development. If you plan to do any server-side program development (such as custom functions or data types written in C), then you may want to install the entire PostgreSQL include tree into your target include directory. To do that, enter

```
gmake install-all-headers
```

This adds a megabyte or two to the installation footprint, and is only useful if you don't plan to keep the whole source tree around for reference. (If you do, you can just use the source's include directory when building server-side software.)

Client-only installation: If you want to install only the client applications and interface libraries, then you can use these commands:

```
gmake -C src/bin install
gmake -C src/include install
gmake -C src/interfaces install
gmake -C doc install
```

Uninstallation: To undo the installation use the command `gmake uninstall`. However, this will not remove any created directories.

Cleaning: After the installation you can make room by removing the built files from the source tree with the command `gmake clean`. This will preserve the files made by the configure program, so that you can rebuild everything with `gmake` later on. To reset the source tree to the state in which it was distributed, use `gmake distclean`. If you are going to build for several platforms from the same source tree you must do this and re-configure for each build.

If you perform a build and then discover that your configure options were wrong, or if you change anything that configure investigates (for example, software upgrades), then it's a good idea to do `gmake distclean` before reconfiguring and rebuilding. Without this, your changes in configuration choices may not propagate everywhere they need to.

1.6. Post-Installation Setup

1.6.1. Shared Libraries

On some systems that have shared libraries (which most systems do) you need to tell your system how to find the newly installed shared libraries. The systems on which this is *not* necessary include BSD/OS, FreeBSD, HP-UX, IRIX, Linux, NetBSD, OpenBSD, Tru64 UNIX (formerly Digital UNIX), and Solaris.

The method to set the shared library search path varies between platforms, but the most widely usable method is to set the environment variable `LD_LIBRARY_PATH` like so: In Bourne shells (`sh`, `ksh`, `bash`, `zsh`)

```
LD_LIBRARY_PATH=/usr/local/pgsql/lib
export LD_LIBRARY_PATH
```

or in `csh` or `tcsh`

```
setenv LD_LIBRARY_PATH /usr/local/pgsql/lib
```

Replace `/usr/local/pgsql/lib` with whatever you set `--libdir` to in Step 1. You should put these commands into a shell start-up file such as `/etc/profile` or `~/.bash_profile`. Some good information about the caveats associated with this method can be found at http://www.visi.com/~barr/ldpath.html.

On some systems it might be preferable to set the environment variable `LD_RUN_PATH` *before* building.

On Cygwin, put the library directory in the `PATH` or move the `.dll` files into the `bin/` directory.

If in doubt, refer to the manual pages of your system (perhaps `ld.so` or `rld`). If you later on get a message like

```
psql: error in loading shared libraries
libpq.so.2.1: cannot open shared object file: No such file or
 directory
```

then this step was necessary. Simply take care of it then.

If you are on BSD/OS, Linux, or SunOS 4 and you have root access you can run

```
/sbin/ldconfig /usr/local/pgsql/lib
```

(or equivalent directory) after installation to enable the run-time linker to find the shared libraries faster. Refer to the manual page of `ldconfig` for more information. On FreeBSD, NetBSD, and OpenBSD the command is

```
/sbin/ldconfig -m /usr/local/pgsql/lib
```

instead. Other systems are not known to have an equivalent command.

1.6.2. Environment Variables

If you installed into `/usr/local/pgsql` or some other location that is not searched for programs by default, you should add `/usr/local/pgsql/bin` (or whatever you set `--bindir` to in Step 1) into your `PATH`. Strictly speaking, this is not necessary, but it will make the use of PostgreSQL much more convenient.

To do this, add the following to your shell start-up file, such as `~/.bash_profile` (or `/etc/profile`, if you want it to affect every user):

```
PATH=/usr/local/pgsql/bin:$PATH
export PATH
```

If you are using `csh` or `tcsh`, then use this command:

```
set path = ( /usr/local/pgsql/bin $path )
```

To enable your system to find the man documentation, you need to add a line like the following to a shell start-up file unless you installed into a location that is searched by default.

```
MANPATH=/usr/local/pgsql/man:$MANPATH
export MANPATH
```

The environment variables `PGHOST` and `PGPORT` specify to client applications the host and port of the database server, overriding the compiled-in defaults. If you are going to run client applications remotely then it is convenient if every user that plans to use the database sets `PGHOST`. This is not required, however: the settings can be communicated via command line options to most client programs.

1.7. Supported Platforms

PostgreSQL has been verified by the developer community to work on the platforms listed below. A supported platform generally means that PostgreSQL builds and installs according to these instructions and that the regression tests pass.

Note

If you are having problems with the installation on a supported platform, please write to `<pgsql-bugs@postgresql.org>` or `<pgsql-ports@postgresql.org>`, not to the people listed here.

OS	Processor	Version	Reported	Remarks
AIX	RS6000	7.3	2002-11-12, Andreas Zeugswetter (`<ZeugswetterA@spardat.at>`)	see also `doc/FAQ_AIX`
BSD/OS	x86	7.3	2002-10-25, Bruce Momjian (`<pgman@candle.pha.pa.us>`)	4.2
FreeBSD	Alpha	7.3	2002-11-13, Chris Kings-Lynne (`<chriskl@familyhealth.com.au>`)	
FreeBSD	x86	7.3	2002-10-29, 3.3, Nigel J. Andrews (`<nandrews@investsystems.co.uk>`), 4.7, Larry Rosenman	

OS	Processor	Version	Reported	Remarks
			(<ler@lerctr.org>), 5.0, Sean Chittenden (<sean@chittenden.org>)	
HP-UX	PA-RISC	7.3	2002-10-28, 10.20 Tom Lane (<tgl@sss.pgh.pa.us>), 11.00, 11.11, 32 & 64 bit, Giles Lean (<giles@nemeton.com.au>)	gcc and cc; see also doc/FAQ_HPUX
IRIX	MIPS	7.3	2002-10-27, Ian Barwick (<barwick@gmx.net>)	Irix64 Komma 6.5
Linux	Alpha	7.3	2002-10-28, Magnus Naeslund (<mag@fbab.net>)	2.4.19-pre6
Linux	PlayStation 2	7.3	2002-11-19, Permaine Cheung <pcheung@redhat.com>)	#undef HAS_TEST_AND_SET, remove slock_t typedef
Linux	PPC74xx	7.3	2002-10-26, Tom Lane (<tgl@sss.pgh.pa.us>)	bye 2.2.18; Apple G3
Linux	S/390	7.3	2002-11-22, Permaine Cheung <pcheung@redhat.com>)	both s390 and s390x (32 and 64 bit)
Linux	Sparc	7.3	2002-10-26, Doug McNaught (<doug@mcnaught.org>)	3.0
Linux	x86	7.3	2002-10-26, Alvaro Herrera (<alvherre@dcc.uchile.cl>)	2.4
MacOS X	PPC	7.3	2002-10-28, 10.1, Tom Lane (<tgl@sss.pgh.pa.us>), 10.2.1, Adam Witney (<awitney@sghms.ac.uk>)	
NetBSD	arm32	7.3	2002-11-19, Patrick Welche (<prlw1@newn.cam.ac.uk>)	1.6
NetBSD	x86	7.3	2002-11-14, Patrick Welche (<prlw1@newn.cam.ac.uk>)	1.6
OpenBSD	Sparc	7.3	2002-11-17, Christopher Kings-Lynne (<chriskl@familyhealth.com.au>)	3.2
OpenBSD	x86	7.3	2002-11-14, 3.1 Magnus Naeslund (<mag@fbab.net>),	

OS	Processor	Version	Reported	Remarks
			3.2 Christopher Kings-Lynne (<chriskl@familyhealth.com.au>)	
SCO OpenServer 5	x86	7.3.1	2002-12-11, Shibashish Satpathy (<shib@postmark.net>)	5.0.4, gcc; see also doc/FAQ_SCO
Solaris	Sparc	7.3	2002-10-28, Andrew Sullivan (<andrew@libertyrms.info>)	Solaris 7 & 8; see also doc/FAQ_Solaris
Solaris	x86	7.3	2002-11-20, Martin Renters (<martin@datafax.com>)	5.8; see also doc/FAQ_Solaris
Tru64 UNIX	Alpha	7.3	2002-11-05, Alessio Bragadini (<alessio@albourne.com>)	
UnixWare	x86	7.3	2002-11-01, 7.1.3 Larry Rosenman (<ler@lerctr.org>), 7.1.1 and 7.1.2(8.0.0) Olivier Prenant (<ohp@pyrenet.fr>)	see also doc/FAQ_SCO
Windows	x86	7.3	2002-10-29, Dave Page (<dpage@vale-housing.co.uk>), Jason Tishler (<jason@tishler.net>)	with Cygwin; see doc/FAQ_MSWIN
Windows	x86	7.3	2002-11-05, Dave Page (<dpage@vale-housing.co.uk>)	native is client-side only; see Chapter 2, *Installation on Windows*

Unsupported Platforms: The following platforms are either known not to work, or they used to work in a previous release and we did not receive explicit confirmation of a successful test with version 7.3 at the time this list was compiled. We include these here to let you know that these platforms *could* be supported if given some attention.

OS	Processor	Version	Reported	Remarks
BeOS	x86	7.2	2001-11-29, Cyril Velter (<cyril.velter@libertysurf.fr>)	needs updates to semaphore code
DG/UX 5.4R4.11	m88k	6.3	1998-03-01, Brian E Gallew (<geek+@cmu.edu>)	no recent reports
Linux	armv4l	7.2	2001-12-10, Mark Knox (<segfault@hardline.org>)	2.2.x
Linux	MIPS	7.2	2001-11-15, Hisao Shibuya (<shibuya@alpha.or.jp>)	2.0.x; Cobalt Qube2

OS	Processor	Version	Reported	Remarks
MkLinux DR1	PPC750	7.0	2001-04-03, Tatsuo Ishii (<t-ishii@sra.co.jp>)	7.1 needs OS update?
NetBSD	Alpha	7.2	2001-11-20, Thomas Thai (<tom@minnesota.com>)	1.5W
NetBSD	m68k	7.0	2000-04-10, Henry B. Hotz (<hotz@jpl.nasa.gov>)	Mac 8xx
NetBSD	MIPS	7.2.1	2002-06-13, Warwick Hunter (<whunter@agile.tv>)	1.5.3
NetBSD	PPC	7.2	2001-11-28, Bill Studenmund (<wrstuden@netbsd.org>)	1.5
NetBSD	Sparc	7.2	2001-12-03, Matthew Green (<mrg@eterna.com.au>)	32- and 64-bit builds
NetBSD	VAX	7.1	2001-03-30, Tom I. Helbekkmo (<tih@kpnQwest.no>)	1.5
NeXTSTEP	x86	6.x	1998-03-01, David Wetzel (<dave@turbocat.de>)	bit rot suspected
QNX 4 RTOS	x86	7.2	2001-12-10, Bernd Tegge (<tegge@repas-aeg.de>)	needs updates to semaphore code; see also doc/FAQ_QNX4
QNX RTOS v6	x86	7.2	2001-11-20, Igor Kovalenko (<Igor.Kovalenko@motorola.com>)	patches available in archives, but too late for 7.2
SunOS 4	Sparc	7.2	2001-12-04, Tatsuo Ishii (<t-ishii@sra.co.jp>)	
System V R4	m88k	6.2.1	1998-03-01, Doug Winterburn (<dlw@seavme.xroads.com>)	needs new TAS spinlock code
System V R4	MIPS	6.4	1998-10-28, Frank Ridderbusch (<ridderbusch.pad@sni.de>)	no recent reports
Ultrix	MIPS	7.1	2001-03-26	TAS spinlock code not detected
Ultrix	VAX	6.x	1998-03-01	

Chapter 2. Installation on Windows

Although PostgreSQL is written for Unix-like operating systems, the C client library (libpq) and the interactive terminal (psql) can be compiled natively under Windows. The makefiles included in the source distribution are written for Microsoft Visual C++ and will probably not work with other systems. It should be possible to compile the libraries manually in other cases.

Tip

If you are using Windows 98 or newer you can build and use all of PostgreSQL "the Unix way" if you install the Cygwin toolkit first. In that case see Chapter 1, *Installation Instructions*.

To build everything that you can on Windows, change into the `src` directory and type the command

```
nmake /f win32.mak
```

This assumes that you have Visual C++ in your path.

The following files will be built:

`interfaces\libpq\Release\libpq.dll`

The dynamically linkable frontend library

`interfaces\libpq\Release\libpqdll.lib`

Import library to link your program to `libpq.dll`

`interfaces\libpq\Release\libpq.lib`

Static library version of the frontend library

`bin\psql\Release\psql.exe`

The PostgreSQL interactive terminal

The only file that really needs to be installed is the `libpq.dll` library. This file should in most cases be placed in the `WINNT\SYSTEM32` directory (or in `WINDOWS\SYSTEM` on a Windows 95/98/ME system). If this file is installed using a setup program, it should be installed with version checking using the `VERSIONINFO` resource included in the file, to ensure that a newer version of the library is not overwritten.

If you plan to do development using libpq on this machine, you will have to add the `src\include` and `src\interfaces\libpq` subdirectories of the source tree to the include path in your compilers settings.

To use the libraries, you must add the `libpqdll.lib` file to your project. (In Visual C++, just right-click on the project and choose to add it.)

Chapter 3. Server Run-time Environment

This chapter discusses how to set up and run the database server and the interactions with the operating system.

3.1. The PostgreSQL User Account

As with any other server daemon that is connected to outside world, it is advisable to run PostgreSQL under a separate user account. This user account should only own the data that is managed by the server, and should not be shared with other daemons. (For example, using the user "nobody" is a bad idea.) It is not advisable to install executables owned by this user because compromised systems could then modify their own binaries.

To add a Unix user account to your system, look for a command `useradd` or `adduser`. The user name postgres is often used but is by no means required.

3.2. Creating a Database Cluster

Before you can do anything, you must initialize a database storage area on disk. We call this a *database cluster*. (SQL uses the term catalog cluster instead.) A database cluster is a collection of databases is accessible by a single instance of a running database server. After initialization, a database cluster will contain a database named `template1`. As the name suggests, this will be used as a template for subsequently created databases; it should not be used for actual work. (See Chapter 5, *Managing Databases* for information about creating databases.)

In file system terms, a database cluster will be a single directory under which all data will be stored. We call this the *data directory* or *data area*. It is completely up to you where you choose to store your data. There is no default, although locations such as `/usr/local/pgsql/data` or `/var/lib/pgsql/data` are popular. To initialize a database cluster, use the command `initdb`, which is installed with PostgreSQL. The desired file system location of your database system is indicated by the `-D` option, for example

```
$ initdb -D /usr/local/pgsql/data
```

Note that you must execute this command while logged into the PostgreSQL user account, which is described in the previous section.

Tip

As an alternative to the `-D` option, you can set the environment variable `PGDATA`.

`initdb` will attempt to create the directory you specify if it does not already exist. It is likely that it will not have the permission to do so (if you followed our advice and created an unprivileged account). In that case you should create the directory yourself (as root) and change the owner to be the PostgreSQL user. Here is how this might be done:

```
root# mkdir /usr/local/pgsql/data
root# chown postgres /usr/local/pgsql/data
root# su postgres
postgres$ initdb -D /usr/local/pgsql/data
```

`initdb` will refuse to run if the data directory looks like it it has already been initialized.

Because the data directory contains all the data stored in the database, it is essential that it be secured from unauthorized access. `initdb` therefore revokes access permissions from everyone but the PostgreSQL user.

However, while the directory contents are secure, the default client authentication setup allows any local user to connect to the database and even become the database superuser. If you don't trust other local users, we recommend you use `initdb`'s `-W` or `--pwprompt` option to assign a password to the database superuser. After `initdb`, modify the `pg_hba.conf` file to use `md5` or `password` instead of `trust` authentication *before* you start the server for the first time. (Other, approaches include using `ident` authentication or file system permissions to restrict connections. See Chapter 6, *Client Authentication* for more information.)

`initdb` also initializes the default locale for the database cluster. Normally, it will just take the locale settings in the environment and apply them to the initialized database. It is possible to specify a different locale for the database; more information about that can be found in Section 7.1, “Locale Support”. One surprise you might encounter while running `initdb` is a notice similar to this:

```
The database cluster will be initialized with locale de_DE.
This locale setting will prevent the use of indexes for pattern
 matching
operations.  If that is a concern, rerun initdb with the collation
 order
set to "C".  For more information see the Administrator's Guide.
```

This is intended to warn you that the currently selected locale will cause indexes to be sorted in an order that prevents them from being used for `LIKE` and regular-expression searches. If you need good performance in such searches, you should set your current locale to `C` and re-run `initdb`, e.g., by running `initdb --lc-collate=C`. The sort order used within a particular database cluster is set by `initdb` and cannot be changed later, short of dumping all data, rerunning `initdb`, and reloading the data. So it's important to make this choice correctly the first time.

3.3. Starting the Database Server

Before anyone can access the database, you must start the database server. The database server is called *postmaster*. The postmaster must know where to find the data it is supposed to use. This is done with the `-D` option. Thus, the simplest way to start the server is:

```
$ postmaster -D /usr/local/pgsql/data
```

which will leave the server running in the foreground. This must be done while logged into the PostgreSQL user account. Without `-D`, the server will try to use the data directory in the environment variable `PGDATA`. If neither of these succeed, it will fail.

To start the postmaster in the background, use the usual shell syntax:

```
$ postmaster -D /usr/local/pgsql/data > logfile 2>&1 &
```

It is an important to store the server's stdout and stderr output somewhere, as shown above. It will help for auditing purposes and to diagnose problems. (See Section 8.4, “Log File Maintenance” for a more thorough discussion of log file handling.)

The postmaster also takes a number of other command line options. For more information, see the reference page and Section 3.4, “Run-time Configuration” below. In particular, in order for the server to accept TCP/IP connections (rather than just Unix domain socket ones), you must specify the `-i` option.

This shell syntax can get tedious quickly. Therefore the shell script wrapper pg_ctl is provided to simplify some tasks. For example:

```
pg_ctl start -l logfile
```

will start the server in the background and put the output into the named log file. The `-D` option has the same meaning here as in the postmaster. pg_ctl is also capable of stopping the server.

Normally, you will want to start the database server when the computer boots. Autostart scripts are operating system-specific. There are a few distributed with PostgreSQL in the `/contrib/start-scripts` directory. This may require root privileges.

Different systems have different conventions for starting up daemons at boot time. Many systems have a file `/etc/rc.local` or `/etc/rc.d/rc.local`. Others use `rc.d` directories. Whatever you do, the server must be run by the PostgreSQL user account *and not by root* or any other user. Therefore you probably should form your commands using `su -c '...' postgres`. For example:

```
su -c 'pg_ctl start -D /usr/local/pgsql/data -l serverlog' postgres
```

Here are a few more operating system specific suggestions. (Always replace these with the proper installation directory and the user name.)

- For FreeBSD, look at the file `contrib/start-scripts/freebsd` in the PostgreSQL source distribution.
- On OpenBSD, add the following lines to the file `/etc/rc.local`:

  ```
  if [ -x /usr/local/pgsql/bin/pg_ctl -a -x /usr/local/pgsql/bin/
  postmaster ]; then
      su - -c '/usr/local/pgsql/bin/pg_ctl start -l /var/
  postgresql/log -s' postgres
      echo -n ' postgresql'
  fi
  ```

- On Linux systems either add

  ```
  /usr/local/pgsql/bin/pg_ctl start -l logfile -D /usr/local/pgsql/
  data
  ```

  to `/etc/rc.d/rc.local` or look at the file `contrib/start-scripts/linux` in the PostgreSQL source distribution.
- On NetBSD, either use the FreeBSD or Linux start scripts, depending on preference.
- On Solaris, create a file called `/etc/init.d/postgresql` which should contain the following line:

  ```
  su - postgres -c "/usr/local/pgsql/bin/pg_ctl start -l logfile -
  D /usr/local/pgsql/data"
  ```

  Then, create a symbolic link to it in `/etc/rc3.d` as `S99postgresql`.

While the postmaster is running, its PID is in the file `postmaster.pid` in the data directory. This is used to prevent multiple postmasters running in the same data directory, and can also be used for shutting down the postmaster.

3.3.1. Server Start-up Failures

There are several common reasons the postmaster might fail to start. Check the postmaster's log file, or start it by hand (without redirecting standard output or standard error) and see what error messages appear. Some of the error messages are self-explanatory, but some are not, as shown below:

```
FATAL: StreamServerPort: bind() failed: Address already in use
```

```
        Is another postmaster already running on that port?
```

This usually means just what it suggests: you tried to start another postmaster on the same port where one is already running. However, if the kernel error message is not `Address already in use` or some variant of that, there may be a different problem. For example, trying to start a postmaster on a reserved port number may draw something like:

```
$ postmaster -i -p 666
FATAL: StreamServerPort: bind() failed: Permission denied
        Is another postmaster already running on that port?
```

A message like:

```
IpcMemoryCreate: shmget(key=5440001, size=83918612, 01600) failed:
 Invalid argument
FATAL 1:  ShmemCreate: cannot create region
```

probably means your kernel's limit on the size of shared memory is smaller than the buffer area PostgreSQL is trying to create (83918612 bytes in this example). Or it could mean that you don't have System-V-style shared memory support configured into your kernel at all. As a temporary workaround, you can try starting the postmaster with a smaller-than-normal number of buffers (`-B` switch). You will eventually want to reconfigure your kernel to increase the allowed shared memory size. You may see this message when trying to start multiple postmasters on the same machine if their total space requested exceeds the kernel limit.

An error like:

```
IpcSemaphoreCreate: semget(key=5440026, num=16, 01600) failed: No
 space left on device
```

does *not* mean you've run out of disk space. It means your kernel's limit on the number of System V semaphores is smaller than the number PostgreSQL wants to create. As above, you may be able to work around the problem by starting the postmaster with a reduced number of allowed connections (`-N` switch), but you'll eventually want to increase the kernel limit.

If you get an “illegal system call” error, it is likely that shared memory or semaphores are not supported in your kernel at all. In that case your only option is to reconfigure the kernel to enable these features.

Details about configuring System V IPC facilities are given in Section 3.5.1, “Shared Memory and Semaphores”.

3.3.2. Client Connection Problems

Although the error conditions possible on the client side are quite varied and application-dependent, a few of them might be directly related to how the server was started up. Conditions other than those shown below should be documented with the respective client application.

```
psql: could not connect to server: Connection refused
        Is the server running on host server.joe.com and accepting
        TCP/IP connections on port 5432?
```

This is the generic “I couldn't find a server to talk to” failure. It looks like the above when TCP/IP communication is attempted. A common mistake is to forget the `-i` option to allow the postmaster to accept TCP/IP connections.

Alternatively, you'll get this when attempting Unix-socket communication to a local postmaster:

```
psql: could not connect to server: Connection refused
        Is the server running locally and accepting
```

```
        connections on Unix domain socket "/tmp/.s.PGSQL.5432"?
```

The last line is useful in verifying that the client is trying to connect to the right place. If there is in fact no postmaster running there, the kernel error message will typically be either `Connection refused` or `No such file or directory`, as illustrated. (It is important to realize that `Connection refused` in this context does *not* mean that the postmaster got your connection request and rejected it -- that case will produce a different message, as shown in Section 6.3, "Authentication problems".) Other error messages such as `Connection timed out` may indicate more fundamental problems, like lack of network connectivity.

3.4. Run-time Configuration

There are a lot of configuration parameters that affect the behavior of the database system. Here we describe how to set them and the following subsections will discuss each in detail.

All parameter names are case-insensitive. Every parameter takes a value of one of the four types: Boolean, integer, floating point, and string. Boolean values are `ON`, `OFF`, `TRUE`, `FALSE`, `YES`, `NO`, `1`, `0` (case-insensitive) or any non-ambiguous prefix of these.

One way to set these options is to edit the file `postgresql.conf` in the data directory. (A default file is installed there.) An example of what this file might look like is:

```
# This is a comment
log_connections = yes
syslog = 2
search_path = '$user, public'
```

As you see, options are one per line. The equal sign between name and value is optional. Whitespace is insignificant and blank lines are ignored. Hash marks ("#") introduce comments anywhere. Parameter values that are not simple identifiers or numbers should be single-quoted.

The configuration file is reread whenever the postmaster receives a SIGHUP signal (which is most easily sent by means of `pg_ctl reload`). The postmaster also propagates this signal to all currently running backend processes so that existing sessions also get the new value. Alternatively, you can send the signal to a single backend process directly.

A second way to set these configuration parameters is to give them as a command line option to the postmaster, such as:

```
postmaster -c log_connections=yes -c syslog=2
```

which would have the same effect as the previous example. Command-line options override any conflicting settings in `postgresql.conf`.

Occasionally it is also useful to give a command line option to one particular backend session only. The environment variable `PGOPTIONS` can be used for this purpose on the client side:

```
env PGOPTIONS='-c geqo=off' psql
```

(This works for any libpq-based client application, not just psql.) Note that this won't work for options that are fixed when the server is started, such as the port number.

Some options can be changed in individual SQL sessions with the `SET` command, for example:

```
=> SET ENABLE_SEQSCAN TO OFF;
```

See the SQL command language reference for details on the syntax.

Furthermore, it is possible to assign a set of option settings to a user or a database. Whenever a session is started, the default settings for the user and database involved are loaded. The commands

ALTER DATABASE and ALTER USER, respectively, are used to configure these settings. Such per-database settings override anything received from the postmaster or the configuration file, and in turn are overridden by per-user settings.

3.4.1. pg_settings

The pg_settings virtual table allows display and update of current session run-time parameters. There is one entry for each of the available parameters provided by SHOW ALL. But it is in a form that allows it to be joined with other relations and have a selection criteria applied.

An UPDATE performed on pg_settings is equivalent to executing the SET command on that named parameter. The change only affects the value used by the current session. If an UPDATE is issued within a transaction that is later aborted, the effects of the UPDATE command disappear when the transaction is rolled back. Once the surrounding transaction is committed, the effects will persist until the end of the session, unless overridden by another UPDATE or SET.

Table 3.1. pg_settings Columns

Name	Type	Description
name	text	The name of a current session run-time parameter
setting	text	The value of a current session run-time parameter

3.4.2. Planner and Optimizer Tuning

CPU_INDEX_TUPLE_COST (floating point)

Sets the query optimizer's estimate of the cost of processing each index tuple during an index scan. This is measured as a fraction of the cost of a sequential page fetch.

CPU_OPERATOR_COST (floating point)

Sets the optimizer's estimate of the cost of processing each operator in a WHERE clause. This is measured as a fraction of the cost of a sequential page fetch.

CPU_TUPLE_COST (floating point)

Sets the query optimizer's estimate of the cost of processing each tuple during a query. This is measured as a fraction of the cost of a sequential page fetch.

DEFAULT_STATISTICS_TARGET (integer)

Sets the default statistics target for table columns that have not had a column-specific target set via ALTER TABLE SET STATISTICS. Larger values increase the time needed to do ANALYZE, but may improve the quality of the planner's estimates.

EFFECTIVE_CACHE_SIZE (floating point)

Sets the optimizer's assumption about the effective size of the disk cache (that is, the portion of the kernel's disk cache that will be used for PostgreSQL data files). This is measured in disk pages, which are normally 8 kB each.

ENABLE_HASHJOIN (boolean)

Enables or disables the query planner's use of hash-join plan types. The default is on. This is used for debugging the query planner.

ENABLE_INDEXSCAN (boolean)

Enables or disables the query planner's use of index-scan plan types. The default is on. This is used to debugging the query planner.

ENABLE_MERGEJOIN (boolean)

Enables or disables the query planner's use of merge-join plan types. The default is on. This is used for debugging the query planner.

ENABLE_NESTLOOP (boolean)

Enables or disables the query planner's use of nested-loop join plans. It's not possible to suppress nested-loop joins entirely, but turning this variable off discourages the planner from using one if there are other methods available. The default is on. This is used for debugging the query planner.

ENABLE_SEQSCAN (boolean)

Enables or disables the query planner's use of sequential scan plan types. It's not possible to suppress sequential scans entirely, but turning this variable off discourages the planner from using one if there are other methods available. The default is on. This is used for debugging the query planner.

ENABLE_SORT (boolean)

Enables or disables the query planner's use of explicit sort steps. It's not possible to suppress explicit sorts entirely, but turning this variable off discourages the planner from using one if there are other methods available. The default is on. This is used for debugging the query planner.

ENABLE_TIDSCAN (boolean)

Enables or disables the query planner's use of TID scan plan types. The default is on. This is used for debugging the query planner.

GEQO (boolean)

Enables or disables genetic query optimization, which is an algorithm that attempts to do query planning without exhaustive searching. This is on by default. See also the various other GEQO_ settings.

GEQO_EFFORT (integer)
GEQO_GENERATIONS (integer)
GEQO_POOL_SIZE (integer)
GEQO_RANDOM_SEED (integer)
GEQO_SELECTION_BIAS (floating point)

Various tuning parameters for the genetic query optimization algorithm: The pool size is the number of individuals in one population. Valid values are between 128 and 1024. If it is set to 0 (the default) a pool size of 2^(QS+1), where QS is the number of FROM items in the query, is taken. The effort is used to calculate a default for generations. Valid values are between 1 and 80, 40 being the default. Generations specifies the number of iterations in the algorithm. The number must be a positive integer. If 0 is specified then Effort * Log2(PoolSize) is used. The run time of the algorithm is roughly proportional to the sum of pool size and generations. The selection bias is the selective pressure within the population. Values can be from 1.50 to 2.00; the latter is the default. The random seed can be set to get reproducible results from the algorithm. If it is set to -1 then the algorithm behaves non-deterministically.

GEQO_THRESHOLD (integer)

Use genetic query optimization to plan queries with at least this many FROM items involved. (Note that a JOIN construct counts as only one FROM item.) The default is 11. For simpler queries it is

usually best to use the deterministic, exhaustive planner. This parameter also controls how hard the optimizer will try to merge subquery `FROM` clauses into the upper query.

`RANDOM_PAGE_COST` (`floating point`)

Sets the query optimizer's estimate of the cost of a nonsequentially fetched disk page. This is measured as a multiple of the cost of a sequential page fetch.

Note

Unfortunately, there is no well-defined method for determining ideal values for the family of "COST" variables that were just described. You are encouraged to experiment and share your findings.

3.4.3. Logging and Debugging

`SERVER_MIN_MESSAGES` (`string`)

This controls how much message detail is written to the server logs. Valid values are `DEBUG5`, `DEBUG4`, `DEBUG3`, `DEBUG2`, `DEBUG1`, `INFO`, `NOTICE`, `WARNING`, `ERROR`, `LOG`, `FATAL`, and `PANIC`. Later values send less detail to the logs. The default is `NOTICE`. Note that `LOG` has a different precedence here than in `CLIENT_MIN_MESSAGES`.

Here is a summary of the various message types:

`DEBUG[1-5]`

Provides information for use by developers.

`INFO`

Provides information implicitly requested by the user, e.g., during `VACUUM VERBOSE`.

`NOTICE`

Provides information that may be helpful to users, e.g., truncation of long identifiers and index creation as part of primary keys.

`WARNING`

Provides warnings to the user, e.g., `COMMIT` outside a transaction.

`ERROR`

Reports the error that caused a transaction to abort.

`LOG`

Reports information of interest to administrators, e.g., checkpoint activity.

`FATAL`

Reports why a backend session terminated.

`PANIC`

Reports why all backend sessions restarted.

`CLIENT_MIN_MESSAGES` (`string`)

This controls how much message detail is written to the client. Valid values are `DEBUG5`, `DEBUG4`, `DEBUG3`, `DEBUG2`, `DEBUG1`, `LOG`, `NOTICE`, `WARNING`, and `ERROR`. Later values

send less information to the client. The default is NOTICE. Note that LOG has a different precedence here than in SERVER_MIN_MESSAGES. Also see that section for an explanation of the various values.

DEBUG_ASSERTIONS (boolean)

Turns on various assertion checks. This is a debugging aid. If you are experiencing strange problems or crashes you might want to turn this on, as it might expose programming mistakes. To use this option, the macro USE_ASSERT_CHECKING must be defined when PostgreSQL is built (accomplished by the configure option --enable-cassert). Note that DEBUG_ASSERTIONS defaults to on if PostgreSQL has been built with assertions enabled.

DEBUG_PRINT_PARSE (boolean)
DEBUG_PRINT_REWRITTEN (boolean)
DEBUG_PRINT_PLAN (boolean)
DEBUG_PRETTY_PRINT (boolean)

These flags enable various debugging output to be sent to the server log. For each executed query, print either the query text, the resulting parse tree, the query rewriter output, or the execution plan. DEBUG_PRETTY_PRINT indents these displays to produce a more readable but much longer output format.

EXPLAIN_PRETTY_PRINT (boolean)

Determines whether EXPLAIN VERBOSE uses the indented or non-indented format for displaying detailed query-tree dumps.

HOSTNAME_LOOKUP (boolean)

By default, connection logs only show the IP address of the connecting host. If you want it to show the host name you can turn this on, but depending on your host name resolution setup it might impose a non-negligible performance penalty. This option can only be set at server start.

LOG_CONNECTIONS (boolean)

This outputs a line to the server logs detailing each successful connection. This is off by default, although it is probably very useful. This option can only be set at server start or in the postgresql.conf configuration file.

LOG_DURATION (boolean)

Causes the duration of every completed statement to be logged. To use this option, enable LOG_STATEMENT and LOG_PID so you can link the statement to the duration using the process ID.

LOG_MIN_ERROR_STATEMENT (string)

This controls for which message levels the SQL statement causing that message is to be recorded in the server log. All statements causing a message of the level of the setting or higher are logged. The default is PANIC (effectively turning this feature off). Valid values are DEBUG5, DEBUG4, DEBUG3, DEBUG2, DEBUG1, INFO, NOTICE, WARNING, ERROR, FATAL, and PANIC. For example, if you set this to ERROR then all SQL statements causing errors, fatal errors, or panics will be logged.

It is recommended you enable LOG_PID as well so you can more easily match the error statement with the error message.

LOG_PID (boolean)

Prefixes each server message in the log file with the process ID of the backend process. This is useful to sort out which messages pertain to which connection. The default is off. This parameter does not affect messages logged via syslog, which always contain the process ID.

`LOG_STATEMENT` (`boolean`)

Causes each SQL statement to be logged.

`LOG_TIMESTAMP` (`boolean`)

Prefixes each server log message with a time stamp. The default is off.

`SHOW_STATEMENT_STATS` (`boolean`)
`SHOW_PARSER_STATS` (`boolean`)
`SHOW_PLANNER_STATS` (`boolean`)
`SHOW_EXECUTOR_STATS` (`boolean`)

For each query, write performance statistics of the respective module to the server log. This is a crude profiling instrument.

`SHOW_SOURCE_PORT` (`boolean`)

Shows the outgoing port number of the connecting host in the connection log messages. You could trace back the port number to find out what user initiated the connection. Other than that, it's pretty useless and therefore off by default. This option can only be set at server start.

`STATS_COMMAND_STRING` (`boolean`)
`STATS_BLOCK_LEVEL` (`boolean`)
`STATS_ROW_LEVEL` (`boolean`)

These flags determine what information backends send to the statistics collector process: current commands, block-level activity statistics, or row-level activity statistics. All default to off. Enabling statistics collection costs a small amount of time per query, but is invaluable for debugging and performance tuning.

`STATS_RESET_ON_SERVER_START` (`boolean`)

If on, collected statistics are zeroed out whenever the server is restarted. If off, statistics are accumulated across server restarts. The default is on. This option can only be set at server start.

`STATS_START_COLLECTOR` (`boolean`)

Controls whether the server should start the statistics-collection subprocess. This is on by default, but may be turned off if you know you have no interest in collecting statistics. This option can only be set at server start.

`SYSLOG` (`integer`)

PostgreSQL allows the use of syslog for logging. If this option is set to 1, messages go both to syslog and the standard output. A setting of 2 sends output only to syslog. (Some messages will still go to the standard output/error.) The default is 0, which means syslog is off. This option must be set at server start.

`SYSLOG_FACILITY` (`string`)

This option determines the syslog “facility” to be used when syslog is enabled. You may choose from `LOCAL0`, `LOCAL1`, `LOCAL2`, `LOCAL3`, `LOCAL4`, `LOCAL5`, `LOCAL6`, `LOCAL7`; the default is `LOCAL0`. See also the documentation of your system's syslog.

`SYSLOG_IDENT` (`string`)

If logging to syslog is enabled, this option determines the program name used to identify PostgreSQL messages in syslog log messages. The default is `postgres`.

`TRACE_NOTIFY` (`boolean`)

Generates a great amount of debugging output for the `LISTEN` and `NOTIFY` commands.

3.4.4. General Operation

AUTOCOMMIT (boolean)

If set to true, PostgreSQL will automatically do a COMMIT after each successful command that is not inside an explicit transaction block (that is, unless a BEGIN with no matching COMMIT has been given). If set to false, PostgreSQL will commit only upon receiving an explicit COMMIT command. This mode can also be thought of as implicitly issuing BEGIN whenever a command is received that is not already inside a transaction block. The default is true, for compatibility with historical PostgreSQL behavior. However, for maximum compatibility with the SQL specification, set it to false.

Note

Even with autocommit set to false, SET, SHOW, and RESET do not start new transaction blocks. They are run in their own transactions. Once another command is issued, a transaction block begins and any SET, SHOW, or RESET commands are considered to be part of the transaction, i.e., they are committed or rolled back depending on the completion status of the transaction. To execute a SET, SHOW, or RESET command at the start of a transaction block, use BEGIN first.

Note

As of PostgreSQL 7.3, setting autocommit to false is not well-supported. This is a new feature and is not yet handled by all client libraries and applications. Before making it the default setting in your installation, test carefully.

AUSTRALIAN_TIMEZONES (boolean)

If set to true, CST, EST, and SAT are interpreted as Australian time zones rather than as North American Central/Eastern time zones and Saturday. The default is false.

AUTHENTICATION_TIMEOUT (integer)

Maximum time to complete client authentication, in seconds. If a would-be client has not completed the authentication protocol in this much time, the server breaks the connection. This prevents hung clients from occupying a connection indefinitely. This option can only be set at server start or in the postgresql.conf file.

BACKSLASH_QUOTE (string)

This controls whether a quote mark can be represented by \' in a string literal. The preferred, SQL-standard way to represent a quote mark is by doubling it ('') but PostgreSQL has historically also accepted \'. However, use of \' creates security risks because in some client character set encodings, there are multibyte characters in which the last byte is numerically equivalent to ASCII \. If client-side code does escaping incorrectly then a SQL-injection attack is possible. This risk can be prevented by making the server reject queries in which a quote mark appears to be escaped by a backslash. The allowed values of backslash_quote are on (allow \' always), off (reject always), and safe_encoding (allow only if client encoding does not allow ASCII \ within a multibyte character). safe_encoding is the default setting.

CLIENT_ENCODING (string)

Sets the client-side encoding for multibyte character sets. The default is to use the database encoding.

DATESTYLE (string)

Sets the display format for dates, as well as the rules for interpreting ambiguous input dates. The default is ISO, US.

DB_USER_NAMESPACE (boolean)

This allows per-database user names. It is off by default.

If this is on, create users as username@dbname. When username is passed by a connecting client, @ and the database name is appended to the user name and that database-specific user name is looked up by the server. Note that when you create users with names containing @ within the SQL environment, you will need to quote the user name.

With this option enabled, you can still create ordinary global users. Simply append @ when specifying the user name in the client. The @ will be stripped off before the user name is looked up by the server.

Note

This feature is intended as a temporary measure until a complete solution is found. At that time, this option will be removed.

DEADLOCK_TIMEOUT (integer)

This is the amount of time, in milliseconds, to wait on a lock before checking to see if there is a deadlock condition. The check for deadlock is relatively slow, so the server doesn't run it every time it waits for a lock. We (optimistically?) assume that deadlocks are not common in production applications and just wait on the lock for a while before starting check for a deadlock. Increasing this value reduces the amount of time wasted in needless deadlock checks, but slows down reporting of real deadlock errors. The default is 1000 (i.e., one second), which is probably about the smallest value you would want in practice. On a heavily loaded server you might want to raise it. Ideally the setting should exceed your typical transaction time, so as to improve the odds that the lock will be released before the waiter decides to check for deadlock. This option can only be set at server start.

DEFAULT_TRANSACTION_ISOLATION (string)

Each SQL transaction has an isolation level, which can be either “read committed” or “serializable”. This parameter controls the default isolation level of each new transaction. The default is “read committed”.

Consult the PostgreSQL 7.3.21 User's Guide and the command SET TRANSACTION for more information.

DYNAMIC_LIBRARY_PATH (string)

If a dynamically loadable module needs to be opened and the specified name does not have a directory component (i.e. the name does not contain a slash), the system will search this path for the specified file. (The name that is used is the name specified in the CREATE FUNCTION or LOAD command.)

The value for dynamic_library_path has to be a colon-separated list of absolute directory names. If a directory name starts with the special value $libdir, the compiled-in PostgreSQL package library directory is substituted. This where the modules provided by the PostgreSQL distribution are installed. (Use pg_config --pkglibdir to print the name of this directory.) For example:

```
dynamic_library_path = '/usr/local/lib/postgresql:/home/
my_project/lib:$libdir'
```

The default value for this parameter is '$libdir'. If the value is set to an empty string, the automatic path search is turned off.

This parameter can be changed at run time by superusers, but a setting done that way will only persist until the end of the client connection, so this method should be reserved for development

purposes. The recommended way to set this parameter is in the `postgresql.conf` configuration file.

`KRB_SERVER_KEYFILE` (`string`)

Sets the location of the Kerberos server key file. See Section 6.2.3, "Kerberos authentication" for details.

`FSYNC` (`boolean`)

If this option is on, the PostgreSQL backend will use the `fsync()` system call in several places to make sure that updates are physically written to disk. This insures that a database installation will recover to a consistent state after an operating system or hardware crash. (Crashes of the database server itself are *not* related to this.)

However, this operation does slow down PostgreSQL because at transaction commit it has wait for the operating system to flush the write-ahead log. Without `fsync`, the operating system is allowed to do its best in buffering, sorting, and delaying writes, which can considerably increase performance. However, if the system crashes, the results of the last few committed transactions may be lost in part or whole. In the worst case, unrecoverable data corruption may occur.

For the above reasons, some administrators always leave it off, some turn it off only for bulk loads, where there is a clear restart point if something goes wrong, and some leave it on just to be on the safe side. Because it is always safe, the default is on. If you trust your operating system, your hardware, and your utility company (or better your UPS), you might want to disable `fsync`.

It should be noted that the performance penalty of having `fsync` on is considerably less in PostgreSQL version 7.1 and later. If you previously suppressed `fsync` for performance reasons, you may wish to reconsider your choice.

This option can only be set at server start or in the `postgresql.conf` file.

`LC_MESSAGES` (`string`)

Sets the language in which messages are displayed. Acceptable values are system-dependent; see Section 7.1, "Locale Support" for more information. If this variable is set to the empty string (which is the default) then the value is inherited from the execution environment of the server in a system-dependent way.

On some systems, this locale category does not exist. Setting this variable will still work, but there will be no effect. Also, there is a chance that no translated messages for the desired language exist. In that case you will continue to see the English messages.

`LC_MONETARY` (`string`)

Sets the locale to use for formatting monetary amounts, for example with the `to_char()` family of functions. Acceptable values are system-dependent; see Section 7.1, "Locale Support" for more information. If this variable is set to the empty string (which is the default) then the value is inherited from the execution environment of the server in a system-dependent way.

`LC_NUMERIC` (`string`)

Sets the locale to use for formatting numbers, for example with the `to_char()` family of functions. Acceptable values are system-dependent; see Section 7.1, "Locale Support" for more information. If this variable is set to the empty string (which is the default) then the value is inherited from the execution environment of the server in a system-dependent way.

`LC_TIME` (`string`)

Sets the locale to use for formatting date and time values. (Currently, this setting does nothing, but it may in the future.) Acceptable values are system-dependent; see Section 7.1, "Locale Support"

for more information. If this variable is set to the empty string (which is the default) then the value is inherited from the execution environment of the server in a system-dependent way.

`MAX_CONNECTIONS` (`integer`)

Determines the maximum number of concurrent connections to the database server. The default is 32 (unless altered while building the server). This parameter can only be set at server start.

`MAX_EXPR_DEPTH` (`integer`)

Sets the maximum expression nesting depth of the parser. The default value is high enough for any normal query, but you can raise it if needed. (But if you raise it too high, you run the risk of backend crashes due to stack overflow.)

`MAX_FILES_PER_PROCESS` (`integer`)

Sets the maximum number of simultaneously open files in each server subprocess. The default is 1000. The limit actually used by the code is the smaller of this setting and the result of `sysconf(_SC_OPEN_MAX)`. Therefore, on systems where `sysconf` returns a reasonable limit, you don't need to worry about this setting. But on some platforms (notably, most BSD systems), `sysconf` returns a value that is much larger than the system can really support when a large number of processes all try to open that many files. If you find yourself seeing "Too many open files" failures, try reducing this setting. This option can only be set at server start or in the `postgresql.conf` configuration file; if changed in the configuration file, it only affects subsequently-started server subprocesses.

`MAX_FSM_RELATIONS` (`integer`)

Sets the maximum number of relations (tables) for which free space will be tracked in the shared free-space map. The default is 1000. This option can only be set at server start.

`MAX_FSM_PAGES` (`integer`)

Sets the maximum number of disk pages for which free space will be tracked in the shared free-space map. The default is 10000. This option can only be set at server start.

`MAX_LOCKS_PER_TRANSACTION` (`integer`)

The shared lock table is sized on the assumption that at most `max_locks_per_transaction` * `max_connections` distinct objects will need to be locked at any one time. The default, 64, which has historically proven sufficient, but you might need to raise this value if you have clients that touch many different tables in a single transaction. This option can only be set at server start.

`PASSWORD_ENCRYPTION` (`boolean`)

When a password is specified in `CREATE USER` or `ALTER USER` without writing either `ENCRYPTED` or `UNENCRYPTED`, this flag determines whether the password is to be encrypted. The default is on (encrypt the password).

`PORT` (`integer`)

The TCP port the server listens on; 5432 by default. This option can only be set at server start.

`SEARCH_PATH` (`string`)

This variable specifies the order in which schemas are searched when an object (table, data type, function, etc.) is referenced by a simple name with no schema component. When there are objects of identical names in different schemas, the one found first in the search path is used. An object that is not in any of the schemas in the search path can only be referenced by specifying its containing schema with a qualified (dotted) name.

The value for search_path has to be a comma-separated list of schema names. If one of the list items is the special value $user, then the schema having the same name as the SESSION_USER is substituted, if there is such a schema. (If not, $user is ignored.)

The system catalog schema, pg_catalog, is always searched, whether it is mentioned in the path or not. If it is mentioned in the path then it will be searched in the specified order. If pg_catalog is not in the path then it will be searched *before* searching any of the path items.

Likewise, the current session's temporary-table schema, pg_temp_*nnn*, is always searched if it exists. It can be explicitly listed in the path by using the alias pg_temp. If it is not listed in the path then it is searched first (before even pg_catalog). However, the temporary schema is only searched for relation (table, view, sequence, etc) and data type names. It will never be searched for function or operator names.

When objects are created without specifying a particular target schema, they will be placed in the first schema listed in the search path. An error is reported if the search path is empty.

The default value for this parameter is '$user, public' (where the second part will be ignored if there is no schema named public). This supports shared use of a database (where no users have private schemas, and all share use of public), private per-user schemas, and combinations of these. Other effects can be obtained by altering the default search path setting, either globally or per-user.

The current effective value of the search path can be examined via the SQL function current_schemas(). This is not quite the same as examining the value of search_path, since current_schemas() shows how the requests appearing in search_path were resolved.

For more information on schema handling, see the PostgreSQL 7.3.21 User's Guide.

STATEMENT_TIMEOUT (integer)

Aborts any statement that takes over the specified number of milliseconds. A value of zero turns off the timer.

SHARED_BUFFERS (integer)

Sets the number of shared memory buffers used by the database server. The default is 64. Each buffer is typically 8192 bytes. This must be greater than 16, as well as at least twice the value of MAX_CONNECTIONS; however, a higher value can often improve performance on modern machines. Values of at least a few thousand are recommended for production installations. This option can only be set at server start.

Increasing this parameter may cause PostgreSQL to request more System V shared memory than your operating system's default configuration allows. See Section 3.5.1, “Shared Memory and Semaphores” for information on how to adjust these parameters, if necessary.

SILENT_MODE (bool)

Runs the server silently. If this option is set, the server will automatically run in background and any controlling ttys are disassociated, thus no messages are written to standard output or standard error (same effect as postmaster's -S option). Unless some logging system such as syslog is enabled, using this option is discouraged since it makes it impossible to see error messages.

SORT_MEM (integer)

Specifies the amount of memory to be used by internal sorts and hashes before switching to temporary disk files. The value is specified in kilobytes, and defaults to 1024 kilobytes (1 MB). Note that for a complex query, several sorts might be running in parallel, and each one will be allowed to use as much memory as this value specifies before it starts to put data into temporary files. Also, each running backend could be doing one or more sorts simultaneously, so the total

memory used could be many times the value of SORT_MEM. Sorts are used by ORDER BY, merge joins, and CREATE INDEX.

SQL_INHERITANCE (bool)

This controls the inheritance semantics, in particular whether subtables are included by various commands by default. They were not included in versions prior to 7.1. If you need the old behavior you can set this variable to off, but in the long run you are encouraged to change your applications to use the ONLY keyword to exclude subtables. See the SQL language reference and the PostgreSQL 7.3.21 User's Guide for more information about inheritance.

SSL (boolean)

Enables SSL connections. Please read Section 3.7, "Secure TCP/IP Connections with SSL" before using this. The default is off.

SUPERUSER_RESERVED_CONNECTIONS (integer)

Determines the number of "connection slots" that are reserved for connections by PostgreSQL superusers. At most max_connections connections can ever be active simultaneously. Whenever the number of active concurrent connections is at least max_connections minus superuser_reserved_connections, new connections will be accepted only from superuser accounts.

The default value is 2. The value must be less than the value of max_connections. This parameter can only be set at server start.

TCPIP_SOCKET (boolean)

If this is true, then the server will accept TCP/IP connections. Otherwise only local Unix domain socket connections are accepted. It is off by default. This option can only be set at server start.

TIMEZONE (string)

Sets the time zone for displaying and interpreting timestamps. The default is to use whatever the system environment specifies as the time zone.

TRANSFORM_NULL_EQUALS (boolean)

When turned on, expressions of the form *expr* = NULL (or NULL = *expr*) are treated as *expr* IS NULL, that is, they return true if *expr* evaluates to the null value, and false otherwise. The correct behavior of *expr* = NULL is to always return null (unknown). Therefore this option defaults to off.

However, filtered forms in Microsoft Access generate queries that appear to use *expr* = NULL to test for null values, so if you use that interface to access the database you might want to turn this option on. Since expressions of the form *expr* = NULL always return the null value (using the correct interpretation) they are not very useful and do not appear often in normal applications, so this option does little harm in practice. But new users are frequently confused about the semantics of expressions involving null values, so this option is not on by default.

Note that this option only affects the literal = operator, not other comparison operators or other expressions that are computationally equivalent to some expression involving the equals operator (such as IN). Thus, this option is not a general fix for bad programming.

Refer to the PostgreSQL 7.3.21 User's Guide for related information.

UNIX_SOCKET_DIRECTORY (string)

Specifies the directory of the Unix-domain socket on which the server is to listen for connections from client applications. The default is normally /tmp, but can be changed at build time.

UNIX_SOCKET_GROUP (string)

Sets the group owner of the Unix domain socket. (The owning user of the socket is always the user that starts the server.) In combination with the option UNIX_SOCKET_PERMISSIONS this can be used as an additional access control mechanism for this socket type. By default this is the empty string, which uses the default group for the current user. This option can only be set at server start.

UNIX_SOCKET_PERMISSIONS (integer)

Sets the access permissions of the Unix domain socket. Unix domain sockets use the usual Unix file system permission set. The option value is expected to be an numeric mode specification in the form accepted by the chmod and umask system calls. (To use the customary octal format the number must start with a 0 (zero).)

The default permissions are 0777, meaning anyone can connect. Reasonable alternatives are 0770 (only user and group, see also under UNIX_SOCKET_GROUP) and 0700 (only user). (Note that actually for a Unix domain socket, only write permission matters and there is no point in setting or revoking read or execute permissions.)

This access control mechanism is independent of the one described in Chapter 6, *Client Authentication*.

This option can only be set at server start.

VACUUM_MEM (integer)

Specifies the maximum amount of memory to be used by VACUUM to keep track of to-be-reclaimed tuples. The value is specified in kilobytes, and defaults to 8192 kilobytes. Larger settings may improve the speed of vacuuming large tables that have many deleted tuples.

VIRTUAL_HOST (string)

Specifies the TCP/IP host name or address on which the postmaster is to listen for connections from client applications. Defaults to listening on all configured addresses (including localhost).

ZERO_DAMAGED_PAGES (boolean)

Detection of a damaged page header normally causes PostgreSQL to report an error, aborting the current transaction. Setting zero_damaged_pages to true causes the system to instead report a warning, zero out the damaged page, and continue processing. This behavior *will destroy data*, namely all the rows on the damaged page. But it allows you to get past the error and retrieve rows from any undamaged pages that may be present in the table. So it is useful for recovering data if corruption has occurred due to hardware or software error. You should generally not set this true until you have given up hope of recovering data from the damaged page(s) of a table. The default setting is off, and it can only be changed by a superuser.

3.4.5. WAL

See also Section 12.3, “WAL Configuration” for details on WAL tuning.

CHECKPOINT_SEGMENTS (integer)

Maximum distance between automatic WAL checkpoints, in log file segments (each segment is normally 16 megabytes). This option can only be set at server start or in the postgresql.conf file.

CHECKPOINT_TIMEOUT (integer)

Maximum time between automatic WAL checkpoints, in seconds. This option can only be set at server start or in the postgresql.conf file.

COMMIT_DELAY (integer)

Time delay between writing a commit record to the WAL buffer and flushing the buffer out to disk, in microseconds. A nonzero delay allows multiple transactions to be committed with only one fsync system call, if system load is high enough additional transactions may become ready to commit within the given interval. But the delay is just wasted if no other transactions become ready to commit. Therefore, the delay is only performed if at least COMMIT_SIBLINGS other transactions are active at the instant that a backend process has written its commit record.

COMMIT_SIBLINGS (integer)

Minimum number of concurrent open transactions to require before performing the COMMIT_DELAY delay. A larger value makes it more probable that at least one other transaction will become ready to commit during the delay interval.

WAL_BUFFERS (integer)

Number of disk-page buffers in shared memory for WAL logging. The default is 4. This option can only be set at server start.

WAL_DEBUG (integer)

If nonzero, turn on WAL-related debugging output on standard error.

WAL_SYNC_METHOD (string)

Method used for forcing WAL updates out to disk. Possible values are FSYNC (call fsync() at each commit), FDATASYNC (call fdatasync() at each commit), OPEN_SYNC (write WAL files with open() option O_SYNC), or OPEN_DATASYNC (write WAL files with open() option O_DSYNC). Not all of these choices are available on all platforms. This option can only be set at server start or in the postgresql.conf file.

3.4.6. Short Options

For convenience there are also single letter option switches available for many parameters. They are described in Table 3.2, “Short option key”.

Table 3.2. Short option key

Short option	Equivalent
-B *x*	shared_buffers = *x*
-d *x*	server_min_messages = DEBUG*x*
-F	fsync = off
-h *x*	virtual_host = *x*
-i	tcpip_socket = on
-k *x*	unix_socket_directory = *x*
-l	ssl = on
-N *x*	max_connections = *x*
-p *x*	port = *x*
-fi, -fh, -fm, -fn, -fs, -ft[a]	enable_indexscan=off, enable_hashjoin=off, enable_mergejoin=off, enable_nestloop=off, enable_seqscan=off, enable_tidscan=off

Short option	Equivalent
`-s`[a]	`show_statement_stats = on`
`-S` *x*[a]	`sort_mem =` *x*
`-tpa`, `-tpl`, `-te`[a]	`show_parser_stats=on`, `show_planner_stats=on`, `show_executor_stats=on`

[a] For historical reasons, these options must be passed to the individual backend process via the `-o` postmaster option, for example,

```
$ postmaster -o '-S 1024 -s'
```

or via `PGOPTIONS` from the client side, as explained above.

3.5. Managing Kernel Resources

A large PostgreSQL installation can quickly exhaust various operating system resource limits. (On some systems, the factory defaults are so low that you don't even need a really “large” installation.) If you have encountered this kind of problem, keep reading.

3.5.1. Shared Memory and Semaphores

Shared memory and semaphores are collectively referred to as “System V IPC” (together with message queues, which are not relevant for PostgreSQL). Almost all modern operating systems provide these features, but not all of them have them turned on or sufficiently sized by default, especially systems with BSD heritage. (For the QNX and BeOS ports, PostgreSQL provides its own replacement implementation of these facilities.)

The complete lack of these facilities is usually manifested by an Illegal system call error upon postmaster start. In that case there's nothing left to do but to reconfigure your kernel -- PostgreSQL won't work without them.

When PostgreSQL exceeds one of the various hard IPC limits, the postmaster will refuse to start and should leave an instructive error message describing the problem encountered and what to do about it. (See also Section 3.3.1, “Server Start-up Failures”.) The relevant kernel parameters are named consistently across different systems; Table 3.3, “System V IPC parameters” gives an overview. The methods to set them, however, vary. Suggestions for some platforms are given below. Be warned that it is often necessary to reboot your machine, and possibly even recompile the kernel, to change these settings.

Table 3.3. System V IPC parameters

Name	Description	Reasonable values
`SHMMAX`	Maximum size of shared memory segment (bytes)	250kB + 8.2 kB * `shared_buffers` + 14.2 kB * `max_connections` or infinity
`SHMMIN`	Minimum size of shared memory segment (bytes)	1
`SHMALL`	Total amount of shared memory available (bytes or pages)	if bytes, same as `SHMMAX`; if pages, `ceil(SHMMAX/PAGE_SIZE)`
`SHMSEG`	Maximum number of shared memory segments per process	only 1 segment is needed, but the default is much higher
`SHMMNI`	Maximum number of shared memory segments system-wide	like `SHMSEG` plus room for other applications

Name	Description	Reasonable values
SEMMNI	Maximum number of semaphore identifiers (i.e., sets)	>= ceil(max_connections / 16)
SEMMNS	Maximum number of semaphores system-wide	ceil(max_connections / 16) * 17 + room for other applications
SEMMSL	Maximum number of semaphores per set	>= 17
SEMMAP	Number of entries in semaphore map	see text
SEMVMX	Maximum value of semaphore	>= 255 (The default is often 32767, don't change unless asked to.)

The most important shared memory parameter is SHMMAX, the maximum size, in bytes, of a shared memory segment. If you get an error message from shmget like Invalid argument, it is possible that this limit has been exceeded. The size of the required shared memory segment varies both with the number of requested buffers (-B option) and the number of allowed connections (-N option), although the former is the most significant. (You can, as a temporary solution, lower these settings to eliminate the failure.) As a rough approximation, you can estimate the required segment size by multiplying the number of buffers and the block size (8 kB by default) plus ample overhead (at least half a megabyte). Any error message you might get will contain the size of the failed allocation request.

Less likely to cause problems is the minimum size for shared memory segments (SHMMIN), which should be at most approximately 256 kB for PostgreSQL (it is usually just 1). The maximum number of segments system-wide (SHMMNI) or per-process (SHMSEG) should not cause a problem unless your system has them set to zero. Some systems also have a limit on the total amount of shared memory in the system; see the platform-specific instructions below.

PostgreSQL uses one semaphore per allowed connection (-N option), in sets of 16. Each such set will also contain a 17th semaphore which contains a "magic number", to detect collision with semaphore sets used by other applications. The maximum number of semaphores in the system is set by SEMMNS, which consequently must be at least as high as the connection setting plus one extra for each 16 allowed connections (see the formula in Table 3.3, "System V IPC parameters"). The parameter SEMMNI determines the limit on the number of semaphore sets that can exist on the system at one time. Hence this parameter must be at least ceil(max_connections / 16). Lowering the number of allowed connections is a temporary workaround for failures, which are usually confusingly worded "No space left on device", from the function semget().

In some cases it might also be necessary to increase SEMMAP to be at least on the order of SEMMNS. This parameter defines the size of the semaphore resource map, in which each contiguous block of available semaphores needs an entry. When a semaphore set is freed it is either added to an existing entry that is adjacent to the freed block or it is registered under a new map entry. If the map is full, the freed semaphores get lost (until reboot). Fragmentation of the semaphore space could over time lead to fewer available semaphores than there should be.

The SEMMSL parameter, which determines how many semaphores can be in a set, must be at least 17 for PostgreSQL.

Various other settings related to "semaphore undo", such as SEMMNU and SEMUME, are not of concern for PostgreSQL.

BSD/OS

Shared Memory. By default, only 4 MB of shared memory is supported. Keep in mind that shared memory is not pageable; it is locked in RAM. To increase the number of shared buffers

supported by the postmaster, add the following to your kernel configuration file. A `SHMALL` value of 1024 represents 4 MB of shared memory. The following increases the maximum shared memory area to 32 MB:

```
options "SHMALL=8192"
options "SHMMAX=\(SHMALL*PAGE_SIZE\)"
```

For those running 4.1 or later, just make the above changes, recompile the kernel, and reboot. For those running earlier releases, use `bpatch` to find the `sysptsize` value in the current kernel. This is computed dynamically at boot time.

```
$ bpatch -r sysptsize
0x9 = 9
```

Next, add `SYSPTSIZE` as a hard-coded value in the kernel configuration file. Increase the value you found using bpatch. Add 1 for every additional 4 MB of shared memory you desire.

```
options "SYSPTSIZE=16"
```

`sysptsize` cannot be changed by `sysctl`.

Semaphores. You may need to increase the number of semaphores. By default, PostgreSQL allocates 34 semaphores, which is over half the default system total of 60.

Set the values you want in your kernel configuration file, e.g.:

```
options "SEMMNI=40"
options "SEMMNS=240"
options "SEMUME=40"
options "SEMMNU=120"
```

FreeBSD
NetBSD
OpenBSD

The options `SYSVSHM` and `SYSVSEM` need to be enabled when the kernel is compiled. (They are by default.) The maximum size of shared memory is determined by the option `SHMMAXPGS` (in pages). The following shows an example of how to set the various parameters:

```
options         SYSVSHM
options         SHMMAXPGS=4096
options         SHMSEG=256

options         SYSVSEM
options         SEMMNI=256
options         SEMMNS=512
options         SEMMNU=256
options         SEMMAP=256
```

(On NetBSD and OpenBSD the key word is actually `option` singular.)

You may also want to use the sysctl setting to lock shared memory into RAM and prevent it from being paged out to swap.

HP-UX

The default settings tend to suffice for normal installations. On HP-UX 10, the factory default for `SEMMNS` is 128, which might be too low for larger database sites.

IPC parameters can be set in the System Administration Manager (SAM) under Kernel Configuration → Configurable Parameters. Hit Create A New Kernel when you're done.

Linux

The default shared memory limit (both `SHMMAX` and `SHMALL`) is 32 MB in 2.2 kernels, but it can be changed in the `proc` file system (without reboot). For example, to allow 128 MB:

```
$ echo 134217728 >/proc/sys/kernel/shmall
$ echo 134217728 >/proc/sys/kernel/shmmax
```

You could put these commands into a script run at boot-time.

Alternatively, you can use sysctl, if available, to control these parameters. Look for a file called `/etc/sysctl.conf` and add lines like the following to it:

```
kernel.shmall = 134217728
kernel.shmmax = 134217728
```

This file is usually processed at boot time, but sysctl can also be called explicitly later.

Other parameters are sufficiently sized for any application. If you want to see for yourself look in `/usr/src/linux/include/asm-`*`xxx`*`/shmparam.h` and `/usr/src/linux/include/linux/sem.h`.

MacOS X

Edit the file `/System/Library/StartupItems/SystemTuning/SystemTuning` and change the following values:

```
sysctl -w kern.sysv.shmmax
sysctl -w kern.sysv.shmmin
sysctl -w kern.sysv.shmmni
sysctl -w kern.sysv.shmseg
sysctl -w kern.sysv.shmall
```

These values have the same meanings on MacOS X as those listed for previous operating systems.

SCO OpenServer

In the default configuration, only 512 kB of shared memory per segment is allowed, which is about enough for `-B 24 -N 12`. To increase the setting, first change directory to `/etc/conf/cf.d`. To display the current value of `SHMMAX`, in bytes, run

```
./configure -y SHMMAX
```

To set a new value for `SHMMAX`, run:

```
./configure SHMMAX=value
```

where *`value`* is the new value you want to use (in bytes). After setting `SHMMAX`, rebuild the kernel

```
./link_unix
```

and reboot.

Solaris

At least in version 2.6, the default maximum size of a shared memory segments is too low for PostgreSQL. The relevant settings can be changed in `/etc/system`, for example:

```
set shmsys:shminfo_shmmax=0x2000000
set shmsys:shminfo_shmmin=1
```

```
set shmsys:shminfo_shmmni=256
set shmsys:shminfo_shmseg=256

set semsys:seminfo_semmap=256
set semsys:seminfo_semmni=512
set semsys:seminfo_semmns=512
set semsys:seminfo_semmsl=32
```

You need to reboot for the changes to take effect.

See also http://www.sunworld.com/swol-09-1997/swol-09-insidesolaris.html for information on shared memory under Solaris.

UnixWare

On UnixWare 7, the maximum size for shared memory segments is 512 kB in the default configuration. This is enough for about `-B 24 -N 12`. To display the current value of `SHMMAX`, run

```
/etc/conf/bin/idtune -g SHMMAX
```

which displays the current, default, minimum, and maximum values, in bytes. To set a new value for `SHMMAX`, run:

```
/etc/conf/bin/idtune SHMMAX value
```

where *`value`* is the new value you want to use (in bytes). After setting `SHMMAX`, rebuild the kernel

```
/etc/conf/bin/idbuild -B
```

and reboot.

3.5.2. Resource Limits

Unix-like operating systems enforce various kinds of resource limits that might interfere with the operation of your PostgreSQL server. Of particular importance are limits on the number of processes per user, the number of open files per process, and the amount of memory available to each process. Each of these have a “hard” and a “soft” limit. The soft limit is what actually counts but it can be changed by the user up to the hard limit. The hard limit can only be changed by the root user. The system call `setrlimit` is responsible for setting these parameters. The shell's built-in command `ulimit` (Bourne shells) or `limit` (csh) is used to control the resource limits from the command line. On BSD-derived systems the file `/etc/login.conf` controls the various resource limits set during login. See login.conf for details. The relevant parameters are `maxproc`, `openfiles`, and `datasize`. For example:

```
default:\
...
        :datasize-cur=256M:\
        :maxproc-cur=256:\
        :openfiles-cur=256:\
...
```

(`-cur` is the soft limit. Append `-max` to set the hard limit.)

Kernels can also have system-wide limits on some resources.

- On Linux `/proc/sys/fs/file-max` determines the maximum number of open files that the kernel will support. It can be changed by writing a different number into the file or by adding an assignment in `/etc/sysctl.conf`. The maximum limit of files per process is fixed at the

time the kernel is compiled; see `/usr/src/linux/Documentation/proc.txt` for more information.

The PostgreSQL server uses one process per connection so you should provide for at least as many processes as allowed connections, in addition to what you need for the rest of your system. This is usually not a problem but if you run several servers on one machine things might get tight.

The factory default limit on open files is often set to "socially friendly" values that allow many users to coexist on a machine without using an inappropriate fraction of the system resources. If you run many servers on a machine this is perhaps what you want, but on dedicated servers you may want to raise this limit.

On the other side of the coin, some systems allow individual processes to open large numbers of files; if more than a few processes do so then the system-wide limit can easily be exceeded. If you find this happening, and don't want to alter the system-wide limit, you can set PostgreSQL's `max_files_per_process` configuration parameter to limit the consumption of open files.

3.6. Shutting Down the Server

There are several ways to shut down the database server. You control the type of shutdown by sending different signals to the server process.

SIGTERM

After receiving SIGTERM, the postmaster disallows new connections, but lets existing backends end their work normally. It shuts down only after all of the backends terminate normally. This is *Smart Shutdown*.

SIGINT

The postmaster disallows new connections and sends all existing backends SIGTERM, which will cause them to abort their current transactions and exit promptly. It then waits for the backends to exit and finally shuts down. This is *Fast Shutdown*.

SIGQUIT

This is *Immediate Shutdown*, which will cause the postmaster to send a SIGQUIT to all backends and exit immediately (without properly shutting itself down). The backends likewise exit immediately upon receiving SIGQUIT. This will lead to recovery (by replaying the WAL log) upon next start-up. This is recommended only in emergencies.

Important

It is best not to use SIGKILL to shut down the postmaster. This will prevent the postmaster from releasing shared memory and semaphores, which may then have to be done by manually.

The PID of the postmaster process can be found using the ps program, or from the file `postmaster.pid` in the data directory. So for example, to do a fast shutdown:

```
$ kill -INT `head -1 /usr/local/pgsql/data/postmaster.pid`
```

The program pg_ctl is a shell script that provides a more convenient interface for shutting down the postmaster.

3.7. Secure TCP/IP Connections with SSL

PostgreSQL has native support for using SSL connections to encrypt client/server communications for increased security. This requires OpenSSL be installed on both client and server systems and support enabled at build time (see Chapter 1, *Installation Instructions*).

With SSL support compiled in, the PostgreSQL server can be started with SSL support by setting the parameter `ssl` to on in `postgresql.conf`. When starting in SSL mode, the server will look for the files `server.key` and `server.crt` in the data directory. These files should contain the server private key and certificate respectively. These files must be set up correctly before an SSL-enabled server can start. If the private key is protected with a passphrase, the server will prompt for the passphrase and will not start until it has been entered.

The server will listen for both standard and SSL connections on the same TCP/IP port, and will negotiate with any connecting client on whether to use SSL. See Chapter 6, *Client Authentication* about how to force the server to require use of SSL for certain connections.

For details on how to create your server private key and certificate, refer to the OpenSSL documentation. A simple self-signed certificate can be used to get started for testing, but a certificate signed by a certificate authority (CA) (either one of the global CAs or a local one) should be used in production so the client can verify the server's identity. To create a quick self-signed certificate, use the following OpenSSL command:

```
openssl req -new -text -out server.req
```

Fill out the information that `openssl` asks for. Make sure that you enter the local host name as Common Name; the challenge password can be left blank. The script will generate a key that is passphrase protected; it will not accept a passphrase that is less than four characters long. To remove the passphrase (as you must if you want automatic start-up of the server), run the commands

```
openssl rsa -in privkey.pem -out server.key
rm privkey.pem
```

Enter the old passphrase to unlock the existing key. Now do

```
openssl req -x509 -in server.req -text -key server.key -out
 server.crt
chmod og-rwx server.key
```

to turn the certificate into a self-signed certificate and to copy the key and certificate to where the server will look for them.

3.8. Secure TCP/IP Connections with SSH Tunnels

Acknowledgement

Idea taken from an email by Gene Selkov, Jr. (<selkovjr@mcs.anl.gov>) written on 1999-09-08 in response to a question from Eric Marsden.

One can use SSH to encrypt the network connection between clients and a PostgreSQL server. Done properly, this provides an adequately secure network connection.

First make sure that an SSH server is running properly on the same machine as PostgreSQL and that you can log in using `ssh` as some user. Then you can establish a secure tunnel with a command like this from the client machine:

```
ssh -L 3333:foo.com:5432 joe@foo.com
```

The first number in the `-L` argument, 3333, is the port number of your end of the tunnel; it can be chosen freely. The second number, 5432, is the remote end of the tunnel -- the port number your server is using. The name or the address in between the port numbers is the host with the database server you are going to connect to. In order to connect to the database server using this tunnel, you connect to port 3333 on the local machine:

```
psql -h localhost -p 3333 template1
```

To the database server it will then look as though you are really user `joe@foo.com` and it will use whatever authentication procedure was set up for this user. In order for the tunnel setup to succeed you must be allowed to connect via `ssh` as joe@foo.com, just as if you had attempted to use `ssh` to set up a terminal session.

Tip

Several other applications exist that can provide secure tunnels using a procedure similar in concept to the one just described.

Chapter 4. Database Users and Privileges

Every database cluster contains a set of database users. Those users are separate from the users managed by the operating system on which the server runs. Users own database objects (for example, tables) and can assign privileges on those objects to other users to control who has access to which object.

This chapter describes how to create and manage users and introduces the privilege system. More information about the various types of database objects and the effects of privileges can be found in the PostgreSQL 7.3.21 User's Guide.

4.1. Database Users

Database users are conceptually completely separate from operating system users. In practice it might be convenient to maintain a correspondence, but this is not required. Database user names are global across a database cluster installation (and not per individual database). To create a user use the `CREATE USER` SQL command:

```
CREATE USER name
```

`name` follows the rules for SQL identifiers: either unadorned without special characters, or double-quoted. To remove an existing user, use the analogous `DROP USER` command:

```
DROP USER name
```

For convenience, the programs createuser and dropuser are provided as wrappers around these SQL commands that can be called from the shell command line:

```
createuser name
dropuser name
```

In order to bootstrap the database system, a freshly initialized system always contains one predefined user. This user will have the fixed ID 1, and by default (unless altered when running initdb) it will have the same name as the operating system user that initialized the database cluster. Customarily, this user will be named postgres. In order to create more users you first have to connect as this initial user.

Exactly one user identity is active for a connection to the database server. The user name to use for a particular database connection is indicated by the client that is initiating the connection request in an application-specific fashion. For example, the psql program uses the `-U` command line option to indicate the user to connect as. Many applications assume the name of the current operating system user by default (including createuser and psql). Therefore it is convenient to maintain a naming correspondence between the two user sets.

The set of database users a given client connection may connect as is determined by the client authentication setup, as explained in Chapter 6, *Client Authentication*. (Thus, a client is not necessarily limited to connect as the user with the same name as its operating system user, in the same way a person is not constrained in its login name by her real name.) Since the user identity determines the set of privileges available to a connected client, it is important to carefully configure this when setting up a multiuser environment.

4.2. User Attributes

A database user may have a number of attributes that define its privileges and interact with the client authentication system.

superuser

A database superuser bypasses all permission checks. Also, only a superuser can create new users. To create a database superuser, use `CREATE USER name CREATEUSER`.

database creation

A user must be explicitly given permission to create databases (except for superusers, since those bypass all permission checks). To create such a user, use `CREATE USER name CREATEDB`.

password

A password is only significant if the client authentication method requires the user to supply a password when connecting to the database. The `password`, `md5`, and `crypt` authentication methods make use of passwords. Database passwords are separate from operating system passwords. Specify a password upon user creation with `CREATE USER name PASSWORD 'string'`.

A user's attributes can be modified after creation with `ALTER USER`. See the reference pages for `CREATE USER` and `ALTER USER` for details.

A user can also set personal defaults for many of the run-time configuration settings described in Section 3.4, “Run-time Configuration”. For example, if for some reason you want to disable index scans (hint: not a good idea) anytime you connect, you can use

```
ALTER USER myname SET enable_indexscan TO off;
```

This will save the setting (but not set it immediately) and in subsequent connections it will appear as though `SET enable_indexscan TO off;` had been called right before the session started. You can still alter this setting during the session; it will only be the default. To undo any such setting, use `ALTER USER username RESET varname;`.

4.3. Groups

As in Unix, groups are a way of logically grouping users to ease management of privileges: privileges can be granted to, or revoked from, a group as a whole. To create a group, use

```
CREATE GROUP name
```

To add users to or remove users from a group, use

```
ALTER GROUP name ADD USER uname1, ...
ALTER GROUP name DROP USER uname1, ...
```

4.4. Privileges

When a database object is created, it is assigned an owner. The owner is the user that executed the creation statement. To change the owner of a table, index, sequence, or view, use the `ALTER TABLE` command. By default, only an owner (or a superuser) can do anything with the object. In order to allow other users to use it, *privileges* must be granted.

There are several different privileges: `SELECT`, `INSERT`, `UPDATE`, `DELETE`, `RULE`, `REFERENCES`, `TRIGGER`, `CREATE`, `TEMPORARY`, `EXECUTE`, `USAGE`, and `ALL PRIVILEGES`. For more information on the different types of privileges support by PostgreSQL, refer to the `GRANT` page in the PostgreSQL 7.3.21 Reference Manual. The right to modify or destroy an object is always the privilege of the owner only. To assign privileges, the `GRANT` command is used. So, if `joe` is an existing user, and `accounts` is an existing table, the privilege to update the table can be granted with

```
GRANT UPDATE ON accounts TO joe;
```

The user executing this command must be the owner of the table. To grant a privilege to a group, use

```
GRANT SELECT ON accounts TO GROUP staff;
```

The special "user" name `PUBLIC` can be used to grant a privilege to every user on the system. Writing `ALL` in place of a specific privilege specifies that all privileges will be granted.

To revoke a privilege, use the fittingly named `REVOKE` command:

```
REVOKE ALL ON accounts FROM PUBLIC;
```

The special privileges of the table owner (i.e., the right to do `DROP`, `GRANT`, `REVOKE`, etc) are always implicit in being the owner, and cannot be granted or revoked. But the table owner can choose to revoke his own ordinary privileges, for example to make a table read-only for himself as well as others.

4.5. Functions and Triggers

Functions and triggers allow users to insert code into the backend server that other users may execute without knowing it. Hence, both mechanisms permit users to *Trojan horse* others with relative impunity. The only real protection is tight control over who can define functions.

Functions written in any language except SQL run inside the backend server process with the operating systems permissions of the database server daemon process. It is possible to change the server's internal data structures from inside of trusted functions. Hence, among many other things, such functions can circumvent any system access controls. This is an inherent problem with user-defined C functions.

Chapter 5. Managing Databases

Every instance of a running PostgreSQL server manages one or more databases. Databases are therefore the topmost hierarchical level for organizing SQL objects ("database objects"). This chapter describes the properties of databases, and how to create, manage, and destroy them.

5.1. Overview

A database is a named collection of SQL objects ("database objects"). Generally, every database object (tables, functions, etc.) belongs to one and only one database. (But there are a few system catalogs, for example `pg_database`, that belong to a whole installation and are accessible from each database within the installation.) More accurately, a database is a collection of schemas and the schemas contain the tables, functions, etc. So the full hierarchy is: server, database, schema, table (or something else instead of a table).

An application that connects to the database server specifies in its connection request the name of the database it wants to connect to. It is not possible to access more than one database per connection. (But an application is not restricted in the number of connections it opens to the same or other databases.) It is possible, however, to access more than one schema from the same connection. Schemas are a purely logical structure and who can access what is managed by the privilege system. Databases are physically separated and access control is managed at the connection level. If one PostgreSQL server instance is to house projects or users that should be separate and for the most part unaware of each other, it is therefore recommendable to put them into separate databases. If the projects or users are interrelated and should be able to use each other's resources they should be put in the same databases but possibly into separate schemas. More information about managing schemas is in the PostgreSQL 7.3.21 User's Guide.

Note

SQL calls databases "catalogs", but there is no difference in practice.

5.2. Creating a Database

In order to create a databases, the PostgreSQL server must be up and running (see Section 3.3, "Starting the Database Server").

Databases are created with the query language command `CREATE DATABASE`:

```
CREATE DATABASE name
```

where *`name`* follows the usual rules for SQL identifiers. The current user automatically becomes the owner of the new database. It is the privilege of the owner of a database to remove it later on (which also removes all the objects in it, even if they have a different owner).

The creation of databases is a restricted operation. See Section 4.2, "User Attributes" for how to grant permission.

Since you need to be connected to the database server in order to execute the `CREATE DATABASE` command, the question remains how the *first* database at any given site can be created. The first database is always created by the `initdb` command when the data storage area is initialized. (See Section 3.2, "Creating a Database Cluster".) By convention this database is called `template1`. So to create the first "real" database you can connect to `template1`.

The name "template1" is no accident: When a new database is created, the template database is essentially cloned. This means that any changes you make in `template1` are propagated to all subsequently created databases. This implies that you should not use the template database for real

work, but when used judiciously this feature can be convenient. More details appear in Section 5.3, “Template Databases”.

As an extra convenience, there is also a program that you can execute from the shell to create new databases, `createdb`.

```
createdb dbname
```

`createdb` does no magic. It connects to the template1 database and issues the `CREATE DATABASE` command, exactly as described above. It uses the psql program internally. The reference page on `createdb` contains the invocation details. Note that `createdb` without any arguments will create a database with the current user name, which may or may not be what you want.

Note

Chapter 6, *Client Authentication* contains information about how to restrict who can connect to a given database.

Sometimes you want to create a database for someone else. That user should become the owner of the new database, so he can configure and manage it himself. To achieve that, use one of the following commands:

```
CREATE DATABASE dbname OWNER username;
```

from the SQL environment, or

```
createdb -O username dbname
```

You must be a superuser to be allowed to create a database for someone else.

5.3. Template Databases

`CREATE DATABASE` actually works by copying an existing database. By default, it copies the standard system database named `template1`. Thus that database is the “template” from which new databases are made. If you add objects to `template1`, these objects will be copied into subsequently created user databases. This behavior allows site-local modifications to the standard set of objects in databases. For example, if you install the procedural language PL/pgSQL in `template1`, it will automatically be available in user databases without any extra action being taken when those databases are made.

There is a second standard system database named `template0`. This database contains the same data as the initial contents of `template1`, that is, only the standard objects predefined by your version of PostgreSQL. `template0` should never be changed after `initdb`. By instructing `CREATE DATABASE` to copy `template0` instead of `template1`, you can create a “virgin” user database that contains none of the site-local additions in `template1`. This is particularly handy when restoring a `pg_dump` dump: the dump script should be restored in a virgin database to ensure that one recreates the correct contents of the dumped database, without any conflicts with additions that may now be present in `template1`.

To create a database by copying `template0`, use

```
CREATE DATABASE dbname TEMPLATE template0;
```

from the SQL environment, or

```
createdb -T template0 dbname
```

from the shell.

It is possible to create additional template databases, and indeed one might copy any database in an installation by specifying its name as the template for `CREATE DATABASE`. It is important to

understand, however, that this is not (yet) intended as a general-purpose "COPY DATABASE" facility. In particular, it is essential that the source database be idle (no data-altering transactions in progress) for the duration of the copying operation. CREATE DATABASE will check that no backend processes (other than itself) are connected to the source database at the start of the operation, but this does not guarantee that changes cannot be made while the copy proceeds, which would result in an inconsistent copied database. Therefore, we recommend that databases used as templates be treated as read-only.

Two useful flags exist in pg_database for each database: the columns datistemplate and datallowconn. datistemplate may be set to indicate that a database is intended as a template for CREATE DATABASE. If this flag is set, the database may be cloned by any user with CREATEDB privileges; if it is not set, only superusers and the owner of the database may clone it. If datallowconn is false, then no new connections to that database will be allowed (but existing sessions are not killed simply by setting the flag false). The template0 database is normally marked datallowconn = false to prevent modification of it. Both template0 and template1 should always be marked with datistemplate = true.

After preparing a template database, or making any changes to one, it is a good idea to perform VACUUM FREEZE or VACUUM FULL FREEZE in that database. If this is done when there are no other open transactions in the same database, then it is guaranteed that all tuples in the database are "frozen" and will not be subject to transaction ID wraparound problems. This is particularly important for a database that will have datallowconn set to false, since it will be impossible to do routine maintenance VACUUMs on such a database. See Section 8.2.3, "Preventing transaction ID wraparound failures" for more information.

Note

template1 and template0 do not have any special status beyond the fact that the name template1 is the default source database name for CREATE DATABASE and the default database-to-connect-to for various programs such as createdb. For example, one could drop template1 and recreate it from template0 without any ill effects. This course of action might be advisable if one has carelessly added a bunch of junk in template1.

5.4. Database Configuration

Recall from Section 3.4, "Run-time Configuration" that the PostgreSQL server provides a large number of run-time configuration variables. You can set database-specific default values for many of these settings.

For example, if for some reason you want to disable the GEQO optimizer for a given database, you'd ordinarily have to either disable it for all databases or make sure that every connecting client is careful to issue SET geqo TO off;. To make this setting the default you can execute the command

```
ALTER DATABASE mydb SET geqo TO off;
```

This will save the setting (but not set it immediately) and in subsequent connections it will appear as though SET geqo TO off; had been called right before the session started. Note that users can still alter this setting during the session; it will only be the default. To undo any such setting, use ALTER DATABASE *dbname* RESET *varname*;.

5.5. Alternative Locations

It is possible to create a database in a location other than the default location for the installation. Remember that all database access occurs through the database server, so any location specified must be accessible by the server.

Alternative database locations are referenced by an environment variable which gives the absolute path to the intended storage location. This environment variable must be present in the server's environment, so it must have been defined before the server was started. (Thus, the set of available

alternative locations is under the site administrator's control; ordinary users can't change it.) Any valid environment variable name may be used to reference an alternative location, although using variable names with a prefix of PGDATA is recommended to avoid confusion and conflict with other variables.

To create the variable in the environment of the server process you must first shut down the server, define the variable, initialize the data area, and finally restart the server. (See Section 3.6, “Shutting Down the Server” and Section 3.3, “Starting the Database Server”.) To set an environment variable, type

```
PGDATA2=/home/postgres/data
export PGDATA2
```

in Bourne shells, or

```
setenv PGDATA2 /home/postgres/data
```

in csh or tcsh. You have to make sure that this environment variable is always defined in the server environment, otherwise you won't be able to access that database. Therefore you probably want to set it in some sort of shell start-up file or server start-up script.

To create a data storage area in PGDATA2, ensure that the containing directory (here, /home/postgres) already exists and is writable by the user account that runs the server (see Section 3.1, “The PostgreSQL User Account”). Then from the command line, type

```
initlocation PGDATA2
```

(*not* initlocation $PGDATA2). Then you can restart the server.

To create a database within the new location, use the command

```
CREATE DATABASE name WITH LOCATION = 'location'
```

where *location* is the environment variable you used, PGDATA2 in this example. The createdb command has the option -D for this purpose.

Databases created in alternative locations can be accessed and dropped like any other database.

Note

It can also be possible to specify absolute paths directly to the CREATE DATABASE command without defining environment variables. This is disallowed by default because it is a security risk. To allow it, you must compile PostgreSQL with the C preprocessor macro ALLOW_ABSOLUTE_DBPATHS defined. One way to do this is to run the compilation step like this:

```
gmake CPPFLAGS=-DALLOW_ABSOLUTE_DBPATHS all
```

5.6. Destroying a Database

Databases are destroyed with the command DROP DATABASE:

```
DROP DATABASE name
```

Only the owner of the database (i.e., the user that created it), or a superuser, can drop a database. Dropping a database removes all objects that were contained within the database. The destruction of a database cannot be undone.

You cannot execute the DROP DATABASE command while connected to the victim database. You can, however, be connected to any other database, including the template1 database, which would be the only option for dropping the last user database of a given cluster.

For convenience, there is also a shell program to drop databases:

```
dropdb dbname
```

(Unlike `createdb`, it is not the default action to drop the database with the current user name.)

Chapter 6. Client Authentication

When a client application connects to the database server, it specifies which PostgreSQL user name it wants to connect as, much the same way one logs into a Unix computer as a particular user. Within the SQL environment the active database user name determines access privileges to database objects -- see Chapter 4, *Database Users and Privileges* for more information. Therefore, it is essential to restrict which database users can connect.

Authentication is the process by which the database server establishes the identity of the client, and by extension determines whether the client application (or the user who runs the client application) is permitted to connect with the user name that was requested.

PostgreSQL offers a number of different client authentication methods. The method used to authenticate a particular client connection can be selected on the basis of (client) host address, database, and user.

PostgreSQL user names are logically separate from user names of the operating system in which the server runs. If all the users of a particular server also have accounts on the server's machine, it makes sense to assign database user names that match their operating system user names. However, a server that accepts remote connections may have many users who have no local account, and in such cases there need be no connection between database user names and OS user names.

6.1. The `pg_hba.conf` file

Client authentication is controlled by the file `pg_hba.conf` in the data directory, e.g., `/usr/local/pgsql/data/pg_hba.conf`. (HBA stands for host-based authentication.) A default `pg_hba.conf` file is installed when the data directory is initialized by `initdb`.

The general format of the `pg_hba.conf` file is a set of records, one per line. Blank lines are ignored, as is any text after the "#" comment character. A record is made up of a number of fields which are separated by spaces and/or tabs. Fields can contain white space if the field value is quoted. Records cannot be continued across lines.

Each record specifies a connection type, a client IP address range (if relevant for the connection type), a database name, a user name, and the authentication method to be used for connections matching these parameters. The first record with a matching connection type, client address, requested database, and user name is used to perform authentication. There is no "fall-through" or "backup": if one record is chosen and the authentication fails, subsequent records are not considered. If no record matches, access is denied.

A record may have one of the three formats

```
local   database  user  authentication-method  [authentication-
option]
host    database  user  IP-address  IP-mask  authentication-method
 [authentication-option]
hostssl  database  user  IP-address  IP-mask  authentication-method
  [authentication-option]
```

The meaning of the fields is as follows:

`local`

This record matches connection attempts using Unix domain sockets. Without a record of this type, Unix-domain socket connections are disallowed

`host`

This record matches connection attempts using TCP/IP networks. Note that TCP/IP connections are disabled unless the server is started with the `-i` option or the `tcpip_socket` `postgresql.conf` configuration parameter is enabled.

`hostssl`

This record matches connection attempts using SSL over TCP/IP. `host` records will match either SSL or non-SSL connection attempts, but `hostssl` records require SSL connections.

To be able make use of this option the server must be built with SSL support enabled. Furthermore, SSL must be enabled by enabling the option `ssl` in `postgresql.conf` (see Section 3.4, "Run-time Configuration").

`database`

Specifies which databases this record matches. The value `all` specifies that it matches all databases. The value `sameuser` specifies that the record matches if the requested database has the same name as the requested user. The value `samegroup` specifies that the requested user must a member of the group with the same name as the requested database. Otherwise, this is the name of a specific PostgreSQL database. Multiple database names can be supplied by separating them with commas. A file containing database names can be specified by preceding the file name with `@`. The file must be in the same directory as `pg_hba.conf`.

`user`

Specifies which PostgreSQL users this record matches. The value `all` specifies that it matches all users. Otherwise, this is the name of a specific PostgreSQL user. Multiple user names can be supplied by separating them with commas. Group names can be specified by preceding the group name with `+`. A file containing user names can be specified by preceding the file name with `@`. The file must be in the same directory as `pg_hba.conf`.

`IP-address`
`IP-mask`

These two fields contain IP address/mask values in standard dotted decimal notation. (IP addresses can only be specified numerically, not as domain or host names.) Taken together they specify the client machine IP addresses that this record matches. The precise logic is that

```
(actual-IP-address xor IP-address-field) and IP-
mask-field
```

must be zero for the record to match. (Of course IP addresses can be spoofed but this consideration is beyond the scope of PostgreSQL.)

These fields only apply to `host` and `hostssl` records.

`authentication-method`

Specifies the authentication method to use when connecting via this record. The possible choices are summarized here; details are in Section 6.2, "Authentication methods".

`trust`

The connection is allowed unconditionally. This method allows anyone that can connect to the PostgreSQL database to login as any PostgreSQL user they like, without the need for a password. See Section 6.2.1, "Trust authentication" for details.

`reject`

The connection is rejected unconditionally. This is useful for "filtering out" certain hosts from a group.

`md5`

Requires the client to supply an MD5 encrypted password for authentication. This is the only method that allows encrypted passwords to be stored in `pg_shadow`. See Section 6.2.2, “Password authentication” for details.

`crypt`

Like `md5` method but uses older crypt encryption, which is needed for pre-7.2 clients. `md5` is preferred for 7.2 and later clients. See Section 6.2.2, “Password authentication” for details.

`password`

Same as "md5", but the password is sent in clear text over the network. This should not be used on untrusted networks. See Section 6.2.2, “Password authentication” for details.

`krb4`

Kerberos V4 is used to authenticate the user. This is only available for TCP/IP connections. See Section 6.2.3, “Kerberos authentication” for details.

`krb5`

Kerberos V5 is used to authenticate the user. This is only available for TCP/IP connections. See Section 6.2.3, “Kerberos authentication” for details.

`ident`

Obtain the operating system user name of the client (for TCP/IP connections by contacting the ident server on the client, for local connections by getting it from the operating system) and check if the user is allowed to connect as the requested database user by consulting the map specified after the `ident` key word.

If you use the map `sameuser`, the user names are assumed to be identical. If not, the map name is looked up in the file `pg_ident.conf` in the same directory as `pg_hba.conf`. The connection is accepted if that file contains an entry for this map name with the ident-supplied user name and the requested PostgreSQL user name.

For local connections, this only works on machines that support Unix-domain socket credentials (currently Linux, FreeBSD, NetBSD, and BSD/OS).

See Section 6.2.4, “Ident-based authentication” below for details.

`pam`

Authenticate using the Pluggable Authentication Modules (PAM) service provided by the operating system. See Section 6.2.5, “PAM Authentication” for details.

`authentication-option`

The meaning of this optional field depends on the chosen authentication method and is described in the next section.

Since the `pg_hba.conf` records are examined sequentially for each connection attempt, the order of the records is significant. Typically, earlier records will have tight connection match parameters and weaker authentication methods, while later records will have looser match parameters and stronger authentication methods. For example, one might wish to use `trust` authentication for local TCP connections but require a password for remote TCP connections. In this case a record specifying `trust` authentication for connections from 127.0.0.1 would appear before a record specifying password authentication for a wider range of allowed client IP addresses.

Important

Do not prevent the superuser from accessing the template1 database. Various utility commands need access to template1.

The `pg_hba.conf` file is read on start-up and when the postmaster receives a SIGHUP signal. If you edit the file on an active system, you will need to signal the postmaster (using `pg_ctl reload` or `kill -HUP`) to make it re-read the file.

An example of a `pg_hba.conf` file is shown in Example 6.1, "An example `pg_hba.conf` file". See below for details on the different authentication methods.

Example 6.1. An example `pg_hba.conf` file

```
# Allow any user on the local system to connect to any database
 under
# any user name using Unix-domain sockets (the default for local
# connections).
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
local   all         all
 trust

# The same using local loopback TCP/IP connections.
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
host    all         all         127.0.0.1         255.255.255.255
 trust

# Allow any user from any host with IP address 192.168.93.x to
 connect
# to database "template1" as the same user name that ident reports
 for
# the connection (typically the Unix user name).
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
host    template1   all         192.168.93.0      255.255.255.0
 ident sameuser

# Allow a user from host 192.168.12.10 to connect to database
# "template1" if the user's password is correctly supplied.
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
host    template1   all         192.168.12.10     255.255.255.255
 md5

# In the absence of preceding "host" lines, these two lines will
# reject all connection from 192.168.54.1 (since that entry will be
# matched first), but allow Kerberos V connections from anywhere
 else
# on the Internet.  The zero mask means that no bits of the host IP
# address are considered so it matches any host.
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
```

```
host    all         all         192.168.54.1      255.255.255.255
 reject
host    all         all         0.0.0.0           0.0.0.0
 krb5

# Allow users from 192.168.x.x hosts to connect to any database, if
# they pass the ident check.  If, for example, ident says the user
 is
# "bryanh" and he requests to connect as PostgreSQL user "guest1",
 the
# connection is allowed if there is an entry in pg_ident.conf for
 map
# "omicron" that says "bryanh" is allowed to connect as "guest1".
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
host    all         all         192.168.0.0       255.255.0.0
 ident omicron

# If these are the only three lines for local connections, they
 will
# allow local users to connect only to their own databases
 (databases
# with the same name as their user name) except for administrators
 and
# members of group "support" who may connect to all databases.  The
 file
# $PGDATA/admins contains a list of user names.  Passwords are
 required in
# all cases.
#
# TYPE  DATABASE    USER        IP-ADDRESS        IP-MASK
 METHOD
local   sameuser    all
 md5
local   all         @admins
 md5
local   all         +support
 md5

# The last two lines above can be combined into a single line:
local   all         @admins,+support
 md5

# The database column can also use lists and file names, but not
 groups:
local   db1,db2,@demodbs  all
 md5
```

6.2. Authentication methods

The following describes the authentication methods in more detail.

6.2.1. Trust authentication

When `trust` authentication is specified, PostgreSQL assumes that anyone who can connect to the server is authorized to access the database as whatever database user he specifies (including the

database superuser). This method should only be used when there is adequate system-level protection on connections to the postmaster port.

`trust` authentication is appropriate and very convenient for local connections on a single-user workstation. It is usually *not* appropriate by itself on a multiuser machine. However, you may be able to use `trust` even on a multiuser machine, if you restrict access to the postmaster's socket file using file-system permissions. To do this, set the parameter `unix_socket_permissions` (and possibly `unix_socket_group`) in `postgresql.conf`, as described in Section 3.4.4, "General Operation". Or you could set `unix_socket_directory` to place the socket file in a suitably restricted directory.

Setting file-system permissions only helps for Unix-socket connections. Local TCP connections are not restricted by it; therefore, if you want to use permissions for local security, remove the `host ... 127.0.0.1 ...` line from `pg_hba.conf`, or change it to a non-`trust` authentication method.

`trust` authentication is only suitable for TCP connections if you trust every user on every machine that is allowed to connect to the server by the `pg_hba.conf` lines that specify `trust`. It is seldom reasonable to use `trust` for any TCP connections other than those from localhost (127.0.0.1).

6.2.2. Password authentication

Password-based authentication methods include `md5`, `crypt`, and `password`. These methods operate similarly except for the way that the password is sent across the connection. If you are at all concerned about password "sniffing" attacks then `md5` is preferred, with `crypt` a second choice if you must support pre-7.2 clients. Plain `password` should especially be avoided for connections over the open Internet (unless you use SSL, SSH, or other communications security wrappers around the connection).

PostgreSQL database passwords are separate from operating system user passwords. The password for each database user is stored in the `pg_shadow` system catalog table. Passwords can be managed with the query language commands `CREATE USER` and `ALTER USER`, e.g., **`CREATE USER foo WITH PASSWORD 'secret';`**. By default, that is, if no password has been set up, the stored password is null and password authentication will always fail for that user.

To restrict the set of users that are allowed to connect to certain databases, list the users separated by commas, or in a separate file. The file should contain user names separated by commas or one user name per line, and be in the same directory as `pg_hba.conf`. Mention the (base) name of the file preceded with `@` in the user column. The database column can similarly accept a list of values or a file name. You can also specify group names by preceding the group name with `+`.

6.2.3. Kerberos authentication

Kerberos is an industry-standard secure authentication system suitable for distributed computing over a public network. A description of the Kerberos system is far beyond the scope of this document; in all generality it can be quite complex (yet powerful). The Kerberos FAQ[1] or MIT Project Athena[2] can be a good starting point for exploration. Several sources for Kerberos distributions exist.

In order to use Kerberos, support for it must be enabled at build time. See Chapter 1, *Installation Instructions* for more information. Both Kerberos 4 and 5 are supported, but only one version can be supported in any one build.

PostgreSQL operates like a normal Kerberos service. The name of the service principal is *`servicename/hostname@realm`*, where *`servicename`* is `postgres` (unless a different service name was selected at configure time with `./configure --with-krb-srvnam=whatever`). *`hostname`* is the fully qualified domain name of the server machine. The service principal's realm is the preferred realm of the server machine.

[1] http://www.nrl.navy.mil/CCS/people/kenh/kerberos-faq.html
[2] ftp://athena-dist.mit.edu

Client principals must have their PostgreSQL user name as their first component, for example *pgusername/otherstuff@realm*. At present the realm of the client is not checked by PostgreSQL; so if you have cross-realm authentication enabled, then any principal in any realm that can communicate with yours will be accepted.

Make sure that your server key file is readable (and preferably only readable) by the PostgreSQL server account (see Section 3.1, "The PostgreSQL User Account"). The location of the key file is specified with the `krb_server_keyfile` run time configuration parameter. (See also Section 3.4, "Run-time Configuration".) The default is `/etc/srvtab` if you are using Kerberos 4 and `FILE:/usr/local/pgsql/etc/krb5.keytab` (or whichever directory was specified as `sysconfdir` at build time) with Kerberos 5.

To generate the keytab file, use for example (with version 5)

```
kadmin% ank -randkey postgres/server.my.domain.org
kadmin% ktadd -k krb5.keytab postgres/server.my.domain.org
```

Read the Kerberos documentation for details.

When connecting to the database make sure you have a ticket for a principal matching the requested database user name. An example: For database user name `fred`, both principal `fred@EXAMPLE.COM` and `fred/users.example.com@EXAMPLE.COM` can be used to authenticate to the database server.

If you use mod_auth_krb and mod_perl on your Apache web server, you can use `AuthType KerberosV5SaveCredentials` with a mod_perl script. This gives secure database access over the web, no extra passwords required.

6.2.4. Ident-based authentication

The ident authentication method works by inspecting the client's operating system user name and determining the allowed database user names by using a map file that lists the permitted corresponding user name pairs. The determination of the client's user name is the security-critical point, and it works differently depending on the connection type.

6.2.4.1. Ident Authentication over TCP/IP

The "Identification Protocol" is described in *RFC 1413*. Virtually every Unix-like operating system ships with an ident server that listens on TCP port 113 by default. The basic functionality of an ident server is to answer questions like "What user initiated the connection that goes out of your port *X* and connects to my port *Y*?". Since PostgreSQL knows both *X* and *Y* when a physical connection is established, it can interrogate the ident server on the host of the connecting client and could theoretically determine the operating system user for any given connection this way.

The drawback of this procedure is that it depends on the integrity of the client: if the client machine is untrusted or compromised an attacker could run just about any program on port 113 and return any user name he chooses. This authentication method is therefore only appropriate for closed networks where each client machine is under tight control and where the database and system administrators operate in close contact. In other words, you must trust the machine running the ident server. Heed the warning:

> The Identification Protocol is not intended as an authorization or access control protocol.
>
> —RFC 1413

6.2.4.2. Ident Authentication over Local Sockets

On systems supporting `SO_PEERCRED` requests for Unix-domain sockets (currently Linux, FreeBSD, NetBSD, and BSD/OS), ident authentication can also be applied to local connections. In this case,

no security risk is added by using ident authentication; indeed it is a preferable choice for local connections on such systems.

On systems without `SO_PEERCRED` requests, ident authentication is only available for TCP/IP connections. As a work around, it is possible to specify the localhost address 127.0.0.1 and make connections to this address.

6.2.4.3. Ident Maps

When using ident-based authentication, after having determined the name of the operating system user that initiated the connection, PostgreSQL checks whether that user is allowed to connect as the database user he is requesting to connect as. This is controlled by the ident map argument that follows the `ident` keyword in the `pg_hba.conf` file. There is a predefined ident map `sameuser`, which allows any operating system user to connect as the database user of the same name (if the latter exists). Other maps must be created manually.

Ident maps other than `sameuser` are defined in the file `pg_ident.conf` in the data directory, which contains lines of the general form:

map-name ident-username database-username

Comments and whitespace are handled in the usual way. The *map-name* is an arbitrary name that will be used to refer to this mapping in `pg_hba.conf`. The other two fields specify which operating system user is allowed to connect as which database user. The same *map-name* can be used repeatedly to specify more user-mappings within a single map. There is no restriction regarding how many database users a given operating system user may correspond to and vice versa.

The `pg_ident.conf` file is read on start-up and when the postmaster receives a SIGHUP signal. If you edit the file on an active system, you will need to signal the postmaster (using `pg_ctl reload` or `kill -HUP`) to make it re-read the file.

A `pg_ident.conf` file that could be used in conjunction with the `pg_hba.conf` file in Example 6.1, “An example `pg_hba.conf` file” is shown in Example 6.2, “An example `pg_ident.conf` file”. In this example setup, anyone logged in to a machine on the 192.168 network that does not have the Unix user name bryanh, ann, or robert would not be granted access. Unix user robert would only be allowed access when he tries to connect as PostgreSQL user bob, not as robert or anyone else. ann would only be allowed to connect as ann. User bryanh would be allowed to connect as either bryanh himself or as guest1.

Example 6.2. An example `pg_ident.conf` file

```
# MAPNAME     IDENT-USERNAME    PG-USERNAME

omicron       bryanh            bryanh
omicron       ann               ann
# bob has user name robert on these machines
omicron       robert            bob
# bryanh can also connect as guest1
omicron       bryanh            guest1
```

6.2.5. PAM Authentication

This authentication type operates similarly to *password* except that it uses PAM (Pluggable Authentication Modules) as the authentication mechanism. The default PAM service name is `postgresql`. You can optionally supply you own service name after the `pam` keyword in the file. For more information about PAM, please read the Linux-PAM Page[3] and the Solaris PAM Page[4].

[3] http://www.kernel.org/pub/linux/libs/pam/
[4] http://www.sun.com/software/solaris/pam/

6.3. Authentication problems

Genuine authentication failures and related problems generally manifest themselves through error messages like the following.

```
No pg_hba.conf entry for host 123.123.123.123, user andym, database
 testdb
```

This is what you are most likely to get if you succeed in contacting the server, but it does not want to talk to you. As the message suggests, the server refused the connection request because it found no authorizing entry in its `pg_hba.conf` configuration file.

```
Password authentication failed for user 'andym'
```

Messages like this indicate that you contacted the server, and it is willing to talk to you, but not until you pass the authorization method specified in the `pg_hba.conf` file. Check the password you are providing, or check your Kerberos or ident software if the complaint mentions one of those authentication types.

```
FATAL 1:  user "andym" does not exist
```

The indicated user name was not found.

```
FATAL 1:  Database "testdb" does not exist in the system catalog.
```

The database you are trying to connect to does not exist. Note that if you do not specify a database name, it defaults to the database user name, which may or may not be the right thing.

Note that the server log may contain more information about an authentication failure than is reported to the client. If you are confused about the reason for a failure, check the log.

Chapter 7. Localization

Describes the available localization features from the point of view of the administrator.

PostgreSQL supports localization with three approaches:

- Using the locale features of the operating system to provide locale-specific collation order, number formatting, translated messages, and other aspects.
- Using explicit multiple-byte character sets defined in the PostgreSQL server to support languages that require more characters than will fit into a single byte, and to provide character set recoding between client and server. The number of supported character sets is fixed at the time the server is compiled, and internal operations such as string comparisons require expansion of each character into a 32-bit word.
- Single byte character recoding provides a more light-weight solution for users of multiple, yet single-byte character sets.

7.1. Locale Support

Locale support refers to an application respecting cultural preferences regarding alphabets, sorting, number formatting, etc. PostgreSQL uses the standard ISO C and POSIX-like locale facilities provided by the server operating system. For additional information refer to the documentation of your system.

7.1.1. Overview

Locale support is automatically initialized when a database cluster is created using `initdb`. `initdb` will initialize the database cluster with the locale setting of its execution environment; so if your system is already set to use the locale that you want in your database cluster then there is nothing else you need to do. If you want to use a different locale (or you are not sure which locale your system is set to), you can tell `initdb` exactly which locale you want with the option `--locale`. For example:

```
$ initdb --locale=sv_SE
```

This example sets the locale to Swedish (`sv`) as spoken in Sweden (`SE`). Other possibilities might be `en_US` (U.S. English) and `fr_CA` (Canada, French). If more than one character set can be useful for a locale then the specifications look like this: `cs_CZ.ISO8859-2`. What locales are available under what names on your system depends on what was provided by the operating system vendor and what was installed.

Occasionally it is useful to mix rules from several locales, e.g., use U.S. collation rules but Spanish messages. To support that, a set of locale subcategories exist that control only a certain aspect of the localization rules.

`LC_COLLATE`	String sort order
`LC_CTYPE`	Character classification (What is a letter? The upper-case equivalent?)
`LC_MESSAGES`	Language of messages
`LC_MONETARY`	Formatting of currency amounts
`LC_NUMERIC`	Formatting of numbers
`LC_TIME`	Formatting of dates and times

The category names translate into names of `initdb` options to override the locale choice for a specific category. For instance, to set the locale to French Canadian, but use U.S. rules for formatting currency, use `initdb --locale=fr_CA --lc-monetary=en_US`.

If you want the system to behave as if it had no locale support, use the special locale `C` or `POSIX`.

The nature of some locale categories is that their value has to be fixed for the lifetime of a database cluster. That is, once `initdb` has run, you cannot change them anymore. `LC_COLLATE` and `LC_CTYPE` are those categories. They affect the sort order of indexes, so they must be kept fixed, or indexes on text columns will become corrupt. PostgreSQL enforces this by recording the values of `LC_COLLATE` and `LC_CTYPE` that are seen by `initdb`. The server automatically adopts those two values when it is started.

The other locale categories can be changed as desired whenever the server is started by setting the run-time configuration variables that have the same name as the locale categories (see Section 3.4, "Run-time Configuration" for details). The defaults that are chosen by `initdb` are actually only written into the configuration file `postgresql.conf` to serve as defaults when the server is started. If you delete the assignments from `postgresql.conf` then the server will inherit the settings from the execution environment.

Note that the locale behavior of the server is determined by the environment variables seen by the server, not by the environment of any client. Therefore, be careful to configure the correct locale settings before starting the server. A consequence of this is that if client and server are set up to different locales, messages may appear in different languages depending on where they originated.

Note

When we speak of inheriting the locale from the execution environment, this means the following on most operating systems: For a given locale category, say the collation, the following environment variables are consulted in this order until one is found to be set: `LC_ALL`, `LC_COLLATE` (the variable corresponding to the respective category), `LANG`. If none of these environment variables are set then the locale defaults to `C`.

Some message localization libraries also look at the environment variable `LANGUAGE` which overrides all other locale settings for the purpose of setting the language of messages. If in doubt, please refer to the documentation of your operating system, in particular the gettext manual page, for more information.

To enable messages translated to the user's preferred language, the `--enable-nls` option must be used. This option is independent of the other locale support.

7.1.2. Benefits

Locale support influences in particular the following features:

- Sort order in `ORDER BY` queries.
- The `to_char` family of functions
- The `LIKE` and ~ operators for pattern matching

The only severe drawback of using the locale support in PostgreSQL is its speed. So use locale only if you actually need it. It should be noted in particular that selecting a non-C locale disables index optimizations for `LIKE` and ~ operators, which can make a huge difference in the speed of searches that use those operators.

7.1.3. Problems

If locale support doesn't work in spite of the explanation above, check that the locale support in your operating system is correctly configured. To check whether a given locale is installed and functional you can use Perl, for example. Perl has also support for locales and if a locale is broken `perl -v` will complain something like this:

```
$ export LC_CTYPE='not_exist'
$ perl -v
perl: warning: Setting locale failed.
```

```
perl: warning: Please check that your locale settings:
LC_ALL = (unset),
LC_CTYPE = "not_exist",
LANG = (unset)
are supported and installed on your system.
perl: warning: Falling back to the standard locale ("C").
```

Check that your locale files are in the right location. Possible locations include: `/usr/lib/locale` (Linux, Solaris), `/usr/share/locale` (Linux), `/usr/lib/nls/loc` (DUX 4.0). Check the locale man page of your system if you are not sure.

Check that PostgreSQL is actually using the locale that you think it is. `LC_COLLATE` and `LC_CTYPE` settings are determined at initdb time and cannot be changed without repeating initdb. Other locale settings including `LC_MESSAGES` and `LC_MONETARY` are determined by the environment the postmaster is started in, and can be changed with a simple postmaster restart. You can check the `LC_COLLATE` and `LC_CTYPE` settings of a database with the `contrib/pg_controldata` utility program.

The directory `src/test/locale` contains a test suite for PostgreSQL's locale support.

Client applications that handle server-side errors by parsing the text of the error message will obviously have problems when the server's messages are in a different language. If you create such an application you need to devise a plan to cope with this situation. The embedded SQL interface (ecpg) is also affected by this problem. It is currently recommended that servers interfacing with ecpg applications be configured to send messages in English.

Maintaining catalogs of message translations requires the on-going efforts of many volunteers that want to see PostgreSQL speak their preferred language well. If messages in your language is currently not available or fully translated, your assistance would be appreciated. If you want to help, refer to the *Developer's Guide* or write to the developers' mailing list.

7.2. Multibyte Support

Author

Tatsuo Ishii (<ishii@postgresql.org>), last updated 2002-07-24. Check Tatsuo's web site[1] for more information.

Multibyte (MB) support is intended to allow PostgreSQL to handle multiple-byte character sets such as EUC (Extended Unix Code), Unicode, and Mule internal code. With MB enabled you can use multibyte character sets in regular expressions (regexp), LIKE, and some other functions. The default encoding system is selected while initializing your PostgreSQL installation using initdb. Note that this can be overridden when you create a database using createdb or by using the SQL command `CREATE DATABASE`. So you can have multiple databases each with a different encoding system. Note that MB can handle single byte characters sets such as ISO-8859-1.

Multibyte support is enabled by default since PostgreSQL version 7.3.

7.2.1. Supported character set encodings

Following encoding can be used as database encoding.

Table 7.1. Character Set Encodings

Encoding	Description
`SQL_ASCII`	ASCII
`EUC_JP`	Japanese EUC

[1] http://www.sra.co.jp/people/t-ishii/PostgreSQL/

Encoding	Description
EUC_CN	Chinese EUC
EUC_KR	Korean EUC
JOHAB	Korean EUC (Hangle base)
EUC_TW	Taiwan EUC
UNICODE	Unicode (UTF-8)
MULE_INTERNAL	Mule internal code
LATIN1	ISO 8859-1 ECMA-94 Latin Alphabet No.1
LATIN2	ISO 8859-2 ECMA-94 Latin Alphabet No.2
LATIN3	ISO 8859-3 ECMA-94 Latin Alphabet No.3
LATIN4	ISO 8859-4 ECMA-94 Latin Alphabet No.4
LATIN5	ISO 8859-9 ECMA-128 Latin Alphabet No.5
LATIN6	ISO 8859-10 ECMA-144 Latin Alphabet No.6
LATIN7	ISO 8859-13 Latin Alphabet No.7
LATIN8	ISO 8859-14 Latin Alphabet No.8
LATIN9	ISO 8859-15 Latin Alphabet No.9
LATIN10	ISO 8859-16 ASRO SR 14111 Latin Alphabet No.10
ISO-8859-5	ECMA-113 Latin/Cyrillic
ISO-8859-6	ECMA-114 Latin/Arabic
ISO-8859-7	ECMA-118 Latin/Greek
ISO-8859-8	ECMA-121 Latin/Hebrew
KOI8	KOI8-R(U)
WIN	Windows CP1251
ALT	Windows CP866
WIN1256	Arabic Windows CP1256
TCVN	Vietnamese TCVN-5712 (Windows CP1258)
WIN874	Thai Windows CP874

Important

Before PostgreSQL7.2, LATIN5 mistakenly meant ISO 8859-5. From 7.2 on, LATIN5 means ISO 8859-9. If you have a LATIN5 database created on 7.1 or earlier and want to migrate to 7.2 (or later), you should be very careful about this change.

Important

Not all APIs supports all the encodings listed above. For example, the PostgreSQL JDBC driver does not support MULE_INTERNAL, LATIN6, LATIN8, and LATIN10.

7.2.2. Setting the Encoding

initdb defines the default encoding for a PostgreSQL installation. For example:

```
$ initdb -E EUC_JP
```

sets the default encoding to EUC_JP (Extended Unix Code for Japanese). Note that you can use --encoding instead of -E if you prefer to type longer option strings. If no -E or --encoding option is given, SQL_ASCII is used.

You can create a database with a different encoding:

```
$ createdb -E EUC_KR korean
```

will create a database named korean with EUC_KR encoding. Another way to accomplish this is to use a SQL command:

```
CREATE DATABASE korean WITH ENCODING = 'EUC_KR';
```

The encoding for a database is represented as an *encoding column* in the pg_database system catalog. You can see that by using the -l option or the \l command of psql.

```
$ psql -l
            List of databases
   Database    |  Owner  |   Encoding
---------------+---------+---------------
 euc_cn        | t-ishii | EUC_CN
 euc_jp        | t-ishii | EUC_JP
 euc_kr        | t-ishii | EUC_KR
 euc_tw        | t-ishii | EUC_TW
 mule_internal | t-ishii | MULE_INTERNAL
 regression    | t-ishii | SQL_ASCII
 template1     | t-ishii | EUC_JP
 test          | t-ishii | EUC_JP
 unicode       | t-ishii | UNICODE
(9 rows)
```

7.2.3. Automatic encoding conversion between server and client

PostgreSQL supports an automatic encoding conversion between server and client for some encodings. The conversion info is stored in pg_conversion system catalog. You can create a new conversion by using CREATE CONVERSION. PostgreSQL comes with some predefined conversions. They are listed in Table 7.2, “Communication Encodings”.

Table 7.2. Client/Server Character Set Encodings

Server Encoding	Available Client Encodings
SQL_ASCII	SQL_ASCII, UNICODE, MULE_INTERNAL
EUC_JP	EUC_JP, SJIS, UNICODE, MULE_INTERNAL
EUC_CN	EUC_CN, UNICODE, MULE_INTERNAL
EUC_KR	EUC_KR, UNICODE, MULE_INTERNAL
JOHAB	JOHAB, UNICODE
EUC_TW	EUC_TW, BIG5, UNICODE, MULE_INTERNAL
LATIN1	LATIN1, UNICODE MULE_INTERNAL
LATIN2	LATIN2, WIN1250, UNICODE, MULE_INTERNAL
LATIN3	LATIN3, UNICODE, MULE_INTERNAL
LATIN4	LATIN4, UNICODE, MULE_INTERNAL
LATIN5	LATIN5, UNICODE
LATIN6	LATIN6, UNICODE, MULE_INTERNAL
LATIN7	LATIN7, UNICODE, MULE_INTERNAL
LATIN8	LATIN8, UNICODE, MULE_INTERNAL

Server Encoding	Available Client Encodings
LATIN9	LATIN9, UNICODE, MULE_INTERNAL
LATIN10	LATIN10, UNICODE, MULE_INTERNAL
ISO_8859_5	ISO_8859_5, UNICODE, MULE_INTERNAL, WIN, ALT, KOI8
ISO_8859_6	ISO_8859_6, UNICODE
ISO_8859_7	ISO_8859_7, UNICODE
ISO_8859_8	ISO_8859_8, UNICODE
UNICODE	EUC_JP, SJIS, EUC_KR, UHC, JOHAB, EUC_CN, GBK, EUC_TW, BIG5, LATIN1 to LATIN10, ISO_8859_5, ISO_8859_6, ISO_8859_7, ISO_8859_8, WIN, ALT, KOI8, WIN1256, TCVN, WIN874, GB18030, WIN1250
MULE_INTERNAL	EUC_JP, SJIS, EUC_KR, EUC_CN, EUC_TW, BIG5, LATIN1 to LATIN5, WIN, ALT, WIN1250, BIG5, ISO_8859_5, KOI8
KOI8	ISO_8859_5, WIN, ALT, KOI8, UNICODE, MULE_INTERNAL
WIN	ISO_8859_5, WIN, ALT, KOI8, UNICODE, MULE_INTERNAL
ALT	ISO_8859_5, WIN, ALT, KOI8, UNICODE, MULE_INTERNAL
WIN1256	WIN1256, UNICODE
TCVN	TCVN, UNICODE
WIN874	WIN874, UNICODE

To enable the automatic encoding translation, you have to tell PostgreSQL the encoding you would like to use in the client. There are several ways to accomplish this.

- Using the `\encoding` command in psql. `\encoding` allows you to change client encoding on the fly. For example, to change the encoding to `SJIS`, type:

  ```
  \encoding SJIS
  ```

- Using libpq functions. `\encoding` actually calls `PQsetClientEncoding()` for its purpose.

  ```
  int PQsetClientEncoding(PGconn *conn, const char *encoding)
  ```

  where *`conn`* is a connection to the server, and *`encoding`* is an encoding you want to use. If it successfully sets the encoding, it returns 0, otherwise -1. The current encoding for this connection can be shown by using:

  ```
  int PQclientEncoding(const PGconn *conn)
  ```

  Note that it returns the encoding ID, not a symbolic string such as `EUC_JP`. To convert an encoding ID to an encoding name, you can use:

  ```
  char *pg_encoding_to_char(int encoding_id)
  ```

- Using `SET CLIENT_ENCODING TO`. Setting the client encoding can be done with this SQL command:

  ```
  SET CLIENT_ENCODING TO 'encoding';
  ```

Also you can use the SQL92 syntax `SET NAMES` for this purpose:

```
SET NAMES 'encoding';
```

To query the current client encoding:

```
SHOW CLIENT_ENCODING;
```

To return to the default encoding:

```
RESET CLIENT_ENCODING;
```

- Using `PGCLIENTENCODING`. If environment variable `PGCLIENTENCODING` is defined in the client's environment, that client encoding is automatically selected when a connection to the server is made. (This can subsequently be overridden using any of the other methods mentioned above.)
- Using client_encoding variable. If the `client_encoding` variable in `postgresql.conf` is set, that client encoding is automatically selected when a connection to the server is made. (This can subsequently be overridden using any of the other methods mentioned above.)

7.2.4. What happens if the translation is not possible?

Suppose you choose `EUC_JP` for the server and `LATIN1` for the client, then some Japanese characters cannot be translated into `LATIN1`. In this case, a letter that cannot be represented in the `LATIN1` character set would be transformed as:

```
(HEXA DECIMAL)
```

7.2.5. References

These are good sources to start learning about various kinds of encoding systems.

ftp://ftp.ora.com/pub/examples/nutshell/ujip/doc/cjk.inf

Detailed explanations of `EUC_JP`, `EUC_CN`, `EUC_KR`, `EUC_TW` appear in section 3.2.

http://www.unicode.org/

The web site of the Unicode Consortium

RFC 2044

UTF-8 is defined here.

7.2.6. History

```
Dec 7, 2000
 * An automatic encoding translation between Unicode and other
   encodings are implemented
 * Changes above will appear in 7.1

May 20, 2000
 * SJIS UDC (NEC selection IBM kanji) support contributed
   by Eiji Tokuya
 * Changes above will appear in 7.0.1

Mar 22, 2000
 * Add new libpq functions PQsetClientEncoding, PQclientEncoding
 * ./configure --with-mb=EUC_JP
   now deprecated. use
```

```
   ./configure --enable-multibyte=EUC_JP
   instead
   * Add SQL_ASCII regression test case
 * Add SJIS User Defined Character (UDC) support
 * All of above will appear in 7.0

July 11, 1999
 * Add support for WIN1250 (Windows Czech) as a client encoding
   (contributed by Pavel Behal)
 * fix some compiler warnings (contributed by Tomoaki Nishiyama)

Mar 23, 1999
 * Add support for KOI8(KOI8-R), WIN(CP1251), ALT(CP866)
   (thanks Oleg Broytmann for testing)
 * Fix problem with MB and locale

Jan 26, 1999
 * Add support for Big5 for frontend encoding
   (you need to create a database with EUC_TW to use Big5)
 * Add regression test case for EUC_TW
   (contributed by Jonah Kuo <jonahkuo@mail.ttn.com.tw>)

Dec 15, 1998
 * Bugs related to SQL_ASCII support fixed

Nov 5, 1998
 * 6.4 release. In this version, pg_database has "encoding"
   column that represents the database encoding

Jul 22, 1998
 * determine encoding at initdb/createdb rather than compile time
 * support for PGCLIENTENCODING when issuing COPY command
 * support for SQL92 syntax "SET NAMES"
 * support for LATIN2-5
 * add UNICODE regression test case
 * new test suite for MB
 * clean up source files

Jun 5, 1998
 * add support for the encoding translation between the backend
   and the frontend
 * new command SET CLIENT_ENCODING etc. added
 * add support for LATIN1 character set
 * enhance 8-bit cleanliness

April 21, 1998 some enhancements/fixes
 * character_length(), position(), substring() are now aware of
   multi-byte characters
 * add octet_length()
 * add --with-mb option to configure
 * new regression tests for EUC_KR
     (contributed by Soonmyung Hong)
 * add some test cases to the EUC_JP regression test
 * fix problem in regress/regress.sh in case of System V
 * fix toupper(), tolower() to handle 8bit chars

Mar 25, 1998 MB PL2 is incorporated into PostgreSQL 6.3.1
```

```
Mar 10, 1998 PL2 released
 * add regression test for EUC_JP, EUC_CN and MULE_INTERNAL
 * add an English document (this file)
 * fix problems concerning 8-bit single byte characters

Mar 1, 1998 PL1 released
```

7.2.7. WIN1250 on Windows/ODBC

The WIN1250 character set on Windows client platforms can be used with PostgreSQL with locale support enabled.

The following should be kept in mind:

- Success depends on proper system locales. This has been tested with Red Hat 6.0 and Slackware 3.6, with the `cs_CZ.iso8859-2` locale.
- Never try to set the server's database encoding to WIN1250. Always use LATIN2 instead since there is no WIN1250 locale in Unix.
- The WIN1250 encoding is usable only for Windows ODBC clients. The characters are recoded on the fly, to be displayed and stored back properly.

WIN1250 on Windows/ODBC

1. Compile PostgreSQL with locale enabled and the server-side encoding set to `LATIN2`.
2. Set up your installation. Do not forget to create locale variables in your environment. For example (this may not be correct for *your* environment):

   ```
   LC_ALL=cs_CZ.ISO8859-2
   ```

3. You have to start the server with locales set!
4. Try it with the Czech language, and have it sort on a query.
5. Install ODBC driver for PostgreSQL on your Windows machine.
6. Set up your data source properly. Include this line in your ODBC configuration dialog in the field Connect Settings:

   ```
   SET CLIENT_ENCODING = 'WIN1250';
   ```

7. Now try it again, but in Windows with ODBC.

7.3. Single-byte character set recoding

You can set up this feature with the `--enable-recode` option to `configure`. This option was formerly described as “Cyrillic recode support” which doesn't express all its power. It can be used for *any* single-byte character set recoding.

This method uses a file `charset.conf` file located in the database directory (`PGDATA`). It's a typical configuration text file where spaces and newlines separate items and records and # specifies comments. Three keywords with the following syntax are recognized here:

```
BaseCharset      server_charset
RecodeTable      from_charset to_charset file_name
HostCharset      host_spec    host_charset
```

`BaseCharset` defines the encoding of the database server. All character set names are only used for mapping inside of `charset.conf` so you can freely use typing-friendly names.

`RecodeTable` records specify translation tables between server and client. The file name is relative to the `PGDATA` directory. The table file format is very simple. There are no keywords and characters are represented by a pair of decimal or hexadecimal (0x prefixed) values on single lines:

`char_value  translated_char_value`

`HostCharset` records define the client character set by IP address. You can use a single IP address, an IP mask range starting from the given address or an IP interval (e.g., 127.0.0.1, 192.168.1.100/24, 192.168.1.20-192.168.1.40).

The `charset.conf` file is always processed up to the end, so you can easily specify exceptions from the previous rules. In the `src/data/` directory you will find an example `charset.conf` and a few recoding tables.

As this solution is based on the client's IP address and character set mapping there are obviously some restrictions as well. You cannot use different encodings on the same host at the same time. It is also inconvenient when you boot your client hosts into multiple operating systems. Nevertheless, when these restrictions are not limiting and you do not need multibyte characters then it is a simple and effective solution.

Chapter 8. Routine Database Maintenance Tasks

8.1. General Discussion

There are a few routine maintenance chores that must be performed on a regular basis to keep a PostgreSQL installation running smoothly. The tasks discussed here are repetitive in nature and can easily be automated using standard Unix tools such as cron scripts. But it is the database administrator's responsibility to set up appropriate scripts, and to check that they execute successfully.

One obvious maintenance task is creation of backup copies of the data on a regular schedule. Without a recent backup, you have no chance of recovery after a catastrophe (disk failure, fire, mistakenly dropping a critical table, etc). The backup and recovery mechanisms available in PostgreSQL are discussed at length in Chapter 9, *Backup and Restore*.

The other main category of maintenance task is periodic “vacuuming” of the database. This activity is discussed in Section 8.2, “Routine Vacuuming”.

Something else that might need periodic attention is log file management. This is discussed in Section 8.4, “Log File Maintenance”.

PostgreSQL is low-maintenance compared to some other database products. Nonetheless, appropriate attention to these tasks will go far towards ensuring a pleasant and productive experience with the system.

8.2. Routine Vacuuming

PostgreSQL's `VACUUM` command must be run on a regular basis for several reasons:

1. To recover disk space occupied by updated or deleted rows.

2. To update data statistics used by the PostgreSQL query planner.

3. To protect against loss of very old data due to *transaction ID wraparound*.

The frequency and scope of `VACUUM`s performed for each of these reasons will vary depending on the needs of each installation. Therefore, database administrators must understand these issues and develop an appropriate maintenance strategy. This section concentrates on explaining the high-level issues; for details about command syntax and so on, see the `VACUUM` command reference page.

Beginning in PostgreSQL 7.2, the standard form of `VACUUM` can run in parallel with normal database operations (selects, inserts, updates, deletes, but not changes to table schemas). Routine vacuuming is therefore not nearly as intrusive as it was in prior releases, and it's not as critical to try to schedule it at low-usage times of day.

8.2.1. Recovering disk space

In normal PostgreSQL operation, an `UPDATE` or `DELETE` of a row does not immediately remove the old *tuple* (version of the row). This approach is necessary to gain the benefits of multiversion concurrency control (see the PostgreSQL 7.3.21 User's Guide): the tuple must not be deleted while it is still potentially visible to other transactions. But eventually, an outdated or deleted tuple is no longer of interest to any transaction. The space it occupies must be reclaimed for reuse by new tuples, to avoid infinite growth of disk space requirements. This is done by running `VACUUM`.

Clearly, a table that receives frequent updates or deletes will need to be vacuumed more often than tables that are seldom updated. It may be useful to set up periodic cron tasks that vacuum only selected

tables, skipping tables that are known not to change often. This is only likely to be helpful if you have both large heavily-updated tables and large seldom-updated tables --- the extra cost of vacuuming a small table isn't enough to be worth worrying about.

The standard form of VACUUM is best used with the goal of maintaining a fairly level steady-state usage of disk space. The standard form finds old tuples and makes their space available for re-use within the table, but it does not try very hard to shorten the table file and return disk space to the operating system. If you need to return disk space to the operating system you can use VACUUM FULL --- but what's the point of releasing disk space that will only have to be allocated again soon? Moderately frequent standard VACUUMs are a better approach than infrequent VACUUM FULLs for maintaining heavily-updated tables.

Recommended practice for most sites is to schedule a database-wide VACUUM once a day at a low-usage time of day, supplemented by more frequent vacuuming of heavily-updated tables if necessary. (If you have multiple databases in an installation, don't forget to vacuum each one; the vacuumdb script may be helpful.) Use plain VACUUM, not VACUUM FULL, for routine vacuuming for space recovery.

VACUUM FULL is recommended for cases where you know you have deleted the majority of tuples in a table, so that the steady-state size of the table can be shrunk substantially with VACUUM FULL's more aggressive approach.

If you have a table whose contents are deleted completely every so often, consider doing it with TRUNCATE rather than using DELETE followed by VACUUM.

8.2.2. Updating planner statistics

The PostgreSQL query planner relies on statistical information about the contents of tables in order to generate good plans for queries. These statistics are gathered by the ANALYZE command, which can be invoked by itself or as an optional step in VACUUM. It is important to have reasonably accurate statistics, otherwise poor choices of plans may degrade database performance.

As with vacuuming for space recovery, frequent updates of statistics are more useful for heavily-updated tables than for seldom-updated ones. But even for a heavily-updated table, there may be no need for statistics updates if the statistical distribution of the data is not changing much. A simple rule of thumb is to think about how much the minimum and maximum values of the columns in the table change. For example, a timestamp column that contains the time of row update will have a constantly-increasing maximum value as rows are added and updated; such a column will probably need more frequent statistics updates than, say, a column containing URLs for pages accessed on a website. The URL column may receive changes just as often, but the statistical distribution of its values probably changes relatively slowly.

It is possible to run ANALYZE on specific tables and even just specific columns of a table, so the flexibility exists to update some statistics more frequently than others if your application requires it. In practice, however, the usefulness of this feature is doubtful. Beginning in PostgreSQL 7.2, ANALYZE is a fairly fast operation even on large tables, because it uses a statistical random sampling of the rows of a table rather than reading every single row. So it's probably much simpler to just run it over the whole database every so often.

Tip

Although per-column tweaking of ANALYZE frequency may not be very productive, you may well find it worthwhile to do per-column adjustment of the level of detail of the statistics collected by ANALYZE. Columns that are heavily used in WHERE clauses and have highly irregular data distributions may require a finer-grain data histogram than other columns. See ALTER TABLE SET STATISTICS.

Recommended practice for most sites is to schedule a database-wide ANALYZE once a day at a low-usage time of day; this can usefully be combined with a nightly VACUUM. However, sites with relatively

slowly changing table statistics may find that this is overkill, and that less-frequent ANALYZE runs are sufficient.

8.2.3. Preventing transaction ID wraparound failures

PostgreSQL's MVCC transaction semantics depend on being able to compare transaction ID (*XID*) numbers: a tuple with an insertion XID newer than the current transaction's XID is "in the future" and should not be visible to the current transaction. But since transaction IDs have limited size (32 bits at this writing) an installation that runs for a long time (more than 4 billion transactions) will suffer *transaction ID wraparound*: the XID counter wraps around to zero, and all of a sudden transactions that were in the past appear to be in the future --- which means their outputs become invisible. In short, catastrophic data loss. (Actually the data is still there, but that's cold comfort if you can't get at it.)

Prior to PostgreSQL 7.2, the only defense against XID wraparound was to re-initdb at least every 4 billion transactions. This of course was not very satisfactory for high-traffic sites, so a better solution has been devised. The new approach allows an installation to remain up indefinitely, without initdb or any sort of restart. The price is this maintenance requirement: *every table in the database must be vacuumed at least once every billion transactions*.

In practice this isn't an onerous requirement, but since the consequences of failing to meet it can be complete data loss (not just wasted disk space or slow performance), some special provisions have been made to help database administrators keep track of the time since the last VACUUM. The remainder of this section gives the details.

The new approach to XID comparison distinguishes two special XIDs, numbers 1 and 2 (BootstrapXID and FrozenXID). These two XIDs are always considered older than every normal XID. Normal XIDs (those greater than 2) are compared using modulo-2^{31} arithmetic. This means that for every normal XID, there are two billion XIDs that are "older" and two billion that are "newer"; another way to say it is that the normal XID space is circular with no endpoint. Therefore, once a tuple has been created with a particular normal XID, the tuple will appear to be "in the past" for the next two billion transactions, no matter which normal XID we are talking about. If the tuple still exists after more than two billion transactions, it will suddenly appear to be in the future. To prevent data loss, old tuples must be reassigned the XID FrozenXID sometime before they reach the two-billion-transactions-old mark. Once they are assigned this special XID, they will appear to be "in the past" to all normal transactions regardless of wraparound issues, and so such tuples will be good until deleted, no matter how long that is. This reassignment of XID is handled by VACUUM.

VACUUM's normal policy is to reassign FrozenXID to any tuple with a normal XID more than one billion transactions in the past. This policy preserves the original insertion XID until it is not likely to be of interest anymore (in fact, most tuples will probably live and die without ever being "frozen"). With this policy, the maximum safe interval between VACUUMs of any table is exactly one billion transactions: if you wait longer, it's possible that a tuple that was not quite old enough to be reassigned last time is now more than two billion transactions old and has wrapped around into the future --- i.e., is lost to you. (Of course, it'll reappear after another two billion transactions, but that's no help.)

Since periodic VACUUMs are needed anyway for the reasons described earlier, it's unlikely that any table would not be vacuumed for as long as a billion transactions. But to help administrators ensure this constraint is met, VACUUM stores transaction ID statistics in the system table pg_database. In particular, the datfrozenxid field of a database's pg_database row is updated at the completion of any database-wide vacuum operation (i.e., VACUUM that does not name a specific table). The value stored in this field is the freeze cutoff XID that was used by that VACUUM command. All normal XIDs older than this cutoff XID are guaranteed to have been replaced by FrozenXID within that database. A convenient way to examine this information is to execute the query

```
SELECT datname, age(datfrozenxid) FROM pg_database;
```

The age column measures the number of transactions from the cutoff XID to the current transaction's XID.

With the standard freezing policy, the age column will start at one billion for a freshly-vacuumed database. When the age approaches two billion, the database must be vacuumed again to avoid risk of wraparound failures. Recommended practice is to vacuum each database at least once every half-a-billion (500 million) transactions, so as to provide plenty of safety margin. To help meet this rule, each database-wide VACUUM automatically delivers a warning if there are any pg_database entries showing an age of more than 1.5 billion transactions, for example:

```
play=# vacuum;
WARNING:  Some databases have not been vacuumed in 1613770184
 transactions.
        Better vacuum them within 533713463 transactions,
        or you may have a wraparound failure.
VACUUM
```

VACUUM with the FREEZE option uses a more aggressive freezing policy: tuples are frozen if they are old enough to be considered good by all open transactions. In particular, if a VACUUM FREEZE is performed in an otherwise-idle database, it is guaranteed that *all* tuples in that database will be frozen. Hence, as long as the database is not modified in any way, it will not need subsequent vacuuming to avoid transaction ID wraparound problems. This technique is used by initdb to prepare the template0 database. It should also be used to prepare any user-created databases that are to be marked datallowconn = false in pg_database, since there isn't any convenient way to vacuum a database that you can't connect to. Note that VACUUM's automatic warning message about unvacuumed databases will ignore pg_database entries with datallowconn = false, so as to avoid giving false warnings about these databases; therefore it's up to you to ensure that such databases are frozen correctly.

8.3. Routine Reindexing

PostgreSQL is unable to reuse B-tree index pages in certain cases. The problem is that if indexed rows are deleted, those index pages can only be reused by rows with similar values. For example, if indexed rows are deleted and newly inserted/updated rows have much higher values, the new rows can't use the index space made available by the deleted rows. Instead, such new rows must be placed on new index pages. In such cases, disk space used by the index will grow indefinitely, even if VACUUM is run frequently.

As a solution, you can use the REINDEX command periodically to discard pages used by deleted rows. There is also contrib/reindexdb which can reindex an entire database.

8.4. Log File Maintenance

It's a good idea to save the database server's log output somewhere, rather than just routing it to /dev/null. The log output is invaluable when it comes time to diagnose problems. However, the log output tends to be voluminous (especially at higher debug levels) and you won't want to save it indefinitely. You need to “rotate” the log files so that new log files are started and old ones thrown away every so often.

If you simply direct the postmaster's stderr into a file, the only way to truncate the log file is to stop and restart the postmaster. This may be OK for development setups but you won't want to run a production server that way.

The simplest production-grade approach to managing log output is to send it all to syslog and let syslog deal with file rotation. To do this, set syslog to 2 (log to syslog only) in postgresql.conf. Then you can send a SIGHUP signal to the syslog daemon whenever you want to force it to start writing a new log file.

On many systems, however, syslog is not very reliable, particularly with large log messages; it may truncate or drop messages just when you need them the most. You may find it more useful to pipe the

postmaster's stderr to some type of log rotation script. If you start the postmaster with pg_ctl, then the postmaster's stderr is already redirected to stdout, so you just need a pipe command:

```
pg_ctl start | logrotate
```

The PostgreSQL distribution doesn't include a suitable log rotation program, but there are many available on the net; one is included in the Apache distribution, for example.

Chapter 9. Backup and Restore

As everything that contains valuable data, PostgreSQL databases should be backed up regularly. While the procedure is essentially simple, it is important to have a basic understanding of the underlying techniques and assumptions.

There are two fundamentally different approaches to backing up PostgreSQL data:

- SQL dump
- File system level backup

9.1. SQL Dump

The idea behind the SQL-dump method is to generate a text file with SQL commands that, when fed back to the server, will recreate the database in the same state as it was at the time of the dump. PostgreSQL provides the utility program pg_dump for this purpose. The basic usage of this command is:

```
pg_dump dbname > outfile
```

As you see, pg_dump writes its results to the standard output. We will see below how this can be useful.

pg_dump is a regular PostgreSQL client application (albeit a particularly clever one). This means that you can do this backup procedure from any remote host that has access to the database. But remember that pg_dump does not operate with special permissions. In particular, you must have read access to all tables that you want to back up, so in practice you almost always have to be a database superuser.

To specify which database server pg_dump should contact, use the command line options `-h host` and `-p port`. The default host is the local host or whatever your `PGHOST` environment variable specifies. Similarly, the default port is indicated by the `PGPORT` environment variable or, failing that, by the compiled-in default. (Conveniently, the server will normally have the same compiled-in default.)

As any other PostgreSQL client application, pg_dump will by default connect with the database user name that is equal to the current operating system user name. To override this, either specify the `-U` option or set the environment variable `PGUSER`. Remember that pg_dump connections are subject to the normal client authentication mechanisms (which are described in Chapter 6, *Client Authentication*).

Dumps created by pg_dump are internally consistent, that is, updates to the database while pg_dump is running will not be in the dump. pg_dump does not block other operations on the database while it is working. (Exceptions are those operations that need to operate with an exclusive lock, such as `VACUUM FULL`.)

Important

When your database schema relies on OIDs (for instance as foreign keys) you must instruct pg_dump to dump the OIDs as well. To do this, use the `-o` command line option. “Large objects” are not dumped by default, either. See pg_dump's command reference page if you use large objects.

9.1.1. Restoring the dump

The text files created by pg_dump are intended to be read in by the psql program. The general command form to restore a dump is

```
psql dbname < infile
```

where *infile* is what you used as *outfile* for the pg_dump command. The database *dbname* will not be created by this command, you must create it yourself from template0 before executing psql (e.g., with createdb -T template0 *dbname*). psql supports similar options to pg_dump for controlling the database server location and the user names. See its reference page for more information.

If the objects in the original database were owned by different users, then the dump will instruct psql to connect as each affected user in turn and then create the relevant objects. This way the original ownership is preserved. This also means, however, that all these users must already exist, and furthermore that you must be allowed to connect as each of them. It might therefore be necessary to temporarily relax the client authentication settings.

The ability of pg_dump and psql to write to or read from pipes makes it possible to dump a database directly from one server to another, for example

```
pg_dump -h host1 dbname | psql -h host2 dbname
```

Important

The dumps produced by pg_dump are relative to template0. This means that any languages, procedures, etc. added to template1 will also be dumped by pg_dump. As a result, when restoring, if you are using a customized template1, you must create the empty database from template0, as in the example above.

9.1.2. Using pg_dumpall

The above mechanism is cumbersome and inappropriate when backing up an entire database cluster. For this reason the pg_dumpall program is provided. pg_dumpall backs up each database in a given cluster and also makes sure that the state of global data such as users and groups is preserved. The call sequence for pg_dumpall is simply

```
pg_dumpall > outfile
```

The resulting dumps can be restored with psql as described above. But in this case it is definitely necessary that you have database superuser access, as that is required to restore the user and group information.

9.1.3. Large Databases

Acknowledgement

Originally written by Hannu Krosing (<hannu@trust.ee>) on 1999-06-19

Since PostgreSQL allows tables larger than the maximum file size on your system, it can be problematic to dump the table to a file, since the resulting file will likely be larger than the maximum size allowed by your system. As pg_dump writes to the standard output, you can just use standard *nix tools to work around this possible problem.

Use compressed dumps. Use your favorite compression program, for example gzip.

```
pg_dump dbname | gzip > filename.gz
```

Reload with

```
createdb dbname
gunzip -c filename.gz | psql dbname
```

or

```
cat filename.gz | gunzip | psql dbname
```

Use split. This allows you to split the output into pieces that are acceptable in size to the underlying file system. For example, to make chunks of 1 megabyte:

```
pg_dump dbname | split -b 1m - filename
```

Reload with

```
createdb dbname
cat filename* | psql dbname
```

Use the custom dump format. If PostgreSQL was built on a system with the zlib compression library installed, the custom dump format will compress data as it writes it to the output file. For large databases, this will produce similar dump sizes to using `gzip`, but has the added advantage that the tables can be restored selectively. The following command dumps a database using the custom dump format:

```
pg_dump -Fc dbname > filename
```

See the pg_dump and pg_restore reference pages for details.

9.1.4. Caveats

pg_dump (and by implication pg_dumpall) has a few limitations which stem from the difficulty to reconstruct certain information from the system catalogs.

Specifically, the order in which pg_dump writes the objects is not very sophisticated. This can lead to problems for example when functions are used as column default values. The only answer is to manually reorder the dump. If you created circular dependencies in your schema then you will have more work to do.

For reasons of backward compatibility, pg_dump does not dump large objects by default. To dump large objects you must use either the custom or the TAR output format, and use the `-b` option in pg_dump. See the reference pages for details. The directory `contrib/pg_dumplo` of the PostgreSQL source tree also contains a program that can dump large objects.

Please familiarize yourself with the pg_dump reference page.

9.2. File system level backup

An alternative backup strategy is to directly copy the files that PostgreSQL uses to store the data in the database. In Section 3.2, “Creating a Database Cluster” it is explained where these files are located, but you have probably found them already if you are interested in this method. You can use whatever method you prefer for doing usual file system backups, for example

```
tar -cf backup.tar /usr/local/pgsql/data
```

There are two restrictions, however, which make this method impractical, or at least inferior to the pg_dump method:

1. The database server *must* be shut down in order to get a usable backup. Half-way measures such as disallowing all connections will not work as there is always some buffering going on. For this reason it is also not advisable to trust file systems that claim to support “consistent snapshots”. Information about stopping the server can be found in Section 3.6, “Shutting Down the Server”.

   Needless to say that you also need to shut down the server before restoring the data.

2. If you have dug into the details of the file system layout you may be tempted to try to back up or restore only certain individual tables or databases from their respective files or directories. This will *not* work because the information contained in these files contains only half the truth. The other half

is in the commit log files `pg_clog/*`, which contain the commit status of all transactions. A table file is only usable with this information. Of course it is also impossible to restore only a table and the associated `pg_clog` data because that will render all other tables in the database cluster useless.

Also note that the file system backup will not necessarily be smaller than an SQL dump. On the contrary, it will most likely be larger. (pg_dump does not need to dump the contents of indexes for example, just the commands to recreate them.)

9.3. Migration between releases

As a general rule, the internal data storage format is subject to change between releases of PostgreSQL. This does not apply to different "patch levels", these always have compatible storage formats. For example, releases 7.0.1, 7.1.2, and 7.2 are not compatible, whereas 7.1.1 and 7.1.2 are. When you update between compatible versions, then you can simply reuse the data area in disk by the new executables. Otherwise you need to "back up" your data and "restore" it on the new server, using pg_dump. (There are checks in place that prevent you from doing the wrong thing, so no harm can be done by confusing these things.) The precise installation procedure is not subject of this section, these details are in Chapter 1, *Installation Instructions*.

The least downtime can be achieved by installing the new server in a different directory and running both the old and the new servers in parallel, on different ports. Then you can use something like

```
pg_dumpall -p 5432 | psql -d template1 -p 6543
```

to transfer your data, or use an intermediate file if you want. Then you can shut down the old server and start the new server at the port the old one was running at. You should make sure that the database is not updated after you run pg_dumpall, otherwise you will obviously lose that data. See Chapter 6, *Client Authentication* for information on how to prohibit access. In practice you probably want to test your client applications on the new setup before switching over.

If you cannot or do not want to run two servers in parallel you can do the back up step before installing the new version, bring down the server, move the old version out of the way, install the new version, start the new server, restore the data. For example:

```
pg_dumpall > backup
pg_ctl stop
mv /usr/local/pgsql /usr/local/pgsql.old
cd /usr/src/postgresql-7.3.21
gmake install
initdb -D /usr/local/pgsql/data
postmaster -D /usr/local/pgsql/data
psql template1 < backup
```

See Chapter 3, *Server Run-time Environment* about ways to start and stop the server and other details. The installation instructions will advise you of strategic places to perform these steps.

Note

When you "move the old installation out of the way" it is no longer perfectly usable. Some parts of the installation contain information about where the other parts are located. This is usually not a big problem but if you plan on using two installations in parallel for a while you should assign them different installation directories at build time.

Chapter 10. Monitoring Database Activity

A database administrator frequently wonders, “What is the system doing right now?” This chapter discusses how to find that out.

Several tools are available for monitoring database activity and analyzing performance. Most of this chapter is devoted to describing PostgreSQL's *statistics collector*, but one should not neglect regular Unix monitoring programs such as `ps` and `top`. Also, once one has identified a poorly-performing query, further investigation may be needed using PostgreSQL's `EXPLAIN` command. The PostgreSQL 7.3.21 User's Guide discusses `EXPLAIN` and other methods for understanding the behavior of an individual query.

10.1. Standard Unix Tools

On most platforms, PostgreSQL modifies its command title as reported by `ps`, so that individual server processes can readily be identified. A sample display is

```
$ ps auxww | grep ^postgres
postgres   960  0.0  1.1  6104 1480 pts/1    SN   13:17   0:00
 postmaster -i
postgres   963  0.0  1.1  7084 1472 pts/1    SN   13:17   0:00
 postgres: stats buffer process
postgres   965  0.0  1.1  6152 1512 pts/1    SN   13:17   0:00
 postgres: stats collector process
postgres   998  0.0  2.3  6532 2992 pts/1    SN   13:18   0:00
 postgres: tgl runbug 127.0.0.1 idle
postgres  1003  0.0  2.4  6532 3128 pts/1    SN   13:19   0:00
 postgres: tgl regression [local] SELECT waiting
postgres  1016  0.1  2.4  6532 3080 pts/1    SN   13:19   0:00
 postgres: tgl regression [local] idle in transaction
```

(The appropriate invocation of `ps` varies across different platforms, as do the details of what is shown. This example is from a recent Linux system.) The first process listed here is the *postmaster*, the master server process. The command arguments shown for it are the same ones given when it was launched. The next two processes implement the statistics collector, which will be described in detail in the next section. (These will not be present if you have set the system not to start the statistics collector.) Each of the remaining processes is a server process handling one client connection. Each such process sets its command line display in the form

```
postgres: user database host activity
```

The user, database, and connection source host items remain the same for the life of the client connection, but the activity indicator changes. The activity may be `idle` (i.e., waiting for a client command), `idle in transaction` (waiting for client inside a `BEGIN` block), or a command type name such as `SELECT`. Also, `waiting` is attached if the server is presently waiting on a lock held by another server process. In the above example we can infer that process 1003 is waiting for process 1016 to complete its transaction and thereby release some lock or other.

Tip

Solaris requires special handling. You must use `/usr/ucb/ps`, rather than `/bin/ps`. You also must use two `w` flags, not just one. In addition, your original invocation of the postmaster must have a shorter `ps` status display than that provided by each backend. If you fail to do all three things, the `ps` output for each backend will be the original postmaster command line.

10.2. Statistics Collector

PostgreSQL's *statistics collector* is a subsystem that supports collection and reporting of information about server activity. Presently, the collector can count accesses to tables and indexes in both disk-block and individual-row terms. It also supports determining the exact query currently being executed by other server processes.

10.2.1. Statistics Collection Configuration

Since collection of statistics adds some overhead to query execution, the system can be configured to collect or not collect information. This is controlled by configuration variables that are normally set in `postgresql.conf` (see Section 3.4, “Run-time Configuration” for details about setting configuration variables).

The variable `STATS_START_COLLECTOR` must be set to `true` for the statistics collector to be launched at all. This is the default and recommended setting, but it may be turned off if you have no interest in statistics and want to squeeze out every last drop of overhead. (The savings is likely to be small, however.) Note that this option cannot be changed while the server is running.

The variables `STATS_COMMAND_STRING`, `STATS_BLOCK_LEVEL`, and `STATS_ROW_LEVEL` control how much information is actually sent to the collector, and thus determine how much run-time overhead occurs. These respectively determine whether a server process sends its current command string, disk-block-level access statistics, and row-level access statistics to the collector. Normally these variables are set in `postgresql.conf` so that they apply to all server processes, but it is possible to turn them on or off in individual server processes using the `SET` command. (To prevent ordinary users from hiding their activity from the administrator, only superusers are allowed to change these variables with `SET`.)

Important

Since the variables `STATS_COMMAND_STRING`, `STATS_BLOCK_LEVEL`, and `STATS_ROW_LEVEL` default to `false`, no statistics are actually collected in the default configuration. You must turn one or more of them on before you will get useful results from the statistical display functions.

10.2.2. Viewing Collected Statistics

Several predefined views are available to show the results of statistics collection, listed in Table 10.1, “Standard Statistics Views”. Alternatively, one can build custom views using the underlying statistics functions.

When using the statistics to monitor current activity, it is important to realize that the information does not update instantaneously. Each individual server process transmits new access counts to the collector just before waiting for another client command; so a query still in progress does not affect the displayed totals. Also, the collector itself emits new totals at most once per `pgstat_stat_interval` milliseconds (500 by default). So the displayed totals lag behind actual activity.

Another important point is that when a server process is asked to display any of these statistics, it first fetches the most recent totals emitted by the collector process. It then continues to use this snapshot for all statistical views and functions until the end of its current transaction. So the statistics will appear not to change as long as you continue the current transaction. This is a feature, not a bug, because it allows you to perform several queries on the statistics and correlate the results without worrying that the numbers are changing underneath you. But if you want to see new results with each query, be sure to do the queries outside any transaction block.

Table 10.1. Standard Statistics Views

View Name	Description
pg_stat_activity	One row per server process, showing process ID, database, user, and current query. The current query column is only available to superusers; for others it reads as null. (Note that because of the collector's reporting delay, current query will only be up-to-date for long-running queries.)
pg_stat_database	One row per database, showing number of active backends, total transactions committed and total rolled back in that database, total disk blocks read, and total number of buffer hits (i.e., block read requests avoided by finding the block already in buffer cache).
pg_stat_all_tables	For each table in the current database, total numbers of sequential and index scans, total numbers of tuples returned by each type of scan, and totals of tuple insertions, updates, and deletes.
pg_stat_sys_tables	Same as pg_stat_all_tables, except that only system tables are shown.
pg_stat_user_tables	Same as pg_stat_all_tables, except that only user tables are shown.
pg_stat_all_indexes	For each index in the current database, the total number of index scans that have used that index, the number of index tuples read, and the number of successfully fetched heap tuples. (This may be less when there are index entries pointing to expired heap tuples.)
pg_stat_sys_indexes	Same as pg_stat_all_indexes, except that only indexes on system tables are shown.
pg_stat_user_indexes	Same as pg_stat_all_indexes, except that only indexes on user tables are shown.
pg_statio_all_tables	For each table in the current database, the total number of disk blocks read from that table, the number of buffer hits, the numbers of disk blocks read and buffer hits in all the indexes of that table, the numbers of disk blocks read and buffer hits from the table's auxiliary TOAST table (if any), and the numbers of disk blocks read and buffer hits for the TOAST table's index.
pg_statio_sys_tables	Same as pg_statio_all_tables, except that only system tables are shown.
pg_statio_user_tables	Same as pg_statio_all_tables, except that only user tables are shown.
pg_statio_all_indexes	For each index in the current database, the numbers of disk blocks read and buffer hits in that index.
pg_statio_sys_indexes	Same as pg_statio_all_indexes, except that only indexes on system tables are shown.
pg_statio_user_indexes	Same as pg_statio_all_indexes, except that only indexes on user tables are shown.

View Name	Description
pg_statio_all_sequences	For each sequence object in the current database, the numbers of disk blocks read and buffer hits in that sequence.
pg_statio_sys_sequences	Same as pg_statio_all_sequences, except that only system sequences are shown. (Presently, no system sequences are defined, so this view is always empty.)
pg_statio_user_sequences	Same as pg_statio_all_sequences, except that only user sequences are shown.

The per-index statistics are particularly useful to determine which indexes are being used and how effective they are.

The pg_statio_ views are primarily useful to determine the effectiveness of the buffer cache. When the number of actual disk reads is much smaller than the number of buffer hits, then the cache is satisfying most read requests without invoking a kernel call.

Other ways of looking at the statistics can be set up by writing queries that use the same underlying statistics access functions as these standard views do. These functions are listed in Table 10.2, “Statistics Access Functions”. The per-database access functions accept a database OID to identify which database to report on. The per-table and per-index functions accept a table or index OID (note that only tables and indexes in the current database can be seen with these functions). The per-backend access functions accept a backend ID number, which ranges from one to the number of currently active backends.

Table 10.2. Statistics Access Functions

Function	Return Type	Description
pg_stat_get_db_numbackends(oid)	integer	Number of active backends in database
pg_stat_get_db_xact_commit(oid)	bigint	Transactions committed in database
pg_stat_get_db_xact_rollback(oid)	bigint	Transactions rolled back in database
pg_stat_get_db_blocks_fetched(oid)	bigint	Number of disk block fetch requests for database
pg_stat_get_db_blocks_hit(oid)	bigint	Number of disk block requests found in cache for database
pg_stat_get_numscans(oid)	bigint	Number of sequential scans done when argument is a table, or number of index scans done when argument is an index
pg_stat_get_tuples_returned(oid)	bigint	Number of tuples read by sequential scans when argument is a table, or number of index tuples read when argument is an index
pg_stat_get_tuples_fetched(oid)	bigint	Number of valid (unexpired) table tuples fetched by sequential scans when argument is a table, or fetched by index scans using this index when argument is an index

Function	Return Type	Description
pg_stat_get_tuples_inserted(oid)	bigint	Number of tuples inserted into table
pg_stat_get_tuples_updated(oid)	bigint	Number of tuples updated in table
pg_stat_get_tuples_deleted(oid)	bigint	Number of tuples deleted from table
pg_stat_get_blocks_fetched(oid)	bigint	Number of disk block fetch requests for table or index
pg_stat_get_blocks_hit(oid)	bigint	Number of disk block requests found in cache for table or index
pg_stat_get_backend_idset()	setof integer	Set of currently active backend IDs (from 1 to N where N is the number of active backends). See usage example below.
pg_backend_pid()	integer	Process ID of the attached backend
pg_stat_get_backend_pid(integer)	integer	Process ID of all backend processes
pg_stat_get_backend_dbid(integer)	oid	Database ID of backend process
pg_stat_get_backend_userid(integer)	oid	User ID of backend process
pg_stat_get_backend_activity(integer)	text	Current query of backend process (NULL if caller is not superuser)
pg_stat_reset()	boolean	Reset all currently collected statistics.

Note

Blocks_fetched minus blocks_hit gives the number of kernel `read()` calls issued for the table, index, or database; but the actual number of physical reads is usually lower due to kernel-level buffering.

The function `pg_stat_get_backend_idset` provides a convenient way to generate one row for each active backend. For example, to show the PIDs and current queries of all backends:

```
SELECT pg_stat_get_backend_pid(S.backendid) AS procpid,
       pg_stat_get_backend_activity(S.backendid) AS current_query
FROM (SELECT pg_stat_get_backend_idset() AS backendid) AS S;
```

10.3. Viewing Locks

Another useful tool for monitoring database activity is the `pg_locks` system catalog. This allows the database administrator to view information about the outstanding locks in the lock manager. For example, this capability can be used to:

- View all the locks currently outstanding, all the locks on relations in a particular database, all the locks on a particular relation, or all the locks held by a particular PostgreSQL session.
- View the relation in the current database with the most ungranted locks (which might be a source of contention among database clients).
- Determine the effect of lock contention on overall database performance, as well as the extent to which contention varies with overall database traffic.

For more information on locking and managing concurrency with PostgreSQL, refer to the PostgreSQL 7.3.21 User's Guide.

Note

When the `pg_locks` view is accessed, the internal lock manager data structures are momentarily locked, and a copy is made for the view to display. This ensures that the view produces a consistent set of results, while not blocking normal lock manager operations longer than necessary. Nonetheless there could be some impact on database performance if this view is examined often.

Table 10.3, "Lock Status System View" shows the definition of the `pg_locks` columns. The `pg_locks` view contains one row per lockable object and requested lock mode. Thus, the same lockable object may appear many times, if multiple transactions are holding or waiting for locks on it. A lockable object is either a relation or a transaction ID. (Note that this view includes only table-level locks, not row-level ones. If a transaction is waiting for a row-level lock, it will appear in the view as waiting for the transaction ID of the current holder of that row lock.)

Table 10.3. Lock Status System View

Column Name	Type	Description
`relation`	`oid`	The OID of the locked relation, or null if the lockable object is a transaction ID. This column can be joined with the `pg_class` system catalog to get more information on the locked relation. Note however that this will only work for relations in the current database (those for which the `database` column is either the current database's OID or zero).
`database`	`oid`	The OID of the database in which the locked relation exists, or null if the lockable object is a transaction ID. If the lock is on a globally-shared table, this field will be zero. This column can be joined with the `pg_database` system catalog to get more information on the locked object's database.
`transaction`	`xid`	The ID of a transaction, or null if the lockable object is a relation. Every transaction holds an exclusive lock on its transaction ID for its entire duration. If one transaction finds it necessary to wait specifically for another transaction, it does so by attempting to acquire share lock on the other transaction ID. That will succeed only when the other transaction terminates and releases its locks.

Column Name	Type	Description
pid	integer	The process ID of the PostgreSQL backend belonging to the session that has acquired or is attempting to acquire the lock. If you have enabled the statistics collector, this column can be joined with the pg_stat_activity view to get more information on the backend holding or waiting to hold the lock.
mode	text	The mode of the requested or held lock on the lockable object. For more information on the different lock modes available in PostgreSQL, refer to the PostgreSQL 7.3.21 User's Guide.
isgranted	boolean	True if this lock has been granted (is held by this session). False indicates that this session is currently waiting to acquire this lock, which implies that some other session is holding a conflicting lock mode on the same lockable object. This backend will sleep until the other lock is released (or a deadlock situation is detected). A single backend can be waiting to acquire at most one lock at a time.

Chapter 11. Monitoring Disk Usage

This chapter discusses how to monitor the disk usage of a PostgreSQL database system. In the current release, the database administrator does not have much control over the on-disk storage layout, so this chapter is mostly informative and can give you some ideas how to manage the disk usage with operating system tools.

11.1. Determining Disk Usage

Each table has a primary heap disk file where most of the data is stored. To store long column values, there is also a TOAST file associated with the table, named based on the table's OID (actually `pg_class.relfilenode`), and an index on the TOAST table. There also may be indexes associated with the base table.

You can monitor disk space from three places: from psql using `VACUUM` information, from psql using `contrib/dbsize`, and from the command line using contrib/oid2name. Using psql on a recently vacuumed (or analyzed) database, you can issue queries to see the disk usage of any table:

```
play=# SELECT relfilenode, relpages
play-# FROM pg_class
play-# WHERE relname = 'customer';
 relfilenode | relpages
-------------+----------
       16806 |       60
(1 row)
```

Each page is typically 8 kilobytes. (Remember, `relpages` is only updated by `VACUUM` and `ANALYZE`.) To show the space used by TOAST tables, use a query based on the heap relfilenode shown above:

```
play=# SELECT relname, relpages
play-# FROM pg_class
play-# WHERE relname = 'pg_toast_16806' OR
play-#       relname = 'pg_toast_16806_index'
play-# ORDER BY relname;
       relname        | relpages
----------------------+----------
 pg_toast_16806       |        0
 pg_toast_16806_index |        1
```

You can easily display index usage too:

```
play=# SELECT c2.relname, c2.relpages
play-# FROM pg_class c, pg_class c2, pg_index i
play-# WHERE c.relname = 'customer' AND
play-#       c.oid = i.indrelid AND
play-#       c2.oid = i.indexrelid
play-# ORDER BY c2.relname;
       relname        | relpages
----------------------+----------
 customer_id_indexdex |       26
```

It is easy to find your largest files using psql:

```
play=# SELECT relname, relpages
play-# FROM pg_class
play-# ORDER BY relpages DESC;
```

```
       relname         | relpages
----------------------+----------
 bigtable              |     3290
 customer              |     3144
```

`contrib/dbsize` loads functions into your database that allow you to find the size of a table or database from inside psql without the need for `VACUUM/ANALYZE`.

You can also use `contrib/oid2name` to show disk usage. See `README.oid2name` for examples. It includes a script that shows disk usage for each database.

11.2. Disk Full Failure

The most important disk monitoring task of a database administrator is to make sure the disk doesn't grow full. A filled data disk may result in subsequent corruption of database indexes, but not of the fundamental data tables. If the WAL files are on the same disk (as is the case for a default configuration) then a filled disk during database initialization may result in corrupted or incomplete WAL files. This failure condition is detected and the database server will refuse to start up.

If you cannot free up additional space on the disk by deleting other things you can move some of the database files to other file systems and create a symlink from the original location. But note that pg_dump cannot save the location layout information of such a setup; a restore would put everything back in one place. To avoid running out of disk space, you can place the WAL files or individual databases in other locations while creating them. See the initdb documentation and Section 5.5, “Alternative Locations” for more information.

Tip

Some file systems perform badly when they are almost full, so do not wait until the disk is full to take action.

Chapter 12. Write-Ahead Logging (WAL)

Author

Vadim Mikheev and Oliver Elphick

12.1. General Description

Write Ahead Logging (WAL) is a standard approach to transaction logging. Its detailed description may be found in most (if not all) books about transaction processing. Briefly, WAL's central concept is that changes to data files (where tables and indexes reside) must be written only after those changes have been logged - that is, when log records have been flushed to permanent storage. When we follow this procedure, we do not need to flush data pages to disk on every transaction commit, because we know that in the event of a crash we will be able to recover the database using the log: any changes that have not been applied to the data pages will first be redone from the log records (this is roll-forward recovery, also known as REDO) and then changes made by uncommitted transactions will be removed from the data pages (roll-backward recovery - UNDO).

12.1.1. Immediate Benefits of WAL

The first obvious benefit of using WAL is a significantly reduced number of disk writes, since only the log file needs to be flushed to disk at the time of transaction commit; in multiuser environments, commits of many transactions may be accomplished with a single `fsync()` of the log file. Furthermore, the log file is written sequentially, and so the cost of syncing the log is much less than the cost of flushing the data pages.

The next benefit is consistency of the data pages. The truth is that, before WAL, PostgreSQL was never able to guarantee consistency in the case of a crash. Before WAL, any crash during writing could result in:

1. index tuples pointing to nonexistent table rows

2. index tuples lost in split operations

3. totally corrupted table or index page content, because of partially written data pages

Problems with indexes (problems 1 and 2) could possibly have been fixed by additional `fsync()` calls, but it is not obvious how to handle the last case without WAL; WAL saves the entire data page content in the log if that is required to ensure page consistency for after-crash recovery.

12.1.2. Future Benefits

UNDO operation is not implemented. This means that changes made by aborted transactions will still occupy disk space and that we still need a permanent `pg_clog` file to hold the status of transactions, since we are not able to re-use transaction identifiers. Once UNDO is implemented, `pg_clog` will no longer be required to be permanent; it will be possible to remove `pg_clog` at shutdown. (However, the urgency of this concern has decreased greatly with the adoption of a segmented storage method for `pg_clog` --- it is no longer necessary to keep old `pg_clog` entries around forever.)

With UNDO, it will also be possible to implement *savepoints* to allow partial rollback of invalid transaction operations (parser errors caused by mistyping commands, insertion of duplicate primary/unique keys and so on) with the ability to continue or commit valid operations made by the transaction before the error. At present, any error will invalidate the whole transaction and require a transaction abort.

WAL offers the opportunity for a new method for database on-line backup and restore (BAR). To use this method, one would have to make periodic saves of data files to another disk, a tape or another host and also archive the WAL log files. The database file copy and the archived log files could be used to restore just as if one were restoring after a crash. Each time a new database file copy was made the old log files could be removed. Implementing this facility will require the logging of data file and index creation and deletion; it will also require development of a method for copying the data files (operating system copy commands are not suitable).

A difficulty standing in the way of realizing these benefits is that they require saving WAL entries for considerable periods of time (eg, as long as the longest possible transaction if transaction UNDO is wanted). The present WAL format is extremely bulky since it includes many disk page snapshots. This is not a serious concern at present, since the entries only need to be kept for one or two checkpoint intervals; but to achieve these future benefits some sort of compressed WAL format will be needed.

12.2. Implementation

WAL is automatically enabled from release 7.1 onwards. No action is required from the administrator with the exception of ensuring that the additional disk-space requirements of the WAL logs are met, and that any necessary tuning is done (see Section 12.3, “WAL Configuration”).

WAL logs are stored in the directory *$PGDATA*/pg_xlog, as a set of segment files, each 16 MB in size. Each segment is divided into 8 kB pages. The log record headers are described in access/xlog.h; record content is dependent on the type of event that is being logged. Segment files are given ever-increasing numbers as names, starting at 0000000000000000. The numbers do not wrap, at present, but it should take a very long time to exhaust the available stock of numbers.

The WAL buffers and control structure are in shared memory, and are handled by the backends; they are protected by lightweight locks. The demand on shared memory is dependent on the number of buffers. The default size of the WAL buffers is 8 buffers of 8 kB each, or 64 kB total.

It is of advantage if the log is located on another disk than the main database files. This may be achieved by moving the directory, pg_xlog, to another location (while the postmaster is shut down, of course) and creating a symbolic link from the original location in *$PGDATA* to the new location.

The aim of WAL, to ensure that the log is written before database records are altered, may be subverted by disk drives that falsely report a successful write to the kernel, when, in fact, they have only cached the data and not yet stored it on the disk. A power failure in such a situation may still lead to irrecoverable data corruption. Administrators should try to ensure that disks holding PostgreSQL's log files do not make such false reports.

12.2.1. Database Recovery with WAL

After a checkpoint has been made and the log flushed, the checkpoint's position is saved in the file pg_control. Therefore, when recovery is to be done, the backend first reads pg_control and then the checkpoint record; then it performs the REDO operation by scanning forward from the log position indicated in the checkpoint record. Because the entire content of data pages is saved in the log on the first page modification after a checkpoint, all pages changed since the checkpoint will be restored to a consistent state.

Using pg_control to get the checkpoint position speeds up the recovery process, but to handle possible corruption of pg_control, we should actually implement the reading of existing log segments in reverse order -- newest to oldest -- in order to find the last checkpoint. This has not been implemented, yet.

12.3. WAL Configuration

There are several WAL-related parameters that affect database performance. This section explains their use. Consult Section 3.4, “Run-time Configuration” for details about setting configuration parameters.

Checkpoints are points in the sequence of transactions at which it is guaranteed that the data files have been updated with all information logged before the checkpoint. At checkpoint time, all dirty data pages are flushed to disk and a special checkpoint record is written to the log file. As result, in the event of a crash, the recoverer knows from what record in the log (known as the redo record) it should start the REDO operation, since any changes made to data files before that record are already on disk. After a checkpoint has been made, any log segments written before the undo records are no longer needed and can be recycled or removed. (When WAL-based BAR is implemented, the log segments would be archived before being recycled or removed.)

The postmaster spawns a special backend process every so often to create the next checkpoint. A checkpoint is created every `CHECKPOINT_SEGMENTS` log segments, or every `CHECKPOINT_TIMEOUT` seconds, whichever comes first. The default settings are 3 segments and 300 seconds respectively. It is also possible to force a checkpoint by using the SQL command `CHECKPOINT`.

Reducing `CHECKPOINT_SEGMENTS` and/or `CHECKPOINT_TIMEOUT` causes checkpoints to be done more often. This allows faster after-crash recovery (since less work will need to be redone). However, one must balance this against the increased cost of flushing dirty data pages more often. In addition, to ensure data page consistency, the first modification of a data page after each checkpoint results in logging the entire page content. Thus a smaller checkpoint interval increases the volume of output to the log, partially negating the goal of using a smaller interval, and in any case causing more disk I/O.

There will be at least one 16MB segment file, and will normally not be more than 2 * `CHECKPOINT_SEGMENTS` + 1 files. You can use this to estimate space requirements for WAL. Ordinarily, when old log segment files are no longer needed, they are recycled (renamed to become the next sequential future segments). If, due to a short-term peak of log output rate, there are more than 2 * `CHECKPOINT_SEGMENTS` + 1 segment files, the unneeded segment files will be deleted instead of recycled until the system gets back under this limit.

There are two commonly used WAL functions: `LogInsert` and `LogFlush`. `LogInsert` is used to place a new record into the WAL buffers in shared memory. If there is no space for the new record, `LogInsert` will have to write (move to kernel cache) a few filled WAL buffers. This is undesirable because `LogInsert` is used on every database low level modification (for example, tuple insertion) at a time when an exclusive lock is held on affected data pages, so the operation needs to be as fast as possible. What is worse, writing WAL buffers may also force the creation of a new log segment, which takes even more time. Normally, WAL buffers should be written and flushed by a `LogFlush` request, which is made, for the most part, at transaction commit time to ensure that transaction records are flushed to permanent storage. On systems with high log output, `LogFlush` requests may not occur often enough to prevent WAL buffers being written by `LogInsert`. On such systems one should increase the number of WAL buffers by modifying the `postgresql.conf WAL_BUFFERS` parameter. The default number of WAL buffers is 8. Increasing this value will correspondingly increase shared memory usage.

The `COMMIT_DELAY` parameter defines for how many microseconds the backend will sleep after writing a commit record to the log with `LogInsert` but before performing a `LogFlush`. This delay allows other backends to add their commit records to the log so as to have all of them flushed with a single log sync. No sleep will occur if `fsync` is not enabled or if fewer than `COMMIT_SIBLINGS` other backends are not currently in active transactions; this avoids sleeping when it's unlikely that any other backend will commit soon. Note that on most platforms, the resolution of a sleep request is ten milliseconds, so that any nonzero `COMMIT_DELAY` setting between 1 and 10000 microseconds will have the same effect. Good values for these parameters are not yet clear; experimentation is encouraged.

The `WAL_SYNC_METHOD` parameter determines how PostgreSQL will ask the kernel to force WAL updates out to disk. All the options should be the same as far as reliability goes, but it's quite platform-specific which one will be the fastest. Note that this parameter is irrelevant if `FSYNC` has been turned off.

Setting the `WAL_DEBUG` parameter to any nonzero value will result in each `LogInsert` and `LogFlush` WAL call being logged to standard error. At present, it makes no difference what the nonzero value is. This option may be replaced by a more general mechanism in the future.

Chapter 13. Regression Tests

13.1. Introduction

The regression tests are a comprehensive set of tests for the SQL implementation in PostgreSQL. They test standard SQL operations as well as the extended capabilities of PostgreSQL. The test suite was originally developed by Jolly Chen and Andrew Yu, and was extensively revised and repackaged by Marc Fournier and Thomas Lockhart. From PostgreSQL 6.1 onward the regression tests are current for every official release.

13.2. Running the Tests

The regression test can be run against an already installed and running server, or using a temporary installation within the build tree. Furthermore, there is a "parallel" and a "sequential" mode for running the tests. The sequential method runs each test script in turn, whereas the parallel method starts up multiple server processes to run groups of tests in parallel. Parallel testing gives confidence that interprocess communication and locking are working correctly. For historical reasons, the sequential test is usually run against an existing installation and the parallel method against a temporary installation, but there are no technical reasons for this.

To run the regression tests after building but before installation, type

```
$ gmake check
```

in the top-level directory. (Or you can change to `src/test/regress` and run the command there.) This will first build several auxiliary files, such as platform-dependent "expected" files and some sample user-defined trigger functions, and then run the test driver script. At the end you should see something like

```
=======================
 All 77 tests passed.
=======================
```

or otherwise a note about what tests failed. See Section 13.3, "Test Evaluation" below for more.

Note

Because this test method runs a temporary server, it will not work when you are the root user (the server will not start as root). If you already did the build as root, you do not have to start all over. Instead, make the regression test directory writable by some other user, log in as that user, and restart the tests. For example,

```
root# chmod -R a+w src/test/regress
root# chmod -R a+w contrib/spi
root# su - joeuser
joeuser$ cd top-level build directory
joeuser$ gmake check
```

(The only possible "security risk" here is that other users might be able to alter the regression test results behind your back. Use common sense when managing user permissions.)

Alternatively, run the tests after installation.

Tip

The parallel regression test starts quite a few processes under your user ID. Presently, the maximum concurrency is twenty parallel test scripts, which means sixty processes --- there's

a backend, a psql, and usually a shell parent process for the psql for each test script. So if your system enforces a per-user limit on the number of processes, make sure this limit is at least seventy-five or so, else you may get random-seeming failures in the parallel test. If you are not in a position to raise the limit, you can edit the file `src/test/regress/parallel_schedule` to split the larger concurrent test sets into more manageable groups.

Tip

On some systems, the default Bourne-compatible shell (`/bin/sh`) gets confused when it has to manage too many child processes in parallel. This may cause the parallel test run to lock up or fail. In such cases, specify a different Bourne-compatible shell on the command line, for example:

```
$ gmake SHELL=/bin/ksh check
```

If no non-broken shell is available, you can alter the parallel test schedule as suggested above.

To run the tests after installation (see Chapter 1, *Installation Instructions*), initialize a data area and start the server, as explained in Chapter 3, *Server Run-time Environment*, then type

```
$ gmake installcheck
```

The tests will expect to contact the server at the local host and the default port number, unless directed otherwise by `PGHOST` and `PGPORT` environment variables.

13.3. Test Evaluation

Some properly installed and fully functional PostgreSQL installations can "fail" some of these regression tests due to platform-specific artifacts such as varying floating-point representation and time zone support. The tests are currently evaluated using a simple diff comparison against the outputs generated on a reference system, so the results are sensitive to small system differences. When a test is reported as "failed", always examine the differences between expected and actual results; you may well find that the differences are not significant. Nonetheless, we still strive to maintain accurate reference files across all supported platforms, so it can be expected that all tests pass.

The actual outputs of the regression tests are in files in the `src/test/regress/results` directory. The test script uses diff to compare each output file against the reference outputs stored in the `src/test/regress/expected` directory. Any differences are saved for your inspection in `src/test/regress/regression.diffs`. (Or you can run diff yourself, if you prefer.)

13.3.1. Error message differences

Some of the regression tests involve intentional invalid input values. Error messages can come from either the PostgreSQL code or from the host platform system routines. In the latter case, the messages may vary between platforms, but should reflect similar information. These differences in messages will result in a "failed" regression test that can be validated by inspection.

13.3.2. Locale differences

If you run the tests against an already-installed server that was initialized with a collation order locale different than C then there may be differences due to sort order and follow-up failures. The regression test suite is set up to handle this problem by providing alternative result files that together are known to handle a large number of locales. For example, for the "char" test, the expected file `char.out` handles the `C` and `POSIX` locales, and the file `char_1.out` handles many other locales. The regression test driver will automatically pick the best file to match against when checking for success and for computing failure differences. (This means that the regression tests cannot detect whether the results are appropriate for the configured locale. The tests will simply pick the one result file that works best.)

If for some reason the existing expected files do not cover some locale, you can add a new file. The naming scheme is *testname_digit*.out. The actual digit is not significant. Remember that the regression test driver will consider all such files to be equally valid test results. If the test results are platform-dependent, the technique described in Section 13.4, “Platform-specific comparison files” should be used instead.

13.3.3. Date and time differences

Some of the queries in the horology test will fail if you run the test on the day of a daylight-saving time changeover, or the day before or after one. These queries assume that the intervals between midnight yesterday, midnight today and midnight tomorrow are exactly twenty-four hours -- which is wrong if daylight-saving time went into or out of effect meanwhile.

Most of the date and time results are dependent on the time zone environment. The reference files are generated for time zone PST8PDT (Berkeley, California) and there will be apparent failures if the tests are not run with that time zone setting. The regression test driver sets environment variable PGTZ to PST8PDT, which normally ensures proper results. However, your system must provide library support for the PST8PDT time zone, or the time zone-dependent tests will fail. To verify that your machine does have this support, type the following:

```
$ env TZ=PST8PDT date
```

The command above should have returned the current system time in the PST8PDT time zone. If the PST8PDT database is not available, then your system may have returned the time in GMT. If the PST8PDT time zone is not available, you can set the time zone rules explicitly:

```
PGTZ='PST8PDT7,M04.01.0,M10.05.03'; export PGTZ
```

There appear to be some systems that do not accept the recommended syntax for explicitly setting the local time zone rules; you may need to use a different PGTZ setting on such machines.

Some systems using older time zone libraries fail to apply daylight-saving corrections to dates before 1970, causing pre-1970 PDT times to be displayed in PST instead. This will result in localized differences in the test results.

13.3.4. Floating-point differences

Some of the tests involve computing 64-bit (double precision) numbers from table columns. Differences in results involving mathematical functions of double precision columns have been observed. The float8 and geometry tests are particularly prone to small differences across platforms, or even with different compiler optimization options. Human eyeball comparison is needed to determine the real significance of these differences which are usually 10 places to the right of the decimal point.

Some systems signal errors from pow() and exp() differently from the mechanism expected by the current PostgreSQL code.

13.3.5. Polygon differences

Several of the tests involve operations on geographic data about the Oakland/Berkeley, California street map. The map data is expressed as polygons whose vertices are represented as pairs of double precision numbers (decimal latitude and longitude). Initially, some tables are created and loaded with geographic data, then some views are created that join two tables using the polygon intersection operator (##), then a select is done on the view.

When comparing the results from different platforms, differences occur in the 2nd or 3rd place to the right of the decimal point. The SQL statements where these problems occur are the following:

```
SELECT * from street;
SELECT * from iexit;
```

13.3.6. Row ordering differences

You might see differences in which the same rows are output in a different order than what appears in the expected file. In most cases this is not, strictly speaking, a bug. Most of the regression test scripts are not so pedantic as to use an ORDER BY for every single SELECT, and so their result row orderings are not well-defined according to the letter of the SQL specification. In practice, since we are looking at the same queries being executed on the same data by the same software, we usually get the same result ordering on all platforms, and so the lack of ORDER BY isn't a problem. Some queries do exhibit cross-platform ordering differences, however. (Ordering differences can also be triggered by non-C locale settings.)

Therefore, if you see an ordering difference, it's not something to worry about, unless the query does have an ORDER BY that your result is violating. But please report it anyway, so that we can add an ORDER BY to that particular query and thereby eliminate the bogus “failure” in future releases.

You might wonder why we don't order all the regress test queries explicitly to get rid of this issue once and for all. The reason is that that would make the regression tests less useful, not more, since they'd tend to exercise query plan types that produce ordered results to the exclusion of those that don't.

13.3.7. The “random” test

There is at least one case in the “random” test script that is intended to produce random results. This causes random to fail the regression test once in a while (perhaps once in every five to ten trials). Typing

```
diff results/random.out expected/random.out
```

should produce only one or a few lines of differences. You need not worry unless the random test always fails in repeated attempts. (On the other hand, if the random test is *never* reported to fail even in many trials of the regression tests, you probably *should* worry.)

13.4. Platform-specific comparison files

Since some of the tests inherently produce platform-specific results, we have provided a way to supply platform-specific result comparison files. Frequently, the same variation applies to multiple platforms; rather than supplying a separate comparison file for every platform, there is a mapping file that defines which comparison file to use. So, to eliminate bogus test “failures” for a particular platform, you must choose or make a variant result file, and then add a line to the mapping file, which is `resultmap`.

Each line in the mapping file is of the form

```
testname/platformpattern=comparisonfilename
```

The test name is just the name of the particular regression test module. The platform pattern is a pattern in the style of expr (that is, a regular expression with an implicit `^` anchor at the start). It is matched against the platform name as printed by `config.guess` followed by `:gcc` or `:cc`, depending on whether you use the GNU compiler or the system's native compiler (on systems where there is a difference). The comparison file name is the name of the substitute result comparison file.

For example: some systems using older time zone libraries fail to apply daylight-saving corrections to dates before 1970, causing pre-1970 PDT times to be displayed in PST instead. This causes a few differences in the `horology` regression test. Therefore, we provide a variant comparison file, `horology-no-DST-before-1970.out`, which includes the results to be expected on these systems. To silence the bogus “failure” message on HPPA platforms, `resultmap` includes

```
horology/hppa=horology-no-DST-before-1970
```

which will trigger on any machine for which the output of `config.guess` begins with “`hppa`”. Other lines in `resultmap` select the variant comparison file for other platforms where it's appropriate.

Appendix A. Release Notes

A.1. Release 7.3.21

Release date

2008-01-07

This release contains a variety of fixes from 7.3.20, including fixes for significant security issues.

This is expected to be the last PostgreSQL release in the 7.3.X series. Users are encouraged to update to a newer release branch soon.

A.1.1. Migration to Version 7.3.21

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.1.2. Changes

- Prevent functions in indexes from executing with the privileges of the user running `VACUUM`, `ANALYZE`, etc (Tom)

  Functions used in index expressions and partial-index predicates are evaluated whenever a new table entry is made. It has long been understood that this poses a risk of trojan-horse code execution if one modifies a table owned by an untrustworthy user. (Note that triggers, defaults, check constraints, etc. pose the same type of risk.) But functions in indexes pose extra danger because they will be executed by routine maintenance operations such as `VACUUM FULL`, which are commonly performed automatically under a superuser account. For example, a nefarious user can execute code with superuser privileges by setting up a trojan-horse index definition and waiting for the next routine vacuum. The fix arranges for standard maintenance operations (including `VACUUM`, `ANALYZE`, `REINDEX`, and `CLUSTER`) to execute as the table owner rather than the calling user, using the same privilege-switching mechanism already used for `SECURITY DEFINER` functions. To prevent bypassing this security measure, execution of `SET SESSION AUTHORIZATION` and `SET ROLE` is now forbidden within a `SECURITY DEFINER` context. (CVE-2007-6600)

- Require non-superusers who use `/contrib/dblink` to use only password authentication, as a security measure (Joe)

  The fix that appeared for this in 7.3.20 was incomplete, as it plugged the hole for only some `dblink` functions. (CVE-2007-6601, CVE-2007-3278)

- Fix potential crash in `translate()` when using a multibyte database encoding (Tom)

- Make `contrib/tablefunc`'s `crosstab()` handle NULL rowid as a category in its own right, rather than crashing (Joe)

- Require a specific version of Autoconf to be used when re-generating the `configure` script (Peter)

  This affects developers and packagers only. The change was made to prevent accidental use of untested combinations of Autoconf and PostgreSQL versions. You can remove the version check if you really want to use a different Autoconf version, but it's your responsibility whether the result works or not.

A.2. Release 7.3.20

Release date

2007-09-17

This release contains fixes from 7.3.19.

A.2.1. Migration to Version 7.3.20

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.2.2. Changes

- Prevent index corruption when a transaction inserts rows and then aborts close to the end of a concurrent `VACUUM` on the same table (Tom)
- Make `CREATE DOMAIN ... DEFAULT NULL` work properly (Tom)
- Fix crash when `log_min_error_statement` logging runs out of memory (Tom)
- Require non-superusers who use `/contrib/dblink` to use only password authentication, as a security measure (Joe)

A.3. Release 7.3.19

Release date

2007-04-23

This release contains fixes from 7.3.18, including a security fix.

A.3.1. Migration to Version 7.3.19

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.3.2. Changes

- Support explicit placement of the temporary-table schema within `search_path`, and disable searching it for functions and operators (Tom)

  This is needed to allow a security-definer function to set a truly secure value of `search_path`. Without it, an unprivileged SQL user can use temporary objects to execute code with the privileges of the security-definer function (CVE-2007-2138). See `CREATE FUNCTION` for more information.

- Fix potential-data-corruption bug in how `VACUUM FULL` handles `UPDATE` chains (Tom, Pavan Deolasee)

A.4. Release 7.3.18

Release date

2007-02-05

This release contains a variety of fixes from 7.3.17, including a security fix.

A.4.1. Migration to Version 7.3.18

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.4.2. Changes

- Remove security vulnerability that allowed connected users to read backend memory (Tom)

  The vulnerability involves changing the data type of a table column used in a SQL function (CVE-2007-0555). This error can easily be exploited to cause a backend crash, and in principle might be used to read database content that the user should not be able to access.

- Fix rare bug wherein btree index page splits could fail due to choosing an infeasible split point (Heikki Linnakangas)

- Tighten security of multi-byte character processing for UTF8 sequences over three bytes long (Tom)

A.5. Release 7.3.17

Release date

2007-01-08

This release contains a variety of fixes from 7.3.16.

A.5.1. Migration to Version 7.3.17

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.5.2. Changes

- `to_number()` and `to_char(numeric)` are now `STABLE`, not `IMMUTABLE`, for new initdb installs (Tom)

  This is because `lc_numeric` can potentially change the output of these functions.

- Improve index usage of regular expressions that use parentheses (Tom)

  This improves psql `\d` performance also.

A.6. Release 7.3.16

Release date

2006-10-16

This release contains a variety of fixes from 7.3.15.

A.6.1. Migration to Version 7.3.16

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.6.2. Changes

- Fix corner cases in pattern matching for psql's `\d` commands
- Fix index-corrupting bugs in /contrib/ltree (Teodor)
- Back-port 7.4 spinlock code to improve performance and support 64-bit architectures better
- Fix SSL-related memory leak in libpq
- Fix backslash escaping in /contrib/dbmirror
- Adjust regression tests for recent changes in US DST laws

A.7. Release 7.3.15

Release date

2006-05-23

This release contains a variety of fixes from 7.3.14, including patches for extremely serious security issues.

A.7.1. Migration to Version 7.3.15

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

Full security against the SQL-injection attacks described in CVE-2006-2313 and CVE-2006-2314 might require changes in application code. If you have applications that embed untrustworthy strings into SQL commands, you should examine them as soon as possible to ensure that they are using recommended escaping techniques. In most cases, applications should be using subroutines provided by libraries or drivers (such as libpq's `PQescapeStringConn()`) to perform string escaping, rather than relying on *ad hoc* code to do it.

A.7.2. Changes

- Change the server to reject invalidly-encoded multibyte characters in all cases (Tatsuo, Tom)

  While PostgreSQL has been moving in this direction for some time, the checks are now applied uniformly to all encodings and all textual input, and are now always errors not merely warnings. This change defends against SQL-injection attacks of the type described in CVE-2006-2313.

- Reject unsafe uses of `\'` in string literals

  As a server-side defense against SQL-injection attacks of the type described in CVE-2006-2314, the server now only accepts `''` and not `\'` as a representation of ASCII single quote in SQL string literals. By default, `\'` is rejected only when `client_encoding` is set to a client-only encoding (SJIS, BIG5, GBK, GB18030, or UHC), which is the scenario in which SQL injection is possible. A new configuration parameter `backslash_quote` is available to adjust this behavior when needed. Note that full security against CVE-2006-2314 might require client-side changes; the purpose of `backslash_quote` is in part to make it obvious that insecure clients are insecure.

- Modify libpq's string-escaping routines to be aware of encoding considerations

  This fixes libpq-using applications for the security issues described in CVE-2006-2313 and CVE-2006-2314. Applications that use multiple PostgreSQL connections concurrently should migrate to `PQescapeStringConn()` and `PQescapeByteaConn()` to ensure that escaping

is done correctly for the settings in use in each database connection. Applications that do string escaping “by hand” should be modified to rely on library routines instead.

- Fix some incorrect encoding conversion functions

  `win1251_to_iso`, `alt_to_iso`, `euc_tw_to_big5`, `euc_tw_to_mic`, `mic_to_euc_tw` were all broken to varying extents.

- Clean up stray remaining uses of `\'` in strings (Bruce, Jan)

- Fix server to use custom DH SSL parameters correctly (Michael Fuhr)

- Fix various minor memory leaks

A.8. Release 7.3.14

Release date

2006-02-14

This release contains a variety of fixes from 7.3.13.

A.8.1. Migration to Version 7.3.14

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.13, see the release notes for 7.3.13.

A.8.2. Changes

- Fix potential crash in `SET SESSION AUTHORIZATION` (CVE-2006-0553)

  An unprivileged user could crash the server process, resulting in momentary denial of service to other users, if the server has been compiled with Asserts enabled (which is not the default). Thanks to Akio Ishida for reporting this problem.

- Fix bug with row visibility logic in self-inserted rows (Tom)

  Under rare circumstances a row inserted by the current command could be seen as already valid, when it should not be. Repairs bug created in 7.3.11 release.

- Fix race condition that could lead to “file already exists” errors during pg_clog file creation (Tom)

- Fix to allow restoring dumps that have cross-schema references to custom operators (Tom)

- Portability fix for testing presence of `finite` and `isinf` during configure (Tom)

A.9. Release 7.3.13

Release date

2006-01-09

This release contains a variety of fixes from 7.3.12.

A.9.1. Migration to Version 7.3.13

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.10, see the release notes for 7.3.10. Also, you might need to `REINDEX` indexes on textual columns after updating, if you are affected by the locale or plperl issues described below.

A.9.2. Changes

- Fix character string comparison for locales that consider different character combinations as equal, such as Hungarian (Tom)

  This might require `REINDEX` to fix existing indexes on textual columns.

- Set locale environment variables during postmaster startup to ensure that plperl won't change the locale later

  This fixes a problem that occurred if the postmaster was started with environment variables specifying a different locale than what initdb had been told. Under these conditions, any use of plperl was likely to lead to corrupt indexes. You might need `REINDEX` to fix existing indexes on textual columns if this has happened to you.

- Fix longstanding bug in strpos() and regular expression handling in certain rarely used Asian multi-byte character sets (Tatsuo)

- Fix bug in `/contrib/pgcrypto` gen_salt, which caused it not to use all available salt space for MD5 and XDES algorithms (Marko Kreen, Solar Designer)

  Salts for Blowfish and standard DES are unaffected.

- Fix `/contrib/dblink` to throw an error, rather than crashing, when the number of columns specified is different from what's actually returned by the query (Joe)

A.10. Release 7.3.12

Release date

2005-12-12

This release contains a variety of fixes from 7.3.11.

A.10.1. Migration to Version 7.3.12

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.10, see the release notes for 7.3.10.

A.10.2. Changes

- Fix race condition in transaction log management

  There was a narrow window in which an I/O operation could be initiated for the wrong page, leading to an Assert failure or data corruption.

- `/contrib/ltree` fixes (Teodor)

- Fix longstanding planning error for outer joins

  This bug sometimes caused a bogus error “RIGHT JOIN is only supported with merge-joinable join conditions”.

- Prevent core dump in pg_autovacuum when a table has been dropped

A.11. Release 7.3.11

Release date

2005-10-04

This release contains a variety of fixes from 7.3.10.

A.11.1. Migration to Version 7.3.11

A dump/restore is not required for those running 7.3.X. However, if you are upgrading from a version earlier than 7.3.10, see the release notes for 7.3.10.

A.11.2. Changes

- Fix error that allowed `VACUUM` to remove `ctid` chains too soon, and add more checking in code that follows `ctid` links

  This fixes a long-standing problem that could cause crashes in very rare circumstances.

- Fix `CHAR()` to properly pad spaces to the specified length when using a multiple-byte character set (Yoshiyuki Asaba)

  In prior releases, the padding of `CHAR()` was incorrect because it only padded to the specified number of bytes without considering how many characters were stored.

- Fix missing rows in queries like `UPDATE a=... WHERE a...` with GiST index on column `a`
- Improve checking for partially-written WAL pages
- Improve robustness of signal handling when SSL is enabled
- Various memory leakage fixes
- Various portability improvements
- Fix PL/PgSQL to handle `var := var` correctly when the variable is of pass-by-reference type

A.12. Release 7.3.10

Release date

2005-05-09

This release contains a variety of fixes from 7.3.9, including several security-related issues.

A.12.1. Migration to Version 7.3.10

A dump/restore is not required for those running 7.3.X. However, it is one possible way of handling a significant security problem that has been found in the initial contents of 7.3.X system catalogs. A dump/initdb/reload sequence using 7.3.10's initdb will automatically correct this problem.

The security problem is that the built-in character set encoding conversion functions can be invoked from SQL commands by unprivileged users, but the functions were not designed for such use and are not secure against malicious choices of arguments. The fix involves changing the declared parameter list of these functions so that they can no longer be invoked from SQL commands. (This does not affect their normal use by the encoding conversion machinery.) It is strongly recommended that all installations repair this error, either by initdb or by following the manual repair procedure given below. The error at least allows unprivileged database users to crash their server process, and might allow unprivileged users to gain the privileges of a database superuser.

If you wish not to do an initdb, perform the following procedure instead. As the database superuser, do:

```
BEGIN;
UPDATE pg_proc SET proargtypes[3] = 'internal'::regtype
```

```
WHERE pronamespace = 11 AND pronargs = 5
     AND proargtypes[2] = 'cstring'::regtype;
-- The command should report having updated 90 rows;
-- if not, rollback and investigate instead of committing!
COMMIT;
```

The above procedure must be carried out in *each* database of an installation, including `template1`, and ideally including `template0` as well. If you do not fix the template databases then any subsequently created databases will contain the same error. `template1` can be fixed in the same way as any other database, but fixing `template0` requires additional steps. First, from any database issue:

```
UPDATE pg_database SET datallowconn = true WHERE datname =
 'template0';
```

Next connect to `template0` and perform the above repair procedure. Finally, do:

```
-- re-freeze template0:
VACUUM FREEZE;
-- and protect it against future alterations:
UPDATE pg_database SET datallowconn = false WHERE datname =
 'template0';
```

A.12.2. Changes

- Change encoding function signature to prevent misuse
- Repair ancient race condition that allowed a transaction to be seen as committed for some purposes (eg SELECT FOR UPDATE) slightly sooner than for other purposes

  This is an extremely serious bug since it could lead to apparent data inconsistencies being briefly visible to applications.
- Repair race condition between relation extension and VACUUM

  This could theoretically have caused loss of a page's worth of freshly-inserted data, although the scenario seems of very low probability. There are no known cases of it having caused more than an Assert failure.
- Fix comparisons of `TIME WITH TIME ZONE` values

  The comparison code was wrong in the case where the `--enable-integer-datetimes` configuration switch had been used. NOTE: if you have an index on a `TIME WITH TIME ZONE` column, it will need to be `REINDEX`ed after installing this update, because the fix corrects the sort order of column values.
- Fix `EXTRACT(EPOCH)` for `TIME WITH TIME ZONE` values
- Fix mis-display of negative fractional seconds in `INTERVAL` values

  This error only occurred when the `--enable-integer-datetimes` configuration switch had been used.
- Additional buffer overrun checks in plpgsql (Neil)
- Fix pg_dump to dump trigger names containing `%` correctly (Neil)
- Prevent `to_char(interval)` from dumping core for month-related formats
- Fix `contrib/pgcrypto` for newer OpenSSL builds (Marko Kreen)
- Still more 64-bit fixes for `contrib/intagg`

- Prevent incorrect optimization of functions returning `RECORD`

A.13. Release 7.3.9

Release date

2005-01-31

This release contains a variety of fixes from 7.3.8, including several security-related issues.

A.13.1. Migration to Version 7.3.9

A dump/restore is not required for those running 7.3.X.

A.13.2. Changes

- Disallow `LOAD` to non-superusers

  On platforms that will automatically execute initialization functions of a shared library (this includes at least Windows and ELF-based Unixen), `LOAD` can be used to make the server execute arbitrary code. Thanks to NGS Software for reporting this.

- Check that creator of an aggregate function has the right to execute the specified transition functions

  This oversight made it possible to bypass denial of EXECUTE permission on a function.

- Fix security and 64-bit issues in contrib/intagg

- Add needed STRICT marking to some contrib functions (Kris Jurka)

- Avoid buffer overrun when plpgsql cursor declaration has too many parameters (Neil)

- Fix planning error for FULL and RIGHT outer joins

  The result of the join was mistakenly supposed to be sorted the same as the left input. This could not only deliver mis-sorted output to the user, but in case of nested merge joins could give outright wrong answers.

- Fix plperl for quote marks in tuple fields

- Fix display of negative intervals in SQL and GERMAN datestyles

A.14. Release 7.3.8

Release date

2004-10-22

This release contains a variety of fixes from 7.3.7.

A.14.1. Migration to Version 7.3.8

A dump/restore is not required for those running 7.3.X.

A.14.2. Changes

- Repair possible failure to update hint bits on disk

Under rare circumstances this oversight could lead to “could not access transaction status” failures, which qualifies it as a potential-data-loss bug.

- Ensure that hashed outer join does not miss tuples

  Very large left joins using a hash join plan could fail to output unmatched left-side rows given just the right data distribution.

- Disallow running pg_ctl as root

  This is to guard against any possible security issues.

- Avoid using temp files in /tmp in make_oidjoins_check

  This has been reported as a security issue, though it's hardly worthy of concern since there is no reason for non-developers to use this script anyway.

A.15. Release 7.3.7

Release date

2004-08-16

This release contains one critical fix over 7.3.6, and some minor items.

A.15.1. Migration to Version 7.3.7

A dump/restore is not required for those running 7.3.X.

A.15.2. Changes

- Prevent possible loss of committed transactions during crash

  Due to insufficient interlocking between transaction commit and checkpointing, it was possible for transactions committed just before the most recent checkpoint to be lost, in whole or in part, following a database crash and restart. This is a serious bug that has existed since PostgreSQL 7.1.

- Remove asymmetrical word processing in tsearch (Teodor)

- Properly schema-qualify function names when pg_dump'ing a CAST

A.16. Release 7.3.6

Release date

2004-03-02

This release contains a variety of fixes from 7.3.5.

A.16.1. Migration to Version 7.3.6

A dump/restore is *not* required for those running 7.3.*.

A.16.2. Changes

- Revert erroneous changes in rule permissions checking

A patch applied in 7.3.3 to fix a corner case in rule permissions checks turns out to have disabled rule-related permissions checks in many not-so-corner cases. This would for example allow users to insert into views they weren't supposed to have permission to insert into. We have therefore reverted the 7.3.3 patch. The original bug will be fixed in 8.0.

- Repair incorrect order of operations in GetNewTransactionId()

  This bug could result in failure under out-of-disk-space conditions, including inability to restart even after disk space is freed.

- Ensure configure selects -fno-strict-aliasing even when an external value for CFLAGS is supplied

  On some platforms, building with -fstrict-aliasing causes bugs.

- Make pg_restore handle 64-bit off_t correctly

  This bug prevented proper restoration from archive files exceeding 4 GB.

- Make contrib/dblink not assume that local and remote type OIDs match (Joe)
- Quote connectby()'s start_with argument properly (Joe)
- Don't crash when a rowtype argument to a plpgsql function is NULL
- Avoid generating invalid character encoding sequences in corner cases when planning LIKE operations
- Ensure text_position() cannot scan past end of source string in multibyte cases (Korea PostgreSQL Users' Group)
- Fix index optimization and selectivity estimates for LIKE operations on bytea columns (Joe)

A.17. Release 7.3.5

Release date

2003-12-03

This has a variety of fixes from 7.3.4.

A.17.1. Migration to Version 7.3.5

A dump/restore is *not* required for those running 7.3.*.

A.17.2. Changes

- Force zero_damaged_pages to be on during recovery from WAL
- Prevent some obscure cases of “variable not in subplan target lists”
- Force stats processes to detach from shared memory, ensuring cleaner shutdown
- Make PQescapeBytea and byteaout consistent with each other (Joe)
- Added missing SPI_finish() calls to dblink's get_tuple_of_interest() (Joe)
- Fix for possible foreign key violation when rule rewrites INSERT (Jan)

- Support qualified type names in PL/Tcl's spi_prepare command (Jan)
- Make pg_dump handle a procedural language handler located in pg_catalog
- Make pg_dump handle cases where a custom opclass is in another schema
- Make pg_dump dump binary-compatible casts correctly (Jan)
- Fix insertion of expressions containing subqueries into rule bodies
- Fix incorrect argument processing in clusterdb script (Anand Ranganathan)
- Fix problems with dropped columns in plpython triggers
- Repair problems with to_char() reading past end of its input string (Karel)
- Fix GB18030 mapping errors (Tatsuo)
- Fix several problems with SSL error handling and asynchronous SSL I/O
- Remove ability to bind a list of values to a single parameter in JDBC (prevents possible SQL-injection attacks)
- Fix some errors in HAVE_INT64_TIMESTAMP code paths
- Fix corner case for btree search in parallel with first root page split

A.18. Release 7.3.4

Release date

2003-07-24

This has a variety of fixes from 7.3.3.

A.18.1. Migration to Version 7.3.4

A dump/restore is *not* required for those running 7.3.*.

A.18.2. Changes

- Repair breakage in timestamp-to-date conversion for dates before 2000
- Prevent rare possibility of server startup failure (Tom)
- Fix bugs in interval-to-time conversion (Tom)
- Add constraint names in a few places in pg_dump (Rod)
- Improve performance of functions with many parameters (Tom)
- Fix to_ascii() buffer overruns (Tom)
- Prevent restore of database comments from throwing an error (Tom)
- Work around buggy strxfrm() present in some Solaris releases (Tom)
- Properly escape jdbc setObject() strings to improve security (Barry)

A.19. Release 7.3.3

Release date

2003-05-22

This release contains a variety of fixes for version 7.3.2.

A.19.1. Migration to Version 7.3.3

A dump/restore is *not* required for those running version 7.3.*.

A.19.2. Changes

- Repair sometimes-incorrect computation of StartUpID after a crash
- Avoid slowness with lots of deferred triggers in one transaction (Stephan)
- Don't lock referenced row when `UPDATE` doesn't change foreign key's value (Jan)
- Use `-fPIC` not `-fpic` on Sparc (Tom Callaway)
- Repair lack of schema-awareness in contrib/reindexdb
- Fix contrib/intarray error for zero-element result array (Teodor)
- Ensure createuser script will exit on control-C (Oliver)
- Fix errors when the type of a dropped column has itself been dropped
- `CHECKPOINT` does not cause database panic on failure in noncritical steps
- Accept 60 in seconds fields of timestamp, time, interval input values
- Issue notice, not error, if `TIMESTAMP`, `TIME`, or `INTERVAL` precision too large
- Fix `abstime-to-time` cast function (fix is not applied unless you initdb)
- Fix pg_proc entry for `timestampt_izone` (fix is not applied unless you initdb)
- Make `EXTRACT(EPOCH FROM timestamp without time zone)` treat input as local time
- `'now'::timestamptz` gave wrong answer if timezone changed earlier in transaction
- `HAVE_INT64_TIMESTAMP` code for time with timezone overwrote its input
- Accept `GLOBAL TEMP/TEMPORARY` as a synonym for `TEMPORARY`
- Avoid improper schema-privilege-check failure in foreign-key triggers
- Fix bugs in foreign-key triggers for `SET DEFAULT` action
- Fix incorrect time-qual check in row fetch for `UPDATE` and `DELETE` triggers
- Foreign-key clauses were parsed but ignored in `ALTER TABLE ADD COLUMN`
- Fix createlang script breakage for case where handler function already exists
- Fix misbehavior on zero-column tables in pg_dump, COPY, ANALYZE, other places

- Fix misbehavior of `func_error()` on type names containing '%'
- Fix misbehavior of `replace()` on strings containing '%'
- Regular-expression patterns containing certain multibyte characters failed
- Account correctly for `NULL`s in more cases in join size estimation
- Avoid conflict with system definition of `isblank()` function or macro
- Fix failure to convert large code point values in EUC_TW conversions (Tatsuo)
- Fix error recovery for `SSL_read`/`SSL_write` calls
- Don't do early constant-folding of type coercion expressions
- Validate page header fields immediately after reading in any page
- Repair incorrect check for ungrouped variables in unnamed joins
- Fix buffer overrun in `to_ascii` (Guido Notari)
- contrib/ltree fixes (Teodor)
- Fix core dump in deadlock detection on machines where char is unsigned
- Avoid running out of buffers in many-way indexscan (bug introduced in 7.3)
- Fix planner's selectivity estimation functions to handle domains properly
- Fix dbmirror memory-allocation bug (Steven Singer)
- Prevent infinite loop in `ln(numeric)` due to roundoff error
- `GROUP BY` got confused if there were multiple equal GROUP BY items
- Fix bad plan when inherited `UPDATE`/`DELETE` references another inherited table
- Prevent clustering on incomplete (partial or non-NULL-storing) indexes
- Service shutdown request at proper time if it arrives while still starting up
- Fix left-links in temporary indexes (could make backwards scans miss entries)
- Fix incorrect handling of client_encoding setting in postgresql.conf (Tatsuo)
- Fix failure to respond to `pg_ctl stop -m fast` after Async_NotifyHandler runs
- Fix SPI for case where rule contains multiple statements of the same type
- Fix problem with checking for wrong type of access privilege in rule query
- Fix problem with `EXCEPT` in `CREATE RULE`
- Prevent problem with dropping temp tables having serial columns
- Fix replace_vars_with_subplan_refs failure in complex views
- Fix regexp slowness in single-byte encodings (Tatsuo)
- Allow qualified type names in `CREATE CAST` and `DROP CAST`
- Accept `SETOF type[]`, which formerly had to be written `SETOF _type`

- Fix pg_dump core dump in some cases with procedural languages
- Force ISO datestyle in pg_dump output, for portability (Oliver)
- pg_dump failed to handle error return from `lo_read` (Oleg Drokin)
- pg_dumpall failed with groups having no members (Nick Eskelinen)
- pg_dumpall failed to recognize --globals-only switch
- pg_restore failed to restore blobs if -X disable-triggers is specified
- Repair intrafunction memory leak in plpgsql
- pltcl's `elog` command dumped core if given wrong parameters (Ian Harding)
- plpython used wrong value of `atttypmod` (Brad McLean)
- Fix improper quoting of boolean values in Python interface (D'Arcy)
- Added `addDataType()` method to PGConnection interface for JDBC
- Fixed various problems with updateable ResultSets for JDBC (Shawn Green)
- Fixed various problems with DatabaseMetaData for JDBC (Kris Jurka, Peter Royal)
- Fixed problem with parsing table ACLs in JDBC
- Better error message for character set conversion problems in JDBC

A.20. Release 7.3.2

Release date

2003-02-04

This release contains a variety of fixes for version 7.3.1.

A.20.1. Migration to Version 7.3.2

A dump/restore is *not* required for those running version 7.3.*.

A.20.2. Changes

- Restore creation of OID column in CREATE TABLE AS / SELECT INTO
- Fix pg_dump core dump when dumping views having comments
- Dump DEFERRABLE/INITIALLY DEFERRED constraints properly
- Fix UPDATE when child table's column numbering differs from parent
- Increase default value of max_fsm_relations
- Fix problem when fetching backwards in a cursor for a single-row query
- Make backward fetch work properly with cursor on SELECT DISTINCT query
- Fix problems with loading pg_dump files containing contrib/lo usage
- Fix problem with all-numeric user names

- Fix possible memory leak and core dump during disconnect in libpgtcl
- Make plpython's spi_execute command handle nulls properly (Andrew Bosma)
- Adjust plpython error reporting so that its regression test passes again
- Work with bison 1.875
- Handle mixed-case names properly in plpgsql's %type (Neil)
- Fix core dump in pltcl when executing a query rewritten by a rule
- Repair array subscript overruns (per report from Yichen Xie)
- Reduce MAX_TIME_PRECISION from 13 to 10 in floating-point case
- Correctly case-fold variable names in per-database and per-user settings
- Fix coredump in plpgsql's RETURN NEXT when SELECT into record returns no rows
- Fix outdated use of pg_type.typprtlen in python client interface
- Correctly handle fractional seconds in timestamps in JDBC driver
- Improve performance of getImportedKeys() in JDBC
- Make shared-library symlinks work standardly on HPUX (Giles)
- Repair inconsistent rounding behavior for timestamp, time, interval
- SSL negotiation fixes (Nathan Mueller)
- Make libpq's ~/.pgpass feature work when connecting with PQconnectDB
- Update my2pg, ora2pg
- Translation updates
- Add casts between types lo and oid in contrib/lo
- fastpath code now checks for privilege to call function

A.21. Release 7.3.1

Release date

2002-12-18

This release contains a variety of fixes for version 7.3.

A.21.1. Migration to Version 7.3.1

A dump/restore is *not* required for those running version 7.3. However, it should be noted that the main PostgreSQL interface library, libpq, has a new major version number for this release, which might require recompilation of client code in certain cases.

A.21.2. Changes

- Fix a core dump of COPY TO when client/server encodings don't match (Tom)

- Allow pg_dump to work with pre-7.2 servers (Philip)
- contrib/adddepend fixes (Tom)
- Fix problem with deletion of per-user/per-database config settings (Tom)
- contrib/vacuumlo fix (Tom)
- Allow 'password' encryption even when pg_shadow contains MD5 passwords (Bruce)
- contrib/dbmirror fix (Steven Singer)
- Optimizer fixes (Tom)
- contrib/tsearch fixes (Teodor Sigaev, Magnus)
- Allow locale names to be mixed case (Nicolai Tufar)
- Increment libpq library's major version number (Bruce)
- pg_hba.conf error reporting fixes (Bruce, Neil)
- Add SCO Openserver 5.0.4 as a supported platform (Bruce)
- Prevent EXPLAIN from crashing server (Tom)
- SSL fixes (Nathan Mueller)
- Prevent composite column creation via ALTER TABLE (Tom)

A.22. Release 7.3

Release date

2002-11-27

A.22.1. Overview

Major changes in this release:

Schemas

Schemas allow users to create objects in separate namespaces, so two people or applications can have tables with the same name. There is also a public schema for shared tables. Table/index creation can be restricted by removing privileges on the public schema.

Drop Column

PostgreSQL now supports the `ALTER TABLE ... DROP COLUMN` functionality.

Table Functions

Functions returning multiple rows and/or multiple columns are now much easier to use than before. You can call such a “table function” in the `SELECT FROM` clause, treating its output like a table. Also, PL/pgSQL functions can now return sets.

Prepared Queries

PostgreSQL now supports prepared queries, for improved performance.

Dependency Tracking

PostgreSQL now records object dependencies, which allows improvements in many areas. `DROP` statements now take either `CASCADE` or `RESTRICT` to control whether dependent objects are also dropped.

Privileges

Functions and procedural languages now have privileges, and functions can be defined to run with the privileges of their creator.

Internationalization

Both multibyte and locale support are now always enabled.

Logging

A variety of logging options have been enhanced.

Interfaces

A large number of interfaces have been moved to http://gborg.postgresql.org where they can be developed and released independently.

Functions/Identifiers

By default, functions can now take up to 32 parameters, and identifiers can be up to 63 bytes long. Also, `OPAQUE` is now deprecated: there are specific "pseudo-datatypes" to represent each of the former meanings of `OPAQUE` in function argument and result types.

A.22.2. Migration to Version 7.3

A dump/restore using pg_dump is required for those wishing to migrate data from any previous release. If your application examines the system catalogs, additional changes will be required due to the introduction of schemas in 7.3; for more information, see: http://developer.postgresql.org/~momjian/upgrade_tips_7.3.

Observe the following incompatibilities:

- Pre-6.3 clients are no longer supported.
- `pg_hba.conf` now has a column for the user name and additional features. Existing files need to be adjusted.
- Several `postgresql.conf` logging parameters have been renamed.
- `LIMIT #,#` has been disabled; use `LIMIT # OFFSET #`.
- `INSERT` statements with column lists must specify a value for each specified column. For example, `INSERT INTO tab (col1, col2) VALUES ('val1')` is now invalid. It's still allowed to supply fewer columns than expected if the `INSERT` does not have a column list.
- `serial` columns are no longer automatically `UNIQUE`; thus, an index will not automatically be created.
- A `SET` command inside an aborted transaction is now rolled back.
- `COPY` no longer considers missing trailing columns to be null. All columns need to be specified. (However, one can achieve a similar effect by specifying a column list in the `COPY` command.)
- The data type `timestamp` is now equivalent to `timestamp without time zone`, instead of `timestamp with time zone`.

- Pre-7.3 databases loaded into 7.3 will not have the new object dependencies for `serial` columns, unique constraints, and foreign keys. See the directory `contrib/adddepend/` for a detailed description and a script that will add such dependencies.
- An empty string (`''`) is no longer allowed as the input into an integer field. Formerly, it was silently interpreted as 0.

A.22.3. Changes

A.22.3.1. Server Operation

- Add pg_locks view to show locks (Neil)
- Security fixes for password negotiation memory allocation (Neil)
- Remove support for version 0 FE/BE protocol (PostgreSQL 6.2 and earlier) (Tom)
- Reserve the last few backend slots for superusers, add parameter superuser_reserved_connections to control this (Nigel J. Andrews)

A.22.3.2. Performance

- Improve startup by calling localtime() only once (Tom)
- Cache system catalog information in flat files for faster startup (Tom)
- Improve caching of index information (Tom)
- Optimizer improvements (Tom, Fernando Nasser)
- Catalog caches now store failed lookups (Tom)
- Hash function improvements (Neil)
- Improve performance of query tokenization and network handling (Peter)
- Speed improvement for large object restore (Mario Weilguni)
- Mark expired index entries on first lookup, saving later heap fetches (Tom)
- Avoid excessive NULL bitmap padding (Manfred Koizar)
- Add BSD-licensed qsort() for Solaris, for performance (Bruce)
- Reduce per-row overhead by four bytes (Manfred Koizar)
- Fix GEQO optimizer bug (Neil Conway)
- Make WITHOUT OID actually save four bytes per row (Manfred Koizar)
- Add default_statistics_target variable to specify ANALYZE buckets (Neil)
- Use local buffer cache for temporary tables so no WAL overhead (Tom)
- Improve free space map performance on large tables (Stephen Marshall, Tom)
- Improved WAL write concurrency (Tom)

A.22.3.3. Privileges

- Add privileges on functions and procedural languages (Peter)

- Add OWNER to CREATE DATABASE so superusers can create databases on behalf of unprivileged users (Gavin Sherry, Tom)
- Add new object privilege bits EXECUTE and USAGE (Tom)
- Add SET SESSION AUTHORIZATION DEFAULT and RESET SESSION AUTHORIZATION (Tom)
- Allow functions to be executed with the privilege of the function owner (Peter)

A.22.3.4. Server Configuration

- Server log messages now tagged with LOG, not DEBUG (Bruce)
- Add user column to pg_hba.conf (Bruce)
- Have log_connections output two lines in log file (Tom)
- Remove debug_level from postgresql.conf, now server_min_messages (Bruce)
- New ALTER DATABASE/USER ... SET command for per-user/database initialization (Peter)
- New parameters server_min_messages and client_min_messages to control which messages are sent to the server logs or client applications (Bruce)
- Allow pg_hba.conf to specify lists of users/databases separated by commas, group names prepended with +, and file names prepended with @ (Bruce)
- Remove secondary password file capability and pg_password utility (Bruce)
- Add variable db_user_namespace for database-local user names (Bruce)
- SSL improvements (Bear Giles)
- Make encryption of stored passwords the default (Bruce)
- Allow pg_statistics to be reset by calling pg_stat_reset() (Christopher)
- Add log_duration parameter (Bruce)
- Rename debug_print_query to log_statement (Bruce)
- Rename show_query_stats to show_statement_stats (Bruce)
- Add param log_min_error_statement to print commands to logs on error (Gavin)

A.22.3.5. Queries

- Make cursors insensitive, meaning their contents do not change (Tom)
- Disable LIMIT #,# syntax; now only LIMIT # OFFSET # supported (Bruce)
- Increase identifier length to 63 (Neil, Bruce)
- UNION fixes for merging >= 3 columns of different lengths (Tom)
- Add DEFAULT key word to INSERT, e.g., INSERT ... (..., DEFAULT, ...) (Rod)
- Allow views to have default values using ALTER COLUMN ... SET DEFAULT (Neil)
- Fail on INSERTs with column lists that don't supply all column values, e.g., INSERT INTO tab (col1, col2) VALUES ('val1'); (Rod)

- Fix for join aliases (Tom)
- Fix for FULL OUTER JOINs (Tom)
- Improve reporting of invalid identifier and location (Tom, Gavin)
- Fix OPEN cursor(args) (Tom)
- Allow 'ctid' to be used in a view and currtid(viewname) (Hiroshi)
- Fix for CREATE TABLE AS with UNION (Tom)
- SQL99 syntax improvements (Thomas)
- Add statement_timeout variable to cancel queries (Bruce)
- Allow prepared queries with PREPARE/EXECUTE (Neil)
- Allow FOR UPDATE to appear after LIMIT/OFFSET (Bruce)
- Add variable autocommit (Tom, David Van Wie)

A.22.3.6. Object Manipulation

- Make equals signs optional in CREATE DATABASE (Gavin Sherry)
- Make ALTER TABLE OWNER change index ownership too (Neil)
- New ALTER TABLE tabname ALTER COLUMN colname SET STORAGE controls TOAST storage, compression (John Gray)
- Add schema support, CREATE/DROP SCHEMA (Tom)
- Create schema for temporary tables (Tom)
- Add variable search_path for schema search (Tom)
- Add ALTER TABLE SET/DROP NOT NULL (Christopher)
- New CREATE FUNCTION volatility levels (Tom)
- Make rule names unique only per table (Tom)
- Add 'ON tablename' clause to DROP RULE and COMMENT ON RULE (Tom)
- Add ALTER TRIGGER RENAME (Joe)
- New current_schema() and current_schemas() inquiry functions (Tom)
- Allow functions to return multiple rows (table functions) (Joe)
- Make WITH optional in CREATE DATABASE, for consistency (Bruce)
- Add object dependency tracking (Rod, Tom)
- Add RESTRICT/CASCADE to DROP commands (Rod)
- Add ALTER TABLE DROP for non-CHECK CONSTRAINT (Rod)
- Autodestroy sequence on DROP of table with SERIAL (Rod)
- Prevent column dropping if column is used by foreign key (Rod)

- Automatically drop constraints/functions when object is dropped (Rod)
- Add CREATE/DROP OPERATOR CLASS (Bill Studenmund, Tom)
- Add ALTER TABLE DROP COLUMN (Christopher, Tom, Hiroshi)
- Prevent inherited columns from being removed or renamed (Alvaro Herrera)
- Fix foreign key constraints to not error on intermediate database states (Stephan)
- Propagate column or table renaming to foreign key constraints
- Add CREATE OR REPLACE VIEW (Gavin, Neil, Tom)
- Add CREATE OR REPLACE RULE (Gavin, Neil, Tom)
- Have rules execute alphabetically, returning more predictable values (Tom)
- Triggers are now fired in alphabetical order (Tom)
- Add /contrib/adddepend to handle pre-7.3 object dependencies (Rod)
- Allow better casting when inserting/updating values (Tom)

A.22.3.7. Utility Commands

- Have COPY TO output embedded carriage returns and newlines as \r and \n (Tom)
- Allow DELIMITER in COPY FROM to be 8-bit clean (Tatsuo)
- Make pg_dump use ALTER TABLE ADD PRIMARY KEY, for performance (Neil)
- Disable brackets in multistatement rules (Bruce)
- Disable VACUUM from being called inside a function (Bruce)
- Allow dropdb and other scripts to use identifiers with spaces (Bruce)
- Restrict database comment changes to the current database
- Allow comments on operators, independent of the underlying function (Rod)
- Rollback SET commands in aborted transactions (Tom)
- EXPLAIN now outputs as a query (Tom)
- Display condition expressions and sort keys in EXPLAIN (Tom)
- Add 'SET LOCAL var = value' to set configuration variables for a single transaction (Tom)
- Allow ANALYZE to run in a transaction (Bruce)
- Improve COPY syntax using new WITH clauses, keep backward compatibility (Bruce)
- Fix pg_dump to consistently output tags in non-ASCII dumps (Bruce)
- Make foreign key constraints clearer in dump file (Rod)
- Add COMMENT ON CONSTRAINT (Rod)
- Allow COPY TO/FROM to specify column names (Brent Verner)
- Dump UNIQUE and PRIMARY KEY constraints as ALTER TABLE (Rod)

- Have SHOW output a query result (Joe)
- Generate failure on short COPY lines rather than pad NULLs (Neil)
- Fix CLUSTER to preserve all table attributes (Alvaro Herrera)
- New pg_settings table to view/modify GUC settings (Joe)
- Add smart quoting, portability improvements to pg_dump output (Peter)
- Dump serial columns out as SERIAL (Tom)
- Enable large file support, >2G for pg_dump (Peter, Philip Warner, Bruce)
- Disallow TRUNCATE on tables that are involved in referential constraints (Rod)
- Have TRUNCATE also auto-truncate the toast table of the relation (Tom)
- Add clusterdb utility that will auto-cluster an entire database based on previous CLUSTER operations (Alvaro Herrera)
- Overhaul pg_dumpall (Peter)
- Allow REINDEX of TOAST tables (Tom)
- Implemented START TRANSACTION, per SQL99 (Neil)
- Fix rare index corruption when a page split affects bulk delete (Tom)
- Fix ALTER TABLE ... ADD COLUMN for inheritance (Alvaro Herrera)

A.22.3.8. Data Types and Functions

- Fix factorial(0) to return 1 (Bruce)
- Date/time/timezone improvements (Thomas)
- Fix for array slice extraction (Tom)
- Fix extract/date_part to report proper microseconds for timestamp (Tatsuo)
- Allow text_substr() and bytea_substr() to read TOAST values more efficiently (John Gray)
- Add domain support (Rod)
- Make WITHOUT TIME ZONE the default for TIMESTAMP and TIME data types (Thomas)
- Allow alternate storage scheme of 64-bit integers for date/time types using --enable-integer-datetimes in configure (Thomas)
- Make timezone(timestamptz) return timestamp rather than a string (Thomas)
- Allow fractional seconds in date/time types for dates prior to 1BC (Thomas)
- Limit timestamp data types to 6 decimal places of precision (Thomas)
- Change timezone conversion functions from timetz() to timezone() (Thomas)
- Add configuration variables datestyle and timezone (Tom)
- Add OVERLAY(), which allows substitution of a substring in a string (Thomas)

- Add SIMILAR TO (Thomas, Tom)
- Add regular expression SUBSTRING(string FROM pat FOR escape) (Thomas)
- Add LOCALTIME and LOCALTIMESTAMP functions (Thomas)
- Add named composite types using CREATE TYPE typename AS (column) (Joe)
- Allow composite type definition in the table alias clause (Joe)
- Add new API to simplify creation of C language table functions (Joe)
- Remove ODBC-compatible empty parentheses from calls to SQL99 functions for which these parentheses do not match the standard (Thomas)
- Allow macaddr data type to accept 12 hex digits with no separators (Mike Wyer)
- Add CREATE/DROP CAST (Peter)
- Add IS DISTINCT FROM operator (Thomas)
- Add SQL99 TREAT() function, synonym for CAST() (Thomas)
- Add pg_backend_pid() to output backend pid (Bruce)
- Add IS OF / IS NOT OF type predicate (Thomas)
- Allow bit string constants without fully-specified length (Thomas)
- Allow conversion between 8-byte integers and bit strings (Thomas)
- Implement hex literal conversion to bit string literal (Thomas)
- Allow table functions to appear in the FROM clause (Joe)
- Increase maximum number of function parameters to 32 (Bruce)
- No longer automatically create index for SERIAL column (Tom)
- Add current_database() (Rod)
- Fix cash_words() to not overflow buffer (Tom)
- Add functions replace(), split_part(), to_hex() (Joe)
- Fix LIKE for bytea as a right-hand argument (Joe)
- Prevent crashes caused by SELECT cash_out(2) (Tom)
- Fix to_char(1,'FM999.99') to return a period (Karel)
- Fix trigger/type/language functions returning OPAQUE to return proper type (Tom)

A.22.3.9. Internationalization

- Add additional encodings: Korean (JOHAB), Thai (WIN874), Vietnamese (TCVN), Arabic (WIN1256), Simplified Chinese (GBK), Korean (UHC) (Eiji Tokuya)
- Enable locale support by default (Peter)
- Add locale variables (Peter)

- Escape byes >= 0x7f for multibyte in PQescapeBytea/PQunescapeBytea (Tatsuo)
- Add locale awareness to regular expression character classes
- Enable multibyte support by default (Tatsuo)
- Add GB18030 multibyte support (Bill Huang)
- Add CREATE/DROP CONVERSION, allowing loadable encodings (Tatsuo, Kaori)
- Add pg_conversion table (Tatsuo)
- Add SQL99 CONVERT() function (Tatsuo)
- pg_dumpall, pg_controldata, and pg_resetxlog now national-language aware (Peter)
- New and updated translations

A.22.3.10. Server-side Languages

- Allow recursive SQL function (Peter)
- Change PL/Tcl build to use configured compiler and Makefile.shlib (Peter)
- Overhaul the PL/pgSQL FOUND variable to be more Oracle-compatible (Neil, Tom)
- Allow PL/pgSQL to handle quoted identifiers (Tom)
- Allow set-returning PL/pgSQL functions (Neil)
- Make PL/pgSQL schema-aware (Joe)
- Remove some memory leaks (Nigel J. Andrews, Tom)

A.22.3.11. psql

- Don't lowercase psql \connect database name for 7.2.0 compatibility (Tom)
- Add psql \timing to time user queries (Greg Sabino Mullane)
- Have psql \d show index information (Greg Sabino Mullane)
- New psql \dD shows domains (Jonathan Eisler)
- Allow psql to show rules on views (Paul ?)
- Fix for psql variable substitution (Tom)
- Allow psql \d to show temporary table structure (Tom)
- Allow psql \d to show foreign keys (Rod)
- Fix \? to honor \pset pager (Bruce)
- Have psql reports its version number on startup (Tom)
- Allow \copy to specify column names (Tom)

A.22.3.12. libpq

- Add ~/.pgpass to store host/user password combinations (Alvaro Herrera)

- Add PQunescapeBytea() function to libpq (Patrick Welche)
- Fix for sending large queries over non-blocking connections (Bernhard Herzog)
- Fix for libpq using timers on Win9X (David Ford)
- Allow libpq notify to handle servers with different-length identifiers (Tom)
- Add libpq PQescapeString() and PQescapeBytea() to Windows (Bruce)
- Fix for SSL with non-blocking connections (Jack Bates)
- Add libpq connection timeout parameter (Denis A Ustimenko)

A.22.3.13. JDBC

- Allow JDBC to compile with JDK 1.4 (Dave)
- Add JDBC 3 support (Barry)
- Allows JDBC to set loglevel by adding ?loglevel=X to the connection URL (Barry)
- Add Driver.info() message that prints out the version number (Barry)
- Add updateable result sets (Raghu Nidagal, Dave)
- Add support for callable statements (Paul Bethe)
- Add query cancel capability
- Add refresh row (Dave)
- Fix MD5 encryption handling for multibyte servers (Jun Kawai)
- Add support for prepared statements (Barry)

A.22.3.14. Miscellaneous Interfaces

- Fixed ECPG bug concerning octal numbers in single quotes (Michael)
- Move src/interfaces/libpgeasy to http://gborg.postgresql.org (Marc, Bruce)
- Improve Python interface (Elliot Lee, Andrew Johnson, Greg Copeland)
- Add libpgtcl connection close event (Gerhard Hintermayer)
- Move src/interfaces/libpq++ to http://gborg.postgresql.org (Marc, Bruce)
- Move src/interfaces/odbc to http://gborg.postgresql.org (Marc)
- Move src/interfaces/libpgeasy to http://gborg.postgresql.org (Marc, Bruce)
- Move src/interfaces/perl5 to http://gborg.postgresql.org (Marc, Bruce)
- Remove src/bin/pgaccess from main tree, now at http://www.pgaccess.org (Bruce)
- Add pg_on_connection_loss command to libpgtcl (Gerhard Hintermayer, Tom)

A.22.3.15. Source Code

- Fix for parallel make (Peter)

- AIX fixes for linking Tcl (Andreas Zeugswetter)
- Allow PL/Perl to build under Cygwin (Jason Tishler)
- Improve MIPS compiles (Peter, Oliver Elphick)
- Require Autoconf version 2.53 (Peter)
- Require readline and zlib by default in configure (Peter)
- Allow Solaris to use Intimate Shared Memory (ISM), for performance (Scott Brunza, P.J. Josh Rovero)
- Always enable syslog in compile, remove --enable-syslog option (Tatsuo)
- Always enable multibyte in compile, remove --enable-multibyte option (Tatsuo)
- Always enable locale in compile, remove --enable-locale option (Peter)
- Fix for Win9x DLL creation (Magnus Naeslund)
- Fix for link() usage by WAL code on Windows, BeOS (Jason Tishler)
- Add sys/types.h to c.h, remove from main files (Peter, Bruce)
- Fix AIX hang on SMP machines (Tomoyuki Niijima)
- AIX SMP hang fix (Tomoyuki Niijima)
- Fix pre-1970 date handling on newer glibc libraries (Tom)
- Fix PowerPC SMP locking (Tom)
- Prevent gcc -ffast-math from being used (Peter, Tom)
- Bison >= 1.50 now required for developer builds
- Kerberos 5 support now builds with Heimdal (Peter)
- Add appendix in the User's Guide which lists SQL features (Thomas)
- Improve loadable module linking to use RTLD_NOW (Tom)
- New error levels WARNING, INFO, LOG, DEBUG[1-5] (Bruce)
- New src/port directory holds replaced libc functions (Peter, Bruce)
- New pg_namespace system catalog for schemas (Tom)
- Add pg_class.relnamespace for schemas (Tom)
- Add pg_type.typnamespace for schemas (Tom)
- Add pg_proc.pronamespace for schemas (Tom)
- Restructure aggregates to have pg_proc entries (Tom)
- System relations now have their own namespace, pg_* test not required (Fernando Nasser)
- Rename TOAST index names to be *_index rather than *_idx (Neil)
- Add namespaces for operators, opclasses (Tom)

- Add additional checks to server control file (Thomas)
- New Polish FAQ (Marcin Mazurek)
- Add Posix semaphore support (Tom)
- Document need for reindex (Bruce)
- Rename some internal identifiers to simplify Windows compile (Jan, Katherine Ward)
- Add documentation on computing disk space (Bruce)
- Remove KSQO from GUC (Bruce)
- Fix memory leak in rtree (Kenneth Been)
- Modify a few error messages for consistency (Bruce)
- Remove unused system table columns (Peter)
- Make system columns NOT NULL where appropriate (Tom)
- Clean up use of sprintf in favor of snprintf() (Neil, Jukka Holappa)
- Remove OPAQUE and create specific subtypes (Tom)
- Cleanups in array internal handling (Joe, Tom)
- Disallow pg_atoi('') (Bruce)
- Remove parameter wal_files because WAL files are now recycled (Bruce)
- Add version numbers to heap pages (Tom)

A.22.3.16. Contrib

- Allow inet arrays in /contrib/array (Neil)
- GiST fixes (Teodor Sigaev, Neil)
- Upgrade /contrib/mysql
- Add /contrib/dbsize which shows table sizes without vacuum (Peter)
- Add /contrib/intagg, integer aggregator routines (mlw)
- Improve /contrib/oid2name (Neil, Bruce)
- Improve /contrib/tsearch (Oleg, Teodor Sigaev)
- Cleanups of /contrib/rserver (Alexey V. Borzov)
- Update /contrib/oracle conversion utility (Gilles Darold)
- Update /contrib/dblink (Joe)
- Improve options supported by /contrib/vacuumlo (Mario Weilguni)
- Improvements to /contrib/intarray (Oleg, Teodor Sigaev, Andrey Oktyabrski)
- Add /contrib/reindexdb utility (Shaun Thomas)

- Add indexing to /contrib/isbn_issn (Dan Weston)
- Add /contrib/dbmirror (Steven Singer)
- Improve /contrib/pgbench (Neil)
- Add /contrib/tablefunc table function examples (Joe)
- Add /contrib/ltree data type for tree structures (Teodor Sigaev, Oleg Bartunov)
- Move /contrib/pg_controldata, pg_resetxlog into main tree (Bruce)
- Fixes to /contrib/cube (Bruno Wolff)
- Improve /contrib/fulltextindex (Christopher)

A.23. Release 7.2.8

Release date

2005-05-09

This release contains a variety of fixes from 7.2.7, including one security-related issue.

A.23.1. Migration to Version 7.2.8

A dump/restore is not required for those running 7.2.X.

A.23.2. Changes

- Repair ancient race condition that allowed a transaction to be seen as committed for some purposes (eg SELECT FOR UPDATE) slightly sooner than for other purposes

  This is an extremely serious bug since it could lead to apparent data inconsistencies being briefly visible to applications.

- Repair race condition between relation extension and VACUUM

  This could theoretically have caused loss of a page's worth of freshly-inserted data, although the scenario seems of very low probability. There are no known cases of it having caused more than an Assert failure.

- Fix `EXTRACT(EPOCH)` for `TIME WITH TIME ZONE` values
- Additional buffer overrun checks in plpgsql (Neil)
- Fix pg_dump to dump index names and trigger names containing `%` correctly (Neil)
- Prevent `to_char(interval)` from dumping core for month-related formats
- Fix `contrib/pgcrypto` for newer OpenSSL builds (Marko Kreen)

A.24. Release 7.2.7

Release date

2005-01-31

This release contains a variety of fixes from 7.2.6, including several security-related issues.

A.24.1. Migration to Version 7.2.7

A dump/restore is not required for those running 7.2.X.

A.24.2. Changes

- Disallow `LOAD` to non-superusers

  On platforms that will automatically execute initialization functions of a shared library (this includes at least Windows and ELF-based Unixen), `LOAD` can be used to make the server execute arbitrary code. Thanks to NGS Software for reporting this.

- Add needed STRICT marking to some contrib functions (Kris Jurka)

- Avoid buffer overrun when plpgsql cursor declaration has too many parameters (Neil)

- Fix planning error for FULL and RIGHT outer joins

  The result of the join was mistakenly supposed to be sorted the same as the left input. This could not only deliver mis-sorted output to the user, but in case of nested merge joins could give outright wrong answers.

- Fix display of negative intervals in SQL and GERMAN datestyles

A.25. Release 7.2.6

Release date

2004-10-22

This release contains a variety of fixes from 7.2.5.

A.25.1. Migration to Version 7.2.6

A dump/restore is not required for those running 7.2.X.

A.25.2. Changes

- Repair possible failure to update hint bits on disk

  Under rare circumstances this oversight could lead to “could not access transaction status” failures, which qualifies it as a potential-data-loss bug.

- Ensure that hashed outer join does not miss tuples

  Very large left joins using a hash join plan could fail to output unmatched left-side rows given just the right data distribution.

- Disallow running pg_ctl as root

  This is to guard against any possible security issues.

- Avoid using temp files in /tmp in make_oidjoins_check

  This has been reported as a security issue, though it's hardly worthy of concern since there is no reason for non-developers to use this script anyway.

- Update to newer versions of Bison

A.26. Release 7.2.5

Release date

2004-08-16

This release contains a variety of fixes from 7.2.4.

A.26.1. Migration to Version 7.2.5

A dump/restore is not required for those running 7.2.X.

A.26.2. Changes

- Prevent possible loss of committed transactions during crash

  Due to insufficient interlocking between transaction commit and checkpointing, it was possible for transactions committed just before the most recent checkpoint to be lost, in whole or in part, following a database crash and restart. This is a serious bug that has existed since PostgreSQL 7.1.

- Fix corner case for btree search in parallel with first root page split
- Fix buffer overrun in `to_ascii` (Guido Notari)
- Fix core dump in deadlock detection on machines where char is unsigned
- Fix failure to respond to `pg_ctl stop -m fast` after Async_NotifyHandler runs
- Repair memory leaks in pg_dump
- Avoid conflict with system definition of `isblank()` function or macro

A.27. Release 7.2.4

Release date

2003-01-30

This release contains a variety of fixes for version 7.2.3, including fixes to prevent possible data loss.

A.27.1. Migration to Version 7.2.4

A dump/restore is *not* required for those running version 7.2.*.

A.27.2. Changes

- Fix some additional cases of VACUUM "No one parent tuple was found" error
- Prevent VACUUM from being called inside a function (Bruce)
- Ensure pg_clog updates are sync'd to disk before marking checkpoint complete
- Avoid integer overflow during large hash joins
- Make GROUP commands work when pg_group.grolist is large enough to be toasted

- Fix errors in datetime tables; some timezone names weren't being recognized
- Fix integer overflows in circle_poly(), path_encode(), path_add() (Neil)
- Repair long-standing logic errors in lseg_eq(), lseg_ne(), lseg_center()

A.28. Release 7.2.3

Release date

2002-10-01

This release contains a variety of fixes for version 7.2.2, including fixes to prevent possible data loss.

A.28.1. Migration to Version 7.2.3

A dump/restore is *not* required for those running version 7.2.*.

A.28.2. Changes

- Prevent possible compressed transaction log loss (Tom)
- Prevent non-superuser from increasing most recent vacuum info (Tom)
- Handle pre-1970 date values in newer versions of glibc (Tom)
- Fix possible hang during server shutdown
- Prevent spinlock hangs on SMP PPC machines (Tomoyuki Niijima)
- Fix pg_dump to properly dump FULL JOIN USING (Tom)

A.29. Release 7.2.2

Release date

2002-08-23

This release contains a variety of fixes for version 7.2.1.

A.29.1. Migration to Version 7.2.2

A dump/restore is *not* required for those running version 7.2.*.

A.29.2. Changes

- Allow EXECUTE of "CREATE TABLE AS ... SELECT" in PL/pgSQL (Tom)
- Fix for compressed transaction log id wraparound (Tom)
- Fix PQescapeBytea/PQunescapeBytea so that they handle bytes > 0x7f (Tatsuo)
- Fix for psql and pg_dump crashing when invoked with non-existent long options (Tatsuo)
- Fix crash when invoking geometric operators (Tom)
- Allow OPEN cursor(args) (Tom)

- Fix for rtree_gist index build (Teodor)
- Fix for dumping user-defined aggregates (Tom)
- contrib/intarray fixes (Oleg)
- Fix for complex UNION/EXCEPT/INTERSECT queries using parens (Tom)
- Fix to pg_convert (Tatsuo)
- Fix for crash with long DATA strings (Thomas, Neil)
- Fix for repeat(), lpad(), rpad() and long strings (Neil)

A.30. Release 7.2.1

Release date

2002-03-21

This release contains a variety of fixes for version 7.2.

A.30.1. Migration to Version 7.2.1

A dump/restore is *not* required for those running version 7.2.

A.30.2. Changes

- Ensure that sequence counters do not go backwards after a crash (Tom)
- Fix pgaccess kanji-conversion key binding (Tatsuo)
- Optimizer improvements (Tom)
- Cash I/O improvements (Tom)
- New Russian FAQ
- Compile fix for missing AuthBlockSig (Heiko)
- Additional time zones and time zone fixes (Thomas)
- Allow psql \connect to handle mixed case database and user names (Tom)
- Return proper OID on command completion even with ON INSERT rules (Tom)
- Allow COPY FROM to use 8-bit DELIMITERS (Tatsuo)
- Fix bug in extract/date_part for milliseconds/microseconds (Tatsuo)
- Improve handling of multiple UNIONs with different lengths (Tom)
- contrib/btree_gist improvements (Teodor Sigaev)
- contrib/tsearch dictionary improvements, see README.tsearch for an additional installation step (Thomas T. Thai, Teodor Sigaev)
- Fix for array subscripts handling (Tom)
- Allow EXECUTE of "CREATE TABLE AS ... SELECT" in PL/pgSQL (Tom)

A.31. Release 7.2

Release date

2002-02-04

A.31.1. Overview

This release improves PostgreSQL for use in high-volume applications.

Major changes in this release:

VACUUM

Vacuuming no longer locks tables, thus allowing normal user access during the vacuum. A new `VACUUM FULL` command does old-style vacuum by locking the table and shrinking the on-disk copy of the table.

Transactions

There is no longer a problem with installations that exceed four billion transactions.

OIDs

OIDs are now optional. Users can now create tables without OIDs for cases where OID usage is excessive.

Optimizer

The system now computes histogram column statistics during `ANALYZE`, allowing much better optimizer choices.

Security

A new MD5 encryption option allows more secure storage and transfer of passwords. A new Unix-domain socket authentication option is available on Linux and BSD systems.

Statistics

Administrators can use the new table access statistics module to get fine-grained information about table and index usage.

Internationalization

Program and library messages can now be displayed in several languages.

A.31.2. Migration to Version 7.2

A dump/restore using `pg_dump` is required for those wishing to migrate data from any previous release.

Observe the following incompatibilities:

- The semantics of the `VACUUM` command have changed in this release. You might wish to update your maintenance procedures accordingly.
- In this release, comparisons using `= NULL` will always return false (or NULL, more precisely). Previous releases automatically transformed this syntax to `IS NULL`. The old behavior can be re-enabled using a `postgresql.conf` parameter.

- The `pg_hba.conf` and `pg_ident.conf` configuration is now only reloaded after receiving a SIGHUP signal, not with each connection.
- The function `octet_length()` now returns the uncompressed data length.
- The date/time value `'current'` is no longer available. You will need to rewrite your applications.
- The `timestamp()`, `time()`, and `interval()` functions are no longer available. Instead of `timestamp()`, use `timestamp 'string'` or `CAST`.

The `SELECT ... LIMIT #,#` syntax will be removed in the next release. You should change your queries to use separate LIMIT and OFFSET clauses, e.g. `LIMIT 10 OFFSET 20`.

A.31.3. Changes

A.31.3.1. Server Operation

- Create temporary files in a separate directory (Bruce)
- Delete orphaned temporary files on postmaster startup (Bruce)
- Added unique indexes to some system tables (Tom)
- System table operator reorganization (Oleg Bartunov, Teodor Sigaev, Tom)
- Renamed pg_log to pg_clog (Tom)
- Enable SIGTERM, SIGQUIT to kill backends (Jan)
- Removed compile-time limit on number of backends (Tom)
- Better cleanup for semaphore resource failure (Tatsuo, Tom)
- Allow safe transaction ID wraparound (Tom)
- Removed OIDs from some system tables (Tom)
- Removed "triggered data change violation" error check (Tom)
- SPI portal creation of prepared/saved plans (Jan)
- Allow SPI column functions to work for system columns (Tom)
- Long value compression improvement (Tom)
- Statistics collector for table, index access (Jan)
- Truncate extra-long sequence names to a reasonable value (Tom)
- Measure transaction times in milliseconds (Thomas)
- Fix TID sequential scans (Hiroshi)
- Superuser ID now fixed at 1 (Peter E)
- New pg_ctl "reload" option (Tom)

A.31.3.2. Performance

- Optimizer improvements (Tom)

- New histogram column statistics for optimizer (Tom)
- Reuse write-ahead log files rather than discarding them (Tom)
- Cache improvements (Tom)
- IS NULL, IS NOT NULL optimizer improvement (Tom)
- Improve lock manager to reduce lock contention (Tom)
- Keep relcache entries for index access support functions (Tom)
- Allow better selectivity with NaN and infinities in NUMERIC (Tom)
- R-tree performance improvements (Kenneth Been)
- B-tree splits more efficient (Tom)

A.31.3.3. Privileges

- Change UPDATE, DELETE privileges to be distinct (Peter E)
- New REFERENCES, TRIGGER privileges (Peter E)
- Allow GRANT/REVOKE to/from more than one user at a time (Peter E)
- New has_table_privilege() function (Joe Conway)
- Allow non-superuser to vacuum database (Tom)
- New SET SESSION AUTHORIZATION command (Peter E)
- Fix bug in privilege modifications on newly created tables (Tom)
- Disallow access to pg_statistic for non-superuser, add user-accessible views (Tom)

A.31.3.4. Client Authentication

- Fork postmaster before doing authentication to prevent hangs (Peter E)
- Add ident authentication over Unix domain sockets on Linux, *BSD (Helge Bahmann, Oliver Elphick, Teodor Sigaev, Bruce)
- Add a password authentication method that uses MD5 encryption (Bruce)
- Allow encryption of stored passwords using MD5 (Bruce)
- PAM authentication (Dominic J. Eidson)
- Load pg_hba.conf and pg_ident.conf only on startup and SIGHUP (Bruce)

A.31.3.5. Server Configuration

- Interpretation of some time zone abbreviations as Australian rather than North American now settable at run time (Bruce)
- New parameter to set default transaction isolation level (Peter E)
- New parameter to enable conversion of "expr = NULL" into "expr IS NULL", off by default (Peter E)
- New parameter to control memory usage by VACUUM (Tom)

- New parameter to set client authentication timeout (Tom)
- New parameter to set maximum number of open files (Tom)

A.31.3.6. Queries

- Statements added by INSERT rules now execute after the INSERT (Jan)
- Prevent unadorned relation names in target list (Bruce)
- NULLs now sort after all normal values in ORDER BY (Tom)
- New IS UNKNOWN, IS NOT UNKNOWN Boolean tests (Tom)
- New SHARE UPDATE EXCLUSIVE lock mode (Tom)
- New EXPLAIN ANALYZE command that shows run times and row counts (Martijn van Oosterhout)
- Fix problem with LIMIT and subqueries (Tom)
- Fix for LIMIT, DISTINCT ON pushed into subqueries (Tom)
- Fix nested EXCEPT/INTERSECT (Tom)

A.31.3.7. Schema Manipulation

- Fix SERIAL in temporary tables (Bruce)
- Allow temporary sequences (Bruce)
- Sequences now use int8 internally (Tom)
- New SERIAL8 creates int8 columns with sequences, default still SERIAL4 (Tom)
- Make OIDs optional using WITHOUT OIDS (Tom)
- Add %TYPE syntax to CREATE TYPE (Ian Lance Taylor)
- Add ALTER TABLE / DROP CONSTRAINT for CHECK constraints (Christopher Kings-Lynne)
- New CREATE OR REPLACE FUNCTION to alter existing function (preserving the function OID) (Gavin Sherry)
- Add ALTER TABLE / ADD [UNIQUE | PRIMARY] (Christopher Kings-Lynne)
- Allow column renaming in views
- Make ALTER TABLE / RENAME COLUMN update column names of indexes (Brent Verner)
- Fix for ALTER TABLE / ADD CONSTRAINT ... CHECK with inherited tables (Stephan Szabo)
- ALTER TABLE RENAME update foreign-key trigger arguments correctly (Brent Verner)
- DROP AGGREGATE and COMMENT ON AGGREGATE now accept an aggtype (Tom)
- Add automatic return type data casting for SQL functions (Tom)
- Allow GiST indexes to handle NULLs and multikey indexes (Oleg Bartunov, Teodor Sigaev, Tom)
- Enable partial indexes (Martijn van Oosterhout)

A.31.3.8. Utility Commands

- Add RESET ALL, SHOW ALL (Marko Kreen)
- CREATE/ALTER USER/GROUP now allow options in any order (Vince)
- Add LOCK A, B, C functionality (Neil Padgett)
- New ENCRYPTED/UNENCRYPTED option to CREATE/ALTER USER (Bruce)
- New light-weight VACUUM does not lock table; old semantics are available as VACUUM FULL (Tom)
- Disable COPY TO/FROM on views (Bruce)
- COPY DELIMITERS string must be exactly one character (Tom)
- VACUUM warning about index tuples fewer than heap now only appears when appropriate (Martijn van Oosterhout)
- Fix privilege checks for CREATE INDEX (Tom)
- Disallow inappropriate use of CREATE/DROP INDEX/TRIGGER/VIEW (Tom)

A.31.3.9. Data Types and Functions

- SUM(), AVG(), COUNT() now uses int8 internally for speed (Tom)
- Add convert(), convert2() (Tatsuo)
- New function bit_length() (Peter E)
- Make the "n" in CHAR(n)/VARCHAR(n) represents letters, not bytes (Tatsuo)
- CHAR(), VARCHAR() now reject strings that are too long (Peter E)
- BIT VARYING now rejects bit strings that are too long (Peter E)
- BIT now rejects bit strings that do not match declared size (Peter E)
- INET, CIDR text conversion functions (Alex Pilosov)
- INET, CIDR operators << and <<= indexable (Alex Pilosov)
- Bytea \### now requires valid three digit octal number
- Bytea comparison improvements, now supports =, <>, >, >=, <, and <=
- Bytea now supports B-tree indexes
- Bytea now supports LIKE, LIKE...ESCAPE, NOT LIKE, NOT LIKE...ESCAPE
- Bytea now supports concatenation
- New bytea functions: position, substring, trim, btrim, and length
- New encode() function mode, "escaped", converts minimally escaped bytea to/from text
- Add pg_database_encoding_max_length() (Tatsuo)
- Add pg_client_encoding() function (Tatsuo)
- now() returns time with millisecond precision (Thomas)

- New TIMESTAMP WITHOUT TIMEZONE data type (Thomas)
- Add ISO date/time specification with "T", yyyy-mm-ddThh:mm:ss (Thomas)
- New xid/int comparison functions (Hiroshi)
- Add precision to TIME, TIMESTAMP, and INTERVAL data types (Thomas)
- Modify type coercion logic to attempt binary-compatible functions first (Tom)
- New encode() function installed by default (Marko Kreen)
- Improved to_*() conversion functions (Karel Zak)
- Optimize LIKE/ILIKE when using single-byte encodings (Tatsuo)
- New functions in contrib/pgcrypto: crypt(), hmac(), encrypt(), gen_salt() (Marko Kreen)
- Correct description of translate() function (Bruce)
- Add INTERVAL argument for SET TIME ZONE (Thomas)
- Add INTERVAL YEAR TO MONTH (etc.) syntax (Thomas)
- Optimize length functions when using single-byte encodings (Tatsuo)
- Fix path_inter, path_distance, path_length, dist_ppath to handle closed paths (Curtis Barrett, Tom)
- octet_length(text) now returns non-compressed length (Tatsuo, Bruce)
- Handle "July" full name in date/time literals (Greg Sabino Mullane)
- Some datatype() function calls now evaluated differently
- Add support for Julian and ISO time specifications (Thomas)

A.31.3.10. Internationalization

- National language support in psql, pg_dump, libpq, and server (Peter E)
- Message translations in Chinese (simplified, traditional), Czech, French, German, Hungarian, Russian, Swedish (Peter E, Serguei A. Mokhov, Karel Zak, Weiping He, Zhenbang Wei, Kovacs Zoltan)
- Make trim, ltrim, rtrim, btrim, lpad, rpad, translate multibyte aware (Tatsuo)
- Add LATIN5,6,7,8,9,10 support (Tatsuo)
- Add ISO 8859-5,6,7,8 support (Tatsuo)
- Correct LATIN5 to mean ISO-8859-9, not ISO-8859-5 (Tatsuo)
- Make mic2ascii() non-ASCII aware (Tatsuo)
- Reject invalid multibyte character sequences (Tatsuo)

A.31.3.11. PL/pgSQL

- Now uses portals for SELECT loops, allowing huge result sets (Jan)
- CURSOR and REFCURSOR support (Jan)
- Can now return open cursors (Jan)

- Add ELSEIF (Klaus Reger)
- Improve PL/pgSQL error reporting, including location of error (Tom)
- Allow IS or FOR key words in cursor declaration, for compatibility (Bruce)
- Fix for SELECT ... FOR UPDATE (Tom)
- Fix for PERFORM returning multiple rows (Tom)
- Make PL/pgSQL use the server's type coercion code (Tom)
- Memory leak fix (Jan, Tom)
- Make trailing semicolon optional (Tom)

A.31.3.12. PL/Perl

- New untrusted PL/Perl (Alex Pilosov)
- PL/Perl is now built on some platforms even if libperl is not shared (Peter E)

A.31.3.13. PL/Tcl

- Now reports errorInfo (Vsevolod Lobko)
- Add spi_lastoid function (bob@redivi.com)

A.31.3.14. PL/Python

- ...is new (Andrew Bosma)

A.31.3.15. psql

- \d displays indexes in unique, primary groupings (Christopher Kings-Lynne)
- Allow trailing semicolons in backslash commands (Greg Sabino Mullane)
- Read password from /dev/tty if possible
- Force new password prompt when changing user and database (Tatsuo, Tom)
- Format the correct number of columns for Unicode (Patrice)

A.31.3.16. libpq

- New function PQescapeString() to escape quotes in command strings (Florian Weimer)
- New function PQescapeBytea() escapes binary strings for use as SQL string literals

A.31.3.17. JDBC

- Return OID of INSERT (Ken K)
- Handle more data types (Ken K)
- Handle single quotes and newlines in strings (Ken K)
- Handle NULL variables (Ken K)
- Fix for time zone handling (Barry Lind)

- Improved Druid support
- Allow eight-bit characters with non-multibyte server (Barry Lind)
- Support BIT, BINARY types (Ned Wolpert)
- Reduce memory usage (Michael Stephens, Dave Cramer)
- Update DatabaseMetaData (Peter E)
- Add DatabaseMetaData.getCatalogs() (Peter E)
- Encoding fixes (Anders Bengtsson)
- Get/setCatalog methods (Jason Davies)
- DatabaseMetaData.getColumns() now returns column defaults (Jason Davies)
- DatabaseMetaData.getColumns() performance improvement (Jeroen van Vianen)
- Some JDBC1 and JDBC2 merging (Anders Bengtsson)
- Transaction performance improvements (Barry Lind)
- Array fixes (Greg Zoller)
- Serialize addition
- Fix batch processing (Rene Pijlman)
- ExecSQL method reorganization (Anders Bengtsson)
- GetColumn() fixes (Jeroen van Vianen)
- Fix isWriteable() function (Rene Pijlman)
- Improved passage of JDBC2 conformance tests (Rene Pijlman)
- Add bytea type capability (Barry Lind)
- Add isNullable() (Rene Pijlman)
- JDBC date/time test suite fixes (Liam Stewart)
- Fix for SELECT 'id' AS xxx FROM table (Dave Cramer)
- Fix DatabaseMetaData to show precision properly (Mark Lillywhite)
- New getImported/getExported keys (Jason Davies)
- MD5 password encryption support (Jeremy Wohl)
- Fix to actually use type cache (Ned Wolpert)

A.31.3.18. ODBC

- Remove query size limit (Hiroshi)
- Remove text field size limit (Hiroshi)
- Fix for SQLPrimaryKeys in multibyte mode (Hiroshi)
- Allow ODBC procedure calls (Hiroshi)

- Improve boolean handing (Aidan Mountford)
- Most configuration options now settable via DSN (Hiroshi)
- Multibyte, performance fixes (Hiroshi)
- Allow driver to be used with iODBC or unixODBC (Peter E)
- MD5 password encryption support (Bruce)
- Add more compatibility functions to odbc.sql (Peter E)

A.31.3.19. ECPG

- EXECUTE ... INTO implemented (Christof Petig)
- Multiple row descriptor support (e.g. CARDINALITY) (Christof Petig)
- Fix for GRANT parameters (Lee Kindness)
- Fix INITIALLY DEFERRED bug
- Various bug fixes (Michael, Christof Petig)
- Auto allocation for indicator variable arrays (int *ind_p=NULL)
- Auto allocation for string arrays (char **foo_pp=NULL)
- ECPGfree_auto_mem fixed
- All function names with external linkage are now prefixed by ECPG
- Fixes for arrays of structures (Michael)

A.31.3.20. Misc. Interfaces

- Python fix fetchone() (Gerhard Haring)
- Use UTF, Unicode in Tcl where appropriate (Vsevolod Lobko, Reinhard Max)
- Add Tcl COPY TO/FROM (ljb)
- Prevent output of default index op class in pg_dump (Tom)
- Fix libpgeasy memory leak (Bruce)

A.31.3.21. Build and Install

- Configure, dynamic loader, and shared library fixes (Peter E)
- Fixes in QNX 4 port (Bernd Tegge)
- Fixes in Cygwin and Windows ports (Jason Tishler, Gerhard Haring, Dmitry Yurtaev, Darko Prenosil, Mikhail Terekhov)
- Fix for Windows socket communication failures (Magnus, Mikhail Terekhov)
- Hurd compile fix (Oliver Elphick)
- BeOS fixes (Cyril Velter)
- Remove configure --enable-unicode-conversion, now enabled by multibyte (Tatsuo)

- AIX fixes (Tatsuo, Andreas)
- Fix parallel make (Peter E)
- Install SQL language manual pages into OS-specific directories (Peter E)
- Rename config.h to pg_config.h (Peter E)
- Reorganize installation layout of header files (Peter E)

A.31.3.22. Source Code

- Remove SEP_CHAR (Bruce)
- New GUC hooks (Tom)
- Merge GUC and command line handling (Marko Kreen)
- Remove EXTEND INDEX (Martijn van Oosterhout, Tom)
- New pgjindent utility to indent java code (Bruce)
- Remove define of true/false when compiling under C++ (Leandro Fanzone, Tom)
- pgindent fixes (Bruce, Tom)
- Replace strcasecmp() with strcmp() where appropriate (Peter E)
- Dynahash portability improvements (Tom)
- Add 'volatile' usage in spinlock structures
- Improve signal handling logic (Tom)

A.31.3.23. Contrib

- New contrib/rtree_gist (Oleg Bartunov, Teodor Sigaev)
- New contrib/tsearch full-text indexing (Oleg, Teodor Sigaev)
- Add contrib/dblink for remote database access (Joe Conway)
- contrib/ora2pg Oracle conversion utility (Gilles Darold)
- contrib/xml XML conversion utility (John Gray)
- contrib/fulltextindex fixes (Christopher Kings-Lynne)
- New contrib/fuzzystrmatch with levenshtein and metaphone, soundex merged (Joe Conway)
- Add contrib/intarray boolean queries, binary search, fixes (Oleg Bartunov)
- New pg_upgrade utility (Bruce)
- Add new pg_resetxlog options (Bruce, Tom)

A.32. Release 7.1.3

Release date

2001-08-15

A.32.1. Migration to Version 7.1.3

A dump/restore is *not* required for those running 7.1.X.

A.32.2. Changes

```
Remove unused WAL segments of large transactions (Tom)
Multiaction rule fix (Tom)
PL/pgSQL memory allocation fix (Jan)
VACUUM buffer fix (Tom)
Regression test fixes (Tom)
pg_dump fixes for GRANT/REVOKE/comments on views, user-defined
 types (Tom)
Fix subselects with DISTINCT ON or LIMIT (Tom)
BeOS fix
Disable COPY TO/FROM a view (Tom)
Cygwin build (Jason Tishler)
```

A.33. Release 7.1.2

Release date

2001-05-11

This has one fix from 7.1.1.

A.33.1. Migration to Version 7.1.2

A dump/restore is *not* required for those running 7.1.X.

A.33.2. Changes

```
Fix PL/pgSQL SELECTs when returning no rows
Fix for psql backslash core dump
Referential integrity privilege fix
Optimizer fixes
pg_dump cleanups
```

A.34. Release 7.1.1

Release date

2001-05-05

This has a variety of fixes from 7.1.

A.34.1. Migration to Version 7.1.1

A dump/restore is *not* required for those running 7.1.

A.34.2. Changes

```
Fix for numeric MODULO operator (Tom)
```

```
pg_dump fixes (Philip)
pg_dump can dump 7.0 databases (Philip)
readline 4.2 fixes (Peter E)
JOIN fixes (Tom)
AIX, MSWIN, VAX, N32K fixes (Tom)
Multibytes fixes (Tom)
Unicode fixes (Tatsuo)
Optimizer improvements (Tom)
Fix for whole rows in functions (Tom)
Fix for pg_ctl and option strings with spaces (Peter E)
ODBC fixes (Hiroshi)
EXTRACT can now take string argument (Thomas)
Python fixes (Darcy)
```

A.35. Release 7.1

Release date

2001-04-13

This release focuses on removing limitations that have existed in the PostgreSQL code for many years.

Major changes in this release:

Write-ahead Log (WAL)

To maintain database consistency in case of an operating system crash, previous releases of PostgreSQL have forced all data modifications to disk before each transaction commit. With WAL, only one log file must be flushed to disk, greatly improving performance. If you have been using -F in previous releases to disable disk flushes, you might want to consider discontinuing its use.

TOAST

TOAST - Previous releases had a compiled-in row length limit, typically 8k - 32k. This limit made storage of long text fields difficult. With TOAST, long rows of any length can be stored with good performance.

Outer Joins

We now support outer joins. The UNION/NOT IN workaround for outer joins is no longer required. We use the SQL92 outer join syntax.

Function Manager

The previous C function manager did not handle null values properly, nor did it support 64-bit CPU's (Alpha). The new function manager does. You can continue using your old custom functions, but you might want to rewrite them in the future to use the new function manager call interface.

Complex Queries

A large number of complex queries that were unsupported in previous releases now work. Many combinations of views, aggregates, UNION, LIMIT, cursors, subqueries, and inherited tables now work properly. Inherited tables are now accessed by default. Subqueries in FROM are now supported.

A.35.1. Migration to Version 7.1

A dump/restore using pg_dump is required for those wishing to migrate data from any previous release.

A.35.2. Changes

```
Bug Fixes
---------
Many multibyte/Unicode/locale fixes (Tatsuo and others)
More reliable ALTER TABLE RENAME (Tom)
Kerberos V fixes (David Wragg)
Fix for INSERT INTO...SELECT where targetlist has subqueries (Tom)
Prompt username/password on standard error (Bruce)
Large objects inv_read/inv_write fixes (Tom)
Fixes for to_char(), to_date(), to_ascii(), and to_timestamp()
 (Karel,
   Daniel Baldoni)
Prevent query expressions from leaking memory (Tom)
Allow UPDATE of arrays elements (Tom)
Wake up lock waiters during cancel (Hiroshi)
Fix rare cursor crash when using hash join (Tom)
Fix for DROP TABLE/INDEX in rolled-back transaction (Hiroshi)
Fix psql crash from \l+ if MULTIBYTE enabled (Peter E)
Fix truncation of rule names during CREATE VIEW (Ross Reedstrom)
Fix PL/perl (Alex Kapranoff)
Disallow LOCK on views (Mark Hollomon)
Disallow INSERT/UPDATE/DELETE on views (Mark Hollomon)
Disallow DROP RULE, CREATE INDEX, TRUNCATE on views (Mark Hollomon)
Allow PL/pgSQL accept non-ASCII identifiers (Tatsuo)
Allow views to proper handle GROUP BY, aggregates, DISTINCT (Tom)
Fix rare failure with TRUNCATE command (Tom)
Allow UNION/INTERSECT/EXCEPT to be used with ALL, subqueries,
 views,
   DISTINCT, ORDER BY, SELECT...INTO (Tom)
Fix parser failures during aborted transactions (Tom)
Allow temporary relations to properly clean up indexes (Bruce)
Fix VACUUM problem with moving rows in same page (Tom)
Modify pg_dump to better handle user-defined items in template1
 (Philip)
Allow LIMIT in VIEW (Tom)
Require cursor FETCH to honor LIMIT (Tom)
Allow PRIMARY/FOREIGN Key definitions on inherited columns
 (Stephan)
Allow ORDER BY, LIMIT in subqueries (Tom)
Allow UNION in CREATE RULE (Tom)
Make ALTER/DROP TABLE rollback-able (Vadim, Tom)
Store initdb collation in pg_control so collation cannot be changed
 (Tom)
Fix INSERT...SELECT with rules (Tom)
Fix FOR UPDATE inside views and subselects (Tom)
Fix OVERLAPS operators conform to SQL92 spec regarding NULLs (Tom)
Fix lpad() and rpad() to handle length less than input string (Tom)
Fix use of NOTIFY in some rules (Tom)
Overhaul btree code (Tom)
Fix NOT NULL use in Pl/pgSQL variables (Tom)
Overhaul GIST code (Oleg)
Fix CLUSTER to preserve constraints and column default (Tom)
Improved deadlock detection handling (Tom)
Allow multiple SERIAL columns in a table (Tom)
Prevent occasional index corruption (Vadim)
```

```
Enhancements
------------
Add OUTER JOINs (Tom)
Function manager overhaul (Tom)
Allow ALTER TABLE RENAME on indexes (Tom)
Improve CLUSTER (Tom)
Improve ps status display for more platforms (Peter E, Marc)
Improve CREATE FUNCTION failure message (Ross)
JDBC improvements (Peter, Travis Bauer, Christopher Cain, William
 Webber,
   Gunnar)
Grand Unified Configuration scheme/GUC.  Many options can now be
 set in
   data/postgresql.conf, postmaster/postgres flags, or SET commands
 (Peter E)
Improved handling of file descriptor cache (Tom)
New warning code about auto-created table alias entries (Bruce)
Overhaul initdb process (Tom, Peter E)
Overhaul of inherited tables; inherited tables now accessed by
 default;
  new ONLY key word prevents it (Chris Bitmead, Tom)
ODBC cleanups/improvements (Nick Gorham, Stephan Szabo, Zoltan
 Kovacs,
   Michael Fork)
Allow renaming of temp tables (Tom)
Overhaul memory manager contexts (Tom)
pg_dumpall uses CREATE USER or CREATE GROUP rather using COPY
 (Peter E)
Overhaul pg_dump (Philip Warner)
Allow pg_hba.conf secondary password file to specify only username
 (Peter E)
Allow TEMPORARY or TEMP key word when creating temporary tables
 (Bruce)
New memory leak checker (Karel)
New SET SESSION CHARACTERISTICS (Thomas)
Allow nested block comments (Thomas)
Add WITHOUT TIME ZONE type qualifier (Thomas)
New ALTER TABLE ADD CONSTRAINT (Stephan)
Use NUMERIC accumulators for INTEGER aggregates (Tom)
Overhaul aggregate code (Tom)
New VARIANCE and STDDEV() aggregates
Improve dependency ordering of pg_dump (Philip)
New pg_restore command (Philip)
New pg_dump tar output option (Philip)
New pg_dump of large objects  (Philip)
New ESCAPE option to LIKE (Thomas)
New case-insensitive LIKE - ILIKE (Thomas)
Allow functional indexes to use binary-compatible type (Tom)
Allow SQL functions to be used in more contexts (Tom)
New pg_config utility (Peter E)
New PL/pgSQL EXECUTE command which allows dynamic SQL and utility
 statements
   (Jan)
New PL/pgSQL GET DIAGNOSTICS statement for SPI value access (Jan)
New quote_identifiers() and quote_literal() functions (Jan)
New ALTER TABLE table OWNER TO user command (Mark Hollomon)
Allow subselects in FROM, i.e. FROM (SELECT ...) [AS] alias (Tom)
Update PyGreSQL to version 3.1 (D'Arcy)
```

```
Store tables as files named by OID (Vadim)
New SQL function setval(seq,val,bool) for use in pg_dump (Philip)
Require DROP VIEW to remove views, no DROP TABLE (Mark)
Allow DROP VIEW view1, view2 (Mark)
Allow multiple objects in DROP INDEX, DROP RULE, and DROP TYPE
 (Tom)
Allow automatic conversion to/from Unicode (Tatsuo, Eiji)
New /contrib/pgcrypto hashing functions (Marko Kreen)
New pg_dumpall --globals-only option (Peter E)
New CHECKPOINT command for WAL which creates new WAL log file
 (Vadim)
New AT TIME ZONE syntax (Thomas)
Allow location of Unix domain socket to be configurable (David J.
 MacKenzie)
Allow postmaster to listen on a specific IP address (David J.
 MacKenzie)
Allow socket path name to be specified in hostname by using leading
 slash
   (David J. MacKenzie)
Allow CREATE DATABASE to specify template database (Tom)
New utility to convert MySQL schema dumps to SQL92 and PostgreSQL
 (Thomas)
New /contrib/rserv replication toolkit (Vadim)
New file format for COPY BINARY (Tom)
New /contrib/oid2name to map numeric files to table names (B
 Palmer)
New "idle in transaction" ps status message (Marc)
Update to pgaccess 0.98.7 (Constantin Teodorescu)
pg_ctl now defaults to -w (wait) on shutdown, new -l (log) option
Add rudimentary dependency checking to pg_dump (Philip)

Types
-----
Fix INET/CIDR type ordering and add new functions (Tom)
Make OID behave as an unsigned type (Tom)
Allow BIGINT as synonym for INT8 (Peter E)
New int2 and int8 comparison operators (Tom)
New BIT and BIT VARYING types (Adriaan Joubert, Tom, Peter E)
CHAR() no longer faster than VARCHAR() because of TOAST (Tom)
New GIST seg/cube examples (Gene Selkov)
Improved round(numeric) handling (Tom)
Fix CIDR output formatting (Tom)
New CIDR abbrev() function (Tom)

Performance
-----------
Write-Ahead Log (WAL) to provide crash recovery with less
 performance
   overhead (Vadim)
ANALYZE stage of VACUUM no longer exclusively locks table (Bruce)
Reduced file seeks (Denis Perchine)
Improve BTREE code for duplicate keys (Tom)
Store all large objects in a single table (Denis Perchine, Tom)
Improve memory allocation performance (Karel, Tom)

Source Code
-----------
New function manager call conventions (Tom)
```

```
SGI portability fixes (David Kaelbling)
New configure --enable-syslog option (Peter E)
New BSDI README (Bruce)
configure script moved to top level, not /src (Peter E)
Makefile/configuration/compilation overhaul (Peter E)
New configure --with-python option (Peter E)
Solaris cleanups (Peter E)
Overhaul /contrib Makefiles (Karel)
New OpenSSL configuration option (Magnus, Peter E)
AIX fixes (Andreas)
QNX fixes (Maurizio)
New heap_open(), heap_openr() API (Tom)
Remove colon and semi-colon operators (Thomas)
New pg_class.relkind value for views (Mark Hollomon)
Rename ichar() to chr() (Karel)
New documentation for btrim(), ascii(), chr(), repeat() (Karel)
Fixes for NT/Cygwin (Pete Forman)
AIX port fixes (Andreas)
New BeOS port (David Reid, Cyril Velter)
Add proofreader's changes to docs (Addison-Wesley, Bruce)
New Alpha spinlock code (Adriaan Joubert, Compaq)
UnixWare port overhaul (Peter E)
New Darwin/MacOS X port (Peter Bierman, Bruce Hartzler)
New FreeBSD Alpha port (Alfred)
Overhaul shared memory segments (Tom)
Add IBM S/390 support (Neale Ferguson)
Moved macmanuf to /contrib (Larry Rosenman)
Syslog improvements (Larry Rosenman)
New template0 database that contains no user additions (Tom)
New /contrib/cube and /contrib/seg GIST sample code (Gene Selkov)
Allow NetBSD's libedit instead of readline (Peter)
Improved assembly language source code format (Bruce)
New contrib/pg_logger
New --template option to createdb
New contrib/pg_control utility (Oliver)
New FreeBSD tools ipc_check, start-scripts/freebsd
```

A.36. Release 7.0.3

Release date

2000-11-11

This has a variety of fixes from 7.0.2.

A.36.1. Migration to Version 7.0.3

A dump/restore is *not* required for those running 7.0.*.

A.36.2. Changes

```
Jdbc fixes (Peter)
Large object fix (Tom)
Fix lean in COPY WITH OIDS leak (Tom)
Fix backwards-index-scan (Tom)
```

```
Fix SELECT ... FOR UPDATE so it checks for duplicate keys (Hiroshi)
Add --enable-syslog to configure (Marc)
Fix abort transaction at backend exit in rare cases (Tom)
Fix for psql \l+ when multibyte enabled (Tatsuo)
Allow PL/pgSQL to accept non ascii identifiers (Tatsuo)
Make vacuum always flush buffers (Tom)
Fix to allow cancel while waiting for a lock (Hiroshi)
Fix for memory allocation problem in user authentication code (Tom)
Remove bogus use of int4out() (Tom)
Fixes for multiple subqueries in COALESCE or BETWEEN (Tom)
Fix for failure of triggers on heap open in certain cases (Jeroen
 van
   Vianen)
Fix for erroneous selectivity of not-equals (Tom)
Fix for erroneous use of strcmp() (Tom)
Fix for bug where storage manager accesses items beyond end of file
   (Tom)
Fix to include kernel errno message in all smgr elog messages (Tom)
Fix for '.' not in PATH at build time (SL Baur)
Fix for out-of-file-descriptors error (Tom)
Fix to make pg_dump dump 'iscachable' flag for functions (Tom)
Fix for subselect in targetlist of Append node (Tom)
Fix for mergejoin plans (Tom)
Fix TRUNCATE failure on relations with indexes (Tom)
Avoid database-wide restart on write error (Hiroshi)
Fix nodeMaterial to honor chgParam by recomputing its output (Tom)
Fix VACUUM problem with moving chain of update row versions when
 source
   and destination of a row version lie on the same page (Tom)
Fix user.c CommandCounterIncrement (Tom)
Fix for AM/PM boundary problem in to_char() (Karel Zak)
Fix TIME aggregate handling (Tom)
Fix to_char() to avoid coredump on NULL input (Tom)
Buffer fix (Tom)
Fix for inserting/copying longer multibyte strings into char() data
   types (Tatsuo)
Fix for crash of backend, on abort (Tom)
```

A.37. Release 7.0.2

Release date

2000-06-05

This is a repackaging of 7.0.1 with added documentation.

A.37.1. Migration to Version 7.0.2

A dump/restore is *not* required for those running 7.*.

A.37.2. Changes

```
Added documentation to tarball.
```

A.38. Release 7.0.1

Release date

2000-06-01

This is a cleanup release for 7.0.

A.38.1. Migration to Version 7.0.1

A dump/restore is *not* required for those running 7.0.

A.38.2. Changes

```
Fix many CLUSTER failures (Tom)
Allow ALTER TABLE RENAME works on indexes (Tom)
Fix plpgsql to handle datetime->timestamp and timespan->interval
 (Bruce)
New configure --with-setproctitle switch to use setproctitle()
 (Marc, Bruce)
Fix the off by one errors in ResultSet from 6.5.3, and more.
jdbc ResultSet fixes (Joseph Shraibman)
optimizer tunings (Tom)
Fix create user for pgaccess
Fix for UNLISTEN failure
IRIX fixes (David Kaelbling)
QNX fixes (Andreas Kardos)
Reduce COPY IN lock level (Tom)
Change libpqeasy to use PQconnectdb() style parameters (Bruce)
Fix pg_dump to handle OID indexes (Tom)
Fix small memory leak (Tom)
Solaris fix for createdb/dropdb (Tatsuo)
Fix for non-blocking connections (Alfred Perlstein)
Fix improper recovery after RENAME TABLE failures (Tom)
Copy pg_ident.conf.sample into /lib directory in install (Bruce)
Add SJIS UDC (NEC selection IBM kanji) support (Eiji Tokuya)
Fix too long syslog message (Tatsuo)
Fix problem with quoted indexes that are too long (Tom)
JDBC ResultSet.getTimestamp() fix (Gregory Krasnow & Floyd
 Marinescu)
ecpg changes (Michael)
```

A.39. Release 7.0

Release date

2000-05-08

This release contains improvements in many areas, demonstrating the continued growth of PostgreSQL. There are more improvements and fixes in 7.0 than in any previous release. The developers have confidence that this is the best release yet; we do our best to put out only solid releases, and this one is no exception.

Major changes in this release:

Foreign Keys

Foreign keys are now implemented, with the exception of PARTIAL MATCH foreign keys. Many users have been asking for this feature, and we are pleased to offer it.

Optimizer Overhaul

Continuing on work started a year ago, the optimizer has been improved, allowing better query plan selection and faster performance with less memory usage.

Updated psql

psql, our interactive terminal monitor, has been updated with a variety of new features. See the psql manual page for details.

Join Syntax

SQL92 join syntax is now supported, though only as `INNER JOIN` for this release. `JOIN`, `NATURAL JOIN`, `JOIN/USING`, and `JOIN/ON` are available, as are column correlation names.

A.39.1. Migration to Version 7.0

A dump/restore using pg_dump is required for those wishing to migrate data from any previous release of PostgreSQL. For those upgrading from 6.5.*, you can instead use pg_upgrade to upgrade to this release; however, a full dump/reload installation is always the most robust method for upgrades.

Interface and compatibility issues to consider for the new release include:

- The date/time types `datetime` and `timespan` have been superseded by the SQL92-defined types `timestamp` and `interval`. Although there has been some effort to ease the transition by allowing PostgreSQL to recognize the deprecated type names and translate them to the new type names, this mechanism cannot be completely transparent to your existing application.
- The optimizer has been substantially improved in the area of query cost estimation. In some cases, this will result in decreased query times as the optimizer makes a better choice for the preferred plan. However, in a small number of cases, usually involving pathological distributions of data, your query times might go up. If you are dealing with large amounts of data, you might want to check your queries to verify performance.
- The JDBC and ODBC interfaces have been upgraded and extended.
- The string function `CHAR_LENGTH` is now a native function. Previous versions translated this into a call to `LENGTH`, which could result in ambiguity with other types implementing `LENGTH` such as the geometric types.

A.39.2. Changes

```
Bug Fixes
---------
Prevent function calls exceeding maximum number of arguments (Tom)
Improve CASE construct (Tom)
Fix SELECT coalesce(f1,0) FROM int4_tbl GROUP BY f1 (Tom)
Fix SELECT sentence.words[0] FROM sentence GROUP BY
 sentence.words[0] (Tom)
Fix GROUP BY scan bug (Tom)
Improvements in SQL grammar processing (Tom)
Fix for views involved in INSERT ... SELECT ... (Tom)
Fix for SELECT a/2, a/2 FROM test_missing_target GROUP BY a/2 (Tom)
Fix for subselects in INSERT ... SELECT (Tom)
Prevent INSERT ... SELECT ... ORDER BY (Tom)
Fixes for relations greater than 2GB, including vacuum
Improve propagating system table changes to other backends (Tom)
```

```
Improve propagating user table changes to other backends (Tom)
Fix handling of temp tables in complex situations (Bruce, Tom)
Allow table locking at table open, improving concurrent reliability
 (Tom)
Properly quote sequence names in pg_dump (Ross J. Reedstrom)
Prevent DROP DATABASE while others accessing
Prevent any rows from being returned by GROUP BY if no rows
 processed (Tom)
Fix SELECT COUNT(1) FROM table WHERE ...' if no rows matching WHERE
 (Tom)
Fix pg_upgrade so it works for MVCC (Tom)
Fix for SELECT ... WHERE x IN (SELECT ... HAVING SUM(x) > 1) (Tom)
Fix for "f1 datetime DEFAULT 'now'"  (Tom)
Fix problems with CURRENT_DATE used in DEFAULT (Tom)
Allow comment-only lines, and ;;; lines too. (Tom)
Improve recovery after failed disk writes, disk full (Hiroshi)
Fix cases where table is mentioned in FROM but not joined (Tom)
Allow HAVING clause without aggregate functions (Tom)
Fix for "--" comment and no trailing newline, as seen in perl
 interface
Improve pg_dump failure error reports (Bruce)
Allow sorts and hashes to exceed 2GB file sizes (Tom)
Fix for pg_dump dumping of inherited rules (Tom)
Fix for NULL handling comparisons (Tom)
Fix inconsistent state caused by failed CREATE/DROP commands
 (Hiroshi)
Fix for dbname with dash
Prevent DROP INDEX from interfering with other backends (Tom)
Fix file descriptor leak in verify_password()
Fix for "Unable to identify an operator =$" problem
Fix ODBC so no segfault if CommLog and Debug enabled (Dirk
 Niggemann)
Fix for recursive exit call (Massimo)
Fix for extra-long timezones (Jeroen van Vianen)
Make pg_dump preserve primary key information (Peter E)
Prevent databases with single quotes (Peter E)
Prevent DROP DATABASE inside  transaction (Peter E)
ecpg memory leak fixes (Stephen Birch)
Fix for SELECT null::text, SELECT int4fac(null) and SELECT 2 +
 (null) (Tom)
Y2K timestamp fix (Massimo)
Fix for VACUUM 'HEAP_MOVED_IN was not expected' errors (Tom)
Fix for views with tables/columns containing spaces  (Tom)
Prevent privileges on indexes (Peter E)
Fix for spinlock stuck problem when error is generated (Hiroshi)
Fix ipcclean on Linux
Fix handling of NULL constraint conditions (Tom)
Fix memory leak in odbc driver (Nick Gorham)
Fix for privilege check on UNION tables (Tom)
Fix to allow SELECT 'a' LIKE 'a' (Tom)
Fix for SELECT 1 + NULL (Tom)
Fixes to CHAR
Fix log() on numeric type (Tom)
Deprecate ':' and ';' operators
Allow vacuum of temporary tables
Disallow inherited columns with the same name as new columns
Recover or force failure when disk space is exhausted (Hiroshi)
Fix INSERT INTO ... SELECT with AS columns matching result columns
```

```
Fix INSERT ... SELECT ... GROUP BY groups by target columns not
 source columns (Tom)
Fix CREATE TABLE test (a char(5) DEFAULT text '', b int4) with
 INSERT (Tom)
Fix UNION with LIMIT
Fix CREATE TABLE x AS SELECT 1 UNION SELECT 2
Fix CREATE TABLE test(col char(2) DEFAULT user)
Fix mismatched types in CREATE TABLE ... DEFAULT
Fix SELECT * FROM pg_class where oid in (0,-1)
Fix SELECT COUNT('asdf') FROM pg_class WHERE oid=12
Prevent user who can create databases can modifying pg_database
 table (Peter E)
Fix btree to give a useful elog when key > 1/2 (page - overhead)
 (Tom)
Fix INSERT of 0.0 into DECIMAL(4,4) field (Tom)

Enhancements
------------
New CLI interface include file sqlcli.h, based on SQL3/SQL98
Remove all limits on query length, row length limit still exists
 (Tom)
Update jdbc protocol to 2.0 (Jens Glaser <jens@jens.de>)
Add TRUNCATE command to quickly truncate relation (Mike Mascari)
Fix to give super user and createdb user proper update catalog
 rights (Peter E)
Allow ecpg bool variables to have NULL values (Christof)
Issue ecpg error if NULL value for variable with no NULL indicator
 (Christof)
Allow ^C to cancel COPY command (Massimo)
Add SET FSYNC and SHOW PG_OPTIONS commands(Massimo)
Function name overloading for dynamically-loaded C functions
 (Frankpitt)
Add CmdTuples() to libpq++(Vince)
New CREATE CONSTRAINT TRIGGER and SET CONSTRAINTS commands(Jan)
Allow CREATE FUNCTION/WITH clause to be used for all language types
configure --enable-debug adds -g (Peter E)
configure --disable-debug removes -g (Peter E)
Allow more complex default expressions (Tom)
First real FOREIGN KEY constraint trigger functionality (Jan)
Add FOREIGN KEY ... MATCH FULL ... ON DELETE CASCADE (Jan)
Add FOREIGN KEY ... MATCH <unspecified> referential actions (Don
 Baccus)
Allow WHERE restriction on ctid (physical heap location) (Hiroshi)
Move pginterface from contrib to interface directory, rename to
 pgeasy (Bruce)
Change pgeasy connectdb() parameter ordering (Bruce)
Require SELECT DISTINCT target list to have all ORDER BY columns
 (Tom)
Add Oracle's COMMENT ON command (Mike Mascari <mascarim@yahoo.com>)
libpq's PQsetNoticeProcessor function now returns previous
 hook(Peter E)
Prevent PQsetNoticeProcessor from being set to NULL (Peter E)
Make USING in COPY optional (Bruce)
Allow subselects in the target list (Tom)
Allow subselects on the left side of comparison operators (Tom)
New parallel regression test (Jan)
Change backend-side COPY to write files with permissions 644 not
 666 (Tom)
```

```
Force permissions on PGDATA directory to be secure, even if it
 exists (Tom)
Added psql LASTOID variable to return last inserted oid (Peter E)
Allow concurrent vacuum and remove pg_vlock vacuum lock file (Tom)
Add privilege check for vacuum (Peter E)
New libpq functions to allow asynchronous connections:
 PQconnectStart(),
  PQconnectPoll(), PQresetStart(), PQresetPoll(), PQsetenvStart(),
  PQsetenvPoll(), PQsetenvAbort (Ewan Mellor)
New libpq PQsetenv() function (Ewan Mellor)
create/alter user extension (Peter E)
New postmaster.pid and postmaster.opts under $PGDATA (Tatsuo)
New scripts for create/drop user/db (Peter E)
Major psql overhaul (Peter E)
Add const to libpq interface (Peter E)
New libpq function PQoidValue (Peter E)
Show specific non-aggregate causing problem with GROUP BY (Tom)
Make changes to pg_shadow recreate pg_pwd file (Peter E)
Add aggregate(DISTINCT ...) (Tom)
Allow flag to control COPY input/output of NULLs (Peter E)
Make postgres user have a password by default (Peter E)
Add CREATE/ALTER/DROP GROUP (Peter E)
All administration scripts now support --long options (Peter E,
 Karel)
Vacuumdb script now supports --all option (Peter E)
ecpg new portable FETCH syntax
Add ecpg EXEC SQL IFDEF, EXEC SQL IFNDEF, EXEC SQL ELSE, EXEC SQL
 ELIF
       and EXEC SQL ENDIF directives
Add pg_ctl script to control backend start-up (Tatsuo)
Add postmaster.opts.default file to store start-up flags (Tatsuo)
Allow --with-mb=SQL_ASCII
Increase maximum number of index keys to 16 (Bruce)
Increase maximum number of function arguments to 16 (Bruce)
Allow configuration of maximum number of index keys and arguments
 (Bruce)
Allow unprivileged users to change their passwords (Peter E)
Password authentication enabled; required for new users (Peter E)
Disallow dropping a user who owns a database (Peter E)
Change initdb option --with-mb to --enable-multibyte
Add option for initdb to prompts for superuser password (Peter E)
Allow complex type casts like col::numeric(9,2) and
 col::int2::float8 (Tom)
Updated user interfaces on initdb, initlocation, pg_dump, ipcclean
 (Peter E)
New pg_char_to_encoding() and pg_encoding_to_char() functions
 (Tatsuo)
libpq non-blocking mode (Alfred Perlstein)
Improve conversion of types in casts that don't specify a length
New plperl internal programming language (Mark Hollomon)
Allow COPY IN to read file that do not end with a newline (Tom)
Indicate when long identifiers are truncated (Tom)
Allow aggregates to use type equivalency (Peter E)
Add Oracle's to_char(), to_date(), to_datetime(), to_timestamp(),
 to_number()
       conversion functions (Karel Zak <zakkr@zf.jcu.cz>)
Add SELECT DISTINCT ON (expr [, expr ...]) targetlist ... (Tom)
```

```
Check to be sure ORDER BY is compatible with the DISTINCT operation
 (Tom)
Add NUMERIC and int8 types to ODBC
Improve EXPLAIN results for Append, Group, Agg, Unique (Tom)
Add ALTER TABLE ... ADD FOREIGN KEY (Stephan Szabo)
Allow SELECT .. FOR UPDATE in PL/pgSQL (Hiroshi)
Enable backward sequential scan even after reaching EOF (Hiroshi)
Add btree indexing of boolean values, >= and <= (Don Baccus)
Print current line number when COPY FROM fails (Massimo)
Recognize POSIX time zone e.g. "PST+8" and "GMT-8" (Thomas)
Add DEC as synonym for DECIMAL (Thomas)
Add SESSION_USER as SQL92 key word, same as CURRENT_USER (Thomas)
Implement SQL92 column aliases (aka correlation names) (Thomas)
Implement SQL92 join syntax (Thomas)
Make INTERVAL reserved word allowed as a column identifier (Thomas)
Implement REINDEX command (Hiroshi)
Accept ALL in aggregate function SUM(ALL col) (Tom)
Prevent GROUP BY from using column aliases (Tom)
New psql \encoding option (Tatsuo)
Allow PQrequestCancel() to terminate when in waiting-for-lock state
 (Hiroshi)
Allow negation of a negative number in all cases
Add ecpg descriptors (Christof, Michael)
Allow CREATE VIEW v AS SELECT f1::char(8) FROM tbl
Allow casts with length, like foo::char(8)
New libpq functions PQsetClientEncoding(), PQclientEncoding()
 (Tatsuo)
Add support for SJIS user defined characters (Tatsuo)
Larger views/rules supported
Make libpq's PQconndefaults() thread-safe (Tom)
Disable // as comment to be ANSI conforming, should use -- (Tom)
Allow column aliases on views CREATE VIEW name (collist)
Fixes for views with subqueries (Tom)
Allow UPDATE table SET fld = (SELECT ...) (Tom)
SET command options no longer require quotes
Update pgaccess to 0.98.6
New SET SEED command
New pg_options.sample file
New SET FSYNC command (Massimo)
Allow pg_descriptions when creating tables
Allow pg_descriptions when creating types, columns, and functions
Allow psql \copy to allow delimiters (Peter E)
Allow psql to print nulls as distinct from "" [null] (Peter E)

Types
-----
Many array fixes (Tom)
Allow bare column names to be subscripted as arrays (Tom)
Improve type casting of int and float constants (Tom)
Cleanups for int8 inputs, range checking, and type conversion (Tom)
Fix for SELECT timespan('21:11:26'::time) (Tom)
netmask('x.x.x.x/0') is 255.255.255.255 instead of 0.0.0.0 (Oleg
 Sharoiko)
Add btree index on NUMERIC (Jan)
Perl fix for large objects containing NUL characters (Douglas
 Thomson)
ODBC fix for large objects (free)
Fix indexing of cidr data type
```

```
Fix for Ethernet MAC addresses (macaddr type) comparisons
Fix for date/time types when overflows happened in computations
 (Tom)
Allow array on int8 (Peter E)
Fix for rounding/overflow of NUMERIC type, like NUMERIC(4,4) (Tom)
Allow NUMERIC arrays
Fix bugs in NUMERIC ceil() and floor() functions (Tom)
Make char_length()/octet_length including trailing blanks (Tom)
Made abstime/reltime use int4 instead of time_t (Peter E)
New lztext data type for compressed text fields
Revise code to handle coercion of int and float constants (Tom)
Start at new code to implement a BIT and BIT VARYING type (Adriaan
 Joubert)
NUMERIC now accepts scientific notation (Tom)
NUMERIC to int4 rounds (Tom)
Convert float4/8 to NUMERIC properly (Tom)
Allow type conversion with NUMERIC (Thomas)
Make ISO date style (2000-02-16 09:33) the default (Thomas)
Add NATIONAL CHAR [ VARYING ] (Thomas)
Allow NUMERIC round and trunc to accept negative scales (Tom)
New TIME WITH TIME ZONE type (Thomas)
Add MAX()/MIN() on time type (Thomas)
Add abs(), mod(), fac() for int8 (Thomas)
Rename functions to round(), sqrt(), cbrt(), pow() for float8
 (Thomas)
Add transcendental math functions (e.g. sin(), acos()) for float8
 (Thomas)
Add exp() and ln() for NUMERIC type
Rename NUMERIC power() to pow() (Thomas)
Improved TRANSLATE() function (Edwin Ramirez, Tom)
Allow X=-Y operators  (Tom)
Allow SELECT float8(COUNT(*))/(SELECT COUNT(*) FROM t) FROM t GROUP
 BY f1; (Tom)
Allow LOCALE to use indexes in regular expression searches (Tom)
Allow creation of functional indexes to use default types

Performance
-----------
Prevent exponential space consumption with many AND's and OR's
 (Tom)
Collect attribute selectivity values for system columns (Tom)
Reduce memory usage of aggregates (Tom)
Fix for LIKE optimization to use indexes with multibyte encodings
 (Tom)
Fix r-tree index optimizer selectivity (Thomas)
Improve optimizer selectivity computations and functions (Tom)
Optimize btree searching for cases where many equal keys exist
 (Tom)
Enable fast LIKE index processing only if index present (Tom)
Re-use free space on index pages with duplicates (Tom)
Improve hash join processing (Tom)
Prevent descending sort if result is already sorted(Hiroshi)
Allow commuting of index scan query qualifications (Tom)
Prefer index scans in cases where ORDER BY/GROUP BY is required
 (Tom)
Allocate large memory requests in fix-sized chunks for performance
 (Tom)
```

```
Fix vacuum's performance by reducing memory allocation requests
 (Tom)
Implement constant-expression simplification (Bernard Frankpitt,
 Tom)
Use secondary columns to be used to determine start of index scan
 (Hiroshi)
Prevent quadruple use of disk space when doing internal sorting
 (Tom)
Faster sorting by calling fewer functions (Tom)
Create system indexes to match all system caches (Bruce, Hiroshi)
Make system caches use system indexes (Bruce)
Make all system indexes unique (Bruce)
Improve pg_statistics management for VACUUM speed improvement (Tom)
Flush backend cache less frequently (Tom, Hiroshi)
COPY now reuses previous memory allocation, improving performance
 (Tom)
Improve optimization cost estimation (Tom)
Improve optimizer estimate of range queries x > lowbound AND x <
 highbound (Tom)
Use DNF instead of CNF where appropriate (Tom, Taral)
Further cleanup for OR-of-AND WHERE-clauses (Tom)
Make use of index in OR clauses (x = 1 AND y = 2) OR (x = 2 AND y =
 4) (Tom)
Smarter optimizer computations for random index page access (Tom)
New SET variable to control optimizer costs (Tom)
Optimizer queries based on LIMIT, OFFSET, and EXISTS qualifications
 (Tom)
Reduce optimizer internal housekeeping of join paths for speedup
 (Tom)
Major subquery speedup (Tom)
Fewer fsync writes when fsync is not disabled (Tom)
Improved LIKE optimizer estimates (Tom)
Prevent fsync in SELECT-only queries (Vadim)
Make index creation use psort code, because it is now faster (Tom)
Allow creation of sort temp tables > 1 Gig

Source Tree Changes
-------------------
Fix for linux PPC compile
New generic expression-tree-walker subroutine (Tom)
Change form() to varargform() to prevent portability problems
Improved range checking for large integers on Alphas
Clean up #include in /include directory (Bruce)
Add scripts for checking includes (Bruce)
Remove un-needed #include's from *.c files (Bruce)
Change #include's to use <> and "" as appropriate (Bruce)
Enable Windows compilation of libpq
Alpha spinlock fix from Uncle George <gatgul@voicenet.com>
Overhaul of optimizer data structures (Tom)
Fix to cygipc library (Yutaka Tanida)
Allow pgsql to work on newer Cygwin snapshots (Dan)
New catalog version number (Tom)
Add Linux ARM
Rename heap_replace to heap_update
Update for QNX (Dr. Andreas Kardos)
New platform-specific regression handling (Tom)
Rename oid8 -> oidvector and int28 -> int2vector (Bruce)
Included all yacc and lex files into the distribution (Peter E.)
```

```
Remove lextest, no longer needed (Peter E)
Fix for libpq and psql on Windows (Magnus)
Internally change datetime and timespan into timestamp and interval
 (Thomas)
Fix for plpgsql on BSD/OS
Add SQL_ASCII test case to the regression test (Tatsuo)
configure --with-mb now deprecated (Tatsuo)
NT fixes
NetBSD fixes (Johnny C. Lam <lamj@stat.cmu.edu>)
Fixes for Alpha compiles
New multibyte encodings
```

A.40. Release 6.5.3

Release date

1999-10-13

This is basically a cleanup release for 6.5.2. We have added a new PgAccess that was missing in 6.5.2, and installed an NT-specific fix.

A.40.1. Migration to Version 6.5.3

A dump/restore is *not* required for those running 6.5.*.

A.40.2. Changes

```
Updated version of pgaccess 0.98
NT-specific patch
Fix dumping rules on inherited tables
```

A.41. Release 6.5.2

Release date

1999-09-15

This is basically a cleanup release for 6.5.1. We have fixed a variety of problems reported by 6.5.1 users.

A.41.1. Migration to Version 6.5.2

A dump/restore is *not* required for those running 6.5.*.

A.41.2. Changes

```
subselect+CASE fixes(Tom)
Add SHLIB_LINK setting for solaris_i386 and solaris_sparc
 ports(Daren Sefcik)
Fixes for CASE in WHERE join clauses(Tom)
Fix BTScan abort(Tom)
Repair the check for redundant UNIQUE and PRIMARY KEY
 indexes(Thomas)
Improve it so that it checks for multicolumn constraints(Thomas)
Fix for Windows making problem with MB enabled(Hiroki Kataoka)
```

```
Allow BSD yacc and bison to compile pl code(Bruce)
Fix SET NAMES working
int8 fixes(Thomas)
Fix vacuum's memory consumption(Hiroshi,Tatsuo)
Reduce the total memory consumption of vacuum(Tom)
Fix for timestamp(datetime)
Rule deparsing bugfixes(Tom)
Fix quoting problems in mkMakefile.tcldefs.sh.in and
 mkMakefile.tkdefs.sh.in(Tom)
This is to re-use space on index pages freed by vacuum(Vadim)
document -x for pg_dump(Bruce)
Fix for unary operators in rule deparser(Tom)
Comment out FileUnlink of excess segments during mdtruncate()(Tom)
IRIX linking fix from Yu Cao >yucao@falcon.kla-tencor.com<
Repair logic error in LIKE: should not return LIKE_ABORT
  when reach end of pattern before end of text(Tom)
Repair incorrect cleanup of heap memory allocation during
 transaction abort(Tom)
Updated version of pgaccess 0.98
```

A.42. Release 6.5.1

Release date

1999-07-15

This is basically a cleanup release for 6.5. We have fixed a variety of problems reported by 6.5 users.

A.42.1. Migration to Version 6.5.1

A dump/restore is *not* required for those running 6.5.

A.42.2. Changes

```
Add NT README file
Portability fixes for linux_ppc, IRIX, linux_alpha, OpenBSD, alpha
Remove QUERY_LIMIT, use SELECT...LIMIT
Fix for EXPLAIN on inheritance(Tom)
Patch to allow vacuum on multisegment tables(Hiroshi)
R-Tree optimizer selectivity fix(Tom)
ACL file descriptor leak fix(Atsushi Ogawa)
New expression subtree code(Tom)
Avoid disk writes for read-only transactions(Vadim)
Fix for removal of temp tables if last transaction was
 aborted(Bruce)
Fix to prevent too large row from being created(Bruce)
plpgsql fixes
Allow port numbers 32k - 64k(Bruce)
Add ^ precedence(Bruce)
Rename sort files called pg_temp to pg_sorttemp(Bruce)
Fix for microseconds in time values(Tom)
Tutorial source cleanup
New linux_m68k port
Fix for sorting of NULL's in some cases(Tom)
Shared library dependencies fixed (Tom)
Fixed glitches affecting GROUP BY in subselects(Tom)
```

```
Fix some compiler warnings (Tomoaki Nishiyama)
Add Win1250 (Czech) support (Pavel Behal)
```

A.43. Release 6.5

Release date

1999-06-09

This release marks a major step in the development team's mastery of the source code we inherited from Berkeley. You will see we are now easily adding major features, thanks to the increasing size and experience of our world-wide development team.

Here is a brief summary of the more notable changes:

Multiversion concurrency control(MVCC)

This removes our old table-level locking, and replaces it with a locking system that is superior to most commercial database systems. In a traditional system, each row that is modified is locked until committed, preventing reads by other users. MVCC uses the natural multiversion nature of PostgreSQL to allow readers to continue reading consistent data during writer activity. Writers continue to use the compact pg_log transaction system. This is all performed without having to allocate a lock for every row like traditional database systems. So, basically, we no longer are restricted by simple table-level locking; we have something better than row-level locking.

Hot backups from pg_dump

pg_dump takes advantage of the new MVCC features to give a consistent database dump/backup while the database stays online and available for queries.

Numeric data type

We now have a true numeric data type, with user-specified precision.

Temporary tables

Temporary tables are guaranteed to have unique names within a database session, and are destroyed on session exit.

New SQL features

We now have CASE, INTERSECT, and EXCEPT statement support. We have new LIMIT/OFFSET, SET TRANSACTION ISOLATION LEVEL, SELECT ... FOR UPDATE, and an improved LOCK TABLE command.

Speedups

We continue to speed up PostgreSQL, thanks to the variety of talents within our team. We have sped up memory allocation, optimization, table joins, and row transfer routines.

Ports

We continue to expand our port list, this time including Windows NT/ix86 and NetBSD/arm32.

Interfaces

Most interfaces have new versions, and existing functionality has been improved.

Documentation

New and updated material is present throughout the documentation. New FAQs have been contributed for SGI and AIX platforms. The *Tutorial* has introductory information on SQL from Stefan Simkovics. For the *User's Guide*, there are reference pages covering the postmaster

and more utility programs, and a new appendix contains details on date/time behavior. The *Administrator's Guide* has a new chapter on troubleshooting from Tom Lane. And the *Programmer's Guide* has a description of query processing, also from Stefan, and details on obtaining the PostgreSQL source tree via anonymous CVS and CVSup.

A.43.1. Migration to Version 6.5

A dump/restore using pg_dump is required for those wishing to migrate data from any previous release of PostgreSQL. pg_upgrade can *not* be used to upgrade to this release because the on-disk structure of the tables has changed compared to previous releases.

The new Multiversion Concurrency Control (MVCC) features can give somewhat different behaviors in multiuser environments. *Read and understand the following section to ensure that your existing applications will give you the behavior you need.*

A.43.1.1. Multiversion Concurrency Control

Because readers in 6.5 don't lock data, regardless of transaction isolation level, data read by one transaction can be overwritten by another. In other words, if a row is returned by `SELECT` it doesn't mean that this row really exists at the time it is returned (i.e. sometime after the statement or transaction began) nor that the row is protected from being deleted or updated by concurrent transactions before the current transaction does a commit or rollback.

To ensure the actual existence of a row and protect it against concurrent updates one must use `SELECT FOR UPDATE` or an appropriate `LOCK TABLE` statement. This should be taken into account when porting applications from previous releases of PostgreSQL and other environments.

Keep the above in mind if you are using `contrib/refint.*` triggers for referential integrity. Additional techniques are required now. One way is to use `LOCK parent_table IN SHARE ROW EXCLUSIVE MODE` command if a transaction is going to update/delete a primary key and use `LOCK parent_table IN SHARE MODE` command if a transaction is going to update/insert a foreign key.

Note

Note that if you run a transaction in SERIALIZABLE mode then you must execute the `LOCK` commands above before execution of any DML statement (`SELECT/INSERT/DELETE/UPDATE/FETCH/COPY_TO`) in the transaction.

These inconveniences will disappear in the future when the ability to read dirty (uncommitted) data (regardless of isolation level) and true referential integrity will be implemented.

A.43.2. Changes

```
Bug Fixes
---------
Fix text<->float8 and text<->float4 conversion functions(Thomas)
Fix for creating tables with mixed-case constraints(Billy)
Change exp()/pow() behavior to generate error on underflow/
overflow(Jan)
Fix bug in pg_dump -z
Memory overrun cleanups(Tatsuo)
Fix for lo_import crash(Tatsuo)
Adjust handling of data type names to suppress double
 quotes(Thomas)
Use type coercion for matching columns and DEFAULT(Thomas)
Fix deadlock so it only checks once after one second of
 sleep(Bruce)
Fixes for aggregates and PL/pgsql(Hiroshi)
```

```
Fix for subquery crash(Vadim)
Fix for libpq function PQfnumber and case-insensitive names(Bahman
 Rafatjoo)
Fix for large object write-in-middle, no extra block, memory
 consumption(Tatsuo)
Fix for pg_dump -d or -D and  quote special characters in INSERT
Repair serious problems with dynahash(Tom)
Fix INET/CIDR portability problems
Fix problem with selectivity error in ALTER TABLE ADD COLUMN(Bruce)
Fix executor so mergejoin of different column types works(Tom)
Fix for Alpha OR selectivity bug
Fix OR index selectivity problem(Bruce)
Fix so \d shows proper length for char()/varchar()(Ryan)
Fix tutorial code(Clark)
Improve destroyuser checking(Oliver)
Fix for Kerberos(Rodney McDuff)
Fix for dropping database while dirty buffers(Bruce)
Fix so sequence nextval() can be case-sensitive(Bruce)
Fix !!= operator
Drop buffers before destroying database files(Bruce)
Fix case where executor evaluates functions twice(Tatsuo)
Allow sequence nextval actions to be case-sensitive(Bruce)
Fix optimizer indexing not working for negative numbers(Bruce)
Fix for memory leak in executor with fjIsNull
Fix for aggregate memory leaks(Erik Riedel)
Allow user name containing a dash to grant privileges
Cleanup of NULL in inet types
Clean up system table bugs(Tom)
Fix problems of PAGER and \? command(Masaaki Sakaida)
Reduce default multisegment file size limit to 1GB(Peter)
Fix for dumping of CREATE OPERATOR(Tom)
Fix for backward scanning of cursors(Hiroshi Inoue)
Fix for COPY FROM STDIN when using \i(Tom)
Fix for subselect is compared inside an expression(Jan)
Fix handling of error reporting while returning rows(Tom)
Fix problems with reference to array types(Tom,Jan)
Prevent UPDATE SET oid(Jan)
Fix pg_dump so -t option can handle case-sensitive tablenames
Fixes for GROUP BY in special cases(Tom, Jan)
Fix for memory leak in failed queries(Tom)
DEFAULT now supports mixed-case identifiers(Tom)
Fix for multisegment uses of DROP/RENAME table, indexes(Ole Gjerde)
Disable use of pg_dump with both -o and -d options(Bruce)
Allow pg_dump to properly dump group privileges(Bruce)
Fix GROUP BY in INSERT INTO table SELECT * FROM table2(Jan)
Fix for computations in views(Jan)
Fix for aggregates on array indexes(Tom)
Fix for DEFAULT handles single quotes in value requiring too many
 quotes
Fix security problem with non-super users importing/exporting large
 objects(Tom)
Rollback of transaction that creates table cleaned up properly(Tom)
Fix to allow long table and column names to generate proper serial
 names(Tom)

Enhancements
------------
Add "vacuumdb" utility
```

```
Speed up libpq by allocating memory better(Tom)
EXPLAIN all indexes used(Tom)
Implement CASE, COALESCE, NULLIF  expression(Thomas)
New pg_dump table output format(Constantin)
Add string min()/max() functions(Thomas)
Extend new type coercion techniques to aggregates(Thomas)
New moddatetime contrib(Terry)
Update to pgaccess 0.96(Constantin)
Add routines for single-byte "char" type(Thomas)
Improved substr() function(Thomas)
Improved multibyte handling(Tatsuo)
Multiversion concurrency control/MVCC(Vadim)
New Serialized mode(Vadim)
Fix for tables over 2gigs(Peter)
New SET TRANSACTION ISOLATION LEVEL(Vadim)
New LOCK TABLE IN ... MODE(Vadim)
Update ODBC driver(Byron)
New NUMERIC data type(Jan)
New SELECT FOR UPDATE(Vadim)
Handle "NaN" and "Infinity" for input values(Jan)
Improved date/year handling(Thomas)
Improved handling of backend connections(Magnus)
New options ELOG_TIMESTAMPS and USE_SYSLOG options for log
 files(Massimo)
New TCL_ARRAYS option(Massimo)
New INTERSECT and EXCEPT(Stefan)
New pg_index.indisprimary for primary key tracking(D'Arcy)
New pg_dump option to allow dropping of tables before
 creation(Brook)
Speedup of row output routines(Tom)
New READ COMMITTED isolation level(Vadim)
New TEMP tables/indexes(Bruce)
Prevent sorting if result is already sorted(Jan)
New memory allocation optimization(Jan)
Allow psql to do \p\g(Bruce)
Allow multiple rule actions(Jan)
Added LIMIT/OFFSET functionality(Jan)
Improve optimizer when joining a large number of tables(Bruce)
New intro to SQL from S. Simkovics' Master's Thesis (Stefan,
 Thomas)
New intro to backend processing from S. Simkovics' Master's Thesis
 (Stefan)
Improved int8 support(Ryan Bradetich, Thomas, Tom)
New routines to convert between int8 and text/varchar types(Thomas)
New bushy plans, where meta-tables are joined(Bruce)
Enable right-hand queries by default(Bruce)
Allow reliable maximum number of backends to be set at configure
 time
     (--with-maxbackends and postmaster switch (-N backends))(Tom)
GEQO default now 10 tables because of optimizer speedups(Tom)
Allow NULL=Var for MS-SQL portability(Michael, Bruce)
Modify contrib check_primary_key() so either "automatic" or
 "dependent"(Anand)
Allow psql \d on a view show query(Ryan)
Speedup for LIKE(Bruce)
Ecpg fixes/features, see src/interfaces/ecpg/ChangeLog
 file(Michael)
JDBC fixes/features, see src/interfaces/jdbc/CHANGELOG(Peter)
```

```
Make % operator have precedence like /(Bruce)
Add new postgres -O option to allow system table structure
 changes(Bruce)
Update contrib/pginterface/findoidjoins script(Tom)
Major speedup in vacuum of deleted rows with indexes(Vadim)
Allow non-SQL functions to run different versions based on
 arguments(Tom)
Add -E option that shows actual queries sent by \dt and
 friends(Masaaki Sakaida)
Add version number in start-up banners for psql(Masaaki Sakaida)
New contrib/vacuumlo removes large objects not referenced(Peter)
New initialization for table sizes so non-vacuumed tables perform
 better(Tom)
Improve error messages when a connection is rejected(Tom)
Support for arrays of char() and varchar() fields(Massimo)
Overhaul of hash code to increase reliability and performance(Tom)
Update to PyGreSQL 2.4(D'Arcy)
Changed debug options so -d4 and -d5 produce different node
 displays(Jan)
New pg_options: pretty_plan, pretty_parse, pretty_rewritten(Jan)
Better optimization statistics for system table access(Tom)
Better handling of non-default block sizes(Massimo)
Improve GEQO optimizer memory consumption(Tom)
UNION now supports ORDER BY of columns not in target list(Jan)
Major libpq++ improvements(Vince Vielhaber)
pg_dump now uses -z(ACL's) as default(Bruce)
backend cache, memory speedups(Tom)
have pg_dump do everything in one snapshot transaction(Vadim)
fix for large object memory leakage, fix for pg_dumping(Tom)
INET type now respects netmask for comparisons
Make VACUUM ANALYZE only use a readlock(Vadim)
Allow VIEWs on UNIONS(Jan)
pg_dump now can generate consistent snapshots on active
 databases(Vadim)

Source Tree Changes
-------------------
Improve port matching(Tom)
Portability fixes for SunOS
Add Windows NT backend port and enable dynamic loading(Magnus and
 Daniel Horak)
New port to Cobalt Qube(Mips) running Linux(Tatsuo)
Port to NetBSD/m68k(Mr. Mutsuki Nakajima)
Port to NetBSD/sun3(Mr. Mutsuki Nakajima)
Port to NetBSD/macppc(Toshimi Aoki)
Fix for tcl/tk configuration(Vince)
Removed CURRENT key word for rule queries(Jan)
NT dynamic loading now works(Daniel Horak)
Add ARM32 support(Andrew McMurry)
Better support for HP-UX 11 and UnixWare
Improve file handling to be more uniform, prevent file descriptor
 leak(Tom)
New install commands for plpgsql(Jan)
```

A.44. Release 6.4.2

Release date

1998-12-20

The 6.4.1 release was improperly packaged. This also has one additional bug fix.

A.44.1. Migration to Version 6.4.2

A dump/restore is *not* required for those running 6.4.*.

A.44.2. Changes

```
Fix for datetime constant problem on some platforms(Thomas)
```

A.45. Release 6.4.1

Release date

1998-12-18

This is basically a cleanup release for 6.4. We have fixed a variety of problems reported by 6.4 users.

A.45.1. Migration to Version 6.4.1

A dump/restore is *not* required for those running 6.4.

A.45.2. Changes

```
Add pg_dump -N flag to force double quotes around identifiers.
 This is
       the default(Thomas)
Fix for NOT in where clause causing crash(Bruce)
EXPLAIN VERBOSE coredump fix(Vadim)
Fix shared-library problems on Linux
Fix test for table existence to allow mixed-case and whitespace in
       the table name(Thomas)
Fix a couple of pg_dump bugs
Configure matches template/.similar entries better(Tom)
Change builtin function names from SPI_* to spi_*
OR WHERE clause fix(Vadim)
Fixes for mixed-case table names(Billy)
contrib/linux/postgres.init.csh/sh fix(Thomas)
libpq memory overrun fix
SunOS fixes(Tom)
Change exp() behavior to generate error on underflow(Thomas)
pg_dump fixes for memory leak, inheritance constraints, layout
 change
update pgaccess to 0.93
Fix prototype for 64-bit platforms
Multibyte fixes(Tatsuo)
New ecpg man page
Fix memory overruns(Tatsuo)
Fix for lo_import() crash(Bruce)
Better search for install program(Tom)
Timezone fixes(Tom)
```

```
HP-UX fixes(Tom)
Use implicit type coercion for matching DEFAULT values(Thomas)
Add routines to help with single-byte (internal) character
 type(Thomas)
Compilation of libpq for Windows fixes(Magnus)
Upgrade to PyGreSQL 2.2(D'Arcy)
```

A.46. Release 6.4

Release date

1998-10-30

There are *many* new features and improvements in this release. Thanks to our developers and maintainers, nearly every aspect of the system has received some attention since the previous release. Here is a brief, incomplete summary:

- Views and rules are now functional thanks to extensive new code in the rewrite rules system from Jan Wieck. He also wrote a chapter on it for the *Programmer's Guide*.
- Jan also contributed a second procedural language, PL/pgSQL, to go with the original PL/pgTCL procedural language he contributed last release.
- We have optional multiple-byte character set support from Tatsuo Ishii to complement our existing locale support.
- Client/server communications has been cleaned up, with better support for asynchronous messages and interrupts thanks to Tom Lane.
- The parser will now perform automatic type coercion to match arguments to available operators and functions, and to match columns and expressions with target columns. This uses a generic mechanism which supports the type extensibility features of PostgreSQL. There is a new chapter in the *User's Guide* which covers this topic.
- Three new data types have been added. Two types, `inet` and `cidr`, support various forms of IP network, subnet, and machine addressing. There is now an 8-byte integer type available on some platforms. See the chapter on data types in the *User's Guide* for details. A fourth type, `serial`, is now supported by the parser as an amalgam of the `int4` type, a sequence, and a unique index.
- Several more SQL92-compatible syntax features have been added, including `INSERT DEFAULT VALUES`
- The automatic configuration and installation system has received some attention, and should be more robust for more platforms than it has ever been.

A.46.1. Migration to Version 6.4

A dump/restore using pg_dump or pg_dumpall is required for those wishing to migrate data from any previous release of PostgreSQL.

A.46.2. Changes

```
Bug Fixes
---------
Fix for a tiny memory leak in PQsetdb/PQfinish(Bryan)
Remove char2-16 data types, use char/varchar(Darren)
Pqfn not handles a NOTICE message(Anders)
Reduced busywaiting overhead for spinlocks with many backends (dg)
Stuck spinlock detection (dg)
Fix up "ISO-style" timespan decoding and encoding(Thomas)
```

```
Fix problem with table drop after rollback of transaction(Vadim)
Change error message and remove non-functional update
 message(Vadim)
Fix for COPY array checking
Fix for SELECT 1 UNION SELECT NULL
Fix for buffer leaks in large object calls(Pascal)
Change owner from oid to int4 type(Bruce)
Fix a bug in the oracle compatibility functions btrim() ltrim() and
 rtrim()
Fix for shared invalidation cache overflow(Massimo)
Prevent file descriptor leaks in failed COPY's(Bruce)
Fix memory leak in libpgtcl's pg_select(Constantin)
Fix problems with username/passwords over 8 characters(Tom)
Fix problems with handling of asynchronous NOTIFY in backend(Tom)
Fix of many bad system table entries(Tom)

Enhancements
------------
Upgrade ecpg and ecpglib,see src/interfaces/ecpc/ChangeLog(Michael)
Show the index used in an EXPLAIN(Zeugswetter)
EXPLAIN  invokes  rule system and shows plan(s) for rewritten
 queries(Jan)
Multibyte awareness of many data types and functions, via
 configure(Tatsuo)
New configure --with-mb option(Tatsuo)
New initdb --pgencoding option(Tatsuo)
New createdb -E multibyte option(Tatsuo)
Select version(); now returns PostgreSQL version(Jeroen)
libpq now allows asynchronous clients(Tom)
Allow cancel from client of backend query(Tom)
psql now cancels query with Control-C(Tom)
libpq users need not issue dummy queries to get NOTIFY
 messages(Tom)
NOTIFY now sends sender's PID, so you can tell whether it was your
 own(Tom)
PGresult struct now includes associated error message, if any(Tom)
Define "tz_hour" and "tz_minute" arguments to date_part()(Thomas)
Add routines to convert between varchar and bpchar(Thomas)
Add routines to allow sizing of varchar and bpchar into target
 columns(Thomas)
Add bit flags to support timezonehour and minute in data
 retrieval(Thomas)
Allow more variations on valid floating point numbers (e.g. ".1",
 "1e6")(Thomas)
Fixes for unary minus parsing with leading spaces(Thomas)
Implement TIMEZONE_HOUR, TIMEZONE_MINUTE per SQL92 specs(Thomas)
Check for and properly ignore FOREIGN KEY column
 constraints(Thomas)
Define USER as synonym for CURRENT_USER per SQL92 specs(Thomas)
Enable HAVING clause but no fixes elsewhere yet.
Make "char" type a synonym for "char(1)" (actually implemented as
 bpchar)(Thomas)
Save string type if specified for DEFAULT clause handling(Thomas)
Coerce operations involving different data types(Thomas)
Allow some index use for columns of different types(Thomas)
Add capabilities for automatic type conversion(Thomas)
Cleanups for large objects, so file is truncated on open(Peter)
Readline cleanups(Tom)
```

```
Allow psql  \f \ to make spaces as delimiter(Bruce)
Pass pg_attribute.atttypmod to the frontend for column field
 lengths(Tom,Bruce)
Msql compatibility library in /contrib(Aldrin)
Remove the requirement that ORDER/GROUP BY clause identifiers be
included in the target list(David)
Convert columns to match columns in UNION clauses(Thomas)
Remove fork()/exec() and only do fork()(Bruce)
Jdbc cleanups(Peter)
Show backend status on ps command line(only works on some
 platforms)(Bruce)
Pg_hba.conf now has a sameuser option in the database field
Make lo_unlink take oid param, not int4
New DISABLE_COMPLEX_MACRO for compilers that cannot handle our
 macros(Bruce)
Libpgtcl now handles NOTIFY as a Tcl event, need not send dummy
 queries(Tom)
libpgtcl cleanups(Tom)
Add -error option to libpgtcl's pg_result command(Tom)
New locale patch, see docs/README/locale(Oleg)
Fix for pg_dump so CONSTRAINT and CHECK syntax is correct(ccb)
New contrib/lo code for large object orphan removal(Peter)
New psql command "SET CLIENT_ENCODING TO 'encoding'" for multibytes
feature, see /doc/README.mb(Tatsuo)
contrib/noupdate code to revoke update permission on a column
libpq can now be compiled on Windows(Magnus)
Add PQsetdbLogin() in libpq
New 8-byte integer type, checked by configure for OS
 support(Thomas)
Better support for quoted table/column names(Thomas)
Surround table and column names with double-quotes in
 pg_dump(Thomas)
PQreset() now works with passwords(Tom)
Handle case of GROUP BY target list column number out of
 range(David)
Allow UNION in subselects
Add auto-size to screen to \d? commands(Bruce)
Use UNION to show all \d? results in one query(Bruce)
Add \d? field search feature(Bruce)
Pg_dump issues fewer \connect requests(Tom)
Make pg_dump -z flag work better, document it in manual page(Tom)
Add HAVING clause with full support for subselects and
 unions(Stephan)
Full text indexing routines in contrib/fulltextindex(Maarten)
Transaction ids now stored in shared memory(Vadim)
New PGCLIENTENCODING when issuing COPY command(Tatsuo)
Support for SQL92 syntax "SET NAMES"(Tatsuo)
Support for LATIN2-5(Tatsuo)
Add UNICODE regression test case(Tatsuo)
Lock manager cleanup, new locking modes for LLL(Vadim)
Allow index use with OR clauses(Bruce)
Allows "SELECT NULL ORDER BY 1;"
Explain VERBOSE prints the plan, and now pretty-prints the plan to
the postmaster log file(Bruce)
Add indexes display to \d command(Bruce)
Allow GROUP BY on functions(David)
New pg_class.relkind for large objects(Bruce)
New way to send libpq NOTICE messages to a different location(Tom)
```

```
New \w write command to psql(Bruce)
New /contrib/findoidjoins scans oid columns to find join
 relationships(Bruce)
Allow binary-compatible indexes to be considered when checking for
 valid
Indexes for restriction clauses containing a constant(Thomas)
New ISBN/ISSN code in /contrib/isbn_issn
Allow NOT LIKE, IN, NOT IN, BETWEEN, and NOT BETWEEN
 constraint(Thomas)
New rewrite system fixes many problems with rules and views(Jan)
       * Rules on relations work
       * Event qualifications on insert/update/delete work
       * New OLD variable to reference CURRENT, CURRENT will be
 remove in future
       * Update rules can reference NEW and OLD in rule
 qualifications/actions
       * Insert/update/delete rules on views work
       * Multiple rule actions are now supported, surrounded by
 parentheses
       * Regular users can create views/rules on tables they have
 RULE permits
       * Rules and views inherit the privileges of the creator
       * No rules at the column level
       * No UPDATE NEW/OLD rules
       * New pg_tables, pg_indexes, pg_rules and pg_views system
 views
       * Only a single action on SELECT rules
       * Total rewrite overhaul, perhaps for 6.5
       * handle subselects
       * handle aggregates on views
       * handle insert into select from view works
System indexes are now multikey(Bruce)
Oidint2, oidint4, and oidname types are removed(Bruce)
Use system cache for more system table lookups(Bruce)
New backend programming language PL/pgSQL in backend/pl(Jan)
New SERIAL data type, auto-creates sequence/index(Thomas)
Enable assert checking without a recompile(Massimo)
User lock enhancements(Massimo)
New setval() command to set sequence value(Massimo)
Auto-remove unix socket file on start-up if no postmaster
 running(Massimo)
Conditional trace package(Massimo)
New UNLISTEN command(Massimo)
psql and libpq now compile under Windows using win32.mak(Magnus)
Lo_read no longer stores trailing NULL(Bruce)
Identifiers are now truncated to 31 characters internally(Bruce)
Createuser options now available on the command line
Code for 64-bit integer supported added, configure tested, int8
 type(Thomas)
Prevent file descriptor leaf from failed COPY(Bruce)
New pg_upgrade command(Bruce)
Updated /contrib directories(Massimo)
New CREATE TABLE DEFAULT VALUES statement available(Thomas)
New INSERT INTO TABLE DEFAULT VALUES statement available(Thomas)
New DECLARE and FETCH feature(Thomas)
libpq's internal structures now not exported(Tom)
Allow up to 8 key indexes(Bruce)
Remove ARCHIVE key word, that is no longer used(Thomas)
```

```
pg_dump -n flag to suppress quotes around indentifiers
disable system columns for views(Jan)
new INET and CIDR types for network addresses(TomH, Paul)
no more double quotes in psql output
pg_dump now dumps views(Terry)
new SET QUERY_LIMIT(Tatsuo,Jan)

Source Tree Changes
-------------------
/contrib cleanup(Jun)
Inline some small functions called for every row(Bruce)
Alpha/linux fixes
HP-UX cleanups(Tom)
Multibyte regression tests(Soonmyung.)
Remove --disabled options from configure
Define PGDOC to use POSTGRESDIR by default
Make regression optional
Remove extra braces code to pgindent(Bruce)
Add bsdi shared library support(Bruce)
New --without-CXX support configure option(Brook)
New FAQ_CVS
Update backend flowchart in tools/backend(Bruce)
Change atttypmod from int16 to int32(Bruce, Tom)
Getrusage() fix for platforms that do not have it(Tom)
Add PQconnectdb, PGUSER, PGPASSWORD to libpq man page
NS32K platform fixes(Phil Nelson, John Buller)
SCO 7/UnixWare 2.x fixes(Billy,others)
Sparc/Solaris 2.5 fixes(Ryan)
Pgbuiltin.3 is obsolete, move to doc files(Thomas)
Even more documentation(Thomas)
Nextstep support(Jacek)
Aix support(David)
pginterface manual page(Bruce)
shared libraries all have version numbers
merged all OS-specific shared library defines into one file
smarter TCL/TK configuration checking(Billy)
smarter perl configuration(Brook)
configure uses supplied install-sh if no install script found(Tom)
new Makefile.shlib for shared library configuration(Tom)
```

A.47. Release 6.3.2

Release date

1998-04-07

This is a bug-fix release for 6.3.x. Refer to the release notes for version 6.3 for a more complete summary of new features.

Summary:

- Repairs automatic configuration support for some platforms, including Linux, from breakage inadvertently introduced in version 6.3.1.
- Correctly handles function calls on the left side of BETWEEN and LIKE clauses.

A dump/restore is NOT required for those running 6.3 or 6.3.1. A `make distclean`, `make`, and `make install` is all that is required. This last step should be performed while the postmaster is not running. You should re-link any custom applications that use PostgreSQL libraries.

For upgrades from pre-6.3 installations, refer to the installation and migration instructions for version 6.3.

A.47.1. Changes

```
Configure detection improvements for tcl/tk(Brook Milligan, Alvin)
Manual page improvements(Bruce)
BETWEEN and LIKE fix(Thomas)
fix for psql \connect used by pg_dump(Oliver Elphick)
New odbc driver
pgaccess, version 0.86
qsort removed, now uses libc version, cleanups(Jeroen)
fix for buffer over-runs detected(Maurice Gittens)
fix for buffer overrun in libpgtcl(Randy Kunkee)
fix for UNION with DISTINCT or ORDER BY(Bruce)
gettimeofday configure check(Doug Winterburn)
Fix "indexes not used" bug(Vadim)
docs additions(Thomas)
Fix for backend memory leak(Bruce)
libreadline cleanup(Erwan MAS)
Remove DISTDIR(Bruce)
Makefile dependency cleanup(Jeroen van Vianen)
ASSERT fixes(Bruce)
```

A.48. Release 6.3.1

Release date

1998-03-23

Summary:

- Additional support for multibyte character sets.
- Repair byte ordering for mixed-endian clients and servers.
- Minor updates to allowed SQL syntax.
- Improvements to the configuration autodetection for installation.

A dump/restore is NOT required for those running 6.3. A `make distclean`, `make`, and `make install` is all that is required. This last step should be performed while the postmaster is not running. You should re-link any custom applications that use PostgreSQL libraries.

For upgrades from pre-6.3 installations, refer to the installation and migration instructions for version 6.3.

A.48.1. Changes

```
ecpg cleanup/fixes, now version 1.1(Michael Meskes)
pg_user cleanup(Bruce)
large object fix for pg_dump and tclsh (alvin)
LIKE fix for multiple adjacent underscores
fix for redefining builtin functions(Thomas)
ultrix4 cleanup
upgrade to pg_access 0.83
updated CLUSTER manual page
multibyte character set support, see doc/README.mb(Tatsuo)
```

```
configure --with-pgport fix
pg_ident fix
big-endian fix for backend communications(Kataoka)
SUBSTR() and substring() fix(Jan)
several jdbc fixes(Peter)
libpgtcl improvements, see libptcl/README(Randy Kunkee)
Fix for "Datasize = 0" error(Vadim)
Prevent \do from wrapping(Bruce)
Remove duplicate Russian character set entries
Sunos4 cleanup
Allow optional TABLE key word in LOCK and SELECT INTO(Thomas)
CREATE SEQUENCE options to allow a negative integer(Thomas)
Add "PASSWORD" as an allowed column identifier(Thomas)
Add checks for UNION target fields(Bruce)
Fix Alpha port(Dwayne Bailey)
Fix for text arrays containing quotes(Doug Gibson)
Solaris compile fix(Albert Chin-A-Young)
Better identify tcl and tk libs and includes(Bruce)
```

A.49. Release 6.3

Release date

1998-03-01

There are *many* new features and improvements in this release. Here is a brief, incomplete summary:

- Many new SQL features, including full SQL92 subselect capability (everything is here but target-list subselects).
- Support for client-side environment variables to specify time zone and date style.
- Socket interface for client/server connection. This is the default now so you might need to start postmaster with the `-i` flag.
- Better password authorization mechanisms. Default table privileges have changed.
- Old-style *time travel* has been removed. Performance has been improved.

Note

Bruce Momjian wrote the following notes to introduce the new release.

There are some general 6.3 issues that I want to mention. These are only the big items that cannot be described in one sentence. A review of the detailed changes list is still needed.

First, we now have subselects. Now that we have them, I would like to mention that without subselects, SQL is a very limited language. Subselects are a major feature, and you should review your code for places where subselects provide a better solution for your queries. I think you will find that there are more uses for subselects than you might think. Vadim has put us on the big SQL map with subselects, and fully functional ones too. The only thing you cannot do with subselects is to use them in the target list.

Second, 6.3 uses Unix domain sockets rather than TCP/IP by default. To enable connections from other machines, you have to use the new postmaster -i option, and of course edit `pg_hba.conf`. Also, for this reason, the format of `pg_hba.conf` has changed.

Third, `char()` fields will now allow faster access than `varchar()` or `text`. Specifically, the `text` and `varchar()` have a penalty for access to any columns after the first column of this type. `char()` used to also have this access penalty, but it no longer does. This might suggest that you redesign some

of your tables, especially if you have short character columns that you have defined as `varchar()` or `text`. This and other changes make 6.3 even faster than earlier releases.

We now have passwords definable independent of any Unix file. There are new SQL USER commands. See the *Administrator's Guide* for more information. There is a new table, pg_shadow, which is used to store user information and user passwords, and it by default only SELECT-able by the postgres super-user. pg_user is now a view of pg_shadow, and is SELECT-able by PUBLIC. You should keep using pg_user in your application without changes.

User-created tables now no longer have SELECT privilege to PUBLIC by default. This was done because the ANSI standard requires it. You can of course GRANT any privileges you want after the table is created. System tables continue to be SELECT-able by PUBLIC.

We also have real deadlock detection code. No more sixty-second timeouts. And the new locking code implements a FIFO better, so there should be less resource starvation during heavy use.

Many complaints have been made about inadequate documentation in previous releases. Thomas has put much effort into many new manuals for this release. Check out the doc/ directory.

For performance reasons, time travel is gone, but can be implemented using triggers (see `pgsql/contrib/spi/README`). Please check out the new \d command for types, operators, etc. Also, views have their own privileges now, not based on the underlying tables, so privileges on them have to be set separately. Check `/pgsql/interfaces` for some new ways to talk to PostgreSQL.

This is the first release that really required an explanation for existing users. In many ways, this was necessary because the new release removes many limitations, and the work-arounds people were using are no longer needed.

A.49.1. Migration to Version 6.3

A dump/restore using pg_dump or pg_dumpall is required for those wishing to migrate data from any previous release of PostgreSQL.

A.49.2. Changes

```
Bug Fixes
---------
Fix binary cursors broken by MOVE implementation(Vadim)
Fix for tcl library crash(Jan)
Fix for array handling, from Gerhard Hintermayer
Fix acl error, and remove duplicate pqtrace(Bruce)
Fix psql \e for empty file(Bruce)
Fix for textcat on varchar() fields(Bruce)
Fix for DBT Sendproc (Zeugswetter Andres)
Fix vacuum analyze syntax problem(Bruce)
Fix for international identifiers(Tatsuo)
Fix aggregates on inherited tables(Bruce)
Fix substr() for out-of-bounds data
Fix for select 1=1 or 2=2, select 1=1 and 2=2, and select sum(2+2)
(Bruce)
Fix notty output to show status result.  -q option still turns it
 off(Bruce)
Fix for count(*), aggs with views and multiple tables and sum(3)
(Bruce)
Fix cluster(Bruce)
Fix for PQtrace start/stop several times(Bruce)
Fix a variety of locking problems like newer lock waiters getting
       lock before older waiters, and having readlock people not
 share
```

```
      locks if a writer is waiting for a lock, and waiting writers
 not
      getting priority over waiting readers(Bruce)
Fix crashes in psql when executing queries from external
 files(James)
Fix problem with multiple order by columns, with the first one
 having
      NULL values(Jeroen)
Use correct hash table support functions for float8 and
 int4(Thomas)
Re-enable JOIN= option in CREATE OPERATOR statement (Thomas)
Change precedence for boolean operators to match expected
 behavior(Thomas)
Generate elog(ERROR) on over-large integer(Bruce)
Allow multiple-argument functions in constraint clauses(Thomas)
Check boolean input literals for 'true','false','yes','no','1','0'
      and throw elog(ERROR) if unrecognized(Thomas)
Major large objects fix
Fix for GROUP BY showing duplicates(Vadim)
Fix for index scans in MergeJoin(Vadim)

Enhancements
------------
Subselects with EXISTS, IN, ALL, ANY key words (Vadim, Bruce,
 Thomas)
New User Manual(Thomas, others)
Speedup by inlining some frequently-called functions
Real deadlock detection, no more timeouts(Bruce)
Add SQL92 "constants" CURRENT_DATE, CURRENT_TIME,
 CURRENT_TIMESTAMP,
      CURRENT_USER(Thomas)
Modify constraint syntax to be SQL92-compliant(Thomas)
Implement SQL92 PRIMARY KEY and UNIQUE clauses using
 indexes(Thomas)
Recognize SQL92 syntax for FOREIGN KEY. Throw elog notice(Thomas)
Allow NOT NULL UNIQUE constraint clause (each allowed separately
 before)(Thomas)
Allow PostgreSQL-style casting ("::") of non-constants(Thomas)
Add support for SQL3 TRUE and FALSE boolean constants(Thomas)
Support SQL92 syntax for IS TRUE/IS FALSE/IS NOT TRUE/IS NOT
 FALSE(Thomas)
Allow shorter strings for boolean literals (e.g. "t", "tr", "tru")
(Thomas)
Allow SQL92 delimited identifiers(Thomas)
Implement SQL92 binary and hexadecimal string decoding (b'10' and
 x'1F')(Thomas)
Support SQL92 syntax for type coercion of literal strings
      (e.g. "DATETIME 'now'")(Thomas)
Add conversions for int2, int4, and OID types to and from
 text(Thomas)
Use shared lock when building indexes(Vadim)
Free memory allocated for an user query inside transaction block
 after
      this query is done, was turned off in <= 6.2.1(Vadim)
New SQL statement CREATE PROCEDURAL LANGUAGE(Jan)
New PostgreSQL Procedural Language (PL) backend interface(Jan)
Rename pg_dump -H option to -h(Bruce)
Add Java support for passwords, European dates(Peter)
```

```
Use indexes for LIKE and ~, !~ operations(Bruce)
Add hash functions for datetime and timespan(Thomas)
Time Travel removed(Vadim, Bruce)
Add paging for \d and \z, and fix \i(Bruce)
Add Unix domain socket support to backend and to frontend
 library(Goran)
Implement CREATE DATABASE/WITH LOCATION and initlocation
 utility(Thomas)
Allow more SQL92 and/or PostgreSQL reserved words as column
 identifiers(Thomas)
Augment support for SQL92 SET TIME ZONE...(Thomas)
SET/SHOW/RESET TIME ZONE uses TZ backend environment
 variable(Thomas)
Implement SET keyword = DEFAULT and SET TIME ZONE DEFAULT(Thomas)
Enable SET TIME ZONE using TZ environment variable(Thomas)
Add PGDATESTYLE environment variable to frontend and backend
 initialization(Thomas)
Add PGTZ, PGCOSTHEAP, PGCOSTINDEX, PGRPLANS, PGGEQO
       frontend library initialization environment
 variables(Thomas)
Regression tests time zone automatically set with "setenv PGTZ
 PST8PDT"(Thomas)
Add pg_description table for info on tables, columns, operators,
 types, and
       aggregates(Bruce)
Increase 16 char limit on system table/index names to 32
 characters(Bruce)
Rename system indexes(Bruce)
Add 'GERMAN' option to SET DATESTYLE(Thomas)
Define an "ISO-style" timespan output format with "hh:mm:ss"
 fields(Thomas)
Allow fractional values for delta times (e.g. '2.5 days')(Thomas)
Validate numeric input more carefully for delta times(Thomas)
Implement day of year as possible input to date_part()(Thomas)
Define timespan_finite() and text_timespan() functions(Thomas)
Remove archive stuff(Bruce)
Allow for a pg_password authentication database that is separate
 from
       the system password file(Todd)
Dump ACLs, GRANT, REVOKE privileges(Matt)
Define text, varchar, and bpchar string length functions(Thomas)
Fix Query handling for inheritance, and cost computations(Bruce)
Implement CREATE TABLE/AS SELECT (alternative to SELECT/INTO)
(Thomas)
Allow NOT, IS NULL, IS NOT NULL in constraints(Thomas)
Implement UNIONs for SELECT(Bruce)
Add UNION, GROUP, DISTINCT to INSERT(Bruce)
varchar() stores only necessary bytes on disk(Bruce)
Fix for BLOBs(Peter)
Mega-Patch for JDBC...see README_6.3 for list of changes(Peter)
Remove unused "option" from PQconnectdb()
New LOCK command and lock manual page describing deadlocks(Bruce)
Add new psql \da, \dd, \df, \do, \dS, and \dT commands(Bruce)
Enhance psql \z to show sequences(Bruce)
Show NOT NULL and DEFAULT in psql \d table(Bruce)
New psql .psqlrc file start-up(Andrew)
Modify sample start-up script in contrib/linux to show
 syslog(Thomas)
```

```
New types for IP and MAC addresses in contrib/ip_and_mac(TomH)
Unix system time conversions with date/time types in contrib/
unixdate(Thomas)
Update of contrib stuff(Massimo)
Add Unix socket support to DBD::Pg(Goran)
New python interface (PyGreSQL 2.0)(D'Arcy)
New frontend/backend protocol has a version number, network byte
 order(Phil)
Security features in pg_hba.conf enhanced and documented, many
 cleanups(Phil)
CHAR() now faster access than VARCHAR() or TEXT
ecpg embedded SQL preprocessor
Reduce system column overhead(Vadmin)
Remove pg_time table(Vadim)
Add pg_type attribute to identify types that need length (bpchar,
 varchar)
Add report of offending line when COPY command fails
Allow VIEW privileges to be set separately from the underlying
 tables.
       For security, use GRANT/REVOKE on views as appropriate(Jan)
Tables now have no default GRANT SELECT TO PUBLIC.  You must
       explicitly grant such privileges.
Clean up tutorial examples(Darren)

Source Tree Changes
-------------------
Add new html development tools, and flow chart in /tools/backend
Fix for SCO compiles
Stratus computer port Robert Gillies
Added support for shlib for BSD44_derived & i386_solaris
Make configure more automated(Brook)
Add script to check regression test results
Break parser functions into smaller files, group together(Bruce)
Rename heap_create to heap_create_and_catalog, rename heap_creatr
       to heap_create()(Bruce)
Sparc/Linux patch for locking(TomS)
Remove PORTNAME and reorganize port-specific stuff(Marc)
Add optimizer README file(Bruce)
Remove some recursion in optimizer and clean up some code
 there(Bruce)
Fix for NetBSD locking(Henry)
Fix for libptcl make(Tatsuo)
AIX patch(Darren)
Change IS TRUE, IS FALSE, ... to expressions using "=" rather than
       function calls to istrue() or isfalse() to allow
 optimization(Thomas)
Various fixes NetBSD/Sparc related(TomH)
Alpha linux locking(Travis,Ryan)
Change elog(WARN) to elog(ERROR)(Bruce)
FAQ for FreeBSD(Marc)
Bring in the PostODBC source tree as part of our standard
 distribution(Marc)
A minor patch for HP/UX 10 vs 9(Stan)
New pg_attribute.atttypmod for type-specific info like varchar
 length(Bruce)
UnixWare patches(Billy)
New i386 'lock' for spinlock asm(Billy)
Support for multiplexed backends is removed
```

```
Start an OpenBSD port
Start an AUX port
Start a Cygnus port
Add string functions to regression suite(Thomas)
Expand a few function names formerly truncated to 16
 characters(Thomas)
Remove un-needed malloc() calls and replace with palloc()(Bruce)
```

A.50. Release 6.2.1

Release date

1997-10-17

6.2.1 is a bug-fix and usability release on 6.2.

Summary:

- Allow strings to span lines, per SQL92.
- Include example trigger function for inserting user names on table updates.

This is a minor bug-fix release on 6.2. For upgrades from pre-6.2 systems, a full dump/reload is required. Refer to the 6.2 release notes for instructions.

A.50.1. Migration from version 6.2 to version 6.2.1

This is a minor bug-fix release. A dump/reload is not required from version 6.2, but is required from any release prior to 6.2.

In upgrading from version 6.2, if you choose to dump/reload you will find that avg(money) is now calculated correctly. All other bug fixes take effect upon updating the executables.

Another way to avoid dump/reload is to use the following SQL command from `psql` to update the existing system table:

```
update pg_aggregate set aggfinalfn = 'cash_div_flt8'
 where aggname = 'avg' and aggbasetype = 790;
```

This will need to be done to every existing database, including template1.

A.50.2. Changes

```
Allow TIME and TYPE column names(Thomas)
Allow larger range of true/false as boolean values(Thomas)
Support output of "now" and "current"(Thomas)
Handle DEFAULT with INSERT of NULL properly(Vadim)
Fix for relation reference counts problem in buffer manager(Vadim)
Allow strings to span lines, like ANSI(Thomas)
Fix for backward cursor with ORDER BY(Vadim)
Fix avg(cash) computation(Thomas)
Fix for specifying a column twice in ORDER/GROUP BY(Vadim)
Documented new libpq function to return affected rows,
 PQcmdTuples(Bruce)
Trigger function for inserting user names for INSERT/UPDATE(Brook
 Milligan)
```

A.51. Release 6.2

Release date

1997-10-02

A dump/restore is required for those wishing to migrate data from previous releases of PostgreSQL.

A.51.1. Migration from version 6.1 to version 6.2

This migration requires a complete dump of the 6.1 database and a restore of the database in 6.2.

Note that the `pg_dump` and `pg_dumpall` utility from 6.2 should be used to dump the 6.1 database.

A.51.2. Migration from version 1.*x* to version 6.2

Those migrating from earlier 1.* releases should first upgrade to 1.09 because the COPY output format was improved from the 1.02 release.

A.51.3. Changes

```
Bug Fixes
---------
Fix problems with pg_dump for inheritance, sequences, archive
 tables(Bruce)
Fix compile errors on overflow due to shifts, unsigned, and bad
 prototypes
        from Solaris(Diab Jerius)
Fix bugs in geometric line arithmetic (bad intersection
 calculations)(Thomas)
Check for geometric intersections at endpoints to avoid rounding
 ugliness(Thomas)
Catch non-functional delete attempts(Vadim)
Change time function names to be more consistent(Michael
 Reifenberg)
Check for zero divides(Michael Reifenberg)
Fix very old bug which made rows changed/inserted by a command
       visible to the command itself (so we had multiple update of
       updated rows, etc.)(Vadim)
Fix for SELECT null, 'fail' FROM pg_am (Patrick)
SELECT NULL as EMPTY_FIELD now allowed(Patrick)
Remove un-needed signal stuff from contrib/pginterface
Fix OR (where x != 1 or x isnull didn't return rows with x NULL)
 (Vadim)
Fix time_cmp function (Vadim)
Fix handling of functions with non-attribute first argument in
       WHERE clauses (Vadim)
Fix GROUP BY when order of entries is different from order
       in target list (Vadim)
Fix pg_dump for aggregates without sfunc1 (Vadim)

Enhancements
------------
Default genetic optimizer GEQO parameter is now 8(Bruce)
Allow use parameters in target list having aggregates in
 functions(Vadim)
Added JDBC driver as an interface(Adrian & Peter)
```

```
pg_password utility
Return number of rows inserted/affected by INSERT/UPDATE/DELETE
 etc.(Vadim)
Triggers implemented with CREATE TRIGGER (SQL3)(Vadim)
SPI (Server Programming Interface) allows execution of queries
 inside
       C-functions (Vadim)
NOT NULL implemented (SQL92)(Robson Paniago de Miranda)
Include reserved words for string handling, outer joins, and
 unions(Thomas)
Implement extended comments ("/* ... */") using exclusive
 states(Thomas)
Add "//" single-line comments(Bruce)
Remove some restrictions on characters in operator names(Thomas)
DEFAULT and CONSTRAINT for tables implemented (SQL92)(Vadim &
 Thomas)
Add text concatenation operator and function (SQL92)(Thomas)
Support WITH TIME ZONE syntax (SQL92)(Thomas)
Support INTERVAL unit TO unit syntax (SQL92)(Thomas)
Define types DOUBLE PRECISION, INTERVAL, CHARACTER,
       and CHARACTER VARYING (SQL92)(Thomas)
Define type FLOAT(p) and rudimentary DECIMAL(p,s), NUMERIC(p,s)
 (SQL92)(Thomas)
Define EXTRACT(), POSITION(), SUBSTRING(), and TRIM() (SQL92)
(Thomas)
Define CURRENT_DATE, CURRENT_TIME, CURRENT_TIMESTAMP (SQL92)
(Thomas)
Add syntax and warnings for UNION, HAVING, INNER and OUTER JOIN
 (SQL92)(Thomas)
Add more reserved words, mostly for SQL92 compliance(Thomas)
Allow hh:mm:ss time entry for timespan/reltime types(Thomas)
Add center() routines for lseg, path, polygon(Thomas)
Add distance() routines for circle-polygon, polygon-polygon(Thomas)
Check explicitly for points and polygons contained within polygons
       using an axis-crossing algorithm(Thomas)
Add routine to convert circle-box(Thomas)
Merge conflicting operators for different geometric data
 types(Thomas)
Replace distance operator "<===>" with "<->"(Thomas)
Replace "above" operator "!^" with ">^" and "below" operator "!|"
 with "<^"(Thomas)
Add routines for text trimming on both ends, substring, and string
 position(Thomas)
Added conversion routines circle(box) and poly(circle)(Thomas)
Allow internal sorts to be stored in memory rather than in
 files(Bruce & Vadim)
Allow functions and operators on internally-identical types to
 succeed(Bruce)
Speed up backend start-up after profiling analysis(Bruce)
Inline frequently called functions for performance(Bruce)
Reduce open() calls(Bruce)
psql:  Add PAGER for \h and \?,\C fix
Fix for psql pager when no tty(Bruce)
New entab utility(Bruce)
General trigger functions for referential integrity (Vadim)
General trigger functions for time travel (Vadim)
General trigger functions for AUTOINCREMENT/IDENTITY feature
 (Vadim)
```

```
MOVE implementation (Vadim)

Source Tree Changes
-------------------
HP-UX 10 patches (Vladimir Turin)
Added SCO support, (Daniel Harris)
MkLinux patches (Tatsuo Ishii)
Change geometric box terminology from "length" to "width"(Thomas)
Deprecate temporary unstored slope fields in geometric code(Thomas)
Remove restart instructions from INSTALL(Bruce)
Look in /usr/ucb first for install(Bruce)
Fix c++ copy example code(Thomas)
Add -o to psql manual page(Bruce)
Prevent relname unallocated string length from being copied into
 database(Bruce)
Cleanup for NAMEDATALEN use(Bruce)
Fix pg_proc names over 15 chars in output(Bruce)
Add strNcpy() function(Bruce)
remove some (void) casts that are unnecessary(Bruce)
new interfaces directory(Marc)
Replace fopen() calls with calls to fd.c functions(Bruce)
Make functions static where possible(Bruce)
enclose unused functions in #ifdef NOT_USED(Bruce)
Remove call to difftime() in timestamp support to fix SunOS(Bruce &
 Thomas)
Changes for Digital Unix
Portability fix for pg_dumpall(Bruce)
Rename pg_attribute.attnvals to attdispersion(Bruce)
"intro/unix" manual page now "pgintro"(Bruce)
"built-in" manual page now "pgbuiltin"(Bruce)
"drop" manual page now "drop_table"(Bruce)
Add "create_trigger", "drop_trigger" manual pages(Thomas)
Add constraints regression test(Vadim & Thomas)
Add comments syntax regression test(Thomas)
Add PGINDENT and support program(Bruce)
Massive commit to run PGINDENT on all *.c and *.h files(Bruce)
Files moved to /src/tools directory(Bruce)
SPI and Trigger programming guides (Vadim & D'Arcy)
```

A.52. Release 6.1.1

Release date

1997-07-22

A.52.1. Migration from version 6.1 to version 6.1.1

This is a minor bug-fix release. A dump/reload is not required from version 6.1, but is required from any release prior to 6.1. Refer to the release notes for 6.1 for more details.

A.52.2. Changes

```
fix for SET with options (Thomas)
allow pg_dump/pg_dumpall to preserve ownership of all tables/
objects(Bruce)
new psql \connect option allows changing usernames without changing
 databases
```

```
fix for initdb --debug option(Yoshihiko Ichikawa))
lextest cleanup(Bruce)
hash fixes(Vadim)
fix date/time month boundary arithmetic(Thomas)
fix timezone daylight handling for some ports(Thomas, Bruce,
 Tatsuo)
timestamp overhauled to use standard functions(Thomas)
other code cleanup in date/time routines(Thomas)
psql's \d now case-insensitive(Bruce)
psql's backslash commands can now have trailing semicolon(Bruce)
fix memory leak in psql when using \g(Bruce)
major fix for endian handling of communication to server(Thomas,
 Tatsuo)
Fix for Solaris assembler and include files(Yoshihiko Ichikawa)
allow underscores in usernames(Bruce)
pg_dumpall now returns proper status, portability fix(Bruce)
```

A.53. Release 6.1

Release date

1997-06-08

The regression tests have been adapted and extensively modified for the 6.1 release of PostgreSQL.

Three new data types (`datetime`, `timespan`, and `circle`) have been added to the native set of PostgreSQL types. Points, boxes, paths, and polygons have had their output formats made consistent across the data types. The polygon output in misc.out has only been spot-checked for correctness relative to the original regression output.

PostgreSQL 6.1 introduces a new, alternate optimizer which uses *genetic* algorithms. These algorithms introduce a random behavior in the ordering of query results when the query contains multiple qualifiers or multiple tables (giving the optimizer a choice on order of evaluation). Several regression tests have been modified to explicitly order the results, and hence are insensitive to optimizer choices. A few regression tests are for data types which are inherently unordered (e.g. points and time intervals) and tests involving those types are explicitly bracketed with `set geqo to 'off'` and `reset geqo`.

The interpretation of array specifiers (the curly braces around atomic values) appears to have changed sometime after the original regression tests were generated. The current `./expected/*.out` files reflect this new interpretation, which might not be correct!

The float8 regression test fails on at least some platforms. This is due to differences in implementations of `pow()` and `exp()` and the signaling mechanisms used for overflow and underflow conditions.

The “random” results in the random test should cause the “random” test to be “failed”, since the regression tests are evaluated using a simple diff. However, “random” does not seem to produce random results on my test machine (Linux/gcc/i686).

A.53.1. Migration to Version 6.1

This migration requires a complete dump of the 6.0 database and a restore of the database in 6.1.

Those migrating from earlier 1.* releases should first upgrade to 1.09 because the COPY output format was improved from the 1.02 release.

A.53.2. Changes

```
Bug Fixes
---------
packet length checking in library routines
lock manager priority patch
check for under/over flow of float8(Bruce)
multitable join fix(Vadim)
SIGPIPE crash fix(Darren)
large object fixes(Sven)
allow btree indexes to handle NULLs(Vadim)
timezone fixes(D'Arcy)
select SUM(x) can return NULL on no rows(Thomas)
internal optimizer, executor bug fixes(Vadim)
fix problem where inner loop in < or <= has no rows(Vadim)
prevent re-commuting join index clauses(Vadim)
fix join clauses for multiple tables(Vadim)
fix hash, hashjoin for arrays(Vadim)
fix btree for abstime type(Vadim)
large object fixes(Raymond)
fix buffer leak in hash indexes (Vadim)
fix rtree for use in inner scan (Vadim)
fix gist for use in inner scan, cleanups (Vadim, Andrea)
avoid unnecessary local buffers allocation (Vadim, Massimo)
fix local buffers leak in transaction aborts (Vadim)
fix file manager memmory leaks, cleanups (Vadim, Massimo)
fix storage manager memmory leaks (Vadim)
fix btree duplicates handling (Vadim)
fix deleted rows reincarnation caused by vacuum (Vadim)
fix SELECT varchar()/char() INTO TABLE made zero-length
 fields(Bruce)
many psql, pg_dump, and libpq memory leaks fixed using Purify
 (Igor)

Enhancements
------------
attribute optimization statistics(Bruce)
much faster new btree bulk load code(Paul)
BTREE UNIQUE added to bulk load code(Vadim)
new lock debug code(Massimo)
massive changes to libpg++(Leo)
new GEQO optimizer speeds table multitable optimization(Martin)
new WARN message for non-unique insert into unique key(Marc)
update x=-3, no spaces, now valid(Bruce)
remove case-sensitive identifier handling(Bruce,Thomas,Dan)
debug backend now pretty-prints tree(Darren)
new Oracle character functions(Edmund)
new plaintext password functions(Dan)
no such class or insufficient privilege changed to distinct
 messages(Dan)
new ANSI timestamp function(Dan)
new ANSI Time and Date types (Thomas)
move large chunks of data in backend(Martin)
multicolumn btree indexes(Vadim)
new SET var TO value command(Martin)
update transaction status on reads(Dan)
new locale settings for character types(Oleg)
```

```
new SEQUENCE serial number generator(Vadim)
GROUP BY function now possible(Vadim)
re-organize regression test(Thomas,Marc)
new optimizer operation weights(Vadim)
new psql \z grant/permit option(Marc)
new MONEY data type(D'Arcy,Thomas)
tcp socket communication speed improved(Vadim)
new VACUUM option for attribute statistics, and for certain columns
 (Vadim)
many geometric type improvements(Thomas,Keith)
additional regression tests(Thomas)
new datestyle variable(Thomas,Vadim,Martin)
more comparison operators for sorting types(Thomas)
new conversion functions(Thomas)
new more compact btree format(Vadim)
allow pg_dumpall to preserve database ownership(Bruce)
new SET GEQO=# and R_PLANS variable(Vadim)
old (!GEQO) optimizer can use right-sided plans (Vadim)
typechecking improvement in SQL parser(Bruce)
new SET, SHOW, RESET commands(Thomas,Vadim)
new \connect database USER option
new destroydb -i option (Igor)
new \dt and \di psql commands (Darren)
SELECT "\n" now escapes newline (A. Duursma)
new geometry conversion functions from old format (Thomas)

Source tree changes
-------------------
new configuration script(Marc)
readline configuration option added(Marc)
OS-specific configuration options removed(Marc)
new OS-specific template files(Marc)
no more need to edit Makefile.global(Marc)
re-arrange include files(Marc)
nextstep patches (Gregor Hoffleit)
removed Windows-specific code(Bruce)
removed postmaster -e option, now only postgres -e option (Bruce)
merge duplicate library code in front/backends(Martin)
now works with eBones, international Kerberos(Jun)
more shared library support
c++ include file cleanup(Bruce)
warn about buggy flex(Bruce)
DG/UX, Ultrix, IRIX, AIX portability fixes
```

A.54. Release 6.0

Release date

1997-01-29

A dump/restore is required for those wishing to migrate data from previous releases of PostgreSQL.

A.54.1. Migration from version 1.09 to version 6.0

This migration requires a complete dump of the 1.09 database and a restore of the database in 6.0.

A.54.2. Migration from pre-1.09 to version 6.0

Those migrating from earlier 1.* releases should first upgrade to 1.09 because the COPY output format was improved from the 1.02 release.

A.54.3. Changes

```
Bug Fixes
---------
ALTER TABLE bug - running postgres process needs to re-read table
 definition
Allow vacuum to be run on one table or entire database(Bruce)
Array fixes
Fix array over-runs of memory writes(Kurt)
Fix elusive btree range/non-range bug(Dan)
Fix for hash indexes on some types like time and date
Fix for pg_log size explosion
Fix permissions on lo_export()(Bruce)
Fix uninitialized reads of memory(Kurt)
Fixed ALTER TABLE ... char(3) bug(Bruce)
Fixed a few small memory leaks
Fixed EXPLAIN handling of options and changed full_path option name
Fixed output of group acl privileges
Memory leaks (hunt and destroy with tools like Purify(Kurt)
Minor improvements to rules system
NOTIFY fixes
New asserts for run-checking
Overhauled parser/analyze code to properly report errors and
 increase speed
Pg_dump -d now handles NULL's properly(Bruce)
Prevent SELECT NULL from crashing server (Bruce)
Properly report errors when INSERT ... SELECT columns did not match
Properly report errors when insert column names were not correct
psql \g filename now works(Bruce)
psql fixed problem with multiple statements on one line with
 multiple outputs
Removed duplicate system OIDs
SELECT * INTO TABLE . GROUP/ORDER BY gives unlink error if table
 exists(Bruce)
Several fixes for queries that crashed the backend
Starting quote in insert string errors(Bruce)
Submitting an empty query now returns empty status, not just " "
 query(Bruce)

Enhancements
------------
Add EXPLAIN manual page(Bruce)
Add UNIQUE index capability(Dan)
Add hostname/user level access control rather than just hostname
 and user
Add synonym of != for <>(Bruce)
Allow "select oid,* from table"
Allow BY,ORDER BY to specify columns by number, or by non-alias
 table.column(Bruce)
Allow COPY from the frontend(Bryan)
Allow GROUP BY to use alias column name(Bruce)
Allow actual compression, not just reuse on the same page(Vadim)
```

```
Allow installation-configuration option to auto-add all local
 users(Bryan)
Allow libpq to distinguish between text value '' and null(Bruce)
Allow non-postgres users with createdb privs to destroydb's
Allow restriction on who can create C functions(Bryan)
Allow restriction on who can do backend COPY(Bryan)
Can shrink tables, pg_time and pg_log(Vadim & Erich)
Change debug level 2 to print queries only, changed debug heading
 layout(Bruce)
Change default decimal constant representation from float4 to
 float8(Bruce)
European date format now set when postmaster is started
Execute lowercase function names if not found with exact case
Fixes for aggregate/GROUP processing, allow 'select
 sum(func(x),sum(x+y) from z'
Gist now included in the distribution(Marc)
Idend authentication of local users(Bryan)
Implement BETWEEN qualifier(Bruce)
Implement IN qualifier(Bruce)
libpq has PQgetisnull()(Bruce)
libpq++ improvements
New options to initdb(Bryan)
Pg_dump allow dump of OIDs(Bruce)
Pg_dump create indexes after tables are loaded for speed(Bruce)
Pg_dumpall dumps all databases, and the user table
Pginterface additions for NULL values(Bruce)
Prevent postmaster from being run as root
psql \h and \? is now readable(Bruce)
psql allow backslashed, semicolons anywhere on the line(Bruce)
psql changed command prompt for lines in query or in quotes(Bruce)
psql char(3) now displays as (bp)char in \d output(Bruce)
psql return code now more accurate(Bryan?)
psql updated help syntax(Bruce)
Re-visit and fix vacuum(Vadim)
Reduce size of regression diffs, remove timezone name
 difference(Bruce)
Remove compile-time parameters to enable binary
 distributions(Bryan)
Reverse meaning of HBA masks(Bryan)
Secure Authentication of local users(Bryan)
Speed up vacuum(Vadim)
Vacuum now had VERBOSE option(Bruce)

Source tree changes
-------------------
All functions now have prototypes that are compared against the
 calls
Allow asserts to be disabled easily from Makefile.global(Bruce)
Change oid constants used in code to #define names
Decoupled sparc and solaris defines(Kurt)
Gcc -Wall compiles cleanly with warnings only from unfixable
 constructs
Major include file reorganization/reduction(Marc)
Make now stops on compile failure(Bryan)
Makefile restructuring(Bryan, Marc)
Merge bsdi_2_1 to bsdi(Bruce)
Monitor program removed
Name change from Postgres95 to PostgreSQL
```

```
New config.h file(Marc, Bryan)
PG_VERSION now set to 6.0 and used by postmaster
Portability additions, including Ultrix, DG/UX, AIX, and Solaris
Reduced the number of #define's, centralized #define's
Remove duplicate OIDS in system tables(Dan)
Remove duplicate system catalog info or report mismatches(Dan)
Removed many os-specific #define's
Restructured object file generation/location(Bryan, Marc)
Restructured port-specific file locations(Bryan, Marc)
Unused/uninitialized variables corrected
```

A.55. Release 1.09

Release date

1996-11-04

Sorry, we didn't keep track of changes from 1.02 to 1.09. Some of the changes listed in 6.0 were actually included in the 1.02.1 to 1.09 releases.

A.56. Release 1.02

Release date

1996-08-01

A.56.1. Migration from version 1.02 to version 1.02.1

Here is a new migration file for 1.02.1. It includes the 'copy' change and a script to convert old ASCII files.

Note

The following notes are for the benefit of users who want to migrate databases from Postgres95 1.01 and 1.02 to Postgres95 1.02.1.

If you are starting afresh with Postgres95 1.02.1 and do not need to migrate old databases, you do not need to read any further.

In order to upgrade older Postgres95 version 1.01 or 1.02 databases to version 1.02.1, the following steps are required:

1. Start up a new 1.02.1 postmaster
2. Add the new built-in functions and operators of 1.02.1 to 1.01 or 1.02 databases. This is done by running the new 1.02.1 server against your own 1.01 or 1.02 database and applying the queries attached at the end of the file. This can be done easily through `psql`. If your 1.01 or 1.02 database is named `testdb` and you have cut the commands from the end of this file and saved them in `addfunc.sql`:

   ```
   % psql testdb -f addfunc.sql
   ```

   Those upgrading 1.02 databases will get a warning when executing the last two statements in the file because they are already present in 1.02. This is not a cause for concern.

A.56.2. Dump/Reload Procedure

If you are trying to reload a pg_dump or text-mode, `copy tablename to stdout` generated with a previous version, you will need to run the attached `sed` script on the ASCII file before loading it

into the database. The old format used '.' as end-of-data, while '\.' is now the end-of-data marker. Also, empty strings are now loaded in as '' rather than NULL. See the copy manual page for full details.

```
        sed 's/^\.$/\\./g' <in_file >out_file
```

If you are loading an older binary copy or non-stdout copy, there is no end-of-data character, and hence no conversion necessary.

```
-- following lines added by agc to reflect the case-insensitive
-- regexp searching for varchar (in 1.02), and bpchar (in 1.02.1)
create operator ~* (leftarg = bpchar, rightarg = text, procedure =
 texticregexeq);
create operator !~* (leftarg = bpchar, rightarg = text, procedure =
 texticregexne);
create operator ~* (leftarg = varchar, rightarg = text, procedure =
 texticregexeq);
create operator !~* (leftarg = varchar, rightarg = text, procedure
 = texticregexne);
```

A.56.3. Changes

```
Source code maintenance and development
 * worldwide team of volunteers
 * the source tree now in CVS at ftp.ki.net

Enhancements
 * psql (and underlying libpq library) now has many more options
 for
   formatting output, including HTML
 * pg_dump now output the schema and/or the data, with many fixes
 to
   enhance completeness.
 * psql used in place of monitor in administration shell scripts.
   monitor to be deprecated in next release.
 * date/time functions enhanced
 * NULL insert/update/comparison fixed/enhanced
 * TCL/TK lib and shell fixed to work with both tck7.4/tk4.0 and
 tcl7.5/tk4.1

Bug Fixes (almost too numerous to mention)
 * indexes
 * storage management
 * check for NULL pointer before dereferencing
 * Makefile fixes

New Ports
 * added SolarisX86 port
 * added BSD/OS 2.1 port
 * added DG/UX port
```

A.57. Release 1.01

Release date

1996-02-23

A.57.1. Migration from version 1.0 to version 1.01

The following notes are for the benefit of users who want to migrate databases from Postgres95 1.0 to Postgres95 1.01.

If you are starting afresh with Postgres95 1.01 and do not need to migrate old databases, you do not need to read any further.

In order to Postgres95 version 1.01 with databases created with Postgres95 version 1.0, the following steps are required:

1. Set the definition of `NAMEDATALEN` in `src/Makefile.global` to 16 and `OIDNAMELEN` to 20.

2. Decide whether you want to use Host based authentication.

   a. If you do, you must create a file name `pg_hba` in your top-level data directory (typically the value of your `$PGDATA`). `src/libpq/pg_hba` shows an example syntax.

   b. If you do not want host-based authentication, you can comment out the line:

   ```
   HBA = 1
   ```

   in `src/Makefile.global`

   Note that host-based authentication is turned on by default, and if you do not take steps A or B above, the out-of-the-box 1.01 will not allow you to connect to 1.0 databases.

3. Compile and install 1.01, but DO NOT do the `initdb` step.

4. Before doing anything else, terminate your 1.0 postmaster, and backup your existing `$PGDATA` directory.

5. Set your `PGDATA` environment variable to your 1.0 databases, but set up path up so that 1.01 binaries are being used.

6. Modify the file `$PGDATA/PG_VERSION` from 5.0 to 5.1

7. Start up a new 1.01 postmaster

8. Add the new built-in functions and operators of 1.01 to 1.0 databases. This is done by running the new 1.01 server against your own 1.0 database and applying the queries attached and saving in the file 1.0_to_1.01.sql. This can be done easily through `psql`. If your 1.0 database is name `testdb`:

   ```
   % psql testdb -f 1.0_to_1.01.sql
   ```

   and then execute the following commands (cut and paste from here):

   ```
   -- add builtin functions that are new to 1.01

   create function int4eqoid (int4, oid) returns bool as 'foo'
   language 'internal';
   create function oideqint4 (oid, int4) returns bool as 'foo'
   language 'internal';
   create function char2icregexeq (char2, text) returns bool as
    'foo'
   language 'internal';
   create function char2icregexne (char2, text) returns bool as
    'foo'
   language 'internal';
   ```

```
create function char4icregexeq (char4, text) returns bool as
 'foo'
language 'internal';
create function char4icregexne (char4, text) returns bool as
 'foo'
language 'internal';
create function char8icregexeq (char8, text) returns bool as
 'foo'
language 'internal';
create function char8icregexne (char8, text) returns bool as
 'foo'
language 'internal';
create function char16icregexeq (char16, text) returns bool as
 'foo'
language 'internal';
create function char16icregexne (char16, text) returns bool as
 'foo'
language 'internal';
create function texticregexeq (text, text) returns bool as
 'foo'
language 'internal';
create function texticregexne (text, text) returns bool as
 'foo'
language 'internal';

-- add builtin functions that are new to 1.01

create operator = (leftarg = int4, rightarg = oid, procedure =
 int4eqoid);
create operator = (leftarg = oid, rightarg = int4, procedure =
 oideqint4);
create operator ~* (leftarg = char2, rightarg = text, procedure
 = char2icregexeq);
create operator !~* (leftarg = char2, rightarg = text,
 procedure = char2icregexne);
create operator ~* (leftarg = char4, rightarg = text, procedure
 = char4icregexeq);
create operator !~* (leftarg = char4, rightarg = text,
 procedure = char4icregexne);
create operator ~* (leftarg = char8, rightarg = text, procedure
 = char8icregexeq);
create operator !~* (leftarg = char8, rightarg = text,
 procedure = char8icregexne);
create operator ~* (leftarg = char16, rightarg = text,
 procedure = char16icregexeq);
create operator !~* (leftarg = char16, rightarg = text,
 procedure = char16icregexne);
create operator ~* (leftarg = text, rightarg = text, procedure
 = texticregexeq);
create operator !~* (leftarg = text, rightarg = text, procedure
 = texticregexne);
```

A.57.2. Changes

```
Incompatibilities:
 * 1.01 is backwards compatible with 1.0 database provided the user
   follow the steps outlined in the MIGRATION_from_1.0_to_1.01
 file.
```

```
    If those steps are not taken, 1.01 is not compatible with 1.0
  database.

Enhancements:
  * added PQdisplayTuples() to libpq and changed monitor and psql to
  use it
  * added NeXT port (requires SysVIPC implementation)
  * added CAST .. AS ... syntax
  * added ASC and DESC key words
  * added 'internal' as a possible language for CREATE FUNCTION
    internal functions are C functions which have been statically
  linked
    into the postgres backend.
  * a new type "name" has been added for system identifiers (table
  names,
    attribute names, etc.)  This replaces the old char16 type.   The
    of name is set by the NAMEDATALEN #define in src/Makefile.global
  * a readable reference manual that describes the query language.
  * added host-based access control.  A configuration file ($PGDATA/
pg_hba)
    is used to hold the configuration data.  If host-based access
  control
    is not desired, comment out HBA=1 in src/Makefile.global.
  * changed regex handling to be uniform use of Henry Spencer's
  regex code
    regardless of platform.  The regex code is included in the
  distribution
  * added functions and operators for case-insensitive regular
  expressions.
    The operators are ~* and !~*.
  * pg_dump uses COPY instead of SELECT loop for better performance

Bug fixes:
  * fixed an optimizer bug that was causing core dumps when
    functions calls were used in comparisons in the WHERE clause
  * changed all uses of getuid to geteuid so that effective uids are
  used
  * psql now returns non-zero status on errors when using -c
  * applied public patches 1-14
```

A.58. Release 1.0

Release date

1995-09-05

A.58.1. Changes

```
Copyright change:
  * The copyright of Postgres 1.0 has been loosened to be freely
  modifiable
    and modifiable for any purpose.  Please read the COPYRIGHT file.
    Thanks to Professor Michael Stonebraker for making this
  possible.

Incompatibilities:
```

```
 *  date formats have to be MM-DD-YYYY (or DD-MM-YYYY if you're
 using
   EUROPEAN STYLE).  This follows SQL-92 specs.
 *  "delimiters" is now a key word

Enhancements:
 *  sql LIKE syntax has been added
 *  copy command now takes an optional USING DELIMITER
 specification.
   delimiters can be any single-character string.
 *  IRIX 5.3 port has been added.
   Thanks to Paul Walmsley and others.
 *  updated pg_dump to work with new libpq
 *  \d has been added psql
   Thanks to Keith Parks
 *  regexp performance for architectures that use POSIX regex has
 been
   improved due to caching of precompiled patterns.
   Thanks to Alistair Crooks
 *  a new version of libpq++
   Thanks to William Wanders

Bug fixes:
 *  arbitrary userids can be specified in the createuser script
 *  \c to connect to other databases in psql now works.
 *  bad pg_proc entry for float4inc() is fixed
 *  users with usecreatedb field set can now create databases
 without
   having to be usesuper
 *  remove access control entries when the entry no longer has any
   privileges
 *  fixed non-portable datetimes implementation
 *  added kerberos flags to the src/backend/Makefile
 *  libpq now works with kerberos
 *  typographic errors in the user manual have been corrected.
 *  btrees with multiple index never worked, now we tell you they
 don't
   work when you try to use them
```

A.59. Postgres95 Release 0.03

Release date

1995-07-21

A.59.1. Changes

```
Incompatible changes:
 * BETA-0.3 IS INCOMPATIBLE WITH DATABASES CREATED WITH PREVIOUS
 VERSIONS
   (due to system catalog changes and indexing structure changes).
 * double-quote (") is deprecated as a quoting character for string
 literals;
   you need to convert them to single quotes (').
 * name of aggregates (eg. int4sum) are renamed in accordance with
 the
   SQL standard (eg. sum).
```

```
 * CHANGE ACL syntax is replaced by GRANT/REVOKE syntax.
 * float literals (eg. 3.14) are now of type float4 (instead of
 float8 in
   previous releases); you might have to do typecasting if you
 depend on it
   being of type float8.  If you neglect to do the typecasting and
 you assign
   a float literal to a field of type float8, you might get
 incorrect values
   stored!
 * LIBPQ has been totally revamped so that frontend applications
   can connect to multiple backends
 * the usesysid field in pg_user has been changed from int2 to int4
 to
   allow wider range of Unix user ids.
 * the netbsd/freebsd/bsd o/s ports have been consolidated into a
   single BSD44_derived port.  (thanks to Alistair Crooks)

SQL standard-compliance (the following details changes that makes
 postgres95
more compliant to the SQL-92 standard):
 * the following SQL types are now built-in: smallint, int(eger),
 float, real,
   char(N), varchar(N), date and time.

   The following are aliases to existing postgres types:
               smallint -> int2
               integer, int -> int4
               float, real  -> float4
   char(N) and varchar(N) are implemented as truncated text types.
 In
   addition, char(N) does blank-padding.
 * single-quote (') is used for quoting string literals; '' (in
 addition to
   \') is supported as means of inserting a single quote in a
 string
 * SQL standard aggregate names (MAX, MIN, AVG, SUM, COUNT) are
 used
   (Also, aggregates can now be overloaded, i.e. you can define
 your
   own MAX aggregate to take in a user-defined type.)
 * CHANGE ACL removed. GRANT/REVOKE syntax added.
   - Privileges can be given to a group using the "GROUP" key word.
        For example:
                GRANT SELECT ON foobar TO GROUP my_group;
        The key word 'PUBLIC' is also supported to mean all users.

        Privileges can only be granted or revoked to one user or
 group
        at a time.

        "WITH GRANT OPTION" is not supported.  Only class owners
 can change
        access control
   - The default access control is to grant users readonly access.
     You must explicitly grant insert/update access to users.  To
 change
     this, modify the line in
```

```
                src/backend/utils/acl.h
     that defines ACL_WORLD_DEFAULT

Bug fixes:
 * the bug where aggregates of empty tables were not run has been
 fixed. Now,
   aggregates run on empty tables will return the initial
 conditions of the
   aggregates. Thus, COUNT of an empty  table will now properly
 return 0.
   MAX/MIN of an empty table will return a row of value NULL.
 * allow the use of \; inside the monitor
 * the LISTEN/NOTIFY asynchronous notification mechanism now work
 * NOTIFY in rule action bodies now work
 * hash indexes work, and access methods in general should perform
 better.
   creation of large btree indexes should be much faster.  (thanks
 to Paul
   Aoki)

Other changes and enhancements:
 * addition of an EXPLAIN statement used for explaining the query
 execution
   plan (eg. "EXPLAIN SELECT * FROM EMP" prints out the execution
 plan for
   the query).
 * WARN and NOTICE messages no longer have timestamps on them. To
 turn on
   timestamps of error messages, uncomment the line in
   src/backend/utils/elog.h:
        /* define ELOG_TIMESTAMPS */
 * On an access control violation, the message
        "Either no such class or insufficient privilege"
   will be given.  This is the same message that is returned when
   a class is not found.  This dissuades non-privileged users from
   guessing the existence of privileged classes.
 * some additional system catalog changes have been made that are
 not
   visible to the user.

libpgtcl changes:
 * The -oid option has been added to the "pg_result" tcl command.
   pg_result -oid returns oid of the last row inserted.   If the
   last command was not an INSERT, then pg_result -oid returns "".
 * the large object interface is available as pg_lo* tcl commands:
   pg_lo_open, pg_lo_close, pg_lo_creat, etc.

Portability enhancements and New Ports:
 * flex/lex problems have been cleared up.  Now, you should be able
 to use
   flex instead of lex on any platforms.  We no longer make
 assumptions of
   what lexer you use based on the platform you use.
 * The Linux-ELF port is now supported.  Various configuration have
 been
   tested:  The following configuration is known to work:
        kernel 1.2.10, gcc 2.6.3, libc 4.7.2, flex 2.5.2, bison
 1.24
```

```
   with everything in ELF format,

New utilities:
 * ipcclean added to the distribution
   ipcclean usually does not need to be run, but if your backend
 crashes
   and leaves shared memory segments hanging around, ipcclean will
   clean them up for you.

New documentation:
 * the user manual has been revised and libpq documentation added.
```

A.60. Postgres95 Release 0.02

Release date

1995-05-25

A.60.1. Changes

```
Incompatible changes:
 * The SQL statement for creating a database is 'CREATE DATABASE'
 instead
   of 'CREATEDB'. Similarly, dropping a database is 'DROP DATABASE'
 instead
   of 'DESTROYDB'. However, the names of the executables 'createdb'
 and
   'destroydb' remain the same.

New tools:
 * pgperl - a Perl (4.036) interface to Postgres95
 * pg_dump - a utility for dumping out a postgres database into a
        script file containing query commands. The script files are
 in a ASCII
        format and can be used to reconstruct the database, even on
 other
        machines and other architectures. (Also good for converting
        a Postgres 4.2 database to Postgres95 database.)

The following ports have been incorporated into postgres95-
beta-0.02:
 * the NetBSD port by Alistair Crooks
 * the AIX port by Mike Tung
 * the Windows NT port by Jon Forrest (more stuff but not done yet)
 * the Linux ELF port by Brian Gallew

The following bugs have been fixed in postgres95-beta-0.02:
 * new lines not escaped in COPY OUT and problem with COPY OUT when
 first
   attribute is a '.'
 * cannot type return to use the default user id in createuser
 * SELECT DISTINCT on big tables crashes
 * Linux installation problems
 * monitor doesn't allow use of 'localhost' as PGHOST
 * psql core dumps when doing \c or \l
 * the "pgtclsh" target missing from src/bin/pgtclsh/Makefile
 * libpgtcl has a hard-wired default port number
```

```
* SELECT DISTINCT INTO TABLE hangs
* CREATE TYPE doesn't accept 'variable' as the internallength
* wrong result using more than 1 aggregate in a SELECT
```

A.61. Postgres95 Release 0.01

Release date

1995-05-01

Initial release.

PostgreSQL 7.3.21
Programmer's Guide

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 Programmer's Guide

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

Preface cxcix
1. What's In This Book cxcix
I. Client Interfaces 1
1. libpq - C Library 4
1.1. Introduction 4
1.2. Database Connection Functions 4
1.3. Command Execution Functions 10
1.4. Asynchronous Query Processing 16
1.5. The Fast-Path Interface 18
1.6. Asynchronous Notification 19
1.7. Functions Associated with the COPY Command 20
1.8. libpq Tracing Functions 22
1.9. libpq Control Functions 22
1.10. Environment Variables 22
1.11. Files 23
1.12. Threading Behavior 23
1.13. Building Libpq Programs 24
1.14. Example Programs 25
2. Large Objects 34
2.1. Introduction 34
2.2. Implementation Features 34
2.3. Interfaces 34
2.4. Server-side Built-in Functions 36
2.5. Accessing Large Objects from Libpq 36
3. pgtcl - Tcl Binding Library 42
3.1. Introduction 42
3.2. Loading pgtcl into your application 43
3.3. pgtcl Command Reference Information 43
4. ECPG - Embedded SQL in C 65
4.1. The Concept 65
4.2. Connecting to the Database Server 65
4.3. Closing a Connection 66
4.4. Running SQL Commands 66
4.5. Passing Data 67
4.6. Error Handling 68
4.7. Including Files 71
4.8. Processing Embedded SQL Programs 71
4.9. Library Functions 72
4.10. Porting From Other RDBMS Packages 72
4.11. For the Developer 72
5. JDBC Interface 75
5.1. Setting up the JDBC Driver 75
5.2. Using the Driver 76
5.3. Issuing a Query and Processing the Result 77
5.4. Performing Updates 78
5.5. Creating and Modifying Database Objects 79
5.6. Storing Binary Data 79
5.7. PostgreSQL Extensions to the JDBC API 82
5.8. Using the driver in a multithreaded or a servlet environment 101
5.9. Connection Pools And DataSources 102
5.10. Further Reading 105
6. PyGreSQL - Python Interface 107
6.1. The `pg` Module 107
6.2. `pg` Module Functions 108
6.3. Connection Object: `pgobject` 120

6.4. Database Wrapper Class: DB 133
6.5. Query Result Object: pgqueryobject 142
6.6. Large Object: pglarge 148
II. Server Programming 159
7. Architecture 162
7.1. PostgreSQL Architectural Concepts 162
8. Extending SQL: An Overview 165
8.1. How Extensibility Works 165
8.2. The PostgreSQL Type System 165
8.3. About the PostgreSQL System Catalogs 165
9. Extending SQL: Functions 168
9.1. Introduction 168
9.2. Query Language (SQL) Functions 168
9.3. Procedural Language Functions 173
9.4. Internal Functions 173
9.5. C Language Functions 173
9.6. Function Overloading 191
9.7. Table Functions 192
9.8. Procedural Language Handlers 193
10. Extending SQL: Types 196
11. Extending SQL: Operators 198
11.1. Introduction 198
11.2. Example 198
11.3. Operator Optimization Information 198
12. Extending SQL: Aggregates 203
13. The Rule System 205
13.1. Introduction 205
13.2. What is a Query Tree? 205
13.3. Views and the Rule System 207
13.4. Rules on INSERT, UPDATE and DELETE 213
13.5. Rules and Permissions 223
13.6. Rules and Command Status 224
13.7. Rules versus Triggers 224
14. Interfacing Extensions To Indexes 227
14.1. Introduction 227
14.2. Access Methods and Operator Classes 227
14.3. Access Method Strategies 227
14.4. Access Method Support Routines 228
14.5. Creating the Operators and Support Routines 229
14.6. Creating the Operator Class 231
14.7. Special Features of Operator Classes 231
15. Index Cost Estimation Functions 233
16. Triggers 236
16.1. Trigger Definition 236
16.2. Interaction with the Trigger Manager 237
16.3. Visibility of Data Changes 239
16.4. Examples 240
17. Server Programming Interface 243
17.1. Interface Functions 243
17.2. Interface Support Functions 256
17.3. Memory Management 263
17.4. Visibility of Data Changes 274
17.5. Examples 274
III. Procedural Languages 278
18. Procedural Languages 281
18.1. Introduction 281
18.2. Installing Procedural Languages 281
19. PL/pgSQL - SQL Procedural Language 283

19.1. Overview 283
19.2. Structure of PL/pgSQL 285
19.3. Declarations 286
19.4. Expressions 289
19.5. Basic Statements 290
19.6. Control Structures 294
19.7. Cursors 299
19.8. Errors and Messages 301
19.9. Trigger Procedures 302
19.10. Examples 304
19.11. Porting from Oracle PL/SQL 304
20. PL/Tcl - Tcl Procedural Language 316
20.1. Overview 316
20.2. Description 316
21. PL/Perl - Perl Procedural Language 323
21.1. PL/Perl Functions and Arguments 323
21.2. Data Values in PL/Perl 324
21.3. Database Access from PL/Perl 324
21.4. Trusted and Untrusted PL/Perl 324
21.5. Missing Features 325
22. PL/Python - Python Procedural Language 326
22.1. PL/Python Functions 326
22.2. Trigger Functions 326
22.3. Database Access 327
22.4. Restricted Environment 328

List of Figures

7.1. How a connection is established 163
8.1. The major PostgreSQL system catalogs 166

List of Tables

3.1. `pgtcl` Commands 42
5.1. ConnectionPoolDataSource Implementations 102
5.2. ConnectionPoolDataSource Configuration Properties 102
5.3. DataSource Implementations 103
5.4. DataSource Configuration Properties 104
5.5. Additional Pooling DataSource Configuration Properties 104
8.1. Catalogs 166
9.1. Equivalent C Types 175
14.1. B-tree 228
14.2. Hash 228
14.3. R-tree 228
14.4. B-tree 229
14.5. Hash 229
14.6. R-tree 229
14.7. GiST 229
19.1. Single Quotes Escaping Chart 305

List of Examples

1.1. libpq Example Program 1 25
1.2. libpq Example Program 2 27
1.3. libpq Example Program 3 30
2.1. Large Objects with Libpq Example Program 37
3.1. pgtcl Example Program 42
5.1. Processing a Simple Query in JDBC 77
5.2. Simple Delete Example 79
5.3. Drop Table Example 79
5.4. Binary Data Examples 80
5.5. `ConnectionPoolDataSource` Configuration Example 103
5.6. `DataSource` Code Example 104
5.7. `DataSource` JNDI Code Example 105
18.1. Manual Installation of PL/pgSQL 282
19.1. A PL/pgSQL Trigger Procedure Example 303
19.2. A Simple PL/pgSQL Function to Increment an Integer 304
19.3. A Simple PL/pgSQL Function to Concatenate Text 304
19.4. A PL/pgSQL Function on Composite Type 304
19.5. A Simple Function 306
19.6. A Function that Creates Another Function 307
19.7. A Procedure with a lot of String Manipulation and OUT Parameters 308

Preface

1. What's In This Book

This book is for PostgreSQL application programmers. It is divided into three parts.

The first part of this book describes the client programming interfaces distributed with PostgreSQL. Each of these chapters can be read independently. Note that there are many other programming interfaces for client programs that are distributed separately and contain their own documentation. Readers of the first part should be familiar with using SQL commands to manipulate and query the database (see the PostgreSQL 7.3.21 User's Guide) and of course with the programming language that the interface uses.

The second part of this book is about extending the server functionality with user-defined functions, data types, triggers, etc. These are advanced topics which should probably be approached only after all the other user documentation about PostgreSQL has been understood.

The third part of this book described the available server-side programming languages. This information is related to the second part and is only useful to readers that have read at least the first few chapters thereof.

This book covers PostgreSQL 7.3.21 only. For information on other versions, please read the documentation that accompanies that release.

Part I. Client Interfaces

This part of the manual is the description of the client-side programming interfaces and support libraries for various languages.

Table of Contents

1. libpq - C Library 4
    1.1. Introduction 4
    1.2. Database Connection Functions 4
    1.3. Command Execution Functions 10
        1.3.1. Main Routines 10
        1.3.2. Escaping Strings for Inclusion in SQL Commands 11
        1.3.3. Escaping Binary Strings for Inclusion in SQL Commands 12
        1.3.4. Retrieving SELECT Result Information 13
        1.3.5. Retrieving SELECT Result Values 14
        1.3.6. Retrieving Non-SELECT Result Information 15
    1.4. Asynchronous Query Processing 16
    1.5. The Fast-Path Interface 18
    1.6. Asynchronous Notification 19
    1.7. Functions Associated with the COPY Command 20
    1.8. libpq Tracing Functions 22
    1.9. libpq Control Functions 22
    1.10. Environment Variables 22
    1.11. Files 23
    1.12. Threading Behavior 23
    1.13. Building Libpq Programs 24
    1.14. Example Programs 25
2. Large Objects 34
    2.1. Introduction 34
    2.2. Implementation Features 34
    2.3. Interfaces 34
        2.3.1. Creating a Large Object 35
        2.3.2. Importing a Large Object 35
        2.3.3. Exporting a Large Object 35
        2.3.4. Opening an Existing Large Object 35
        2.3.5. Writing Data to a Large Object 35
        2.3.6. Reading Data from a Large Object 35
        2.3.7. Seeking on a Large Object 36
        2.3.8. Closing a Large Object Descriptor 36
        2.3.9. Removing a Large Object 36
    2.4. Server-side Built-in Functions 36
    2.5. Accessing Large Objects from Libpq 36
3. pgtcl - Tcl Binding Library 42
    3.1. Introduction 42
    3.2. Loading pgtcl into your application 43
    3.3. pgtcl Command Reference Information 43
4. ECPG - Embedded SQL in C 65
    4.1. The Concept 65
    4.2. Connecting to the Database Server 65
    4.3. Closing a Connection 66
    4.4. Running SQL Commands 66
    4.5. Passing Data 67
    4.6. Error Handling 68
    4.7. Including Files 71
    4.8. Processing Embedded SQL Programs 71
    4.9. Library Functions 72
    4.10. Porting From Other RDBMS Packages 72
    4.11. For the Developer 72
        4.11.1. The Preprocessor 72
        4.11.2. The Library 74
5. JDBC Interface 75

5.1. Setting up the JDBC Driver 75
5.1.1. Getting the Driver 75
5.1.2. Setting up the Class Path 75
5.1.3. Preparing the Database for JDBC 75
5.2. Using the Driver 76
5.2.1. Importing JDBC 76
5.2.2. Loading the Driver 76
5.2.3. Connecting to the Database 76
5.2.4. Closing the Connection 77
5.3. Issuing a Query and Processing the Result 77
5.3.1. Using the `Statement` or `PreparedStatement` Interface 78
5.3.2. Using the `ResultSet` Interface 78
5.4. Performing Updates 78
5.5. Creating and Modifying Database Objects 79
5.6. Storing Binary Data 79
5.7. PostgreSQL Extensions to the JDBC API 82
5.7.1. Accessing the Extensions 82
5.7.2. Geometric Data Types 86
5.7.3. Large Objects 98
5.8. Using the driver in a multithreaded or a servlet environment 101
5.9. Connection Pools And DataSources 102
5.9.1. JDBC, JDK Version Support 102
5.9.2. JDBC Connection Pooling API 102
5.9.3. Application Servers: ConnectionPoolDataSource 102
5.9.4. Applications: DataSource 103
5.9.5. DataSources and JNDI 105
5.9.6. Specific Application Server Configurations 105
5.10. Further Reading 105
6. PyGreSQL - Python Interface 107
6.1. The `pg` Module 107
6.1.1. Constants 107
6.2. `pg` Module Functions 108
6.3. Connection Object: `pgobject` 120
6.4. Database Wrapper Class: `DB` 133
6.5. Query Result Object: `pgqueryobject` 142
6.6. Large Object: `pglarge` 148

Chapter 1. libpq - C Library

1.1. Introduction

libpq is the C application programmer's interface to PostgreSQL. libpq is a set of library routines that allow client programs to pass queries to the PostgreSQL backend server and to receive the results of these queries. libpq is also the underlying engine for several other PostgreSQL application interfaces, including libpq++ (C++), `libpgtcl` (Tcl), Perl, and `ecpg`. So some aspects of libpq's behavior will be important to you if you use one of those packages.

Three short programs are included at the end of this section to show how to write programs that use `libpq`. There are several complete examples of `libpq` applications in the following directories:

```
src/test/examples
src/bin/psql
```

Frontend programs that use `libpq` must include the header file `libpq-fe.h` and must link with the `libpq` library.

1.2. Database Connection Functions

The following routines deal with making a connection to a PostgreSQL backend server. The application program can have several backend connections open at one time. (One reason to do that is to access more than one database.) Each connection is represented by a `PGconn` object which is obtained from `PQconnectdb` or `PQsetdbLogin`. Note that these functions will always return a non-null object pointer, unless perhaps there is too little memory even to allocate the `PGconn` object. The `PQstatus` function should be called to check whether a connection was successfully made before queries are sent via the connection object.

- `PQconnectdb` Makes a new connection to the database server.

  ```
  PGconn *PQconnectdb(const char *conninfo)
  ```

  This routine opens a new database connection using the parameters taken from the string `conninfo`. Unlike `PQsetdbLogin` below, the parameter set can be extended without changing the function signature, so use either of this routine or the nonblocking analogues `PQconnectStart` and `PQconnectPoll` is preferred for application programming. The passed string can be empty to use all default parameters, or it can contain one or more parameter settings separated by whitespace.

  Each parameter setting is in the form `keyword = value`. (To write an empty value or a value containing spaces, surround it with single quotes, e.g., `keyword = 'a value'`. Single quotes and backslashes within the value must be escaped with a backslash, e.g., `\'` or `\\`.) Spaces around the equal sign are optional. The currently recognized parameter keywords are:

  `host`

  Name of host to connect to. If this begins with a slash, it specifies Unix-domain communication rather than TCP/IP communication; the value is the name of the directory in which the socket file is stored. The default is to connect to a Unix-domain socket in `/tmp`.

  `hostaddr`

  IP address of host to connect to. This should be in standard numbers-and-dots form, as used by the BSD functions `inet_aton` et al. If a nonzero-length string is specified, TCP/IP communication is used.

Using `hostaddr` instead of host allows the application to avoid a host name look-up, which may be important in applications with time constraints. However, Kerberos authentication requires the host name. The following therefore applies. If host is specified without `hostaddr`, a host name lookup is forced. If `hostaddr` is specified without host, the value for `hostaddr` gives the remote address; if Kerberos is used, this causes a reverse name query. If both host and `hostaddr` are specified, the value for `hostaddr` gives the remote address; the value for host is ignored, unless Kerberos is used, in which case that value is used for Kerberos authentication. Note that authentication is likely to fail if libpq is passed a host name that is not the name of the machine at `hostaddr`.

Without either a host name or host address, libpq will connect using a local Unix domain socket.

`port`

Port number to connect to at the server host, or socket file name extension for Unix-domain connections.

`dbname`

The database name.

`user`

User name to connect as.

`password`

Password to be used if the server demands password authentication.

`connect_timeout`

Time space in seconds given to connect routine. Zero or not set means infinite.

`options`

Trace/debug options to be sent to the server.

`tty`

A file or tty for optional debug output from the backend.

`requiressl`

Set to 1 to require SSL connection to the server. Libpq will then refuse to connect if the server does not accept an SSL connection. Set to 0 (default) to negotiate with server. This option is only available if PostgreSQL is compiled with SSL support.

If any parameter is unspecified, then the corresponding environment variable (see Section 1.10, “Environment Variables”) is checked. If the environment variable is not set either, then hardwired defaults are used. The return value is a pointer to an abstract `struct` representing the connection to the backend.

- `PQsetdbLogin` Makes a new connection to the database server.

```
PGconn *PQsetdbLogin(const char *pghost,
                     const char *pgport,
                     const char *pgoptions,
                     const char *pgtty,
                     const char *dbName,
                     const char *login,
                     const char *pwd)
```

This is the predecessor of PQconnectdb with a fixed number of parameters but the same functionality.

- PQsetdb Makes a new connection to the database server.

```
PGconn *PQsetdb(char *pghost,
                char *pgport,
                char *pgoptions,
                char *pgtty,
                char *dbName)
```

This is a macro that calls PQsetdbLogin with null pointers for the *login* and *pwd* parameters. It is provided primarily for backward compatibility with old programs.

- PQconnectStart, PQconnectPoll Make a connection to the database server in a nonblocking manner.

```
PGconn *PQconnectStart(const char *conninfo)

PostgresPollingStatusType PQconnectPoll(PGconn *conn)
```

These two routines are used to open a connection to a database server such that your application's thread of execution is not blocked on remote I/O whilst doing so.

The database connection is made using the parameters taken from the string conninfo, passed to PQconnectStart. This string is in the same format as described above for PQconnectdb.

Neither PQconnectStart nor PQconnectPoll will block, as long as a number of restrictions are met:

- The hostaddr and host parameters are used appropriately to ensure that name and reverse name queries are not made. See the documentation of these parameters under PQconnectdb above for details.
- If you call PQtrace, ensure that the stream object into which you trace will not block.
- You ensure for yourself that the socket is in the appropriate state before calling PQconnectPoll, as described below.

To begin, call conn=PQconnectStart("*connection_info_string*"). If conn is NULL, then libpq has been unable to allocate a new PGconn structure. Otherwise, a valid PGconn pointer is returned (though not yet representing a valid connection to the database). On return from PQconnectStart, call status=PQstatus(conn). If status equals CONNECTION_BAD, PQconnectStart has failed.

If PQconnectStart succeeds, the next stage is to poll libpq so that it may proceed with the connection sequence. Loop thus: Consider a connection “inactive” by default. If PQconnectPoll last returned PGRES_POLLING_ACTIVE, consider it “active” instead. If PQconnectPoll(conn) last returned PGRES_POLLING_READING, perform a select() for reading on PQsocket(conn). If it last returned PGRES_POLLING_WRITING, perform a select() for writing on PQsocket(conn). If you have yet to call PQconnectPoll, i.e. after the call to PQconnectStart, behave as if it last returned PGRES_POLLING_WRITING. If the select() shows that the socket is ready, consider it “active”. If it has been decided that this connection is “active”, call PQconnectPoll(conn) again. If this call returns PGRES_POLLING_FAILED, the connection procedure has failed. If this call returns PGRES_POLLING_OK, the connection has been successfully made.

Note that the use of select() to ensure that the socket is ready is merely a (likely) example; those with other facilities available, such as a poll() call, may of course use that instead.

At any time during connection, the status of the connection may be checked, by calling PQstatus. If this is CONNECTION_BAD, then the connection procedure has failed; if this is CONNECTION_OK, then the connection is ready. Either of these states should be equally detectable from the return value of PQconnectPoll, as above. Other states may be shown during (and only during) an asynchronous connection procedure. These indicate the current stage of the connection procedure, and may be useful to provide feedback to the user for example. These statuses may include:

CONNECTION_STARTED

Waiting for connection to be made.

CONNECTION_MADE

Connection OK; waiting to send.

CONNECTION_AWAITING_RESPONSE

Waiting for a response from the server.

CONNECTION_AUTH_OK

Received authentication; waiting for connection start-up to continue.

CONNECTION_SETENV

Negotiating environment (part of the connection start-up).
Note that, although these constants will remain (in order to maintain compatibility), an application should never rely upon these appearing in a particular order, or at all, or on the status always being one of these documented values. An application may do something like this:

```
switch(PQstatus(conn))
{
    case CONNECTION_STARTED:
        feedback = "Connecting...";
        break;

    case CONNECTION_MADE:
        feedback = "Connected to server...";
        break;
.
.
.
    default:
        feedback = "Connecting...";
}
```

Note that if PQconnectStart returns a non-NULL pointer, you must call PQfinish when you are finished with it, in order to dispose of the structure and any associated memory blocks. This must be done even if a call to PQconnectStart or PQconnectPoll failed.

PQconnectPoll will currently block if libpq is compiled with USE_SSL defined. This restriction may be removed in the future.

These functions leave the socket in a nonblocking state as if PQsetnonblocking had been called.

- PQconndefaults Returns the default connection options.

```
PQconninfoOption *PQconndefaults(void)
```

```
struct PQconninfoOption
{
    char   *keyword;   /* The keyword of the option */
    char   *envvar;    /* Fallback environment variable name */
    char   *compiled;  /* Fallback compiled in default value */
    char   *val;       /* Option's current value, or NULL */
    char   *label;     /* Label for field in connect dialog */
    char   *dispchar;  /* Character to display for this field
                          in a connect dialog. Values are:
                          ""        Display entered value as is
                          "*"       Password field - hide value
                          "D"       Debug option - don't show by
 default */
    int     dispsize;  /* Field size in characters for dialog */
}
```

Returns a connection options array. This may be used to determine all possible `PQconnectdb` options and their current default values. The return value points to an array of `PQconninfoOption` `struct`s, which ends with an entry having a NULL keyword pointer. Note that the default values (`val` fields) will depend on environment variables and other context. Callers must treat the connection options data as read-only.

After processing the options array, free it by passing it to `PQconninfoFree`. If this is not done, a small amount of memory is leaked for each call to `PQconndefaults`.

In PostgreSQL versions before 7.0, `PQconndefaults` returned a pointer to a static array, rather than a dynamically allocated array. That was not thread-safe, so the behavior has been changed.

- `PQfinish` Close the connection to the backend. Also frees memory used by the `PGconn` object.

  ```
  void PQfinish(PGconn *conn)
  ```

  Note that even if the backend connection attempt fails (as indicated by `PQstatus`), the application should call `PQfinish` to free the memory used by the `PGconn` object. The `PGconn` pointer should not be used after `PQfinish` has been called.

- `PQreset` Reset the communication port with the backend.

  ```
  void PQreset(PGconn *conn)
  ```

  This function will close the connection to the backend and attempt to reestablish a new connection to the same server, using all the same parameters previously used. This may be useful for error recovery if a working connection is lost.

- `PQresetStart PQresetPoll` Reset the communication port with the backend, in a nonblocking manner.

  ```
  int PQresetStart(PGconn *conn);

  PostgresPollingStatusType PQresetPoll(PGconn *conn);
  ```

  These functions will close the connection to the backend and attempt to reestablish a new connection to the same server, using all the same parameters previously used. This may be useful for error recovery if a working connection is lost. They differ from `PQreset` (above) in that they act in a nonblocking manner. These functions suffer from the same restrictions as `PQconnectStart` and `PQconnectPoll`.

Call PQresetStart. If it returns 0, the reset has failed. If it returns 1, poll the reset using PQresetPoll in exactly the same way as you would create the connection using PQconnectPoll.

libpq application programmers should be careful to maintain the PGconn abstraction. Use the accessor functions below to get at the contents of PGconn. Avoid directly referencing the fields of the PGconn structure because they are subject to change in the future. (Beginning in PostgreSQL release 6.4, the definition of struct PGconn is not even provided in libpq-fe.h. If you have old code that accesses PGconn fields directly, you can keep using it by including libpq-int.h too, but you are encouraged to fix the code soon.)

- PQdb Returns the database name of the connection.

  ```
  char *PQdb(const PGconn *conn)
  ```

  PQdb and the next several functions return the values established at connection. These values are fixed for the life of the PGconn object.

- PQuser Returns the user name of the connection.

  ```
  char *PQuser(const PGconn *conn)
  ```

- PQpass Returns the password of the connection.

  ```
  char *PQpass(const PGconn *conn)
  ```

- PQhost Returns the server host name of the connection.

  ```
  char *PQhost(const PGconn *conn)
  ```

- PQport Returns the port of the connection.

  ```
  char *PQport(const PGconn *conn)
  ```

- PQtty Returns the debug tty of the connection.

  ```
  char *PQtty(const PGconn *conn)
  ```

- PQoptions Returns the backend options used in the connection.

  ```
  char *PQoptions(const PGconn *conn)
  ```

- PQstatus Returns the status of the connection.

  ```
  ConnStatusType PQstatus(const PGconn *conn)
  ```

  The status can be one of a number of values. However, only two of these are seen outside of an asynchronous connection procedure - CONNECTION_OK or CONNECTION_BAD. A good connection to the database has the status CONNECTION_OK. A failed connection attempt is signaled by status CONNECTION_BAD. Ordinarily, an OK status will remain so until PQfinish, but a communications failure might result in the status changing to CONNECTION_BAD prematurely. In that case the application could try to recover by calling PQreset.

  See the entry for PQconnectStart and PQconnectPoll with regards to other status codes that might be seen.

- PQerrorMessage Returns the error message most recently generated by an operation on the connection.

  ```
  char *PQerrorMessage(const PGconn* conn);
  ```

Nearly all libpq functions will set PQerrorMessage if they fail. Note that by libpq convention, a non-empty PQerrorMessage will include a trailing newline.

- PQbackendPID Returns the process ID of the backend server handling this connection.

  ```
  int PQbackendPID(const PGconn *conn);
  ```

  The backend PID is useful for debugging purposes and for comparison to NOTIFY messages (which include the PID of the notifying backend). Note that the PID belongs to a process executing on the database server host, not the local host!

- PQgetssl Returns the SSL structure used in the connection, or NULL if SSL is not in use.

  ```
  SSL *PQgetssl(const PGconn *conn);
  ```

  This structure can be used to verify encryption levels, check server certificate and more. Refer to the SSL documentation for information about this structure.

  You must define USE_SSL in order to get the prototype for this function. Doing this will also automatically include ssl.h from OpenSSL.

1.3. Command Execution Functions

Once a connection to a database server has been successfully established, the functions described here are used to perform SQL queries and commands.

1.3.1. Main Routines

- PQexec Submit a command to the server and wait for the result.

  ```
  PGresult *PQexec(PGconn *conn,
                   const char *query);
  ```

  Returns a PGresult pointer or possibly a NULL pointer. A non-NULL pointer will generally be returned except in out-of-memory conditions or serious errors such as inability to send the command to the backend. If a NULL is returned, it should be treated like a PGRES_FATAL_ERROR result. Use PQerrorMessage to get more information about the error.

The PGresult structure encapsulates the result returned by the backend. libpq application programmers should be careful to maintain the PGresult abstraction. Use the accessor functions below to get at the contents of PGresult. Avoid directly referencing the fields of the PGresult structure because they are subject to change in the future. (Beginning in PostgreSQL 6.4, the definition of struct PGresult is not even provided in libpq-fe.h. If you have old code that accesses PGresult fields directly, you can keep using it by including libpq-int.h too, but you are encouraged to fix the code soon.)

- PQresultStatus Returns the result status of the command.

  ```
  ExecStatusType PQresultStatus(const PGresult *res)
  ```

  PQresultStatus can return one of the following values:

  - PGRES_EMPTY_QUERY -- The string sent to the backend was empty.
  - PGRES_COMMAND_OK -- Successful completion of a command returning no data
  - PGRES_TUPLES_OK -- The query successfully executed

- PGRES_COPY_OUT -- Copy Out (from server) data transfer started
- PGRES_COPY_IN -- Copy In (to server) data transfer started
- PGRES_BAD_RESPONSE -- The server's response was not understood
- PGRES_NONFATAL_ERROR
- PGRES_FATAL_ERROR

If the result status is PGRES_TUPLES_OK, then the routines described below can be used to retrieve the rows returned by the query. Note that a SELECT command that happens to retrieve zero rows still shows PGRES_TUPLES_OK. PGRES_COMMAND_OK is for commands that can never return rows (INSERT, UPDATE, etc.). A response of PGRES_EMPTY_QUERY often exposes a bug in the client software.

- PQresStatus Converts the enumerated type returned by PQresultStatus into a string constant describing the status code.

  ```
  char *PQresStatus(ExecStatusType status);
  ```

- PQresultErrorMessage returns the error message associated with the query, or an empty string if there was no error.

  ```
  char *PQresultErrorMessage(const PGresult *res);
  ```

  Immediately following a PQexec or PQgetResult call, PQerrorMessage (on the connection) will return the same string as PQresultErrorMessage (on the result). However, a PGresult will retain its error message until destroyed, whereas the connection's error message will change when subsequent operations are done. Use PQresultErrorMessage when you want to know the status associated with a particular PGresult; use PQerrorMessage when you want to know the status from the latest operation on the connection.

- PQclear Frees the storage associated with the PGresult. Every query result should be freed via PQclear when it is no longer needed.

  ```
  void PQclear(PQresult *res);
  ```

  You can keep a PGresult object around for as long as you need it; it does not go away when you issue a new query, nor even if you close the connection. To get rid of it, you must call PQclear. Failure to do this will result in memory leaks in the frontend application.

- PQmakeEmptyPGresult Constructs an empty PGresult object with the given status.

  ```
  PGresult* PQmakeEmptyPGresult(PGconn *conn, ExecStatusType
   status);
  ```

  This is libpq's internal routine to allocate and initialize an empty PGresult object. It is exported because some applications find it useful to generate result objects (particularly objects with error status) themselves. If *conn* is not NULL and status indicates an error, the connection's current error message is copied into the PGresult. Note that PQclear should eventually be called on the object, just as with a PGresult returned by libpq itself.

1.3.2. Escaping Strings for Inclusion in SQL Commands

PQescapeStringConn escapes a string for use within an SQL command. This is useful when inserting data values as literal constants in SQL commands. Certain characters (such as quotes and backslashes) must be escaped to prevent them from being interpreted specially by the SQL parser. PQescapeStringConn performs this operation.

Tip

It is especially important to do proper escaping when handling strings that were received from an untrustworthy source. Otherwise there is a security risk: you are vulnerable to "SQL injection" attacks wherein unwanted SQL commands are fed to your database.

```
size_t PQescapeStringConn (PGconn *conn,
                           char *to, const char *from, size_t
 length,
                           int *error);
```

`PQescapeStringConn` writes an escaped version of the *`from`* string to the *`to`* buffer, escaping special characters so that they cannot cause any harm, and adding a terminating zero byte. The single quotes that must surround PostgreSQL string literals are not included in the result string; they should be provided in the SQL command that the result is inserted into. The parameter *`from`* points to the first character of the string that is to be escaped, and the *`length`* parameter gives the number of bytes in this string. A terminating zero byte is not required, and should not be counted in *`length`*. (If a terminating zero byte is found before *`length`* bytes are processed, `PQescapeStringConn` stops at the zero; the behavior is thus rather like `strncpy`.) *`to`* shall point to a buffer that is able to hold at least one more byte than twice the value of *`length`*, otherwise the behavior is undefined. Behavior is likewise undefined if the *`to`* and *`from`* strings overlap.

If the *`error`* parameter is not NULL, then `*error` is set to zero on success, nonzero on error. Presently the only possible error conditions involve invalid multibyte encoding in the source string. The output string is still generated on error, but it can be expected that the server will reject it as malformed. On error, a suitable message is stored in the *`conn`* object, whether or not *`error`* is NULL.

`PQescapeStringConn` returns the number of bytes written to *`to`*, not including the terminating zero byte.

```
size_t PQescapeString (char *to, const char *from, size_t length);
```

`PQescapeString` is an older, deprecated version of `PQescapeStringConn`; the difference is that it does not take *`conn`* or *`error`* parameters. Because of this, it cannot adjust its behavior depending on the connection properties (such as character encoding) and therefore *it may give the wrong results*. Also, it has no way to report error conditions.

`PQescapeString` can be used safely in single-threaded client programs that work with only one PostgreSQL connection at a time (in this case it can find out what it needs to know "behind the scenes"). In other contexts it is a security hazard and should be avoided in favor of `PQescapeStringConn`.

1.3.3. Escaping Binary Strings for Inclusion in SQL Commands

`PQescapeByteaConn`

Escapes binary data for use within an SQL command with the type `bytea`.

```
unsigned char *PQescapeByteaConn(PGconn *conn,
                                 const unsigned char *from,
                                 size_t from_length,
                                 size_t *to_length);
```

Certain byte values *must* be escaped (but all byte values *can* be escaped) when used as part of a `bytea` literal in an SQL statement. In general, to escape a byte, it is converted into the three digit octal number equal to the octet value, and preceded by one or two backslashes. The single quote (`'`) and backslash (`\`) characters have special alternative escape sequences. `PQescapeByteaConn` performs this operation, escaping only the minimally required bytes.

The *from* parameter points to the first byte of the string that is to be escaped, and the *from_length* parameter gives the number of bytes in this binary string. (A terminating zero byte is neither necessary nor counted.) The *to_length* parameter points to a variable that will hold the resultant escaped string length. This result string length includes the terminating zero byte of the result.

PQescapeByteaConn returns an escaped version of the *from* parameter binary string in memory allocated with malloc(). This memory must be freed using free() when the result is no longer needed. The return string has all special characters replaced so that they can be properly processed by the PostgreSQL string literal parser, and the bytea input function. A terminating zero byte is also added. The single quotes that must surround PostgreSQL string literals are not part of the result string.

On error, a NULL pointer is returned, and a suitable error message is stored in the *conn* object. Currently, the only possible error is insufficient memory for the result string.

PQescapeBytea

PQescapeBytea is an older, deprecated version of PQescapeByteaConn.

```
unsigned char *PQescapeBytea(unsigned char *from,
                             size_t from_length,
                             size_t *to_length);
```

The only difference from PQescapeByteaConn is that PQescapeBytea does not take a PGconn parameter. Because of this, it cannot adjust its behavior depending on the connection properties and therefore *it may give the wrong results*. Also, it has no way to return an error message on failure.

PQescapeBytea can be used safely in single-threaded client programs that work with only one PostgreSQL connection at a time (in this case it can find out what it needs to know "behind the scenes"). In other contexts it is a security hazard and should be avoided in favor of PQescapeByteaConn.

PQunescapeBytea

Converts a string representation of binary data into binary data --- the reverse of PQescapeBytea. This is needed when retrieving bytea data in text format, but not when retrieving it in binary format.

```
unsigned char *PQunescapeBytea(unsigned char *from, size_t
 *to_length);
```

The *from* parameter points to a string such as might be returned by PQgetvalue when applied to a bytea column. PQunescapeBytea converts this string representation into its binary representation. It returns a pointer to a buffer allocated with malloc(), or null on error, and puts the size of the buffer in *to_length*. The result must be freed using free() when it is no longer needed.

This conversion is not exactly the inverse of PQescapeBytea, because the string is not expected to be "escaped" when received from PQgetvalue. In particular this means there is no need for string quoting considerations, and so no need for a PGconn parameter.

1.3.4. Retrieving SELECT Result Information

- PQntuples Returns the number of tuples (rows) in the query result.

  ```
  int PQntuples(const PGresult *res);
  ```

- PQnfields Returns the number of fields (columns) in each row of the query result.

```
int PQnfields(const PGresult *res);
```

- `PQfname` Returns the field (column) name associated with the given field index. Field indices start at 0.

  ```
  char *PQfname(const PGresult *res,
                int field_index);
  ```

- `PQfnumber` Returns the field (column) index associated with the given field name.

  ```
  int PQfnumber(const PGresult *res,
                const char *field_name);
  ```

  -1 is returned if the given name does not match any field.

- `PQftype` Returns the field type associated with the given field index. The integer returned is an internal coding of the type. Field indices start at 0.

  ```
  Oid PQftype(const PGresult *res,
              int field_index);
  ```

  You can query the system table `pg_type` to obtain the name and properties of the various data types. The OIDs of the built-in data types are defined in `src/include/catalog/pg_type.h` in the source tree.

- `PQfmod` Returns the type-specific modification data of the field associated with the given field index. Field indices start at 0.

  ```
  int PQfmod(const PGresult *res,
             int field_index);
  ```

- `PQfsize` Returns the size in bytes of the field associated with the given field index. Field indices start at 0.

  ```
  int PQfsize(const PGresult *res,
              int field_index);
  ```

  `PQfsize` returns the space allocated for this field in a database tuple, in other words the size of the server's binary representation of the data type. -1 is returned if the field is variable size.

- `PQbinaryTuples` Returns 1 if the `PGresult` contains binary tuple data, 0 if it contains ASCII data.

  ```
  int PQbinaryTuples(const PGresult *res);
  ```

  Currently, binary tuple data can only be returned by a query that extracts data from a binary cursor.

1.3.5. Retrieving SELECT Result Values

- `PQgetvalue` Returns a single field (column) value of one tuple (row) of a `PGresult`. Tuple and field indices start at 0.

  ```
  char* PQgetvalue(const PGresult *res,
                   int tup_num,
                   int field_num);
  ```

  For most queries, the value returned by `PQgetvalue` is a null-terminated character string representation of the attribute value. But if `PQbinaryTuples()` is 1, the value returned by `PQgetvalue` is the binary representation of the type in the internal format of the backend server (but not including the size word, if the field is variable-length). It is then the programmer's

responsibility to cast and convert the data to the correct C type. The pointer returned by `PQgetvalue` points to storage that is part of the `PGresult` structure. One should not modify it, and one must explicitly copy the value into other storage if it is to be used past the lifetime of the `PGresult` structure itself.

- `PQgetisnull` Tests a field for a NULL entry. Tuple and field indices start at 0.

```
int PQgetisnull(const PGresult *res,
                int tup_num,
                int field_num);
```

This function returns 1 if the field contains a NULL, 0 if it contains a non-null value. (Note that `PQgetvalue` will return an empty string, not a null pointer, for a NULL field.)

- `PQgetlength` Returns the length of a field (attribute) value in bytes. Tuple and field indices start at 0.

```
int PQgetlength(const PGresult *res,
                int tup_num,
                int field_num);
```

This is the actual data length for the particular data value, that is the size of the object pointed to by `PQgetvalue`. Note that for character-represented values, this size has little to do with the binary size reported by `PQfsize`.

- `PQprint` Prints out all the tuples and, optionally, the attribute names to the specified output stream.

```
void PQprint(FILE* fout,      /* output stream */
             const PGresult *res,
             const PQprintOpt *po);

struct {
    pqbool  header;      /* print output field headings and row
 count */
    pqbool  align;       /* fill align the fields */
    pqbool  standard;    /* old brain dead format */
    pqbool  html3;       /* output html tables */
    pqbool  expanded;    /* expand tables */
    pqbool  pager;       /* use pager for output if needed */
    char    *fieldSep;   /* field separator */
    char    *tableOpt;   /* insert to HTML table ... */
    char    *caption;    /* HTML caption */
    char    **fieldName; /* null terminated array of replacement
 field names */
} PQprintOpt;
```

This function was formerly used by psql to print query results, but this is no longer the case and this function is no longer actively supported.

1.3.6. Retrieving Non-SELECT Result Information

- `PQcmdStatus` Returns the command status string from the SQL command that generated the `PGresult`.

```
char * PQcmdStatus(PGresult *res);
```

- `PQcmdTuples` Returns the number of rows affected by the SQL command.

```
char * PQcmdTuples(PGresult *res);
```

If the SQL command that generated the PGresult was INSERT, UPDATE or DELETE, this returns a string containing the number of rows affected. If the command was anything else, it returns the empty string.

- PQoidValue Returns the object ID of the inserted row, if the SQL command was an INSERT that inserted exactly one row into a table that has OIDs. Otherwise, returns InvalidOid.

  ```
  Oid PQoidValue(const PGresult *res);
  ```

  The type Oid and the constant InvalidOid will be defined if you include the libpq header file. They will both be some integer type.

- PQoidStatus Returns a string with the object ID of the inserted row, if the SQL command was an INSERT. (The string will be 0 if the INSERT did not insert exactly one row, or if the target table does not have OIDs.) If the command was not an INSERT, returns an empty string.

  ```
  char * PQoidStatus(const PGresult *res);
  ```

  This function is deprecated in favor of PQoidValue and is not thread-safe.

1.4. Asynchronous Query Processing

The PQexec function is adequate for submitting commands in simple synchronous applications. It has a couple of major deficiencies however:

- PQexec waits for the command to be completed. The application may have other work to do (such as maintaining a user interface), in which case it won't want to block waiting for the response.
- Since control is buried inside PQexec, it is hard for the frontend to decide it would like to try to cancel the ongoing command. (It can be done from a signal handler, but not otherwise.)
- PQexec can return only one PGresult structure. If the submitted command string contains multiple SQL commands, all but the last PGresult are discarded by PQexec.

Applications that do not like these limitations can instead use the underlying functions that PQexec is built from: PQsendQuery and PQgetResult.

Older programs that used this functionality as well as PQputline and PQputnbytes could block waiting to send data to the backend. To address that issue, the function PQsetnonblocking was added.

Old applications can neglect to use PQsetnonblocking and get the older potentially blocking behavior. Newer programs can use PQsetnonblocking to achieve a completely nonblocking connection to the backend.

- PQsetnonblocking Sets the nonblocking status of the connection.

  ```
  int PQsetnonblocking(PGconn *conn, int arg)
  ```

  Sets the state of the connection to nonblocking if *arg* is 1, blocking if *arg* is 0. Returns 0 if OK, -1 if error.

  In the nonblocking state, calls to PQputline, PQputnbytes, PQsendQuery and PQendcopy will not block but instead return an error if they need to be called again.

  When a database connection has been set to nonblocking mode and PQexec is called, it will temporarily set the state of the connection to blocking until the PQexec completes.

  More of libpq is expected to be made safe for PQsetnonblocking functionality in the near future.

- `PQisnonblocking` Returns the blocking status of the database connection.

  ```
  int PQisnonblocking(const PGconn *conn)
  ```

  Returns 1 if the connection is set to nonblocking mode, 0 if blocking.

- `PQsendQuery` Submit a command to the server without waiting for the result(s). 1 is returned if the command was successfully dispatched, 0 if not (in which case, use `PQerrorMessage` to get more information about the failure).

  ```
  int PQsendQuery(PGconn *conn,
                  const char *query);
  ```

  After successfully calling `PQsendQuery`, call `PQgetResult` one or more times to obtain the results. `PQsendQuery` may not be called again (on the same connection) until `PQgetResult` has returned NULL, indicating that the command is done.

- `PQgetResult` Wait for the next result from a prior `PQsendQuery`, and return it. NULL is returned when the query is complete and there will be no more results.

  ```
  PGresult *PQgetResult(PGconn *conn);
  ```

  `PQgetResult` must be called repeatedly until it returns NULL, indicating that the command is done. (If called when no command is active, `PQgetResult` will just return NULL at once.) Each non-NULL result from `PQgetResult` should be processed using the same `PGresult` accessor functions previously described. Don't forget to free each result object with `PQclear` when done with it. Note that `PQgetResult` will block only if a query is active and the necessary response data has not yet been read by `PQconsumeInput`.

Using `PQsendQuery` and `PQgetResult` solves one of `PQexec`'s problems: If a command string contains multiple SQL commands, the results of those commands can be obtained individually. (This allows a simple form of overlapped processing, by the way: the frontend can be handling the results of one query while the backend is still working on later queries in the same command string.) However, calling `PQgetResult` will still cause the frontend to block until the backend completes the next SQL command. This can be avoided by proper use of three more functions:

- `PQconsumeInput` If input is available from the backend, consume it.

  ```
  int PQconsumeInput(PGconn *conn);
  ```

  `PQconsumeInput` normally returns 1 indicating “no error”, but returns 0 if there was some kind of trouble (in which case `PQerrorMessage` is set). Note that the result does not say whether any input data was actually collected. After calling `PQconsumeInput`, the application may check `PQisBusy` and/or `PQnotifies` to see if their state has changed.

  `PQconsumeInput` may be called even if the application is not prepared to deal with a result or notification just yet. The routine will read available data and save it in a buffer, thereby causing a `select()` read-ready indication to go away. The application can thus use `PQconsumeInput` to clear the `select()` condition immediately, and then examine the results at leisure.

- `PQisBusy` Returns 1 if a query is busy, that is, `PQgetResult` would block waiting for input. A 0 return indicates that `PQgetResult` can be called with assurance of not blocking.

  ```
  int PQisBusy(PGconn *conn);
  ```

  `PQisBusy` will not itself attempt to read data from the backend; therefore `PQconsumeInput` must be invoked first, or the busy state will never end.

- `PQflush` Attempt to flush any data queued to the backend, returns 0 if successful (or if the send queue is empty) or `EOF` if it failed for some reason.

  ```
  int PQflush(PGconn *conn);
  ```

PQflush needs to be called on a nonblocking connection before calling select() to determine if a response has arrived. If 0 is returned it ensures that there is no data queued to the backend that has not actually been sent. Only applications that have used PQsetnonblocking have a need for this.

- PQsocket Obtain the file descriptor number for the backend connection socket. A valid descriptor will be >= 0; a result of -1 indicates that no backend connection is currently open.

  ```
  int PQsocket(const PGconn *conn);
  ```

  PQsocket should be used to obtain the backend socket descriptor in preparation for executing select(). This allows an application using a blocking connection to wait for either backend responses or other conditions. If the result of select() indicates that data can be read from the backend socket, then PQconsumeInput should be called to read the data; after which, PQisBusy, PQgetResult, and/or PQnotifies can be used to process the response.

  Nonblocking connections (that have used PQsetnonblocking) should not use select() until PQflush has returned 0 indicating that there is no buffered data waiting to be sent to the backend.

A typical frontend using these functions will have a main loop that uses select to wait for all the conditions that it must respond to. One of the conditions will be input available from the backend, which in select's terms is readable data on the file descriptor identified by PQsocket. When the main loop detects input ready, it should call PQconsumeInput to read the input. It can then call PQisBusy, followed by PQgetResult if PQisBusy returns false (0). It can also call PQnotifies to detect NOTIFY messages (see Section 1.6, “Asynchronous Notification”).

A frontend that uses PQsendQuery/PQgetResult can also attempt to cancel a command that is still being processed by the backend.

- PQrequestCancel Request that PostgreSQL abandon processing of the current command.

  ```
  int PQrequestCancel(PGconn *conn);
  ```

  The return value is 1 if the cancel request was successfully dispatched, 0 if not. (If not, PQerrorMessage tells why not.) Successful dispatch is no guarantee that the request will have any effect, however. Regardless of the return value of PQrequestCancel, the application must continue with the normal result-reading sequence using PQgetResult. If the cancellation is effective, the current command will terminate early and return an error result. If the cancellation fails (say, because the backend was already done processing the command), then there will be no visible result at all.

Note that if the current command is part of a transaction, cancellation will abort the whole transaction.

PQrequestCancel can safely be invoked from a signal handler. So, it is also possible to use it in conjunction with plain PQexec, if the decision to cancel can be made in a signal handler. For example, psql invokes PQrequestCancel from a SIGINT signal handler, thus allowing interactive cancellation of queries that it issues through PQexec. Note that PQrequestCancel will have no effect if the connection is not currently open or the backend is not currently processing a command.

1.5. The Fast-Path Interface

PostgreSQL provides a fast-path interface to send function calls to the backend. This is a trapdoor into system internals and can be a potential security hole. Most users will not need this feature.

- PQfn Request execution of a backend function via the fast-path interface.

  ```
  PGresult* PQfn(PGconn* conn,
                 int fnid,
                 int *result_buf,
                 int *result_len,
  ```

```
                int result_is_int,
                const PQArgBlock *args,
                int nargs);
```

The *fnid* argument is the object identifier of the function to be executed. *result_buf* is the buffer in which to place the return value. The caller must have allocated sufficient space to store the return value (there is no check!). The actual result length will be returned in the integer pointed to by *result_len*. If a 4-byte integer result is expected, set *result_is_int* to 1; otherwise set it to 0. (Setting *result_is_int* to 1 tells libpq to byte-swap the value if necessary, so that it is delivered as a proper int value for the client machine. When *result_is_int* is 0, the byte string sent by the backend is returned unmodified.) *args* and *nargs* specify the arguments to be passed to the function.

```
typedef struct {
    int len;
    int isint;
    union {
        int *ptr;
        int integer;
    } u;
} PQArgBlock;
```

PQfn always returns a valid PGresult*. The result status should be checked before the result is used. The caller is responsible for freeing the PGresult with PQclear when it is no longer needed.

1.6. Asynchronous Notification

PostgreSQL supports asynchronous notification via the LISTEN and NOTIFY commands. A backend registers its interest in a particular notification condition with the LISTEN command (and can stop listening with the UNLISTEN command). All backends listening on a particular condition will be notified asynchronously when a NOTIFY of that condition name is executed by any backend. No additional information is passed from the notifier to the listener. Thus, typically, any actual data that needs to be communicated is transferred through a database relation. Commonly the condition name is the same as the associated relation, but it is not necessary for there to be any associated relation.

libpq applications submit LISTEN and UNLISTEN commands as ordinary SQL command. Subsequently, arrival of NOTIFY messages can be detected by calling PQnotifies.

- PQnotifies Returns the next notification from a list of unhandled notification messages received from the backend. Returns NULL if there are no pending notifications. Once a notification is returned from PQnotifies, it is considered handled and will be removed from the list of notifications.

  ```
  PGnotify* PQnotifies(PGconn *conn);

  typedef struct pgNotify {
      char *relname;              /* name of relation containing
   data */
      int  be_pid;                /* process id of backend */
  } PGnotify;
  ```

  After processing a PGnotify object returned by PQnotifies, be sure to free it with free() to avoid a memory leak.

  ### Note

  In PostgreSQL 6.4 and later, the be_pid is that of the notifying backend, whereas in earlier versions it was always the PID of your own backend.

The second sample program gives an example of the use of asynchronous notification.

`PQnotifies()` does not actually read backend data; it just returns messages previously absorbed by another libpq function. In prior releases of libpq, the only way to ensure timely receipt of NOTIFY messages was to constantly submit queries, even empty ones, and then check `PQnotifies()` after each `PQexec()`. While this still works, it is deprecated as a waste of processing power.

A better way to check for NOTIFY messages when you have no useful queries to make is to call `PQconsumeInput()`, then check `PQnotifies()`. You can use `select()` to wait for backend data to arrive, thereby using no CPU power unless there is something to do. (See `PQsocket()` to obtain the file descriptor number to use with `select()`.) Note that this will work OK whether you submit queries with `PQsendQuery`/`PQgetResult` or simply use `PQexec`. You should, however, remember to check `PQnotifies()` after each `PQgetResult` or `PQexec`, to see if any notifications came in during the processing of the query.

1.7. Functions Associated with the COPY Command

The COPY command in PostgreSQL has options to read from or write to the network connection used by `libpq`. Therefore, functions are necessary to access this network connection directly so applications may take advantage of this capability.

These functions should be executed only after obtaining a `PGRES_COPY_OUT` or `PGRES_COPY_IN` result object from `PQexec` or `PQgetResult`.

- `PQgetline` Reads a newline-terminated line of characters (transmitted by the backend server) into a buffer string of size length.

  ```
  int PQgetline(PGconn *conn,
                char *string,
                int length)
  ```

  Like `fgets`, this routine copies up to length-1 characters into string. It is like `gets`, however, in that it converts the terminating newline into a zero byte. `PQgetline` returns `EOF` at the end of input, 0 if the entire line has been read, and 1 if the buffer is full but the terminating newline has not yet been read.

  Notice that the application must check to see if a new line consists of the two characters `\.`, which indicates that the backend server has finished sending the results of the copy command. If the application might receive lines that are more than length-1 characters long, care is needed to be sure one recognizes the `\.` line correctly (and does not, for example, mistake the end of a long data line for a terminator line). The code in `src/bin/psql/copy.c` contains example routines that correctly handle the copy protocol.

- `PQgetlineAsync` Reads a newline-terminated line of characters (transmitted by the backend server) into a buffer without blocking.

  ```
  int PQgetlineAsync(PGconn *conn,
                     char *buffer,
                     int bufsize)
  ```

  This routine is similar to `PQgetline`, but it can be used by applications that must read COPY data asynchronously, that is without blocking. Having issued the COPY command and gotten a `PGRES_COPY_OUT` response, the application should call `PQconsumeInput` and `PQgetlineAsync` until the end-of-data signal is detected. Unlike `PQgetline`, this routine takes responsibility for detecting end-of-data. On each call, `PQgetlineAsync` will return data if a complete newline- terminated data line is available in libpq's input buffer, or if the incoming data

line is too long to fit in the buffer offered by the caller. Otherwise, no data is returned until the rest of the line arrives.

The routine returns -1 if the end-of-copy-data marker has been recognized, or 0 if no data is available, or a positive number giving the number of bytes of data returned. If -1 is returned, the caller must next call PQendcopy, and then return to normal processing. The data returned will not extend beyond a newline character. If possible a whole line will be returned at one time. But if the buffer offered by the caller is too small to hold a line sent by the backend, then a partial data line will be returned. This can be detected by testing whether the last returned byte is \n or not. The returned string is not null-terminated. (If you want to add a terminating null, be sure to pass a *bufsize* one smaller than the room actually available.)

- PQputline Sends a null-terminated string to the backend server. Returns 0 if OK, EOF if unable to send the string.

```
int PQputline(PGconn *conn,
              const char *string);
```

Note the application must explicitly send the two characters \. on a final line to indicate to the backend that it has finished sending its data.

- PQputnbytes Sends a non-null-terminated string to the backend server. Returns 0 if OK, EOF if unable to send the string.

```
int PQputnbytes(PGconn *conn,
                const char *buffer,
                int nbytes);
```

This is exactly like PQputline, except that the data buffer need not be null-terminated since the number of bytes to send is specified directly.

- PQendcopy Synchronizes with the backend. This function waits until the backend has finished the copy. It should either be issued when the last string has been sent to the backend using PQputline or when the last string has been received from the backend using PGgetline. It must be issued or the backend may get "out of sync" with the frontend. Upon return from this function, the backend is ready to receive the next SQL command. The return value is 0 on successful completion, nonzero otherwise.

```
int PQendcopy(PGconn *conn);
```

As an example:

```
PQexec(conn, "CREATE TABLE foo (a int4, b char(16), d double
 precision)");
PQexec(conn, "COPY foo FROM STDIN");
PQputline(conn, "3\thello world\t4.5\n");
PQputline(conn,"4\tgoodbye world\t7.11\n");
...
PQputline(conn,"\\.\n");
PQendcopy(conn);
```

When using PQgetResult, the application should respond to a PGRES_COPY_OUT result by executing PQgetline repeatedly, followed by PQendcopy after the terminator line is seen. It should then return to the PQgetResult loop until PQgetResult returns NULL. Similarly a PGRES_COPY_IN result is processed by a series of PQputline calls followed by PQendcopy, then return to the PQgetResult loop. This arrangement will ensure that a copy in or copy out command embedded in a series of SQL commands will be executed correctly.

Older applications are likely to submit a copy in or copy out via PQexec and assume that the transaction is done after PQendcopy. This will work correctly only if the copy in/out is the only SQL command in the command string.

1.8. libpq Tracing Functions

- PQtrace Enable tracing of the frontend/backend communication to a debugging file stream.

```
void PQtrace(PGconn *conn
             FILE *debug_port)
```

- PQuntrace Disable tracing started by PQtrace.

```
void PQuntrace(PGconn *conn)
```

1.9. libpq Control Functions

- PQsetNoticeProcessor Control reporting of notice and warning messages generated by libpq.

```
typedef void (*PQnoticeProcessor) (void *arg, const char
 *message);

PQnoticeProcessor
PQsetNoticeProcessor(PGconn *conn,
                     PQnoticeProcessor proc,
                     void *arg);
```

By default, libpq prints notice messages from the backend on stderr, as well as a few error messages that it generates by itself. This behavior can be overridden by supplying a callback function that does something else with the messages. The callback function is passed the text of the error message (which includes a trailing newline), plus a void pointer that is the same one passed to PQsetNoticeProcessor. (This pointer can be used to access application-specific state if needed.) The default notice processor is simply

```
static void
defaultNoticeProcessor(void * arg, const char * message)
{
    fprintf(stderr, "%s", message);
}
```

To use a special notice processor, call PQsetNoticeProcessor just after creation of a new PGconn object.

The return value is the pointer to the previous notice processor. If you supply a callback function pointer of NULL, no action is taken, but the current pointer is returned.

Once you have set a notice processor, you should expect that that function could be called as long as either the PGconn object or PGresult objects made from it exist. At creation of a PGresult, the PGconn's current notice processor pointer is copied into the PGresult for possible use by routines like PQgetvalue.

1.10. Environment Variables

The following environment variables can be used to select default connection parameter values, which will be used by PQconnectdb, PQsetdbLogin and PQsetdb if no value is directly specified by the calling code. These are useful to avoid hard-coding database connection information into simple client applications.

- PGHOST sets the default server name. If this begins with a slash, it specifies Unix-domain communication rather than TCP/IP communication; the value is the name of the directory in which the socket file is stored (default /tmp).

- PGPORT sets the default TCP port number or Unix-domain socket file extension for communicating with the PostgreSQL backend.
- PGDATABASE sets the default PostgreSQL database name.
- PGUSER sets the user name used to connect to the database and for authentication.
- PGPASSWORD sets the password used if the backend demands password authentication. This functionality is deprecated for security reasons; consider migrating to use the $HOME/.pgpass file.
- PGREALM sets the Kerberos realm to use with PostgreSQL, if it is different from the local realm. If PGREALM is set, PostgreSQL applications will attempt authentication with servers for this realm and use separate ticket files to avoid conflicts with local ticket files. This environment variable is only used if Kerberos authentication is selected by the backend.
- PGOPTIONS sets additional run-time options for the PostgreSQL backend.
- PGTTY sets the file or tty on which debugging messages from the backend server are displayed.
- PGREQUIRESSL sets whether or not the connection must be made over SSL. If set to "1", libpq will refuse to connect if the server does not accept an SSL connection. This option is only available if PostgreSQL is compiled with SSL support.
- PGCONNECT_TIMEOUT sets the maximum number of seconds that libpq will wait when attempting to connect to the PostgreSQL server. This option should be set to at least 2 seconds.

The following environment variables can be used to specify user-level default behavior for every PostgreSQL session:

- PGDATESTYLE sets the default style of date/time representation.
- PGTZ sets the default time zone.
- PGCLIENTENCODING sets the default client encoding (if multibyte support was selected when configuring PostgreSQL).

The following environment variables can be used to specify default internal behavior for every PostgreSQL session:

- PGGEQO sets the default mode for the genetic optimizer.

Refer to the SET SQL command for information on correct values for these environment variables.

1.11. Files

The file .pgpass in the home directory is a file that can contain passwords to be used if the connection requires a password. This file should have the format:

hostname:*port*:*database*:*username*:*password*

Any of these may be a literal name, or *, which matches anything. The first matching entry will be used, so put more-specific entries first. When an entry contains : or \, it must be escaped with \.

The permissions on .pgpass must disallow any access to world or group; achieve this by the command chmod 0600 .pgpass. If the permissions are less strict than this, the file will be ignored.

1.12. Threading Behavior

libpq is thread-safe as of PostgreSQL 7.0, so long as no two threads attempt to manipulate the same PGconn object at the same time. In particular, you cannot issue concurrent queries from different threads through the same connection object. (If you need to run concurrent queries, start up multiple connections.)

PGresult objects are read-only after creation, and so can be passed around freely between threads.

The deprecated functions PQoidStatus and fe_setauthsvc are not thread-safe and should not be used in multithread programs. PQoidStatus can be replaced by PQoidValue. There is no good reason to call fe_setauthsvc at all.

Libpq clients using the crypt encryption method rely on the crypt() operating system function, which is often not thread-safe. It is better to use MD5 encryption, which is thread-safe on all platforms.

1.13. Building Libpq Programs

To build (i.e., compile and link) your libpq programs you need to do all of the following things:

- Include the libpq-fe.h header file:

  ```
  #include <libpq-fe.h>
  ```

  If you failed to do that then you will normally get error messages from your compiler similar to

  ```
  foo.c: In function `main':
  foo.c:34: `PGconn' undeclared (first use in this function)
  foo.c:35: `PGresult' undeclared (first use in this function)
  foo.c:54: `CONNECTION_BAD' undeclared (first use in this
   function)
  foo.c:68: `PGRES_COMMAND_OK' undeclared (first use in this
   function)
  foo.c:95: `PGRES_TUPLES_OK' undeclared (first use in this
   function)
  ```

- Point your compiler to the directory where the PostgreSQL header files were installed, by supplying the -I*directory* option to your compiler. (In some cases the compiler will look into the directory in question by default, so you can omit this option.) For instance, your compile command line could look like:

  ```
  cc -c -I/usr/local/pgsql/include testprog.c
  ```

  If you are using makefiles then add the option to the CPPFLAGS variable:

  ```
  CPPFLAGS += -I/usr/local/pgsql/include
  ```

  If there is any chance that your program might be compiled by other users then you should not hardcode the directory location like that. Instead, you can run the utility pg_config to find out where the header files are on the local system:

  ```
  $ pg_config --includedir
  /usr/local/include
  ```

  Failure to specify the correct option to the compiler will result in an error message such as

  ```
  testlibpq.c:8:22: libpq-fe.h: No such file or directory
  ```

- When linking the final program, specify the option -lpq so that the libpq library gets pulled in, as well as the option -L*directory* to point it to the directory where the libpq library resides. (Again, the compiler will search some directories by default.) For maximum portability, put the -L option before the -lpq option. For example:

  ```
  cc -o testprog testprog1.o testprog2.o -L/usr/local/pgsql/lib -
  lpq
  ```

  You can find out the library directory using pg_config as well:

```
$ pg_config --libdir
/usr/local/pgsql/lib
```

Error messages that point to problems in this area could look like the following.

```
testlibpq.o: In function `main':
testlibpq.o(.text+0x60): undefined reference to `PQsetdbLogin'
testlibpq.o(.text+0x71): undefined reference to `PQstatus'
testlibpq.o(.text+0xa4): undefined reference to `PQerrorMessage'
```

This means you forgot `-lpq`.

```
/usr/bin/ld: cannot find -lpq
```

This means you forgot the `-L` or did not specify the right path.

If your codes references the header file `libpq-int.h` and you refuse to fix your code to not use it, starting in PostgreSQL 7.2, this file will be found in *`includedir`*`/postgresql/internal/libpq-int.h`, so you need to add the appropriate `-I` option to your compiler command line.

1.14. Example Programs

Example 1.1. libpq Example Program 1

```
/*
 * testlibpq.c
 *
 * Test the C version of libpq, the PostgreSQL frontend
 * library.
 */
#include <stdio.h>
#include <libpq-fe.h>

void
exit_nicely(PGconn *conn)
{
    PQfinish(conn);
    exit(1);
}

main()
{
    char       *pghost,
               *pgport,
               *pgoptions,
               *pgtty;
    char       *dbName;
    int         nFields;
    int         i,
                j;

    /* FILE *debug; */

    PGconn     *conn;
    PGresult   *res;

    /*
```

```
    * begin, by setting the parameters for a backend connection if
the
    * parameters are null, then the system will try to use
reasonable
    * defaults by looking up environment variables or, failing
that,
    * using hardwired constants
    */
   pghost = NULL;              /* host name of the backend server
*/
   pgport = NULL;              /* port of the backend server */
   pgoptions = NULL;           /* special options to start up the
backend
                                * server */
   pgtty = NULL;               /* debugging tty for the backend
server */
   dbName = "template1";

   /* make a connection to the database */
   conn = PQsetdb(pghost, pgport, pgoptions, pgtty, dbName);

   /*
    * check to see that the backend connection was successfully
made
    */
   if (PQstatus(conn) == CONNECTION_BAD)
   {
       fprintf(stderr, "Connection to database '%s' failed.\n",
dbName);
       fprintf(stderr, "%s", PQerrorMessage(conn));
       exit_nicely(conn);
   }

   /* debug = fopen("/tmp/trace.out","w"); */
   /* PQtrace(conn, debug);  */

   /* start a transaction block */
   res = PQexec(conn, "BEGIN");
   if (!res || PQresultStatus(res) != PGRES_COMMAND_OK)
   {
       fprintf(stderr, "BEGIN command failed\n");
       PQclear(res);
       exit_nicely(conn);
   }

   /*
    * should PQclear PGresult whenever it is no longer needed to
avoid
    * memory leaks
    */
   PQclear(res);

   /*
    * fetch rows from the pg_database, the system catalog of
    * databases
    */
   res = PQexec(conn, "DECLARE mycursor CURSOR FOR SELECT * FROM
pg_database");
```

```
    if (!res || PQresultStatus(res) != PGRES_COMMAND_OK)
    {
        fprintf(stderr, "DECLARE CURSOR command failed\n");
        PQclear(res);
        exit_nicely(conn);
    }
    PQclear(res);
    res = PQexec(conn, "FETCH ALL in mycursor");
    if (!res || PQresultStatus(res) != PGRES_TUPLES_OK)
    {
        fprintf(stderr, "FETCH ALL command didn't return tuples
 properly\n");
        PQclear(res);
        exit_nicely(conn);
    }

    /* first, print out the attribute names */
    nFields = PQnfields(res);
    for (i = 0; i < nFields; i++)
        printf("%-15s", PQfname(res, i));
    printf("\n\n");

    /* next, print out the rows */
    for (i = 0; i < PQntuples(res); i++)
    {
        for (j = 0; j < nFields; j++)
            printf("%-15s", PQgetvalue(res, i, j));
        printf("\n");
    }
    PQclear(res);

    /* close the cursor */
    res = PQexec(conn, "CLOSE mycursor");
    PQclear(res);

    /* commit the transaction */
    res = PQexec(conn, "COMMIT");
    PQclear(res);

    /* close the connection to the database and cleanup */
    PQfinish(conn);

    /* fclose(debug); */
    return 0;

}
```

Example 1.2. libpq Example Program 2

```
/*
 * testlibpq2.c
 *  Test of the asynchronous notification interface
 *
 * Start this program, then from psql in another window do
 *   NOTIFY TBL2;
 *
 * Or, if you want to get fancy, try this:
 * Populate a database with the following:
```

```
 *
 *   CREATE TABLE TBL1 (i int4);
 *
 *   CREATE TABLE TBL2 (i int4);
 *
 *   CREATE RULE r1 AS ON INSERT TO TBL1 DO
 *     (INSERT INTO TBL2 values (new.i); NOTIFY TBL2);
 *
 * and do
 *
 *   INSERT INTO TBL1 values (10);
 *
 */
#include <stdio.h>
#include "libpq-fe.h"

void
exit_nicely(PGconn *conn)
{
    PQfinish(conn);
    exit(1);
}

main()
{
    char       *pghost,
               *pgport,
               *pgoptions,
               *pgtty;
    char       *dbName;
    int         nFields;
    int         i,
                j;

    PGconn     *conn;
    PGresult   *res;
    PGnotify   *notify;

    /*
     * begin, by setting the parameters for a backend connection if
 the
     * parameters are null, then the system will try to use
 reasonable
     * defaults by looking up environment variables or, failing
 that,
     * using hardwired constants
     */
    pghost = NULL;              /* host name of the backend server
 */
    pgport = NULL;              /* port of the backend server */
    pgoptions = NULL;           /* special options to start up the
 backend
                                 * server */
    pgtty = NULL;               /* debugging tty for the backend
 server */
    dbName = getenv("USER");    /* change this to the name of your
 test
                                 * database */
```

```
    /* make a connection to the database */
    conn = PQsetdb(pghost, pgport, pgoptions, pgtty, dbName);

    /*
     * check to see that the backend connection was successfully
made
     */
    if (PQstatus(conn) == CONNECTION_BAD)
    {
        fprintf(stderr, "Connection to database '%s' failed.\n",
dbName);
        fprintf(stderr, "%s", PQerrorMessage(conn));
        exit_nicely(conn);
    }

    res = PQexec(conn, "LISTEN TBL2");
    if (!res || PQresultStatus(res) != PGRES_COMMAND_OK)
    {
        fprintf(stderr, "LISTEN command failed\n");
        PQclear(res);
        exit_nicely(conn);
    }

    /*
     * should PQclear PGresult whenever it is no longer needed to
avoid
     * memory leaks
     */
    PQclear(res);

    while (1)
    {

        /*
         * wait a little bit between checks; waiting with select()
         * would be more efficient.
         */
        sleep(1);
        /* collect any asynchronous backend messages */
        PQconsumeInput(conn);
        /* check for asynchronous notify messages */
        while ((notify = PQnotifies(conn)) != NULL)
        {
            fprintf(stderr,
                 "ASYNC NOTIFY of '%s' from backend pid '%d'
received\n",
                    notify->relname, notify->be_pid);
            free(notify);
        }
    }

    /* close the connection to the database and cleanup */
    PQfinish(conn);

    return 0;
}
```

Example 1.3. libpq Example Program 3

```
/*
 * testlibpq3.c Test the C version of Libpq, the PostgreSQL
 frontend
 * library. tests the binary cursor interface
 *
 *
 *
 * populate a database by doing the following:
 *
 * CREATE TABLE test1 (i int4, d real, p polygon);
 *
 * INSERT INTO test1 values (1, 3.567, polygon '(3.0, 4.0, 1.0,
 2.0)');
 *
 * INSERT INTO test1 values (2, 89.05, polygon '(4.0, 3.0, 2.0,
 1.0)');
 *
 * the expected output is:
 *
 * tuple 0: got i = (4 bytes) 1, d = (4 bytes) 3.567000, p = (4
 * bytes) 2 points   boundbox = (hi=3.000000/4.000000, lo =
 * 1.000000,2.000000) tuple 1: got i = (4 bytes) 2, d = (4 bytes)
 * 89.050003, p = (4 bytes) 2 points   boundbox =
 * (hi=4.000000/3.000000, lo = 2.000000,1.000000)
 *
 *
 */
#include <stdio.h>
#include "libpq-fe.h"
#include "utils/geo_decls.h"    /* for the POLYGON type */

void
exit_nicely(PGconn *conn)
{
    PQfinish(conn);
    exit(1);
}

main()
{
    char       *pghost,
               *pgport,
               *pgoptions,
               *pgtty;
    char       *dbName;
    int         nFields;
    int         i,
                j;
    int         i_fnum,
                d_fnum,
                p_fnum;
    PGconn     *conn;
    PGresult   *res;

    /*
```

```
    * begin, by setting the parameters for a backend connection if
the
    * parameters are null, then the system will try to use
reasonable
    * defaults by looking up environment variables or, failing
that,
    * using hardwired constants
    */
   pghost = NULL;              /* host name of the backend server
*/
   pgport = NULL;              /* port of the backend server */
   pgoptions = NULL;           /* special options to start up the
backend
                                * server */
   pgtty = NULL;               /* debugging tty for the backend
server */

   dbName = getenv("USER");    /* change this to the name of your
test
                                * database */

   /* make a connection to the database */
   conn = PQsetdb(pghost, pgport, pgoptions, pgtty, dbName);

   /*
    * check to see that the backend connection was successfully
made
    */
   if (PQstatus(conn) == CONNECTION_BAD)
   {
       fprintf(stderr, "Connection to database '%s' failed.\n",
dbName);
       fprintf(stderr, "%s", PQerrorMessage(conn));
       exit_nicely(conn);
   }

   /* start a transaction block */
   res = PQexec(conn, "BEGIN");
   if (!res || PQresultStatus(res) != PGRES_COMMAND_OK)
   {
       fprintf(stderr, "BEGIN command failed\n");
       PQclear(res);
       exit_nicely(conn);
   }

   /*
    * should PQclear PGresult whenever it is no longer needed to
avoid
    * memory leaks
    */
   PQclear(res);

   /*
    * fetch rows from the pg_database, the system catalog of
    * databases
    */
   res = PQexec(conn, "DECLARE mycursor BINARY CURSOR FOR SELECT *
FROM test1");
```

```
    if (!res || PQresultStatus(res) != PGRES_COMMAND_OK)
    {
        fprintf(stderr, "DECLARE CURSOR command failed\n");
        PQclear(res);
        exit_nicely(conn);
    }
    PQclear(res);

    res = PQexec(conn, "FETCH ALL in mycursor");
    if (!res || PQresultStatus(res) != PGRES_TUPLES_OK)
    {
        fprintf(stderr, "FETCH ALL command didn't return tuples
properly\n");
        PQclear(res);
        exit_nicely(conn);
    }

    i_fnum = PQfnumber(res, "i");
    d_fnum = PQfnumber(res, "d");
    p_fnum = PQfnumber(res, "p");

    for (i = 0; i < 3; i++)
    {
        printf("type[%d] = %d, size[%d] = %d\n",
               i, PQftype(res, i),
               i, PQfsize(res, i));
    }
    for (i = 0; i < PQntuples(res); i++)
    {
        int         *ival;
        float       *dval;
        int          plen;
        POLYGON     *pval;

        /* we hard-wire this to the 3 fields we know about */
        ival = (int *) PQgetvalue(res, i, i_fnum);
        dval = (float *) PQgetvalue(res, i, d_fnum);
        plen = PQgetlength(res, i, p_fnum);

        /*
         * plen doesn't include the length field so need to
         * increment by VARHDSZ
         */
        pval = (POLYGON *) malloc(plen + VARHDRSZ);
        pval->size = plen;
        memmove((char *) &pval->npts, PQgetvalue(res, i, p_fnum),
plen);
        printf("tuple %d: got\n", i);
        printf(" i = (%d bytes) %d,\n",
               PQgetlength(res, i, i_fnum), *ival);
        printf(" d = (%d bytes) %f,\n",
               PQgetlength(res, i, d_fnum), *dval);
        printf(" p = (%d bytes) %d points \tboundbox = (hi=%f/%f,
lo = %f,%f)\n",
               PQgetlength(res, i, d_fnum),
               pval->npts,
               pval->boundbox.xh,
               pval->boundbox.yh,
```

```
                pval->boundbox.xl,
                pval->boundbox.yl);
        }
        PQclear(res);

        /* close the cursor */
        res = PQexec(conn, "CLOSE mycursor");
        PQclear(res);

        /* commit the transaction */
        res = PQexec(conn, "COMMIT");
        PQclear(res);

        /* close the connection to the database and cleanup */
        PQfinish(conn);

        return 0;
    }
```

Chapter 2. Large Objects

2.1. Introduction

In PostgreSQL releases prior to 7.1, the size of any row in the database could not exceed the size of a data page. Since the size of a data page is 8192 bytes (the default, which can be raised up to 32768), the upper limit on the size of a data value was relatively low. To support the storage of larger atomic values, PostgreSQL provided and continues to provide a large object interface. This interface provides file-oriented access to user data that has been declared to be a large object.

POSTGRES 4.2, the indirect predecessor of PostgreSQL, supported three standard implementations of large objects: as files external to the POSTGRES server, as external files managed by the POSTGRES server, and as data stored within the POSTGRES database. This caused considerable confusion among users. As a result, only support for large objects as data stored within the database is retained in PostgreSQL. Even though this is slower to access, it provides stricter data integrity. For historical reasons, this storage scheme is referred to as *Inversion large objects*. (You will see the term Inversion used occasionally to mean the same thing as large object.) Since PostgreSQL 7.1, all large objects are placed in one system table called `pg_largeobject`.

PostgreSQL 7.1 introduced a mechanism (nicknamed "TOAST") that allows data rows to be much larger than individual data pages. This makes the large object interface partially obsolete. One remaining advantage of the large object interface is that it allows random access to the data, i.e., the ability to read or write small chunks of a large value. It is planned to equip TOAST with such functionality in the future.

This section describes the implementation and the programming and query language interfaces to PostgreSQL large object data. We use the libpq C library for the examples in this section, but most programming interfaces native to PostgreSQL support equivalent functionality. Other interfaces may use the large object interface internally to provide generic support for large values. This is not described here.

2.2. Implementation Features

The large object implementation breaks large objects up into "chunks" and stores the chunks in tuples in the database. A B-tree index guarantees fast searches for the correct chunk number when doing random access reads and writes.

2.3. Interfaces

The facilities PostgreSQL provides to access large objects, both in the backend as part of user-defined functions or the front end as part of an application using the interface, are described below. For users familiar with POSTGRES 4.2, PostgreSQL has a new set of functions providing a more coherent interface.

Note

All large object manipulation *must* take place within an SQL transaction. This requirement is strictly enforced as of PostgreSQL 6.5, though it has been an implicit requirement in previous versions, resulting in misbehavior if ignored.

The PostgreSQL large object interface is modeled after the Unix file-system interface, with analogues of `open(2)`, `read(2)`, `write(2)`, `lseek(2)`, etc. User functions call these routines to retrieve only the data of interest from a large object. For example, if a large object type called `mugshot` existed that stored photographs of faces, then a function called `beard` could be declared on `mugshot` data. `beard` could look at the lower third of a photograph, and determine the color of the beard that appeared there, if any. The entire large-object value need not be buffered, or even examined, by the

beard function. Large objects may be accessed from dynamically-loaded C functions or database client programs that link the library. PostgreSQL provides a set of routines that support opening, reading, writing, closing, and seeking on large objects.

2.3.1. Creating a Large Object

The routine

```
Oid lo_creat(PGconn *conn, int mode)
```

creates a new large object. *mode* is a bit mask describing several different attributes of the new object. The symbolic constants listed here are defined in the header file libpq/libpq-fs.h. The access type (read, write, or both) is controlled by or'ing together the bits INV_READ and INV_WRITE. The low-order sixteen bits of the mask have historically been used at Berkeley to designate the storage manager number on which the large object should reside. These bits should always be zero now. The commands below create a large object:

```
inv_oid = lo_creat(INV_READ|INV_WRITE);
```

2.3.2. Importing a Large Object

To import an operating system file as a large object, call

```
Oid lo_import(PGconn *conn, const char *filename)
```

filename specifies the operating system name of the file to be imported as a large object.

2.3.3. Exporting a Large Object

To export a large object into an operating system file, call

```
int lo_export(PGconn *conn, Oid lobjId, const char *filename)
```

The *lobjId* argument specifies the OID of the large object to export and the *filename* argument specifies the operating system name name of the file.

2.3.4. Opening an Existing Large Object

To open an existing large object, call

```
int lo_open(PGconn *conn, Oid lobjId, int mode)
```

The *lobjId* argument specifies the OID of the large object to open. The *mode* bits control whether the object is opened for reading (INV_READ), writing (INV_WRITE), or both. A large object cannot be opened before it is created. lo_open returns a large object descriptor for later use in lo_read, lo_write, lo_lseek, lo_tell, and lo_close.

2.3.5. Writing Data to a Large Object

The routine

```
int lo_write(PGconn *conn, int fd, const char *buf, size_t len)
```

writes *len* bytes from *buf* to large object *fd*. The *fd* argument must have been returned by a previous lo_open. The number of bytes actually written is returned. In the event of an error, the return value is negative.

2.3.6. Reading Data from a Large Object

The routine

```
int lo_read(PGconn *conn, int fd, char *buf, size_t len)
```

reads *len* bytes from large object *fd* into *buf*. The *fd* argument must have been returned by a previous lo_open. The number of bytes actually read is returned. In the event of an error, the return value is negative.

2.3.7. Seeking on a Large Object

To change the current read or write location on a large object, call

```
int lo_lseek(PGconn *conn, int fd, int offset, int whence)
```

This routine moves the current location pointer for the large object described by *fd* to the new location specified by *offset*. The valid values for *whence* are SEEK_SET, SEEK_CUR, and SEEK_END.

2.3.8. Closing a Large Object Descriptor

A large object may be closed by calling

```
int lo_close(PGconn *conn, int fd)
```

where *fd* is a large object descriptor returned by lo_open. On success, lo_close returns zero. On error, the return value is negative.

2.3.9. Removing a Large Object

To remove a large object from the database, call

```
int lo_unlink(PGconn *conn, Oid lobjId)
```

The *lobjId* argument specifies the OID of the large object to remove. In the event of an error, the return value is negative.

2.4. Server-side Built-in Functions

There are two built-in registered functions, lo_import and lo_export which are convenient for use in SQL queries. Here is an example of their use

```
CREATE TABLE image (
    name            text,
    raster          oid
);

INSERT INTO image (name, raster)
    VALUES ('beautiful image', lo_import('/etc/motd'));

SELECT lo_export(image.raster, '/tmp/motd') FROM image
    WHERE name = 'beautiful image';
```

2.5. Accessing Large Objects from Libpq

Example 2.1, “Large Objects with Libpq Example Program” is a sample program which shows how the large object interface in libpq can be used. Parts of the program are commented out but are left in the source for the reader's benefit. This program can be found in src/test/examples/testlo.c in the source distribution. Frontend applications which use the large object interface in libpq should include the header file libpq/libpq-fs.h and link with the libpq library.

Example 2.1. Large Objects with Libpq Example Program

```
/*-------------------------------------------------------------
 *
 * testlo.c--
 *    test using large objects with libpq
 *
 * Copyright (c) 1994, Regents of the University of California
 *
 *-------------------------------------------------------------
 */
#include <stdio.h>
#include "libpq-fe.h"
#include "libpq/libpq-fs.h"

#define BUFSIZE          1024

/*
 * importFile
 *    import file "in_filename" into database as large object
 "lobjOid"
 *
 */
Oid
importFile(PGconn *conn, char *filename)
{
    Oid         lobjId;
    int         lobj_fd;
    char        buf[BUFSIZE];
    int         nbytes,
                tmp;
    int         fd;

    /*
     * open the file to be read in
     */
    fd = open(filename, O_RDONLY, 0666);
    if (fd < 0)
    {                           /* error */
        fprintf(stderr, "can't open unix file %s\n", filename);
    }

    /*
     * create the large object
     */
    lobjId = lo_creat(conn, INV_READ | INV_WRITE);
    if (lobjId == 0)
        fprintf(stderr, "can't create large object\n");

    lobj_fd = lo_open(conn, lobjId, INV_WRITE);

    /*
     * read in from the Unix file and write to the inversion file
     */
    while ((nbytes = read(fd, buf, BUFSIZE)) > 0)
    {
        tmp = lo_write(conn, lobj_fd, buf, nbytes);
        if (tmp < nbytes)
```

```
                fprintf(stderr, "error while reading large object\n");
        }

        (void) close(fd);
        (void) lo_close(conn, lobj_fd);

        return lobjId;
    }

    void
    pickout(PGconn *conn, Oid lobjId, int start, int len)
    {
        int         lobj_fd;
        char       *buf;
        int         nbytes;
        int         nread;

        lobj_fd = lo_open(conn, lobjId, INV_READ);
        if (lobj_fd < 0)
        {
            fprintf(stderr, "can't open large object %d\n",
                    lobjId);
        }

        lo_lseek(conn, lobj_fd, start, SEEK_SET);
        buf = malloc(len + 1);

        nread = 0;
        while (len - nread > 0)
        {
            nbytes = lo_read(conn, lobj_fd, buf, len - nread);
            buf[nbytes] = ' ';
            fprintf(stderr, ">>> %s", buf);
            nread += nbytes;
        }
        free(buf);
        fprintf(stderr, "\n");
        lo_close(conn, lobj_fd);
    }

    void
    overwrite(PGconn *conn, Oid lobjId, int start, int len)
    {
        int         lobj_fd;
        char       *buf;
        int         nbytes;
        int         nwritten;
        int         i;

        lobj_fd = lo_open(conn, lobjId, INV_READ);
        if (lobj_fd < 0)
        {
            fprintf(stderr, "can't open large object %d\n",
                    lobjId);
        }

        lo_lseek(conn, lobj_fd, start, SEEK_SET);
        buf = malloc(len + 1);
```

```
    for (i = 0; i < len; i++)
        buf[i] = 'X';
    buf[i] = ' ';

    nwritten = 0;
    while (len - nwritten > 0)
    {
        nbytes = lo_write(conn, lobj_fd, buf + nwritten, len -
 nwritten);
        nwritten += nbytes;
    }
    free(buf);
    fprintf(stderr, "\n");
    lo_close(conn, lobj_fd);
}

/*
 * exportFile *    export large object "lobjOid" to file
 "out_filename"
 *
 */
void
exportFile(PGconn *conn, Oid lobjId, char *filename)
{
    int         lobj_fd;
    char        buf[BUFSIZE];
    int         nbytes,
                tmp;
    int         fd;

    /*
     * create an inversion "object"
     */
    lobj_fd = lo_open(conn, lobjId, INV_READ);
    if (lobj_fd < 0)
    {
        fprintf(stderr, "can't open large object %d\n",
                lobjId);
    }

    /*
     * open the file to be written to
     */
    fd = open(filename, O_CREAT | O_WRONLY, 0666);
    if (fd < 0)
    {                           /* error */
        fprintf(stderr, "can't open unix file %s\n",
                filename);
    }

    /*
     * read in from the Unix file and write to the inversion file
     */
    while ((nbytes = lo_read(conn, lobj_fd, buf, BUFSIZE)) > 0)
    {
        tmp = write(fd, buf, nbytes);
        if (tmp < nbytes)
```

```
        {
            fprintf(stderr, "error while writing %s\n",
                    filename);
        }
    }

    (void) lo_close(conn, lobj_fd);
    (void) close(fd);

    return;
}

void
exit_nicely(PGconn *conn)
{
    PQfinish(conn);
    exit(1);
}

int
main(int argc, char **argv)
{
    char       *in_filename,
               *out_filename;
    char       *database;
    Oid         lobjOid;
    PGconn     *conn;
    PGresult   *res;

    if (argc != 4)
    {
        fprintf(stderr, "Usage: %s database_name in_filename
 out_filename\n",
                argv[0]);
        exit(1);
    }

    database = argv[1];
    in_filename = argv[2];
    out_filename = argv[3];

    /*
     * set up the connection
     */
    conn = PQsetdb(NULL, NULL, NULL, NULL, database);

    /* check to see that the backend connection was successfully
 made */
    if (PQstatus(conn) == CONNECTION_BAD)
    {
        fprintf(stderr, "Connection to database '%s' failed.\n",
 database);
        fprintf(stderr, "%s", PQerrorMessage(conn));
        exit_nicely(conn);
    }

    res = PQexec(conn, "begin");
    PQclear(res);
```

```
    printf("importing file %s\n", in_filename);
/*  lobjOid = importFile(conn, in_filename); */
    lobjOid = lo_import(conn, in_filename);
/*
    printf("as large object %d.\n", lobjOid);

    printf("picking out bytes 1000-2000 of the large object\n");
    pickout(conn, lobjOid, 1000, 1000);

    printf("overwriting bytes 1000-2000 of the large object with
 X's\n");
    overwrite(conn, lobjOid, 1000, 1000);
*/

    printf("exporting large object to file %s\n", out_filename);
/*    exportFile(conn, lobjOid, out_filename); */
    lo_export(conn, lobjOid, out_filename);

    res = PQexec(conn, "end");
    PQclear(res);
    PQfinish(conn);
    exit(0);
}
```

Chapter 3. pgtcl - Tcl Binding Library

3.1. Introduction

pgtcl is a Tcl package for client programs to interface with PostgreSQL servers. It makes most of the functionality of libpq available to Tcl scripts.

This package was originally written by Jolly Chen.

Table 3.1, "`pgtcl` Commands" gives an overview over the commands available in pgtcl. These commands are described further on subsequent pages.

Table 3.1. `pgtcl` Commands

Command	Description
`pg_connect`	opens a connection to the backend server
`pg_disconnect`	closes a connection
`pg_conndefaults`	get connection options and their defaults
`pg_exec`	send a query to the backend
`pg_result`	manipulate the results of a query
`pg_select`	loop over the result of a SELECT statement
`pg_execute`	send a query and optionally loop over the results
`pg_listen`	establish a callback for NOTIFY messages
`pg_on_connection_loss`	establish a callback for unexpected connection loss
`pg_lo_creat`	create a large object
`pg_lo_open`	open a large object
`pg_lo_close`	close a large object
`pg_lo_read`	read a large object
`pg_lo_write`	write a large object
`pg_lo_lseek`	seek to a position in a large object
`pg_lo_tell`	return the current seek position of a large object
`pg_lo_unlink`	delete a large object
`pg_lo_import`	import a Unix file into a large object
`pg_lo_export`	export a large object into a Unix file

The `pg_lo_*` routines are interfaces to the large object features of PostgreSQL. The functions are designed to mimic the analogous file system functions in the standard Unix file system interface. The `pg_lo_*` routines should be used within a `BEGIN/COMMIT` transaction block because the file descriptor returned by `pg_lo_open` is only valid for the current transaction. `pg_lo_import` and `pg_lo_export` *must* be used in a `BEGIN/COMMIT` transaction block.

Example 3.1, "pgtcl Example Program" shows a small example of how to use the routines.

Example 3.1. pgtcl Example Program

```
# getDBs :
#   get the names of all the databases at a given host and port
 number
```

```
#   with the defaults being the localhost and port 5432
#   return them in alphabetical order
proc getDBs { {host "localhost"} {port "5432"} } {
    # datnames is the list to be result
    set conn [pg_connect template1 -host $host -port $port]
    set res [pg_exec $conn "SELECT datname FROM pg_database ORDER
 BY datname"]
    set ntups [pg_result $res -numTuples]
    for {set i 0} {$i < $ntups} {incr i} {
 lappend datnames [pg_result $res -getTuple $i]
    }
    pg_result $res -clear
    pg_disconnect $conn
    return $datnames
}
```

3.2. Loading pgtcl into your application

Before using pgtcl commands, you must load `libpgtcl` into your Tcl application. This is normally done with the Tcl `load` command. Here is an example:

```
load libpgtcl[info sharedlibextension]
```

The use of `info sharedlibextension` is recommended in preference to hard-wiring `.so` or `.sl` into the program.

The `load` command will fail unless the system's dynamic loader knows where to look for the `libpgtcl` shared library file. You may need to work with `ldconfig`, or set the environment variable `LD_LIBRARY_PATH`, or use some equivalent facility for your platform to make it work. Refer to the PostgreSQL installation instructions for more information.

`libpgtcl` in turn depends on `libpq`, so the dynamic loader must also be able to find the `libpq` shared library. In practice this is seldom an issue, since both of these shared libraries are normally stored in the same directory, but it can be a stumbling block in some configurations.

If you use a custom executable for your application, you might choose to statically bind `libpgtcl` into the executable and thereby avoid the `load` command and the potential problems of dynamic linking. See the source code for pgtclsh for an example.

3.3. pgtcl Command Reference Information

Name

pg_connect — open a connection to the backend server

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
pg_connect -conninfo connectOptions
pg_connect dbName [-host hostName]
  [-port portNumber] [-tty pqtty]
  [-options optionalBackendArgs]
```

Inputs (new style)

connectOptions

A string of connection options, each written in the form keyword = value. A list of valid options can be found in libpq's PQconnectdb() manual entry.

Inputs (old style)

dbName

Specifies a valid database name.

[-host *hostName*]

Specifies the domain name of the backend server for *dbName*.

[-port *portNumber*]

Specifies the IP port number of the backend server for *dbName*.

[-tty *pqtty*]

Specifies file or tty for optional debug output from backend.

[-options *optionalBackendArgs*]

Specifies options for the backend server for *dbName*.

Outputs

dbHandle

If successful, a handle for a database connection is returned. Handles start with the prefix pgsql.

Description

pg_connect opens a connection to the PostgreSQL backend.

Two syntaxes are available. In the older one, each possible option has a separate option switch in the pg_connect statement. In the newer form, a single option string is supplied that can contain multiple option values. See pg_conndefaults for info about the available options in the newer syntax.

Usage

Name

pg_disconnect — close a connection to the backend server

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_disconnect` *`dbHandle`*

Inputs

`dbHandle`

Specifies a valid database handle.

Outputs

None

Description

`pg_disconnect` closes a connection to the PostgreSQL backend.

Name

pg_conndefaults — obtain information about default connection parameters

Synopsis

<refsynopsisdivinfo>1998-10-07</refsynopsisdivinfo>

```
pg_conndefaults
```

Inputs

None.

Outputs

option list

The result is a list describing the possible connection options and their current default values. Each entry in the list is a sublist of the format:

```
{optname label dispchar dispsize value}
```

where the *optname* is usable as an option in `pg_connect -conninfo`.

Description

`pg_conndefaults` returns info about the connection options available in `pg_connect -conninfo` and the current default value for each option.

Usage

```
pg_conndefaults
```

Name

pg_exec — send a command string to the server

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_exec` *`dbHandle queryString`*

Inputs

`dbHandle`

Specifies a valid database handle.

`queryString`

Specifies a valid SQL query.

Outputs

`resultHandle`

A Tcl error will be returned if pgtcl was unable to obtain a backend response. Otherwise, a query result object is created and a handle for it is returned. This handle can be passed to `pg_result` to obtain the results of the query.

Description

`pg_exec` submits a query to the PostgreSQL backend and returns a result. Query result handles start with the connection handle and add a period and a result number.

Note that lack of a Tcl error is not proof that the query succeeded! An error message returned by the backend will be processed as a query result with failure status, not by generating a Tcl error in pg_exec.

Name

pg_result — get information about a query result

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_result` *`resultHandle resultOption`*

Inputs

`resultHandle`

The handle for a query result.

`resultOption`

Specifies one of several possible options.

Options

`-status`

the status of the result.

`-error`

the error message, if the status indicates error; otherwise an empty string.

`-conn`

the connection that produced the result.

`-oid`

if the command was an INSERT, the OID of the inserted tuple; otherwise 0.

`-numTuples`

the number of tuples returned by the query.

`-numAttrs`

the number of attributes in each tuple.

`-assign arrayName`

assign the results to an array, using subscripts of the form `(tupno,attributeName)`.

`-assignbyidx arrayName ?appendstr?`

assign the results to an array using the first attribute's value and the remaining attributes' names as keys. If *`appendstr`* is given then it is appended to each key. In short, all but the first field of each tuple are stored into the array, using subscripts of the form `(firstFieldValue,fieldNameAppendStr)`.

`-getTuple tupleNumber`

returns the fields of the indicated tuple in a list. Tuple numbers start at zero.

`-tupleArray tupleNumber arrayName`

stores the fields of the tuple in array *`arrayName`*, indexed by field names. Tuple numbers start at zero.

`-attributes`

returns a list of the names of the tuple attributes.

`-lAttributes`

returns a list of sublists, `{name ftype fsize}` for each tuple attribute.

`-clear`

clear the result query object.

Outputs

The result depends on the selected option, as described above.

Description

`pg_result` returns information about a query result created by a prior `pg_exec`.

You can keep a query result around for as long as you need it, but when you are done with it, be sure to free it by executing `pg_result -clear`. Otherwise, you have a memory leak, and Pgtcl will eventually start complaining that you've created too many query result objects.

Name

pg_select — loop over the result of a SELECT statement

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_select` *`dbHandle queryString arrayVar queryProcedure`*

Inputs

`dbHandle`

Specifies a valid database handle.

`queryString`

Specifies a valid SQL select query.

`arrayVar`

Array variable for tuples returned.

`queryProcedure`

Procedure run on each tuple found.

Outputs

None.

Description

`pg_select` submits a SELECT query to the PostgreSQL backend, and executes a given chunk of code for each tuple in the result. The *`queryString`* must be a SELECT statement. Anything else returns an error. The *`arrayVar`* variable is an array name used in the loop. For each tuple, *`arrayVar`* is filled in with the tuple field values, using the field names as the array indexes. Then the *`queryProcedure`* is executed.

In addition to the field values, the following special entries are made in the array:

`.headers`

A list of the column names returned by the SELECT.

`.numcols`

The number of columns returned by the SELECT.

`.tupno`

The current tuple number, starting at zero and incrementing for each iteration of the loop body.

Usage

This would work if table `table` has fields `control` and `name` (and, perhaps, other fields):

```
pg_select $pgconn "SELECT * FROM table" array {
 puts [format "%5d %s" $array(control) $array(name)]
}
```

Name

pg_execute — send a query and optionally loop over the results

Synopsis

<refsynopsisdivinfo>2002-03-06</refsynopsisdivinfo>

```
pg_execute [-array arrayVar] [-oid oidVar] dbHandle queryString
  [queryProcedure]
```

Inputs

[-array *arrayVar*]

Specifies the name of an array variable where result tuples are stored, indexed by the field names. This is ignored if *queryString* is not a SELECT statement. For SELECT statements, if this option is not used, result tuples values are stored in individual variables named according to the field names in the result.

[-oid *oidVar*]

Specifies the name of a variable into which the OID from an INSERT statement will be stored.

dbHandle

Specifies a valid database handle.

queryString

Specifies a valid SQL query.

[*queryProcedure*]

Optional command to execute for each result tuple of a SELECT statement.

Outputs

ntuples

The number of tuples affected or returned by the query.

Description

`pg_execute` submits a query to the PostgreSQL backend.

If the query is not a SELECT statement, the query is executed and the number of tuples affected by the query is returned. If the query is an INSERT and a single tuple is inserted, the OID of the inserted tuple is stored in the *oidVar* variable if the optional *-oid* argument is supplied.

If the query is a SELECT statement, the query is executed. For each tuple in the result, the tuple field values are stored in the *arrayVar* variable, if supplied, using the field names as the array indexes, else in variables named by the field names, and then the optional *queryProcedure* is executed if supplied. (Omitting the *queryProcedure* probably makes sense only if the query will return a single tuple.) The number of tuples selected is returned.

The *queryProcedure* can use the Tcl `break`, `continue`, and `return` commands, with the expected behavior. Note that if the *queryProcedure* executes `return`, `pg_execute` does not return *ntuples*.

`pg_execute` is a newer function which provides a superset of the features of `pg_select`, and can replace `pg_exec` in many cases where access to the result handle is not needed.

For backend-handled errors, `pg_execute` will throw a Tcl error and return two element list. The first element is an error code such as `PGRES_FATAL_ERROR`, and the second element is the backend error text. For more serious errors, such as failure to communicate with the backend, `pg_execute` will throw a Tcl error and return just the error message text.

Usage

In the following examples, error checking with `catch` has been omitted for clarity.

Insert a row and save the OID in `result_oid`:

```
    pg_execute -oid result_oid $pgconn "insert into mytable values
 (1)"
```

Print the item and value fields from each row:

```
    pg_execute -array d $pgconn "select item, value from mytable" {
       puts "Item=$d(item) Value=$d(value)"
    }
```

Find the maximum and minimum values and store them in $s(max) and $s(min):

```
    pg_execute -array s $pgconn "select max(value) as max,\
      min(value) as min from mytable"
```

Find the maximum and minimum values and store them in $max and $min:

```
    pg_execute $pgconn "select max(value) as max, min(value) as min
from mytable"
```

Name

pg_listen — set or change a callback for asynchronous NOTIFY messages

Synopsis

<refsynopsisdivinfo>1998-5-22</refsynopsisdivinfo>

`pg_listen` *`dbHandle notifyName callbackCommand`*

Inputs

`dbHandle`

Specifies a valid database handle.

`notifyName`

Specifies the notify condition name to start or stop listening to.

`callbackCommand`

If present, provides the command string to execute when a matching notification arrives.

Outputs

None

Description

`pg_listen` creates, changes, or cancels a request to listen for asynchronous NOTIFY messages from the PostgreSQL backend. With a *`callbackCommand`* parameter, the request is established, or the command string of an already existing request is replaced. With no *`callbackCommand`* parameter, a prior request is canceled.

After a `pg_listen` request is established, the specified command string is executed whenever a NOTIFY message bearing the given name arrives from the backend. This occurs when any PostgreSQL client application issues a NOTIFY command referencing that name. (Note that the name can be, but does not have to be, that of an existing relation in the database.) The command string is executed from the Tcl idle loop. That is the normal idle state of an application written with Tk. In non-Tk Tcl shells, you can execute `update` or `vwait` to cause the idle loop to be entered.

You should not invoke the SQL statements `LISTEN` or `UNLISTEN` directly when using `pg_listen`. Pgtcl takes care of issuing those statements for you. But if you want to send a NOTIFY message yourself, invoke the SQL NOTIFY statement using `pg_exec`.

Name

pg_on_connection_loss — set or change a callback for unexpected connection loss

Synopsis

<refsynopsisdivinfo>2002-09-02</refsynopsisdivinfo>

`pg_on_connection_loss` *`dbHandle callbackCommand`*

Inputs

`dbHandle`

Specifies a valid database handle.

`callbackCommand`

If present, provides the command string to execute when connection loss is detected.

Outputs

None

Description

`pg_on_connection_loss` creates, changes, or cancels a request to execute a callback command if an unexpected loss of connection to the database occurs. With a *`callbackCommand`* parameter, the request is established, or the command string of an already existing request is replaced. With no *`callbackCommand`* parameter, a prior request is canceled.

The callback command string is executed from the Tcl idle loop. That is the normal idle state of an application written with Tk. In non-Tk Tcl shells, you can execute `update` or `vwait` to cause the idle loop to be entered.

Name

pg_lo_creat — create a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_creat` *`conn mode`*

Inputs

`conn`

Specifies a valid database connection.

`mode`

Specifies the access mode for the large object

Outputs

`objOid`

The OID of the large object created.

Description

`pg_lo_creat` creates an Inversion Large Object.

Usage

mode can be any or'ing together of `INV_READ` and `INV_WRITE`. The “or” operator is `|`.

```
[pg_lo_creat $conn "INV_READ|INV_WRITE"]
```

Name

pg_lo_open — open a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_open` *`conn objOid mode`*

Inputs

`conn`

Specifies a valid database connection.

`objOid`

Specifies a valid large object OID.

`mode`

Specifies the access mode for the large object

Outputs

`fd`

A file descriptor for use in later pg_lo* routines.

Description

`pg_lo_open` open an Inversion Large Object.

Usage

Mode can be either `r`, `w`, or `rw`.

Name

pg_lo_close — close a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_close` *`conn fd`*

Inputs

`conn`

Specifies a valid database connection.

`fd`

A file descriptor for use in later pg_lo* routines.

Outputs

None

Description

`pg_lo_close` closes an Inversion Large Object.

Usage

Name

pg_lo_read — read a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_read` *`conn fd bufVar len`*

Inputs

`conn`

Specifies a valid database connection.

`fd`

File descriptor for the large object from pg_lo_open.

`bufVar`

Specifies a valid buffer variable to contain the large object segment.

`len`

Specifies the maximum allowable size of the large object segment.

Outputs

None

Description

`pg_lo_read` reads at most *`len`* bytes from a large object into a variable named *`bufVar`*.

Usage

`bufVar` must be a valid variable name.

Name

pg_lo_write — write a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_write` *`conn fd buf len`*

Inputs

`conn`

Specifies a valid database connection.

`fd`

File descriptor for the large object from pg_lo_open.

`buf`

Specifies a valid string variable to write to the large object.

`len`

Specifies the maximum size of the string to write.

Outputs

None

Description

`pg_lo_write` writes at most *`len`* bytes to a large object from a variable *`buf`*.

Usage

`buf` must be the actual string to write, not a variable name.

Name

pg_lo_lseek — seek to a position in a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_lseek` *`conn fd offset whence`*

Inputs

`conn`

Specifies a valid database connection.

`fd`

File descriptor for the large object from pg_lo_open.

`offset`

Specifies a zero-based offset in bytes.

`whence`

whence can be `SEEK_CUR`, `SEEK_END`, or `SEEK_SET`

Outputs

None

Description

`pg_lo_lseek` positions to *`offset`* bytes from the beginning of the large object.

Usage

`whence` can be `SEEK_CUR`, `SEEK_END`, or `SEEK_SET`.

Name

pg_lo_tell — return the current seek position of a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_tell` *`conn fd`*

Inputs

`conn`

Specifies a valid database connection.

`fd`

File descriptor for the large object from pg_lo_open.

Outputs

`offset`

A zero-based offset in bytes suitable for input to `pg_lo_lseek`.

Description

`pg_lo_tell` returns the current to *`offset`* in bytes from the beginning of the large object.

Usage

Name

pg_lo_unlink — delete a large object

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_unlink` *`conn lobjId`*

Inputs

`conn`

Specifies a valid database connection.

`lobjId`

Identifier for a large object.

Outputs

None

Description

`pg_lo_unlink` deletes the specified large object.

Usage

Name

pg_lo_import — import a large object from a file

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_import` *`conn filename`*

Inputs

`conn`

Specifies a valid database connection.

`filename`

Unix file name.

Outputs

None

Description

`pg_lo_import` reads the specified file and places the contents into a large object.

Usage

`pg_lo_import` must be called within a BEGIN/END transaction block.

Name

pg_lo_export — export a large object to a file

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

`pg_lo_export` *`conn lobjId filename`*

Inputs

`conn`

Specifies a valid database connection.

`lobjId`

Large object identifier.

`filename`

Unix file name.

Outputs

None

Description

`pg_lo_export` writes the specified large object into a Unix file.

Usage

`pg_lo_export` must be called within a BEGIN/END transaction block.

Chapter 4. ECPG - Embedded SQL in C

This chapter describes the embedded SQL package for PostgreSQL. It works with C and C++. It was written by Linus Tolke (<linus@epact.se>) and Michael Meskes (<meskes@postgresql.org>).

Admittedly, this documentation is quite incomplete. But since this interface is standardized, additional information can be found in many resources about SQL.

4.1. The Concept

An embedded SQL program consists of code written in an ordinary programming language, in this case C, mixed with SQL commands in specially marked sections. To build the program, the source code is first passed to the embedded SQL preprocessor, which converts it to an ordinary C program, and afterwards it can be processed by a C compilation tool chain.

Embedded SQL has advantages over other methods for handling SQL commands from C code. First, it takes care of the tedious passing of information to and from variables in your C program. Secondly, embedded SQL in C is defined in the SQL standard and supported by many other SQL databases. The PostgreSQL implementation is designed to match this standard as much as possible, and it is usually possible to port embedded SQL programs written for other RDBMS to PostgreSQL with relative ease.

As indicated, programs written for the embedded SQL interface are normal C programs with special code inserted to perform database-related actions. This special code always has the form

```
EXEC SQL ...;
```

These statements syntactically take the place of a C statement. Depending on the particular statement, they may appear in the global context or within a function. Embedded SQL statements follow the case-sensitivity rules of normal SQL code, and not those of C.

The following sections explain all the embedded SQL statements.

4.2. Connecting to the Database Server

One connects to a database using the following statement:

```
EXEC SQL CONNECT TO target [AS connection-name] [USER user-name];
```

The *target* can be specified in the following ways:

- *dbname*[@*hostname*][:*port*]
- tcp:postgresql://*hostname*[:*port*][/*dbname*][?*options*]
- unix:postgresql://*hostname*[:*port*][/*dbname*][?*options*]
- *character variable*
- *character string*
- DEFAULT

There are also different ways to specify the user name:

- *userid*

- *userid*/*password*
- *userid* IDENTIFIED BY *password*
- *userid* USING *password*

The *userid* and *password* may be a constant text, a character variable, or a character string.

The *connection-name* is used to handle multiple connections in one program. It can be omitted if a program uses only one connection.

4.3. Closing a Connection

To close a connection, use the following statement:

```
EXEC SQL DISCONNECT [connection];
```

The *connection* can be specified in the following ways:

- *connection-name*
- DEFAULT
- CURRENT
- ALL

4.4. Running SQL Commands

Any SQL command can be run from within an embedded SQL application. Below are some examples of how to do that.

Creating a table:

```
EXEC SQL CREATE TABLE foo (number integer, ascii char(16));
EXEC SQL CREATE UNIQUE INDEX num1 ON foo(number);
EXEC SQL COMMIT;
```

Inserting rows:

```
EXEC SQL INSERT INTO foo (number, ascii) VALUES (9999, 'doodad');
EXEC SQL COMMIT;
```

Deleting rows:

```
EXEC SQL DELETE FROM foo WHERE number = 9999;
EXEC SQL COMMIT;
```

Singleton Select:

```
EXEC SQL SELECT foo INTO :FooBar FROM table1 WHERE ascii =
 'doodad';
```

Select using Cursors:

```
EXEC SQL DECLARE foo_bar CURSOR FOR
    SELECT number, ascii FROM foo
    ORDER BY ascii;
EXEC SQL FETCH foo_bar INTO :FooBar, DooDad;
```

```
...
EXEC SQL CLOSE foo_bar;
EXEC SQL COMMIT;
```

Updates:

```
EXEC SQL UPDATE foo
    SET ascii = 'foobar'
    WHERE number = 9999;
EXEC SQL COMMIT;
```

The tokens of the form `:something` are *host variables*, that is, they refer to variables in the C program. They are explained in the next section.

In the default mode, statements are committed only when `EXEC SQL COMMIT` is issued. The embedded SQL interface also supports autocommit of transactions (as known from other interfaces) via the `-t` command-line option to `ecpg` (see below) or via the `EXEC SQL SET AUTOCOMMIT TO ON` statement. In autocommit mode, each query is automatically committed unless it is inside an explicit transaction block. This mode can be explicitly turned off using `EXEC SQL SET AUTOCOMMIT TO OFF`.

4.5. Passing Data

To pass data from the program to the database, for example as parameters in a query, or to pass data from the database back to the program, the C variables that are intended to contain this data need to be declared in a specially marked section, so the embedded SQL preprocessor is made aware of them.

This section starts with

```
EXEC SQL BEGIN DECLARE SECTION;
```

and ends with

```
EXEC SQL END DECLARE SECTION;
```

Between those lines, there must be normal C variable declarations, such as

```
int   x;
char  foo[16], bar[16];
```

The declarations are also echoed to the output file as a normal C variables, so there's no need to declare them again. Variables that are not intended to be used with SQL commands can be declared normally outside these special sections.

The definition of a structure or union also must be listed inside a `DECLARE` section. Otherwise the preprocessor cannot handle these types since it does not know the definition.

The special types `VARCHAR` and `VARCHAR2` are converted into a named `struct` for every variable. A declaration like:

```
VARCHAR var[180];
```

is converted into:

```
struct varchar_var { int len; char arr[180]; } var;
```

This structure is suitable for interfacing with SQL datums of type `VARCHAR`.

To use a properly declared C variable in an SQL statement, write `:varname` where an expression is expected. See the previous section for some examples.

4.6. Error Handling

The embedded SQL interface provides a simplistic and a complex way to handle exceptional conditions in a program. The first method causes a message to printed automatically when a certain condition occurs. For example:

```
EXEC SQL WHENEVER sqlerror sqlprint;
```

or

```
EXEC SQL WHENEVER not found sqlprint;
```

This error handling remains enabled throughout the entire program.

Note

This is *not* an exhaustive example of usage for the `EXEC SQL WHENEVER` statement. Further examples of usage may be found in SQL manuals (e.g., *The LAN TIMES Guide to SQL* by Groff and Weinberg).

For a more powerful error handling, the embedded SQL interface provides a `struct` and a variable with the name `sqlca` as follows:

```
struct sqlca
{
    char sqlcaid[8];
    long sqlabc;
    long sqlcode;
    struct
    {
        int sqlerrml;
        char sqlerrmc[70];
    } sqlerrm;
    char sqlerrp[8];

    long sqlerrd[6];
    /* 0: empty                                        */
    /* 1: OID of processed tuple if applicable         */
    /* 2: number of rows processed in an INSERT, UPDATE */
    /*    or DELETE statement                          */
    /* 3: empty                                        */
    /* 4: empty                                        */
    /* 5: empty                                        */

    char sqlwarn[8];
    /* 0: set to 'W' if at least one other is 'W'      */
    /* 1: if 'W' at least one character string         */
    /*    value was truncated when it was              */
    /*    stored into a host variable.                 */
    /* 2: empty                                        */
    /* 3: empty                                        */
    /* 4: empty                                        */
    /* 5: empty                                        */
    /* 6: empty                                        */
    /* 7: empty                                        */

    char sqlext[8];
} sqlca;
```

(Many of the empty fields may be used in a future release.)

If no error occurred in the last SQL statement, `sqlca.sqlcode` will be 0 (`ECPG_NO_ERROR`). If `sqlca.sqlcode` is less that zero, this is a serious error, like the database definition does not match the query. If it is greater than zero, it is a normal error like the table did not contain the requested row.

`sqlca.sqlerrm.sqlerrmc` will contain a string that describes the error. The string ends with the line number in the source file.

These are the errors that can occur:

`-12, Out of memory in line %d.`

Should not normally occur. This indicates your virtual memory is exhausted.

`-200 (ECPG_UNSUPPORTED): Unsupported type %s on line %d.`

Should not normally occur. This indicates the preprocessor has generated something that the library does not know about. Perhaps you are running incompatible versions of the preprocessor and the library.

`-201 (ECPG_TOO_MANY_ARGUMENTS): Too many arguments line %d.`

This means that the server has returned more arguments than we have matching variables. Perhaps you have forgotten a couple of the host variables in the `INTO :var1,:var2` list.

`-202 (ECPG_TOO_FEW_ARGUMENTS): Too few arguments line %d.`

This means that the server has returned fewer arguments than we have host variables. Perhaps you have too many host variables in the `INTO :var1,:var2` list.

`-203 (ECPG_TOO_MANY_MATCHES): Too many matches line %d.`

This means the query has returned several rows but the variables specified are not arrays. The `SELECT` command was not unique.

`-204 (ECPG_INT_FORMAT): Not correctly formatted int type: %s line %d.`

This means the host variable is of type `int` and the field in the PostgreSQL database is of another type and contains a value that cannot be interpreted as an `int`. The library uses `strtol()` for this conversion.

`-205 (ECPG_UINT_FORMAT): Not correctly formatted unsigned type: %s line %d.`

This means the host variable is of type `unsigned int` and the field in the PostgreSQL database is of another type and contains a value that cannot be interpreted as an `unsigned int`. The library uses `strtoul()` for this conversion.

`-206 (ECPG_FLOAT_FORMAT): Not correctly formatted floating-point type: %s line %d.`

This means the host variable is of type `float` and the field in the PostgreSQL database is of another type and contains a value that cannot be interpreted as a `float`. The library uses `strtod()` for this conversion.

`-207 (ECPG_CONVERT_BOOL): Unable to convert %s to bool on line %d.`

This means the host variable is of type `bool` and the field in the PostgreSQL database is neither `'t'` nor `'f'`.

```
-208 (ECPG_EMPTY): Empty query line %d.
```

The query was empty. (This cannot normally happen in an embedded SQL program, so it may point to an internal error.)

```
-209 (ECPG_MISSING_INDICATOR): NULL value without indicator in line
%d.
```

A null value was returned and no null indicator variable was supplied.

```
-210 (ECPG_NO_ARRAY): Variable is not an array in line %d.
```

An ordinary variable was used in a place that requires an array.

```
-211 (ECPG_DATA_NOT_ARRAY): Data read from backend is not an array
in line %d.
```

The database returned an ordinary variable in a place that requires array value.

```
-220 (ECPG_NO_CONN): No such connection %s in line %d.
```

The program tried to access a connection that does not exist.

```
-221 (ECPG_NOT_CONN): Not connected in line %d.
```

The program tried to access a connection that does exist but is not open.

```
-230 (ECPG_INVALID_STMT): Invalid statement name %s in line %d.
```

The statement you are trying to use has not been prepared.

```
-240 (ECPG_UNKNOWN_DESCRIPTOR): Descriptor %s not found in line %d.
```

The descriptor specified was not found. The statement you are trying to use has not been prepared.

```
-241 (ECPG_INVALID_DESCRIPTOR_INDEX): Descriptor index out of range
in line %d.
```

The descriptor index specified was out of range.

```
-242 (ECPG_UNKNOWN_DESCRIPTOR_ITEM): Descriptor %s not found in line
%d.
```

The descriptor specified was not found. The statement you are trying to use has not been prepared.

```
-243 (ECPG_VAR_NOT_NUMERIC): Variable is not a numeric type in line
%d.
```

The database returned a numeric value and the variable was not numeric.

```
-244 (ECPG_VAR_NOT_CHAR): Variable is not a character type in line %d.
```

The database returned a non-numeric value and the variable was numeric.

```
-400 (ECPG_PGSQL): Postgres error: %s line %d.
```

Some PostgreSQL error. The message contains the error message from the PostgreSQL backend.

```
-401 (ECPG_TRANS): Error in transaction processing line %d.
```

PostgreSQL signaled that we cannot start, commit, or rollback the transaction.

`-402 (ECPG_CONNECT): Could not connect to database %s in line %d.`

The connect to the database did not work.

`100 (ECPG_NOT_FOUND): Data not found line %d.`

This is a "normal" error that tells you that what you are querying cannot be found or you are at the end of the cursor.

4.7. Including Files

To include an external file into your embedded SQL program, use:

```
EXEC SQL INCLUDE filename;
```

The embedded SQL preprocessor will look for a file named *filename*.h, preprocess it, and include it in the resulting C output. Thus, embedded SQL statements in the included file are handled correctly.

Note that this is *not* the same as

```
#include <filename.h>
```

because the file would not be subject to SQL command preprocessing. Naturally, you can continue to use the C `#include` directive to include other header files.

Note

The include file name is case-sensitive, even though the rest of the `EXEC SQL INCLUDE` command follows the normal SQL case-sensitivity rules.

4.8. Processing Embedded SQL Programs

Now that you have an idea how to form embedded SQL C programs, you probably want to know how to compile them. Before compiling you run the file through the embedded SQL C preprocessor, which converts the SQL statements you used to special function calls. After compiling, you must link with a special library that contains the needed functions. These functions fetch information from the arguments, perform the SQL query using the libpq interface, and put the result in the arguments specified for output.

The preprocessor program is called `ecpg` and is included in a normal PostgreSQL installation. Embedded SQL programs are typically named with an extension `.pgc`. If you have a program file called `prog1.pgc`, you can preprocess it by simply calling

```
ecpg prog1.pgc
```

This will create a file called `prog1.c`. If your input files do not follow the suggested naming pattern, you can specify the output file explicitly using the `-o` option.

The preprocessed file can be compiled normally, for example

```
cc -c prog1.c
```

The generated C source files include headers files from the PostgreSQL installation, so if you installed PostgreSQL in a location that is not searched by default, you have to add an option such as `-I/usr/local/pgsql/include` to the compilation command line.

To link an embedded SQL program, you need to include the `libecpg` library, like so:

```
cc -o myprog prog1.o prog2.o ... -lecpg
```

Again, you might have to add an option like `-L/usr/local/pgsql/lib` to that command line.

If you manage the build process of a larger project using make, it may be convenient to include the following implicit rule to your makefiles:

```
ECPG = ecpg

%.c: %.pgc
        $(ECPG) $<
```

The complete syntax of the `ecpg` command is detailed in the PostgreSQL 7.3.21 Reference Manual.

4.9. Library Functions

The `libecpg` library primarily contains "hidden" functions that are used to implement the functionality expressed by the embedded SQL commands. But there are some functions that can usefully be called directly. Note that this makes your code unportable.

- `ECPGdebug(int on, FILE *stream)` turns on debug logging if called with the first argument non-zero. Debug logging is done on *`stream`*. Most SQL statement log their arguments and results.

  The most important function, `ECPGdo`, logs all SQL statements with both the expanded string, i.e. the string with all the input variables inserted, and the result from the PostgreSQL server. This can be very useful when searching for errors in your SQL statements.

- `ECPGstatus()` This method returns true if we are connected to a database and false if not.

4.10. Porting From Other RDBMS Packages

The design of ecpg follows the SQL standard. Porting from a standard RDBMS should not be a problem. Unfortunately there is no such thing as a standard RDBMS. Therefore ecpg tries to understand syntax extensions as long as they do not create conflicts with the standard.

The following list shows all the known incompatibilities. If you find one not listed please notify the developers. Note, however, that we list only incompatibilities from a preprocessor of another RDBMS to ecpg and not ecpg features that these RDBMS do not support.

Syntax of `FETCH`

The standard syntax for `FETCH` is:

```
FETCH [direction] [amount] IN|FROM cursor
```

Oracle, however, does not use the keywords `IN` or `FROM`. This feature cannot be added since it would create parsing conflicts.

4.11. For the Developer

This section explain how ecpg works internally. This information can occasionally be useful to help users understand how to use ecpg.

4.11.1. The Preprocessor

The first four lines written by `ecpg` to the output are fixed lines. Two are comments and two are include lines necessary to interface to the library. Then the preprocessor reads through the file and writes output. Normally it just echoes everything to the output.

When it sees an `EXEC SQL` statement, it intervenes and changes it. The command starts with `exec sql` and ends with `;`. Everything in between is treated as an SQL statement and parsed for variable substitution.

Variable substitution occurs when a symbol starts with a colon (`:`). The variable with that name is looked up among the variables that were previously declared within a `EXEC SQL DECLARE` section. Depending on whether the variable is being use for input or output, a pointer to the variable is output to allow access by the function.

For every variable that is part of the SQL query, the function gets other arguments:

- The type as a special symbol.
- A pointer to the value or a pointer to the pointer.
- The size of the variable if it is a `char` or `varchar`.
- The number of elements in the array (for array fetches).
- The offset to the next element in the array (for array fetches).
- The type of the indicator variable as a special symbol.
- A pointer to the value of the indicator variable or a pointer to the pointer of the indicator variable.
- 0
- Number of elements in the indicator array (for array fetches).
- The offset to the next element in the indicator array (for array fetches).

Note that not all SQL commands are treated in this way. For instance, an open cursor statement like

```
EXEC SQL OPEN cursor;
```

is not copied to the output. Instead, the cursor's `DECLARE` command is used because it opens the cursor as well.

Here is a complete example describing the output of the preprocessor of a file `foo.pgc` (details may change with each particular version of the preprocessor):

```
EXEC SQL BEGIN DECLARE SECTION;
int index;
int result;
EXEC SQL END DECLARE SECTION;
...
EXEC SQL SELECT res INTO :result FROM mytable WHERE index = :index;
```

is translated into:

```
/* Processed by ecpg (2.6.0) */
/* These two include files are added by the preprocessor */
#include <ecpgtype.h>;
#include <ecpglib.h>;

/* exec sql begin declare section */

#line 1 "foo.pgc"

 int index;
 int result;
```

```
/* exec sql end declare section */
...
ECPGdo(__LINE__, NULL, "SELECT res FROM mytable WHERE index = ?
 ",
        ECPGt_int,&(index),1L,1L,sizeof(int),
        ECPGt_NO_INDICATOR, NULL , 0L, 0L, 0L, ECPGt_EOIT,
        ECPGt_int,&(result),1L,1L,sizeof(int),
        ECPGt_NO_INDICATOR, NULL , 0L, 0L, 0L, ECPGt_EORT);
#line 147 "foo.pgc"
```

(The indentation in this manual is added for readability and not something the preprocessor does.)

4.11.2. The Library

The most important function in the library is `ECPGdo`. It takes a variable number of arguments. Hopefully there are no computers that limit the number of variables that can be accepted by a `varargs()` function. This can easily add up to 50 or so arguments.

The arguments are:

A line number

This is a line number of the original line; used in error messages only.

A string

This is the SQL query that is to be issued. It is modified by the input variables, i.e. the variables that where not known at compile time but are to be entered in the query. Where the variables should go the string contains `?`.

Input variables

As described in the section about the preprocessor, every input variable gets ten arguments.

`ECPGt_EOIT`

An `enum` telling that there are no more input variables.

Output variables

As described in the section about the preprocessor, every input variable gets ten arguments. These variables are filled by the function.

`ECPGt_EORT`

An `enum` telling that there are no more variables.

Chapter 5. JDBC Interface

Author

Originally written by Peter T. Mount (<peter@retep.org.uk>), the original author of the JDBC driver.

JDBC is a core API of Java 1.1 and later. It provides a standard set of interfaces to SQL-compliant databases.

PostgreSQL provides a *type 4* JDBC Driver. Type 4 indicates that the driver is written in Pure Java, and communicates in the database system's own network protocol. Because of this, the driver is platform independent; once compiled, the driver can be used on any system.

This chapter is not intended as a complete guide to JDBC programming, but should help to get you started. For more information refer to the standard JDBC API documentation. Also, take a look at the examples included with the source. The basic example is used here.

5.1. Setting up the JDBC Driver

5.1.1. Getting the Driver

Precompiled versions of the driver can be downloaded from the PostgreSQL JDBC web site[1].

Alternatively you can build the driver from source, but you should only need to do this if you are making changes to the source code. For details, refer to the PostgreSQL installation instructions. After installation, the driver should be found in *PREFIX*/share/java/postgresql.jar. The resulting driver will be built for the version of Java you are running. If you build with a 1.1 JDK you will build a version that supports the JDBC 1 specification, if you build with a Java 2 JDK (e.g., JDK 1.2 or JDK 1.3) you will build a version that supports the JDBC 2 specification.

5.1.2. Setting up the Class Path

To use the driver, the JAR archive (named postgresql.jar if you built from source, otherwise it will likely be named jdbc7.2-1.1.jar or jdbc7.2-1.2.jar for the JDBC 1 and JDBC 2 versions respectively) needs to be included in the class path, either by putting it in the CLASSPATH environment variable, or by using flags on the java command line.

For instance, I have an application that uses the JDBC driver to access a large database containing astronomical objects. I have the application and the JDBC driver installed in the /usr/local/lib directory, and the Java JDK installed in /usr/local/jdk1.3.1. To run the application, I would use:

```
export CLASSPATH=/usr/local/lib/finder.jar[1]:/usr/local/pgsql/share/
java/postgresql.jar:.
java Finder
```

[1] finder.jar contains the Finder application.

Loading the driver from within the application is covered in Section 5.2, “Using the Driver”.

5.1.3. Preparing the Database for JDBC

Because Java only uses TCP/IP connections, the PostgreSQL server must be configured to accept TCP/IP connections. This can be done by setting tcpip_socket = true in the postgresql.conf file or by supplying the -i option flag when starting postmaster.

[1] http://jdbc.postgresql.org

Also, the client authentication setup in the `pg_hba.conf` file may need to be configured. Refer to the *Administrator's Guide* for details. The JDBC Driver supports the trust, ident, password, md5, and crypt authentication methods.

5.2. Using the Driver

5.2.1. Importing JDBC

Any source that uses JDBC needs to import the `java.sql` package, using:

```
import java.sql.*;
```

Important

Do not import the `org.postgresql` package. If you do, your source will not compile, as `javac` will get confused.

5.2.2. Loading the Driver

Before you can connect to a database, you need to load the driver. There are two methods available, and it depends on your code which is the best one to use.

In the first method, your code implicitly loads the driver using the `Class.forName()` method. For PostgreSQL, you would use:

```
Class.forName("org.postgresql.Driver");
```

This will load the driver, and while loading, the driver will automatically register itself with JDBC.

Note

The `forName()` method can throw a `ClassNotFoundException` if the driver is not available.

This is the most common method to use, but restricts your code to use just PostgreSQL. If your code may access another database system in the future, and you do not use any PostgreSQL-specific extensions, then the second method is advisable.

The second method passes the driver as a parameter to the JVM as it starts, using the `-D` argument. Example:

```
java -Djdbc.drivers=org.postgresql.Driver example.ImageViewer
```

In this example, the JVM will attempt to load the driver as part of its initialization. Once done, the `ImageViewer` is started.

Now, this method is the better one to use because it allows your code to be used with other database packages without recompiling the code. The only thing that would also change is the connection URL, which is covered next.

One last thing: When your code then tries to open a `Connection`, and you get a No driver available `SQLException` being thrown, this is probably caused by the driver not being in the class path, or the value in the parameter not being correct.

5.2.3. Connecting to the Database

With JDBC, a database is represented by a URL (Uniform Resource Locator). With PostgreSQL, this takes one of the following forms:

- `jdbc:postgresql:`*`database`*
- `jdbc:postgresql://`*`host`*`/`*`database`*
- `jdbc:postgresql://`*`host`*`:`*`port`*`/`*`database`*

where:

`host`

The host name of the server. Defaults to `localhost`.

`port`

The port number the server is listening on. Defaults to the PostgreSQL standard port number (5432).

`database`

The database name.

To connect, you need to get a `Connection` instance from JDBC. To do this, you would use the `DriverManager.getConnection()` method:

```
Connection db = DriverManager.getConnection(url, username,
 password);
```

5.2.4. Closing the Connection

To close the database connection, simply call the `close()` method to the `Connection`:

```
db.close();
```

5.3. Issuing a Query and Processing the Result

Any time you want to issue SQL statements to the database, you require a `Statement` or `PreparedStatement` instance. Once you have a `Statement` or `PreparedStatement`, you can use issue a query. This will return a `ResultSet` instance, which contains the entire result. Example 5.1, “Processing a Simple Query in JDBC” illustrates this process.

Example 5.1. Processing a Simple Query in JDBC

This example will issue a simple query and print out the first column of each row using a `Statement`.

```
Statement st = db.createStatement();
ResultSet rs = st.executeQuery("SELECT * FROM mytable where
 columnfoo = 500");
while(rs.next()) {
    System.out.print("Column 1 returned ");
    System.out.println(rs.getString(1));
}
rs.close();
st.close();
```

This example will issue the same query as before using a `PreparedStatement` and a bind value in the query.

```
int foovalue = 500;
PreparedStatement st = db.prepareStatement("SELECT * FROM mytable
 where columnfoo = ?");
st.setInt(1, foovalue);
ResultSet rs = st.executeQuery();
while(rs.next()) {
    System.out.print("Column 1 returned ");
    System.out.println(rs.getString(1));
}
rs.close();
st.close();
```

5.3.1. Using the `Statement` or `PreparedStatement` Interface

The following must be considered when using the `Statement` or `PreparedStatement` interface:

- You can use a single `Statement` instance as many times as you want. You could create one as soon as you open the connection and use it for the connection's lifetime. But you have to remember that only one `ResultSet` can exist per `Statement` or `PreparedStatement` at a given time.
- If you need to perform a query while processing a `ResultSet`, you can simply create and use another `Statement`.
- If you are using threads, and several are using the database, you must use a separate `Statement` for each thread. Refer to Section 5.8, “Using the driver in a multithreaded or a servlet environment” if you are thinking of using threads, as it covers some important points.
- When you are done using the `Statement` or `PreparedStatement` you should close it.

5.3.2. Using the `ResultSet` Interface

The following must be considered when using the `ResultSet` interface:

- Before reading any values, you must call `next()`. This returns true if there is a result, but more importantly, it prepares the row for processing.
- Under the JDBC specification, you should access a field only once. It is safest to stick to this rule, although at the current time, the PostgreSQL driver will allow you to access a field as many times as you want.
- You must close a `ResultSet` by calling `close()` once you have finished using it.
- Once you make another query with the `Statement` used to create a `ResultSet`, the currently open `ResultSet` instance is closed automatically.
- `ResultSet` is currently read only. You can not update data through the `ResultSet`. If you want to update data you need to do it the old fashioned way by issuing a SQL update statement. This is in conformance with the JDBC specification which does not require drivers to provide this functionality.

5.4. Performing Updates

To change data (perform an insert, update, or delete) you use the `executeUpdate()` method. `executeUpdate()` is similar to the `executeQuery()` used to issue a select, however it doesn't

return a ResultSet, instead it returns the number of records affected by the insert, update, or delete statement.

Example 5.2. Simple Delete Example

This example will issue a simple delete and print out the number of rows deleted.

```
int foovalue = 500;
PreparedStatement st = db.prepareStatement("DELETE FROM mytable
 where columnfoo = ?");
st.setInt(1, foovalue);
int rowsDeleted = st.executeUpdate();
System.out.println(rowsDeleted + " rows deleted");
st.close();
```

5.5. Creating and Modifying Database Objects

To create, modify or drop a database object like a table or view you use the execute() method. execute is similar to the executeQuery() used to issue a select, however it doesn't return a result.

Example 5.3. Drop Table Example

This example will drop a table.

```
Statement st = db.createStatement();
ResultSet rs = st.executeQuery("DROP TABLE mytable");
st.close();
```

5.6. Storing Binary Data

PostgreSQL provides two distinct ways to store binary data. Binary data can be stored in a table using PostgreSQL's binary data type bytea, or by using the *Large Object* feature which stores the binary data in a separate table in a special format, and refers to that table by storing a value of type OID in your table.

In order to determine which method is appropriate you need to understand the limitations of each method. The bytea data type is not well suited for storing very large amounts of binary data. While a column of type bytea can hold up to 1 GB of binary data, it would require a huge amount of memory (RAM) to process such a large value. The Large Object method for storing binary data is better suited to storing very large values, but it has its own limitations. Specifically deleting a row that contains a Large Object does not delete the Large Object. Deleting the Large Object is a separate operation that needs to be performed. Large Objects also have some security issues since anyone connected to the database case view and/or modify any Large Object, even if they don't have permissions to view/update the row containing the Large Object.

7.2 is the first release of the JDBC Driver that supports the bytea data type. The introduction of this functionality in 7.2 has introduced a change in behavior as compared to previous releases. In 7.2 the methods getBytes(), setBytes(), getBinaryStream(), and setBinaryStream() operate on the bytea data type. In 7.1 these methods operated on the OID data type associated with Large Objects. It is possible to revert the driver back to the old 7.1 behavior by setting the *compatible* property on the Connection to a value of 7.1

To use the bytea data type you should simply use the getBytes(), setBytes(), getBinaryStream(), or setBinaryStream() methods.

To use the Large Object functionality you can use either the LargeObject API provided by the PostgreSQL JDBC Driver, or by using the getBLOB() and setBLOB() methods.

Important

For PostgreSQL, you must access Large Objects within an SQL transaction. You would open a transaction by using the `setAutoCommit()` method with an input parameter of `false`.

Note

In a future release of the JDBC Driver, the `getBLOB()` and `setBLOB()` methods may no longer interact with Large Objects and will instead work on `bytea` data types. So it is recommended that you use the `LargeObject` API if you intend to use Large Objects.

Example 5.4. Binary Data Examples

For example, suppose you have a table containing the file name of an image and you also want to store the image in a `bytea` column:

```
CREATE TABLE images (imgname text, img bytea);
```

To insert an image, you would use:

```
File file = new File("myimage.gif");
FileInputStream fis = new FileInputStream(file);
PreparedStatement ps = conn.prepareStatement("INSERT INTO images
 VALUES (?, ?)");
ps.setString(1, file.getName());
ps.setBinaryStream(2, fis, file.length());
ps.executeUpdate();
ps.close();
fis.close();
```

Here, `setBinaryStream()` transfers a set number of bytes from a stream into the column of type `bytea`. This also could have been done using the `setBytes()` method if the contents of the image was already in a `byte[]`.

Retrieving an image is even easier. (We use `PreparedStatement` here, but the `Statement` class can equally be used.)

```
PreparedStatement ps = con.prepareStatement("SELECT img FROM images
 WHERE imgname=?");
ps.setString(1, "myimage.gif");
ResultSet rs = ps.executeQuery();
if (rs != null) {
    while(rs.next()) {
        byte[] imgBytes = rs.getBytes(1);
        // use the stream in some way here
    }
    rs.close();
}
ps.close();
```

Here the binary data was retrieved as an `byte[]`. You could have used a `InputStream` object instead.

Alternatively you could be storing a very large file and want to use the `LargeObject` API to store the file:

```
CREATE TABLE imagesLO (imgname text, imgOID OID);
```

To insert an image, you would use:

```
// All LargeObject API calls must be within a transaction
conn.setAutoCommit(false);

// Get the Large Object Manager to perform operations with
LargeObjectManager lobj =
 ((org.postgresql.PGConnection)conn).getLargeObjectAPI();

//create a new large object
int oid = lobj.create(LargeObjectManager.READ |
 LargeObjectManager.WRITE);

//open the large object for write
LargeObject obj = lobj.open(oid, LargeObjectManager.WRITE);

// Now open the file
File file = new File("myimage.gif");
FileInputStream fis = new FileInputStream(file);

// copy the data from the file to the large object
byte buf[] = new byte[2048];
int s, tl = 0;
while ((s = fis.read(buf, 0, 2048)) > 0)
{
 obj.write(buf, 0, s);
 tl += s;
}

// Close the large object
obj.close();

//Now insert the row into imagesLO
PreparedStatement ps = conn.prepareStatement("INSERT INTO imagesLO
 VALUES (?, ?)");
ps.setString(1, file.getName());
ps.setInt(2, oid);
ps.executeUpdate();
ps.close();
fis.close();
```

Retrieving the image from the Large Object:

```
// All LargeObject API calls must be within a transaction
conn.setAutoCommit(false);

// Get the Large Object Manager to perform operations with
LargeObjectManager lobj =
 ((org.postgresql.PGConnection)conn).getLargeObjectAPI();

PreparedStatement ps = con.prepareStatement("SELECT imgOID FROM
 imagesLO WHERE imgname=?");
ps.setString(1, "myimage.gif");
ResultSet rs = ps.executeQuery();
if (rs != null) {
    while(rs.next()) {
 //open the large object for reading
 int oid = rs.getInt(1);
 LargeObject obj = lobj.open(oid, LargeObjectManager.READ);
```

```
 //read the data
 byte buf[] = new byte[obj.size()];
 obj.read(buf, 0, obj.size());
 //do something with the data read here

 // Close the object
 obj.close();
    }
    rs.close();
}
ps.close();
```

5.7. PostgreSQL Extensions to the JDBC API

PostgreSQL is an extensible database system. You can add your own functions to the backend, which can then be called from queries, or even add your own data types. As these are facilities unique to PostgreSQL, we support them from Java, with a set of extension API's. Some features within the core of the standard driver actually use these extensions to implement Large Objects, etc.

5.7.1. Accessing the Extensions

To access some of the extensions, you need to use some extra methods in the `org.postgresql.PGConnection` class. In this case, you would need to case the return value of `Driver.getConnection()`. For example:

```
Connection db = Driver.getConnection(url, username, password);
// ...
// later on
Fastpath fp = ((org.postgresql.PGConnection)db).getFastpathAPI();
```

5.7.1.1. Class `org.postgresql.PGConnection`

```
public class PGConnection
```

These are the extra methods used to gain access to PostgreSQL's extensions.

5.7.1.1.1. Methods

- `public Fastpath getFastpathAPI() throws SQLException`

  This returns the Fastpath API for the current connection. It is primarily used by the Large Object API.

  The best way to use this is as follows:

  ```
  import org.postgresql.fastpath.*;
  ...
  Fastpath fp =
   ((org.postgresql.PGConnection)myconn).getFastpathAPI();
  ```

  where `myconn` is an open `Connection` to PostgreSQL.

  Returns: Fastpath object allowing access to functions on the PostgreSQL backend.

  Throws: `SQLException` by Fastpath when initializing for first time

- `public LargeObjectManager getLargeObjectAPI() throws SQLException`

  This returns the Large Object API for the current connection.

The best way to use this is as follows:

```
import org.postgresql.largeobject.*;
...
LargeObjectManager lo =
 ((org.postgresql.PGConnection)myconn).getLargeObjectAPI();
```

where `myconn` is an open `Connection` to PostgreSQL.

Returns: `LargeObject` object that implements the API

Throws: `SQLException` by `LargeObject` when initializing for first time

- `public void addDataType(String type, String name)`

  This allows client code to add a handler for one of PostgreSQL's more unique data types. Normally, a data type not known by the driver is returned by `ResultSet.getObject()` as a `PGobject` instance. This method allows you to write a class that extends `PGobject`, and tell the driver the type name, and class name to use. The down side to this, is that you must call this method each time a connection is made.

  The best way to use this is as follows:

```
 ...
((org.postgresql.PGConnection)myconn).addDataType("mytype","my.class.name");
 ...
```

  where `myconn` is an open `Connection` to PostgreSQL. The handling class must extend `org.postgresql.util.PGobject`.

5.7.1.2. Class `org.postgresql.Fastpath`

```
public class Fastpath extends Object

java.lang.Object
   |
   +----org.postgresql.fastpath.Fastpath
```

`Fastpath` is an API that exists within the libpq C interface, and allows a client machine to execute a function on the database backend. Most client code will not need to use this method, but it is provided because the Large Object API uses it.

To use, you need to import the `org.postgresql.fastpath` package, using the line:

```
import org.postgresql.fastpath.*;
```

Then, in your code, you need to get a `FastPath` object:

```
Fastpath fp = ((org.postgresql.PGConnection)conn).getFastpathAPI();
```

This will return an instance associated with the database connection that you can use to issue commands. The casing of `Connection` to `org.postgresql.PGConnection` is required, as the `getFastpathAPI()` is an extension method, not part of JDBC. Once you have a `Fastpath` instance, you can use the `fastpath()` methods to execute a backend function.

See Also: `FastpathFastpathArg`, `LargeObject`

5.7.1.2.1. Methods

- `public Object fastpath(int fnid,`
  `boolean resulttype,`
  `FastpathArg args[]) throws SQLException`

Send a function call to the PostgreSQL backend.

Parameters: *fnid* - Function id *resulttype* - True if the result is an integer, false for other results *args* - FastpathArguments to pass to fastpath

Returns: null if no data, Integer if an integer result, or byte[] otherwise

- `public Object fastpath(String name,`
  `boolean resulttype,`
  `FastpathArg args[]) throws SQLException`

  Send a function call to the PostgreSQL backend by name.

  ## Note

  The mapping for the procedure name to function id needs to exist, usually to an earlier call to `addfunction()`. This is the preferred method to call, as function id's can/may change between versions of the backend. For an example of how this works, refer to org.postgresql.LargeObject

  Parameters: *name* - Function name *resulttype* - True if the result is an integer, false for other results *args* - FastpathArguments to pass to fastpath

  Returns: null if no data, Integer if an integer result, or byte[] otherwise

  See Also: LargeObject

- `public int getInteger(String name,`
  `FastpathArg args[]) throws SQLException`

  This convenience method assumes that the return value is an Integer

  Parameters: *name* - Function name *args* - Function arguments

  Returns: integer result

  Throws: SQLException if a database-access error occurs or no result

- `public byte[] getData(String name,`
  `FastpathArg args[]) throws SQLException`

  This convenience method assumes that the return value is binary data.

  Parameters: *name* - Function name *args* - Function arguments

  Returns: byte[] array containing result

  Throws: SQLException if a database-access error occurs or no result

- `public void addFunction(String name,`
  `int fnid)`

  This adds a function to our look-up table. User code should use the addFunctions method, which is based upon a query, rather than hard coding the OID. The OID for a function is not guaranteed to remain static, even on different servers of the same version.

- `public void addFunctions(ResultSet rs) throws SQLException`

  This takes a ResultSet containing two columns. Column 1 contains the function name, Column 2 the OID. It reads the entire ResultSet, loading the values into the function table.

Important

Remember to `close()` the `ResultSet` after calling this!

Implementation note about function name look-ups

PostgreSQL stores the function id's and their corresponding names in the `pg_proc` table. To speed things up locally, instead of querying each function from that table when required, a `Hashtable` is used. Also, only the function's required are entered into this table, keeping connection times as fast as possible.

The `org.postgresql.LargeObject` class performs a query upon its start-up, and passes the returned `ResultSet` to the `addFunctions()` method here. Once this has been done, the Large Object API refers to the functions by name.

Do not think that manually converting them to the OIDs will work. OK, they will for now, but they can change during development (there was some discussion about this for V7.0), so this is implemented to prevent any unwarranted headaches in the future.

See Also: `LargeObjectManager`

- `public int getID(String name) throws SQLException`

  This returns the function id associated by its name If `addFunction()` or `addFunctions()` have not been called for this name, then an `SQLException` is thrown.

5.7.1.3. Class `org.postgresql.fastpath.FastpathArg`

```
public class FastpathArg extends Object

java.lang.Object
   |
   +----org.postgresql.fastpath.FastpathArg
```

Each fastpath call requires an array of arguments, the number and type dependent on the function being called. This class implements methods needed to provide this capability.

For an example on how to use this, refer to the `org.postgresql.LargeObject` package.

See Also: `Fastpath`, `LargeObjectManager`, `LargeObject`

5.7.1.3.1. Constructors

- `public FastpathArg(int value)`

  Constructs an argument that consists of an integer value

  Parameters: value - int value to set

- `public FastpathArg(byte bytes[])`

  Constructs an argument that consists of an array of bytes

  Parameters: bytes - array to store

- ```
  public FastpathArg(byte buf[],
                     int off,
                     int len)
  ```

  Constructs an argument that consists of part of a byte array
  ```

Parameters:

buf

source array

off

offset within array

len

length of data to include

- `public FastpathArg(String s)`

  Constructs an argument that consists of a String.

5.7.2. Geometric Data Types

PostgreSQL has a set of data types that can store geometric features into a table. These include single points, lines, and polygons. We support these types in Java with the org.postgresql.geometric package. It contains classes that extend the org.postgresql.util.PGobject class. Refer to that class for details on how to implement your own data type handlers.

```
Class org.postgresql.geometric.PGbox

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGbox

   public class PGbox extends PGobject implements Serializable,
Cloneable

   This represents the box data type within PostgreSQL.

Variables

 public PGpoint point[]

          These are the two corner points of the box.

Constructors

 public PGbox(double x1,
              double y1,
              double x2,
              double y2)

        Parameters:
                x1 - first x coordinate
                y1 - first y coordinate
                x2 - second x coordinate
                y2 - second y coordinate

 public PGbox(PGpoint p1,
              PGpoint p2)
```

```
        Parameters:
                p1 - first point
                p2 - second point

 public PGbox(String s) throws SQLException

        Parameters:
                s - Box definition in PostgreSQL syntax

        Throws: SQLException
                if definition is invalid

 public PGbox()

          Required constructor

Methods

 public void setValue(String value) throws SQLException

          This method sets the value of this object. It should be
overridden, but still called by subclasses.

        Parameters:
                value - a string representation of the value of
 the
object
        Throws: SQLException
                thrown if value is invalid for this type

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two boxes are identical

        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
                clone in class PGobject

 public String getValue()

        Returns:
                the PGbox in the syntax expected by PostgreSQL

        Overrides:
```

```
               getValue in class PGobject

Class org.postgresql.geometric.PGcircle

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGcircle

   public class PGcircle extends PGobject implements Serializable,
Cloneable

   This represents PostgreSQL's circle data type, consisting of a
 point
and a radius

Variables

 public PGpoint center

          This is the center point

 double radius

          This is the radius

Constructors

 public PGcircle(double x,
                 double y,
                 double r)

        Parameters:
               x - coordinate of center
                y - coordinate of center
                r - radius of circle

 public PGcircle(PGpoint c,
                 double r)

        Parameters:
                c - PGpoint describing the circle's center
                r - radius of circle

 public PGcircle(String s) throws SQLException

        Parameters:
                s - definition of the circle in PostgreSQL's
 syntax.

        Throws: SQLException
                on conversion failure

 public PGcircle()

          This constructor is used by the driver.
```

```
Methods

 public void setValue(String s) throws SQLException

        Parameters:
                s - definition of the circle in PostgreSQL's
 syntax.

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two circles are identical

        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
                clone in class PGobject

 public String getValue()

        Returns:
                the PGcircle in the syntax expected by PostgreSQL

        Overrides:
                getValue in class PGobject

Class org.postgresql.geometric.PGline

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGline

   public class PGline extends PGobject implements Serializable,
Cloneable

   This implements a line consisting of two points. Currently line
 is
not yet implemented in the backend, but this class ensures that
 when
it's done were ready for it.

Variables
```

```
 public PGpoint point[]

          These are the two points.

Constructors

 public PGline(double x1,
               double y1,
               double x2,
               double y2)

        Parameters:
                x1 - coordinate for first point
                y1 - coordinate for first point
                x2 - coordinate for second point
                y2 - coordinate for second point

 public PGline(PGpoint p1,
               PGpoint p2)

        Parameters:
                p1 - first point
                p2 - second point

 public PGline(String s) throws SQLException

        Parameters:
                s - definition of the line in PostgreSQL's syntax.

        Throws: SQLException
                on conversion failure

 public PGline()

          required by the driver

Methods

 public void setValue(String s) throws SQLException

        Parameters:
                s - Definition of the line segment in PostgreSQL's
syntax

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two lines are identical
```

```
        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
                clone in class PGobject

 public String getValue()

        Returns:
                the PGline in the syntax expected by PostgreSQL

        Overrides:
                getValue in class PGobject

Class org.postgresql.geometric.PGlseg

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGlseg

   public class PGlseg extends PGobject implements Serializable,
Cloneable

   This implements a lseg (line segment) consisting of two points

Variables

 public PGpoint point[]

          These are the two points.

Constructors

 public PGlseg(double x1,
               double y1,
               double x2,
               double y2)

        Parameters:

                x1 - coordinate for first point
                y1 - coordinate for first point
                x2 - coordinate for second point
                y2 - coordinate for second point

 public PGlseg(PGpoint p1,
               PGpoint p2)

        Parameters:
                p1 - first point
                p2 - second point
```

```
 public PGlseg(String s) throws SQLException

        Parameters:
                s - Definition of the line segment in PostgreSQL's
 syntax.

        Throws: SQLException
                on conversion failure

 public PGlseg()

          required by the driver

Methods

 public void setValue(String s) throws SQLException

        Parameters:
                s - Definition of the line segment in PostgreSQL's
syntax

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two line segments are identical

        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
               clone in class PGobject

 public String getValue()

        Returns:
                the PGlseg in the syntax expected by PostgreSQL

        Overrides:
                getValue in class PGobject

Class org.postgresql.geometric.PGpath

java.lang.Object
   |
```

```
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGpath

   public class PGpath extends PGobject implements Serializable,
Cloneable

   This implements a path (a multiply segmented line, which may be
closed)

Variables

 public boolean open

          True if the path is open, false if closed

 public PGpoint points[]

          The points defining this path

Constructors

 public PGpath(PGpoint points[],
               boolean open)

        Parameters:
                points - the PGpoints that define the path
                open - True if the path is open, false if closed

 public PGpath()

          Required by the driver

 public PGpath(String s) throws SQLException

        Parameters:
                s - definition of the path in PostgreSQL's syntax.

        Throws: SQLException
                on conversion failure

Methods

 public void setValue(String s) throws SQLException

        Parameters:
                s - Definition of the path in PostgreSQL's syntax

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with
```

```
        Returns:
                true if the two pathes are identical

        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
                clone in class PGobject

 public String getValue()

          This returns the path in the syntax expected by
PostgreSQL

        Overrides:
                getValue in class PGobject

 public boolean isOpen()

     This returns true if the path is open

 public boolean isClosed()

     This returns true if the path is closed

 public void closePath()

     Marks the path as closed

 public void openPath()

     Marks the path as open

Class org.postgresql.geometric.PGpoint

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGpoint

   public class PGpoint extends PGobject implements Serializable,
Cloneable

   This implements a version of java.awt.Point, except it uses
 double
to represent the coordinates.

   It maps to the point data type in PostgreSQL.

Variables

 public double x
```

```
          The X coordinate of the point

 public double y

          The Y coordinate of the point

Constructors

 public PGpoint(double x,
                double y)

        Parameters:
                x - coordinate
                y - coordinate

 public PGpoint(String value) throws SQLException

          This is called mainly from the other geometric types,
 when a
point is embedded within their definition.

        Parameters:
                value - Definition of this point in PostgreSQL's
syntax

 public PGpoint()

          Required by the driver

Methods

 public void setValue(String s) throws SQLException

        Parameters:
                s - Definition of this point in PostgreSQL's syntax

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

 public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two points are identical

        Overrides:
                equals in class PGobject

 public Object clone()

          This must be overridden to allow the object to be cloned
```

```
        Overrides:
                clone in class PGobject

 public String getValue()

        Returns:
                the PGpoint in the syntax expected by PostgreSQL

        Overrides:
                getValue in class PGobject

 public void translate(int x,
                       int y)

          Translate the point with the supplied amount.

        Parameters:
                x - integer amount to add on the x axis
                y - integer amount to add on the y axis

 public void translate(double x,
                       double y)

          Translate the point with the supplied amount.

        Parameters:
                x - double amount to add on the x axis
                y - double amount to add on the y axis

 public void move(int x,
                  int y)

          Moves the point to the supplied coordinates.

        Parameters:
                x - integer coordinate
                y - integer coordinate

public void move(double x,
                 double y)

          Moves the point to the supplied coordinates.

        Parameters:
                x - double coordinate
                y - double coordinate

 public void setLocation(int x,
                         int y)

          Moves the point to the supplied coordinates. refer to
          java.awt.Point for description of this

        Parameters:
                x - integer coordinate
                y - integer coordinate

        See Also:
```

```
                Point

 public void setLocation(Point p)

          Moves the point to the supplied java.awt.Point refer to
          java.awt.Point for description of this

        Parameters:
                p - Point to move to

        See Also:
                Point

Class org.postgresql.geometric.PGpolygon

java.lang.Object
   |
   +----org.postgresql.util.PGobject
           |
           +----org.postgresql.geometric.PGpolygon

   public class PGpolygon extends PGobject implements
 Serializable,
Cloneable

   This implements the polygon data type within PostgreSQL.

Variables

 public PGpoint points[]

          The points defining the polygon

Constructors

 public PGpolygon(PGpoint points[])

          Creates a polygon using an array of PGpoints

        Parameters:
                points - the points defining the polygon

 public PGpolygon(String s) throws SQLException

        Parameters:
                s - definition of the polygon in PostgreSQL's
 syntax.

        Throws: SQLException
                on conversion failure

 public PGpolygon()

          Required by the driver

Methods

 public void setValue(String s) throws SQLException
```

```
        Parameters:
                s - Definition of the polygon in PostgreSQL's
syntax

        Throws: SQLException
                on conversion failure

        Overrides:
                setValue in class PGobject

public boolean equals(Object obj)

        Parameters:
                obj - Object to compare with

        Returns:
                true if the two polygons are identical

        Overrides:
                equals in class PGobject

public Object clone()

          This must be overridden to allow the object to be cloned

        Overrides:
                clone in class PGobject

public String getValue()

        Returns:
                the PGpolygon in the syntax expected by PostgreSQL

        Overrides:
                getValue in class PGobject
```

5.7.3. Large Objects

Large objects are supported in the standard JDBC specification. However, that interface is limited, and the API provided by PostgreSQL allows for random access to the objects contents, as if it was a local file.

The org.postgresql.largeobject package provides to Java the libpq C interface's large object API. It consists of two classes, `LargeObjectManager`, which deals with creating, opening and deleting large objects, and `LargeObject` which deals with an individual object.

5.7.3.1. Class `org.postgresql.largeobject.LargeObject`

```
public class LargeObject extends Object

java.lang.Object
   |
   +----org.postgresql.largeobject.LargeObject
```

This class implements the large object interface to PostgreSQL.

It provides the basic methods required to run the interface, plus a pair of methods that provide `InputStream` and `OutputStream` classes for this object.

Normally, client code would use the methods in `BLOB` to access large objects.

However, sometimes lower level access to Large Objects is required, that is not supported by the JDBC specification.

Refer to org.postgresql.largeobject.LargeObjectManager on how to gain access to a Large Object, or how to create one.

See Also: `LargeObjectManager`

5.7.3.1.1. Variables

public static final int SEEK_SET

Indicates a seek from the beginning of a file

public static final int SEEK_CUR

Indicates a seek from the current position

public static final int SEEK_END

Indicates a seek from the end of a file

5.7.3.1.2. Methods

- `public int getOID()`

  Returns the OID of this `LargeObject`

- `public void close() throws SQLException`

  This method closes the object. You must not call methods in this object after this is called.

- `public byte[] read(int len) throws SQLException`

  Reads some data from the object, and return as a byte[] array

- ```
  public int read(byte buf[],
                  int off,
                  int len) throws SQLException
  ```

  Reads some data from the object into an existing array

  Parameters:

  buf

  destination array

  off

  offset within array

  len

  number of bytes to read

- `public void write(byte buf[]) throws SQLException`

  Writes an array to the object

- `public void write(byte buf[],`
  ```

```
                    int off,
                    int len) throws SQLException
```

Writes some data from an array to the object

Parameters:

buf

destination array

off

offset within array

len

number of bytes to write

5.7.3.2. Class `org.postgresql.largeobject.LargeObjectManager`

```
public class LargeObjectManager extends Object

java.lang.Object
   |
   +----org.postgresql.largeobject.LargeObjectManager
```

This class implements the large object interface to PostgreSQL. It provides methods that allow client code to create, open and delete large objects from the database. When opening an object, an instance of `org.postgresql.largeobject.LargeObject` is returned, and its methods then allow access to the object.

This class can only be created by org.postgresql.PGConnection. To get access to this class, use the following segment of code:

```
import org.postgresql.largeobject.*;
Connection  conn;
LargeObjectManager lobj;
// ... code that opens a connection ...
lobj = ((org.postgresql.PGConnection)myconn).getLargeObjectAPI();
```

Normally, client code would use the `BLOB` methods to access large objects. However, sometimes lower level access to Large Objects is required, that is not supported by the JDBC specification.

Refer to org.postgresql.largeobject.LargeObject on how to manipulate the contents of a Large Object.

5.7.3.2.1. Variables

```
public static final int WRITE
```

This mode indicates we want to write to an object.

```
public static final int READ
```

This mode indicates we want to read an object.

```
public static final int READWRITE
```

This mode is the default. It indicates we want read and write access to a large object.

5.7.3.2.2. Methods

- `public LargeObject open(int oid) throws SQLException`

  This opens an existing large object, based on its OID. This method assumes that `READ` and `WRITE` access is required (the default).

- ```
  public LargeObject open(int oid,
                          int mode) throws SQLException
  ```

  This opens an existing large object, based on its OID, and allows setting the access mode.

- `public int create() throws SQLException`

  This creates a large object, returning its OID. It defaults to `READWRITE` for the new object's attributes.

- `public int create(int mode) throws SQLException`

  This creates a large object, returning its OID, and sets the access mode.

- `public void delete(int oid) throws SQLException`

  This deletes a large object.

- `public void unlink(int oid) throws SQLException`

  This deletes a large object. It is identical to the delete method, and is supplied as the C API uses “unlink”.

5.8. Using the driver in a multithreaded or a servlet environment

A problem with many JDBC drivers is that only one thread can use a `Connection` at any one time -- otherwise a thread could send a query while another one is receiving results, and this would be a bad thing for the database engine.

The PostgreSQL JDBC Driver is thread safe. Consequently, if your application uses multiple threads then you do not have to worry about complex algorithms to ensure that only one uses the database at any time.

If a thread attempts to use the connection while another one is using it, it will wait until the other thread has finished its current operation. If it is a regular SQL statement, then the operation consists of sending the statement and retrieving any `ResultSet` (in full). If it is a `Fastpath` call (e.g., reading a block from a `LargeObject`) then it is the time to send and retrieve that block.

This is fine for applications and applets but can cause a performance problem with servlets. With servlets you can have a heavy load on the connection. If you have several threads performing queries then each but one will pause, which may not be what you are after.

To solve this, you would be advised to create a pool of connections. When ever a thread needs to use the database, it asks a manager class for a `Connection`. The manager hands a free connection to the thread and marks it as busy. If a free connection is not available, it opens one. Once the thread has finished with it, it returns it to the manager who can then either close it or add it to the pool. The manager would also check that the connection is still alive and remove it from the pool if it is dead.

So, with servlets, it is up to you to use either a single connection, or a pool. The plus side for a pool is that threads will not be hit by the bottle neck caused by a single network connection. The down side
  ```

is that it increases the load on the server, as a backend process is created for each `Connection`. It is up to you and your applications requirements.

5.9. Connection Pools And DataSources

5.9.1. JDBC, JDK Version Support

JDBC 2 introduced standard connection pooling features in an add-on API known as the JDBC 2.0 Optional Package (also known as the JDBC 2.0 Standard Extension). These features have since been included in the core JDBC 3 API. The PostgreSQL JDBC drivers support these features with JDK 1.3.x in combination with the JDBC 2.0 Optional Package (JDBC 2), or with JDK 1.4+ (JDBC 3). Most application servers include the JDBC 2.0 Optional Package, but it is also available separately from the Sun JDBC download site[2].

5.9.2. JDBC Connection Pooling API

The JDBC API provides a client and a server interface for connection pooling. The client interface is `javax.sql.DataSource`, which is what application code will typically use to acquire a pooled database connection. The server interface is `javax.sql.ConnectionPoolDataSource`, which is how most application servers will interface with the PostgreSQL JDBC driver.

In an application server environment, the application server configuration will typically refer to the PostgreSQL `ConnectionPoolDataSource` implementation, while the application component code will typically acquire a `DataSource` implementation provided by the application server (not by PostgreSQL).

In an environment without an application server, PostgreSQL provides two implementations of `DataSource` which an application can use directly. One implementation performs connection pooling, while the other simply provides access to database connections through the `DataSource` interface without any pooling. Again, these implementations should not be used in an application server environment unless the application server does not support the `ConnectionPoolDataSource` interface.

5.9.3. Application Servers: ConnectionPoolDataSource

PostgreSQL includes one implementation of `ConnectionPoolDataSource` for JDBC 2, and one for JDBC 3:

Table 5.1. ConnectionPoolDataSource Implementations

JDBC	Implementation Class
2	`org.postgresql.jdbc2.optional.ConnectionPool`
3	`org.postgresql.jdbc3.Jdbc3ConnectionPool`

Both implementations use the same configuration scheme. JDBC requires that a `ConnectionPoolDataSource` be configured via JavaBean properties, so there are get and set methods for each of these properties:

Table 5.2. ConnectionPoolDataSource Configuration Properties

Property	Type	Description
serverName	`String`	PostgreSQL database server hostname
databaseName	`String`	PostgreSQL database name

[2] http://java.sun.com/products/jdbc/download.html#spec

Property	Type	Description
portNumber	`int`	TCP/IP port which the PostgreSQL database server is listening on (or 0 to use the default port)
user	`String`	User used to make database connections
password	`String`	Password used to make database connections
defaultAutoCommit	`boolean`	Whether connections should have autoCommit enabled or disabled when they are supplied to the caller. The default is `false`, to disable autoCommit.

Many application servers use a properties-style syntax to configure these properties, so it would not be unusual to enter properties as a block of text.

Example 5.5. `ConnectionPoolDataSource` Configuration Example

If the application server provides a single area to enter all the properties, they might be listed like this:

```
serverName=localhost
databaseName=test
user=testuser
password=testpassword
```

Or, separated by semicolons instead of newlines, like this:

```
serverName=localhost;databaseName=test;user=testuser;password=testpassword
```

5.9.4. Applications: DataSource

PostgreSQL includes two implementations of `DataSource` for JDBC 2, and two for JDBC 3. The pooling implementations do not actually close connections when the client calls the `close` method, but instead return the connections to a pool of available connections for other clients to use. This avoids any overhead of repeatedly opening and closing connections, and allows a large number of clients to share a small number of database connections.

The pooling datasource implementation provided here is not the most feature-rich in the world. Among other things, connections are never closed until the pool itself is closed; there is no way to shrink the pool. As well, connections requested for users other than the default configured user are not pooled. Many application servers provide more advanced pooling features, and use the `ConnectionPoolDataSource` implementation instead.

Table 5.3. DataSource Implementations

JDBC	Pooling	Implementation Class
2	No	`org.postgresql.jdbc2.optional.Simp`
2	Yes	`org.postgresql.jdbc2.optional.Pool`
3	No	`org.postgresql.jdbc3.Jdbc3SimpleDa`
3	Yes	`org.postgresql.jdbc3.Jdbc3PoolingD`

All the implementations use the same configuration scheme. JDBC requires that a `DataSource` be configured via JavaBean properties, so there are get and set methods for each of these properties.

Table 5.4. DataSource Configuration Properties

Property	Type	Description
serverName	`String`	PostgreSQL database server hostname
databaseName	`String`	PostgreSQL database name
portNumber	`int`	TCP/IP port which the PostgreSQL database server is listening on (or 0 to use the default port)
user	`String`	User used to make database connections
password	`String`	Password used to make database connections

The pooling implementations require some additional configuration properties:

Table 5.5. Additional Pooling DataSource Configuration Properties

Property	Type	Description
dataSourceName	`String`	Every pooling `DataSource` must have a unique name
initialConnections	`int`	The number of database connections to be created when the pool is initialized.
maxConnections	`int`	The maximum number of open database connections to allow. When more connections are requested, the caller will hang until a connection is returned to the pool.

Here's an example of typical application code using a pooling `DataSource`:

Example 5.6. `DataSource` Code Example

Code to initialize a pooling DataSource might look like this:

```
Jdbc3PoolingDataSource source = new Jdbc3PoolingDataSource();
source.setDataSourceName("A Data Source");
source.setServerName("localhost");
source.setDatabaseName("test");
source.setUser("testuser");
source.setPassword("testpassword");
source.setMaxConnections(10);
```

Then code to use a connection from the pool might look like this. Note that it is critical that the connections are closed, or else the pool will "leak" connections, and eventually lock all the clients out.

```
Connection con = null;
try {
    con = source.getConnection();
    // use connection
} catch(SQLException e) {
    // log error
} finally {
```

```
    if(con != null) {
        try {con.close();}catch(SQLException e) {}
    }
}
```

5.9.5. DataSources and JNDI

All the `ConnectionPoolDataSource` and `DataSource` implementations can be stored in JNDI. In the case of the non-pooling implementations, a new instance will be created every time the object is retrieved from JNDI, with the same settings as the instance which was stored. For the pooling implementations, the same instance will be retrieved as long as it is available (e.g. not a different JVM retrieving the pool from JNDI), or a new instance with the same settings created otherwise.

In the application server environment, typically the application server's `DataSource` instance will be stored in JNDI, instead of the PostgreSQL `ConnectionPoolDataSource` implementation.

In an application environment, the application may store the `DataSource` in JNDI so that it doesn't have to make a reference to the `DataSource` available to all application components that may need to use it:

Example 5.7. `DataSource` JNDI Code Example

Application code to initialize a pooling DataSource and add it to JNDI might look like this:

```
Jdbc3PoolingDataSource source = new Jdbc3PoolingDataSource();
source.setDataSourceName("A Data Source");
source.setServerName("localhost");
source.setDatabaseName("test");
source.setUser("testuser");
source.setPassword("testpassword");
source.setMaxConnections(10);
new InitialContext().rebind("DataSource", source);
```

Then code to use a connection from the pool might look like this:

```
Connection con = null;
try {
    DataSource source = (DataSource)new
 InitialContext().lookup("DataSource");
    con = source.getConnection();
    // use connection
} catch(SQLException e) {
    // log error
} catch(NamingException e) {
    // DataSource wasn't found in JNDI
} finally {
    if(con != null) {
        try {con.close();}catch(SQLException e) {}
    }
}
```

5.9.6. Specific Application Server Configurations

Configuration examples for specific application servers will be included here.

5.10. Further Reading

If you have not yet read it, I'd advise you read the JDBC API Documentation (supplied with Sun's JDK), and the JDBC Specification. Both are available from http://java.sun.com/products/jdbc/index.html.

http://jdbc.postgresql.org contains updated information not included in this document, and also includes precompiled drivers.

Chapter 6. PyGreSQL - Python Interface

Author

Written by D'Arcy J.M. Cain (<darcy@druid.net>). Based heavily on code written by Pascal Andre <andre@chimay.via.ecp.fr>. Copyright © 1995, Pascal Andre. Further modifications Copyright © 1997-2000 by D'Arcy J.M. Cain.

You may either choose to use the old mature interface provided by the `pg` module or otherwise the newer `pgdb` interface compliant with the DB-API 2.0[1] specification developed by the Python DB-SIG.

Here we describe only the older `pg` API. As long as PyGreSQL does not contain a description of the DB-API you should read about the API at http://www.python.org/topics/database/DatabaseAPI-2.0.html.

A tutorial-like introduction to the DB-API can be found at http://www2.linuxjournal.com/lj-issues/issue49/2605.html

6.1. The pg Module

The `pg` module defines three objects:

- `pgobject`, which handles the connection and all the requests to the database,
- `pglargeobject`, which handles all the accesses to PostgreSQL large objects, and
- `pgqueryobject` that handles query results.

If you want to see a simple example of the use of some of these functions, see http://www.druid.net/rides where you can find a link at the bottom to the actual Python code for the page.

6.1.1. Constants

Some constants are defined in the `pg` module dictionary. They are intended to be used as a parameters for methods calls. You should refer to the libpq description (Chapter 1, *libpq - C Library*) for more information about them. These constants are:

```
INV_READ
INV_WRITE
```

large objects access modes, used by `(pgobject.)locreate` and `(pglarge.)open`.

```
SEEK_SET
SEEK_CUR
SEEK_END
```

positional flags, used by `(pglarge.)seek`.

```
version
__version__
```

constants that give the current version

[1] http://www.python.org/topics/database/DatabaseAPI-2.0.html

6.2. pg Module Functions

pg module defines only a few methods that allow to connect to a database and to define “default variables” that override the environment variables used by PostgreSQL.

These “default variables” were designed to allow you to handle general connection parameters without heavy code in your programs. You can prompt the user for a value, put it in the default variable, and forget it, without having to modify your environment. The support for default variables can be disabled by setting the -DNO_DEF_VAR option in the Python Setup file. Methods relative to this are specified by the tag [DV].

All variables are set to None at module initialization, specifying that standard environment variables should be used.

Name

connect — open a connection to the database server

Synopsis

```
connect([dbname], [host], [port], [opt], [tty], [user], [passwd])
```

Parameters

dbname

Name of connected database (string/None).

host

Name of the server host (string/None).

port

Port used by the database server (integer/-1).

opt

Options for the server (string/None).

tty

File or tty for optional debug output from backend (string/None).

user

PostgreSQL user (string/None).

passwd

Password for user (string/None).

Return Type

pgobject

If successful, an object handling a database connection is returned.

Exceptions

TypeError

Bad argument type, or too many arguments.

SyntaxError

Duplicate argument definition.

pg.error

Some error occurred during pg connection definition.

(plus all exceptions relative to object allocation)

Description

This method opens a connection to a specified database on a given PostgreSQL server. You can use key words here, as described in the Python tutorial. The names of the key words are the name of the

parameters given in the syntax line. For a precise description of the parameters, please refer to the PostgreSQL user manual.

Examples

```
import pg

con1 = pg.connect('testdb', 'myhost', 5432, None, None, 'bob',
 None)
con2 = pg.connect(dbname='testdb', host='localhost', user='bob')
```

Name

get_defhost — get default host name [DV]

Synopsis

```
get_defhost()
```

Parameters

none

Return Type

string or `None`

Default host specification

Exceptions

`SyntaxError`

Too many arguments.

Description

`get_defhost()` returns the current default host specification, or `None` if the environment variables should be used. Environment variables will not be looked up.

Name

set_defhost — set default host name [DV]

Synopsis

```
set_defhost(host)
```

Parameters

host

New default host (string/None).

Return Type

string or None

Previous default host specification.

Exceptions

TypeError

Bad argument type, or too many arguments.

Description

set_defhost() sets the default host value for new connections. If None is supplied as parameter, environment variables will be used in future connections. It returns the previous setting for default host.

Name

get_defport — get default port [DV]

Synopsis

```
get_defport()
```

Parameters

none

Return Type

integer or `None`

Default port specification

Exceptions

`SyntaxError`

Too many arguments.

Description

`get_defport()` returns the current default port specification, or `None` if the environment variables should be used. Environment variables will not be looked up.

Name

set_defport — set default port [DV]

Synopsis

```
set_defport(port)
```

Parameters

port

New default host (integer/-1).

Return Type

integer or `None`

Previous default port specification.

Exceptions

`TypeError`

Bad argument type, or too many arguments.

Description

`set_defport()` sets the default port value for new connections. If -1 is supplied as parameter, environment variables will be used in future connections. It returns the previous setting for default port.

Name

get_defopt — get default options specification [DV]

Synopsis

```
get_defopt()
```

Parameters

none

Return Type

string or `None`

Default options specification

Exceptions

`SyntaxError`

Too many arguments.

Description

`get_defopt()` returns the current default connection options specification, or `None` if the environment variables should be used. Environment variables will not be looked up.

Name

set_defopt — set default options specification [DV]

Synopsis

`set_defopt(`*`options`*`)`

Parameters

`options`

New default connection options (string/`None`).

Return Type

string or `None`

Previous default opt specification.

Exceptions

`TypeError`

Bad argument type, or too many arguments.

Description

`set_defopt()` sets the default connection options value for new connections. If `None` is supplied as parameter, environment variables will be used in future connections. It returns the previous setting for default options.

Name

get_deftty — get default connection debug terminal specification [DV]

Synopsis

```
get_deftty()
```

Parameters

none

Return Type

string or `None`

Default debug terminal specification

Exceptions

`SyntaxError`

Too many arguments.

Description

`get_deftty()` returns the current default debug terminal specification, or `None` if the environment variables should be used. Environment variables will not be looked up.

Name

set_deftty — set default connection debug terminal specification [DV]

Synopsis

```
set_deftty(terminal)
```

Parameters

terminal

New default debug terminal (string/`None`).

Return Type

string or `None`

Previous default debug terminal specification.

Exceptions

`TypeError`

Bad argument type, or too many arguments.

Description

`set_deftty()` sets the default terminal value for new connections. If `None` is supplied as parameter, environment variables will be used in future connections. It returns the previous setting for default terminal.

Name

get_defbase — get default database name specification [DV]

Synopsis

```
get_defbase()
```

Parameters

none

Return Type

string or `None`

Default debug database name specification

Exceptions

`SyntaxError`

Too many arguments.

Description

`get_defbase()` returns the current default database name specification, or `None` if the environment variables should be used. Environment variables will not be looked up.

Name

set_defbase — set default database name specification [DV]

Synopsis

`set_defbase(`*`database`*`)`

Parameters

`database`

New default database name (string/`None`).

Return Type

string or `None`

Previous default database name specification.

Exceptions

`TypeError`

Bad argument type, or too many arguments.

Description

`set_defbase()` sets the default database name for new connections. If `None` is supplied as parameter, environment variables will be used in future connections. It returns the previous setting for default database name.

6.3. Connection Object: `pgobject`

This object handles a connection to the PostgreSQL database. It embeds and hides all the parameters that define this connection, leaving just really significant parameters in function calls.

Some methods give direct access to the connection socket. They are specified by the tag [DA]. *Do not use them unless you really know what you are doing.* If you prefer disabling them, set the `-DNO_DIRECT` option in the Python `Setup` file.

Some other methods give access to large objects. if you want to forbid access to these from the module, set the `-DNO_LARGE` option in the Python `Setup` file. These methods are specified by the tag [LO].

Every `pgobject` defines a set of read-only attributes that describe the connection and its status. These attributes are:

host

the host name of the server (string)

port

the port of the server (integer)

db

the selected database (string)

options

the connection options (string)

tty

the connection debug terminal (string)

user

user name on the database system (string)

status

the status of the connection (integer: 1 - OK, 0 - bad)

error

the last warning/error message from the server (string)

Name

query — execute a SQL command

Synopsis

`query(`*`command`*`)`

Parameters

`command`

SQL command (string).

Return Type

`pgqueryobject` or `None`

Result values.

Exceptions

`TypeError`

Bad argument type, or too many arguments.

`ValueError`

Empty SQL query.

`pg.error`

Error during query processing, or invalid connection.

Description

`query()` method sends a SQL query to the database. If the query is an insert statement, the return value is the OID of the newly inserted row. If it is otherwise a query that does not return a result (i.e., is not a some kind of `SELECT` statement), it returns `None`. Otherwise, it returns a `pgqueryobject` that can be accessed via the `getresult()` or `dictresult()` methods or simply printed.

Name

reset — reset the connection

Synopsis

```
reset()
```

Parameters

none

Return Type

none

Exceptions

`TypeError`

Too many (any) arguments.

Description

`reset()` method resets the current database.

Name

close — close the database connection

Synopsis

```
close()
```

Parameters

none

Return Type

none

Exceptions

`TypeError`

Too many (any) arguments.

Description

`close()` method closes the database connection. The connection will be closed in any case when the connection is deleted but this allows you to explicitly close it. It is mainly here to allow the DB-SIG API wrapper to implement a close function.

Name

fileno — return the socket used to connect to the database

Synopsis

```
fileno()
```

Parameters

none

Return Type

socket id

The underlying socket id used to connect to the database.

Exceptions

`TypeError`

Too many (any) arguments.

Description

`fileno()` method returns the underlying socket id used to connect to the database. This is useful for use in `select` calls, etc.

Name

getnotify — get the last notify from the server

Synopsis

```
getnotify()
```

Parameters

none

Return Type

tuple, `None`

Last notify from server

Exceptions

`TypeError`

Too many (any) arguments.

`pg.error`

Invalid connection.

Description

`getnotify()` method tries to get a notify from the server (from the SQL statement `NOTIFY`). If the server returns no notify, the methods returns `None`. Otherwise, it returns a tuple (couple) `(relname, pid)`, where `relname` is the name of the notify and `pid` the process id of the connection that triggered the notify. Remember to do a listen query first otherwise `getnotify` will always return `None`.

Name

inserttable — insert a list into a table

Synopsis

`inserttable(`*`table`*`, `*`values`*`)`

Parameters

`table`

The table name (string).

`values`

The list of rows values to insert (list).

Return Type

none

Exceptions

`TypeError`

Bad argument type or too many (any) arguments.

`pg.error`

Invalid connection.

Description

`inserttable()` method allows to quickly insert large blocks of data in a table: it inserts the whole values list into the given table. The list is a list of tuples/lists that define the values for each inserted row. The rows values may contain string, integer, long or double (real) values. *Be very careful:* this method does not type-check the fields according to the table definition; it just look whether or not it knows how to handle such types.

Name

putline — write a line to the server socket [DA]

Synopsis

```
putline(line)
```

Parameters

line

Line to be written (string).

Return Type

none

Exceptions

`TypeError`

Bad argument type or too many (any) arguments.

`pg.error`

Invalid connection.

Description

`putline()` method allows to directly write a string to the server socket.

Name

getline — get a line from server socket [DA]

Synopsis

```
getline()
```

Parameters

none

Return Type

string

The line read.

Exceptions

`TypeError`

Bad argument type or too many (any) arguments.

`pg.error`

Invalid connection.

Description

`getline()` method allows to directly read a string from the server socket.

Name

endcopy — synchronize client and server [DA]

Synopsis

```
endcopy()
```

Parameters

none

Return Type

none

Exceptions

`TypeError`

Bad argument type or too many (any) arguments.

`pg.error`

Invalid connection.

Description

The use of direct access methods may desynchronize client and server. This method ensure that client and server will be synchronized.

Name

locreate — create a large object in the database [LO]

Synopsis

`locreate(`*`mode`*`)`

Parameters

`mode`

Large object create mode.

Return Type

`pglarge`

Object handling the PostgreSQL large object.

Exceptions

`TypeError`

Bad argument type or too many arguments.

`pg.error`

Invalid connection, or creation error.

Description

`locreate()` method creates a large object in the database. The mode can be defined by OR-ing the constants defined in the pg module (`INV_READ` and `INV_WRITE`).

Name

getlo — build a large object from given OID [LO]

Synopsis

`getlo(`*`oid`*`)`

Parameters

`oid`

OID of the existing large object (integer).

Return Type

`pglarge`

Object handling the PostgreSQL large object.

Exceptions

`TypeError`

Bad argument type or too many arguments.

`pg.error`

Invalid connection.

Description

`getlo()` method allows to reuse a formerly created large object through the `pglarge` interface, providing the user has its OID.

Name

loimport — import a file to a PostgreSQL large object [LO]

Synopsis

`loimport(`*`filename`*`)`

Parameters

`filename`

The name of the file to be imported (string).

Return Type

`pglarge`

Object handling the PostgreSQL large object.

Exceptions

`TypeError`

Bad argument type or too many arguments.

`pg.error`

Invalid connection, or error during file import.

Description

`loimport()` method allows to create large objects in a very simple way. You just give the name of a file containing the data to be use.

6.4. Database Wrapper Class: `DB`

`pg` module contains a class called `DB`. All `pgobject` methods are included in this class also. A number of additional `DB` class methods are described below. The preferred way to use this module is as follows (See description of the initialization method below.):

```
import pg

db = pg.DB(...)

for r in db.query(
    "SELECT foo,bar
       FROM foo_bar_table
      WHERE foo !~ bar"
    ).dictresult():

    print '%(foo)s %(bar)s' % r
```

The following describes the methods and variables of this class.

The `DB` class is initialized with the same arguments as the `pg.connect` method. It also initializes a few internal variables. The statement `db = DB()` will open the local database with the name of the user just like `pg.connect()` does.

Name

pkey — return the primary key of a table

Synopsis

`pkey(`*`table`*`)`

Parameters

`table`

name of table.

Return Type

string

Name of field which is the primary key of the table.

Description

`pkey()` method returns the primary key of a table. Note that this raises an exception if the table does not have a primary key.

Name

get_databases — get list of databases in the system

Synopsis

```
get_databases()
```

Parameters

none

Return Type

list

List of databases in the system.

Description

Although you can do this with a simple select, it is added here for convenience

Name

get_tables — get list of tables in connected database

Synopsis

```
get_tables()
```

Parameters

none

Return Type

list

List of tables in connected database.

Description

Although you can do this with a simple select, it is added here for convenience

Name

get_attnames — return the attribute names of a table

Synopsis

```
get_attnames(table)
```

Parameters

table

name of table.

Return Type

dictionary

The dictionary's keys are the attribute names, the values are the type names of the attributes.

Description

Given the name of a table, digs out the set of attribute names and types.

Name

get — get a tuple from a database table

Synopsis

```
get(table, arg, [keyname])
```

Parameters

table

Name of table.

arg

Either a dictionary or the value to be looked up.

[*keyname*]

Name of field to use as key (optional).

Return Type

dictionary

A dictionary mapping attribute names to row values.

Description

This method is the basic mechanism to get a single row. It assumes that the key specifies a unique row. If *keyname* is not specified then the primary key for the table is used. If *arg* is a dictionary then the value for the key is taken from it and it is modified to include the new values, replacing existing values where necessary. The OID is also put into the dictionary but in order to allow the caller to work with multiple tables, the attribute name is munged to make it unique. It consists of the string `oid_` followed by the name of the table.

Name

insert — insert a tuple into a database table

Synopsis

```
insert(table, a)
```

Parameters

table

Name of table.

a

A dictionary of values.

Return Type

integer

The OID of the newly inserted row.

Description

This method inserts values into the table specified filling in the values from the dictionary. It then reloads the dictionary with the values from the database. This causes the dictionary to be updated with values that are modified by rules, triggers, etc.

Due to the way that this function works you will find inserts taking longer and longer as your table gets bigger. To overcome this problem simply add an index onto the OID of any table that you think may get large over time.

Name

update — update a database table

Synopsis

```
update(table, a)
```

Parameters

table

Name of table.

a

A dictionary of values.

Return Type

integer

The OID of the newly updated row.

Description

Similar to insert but updates an existing row. The update is based on the OID value as munged by get. The array returned is the one sent modified to reflect any changes caused by the update due to triggers, rules, defaults, etc.

Name

clear — clear a database table

Synopsis

```
clear(table, [a])
```

Parameters

table

Name of table.

[*a*]

A dictionary of values.

Return Type

dictionary

A dictionary with an empty row.

Description

This method clears all the attributes to values determined by the types. Numeric types are set to 0, dates are set to `'today'` and everything else is set to the empty string. If the array argument is present, it is used as the array and any entries matching attribute names are cleared with everything else left unchanged.

Name

delete — delete a row from a table

Synopsis

```
delete(table, [a])
```

Parameters

table

Name of table.

[*a*]

A dictionary of values.

Return Type

none

Description

This method deletes the row from a table. It deletes based on the OID as munged as described above.

6.5. Query Result Object: `pgqueryobject`

Name

getresult — get the values returned by the query

Synopsis

```
getresult()
```

Parameters

none

Return Type

list

List of tuples.

Exceptions

`SyntaxError`

Too many arguments.

`pg.error`

Invalid previous result.

Description

`getresult()` method returns the list of the values returned by the query. More information about this result may be accessed using `listfields`, `fieldname` and `fieldnum` methods.

Name

dictresult — get the values returned by the query as a list of dictionaries

Synopsis

```
dictresult()
```

Parameters

none

Return Type

list

List of dictionaries.

Exceptions

`SyntaxError`

Too many arguments.

`pg.error`

Invalid previous result.

Description

`dictresult()` method returns the list of the values returned by the query with each tuple returned as a dictionary with the field names used as the dictionary index.

Name

listfields — list the fields names of the query result

Synopsis

```
listfields()
```

Parameters

none

Return Type

list

field names

Exceptions

`SyntaxError`

Too many arguments.

`pg.error`

Invalid query result, or invalid connection.

Description

`listfields()` method returns the list of field names defined for the query result. The fields are in the same order as the result values.

Name

fieldname — get field name by number

Synopsis

```
fieldname(i)
```

Parameters

i

field number (integer).

Return Type

string

field name.

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`ValueError`

Invalid field number.

`pg.error`

Invalid query result, or invalid connection.

Description

`fieldname()` method allows to find a field name from its rank number. It can be useful for displaying a result. The fields are in the same order than the result values.

Name

fieldnum — get field number by name

Synopsis

`fieldnum(`*`name`*`)`

Parameters

`name`

field name (string).

Return Type

integer

field number (integer).

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`ValueError`

Unknown field name.

`pg.error`

Invalid query result, or invalid connection.

Description

`fieldnum()` method returns a field number from its name. It can be used to build a function that converts result list strings to their correct type, using a hardcoded table definition. The number returned is the field rank in the result values list.

Name

ntuples — return the number of tuples in query object

Synopsis

```
ntuples()
```

Parameters

none

Return Type

integer

The number of tuples in query object.

Exceptions

`SyntaxError`

Too many arguments.

Description

`ntuples()` method returns the number of tuples found in a query.

6.6. Large Object: `pglarge`

This object handles all the request concerning a PostgreSQL large object. It embeds and hides all the "recurrent" variables (object OID and connection), exactly in the same way `pgobject`s do, thus only keeping significant parameters in function calls. It keeps a reference to the `pgobject` used for its creation, sending requests though with its parameters. Any modification but dereferencing the `pgobject` will thus affect the `pglarge` object. Dereferencing the initial `pgobject` is not a problem since Python will not deallocate it before the large object dereference it. All functions return a generic error message on call error, whatever the exact error was. The `error` attribute of the object allows to get the exact error message.

`pglarge` objects define a read-only set of attributes that allow to get some information about it. These attributes are:

`oid`

the OID associated with the object

`pgcnx`

the `pgobject` associated with the object

`error`

the last warning/error message of the connection

Important

In multithreaded environments, `error` may be modified by another thread using the same `pgobject`. Remember that these object are shared, not duplicated; you should provide some locking if you want to check for the error message in this situation. The OID attribute is very

interesting because it allow you to reuse the OID later, creating the `pglarge` object with a `pgobject` `getlo()` method call.

See also Chapter 2, *Large Objects* for more information about the PostgreSQL large object interface.

Name

open — open a large object

Synopsis

`open(`*`mode`*`)`

Parameters

`mode`

open mode definition (integer).

Return Type

none

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`IOError`

Already opened object, or open error.

`pg.error`

Invalid connection.

Description

`open()` method opens a large object for reading/writing, in the same way than the Unix `open()` function. The mode value can be obtained by OR-ing the constants defined in the pg module (`INV_READ`, `INV_WRITE`).

Name

close — close the large object

Synopsis

```
close()
```

Parameters

none

Return Type

none

Exceptions

`SyntaxError`

Too many arguments.

`IOError`

Object is not opened, or close error.

`pg.error`

Invalid connection.

Description

`close()` method closes previously opened large object, in the same way than the Unix `close()` function.

Name

read — read from the large object

Synopsis

`read(size)`

Parameters

size

Maximal size of the buffer to be read (integer).

Return Type

string

The read buffer.

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`IOError`

Object is not opened, or read error.

`pg.error`

Invalid connection or invalid object.

Description

`read()` method allows to read data from the large object, starting at current position.

Name

write — write to the large object

Synopsis

`write(`*`string`*`)`

Parameters

`string`

Buffer to be written (string).

Return Type

none

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`IOError`

Object is not opened, or write error.

`pg.error`

Invalid connection or invalid object.

Description

`write()` method allows to write data to the large object, starting at current position.

Name

seek — change current position in the large object

Synopsis

`seek(`*`offset, whence`*`)`

Parameters

`offset`

Position offset (integer).

`whence`

Positional parameter (integer).

Return Type

integer

New current position in the object.

Exceptions

`TypeError`

Bad parameter type, or too many arguments.

`IOError`

Object is not opened, or seek error.

`pg.error`

Invalid connection or invalid object.

Description

`seek()` method allows to move the cursor position in the large object. The whence parameter can be obtained by OR-ing the constants defined in the `pg` module (`SEEK_SET`, `SEEK_CUR`, `SEEK_END`).

Name

tell — return current position in the large object

Synopsis

```
tell()
```

Parameters

none

Return Type

integer

Current position in the object.

Exceptions

`SyntaxError`

Too many arguments.

`IOError`

Object is not opened, or seek error.

`pg.error`

Invalid connection or invalid object.

Description

`tell()` method allows to get the current position in the large object.

Name

unlink — delete the large object

Synopsis

```
unlink()
```

Parameters

none

Return Type

none

Exceptions

`SyntaxError`

Too many arguments.

`IOError`

Object is not closed, or unlink error.

`pg.error`

Invalid connection or invalid object.

Description

`unlink()` method unlinks (deletes) the large object.

Name

size — return the large object size

Synopsis

```
size()
```

Parameters

none

Return Type

integer

The large object size.

Exceptions

`SyntaxError`

Too many arguments.

`IOError`

Object is not opened, or seek/tell error.

`pg.error`

Invalid connection or invalid object.

Description

`size()` method allows to get the size of the large object. It was implemented because this function is very useful for a WWW-interfaced database. Currently, the large object needs to be opened first.

Name

export — save the large object to file

Synopsis

`export(`*`filename`*`)`

Parameters

`filename`

The file to be created.

Return Type

none

Exceptions

`TypeError`

Bad argument type, or too many arguments.

`IOError`

Object is not closed, or export error.

`pg.error`

Invalid connection or invalid object.

Description

`export()` method allows to dump the content of a large object in a very simple way. The exported file is created on the host of the program, not the server host.

Part II. Server Programming

This second part of the manual explains the PostgreSQL approach to extensibility and describe how users can extend PostgreSQL by adding user-defined types, operators, aggregates, and both query language and programming language functions. After a discussion of the PostgreSQL rule system, we discuss the trigger and SPI interfaces.

Table of Contents

7. Architecture 162
    7.1. PostgreSQL Architectural Concepts 162
8. Extending SQL: An Overview 165
    8.1. How Extensibility Works 165
    8.2. The PostgreSQL Type System 165
    8.3. About the PostgreSQL System Catalogs 165
9. Extending SQL: Functions 168
    9.1. Introduction 168
    9.2. Query Language (SQL) Functions 168
        9.2.1. Examples 168
        9.2.2. SQL Functions on Base Types 169
        9.2.3. SQL Functions on Composite Types 170
        9.2.4. SQL Table Functions 171
        9.2.5. SQL Functions Returning Sets 172
    9.3. Procedural Language Functions 173
    9.4. Internal Functions 173
    9.5. C Language Functions 173
        9.5.1. Dynamic Loading 174
        9.5.2. Base Types in C-Language Functions 175
        9.5.3. Version-0 Calling Conventions for C-Language Functions 177
        9.5.4. Version-1 Calling Conventions for C-Language Functions 179
        9.5.5. Composite Types in C-Language Functions 181
        9.5.6. Table Function API 182
        9.5.7. Writing Code 188
        9.5.8. Compiling and Linking Dynamically-Loaded Functions 189
    9.6. Function Overloading 191
    9.7. Table Functions 192
    9.8. Procedural Language Handlers 193
10. Extending SQL: Types 196
11. Extending SQL: Operators 198
    11.1. Introduction 198
    11.2. Example 198
    11.3. Operator Optimization Information 198
        11.3.1. COMMUTATOR 199
        11.3.2. NEGATOR 199
        11.3.3. RESTRICT 200
        11.3.4. JOIN 200
        11.3.5. HASHES 201
        11.3.6. MERGES (SORT1, SORT2, LTCMP, GTCMP) 201
12. Extending SQL: Aggregates 203
13. The Rule System 205
    13.1. Introduction 205
    13.2. What is a Query Tree? 205
        13.2.1. The Parts of a Query tree 205
    13.3. Views and the Rule System 207
        13.3.1. Implementation of Views in PostgreSQL 207
        13.3.2. How SELECT Rules Work 207
        13.3.3. View Rules in Non-SELECT Statements 212
        13.3.4. The Power of Views in PostgreSQL 213
        13.3.5. What about updating a view? 213
    13.4. Rules on INSERT, UPDATE and DELETE 213
        13.4.1. Differences from View Rules 213
        13.4.2. How These Rules Work 214
        13.4.3. Cooperation with Views 218
    13.5. Rules and Permissions 223

13.6. Rules and Command Status 224
13.7. Rules versus Triggers 224
14. Interfacing Extensions To Indexes 227
14.1. Introduction 227
14.2. Access Methods and Operator Classes 227
14.3. Access Method Strategies 227
14.4. Access Method Support Routines 228
14.5. Creating the Operators and Support Routines 229
14.6. Creating the Operator Class 231
14.7. Special Features of Operator Classes 231
15. Index Cost Estimation Functions 233
16. Triggers 236
16.1. Trigger Definition 236
16.2. Interaction with the Trigger Manager 237
16.3. Visibility of Data Changes 239
16.4. Examples 240
17. Server Programming Interface 243
17.1. Interface Functions 243
17.2. Interface Support Functions 256
17.3. Memory Management 263
17.4. Visibility of Data Changes 274
17.5. Examples 274

Chapter 7. Architecture

7.1. PostgreSQL Architectural Concepts

Before we begin, you should understand the basic PostgreSQL system architecture. Understanding how the parts of PostgreSQL interact will make the next chapter somewhat clearer. In database jargon, PostgreSQL uses a simple "process per-user" client/server model. A PostgreSQL session consists of the following cooperating Unix processes (programs):

- A supervisory daemon process (the postmaster),
- the user's frontend application (e.g., the psql program), and
- one or more backend database servers (the postgres process itself).

A single postmaster manages a given collection of databases on a single host. Such a collection of databases is called a cluster (of databases). A frontend application that wishes to access a given database within a cluster makes calls to an interface library (e.g., libpq) that is linked into the application. The library sends user requests over the network to the postmaster (Figure 7.1, “How a connection is established”(a)), which in turn starts a new backend server process (Figure 7.1, “How a connection is established”(b))



(a) frontend sends request to postmaster via well-known network socket



(b) postmaster creates backend server



(c) frontend connected to backend server

And multiple connections can be established...



(d) frontend connected to multiple backend servers

and connects the frontend process to the new server (Figure 7.1, “How a connection is established”(c)). From that point on, the frontend process and the backend server communicate without intervention by the postmaster. Hence, the postmaster is always running, waiting for connection requests, whereas frontend and backend processes come and go. The `libpq` library allows a single frontend to make multiple connections to backend processes. However, each backend process is a single-threaded process that can only execute one query at a time; so the communication over any one frontend-to-backend connection is single-threaded.

One implication of this architecture is that the postmaster and the backend always run on the same machine (the database server), while the frontend application may run anywhere. You should keep this in mind, because the files that can be accessed on a client machine may not be accessible (or may only be accessed using a different path name) on the database server machine.

You should also be aware that the postmaster and postgres servers run with the user ID of the PostgreSQL “superuser”. Note that the PostgreSQL superuser does not have to be any particular user (e.g., a user named `postgres`), although many systems are installed that way. Furthermore, the PostgreSQL superuser should definitely not be the Unix superuser, `root`! It is safest if the PostgreSQL superuser is an ordinary, unprivileged user so far as the surrounding Unix system is concerned. In any case, all files relating to a database should belong to this Postgres superuser.

Chapter 8. Extending SQL: An Overview

In the sections that follow, we will discuss how you can extend the PostgreSQL SQL query language by adding:

- functions
- data types
- operators
- aggregates

8.1. How Extensibility Works

PostgreSQL is extensible because its operation is catalog-driven. If you are familiar with standard relational systems, you know that they store information about databases, tables, columns, etc., in what are commonly known as system catalogs. (Some systems call this the data dictionary). The catalogs appear to the user as tables like any other, but the DBMS stores its internal bookkeeping in them. One key difference between PostgreSQL and standard relational systems is that PostgreSQL stores much more information in its catalogs -- not only information about tables and columns, but also information about its types, functions, access methods, and so on. These tables can be modified by the user, and since PostgreSQL bases its internal operation on these tables, this means that PostgreSQL can be extended by users. By comparison, conventional database systems can only be extended by changing hardcoded procedures within the DBMS or by loading modules specially written by the DBMS vendor.

PostgreSQL is also unlike most other data managers in that the server can incorporate user-written code into itself through dynamic loading. That is, the user can specify an object code file (e.g., a shared library) that implements a new type or function and PostgreSQL will load it as required. Code written in SQL is even more trivial to add to the server. This ability to modify its operation “on the fly” makes PostgreSQL uniquely suited for rapid prototyping of new applications and storage structures.

8.2. The PostgreSQL Type System

The PostgreSQL type system can be broken down in several ways. Types are divided into base types and composite types. Base types are those, like `int4`, that are implemented in a language such as C. They generally correspond to what are often known as *abstract data types*; PostgreSQL can only operate on such types through methods provided by the user and only understands the behavior of such types to the extent that the user describes them. Composite types are created whenever the user creates a table.

PostgreSQL stores these types in only one way (within the file that stores all rows of a table) but the user can “look inside” at the attributes of these types from the query language and optimize their retrieval by (for example) defining indexes on the attributes. PostgreSQL base types are further divided into built-in types and user-defined types. Built-in types (like `int4`) are those that are compiled into the system. User-defined types are those created by the user in the manner to be described later.

8.3. About the PostgreSQL System Catalogs

Having introduced the basic extensibility concepts, we can now take a look at how the catalogs are actually laid out. You can skip this section for now, but some later sections will be incomprehensible without the information given here, so mark this page for later reference. All system catalogs have names that begin with `pg_`. The following tables contain information that may be useful to the end user. (There are many other system catalogs, but there should rarely be a reason to query them directly.)

Table 8.1. PostgreSQL System Catalogs

Catalog Name	Description
pg_database	databases
pg_class	tables
pg_attribute	table columns
pg_index	indexes
pg_proc	procedures/functions
pg_type	data types (both base and complex)
pg_operator	operators
pg_aggregate	aggregate functions
pg_am	access methods
pg_amop	access method operators
pg_amproc	access method support functions
pg_opclass	access method operator classes

Figure 8.1. The major PostgreSQL system catalogs



Figure 3. The major POSTGRES system catalogs.

The *Developer's Guide* gives a more detailed explanation of these catalogs and their columns. However, Figure 8.1, “The major PostgreSQL system catalogs” shows the major entities and their relationships in the system catalogs. (Columns that do not refer to other entities are not shown unless they are part of a primary key.) This diagram is more or less incomprehensible until you actually start looking at the contents of the catalogs and see how they relate to each other. For now, the main things to take away from this diagram are as follows:

- In several of the sections that follow, we will present various join queries on the system catalogs that display information we need to extend the system. Looking at this diagram should make some of these join queries (which are often three- or four-way joins) more understandable, because you will be able to see that the columns used in the queries form foreign keys in other tables.
- Many different features (tables, columns, functions, types, access methods, etc.) are tightly integrated in this schema. A simple create command may modify many of these catalogs.
- Types and procedures are central to the schema.

  ## Note

  We use the words *procedure* and *function* more or less interchangeably.

  Nearly every catalog contains some reference to rows in one or both of these tables. For example, PostgreSQL frequently uses type signatures (e.g., of functions and operators) to identify unique rows of other catalogs.
- There are many columns and relationships that have obvious meanings, but there are many (particularly those that have to do with access methods) that do not.

Chapter 9. Extending SQL: Functions

9.1. Introduction

PostgreSQL provides four kinds of functions:

- query language functions (functions written in SQL)
- procedural language functions (functions written in, for example, PL/Tcl or PL/pgSQL)
- internal functions
- C language functions

Every kind of function can take a base type, a composite type, or some combination as arguments (parameters). In addition, every kind of function can return a base type or a composite type. It's easiest to define SQL functions, so we'll start with those. Examples in this section can also be found in `funcs.sql` and `funcs.c` in the tutorial directory.

Throughout this chapter, it can be useful to look at the reference page of the `CREATE FUNCTION` command to understand the examples better.

9.2. Query Language (SQL) Functions

SQL functions execute an arbitrary list of SQL statements, returning the result of the last query in the list, which must be a `SELECT`. In the simple (non-set) case, the first row of the last query's result will be returned. (Bear in mind that "the first row" of a multirow result is not well-defined unless you use `ORDER BY`.) If the last query happens to return no rows at all, NULL will be returned.

Alternatively, an SQL function may be declared to return a set, by specifying the function's return type as `SETOF` *`sometype`*. In this case all rows of the last query's result are returned. Further details appear below.

The body of an SQL function should be a list of one or more SQL statements separated by semicolons. Note that because the syntax of the `CREATE FUNCTION` command requires the body of the function to be enclosed in single quotes, single quote marks (`'`) used in the body of the function must be escaped, by writing two single quotes (`''`) or a backslash (`\'`) where each quote is desired.

Arguments to the SQL function may be referenced in the function body using the syntax `$`*`n`*: $1 refers to the first argument, $2 to the second, and so on. If an argument is of a composite type, then the "dot notation", e.g., `$1.emp`, may be used to access attributes of the argument.

9.2.1. Examples

To illustrate a simple SQL function, consider the following, which might be used to debit a bank account:

```
CREATE FUNCTION tp1 (integer, numeric) RETURNS integer AS '
    UPDATE bank
        SET balance = balance - $2
        WHERE accountno = $1;
    SELECT 1;
' LANGUAGE SQL;
```

A user could execute this function to debit account 17 by $100.00 as follows:

```
SELECT tp1(17, 100.0);
```

In practice one would probably like a more useful result from the function than a constant "1", so a more likely definition is

```
CREATE FUNCTION tp1 (integer, numeric) RETURNS numeric AS '
    UPDATE bank
        SET balance = balance - $2
        WHERE accountno = $1;
    SELECT balance FROM bank WHERE accountno = $1;
' LANGUAGE SQL;
```

which adjusts the balance and returns the new balance.

Any collection of commands in the SQL language can be packaged together and defined as a function. The commands can include data modification (i.e., `INSERT`, `UPDATE`, and `DELETE`) as well as `SELECT` queries. However, the final command must be a `SELECT` that returns whatever is specified as the function's return type. Alternatively, if you want to define a SQL function that performs actions but has no useful value to return, you can define it as returning `void`. In that case it must not end with a `SELECT`. For example:

```
CREATE FUNCTION clean_EMP () RETURNS void AS '
    DELETE FROM EMP
        WHERE EMP.salary <= 0;
' LANGUAGE SQL;

SELECT clean_EMP();

 clean_emp
-----------

(1 row)
```

9.2.2. SQL Functions on Base Types

The simplest possible SQL function has no arguments and simply returns a base type, such as `integer`:

```
CREATE FUNCTION one() RETURNS integer AS '
    SELECT 1 as RESULT;
' LANGUAGE SQL;

SELECT one();

 one
-----
   1
```

Notice that we defined a column alias within the function body for the result of the function (with the name `RESULT`), but this column alias is not visible outside the function. Hence, the result is labeled `one` instead of `RESULT`.

It is almost as easy to define SQL functions that take base types as arguments. In the example below, notice how we refer to the arguments within the function as `$1` and `$2`:

```
CREATE FUNCTION add_em(integer, integer) RETURNS integer AS '
    SELECT $1 + $2;
' LANGUAGE SQL;

SELECT add_em(1, 2) AS answer;

 answer
--------
      3
```

9.2.3. SQL Functions on Composite Types

When specifying functions with arguments of composite types, we must not only specify which argument we want (as we did above with `$1` and `$2`) but also the attributes of that argument. For example, suppose that `EMP` is a table containing employee data, and therefore also the name of the composite type of each row of the table. Here is a function `double_salary` that computes what your salary would be if it were doubled:

```
CREATE FUNCTION double_salary(EMP) RETURNS integer AS '
    SELECT $1.salary * 2 AS salary;
' LANGUAGE SQL;

SELECT name, double_salary(EMP) AS dream
    FROM EMP
    WHERE EMP.cubicle ~= point '(2,1)';

 name | dream
------+-------
 Sam  |  2400
```

Notice the use of the syntax `$1.salary` to select one field of the argument row value. Also notice how the calling `SELECT` command uses a table name to denote the entire current row of that table as a composite value.

It is also possible to build a function that returns a composite type. This is an example of a function that returns a single `EMP` row:

```
CREATE FUNCTION new_emp() RETURNS EMP AS '
    SELECT text ''None'' AS name,
        1000 AS salary,
        25 AS age,
        point ''(2,2)'' AS cubicle;
' LANGUAGE SQL;
```

In this case we have specified each of the attributes with a constant value, but any computation or expression could have been substituted for these constants. Note two important things about defining the function:

- The target list order must be exactly the same as that in which the columns appear in the table associated with the composite type. (Naming the columns, as we did above, is irrelevant to the system.)
- You must typecast the expressions to match the definition of the composite type, or you will get errors like this:

  ```
  ERROR:  function declared to return emp returns varchar instead
   of text at column 1
  ```

A function that returns a row (composite type) can be used as a table function, as described below. It can also be called in the context of an SQL expression, but only when you extract a single attribute out of the row or pass the entire row into another function that accepts the same composite type. For example,

```
SELECT (new_emp()).name;

 name
------
 None
```

We need the extra parentheses to keep the parser from getting confused:

```
SELECT new_emp().name;
```

```
ERROR:  parser: parse error at or near "."
```

Another option is to use functional notation for extracting an attribute. The simple way to explain this is that we can use the notations `attribute(table)` and `table.attribute` interchangeably:

```
SELECT name(new_emp());

 name
------
 None

--
-- this is the same as:
--  SELECT EMP.name AS youngster FROM EMP WHERE EMP.age < 30
--
SELECT name(EMP) AS youngster
    FROM EMP
    WHERE age(EMP) < 30;

 youngster
-----------
 Sam
```

Another way to use a function returning a row result is to declare a second function accepting a row type parameter, and pass the function result to it:

```
CREATE FUNCTION getname(emp) RETURNS text AS
'SELECT $1.name;'
LANGUAGE SQL;

SELECT getname(new_emp());
 getname
---------
 None
(1 row)
```

9.2.4. SQL Table Functions

A table function is one that may be used in the `FROM` clause of a query. All SQL language functions may be used in this manner, but it is particularly useful for functions returning composite types. If the function is defined to return a base type, the table function produces a one-column table. If the function is defined to return a composite type, the table function produces a column for each column of the composite type.

Here is an example:

```
CREATE TABLE foo (fooid int, foosubid int, fooname text);
INSERT INTO foo VALUES(1,1,'Joe');
INSERT INTO foo VALUES(1,2,'Ed');
INSERT INTO foo VALUES(2,1,'Mary');

CREATE FUNCTION getfoo(int) RETURNS foo AS '
    SELECT * FROM foo WHERE fooid = $1;
' LANGUAGE SQL;

SELECT *, upper(fooname) FROM getfoo(1) AS t1;

 fooid | foosubid | fooname | upper
-------+----------+---------+-------
     1 |        1 | Joe     | JOE
(2 rows)
```

As the example shows, we can work with the columns of the function's result just the same as if they were columns of a regular table.

Note that we only got one row out of the function. This is because we did not say `SETOF`.

9.2.5. SQL Functions Returning Sets

When an SQL function is declared as returning `SETOF` *`sometype`*, the function's final `SELECT` query is executed to completion, and each row it outputs is returned as an element of the set.

This feature is normally used by calling the function as a table function. In this case each row returned by the function becomes a row of the table seen by the query. For example, assume that table `foo` has the same contents as above, and we say:

```
CREATE FUNCTION getfoo(int) RETURNS setof foo AS '
    SELECT * FROM foo WHERE fooid = $1;
' LANGUAGE SQL;

SELECT * FROM getfoo(1) AS t1;

 fooid | foosubid | fooname
-------+----------+---------
     1 |        1 | Joe
     1 |        2 | Ed
(2 rows)
```

Currently, functions returning sets may also be called in the target list of a `SELECT` query. For each row that the `SELECT` generates by itself, the function returning set is invoked, and an output row is generated for each element of the function's result set. Note, however, that this capability is deprecated and may be removed in future releases. The following is an example function returning a set from the target list:

```
CREATE FUNCTION listchildren(text) RETURNS SETOF text AS
'SELECT name FROM nodes WHERE parent = $1'
LANGUAGE SQL;

SELECT * FROM nodes;
   name    | parent
-----------+--------
 Top       |
 Child1    | Top
 Child2    | Top
 Child3    | Top
 SubChild1 | Child1
 SubChild2 | Child1
(6 rows)

SELECT listchildren('Top');
 listchildren
--------------
 Child1
 Child2
 Child3
(3 rows)

SELECT name, listchildren(name) FROM nodes;
  name  | listchildren
--------+--------------
 Top    | Child1
 Top    | Child2
```

```
 Top    | Child3
 Child1 | SubChild1
 Child1 | SubChild2
(5 rows)
```

In the last `SELECT`, notice that no output row appears for `Child2`, `Child3`, etc. This happens because `listchildren` returns an empty set for those inputs, so no output rows are generated.

9.3. Procedural Language Functions

Procedural languages aren't built into the PostgreSQL server; they are offered by loadable modules. Please refer to the documentation of the procedural language in question for details about the syntax and how the function body is interpreted for each language.

There are currently four procedural languages available in the standard PostgreSQL distribution: PL/pgSQL, PL/Tcl, PL/Perl, and PL/Python. Other languages can be defined by users. Refer to Chapter 18, *Procedural Languages* for more information. The basics of developing a new procedural language are covered in Section 9.8, “Procedural Language Handlers”.

9.4. Internal Functions

Internal functions are functions written in C that have been statically linked into the PostgreSQL server. The “body” of the function definition specifies the C-language name of the function, which need not be the same as the name being declared for SQL use. (For reasons of backwards compatibility, an empty body is accepted as meaning that the C-language function name is the same as the SQL name.)

Normally, all internal functions present in the backend are declared during the initialization of the database cluster (`initdb`), but a user could use `CREATE FUNCTION` to create additional alias names for an internal function. Internal functions are declared in `CREATE FUNCTION` with language name `internal`. For instance, to create an alias for the `sqrt` function:

```
CREATE FUNCTION square_root(double precision) RETURNS double
 precision
    AS 'dsqrt'
    LANGUAGE INTERNAL
    WITH (isStrict);
```

(Most internal functions expect to be declared “strict”.)

Note

Not all “predefined” functions are “internal” in the above sense. Some predefined functions are written in SQL.

9.5. C Language Functions

User-defined functions can be written in C (or a language that can be made compatible with C, such as C++). Such functions are compiled into dynamically loadable objects (also called shared libraries) and are loaded by the server on demand. The dynamic loading feature is what distinguishes “C language” functions from “internal” functions --- the actual coding conventions are essentially the same for both. (Hence, the standard internal function library is a rich source of coding examples for user-defined C functions.)

Two different calling conventions are currently used for C functions. The newer “version 1” calling convention is indicated by writing a `PG_FUNCTION_INFO_V1()` macro call for the function, as illustrated below. Lack of such a macro indicates an old-style ("version 0") function. The language name specified in `CREATE FUNCTION` is `C` in either case. Old-style functions are now deprecated because of portability problems and lack of functionality, but they are still supported for compatibility reasons.

9.5.1. Dynamic Loading

The first time a user-defined function in a particular loadable object file is called in a backend session, the dynamic loader loads that object file into memory so that the function can be called. The `CREATE FUNCTION` for a user-defined C function must therefore specify two pieces of information for the function: the name of the loadable object file, and the C name (link symbol) of the specific function to call within that object file. If the C name is not explicitly specified then it is assumed to be the same as the SQL function name.

The following algorithm is used to locate the shared object file based on the name given in the `CREATE FUNCTION` command:

1. If the name is an absolute path, the given file is loaded.

2. If the name starts with the string `$libdir`, that part is replaced by the PostgreSQL package library directory name, which is determined at build time.

3. If the name does not contain a directory part, the file is searched for in the path specified by the configuration variable `dynamic_library_path`.

4. Otherwise (the file was not found in the path, or it contains a non-absolute directory part), the dynamic loader will try to take the name as given, which will most likely fail. (It is unreliable to depend on the current working directory.)

If this sequence does not work, the platform-specific shared library file name extension (often `.so`) is appended to the given name and this sequence is tried again. If that fails as well, the load will fail.

Note

The user ID the PostgreSQL server runs as must be able to traverse the path to the file you intend to load. Making the file or a higher-level directory not readable and/or not executable by the postgres user is a common mistake.

In any case, the file name that is given in the `CREATE FUNCTION` command is recorded literally in the system catalogs, so if the file needs to be loaded again the same procedure is applied.

Note

PostgreSQL will not compile a C function automatically. The object file must be compiled before it is referenced in a `CREATE FUNCTION` command. See Section 9.5.8, “Compiling and Linking Dynamically-Loaded Functions” for additional information.

Note

After it is used for the first time, a dynamically loaded object file is retained in memory. Future calls in the same session to the function(s) in that file will only incur the small overhead of a symbol table lookup. If you need to force a reload of an object file, for example after recompiling it, use the `LOAD` command or begin a fresh session.

It is recommended to locate shared libraries either relative to `$libdir` or through the dynamic library path. This simplifies version upgrades if the new installation is at a different location. The actual directory that `$libdir` stands for can be found out with the command `pg_config --pkglibdir`.

Note

Before PostgreSQL release 7.2, only exact absolute paths to object files could be specified in `CREATE FUNCTION`. This approach is now deprecated since it makes the function definition unnecessarily unportable. It's best to specify just the shared library name with no path nor extension, and let the search mechanism provide that information instead.

9.5.2. Base Types in C-Language Functions

Table 9.1, “Equivalent C Types” gives the C type required for parameters in the C functions that will be loaded into PostgreSQL. The “Defined In” column gives the header file that needs to be included to get the type definition. (The actual definition may be in a different file that is included by the listed file. It is recommended that users stick to the defined interface.) Note that you should always include `postgres.h` first in any source file, because it declares a number of things that you will need anyway.

Table 9.1. Equivalent C Types for Built-In PostgreSQL Types

SQL Type	C Type	Defined In
abstime	AbsoluteTime	utils/nabstime.h
boolean	bool	postgres.h (maybe compiler built-in)
box	BOX*	utils/geo_decls.h
bytea	bytea*	postgres.h
"char"	char	(compiler built-in)
character	BpChar*	postgres.h
cid	CommandId	postgres.h
date	DateADT	utils/date.h
smallint (int2)	int2 or int16	postgres.h
int2vector	int2vector*	postgres.h
integer (int4)	int4 or int32	postgres.h
real (float4)	float4*	postgres.h
double precision (float8)	float8*	postgres.h
interval	Interval*	utils/timestamp.h
lseg	LSEG*	utils/geo_decls.h
name	Name	postgres.h
oid	Oid	postgres.h
oidvector	oidvector*	postgres.h
path	PATH*	utils/geo_decls.h
point	POINT*	utils/geo_decls.h
regproc	regproc	postgres.h
reltime	RelativeTime	utils/nabstime.h
text	text*	postgres.h
tid	ItemPointer	storage/itemptr.h
time	TimeADT	utils/date.h
time with time zone	TimeTzADT	utils/date.h
timestamp	Timestamp*	utils/timestamp.h
tinterval	TimeInterval	utils/nabstime.h
varchar	VarChar*	postgres.h
xid	TransactionId	postgres.h

Internally, PostgreSQL regards a base type as a “blob of memory”. The user-defined functions that you define over a type in turn define the way that PostgreSQL can operate on it. That is, PostgreSQL

will only store and retrieve the data from disk and use your user-defined functions to input, process, and output the data. Base types can have one of three internal formats:

- pass by value, fixed-length
- pass by reference, fixed-length
- pass by reference, variable-length

By-value types can only be 1, 2 or 4 bytes in length (also 8 bytes, if `sizeof(Datum)` is 8 on your machine). You should be careful to define your types such that they will be the same size (in bytes) on all architectures. For example, the `long` type is dangerous because it is 4 bytes on some machines and 8 bytes on others, whereas `int` type is 4 bytes on most Unix machines. A reasonable implementation of the `int4` type on Unix machines might be:

```
/* 4-byte integer, passed by value */
typedef int int4;
```

PostgreSQL automatically figures things out so that the integer types really have the size they advertise.

On the other hand, fixed-length types of any size may be passed by-reference. For example, here is a sample implementation of a PostgreSQL type:

```
/* 16-byte structure, passed by reference */
typedef struct
{
    double  x, y;
} Point;
```

Only pointers to such types can be used when passing them in and out of PostgreSQL functions. To return a value of such a type, allocate the right amount of memory with `palloc()`, fill in the allocated memory, and return a pointer to it. (Alternatively, you can return an input value of the same type by returning its pointer. *Never* modify the contents of a pass-by-reference input value, however.)

Finally, all variable-length types must also be passed by reference. All variable-length types must begin with a length field of exactly 4 bytes, and all data to be stored within that type must be located in the memory immediately following that length field. The length field is the total length of the structure (i.e., it includes the size of the length field itself). We can define the text type as follows:

```
typedef struct {
    int4 length;
    char data[1];
} text;
```

Obviously, the data field declared here is not long enough to hold all possible strings. Since it's impossible to declare a variable-size structure in C, we rely on the knowledge that the C compiler won't range-check array subscripts. We just allocate the necessary amount of space and then access the array as if it were declared the right length. (If this isn't a familiar trick to you, you may wish to spend some time with an introductory C programming textbook before delving deeper into PostgreSQL server programming.) When manipulating variable-length types, we must be careful to allocate the correct amount of memory and set the length field correctly. For example, if we wanted to store 40 bytes in a text structure, we might use a code fragment like this:

```
#include "postgres.h"
...
char buffer[40]; /* our source data */
...
text *destination = (text *) palloc(VARHDRSZ + 40);
destination->length = VARHDRSZ + 40;
memcpy(destination->data, buffer, 40);
...
```

`VARHDRSZ` is the same as `sizeof(int4)`, but it's considered good style to use the macro `VARHDRSZ` to refer to the size of the overhead for a variable-length type.

Now that we've gone over all of the possible structures for base types, we can show some examples of real functions.

9.5.3. Version-0 Calling Conventions for C-Language Functions

We present the “old style” calling convention first --- although this approach is now deprecated, it's easier to get a handle on initially. In the version-0 method, the arguments and result of the C function are just declared in normal C style, but being careful to use the C representation of each SQL data type as shown above.

Here are some examples:

```
#include "postgres.h"
#include <string.h>

/* By Value */

int
add_one(int arg)
{
    return arg + 1;
}

/* By Reference, Fixed Length */

float8 *
add_one_float8(float8 *arg)
{
    float8    *result = (float8 *) palloc(sizeof(float8));

    *result = *arg + 1.0;

    return result;
}

Point *
makepoint(Point *pointx, Point *pointy)
{
    Point     *new_point = (Point *) palloc(sizeof(Point));

    new_point->x = pointx->x;
    new_point->y = pointy->y;

    return new_point;
}

/* By Reference, Variable Length */

text *
copytext(text *t)
{
    /*
     * VARSIZE is the total size of the struct in bytes.
     */
```

```
    text *new_t = (text *) palloc(VARSIZE(t));
    VARATT_SIZEP(new_t) = VARSIZE(t);
    /*
     * VARDATA is a pointer to the data region of the struct.
     */
    memcpy((void *) VARDATA(new_t), /* destination */
           (void *) VARDATA(t),     /* source */
           VARSIZE(t)-VARHDRSZ);    /* how many bytes */
    return new_t;
}

text *
concat_text(text *arg1, text *arg2)
{
    int32 new_text_size = VARSIZE(arg1) + VARSIZE(arg2) - VARHDRSZ;
    text *new_text = (text *) palloc(new_text_size);

    VARATT_SIZEP(new_text) = new_text_size;
    memcpy(VARDATA(new_text), VARDATA(arg1), VARSIZE(arg1)-
VARHDRSZ);
    memcpy(VARDATA(new_text) + (VARSIZE(arg1)-VARHDRSZ),
           VARDATA(arg2), VARSIZE(arg2)-VARHDRSZ);
    return new_text;
}
```

Supposing that the above code has been prepared in file `funcs.c` and compiled into a shared object, we could define the functions to PostgreSQL with commands like this:

```
CREATE FUNCTION add_one(int4) RETURNS int4
     AS 'PGROOT/tutorial/funcs' LANGUAGE C
     WITH (isStrict);

-- note overloading of SQL function name add_one()
CREATE FUNCTION add_one(float8) RETURNS float8
     AS 'PGROOT/tutorial/funcs',
        'add_one_float8'
     LANGUAGE C WITH (isStrict);

CREATE FUNCTION makepoint(point, point) RETURNS point
     AS 'PGROOT/tutorial/funcs' LANGUAGE C
     WITH (isStrict);

CREATE FUNCTION copytext(text) RETURNS text
     AS 'PGROOT/tutorial/funcs' LANGUAGE C
     WITH (isStrict);

CREATE FUNCTION concat_text(text, text) RETURNS text
     AS 'PGROOT/tutorial/funcs' LANGUAGE C
     WITH (isStrict);
```

Here *PGROOT* stands for the full path to the PostgreSQL source tree. (Better style would be to use just `'funcs'` in the `AS` clause, after having added *PGROOT*`/tutorial` to the search path. In any case, we may omit the system-specific extension for a shared library, commonly `.so` or `.sl`.)

Notice that we have specified the functions as “strict”, meaning that the system should automatically assume a NULL result if any input value is NULL. By doing this, we avoid having to check for NULL inputs in the function code. Without this, we'd have to check for null values explicitly, for example by checking for a null pointer for each pass-by-reference argument. (For pass-by-value arguments, we don't even have a way to check!)

Although this calling convention is simple to use, it is not very portable; on some architectures there are problems with passing smaller-than-int data types this way. Also, there is no simple way to return a NULL result, nor to cope with NULL arguments in any way other than making the function strict. The version-1 convention, presented next, overcomes these objections.

9.5.4. Version-1 Calling Conventions for C-Language Functions

The version-1 calling convention relies on macros to suppress most of the complexity of passing arguments and results. The C declaration of a version-1 function is always

```
Datum funcname(PG_FUNCTION_ARGS)
```

In addition, the macro call

```
PG_FUNCTION_INFO_V1(funcname);
```

must appear in the same source file (conventionally it's written just before the function itself). This macro call is not needed for `internal`-language functions, since PostgreSQL currently assumes all internal functions are version-1. However, it is *required* for dynamically-loaded functions.

In a version-1 function, each actual argument is fetched using a `PG_GETARG_`*xxx*`()` macro that corresponds to the argument's data type, and the result is returned using a `PG_RETURN_`*xxx*`()` macro for the return type.

Here we show the same functions as above, coded in version-1 style:

```
#include "postgres.h"
#include <string.h>
#include "fmgr.h"

/* By Value */

PG_FUNCTION_INFO_V1(add_one);

Datum
add_one(PG_FUNCTION_ARGS)
{
    int32   arg = PG_GETARG_INT32(0);

    PG_RETURN_INT32(arg + 1);
}

/* By Reference, Fixed Length */

PG_FUNCTION_INFO_V1(add_one_float8);

Datum
add_one_float8(PG_FUNCTION_ARGS)
{
    /* The macros for FLOAT8 hide its pass-by-reference nature */
    float8   arg = PG_GETARG_FLOAT8(0);

    PG_RETURN_FLOAT8(arg + 1.0);
}

PG_FUNCTION_INFO_V1(makepoint);
```

```
Datum
makepoint(PG_FUNCTION_ARGS)
{
    /* Here, the pass-by-reference nature of Point is not hidden */
    Point     *pointx = PG_GETARG_POINT_P(0);
    Point     *pointy = PG_GETARG_POINT_P(1);
    Point     *new_point = (Point *) palloc(sizeof(Point));

    new_point->x = pointx->x;
    new_point->y = pointy->y;

    PG_RETURN_POINT_P(new_point);
}

/* By Reference, Variable Length */

PG_FUNCTION_INFO_V1(copytext);

Datum
copytext(PG_FUNCTION_ARGS)
{
    text     *t = PG_GETARG_TEXT_P(0);
    /*
     * VARSIZE is the total size of the struct in bytes.
     */
    text     *new_t = (text *) palloc(VARSIZE(t));
    VARATT_SIZEP(new_t) = VARSIZE(t);
    /*
     * VARDATA is a pointer to the data region of the struct.
     */
    memcpy((void *) VARDATA(new_t), /* destination */
           (void *) VARDATA(t),     /* source */
           VARSIZE(t)-VARHDRSZ);    /* how many bytes */
    PG_RETURN_TEXT_P(new_t);
}

PG_FUNCTION_INFO_V1(concat_text);

Datum
concat_text(PG_FUNCTION_ARGS)
{
    text  *arg1 = PG_GETARG_TEXT_P(0);
    text  *arg2 = PG_GETARG_TEXT_P(1);
    int32 new_text_size = VARSIZE(arg1) + VARSIZE(arg2) - VARHDRSZ;
    text *new_text = (text *) palloc(new_text_size);

    VARATT_SIZEP(new_text) = new_text_size;
    memcpy(VARDATA(new_text), VARDATA(arg1), VARSIZE(arg1)-
VARHDRSZ);
    memcpy(VARDATA(new_text) + (VARSIZE(arg1)-VARHDRSZ),
           VARDATA(arg2), VARSIZE(arg2)-VARHDRSZ);
    PG_RETURN_TEXT_P(new_text);
}
```

The `CREATE FUNCTION` commands are the same as for the version-0 equivalents.

At first glance, the version-1 coding conventions may appear to be just pointless obscurantism. However, they do offer a number of improvements, because the macros can hide unnecessary detail.

An example is that in coding `add_one_float8`, we no longer need to be aware that `float8` is a pass-by-reference type. Another example is that the `GETARG` macros for variable-length types hide the need to deal with fetching "toasted" (compressed or out-of-line) values. The old-style `copytext` and `concat_text` functions shown above are actually wrong in the presence of toasted values, because they don't call `pg_detoast_datum()` on their inputs. (The handler for old-style dynamically-loaded functions currently takes care of this detail, but it does so less efficiently than is possible for a version-1 function.)

One big improvement in version-1 functions is better handling of NULL inputs and results. The macro `PG_ARGISNULL(`*`n`*`)` allows a function to test whether each input is NULL (of course, doing this is only necessary in functions not declared "strict"). As with the `PG_GETARG_`*`xxx`*`()` macros, the input arguments are counted beginning at zero. Note that one should refrain from executing `PG_GETARG_`*`xxx`*`()` until one has verified that the argument isn't NULL. To return a NULL result, execute `PG_RETURN_NULL()`; this works in both strict and nonstrict functions.

Other options provided in the new-style interface are two variants of the `PG_GETARG_`*`xxx`*`()` macros. The first of these, `PG_GETARG_`*`xxx`*`_COPY()` guarantees to return a copy of the specified parameter which is safe for writing into. (The normal macros will sometimes return a pointer to a value that is physically stored in a table, and so must not be written to. Using the `PG_GETARG_`*`xxx`*`_COPY()` macros guarantees a writable result.)

The second variant consists of the `PG_GETARG_`*`xxx`*`_SLICE()` macros which take three parameters. The first is the number of the parameter (as above). The second and third are the offset and length of the segment to be returned. Offsets are counted from zero, and a negative length requests that the remainder of the value be returned. These routines provide more efficient access to parts of large values in the case where they have storage type "external". (The storage type of a column can be specified using `ALTER TABLE` *`tablename`* `ALTER COLUMN` *`colname`* `SET STORAGE` *`storagetype`*. Storage type is one of `plain`, `external`, `extended`, or `main`.)

The version-1 function call conventions make it possible to return "set" results and implement trigger functions and procedural-language call handlers. Version-1 code is also more portable than version-0, because it does not break ANSI C restrictions on function call protocol. For more details see `src/backend/utils/fmgr/README` in the source distribution.

9.5.5. Composite Types in C-Language Functions

Composite types do not have a fixed layout like C structures. Instances of a composite type may contain null fields. In addition, composite types that are part of an inheritance hierarchy may have different fields than other members of the same inheritance hierarchy. Therefore, PostgreSQL provides a procedural interface for accessing fields of composite types from C. As PostgreSQL processes a set of rows, each row will be passed into your function as an opaque structure of type `TUPLE`. Suppose we want to write a function to answer the query

```
SELECT name, c_overpaid(emp, 1500) AS overpaid
FROM emp
WHERE name = 'Bill' OR name = 'Sam';
```

In the query above, we can define `c_overpaid` as:

```
#include "postgres.h"
#include "executor/executor.h"  /* for GetAttributeByName() */

bool
c_overpaid(TupleTableSlot *t, /* the current row of EMP */
           int32 limit)
{
    bool isnull;
    int32 salary;
```

```
    salary = DatumGetInt32(GetAttributeByName(t, "salary",
 &isnull));
    if (isnull)
        return (false);
    return salary > limit;
}

/* In version-1 coding, the above would look like this: */

PG_FUNCTION_INFO_V1(c_overpaid);

Datum
c_overpaid(PG_FUNCTION_ARGS)
{
    TupleTableSlot  *t = (TupleTableSlot *) PG_GETARG_POINTER(0);
    int32            limit = PG_GETARG_INT32(1);
    bool isnull;
    int32 salary;

    salary = DatumGetInt32(GetAttributeByName(t, "salary",
 &isnull));
    if (isnull)
        PG_RETURN_BOOL(false);
    /* Alternatively, we might prefer to do PG_RETURN_NULL() for
 null salary */

    PG_RETURN_BOOL(salary > limit);
}
```

`GetAttributeByName` is the PostgreSQL system function that returns attributes out of the current row. It has three arguments: the argument of type `TupleTableSlot*` passed into the function, the name of the desired attribute, and a return parameter that tells whether the attribute is null. `GetAttributeByName` returns a `Datum` value that you can convert to the proper data type by using the appropriate `DatumGet`*`XXX`*`()` macro.

The following command lets PostgreSQL know about the `c_overpaid` function:

```
CREATE FUNCTION c_overpaid(emp, int4)
RETURNS bool
AS 'PGROOT/tutorial/funcs'
LANGUAGE C;
```

9.5.6. Table Function API

The Table Function API assists in the creation of user-defined C language table functions (Section 9.7, “Table Functions”). Table functions are functions that produce a set of rows, made up of either base (scalar) data types, or composite (multi-column) data types. The API is split into two main components: support for returning composite data types, and support for returning multiple rows (set returning functions or SRFs).

The Table Function API relies on macros and functions to suppress most of the complexity of building composite data types and returning multiple results. A table function must follow the version-1 calling convention described above. In addition, the source file must include:

```
#include "funcapi.h"
```

9.5.6.1. Returning Rows (Composite Types)

The Table Function API support for returning composite data types (or rows) starts with the `AttInMetadata` structure. This structure holds arrays of individual attribute information needed to create a row from raw C strings. It also saves a pointer to the `TupleDesc`. The information carried here is derived from the `TupleDesc`, but it is stored here to avoid redundant CPU cycles on each call to a table function. In the case of a function returning a set, the `AttInMetadata` structure should be computed once during the first call and saved for re-use in later calls.

```
typedef struct AttInMetadata
{
    /* full TupleDesc */
    TupleDesc       tupdesc;

    /* array of attribute type input function finfo */
    FmgrInfo       *attinfuncs;

    /* array of attribute type typelem */
    Oid            *attelems;

    /* array of attribute typmod */
    int32        *atttypmods;
} AttInMetadata;
```

To assist you in populating this structure, several functions and a macro are available. Use

```
TupleDesc RelationNameGetTupleDesc(const char *relname)
```

to get a `TupleDesc` based on a specified relation, or

```
TupleDesc TypeGetTupleDesc(Oid typeoid, List *colaliases)
```

to get a `TupleDesc` based on a type OID. This can be used to get a `TupleDesc` for a base (scalar) or composite (relation) type. Then

```
AttInMetadata *TupleDescGetAttInMetadata(TupleDesc tupdesc)
```

will return a pointer to an `AttInMetadata`, initialized based on the given `TupleDesc`. `AttInMetadata` can be used in conjunction with C strings to produce a properly formed tuple. The metadata is stored here to avoid redundant work across multiple calls.

To return a tuple you must create a tuple slot based on the `TupleDesc`. You can use

```
TupleTableSlot *TupleDescGetSlot(TupleDesc tupdesc)
```

to initialize this tuple slot, or obtain one through other (user provided) means. The tuple slot is needed to create a `Datum` for return by the function. The same slot can (and should) be re-used on each call.

After constructing an `AttInMetadata` structure,

```
HeapTuple BuildTupleFromCStrings(AttInMetadata *attinmeta, char
 **values)
```

can be used to build a `HeapTuple` given user data in C string form. "values" is an array of C strings, one for each attribute of the return tuple. Each C string should be in the form expected by the input function of the attribute data type. In order to return a null value for one of the attributes, the corresponding pointer in the *`values`* array should be set to `NULL`. This function will need to be called again for each tuple you return.

Building a tuple via `TupleDescGetAttInMetadata` and `BuildTupleFromCStrings` is only convenient if your function naturally computes the values to be returned as text strings. If your code naturally computes the values as a set of Datums, you should instead use the underlying

heap_formtuple routine to convert the Datums directly into a tuple. You will still need the TupleDesc and a TupleTableSlot, but not AttInMetadata.

Once you have built a tuple to return from your function, the tuple must be converted into a Datum. Use

```
TupleGetDatum(TupleTableSlot *slot, HeapTuple tuple)
```

to get a Datum given a tuple and a slot. This Datum can be returned directly if you intend to return just a single row, or it can be used as the current return value in a set-returning function.

An example appears below.

9.5.6.2. Returning Sets

A set-returning function (SRF) is normally called once for each item it returns. The SRF must therefore save enough state to remember what it was doing and return the next item on each call. The Table Function API provides the FuncCallContext structure to help control this process. fcinfo->flinfo->fn_extra is used to hold a pointer to FuncCallContext across calls.

```
typedef struct
{
    /*
     * Number of times we've been called before.
     *
     * call_cntr is initialized to 0 for you by
 SRF_FIRSTCALL_INIT(), and
     * incremented for you every time SRF_RETURN_NEXT() is called.
     */
    uint32 call_cntr;

    /*
     * OPTIONAL maximum number of calls
     *
     * max_calls is here for convenience ONLY and setting it is
 OPTIONAL.
     * If not set, you must provide alternative means to know when
 the
     * function is done.
     */
    uint32 max_calls;

    /*
     * OPTIONAL pointer to result slot
     *
     * slot is for use when returning tuples (i.e. composite data
 types)
     * and is not needed when returning base (i.e. scalar) data
 types.
     */
    TupleTableSlot *slot;

    /*
     * OPTIONAL pointer to misc user provided context info
     *
     * user_fctx is for use as a pointer to your own struct to
 retain
     * arbitrary context information between calls for your
 function.
     */
```

```
    void *user_fctx;

    /*
     * OPTIONAL pointer to struct containing arrays of attribute
 type input
     * metainfo
     *
     * attinmeta is for use when returning tuples (i.e. composite
 data types)
     * and is not needed when returning base (i.e. scalar) data
 types. It
     * is ONLY needed if you intend to use BuildTupleFromCStrings()
 to create
     * the return tuple.
     */
    AttInMetadata *attinmeta;

    /*
     * memory context used for structures which must live for
 multiple calls
     *
     * multi_call_memory_ctx is set by SRF_FIRSTCALL_INIT() for
 you, and used
     * by SRF_RETURN_DONE() for cleanup. It is the most appropriate
 memory
     * context for any memory that is to be re-used across multiple
 calls
     * of the SRF.
     */
    MemoryContext multi_call_memory_ctx;
} FuncCallContext;
```

An SRF uses several functions and macros that automatically manipulate the `FuncCallContext` structure (and expect to find it via `fn_extra`). Use

```
SRF_IS_FIRSTCALL()
```

to determine if your function is being called for the first or a subsequent time. On the first call (only) use

```
SRF_FIRSTCALL_INIT()
```

to initialize the `FuncCallContext`. On every function call, including the first, use

```
SRF_PERCALL_SETUP()
```

to properly set up for using the `FuncCallContext` and clearing any previously returned data left over from the previous pass.

If your function has data to return, use

```
SRF_RETURN_NEXT(funcctx, result)
```

to return it to the caller. (The `result` must be a `Datum`, either a single value or a tuple prepared as described earlier.) Finally, when your function is finished returning data, use

```
SRF_RETURN_DONE(funcctx)
```

to clean up and end the SRF.

The memory context that is current when the SRF is called is a transient context that will be cleared between calls. This means that you do not need to `pfree` everything you `palloc`; it will go away anyway. However, if you want to allocate any data structures to live across calls, you need to put

them somewhere else. The memory context referenced by `multi_call_memory_ctx` is a suitable location for any data that needs to survive until the SRF is finished running. In most cases, this means that you should switch into `multi_call_memory_ctx` while doing the first-call setup.

A complete pseudo-code example looks like the following:

```
Datum
my_Set_Returning_Function(PG_FUNCTION_ARGS)
{
    FuncCallContext  *funcctx;
    Datum             result;
    MemoryContext     oldcontext;
    [user defined declarations]

    if (SRF_IS_FIRSTCALL())
    {
        funcctx = SRF_FIRSTCALL_INIT();
        oldcontext = MemoryContextSwitchTo(funcctx-
>multi_call_memory_ctx);
        /* one-time setup code appears here: */
        [user defined code]
        [if returning composite]
            [build TupleDesc, and perhaps AttInMetadata]
            [obtain slot]
            funcctx->slot = slot;
        [endif returning composite]
        [user defined code]
        MemoryContextSwitchTo(oldcontext);
    }

    /* each-time setup code appears here: */
    [user defined code]
    funcctx = SRF_PERCALL_SETUP();
    [user defined code]

    /* this is just one way we might test whether we are done: */
    if (funcctx->call_cntr < funcctx->max_calls)
    {
        /* here we want to return another item: */
        [user defined code]
        [obtain result Datum]
        SRF_RETURN_NEXT(funcctx, result);
    }
    else
    {
        /* here we are done returning items, and just need to clean
 up: */
        [user defined code]
        SRF_RETURN_DONE(funcctx);
    }
}
```

A complete example of a simple SRF returning a composite type looks like:

```
PG_FUNCTION_INFO_V1(testpassbyval);
Datum
testpassbyval(PG_FUNCTION_ARGS)
{
    FuncCallContext     *funcctx;
```

```
    int                  call_cntr;
    int                  max_calls;
    TupleDesc            tupdesc;
    TupleTableSlot       *slot;
    AttInMetadata       *attinmeta;

     /* stuff done only on the first call of the function */
     if (SRF_IS_FIRSTCALL())
     {
        MemoryContext oldcontext;

        /* create a function context for cross-call persistence */
        funcctx = SRF_FIRSTCALL_INIT();

        /* switch to memory context appropriate for multiple
 function calls */
        oldcontext = MemoryContextSwitchTo(funcctx-
>multi_call_memory_ctx);

        /* total number of tuples to be returned */
        funcctx->max_calls = PG_GETARG_UINT32(0);

        /*
         * Build a tuple description for a __testpassbyval tuple
         */
        tupdesc = RelationNameGetTupleDesc("__testpassbyval");

        /* allocate a slot for a tuple with this tupdesc */
        slot = TupleDescGetSlot(tupdesc);

        /* assign slot to function context */
        funcctx->slot = slot;

        /*
         * Generate attribute metadata needed later to produce
 tuples from raw
         * C strings
         */
        attinmeta = TupleDescGetAttInMetadata(tupdesc);
        funcctx->attinmeta = attinmeta;

        MemoryContextSwitchTo(oldcontext);
    }

    /* stuff done on every call of the function */
    funcctx = SRF_PERCALL_SETUP();

    call_cntr = funcctx->call_cntr;
    max_calls = funcctx->max_calls;
    slot = funcctx->slot;
    attinmeta = funcctx->attinmeta;

    if (call_cntr < max_calls)    /* do when there is more left to
 send */
    {
        char       **values;
        HeapTuple    tuple;
        Datum        result;
```

```
        /*
         * Prepare a values array for storage in our slot.
         * This should be an array of C strings which will
         * be processed later by the appropriate "in" functions.
         */
        values = (char **) palloc(3 * sizeof(char *));
        values[0] = (char *) palloc(16 * sizeof(char));
        values[1] = (char *) palloc(16 * sizeof(char));
        values[2] = (char *) palloc(16 * sizeof(char));

        snprintf(values[0], 16, "%d", 1 * PG_GETARG_INT32(1));
        snprintf(values[1], 16, "%d", 2 * PG_GETARG_INT32(1));
        snprintf(values[2], 16, "%d", 3 * PG_GETARG_INT32(1));

        /* build a tuple */
        tuple = BuildTupleFromCStrings(attinmeta, values);

        /* make the tuple into a datum */
        result = TupleGetDatum(slot, tuple);

        /* Clean up (this is not actually necessary) */
        pfree(values[0]);
        pfree(values[1]);
        pfree(values[2]);
        pfree(values);

         SRF_RETURN_NEXT(funcctx, result);
    }
    else    /* do when there is no more left */
    {
         SRF_RETURN_DONE(funcctx);
    }
}
```

with supporting SQL code of

```
CREATE TYPE __testpassbyval AS (f1 int4, f2 int4, f3 int4);

CREATE OR REPLACE FUNCTION testpassbyval(int4, int4) RETURNS setof
 __testpassbyval
  AS 'MODULE_PATHNAME','testpassbyval' LANGUAGE 'c' IMMUTABLE
 STRICT;
```

See `contrib/tablefunc` for more examples of table functions.

9.5.7. Writing Code

We now turn to the more difficult task of writing programming language functions. Be warned: this section of the manual will not make you a programmer. You must have a good understanding of C (including the use of pointers) before trying to write C functions for use with PostgreSQL. While it may be possible to load functions written in languages other than C into PostgreSQL, this is often difficult (when it is possible at all) because other languages, such as FORTRAN and Pascal often do not follow the same *calling convention* as C. That is, other languages do not pass argument and return values between functions in the same way. For this reason, we will assume that your programming language functions are written in C.

The basic rules for building C functions are as follows:

- Use `pg_config --includedir-server` to find out where the PostgreSQL server header files are installed on your system (or the system that your users will be running on). This option is new with PostgreSQL 7.2. For PostgreSQL 7.1 you should use the option `--includedir`. (`pg_config` will exit with a non-zero status if it encounters an unknown option.) For releases prior to 7.1 you will have to guess, but since that was before the current calling conventions were introduced, it is unlikely that you want to support those releases.

- When allocating memory, use the PostgreSQL routines `palloc` and `pfree` instead of the corresponding C library routines `malloc` and `free`. The memory allocated by `palloc` will be freed automatically at the end of each transaction, preventing memory leaks.

- Always zero the bytes of your structures using `memset` or `bzero`. Several routines (such as the hash access method, hash join and the sort algorithm) compute functions of the raw bits contained in your structure. Even if you initialize all fields of your structure, there may be several bytes of alignment padding (holes in the structure) that may contain garbage values.

- Most of the internal PostgreSQL types are declared in `postgres.h`, while the function manager interfaces (`PG_FUNCTION_ARGS`, etc.) are in `fmgr.h`, so you will need to include at least these two files. For portability reasons it's best to include `postgres.h` *first*, before any other system or user header files. Including `postgres.h` will also include `elog.h` and `palloc.h` for you.

- Symbol names defined within object files must not conflict with each other or with symbols defined in the PostgreSQL server executable. You will have to rename your functions or variables if you get error messages to this effect.

- Compiling and linking your object code so that it can be dynamically loaded into PostgreSQL always requires special flags. See Section 9.5.8, “Compiling and Linking Dynamically-Loaded Functions” for a detailed explanation of how to do it for your particular operating system.

9.5.8. Compiling and Linking Dynamically-Loaded Functions

Before you are able to use your PostgreSQL extension functions written in C, they must be compiled and linked in a special way to produce a file that can be dynamically loaded by the server. To be precise, a *shared library* needs to be created.

For more information you should read the documentation of your operating system, in particular the manual pages for the C compiler, `cc`, and the link editor, `ld`. In addition, the PostgreSQL source code contains several working examples in the `contrib` directory. If you rely on these examples you will make your modules dependent on the availability of the PostgreSQL source code, however.

Creating shared libraries is generally analogous to linking executables: first the source files are compiled into object files, then the object files are linked together. The object files need to be created as *position-independent code* (PIC), which conceptually means that they can be placed at an arbitrary location in memory when they are loaded by the executable. (Object files intended for executables are usually not compiled that way.) The command to link a shared library contains special flags to distinguish it from linking an executable. --- At least this is the theory. On some systems the practice is much uglier.

In the following examples we assume that your source code is in a file `foo.c` and we will create a shared library `foo.so`. The intermediate object file will be called `foo.o` unless otherwise noted. A shared library can contain more than one object file, but we only use one here.

BSD/OS

The compiler flag to create PIC is `-fpic`. The linker flag to create shared libraries is `-shared`.

```
gcc -fpic -c foo.c
ld -shared -o foo.so foo.o
```

This is applicable as of version 4.0 of BSD/OS.

FreeBSD

The compiler flag to create PIC is `-fpic`. To create shared libraries the compiler flag is `-shared`.

```
gcc -fpic -c foo.c
gcc -shared -o foo.so foo.o
```

This is applicable as of version 3.0 of FreeBSD.

HP-UX

The compiler flag of the system compiler to create PIC is `+z`. When using GCC it's `-fpic`. The linker flag for shared libraries is `-b`. So

```
cc +z -c foo.c
```

or

```
gcc -fpic -c foo.c
```

and then

```
ld -b -o foo.sl foo.o
```

HP-UX uses the extension `.sl` for shared libraries, unlike most other systems.

IRIX

PIC is the default, no special compiler options are necessary. The linker option to produce shared libraries is `-shared`.

```
cc -c foo.c
ld -shared -o foo.so foo.o
```

Linux

The compiler flag to create PIC is `-fpic`. On some platforms in some situations `-fPIC` must be used if `-fpic` does not work. Refer to the GCC manual for more information. The compiler flag to create a shared library is `-shared`. A complete example looks like this:

```
cc -fpic -c foo.c
cc -shared -o foo.so foo.o
```

MacOS X

Here is a sample. It assumes the developer tools are installed.

```
cc -c foo.c
cc -bundle -flat_namespace -undefined suppress -o foo.so foo.o
```

NetBSD

The compiler flag to create PIC is `-fpic`. For ELF systems, the compiler with the flag `-shared` is used to link shared libraries. On the older non-ELF systems, `ld -Bshareable` is used.

```
gcc -fpic -c foo.c
gcc -shared -o foo.so foo.o
```

OpenBSD

The compiler flag to create PIC is `-fpic`. `ld -Bshareable` is used to link shared libraries.

```
gcc -fpic -c foo.c
ld -Bshareable -o foo.so foo.o
```

Solaris

The compiler flag to create PIC is `-KPIC` with the Sun compiler and `-fpic` with GCC. To link shared libraries, the compiler option is `-G` with either compiler or alternatively `-shared` with GCC.

```
cc -KPIC -c foo.c
cc -G -o foo.so foo.o
```

or

```
gcc -fpic -c foo.c
gcc -G -o foo.so foo.o
```

Tru64 UNIX

PIC is the default, so the compilation command is the usual one. `ld` with special options is used to do the linking:

```
cc -c foo.c
ld -shared -expect_unresolved '*' -o foo.so foo.o
```

The same procedure is used with GCC instead of the system compiler; no special options are required.

UnixWare

The compiler flag to create PIC is `-K PIC` with the SCO compiler and `-fpic` with GCC. To link shared libraries, the compiler option is `-G` with the SCO compiler and `-shared` with GCC.

```
cc -K PIC -c foo.c
cc -G -o foo.so foo.o
```

or

```
gcc -fpic -c foo.c
gcc -shared -o foo.so foo.o
```

Tip

If you want to package your extension modules for wide distribution you should consider using GNU Libtool[1] for building shared libraries. It encapsulates the platform differences into a general and powerful interface. Serious packaging also requires considerations about library versioning, symbol resolution methods, and other issues.

The resulting shared library file can then be loaded into PostgreSQL. When specifying the file name to the `CREATE FUNCTION` command, one must give it the name of the shared library file, not the intermediate object file. Note that the system's standard shared-library extension (usually `.so` or `.sl`) can be omitted from the `CREATE FUNCTION` command, and normally should be omitted for best portability.

Refer back to Section 9.5.1, “Dynamic Loading” about where the server expects to find the shared library files.

9.6. Function Overloading

[1] http://www.gnu.org/software/libtool/

More than one function may be defined with the same SQL name, so long as the arguments they take are different. In other words, function names can be *overloaded*. When a query is executed, the server will determine which function to call from the data types and the number of the provided arguments. Overloading can also be used to simulate functions with a variable number of arguments, up to a finite maximum number.

A function may also have the same name as an attribute. In the case that there is an ambiguity between a function on a complex type and an attribute of the complex type, the attribute will always be used.

When creating a family of overloaded functions, one should be careful not to create ambiguities. For instance, given the functions

```
CREATE FUNCTION test(int, real) RETURNS ...
CREATE FUNCTION test(smallint, double precision) RETURNS ...
```

it is not immediately clear which function would be called with some trivial input like `test(1, 1.5)`. The currently implemented resolution rules are described in the *User's Guide*, but it is unwise to design a system that subtly relies on this behavior.

When overloading C language functions, there is an additional constraint: The C name of each function in the family of overloaded functions must be different from the C names of all other functions, either internal or dynamically loaded. If this rule is violated, the behavior is not portable. You might get a run-time linker error, or one of the functions will get called (usually the internal one). The alternative form of the `AS` clause for the SQL `CREATE FUNCTION` command decouples the SQL function name from the function name in the C source code. E.g.,

```
CREATE FUNCTION test(int) RETURNS int
    AS 'filename', 'test_1arg'
    LANGUAGE C;
CREATE FUNCTION test(int, int) RETURNS int
    AS 'filename', 'test_2arg'
    LANGUAGE C;
```

The names of the C functions here reflect one of many possible conventions.

Prior to PostgreSQL 7.0, this alternative syntax did not exist. There is a trick to get around the problem, by defining a set of C functions with different names and then define a set of identically-named SQL function wrappers that take the appropriate argument types and call the matching C function.

9.7. Table Functions

Table functions are functions that produce a set of rows, made up of either base (scalar) data types, or composite (multi-column) data types. They are used like a table, view, or subselect in the `FROM` clause of a query. Columns returned by table functions may be included in `SELECT`, `JOIN`, or `WHERE` clauses in the same manner as a table, view, or subselect column.

If a table function returns a base data type, the single result column is named for the function. If the function returns a composite type, the result columns get the same names as the individual attributes of the type.

A table function may be aliased in the `FROM` clause, but it also may be left unaliased. If a function is used in the FROM clause with no alias, the function name is used as the relation name.

Table functions work wherever tables do in `SELECT` statements. For example

```
CREATE TABLE foo (fooid int, foosubid int, fooname text);

CREATE FUNCTION getfoo(int) RETURNS setof foo AS '
    SELECT * FROM foo WHERE fooid = $1;
```

```
' LANGUAGE SQL;

SELECT * FROM getfoo(1) AS t1;

SELECT * FROM foo
WHERE foosubid in (select foosubid from getfoo(foo.fooid) z
                   where z.fooid = foo.fooid);

CREATE VIEW vw_getfoo AS SELECT * FROM getfoo(1);
SELECT * FROM vw_getfoo;
```

are all valid statements.

In some cases it is useful to define table functions that can return different column sets depending on how they are invoked. To support this, the table function can be declared as returning the pseudo-type `record`. When such a function is used in a query, the expected row structure must be specified in the query itself, so that the system can know how to parse and plan the query. Consider this example:

```
SELECT *
FROM dblink('dbname=template1', 'select proname, prosrc from
 pg_proc')
  AS t1(proname name, prosrc text)
WHERE proname LIKE 'bytea%';
```

The `dblink` function executes a remote query (see `contrib/dblink`). It is declared to return `record` since it might be used for any kind of query. The actual column set must be specified in the calling query so that the parser knows, for example, what `*` should expand to.

9.8. Procedural Language Handlers

All calls to functions that are written in a language other than the current "version 1" interface for compiled languages (this includes functions in user-defined procedural languages, functions written in SQL, and functions using the version 0 compiled language interface), go through a *call handler* function for the specific language. It is the responsibility of the call handler to execute the function in a meaningful way, such as by interpreting the supplied source text. This section describes how a language call handler can be written. This is not a common task, in fact, it has only been done a handful of times in the history of PostgreSQL, but the topic naturally belongs in this chapter, and the material might give some insight into the extensible nature of the PostgreSQL system.

The call handler for a procedural language is a "normal" function, which must be written in a compiled language such as C and registered with PostgreSQL as taking no arguments and returning the `language_handler` type. This special pseudo-type identifies the handler as a call handler and prevents it from being called directly in queries.

Note

In PostgreSQL 7.1 and later, call handlers must adhere to the "version 1" function manager interface, not the old-style interface.

The call handler is called in the same way as any other function: It receives a pointer to a `FunctionCallInfoData` `struct` containing argument values and information about the called function, and it is expected to return a `Datum` result (and possibly set the `isnull` field of the `FunctionCallInfoData` structure, if it wishes to return an SQL NULL result). The difference between a call handler and an ordinary callee function is that the `flinfo->fn_oid` field of the `FunctionCallInfoData` structure will contain the OID of the actual function to be called, not of the call handler itself. The call handler must use this field to determine which function to execute. Also, the passed argument list has been set up according to the declaration of the target function, not of the call handler.

It's up to the call handler to fetch the `pg_proc` entry and to analyze the argument and return types of the called procedure. The AS clause from the `CREATE FUNCTION` of the procedure will be found in the `prosrc` attribute of the `pg_proc` table entry. This may be the source text in the procedural language itself (like for PL/Tcl), a path name to a file, or anything else that tells the call handler what to do in detail.

Often, the same function is called many times per SQL statement. A call handler can avoid repeated lookups of information about the called function by using the `flinfo->fn_extra` field. This will initially be NULL, but can be set by the call handler to point at information about the PL function. On subsequent calls, if `flinfo->fn_extra` is already non-NULL then it can be used and the information lookup step skipped. The call handler must be careful that `flinfo->fn_extra` is made to point at memory that will live at least until the end of the current query, since an `FmgrInfo` data structure could be kept that long. One way to do this is to allocate the extra data in the memory context specified by `flinfo->fn_mcxt`; such data will normally have the same lifespan as the `FmgrInfo` itself. But the handler could also choose to use a longer-lived context so that it can cache function definition information across queries.

When a PL function is invoked as a trigger, no explicit arguments are passed, but the `FunctionCallInfoData`'s `context` field points at a `TriggerData` node, rather than being NULL as it is in a plain function call. A language handler should provide mechanisms for PL functions to get at the trigger information.

This is a template for a PL handler written in C:

```
#include "postgres.h"
#include "executor/spi.h"
#include "commands/trigger.h"
#include "utils/elog.h"
#include "fmgr.h"
#include "access/heapam.h"
#include "utils/syscache.h"
#include "catalog/pg_proc.h"
#include "catalog/pg_type.h"

PG_FUNCTION_INFO_V1(plsample_call_handler);

Datum
plsample_call_handler(PG_FUNCTION_ARGS)
{
    Datum          retval;

    if (CALLED_AS_TRIGGER(fcinfo))
    {
        /*
         * Called as a trigger procedure
         */
        TriggerData    *trigdata = (TriggerData *) fcinfo->context;

        retval = ...
    }
    else {
        /*
         * Called as a function
         */

        retval = ...
    }

    return retval;
```

```
}
```

Only a few thousand lines of code have to be added instead of the dots to complete the call handler. See Section 9.5, “C Language Functions” for information on how to compile it into a loadable module.

The following commands then register the sample procedural language:

```
CREATE FUNCTION plsample_call_handler () RETURNS language_handler
    AS '/usr/local/pgsql/lib/plsample'
    LANGUAGE C;
CREATE LANGUAGE plsample
    HANDLER plsample_call_handler;
```

Chapter 10. Extending SQL: Types

As previously mentioned, there are two kinds of types in PostgreSQL: base types (defined in a programming language) and composite types. This chapter describes how to define new base types.

The examples in this section can be found in `complex.sql` and `complex.c` in the tutorial directory. Composite examples are in `funcs.sql`.

A user-defined type must always have input and output functions. These functions determine how the type appears in strings (for input by the user and output to the user) and how the type is organized in memory. The input function takes a null-terminated character string as its input and returns the internal (in memory) representation of the type. The output function takes the internal representation of the type and returns a null-terminated character string.

Suppose we want to define a complex type which represents complex numbers. Naturally, we would choose to represent a complex in memory as the following C structure:

```
typedef struct Complex {
    double      x;
    double      y;
} Complex;
```

and a string of the form `(x,y)` as the external string representation.

The functions are usually not hard to write, especially the output function. However, there are a number of points to remember:

- When defining your external (string) representation, remember that you must eventually write a complete and robust parser for that representation as your input function!

  For instance:

  ```
  Complex *
  complex_in(char *str)
  {
      double x, y;
      Complex *result;
      if (sscanf(str, " ( %lf , %lf )", &x, &y) != 2) {
          elog(ERROR, "complex_in: error in parsing %s", str);
          return NULL;
      }
      result = (Complex *)palloc(sizeof(Complex));
      result->x = x;
      result->y = y;
      return (result);
  }
  ```

  The output function can simply be:

  ```
  char *
  complex_out(Complex *complex)
  {
      char *result;
      if (complex == NULL)
          return(NULL);
      result = (char *) palloc(60);
      sprintf(result, "(%g,%g)", complex->x, complex->y);
      return(result);
  }
  ```

- You should try to make the input and output functions inverses of each other. If you do not, you will have severe problems when you need to dump your data into a file and then read it back in (say, into someone else's database on another computer). This is a particularly common problem when floating-point numbers are involved.

To define the `complex` type, we need to create the two user-defined functions `complex_in` and `complex_out` before creating the type:

```
CREATE FUNCTION complex_in(cstring)
    RETURNS complex
    AS 'PGROOT/tutorial/complex'
    LANGUAGE C;

CREATE FUNCTION complex_out(complex)
    RETURNS cstring
    AS 'PGROOT/tutorial/complex'
    LANGUAGE C;
```

Finally, we can declare the data type:

```
CREATE TYPE complex (
    internallength = 16,
    input = complex_in,
    output = complex_out
);
```

Notice that the declarations of the input and output functions must reference the not-yet-defined type. This is allowed, but will draw warning messages that may be ignored.

As discussed earlier, PostgreSQL fully supports arrays of base types. Additionally, PostgreSQL supports arrays of user-defined types as well. When you define a type, PostgreSQL automatically provides support for arrays of that type. For historical reasons, the array type has the same name as the user-defined type with the underscore character _ prepended.

Composite types do not need any function defined on them, since the system already understands what they look like inside.

If the values of your data type might exceed a few hundred bytes in size (in internal form), you should be careful to mark them TOAST-able. To do this, the internal representation must follow the standard layout for variable-length data: the first four bytes must be an `int32` containing the total length in bytes of the datum (including itself). Then, all your functions that accept values of the type must be careful to call `pg_detoast_datum()` on the supplied values --- after checking that the value is not NULL, if your function is not strict. Finally, select the appropriate storage option when giving the `CREATE TYPE` command.

Chapter 11. Extending SQL: Operators

11.1. Introduction

PostgreSQL supports left unary, right unary, and binary operators. Operators can be overloaded; that is, the same operator name can be used for different operators that have different numbers and types of operands. If there is an ambiguous situation and the system cannot determine the correct operator to use, it will return an error. You may have to type-cast the left and/or right operands to help it understand which operator you meant to use.

Every operator is "syntactic sugar" for a call to an underlying function that does the real work; so you must first create the underlying function before you can create the operator. However, an operator is *not merely* syntactic sugar, because it carries additional information that helps the query planner optimize queries that use the operator. Much of this chapter will be devoted to explaining that additional information.

11.2. Example

Here is an example of creating an operator for adding two complex numbers. We assume we've already created the definition of type `complex` (see Chapter 10, *Extending SQL: Types*). First we need a function that does the work, then we can define the operator:

```
CREATE FUNCTION complex_add(complex, complex)
    RETURNS complex
    AS 'PGROOT/tutorial/complex'
    LANGUAGE C;

CREATE OPERATOR + (
    leftarg = complex,
    rightarg = complex,
    procedure = complex_add,
    commutator = +
);
```

Now we can do:

```
SELECT (a + b) AS c FROM test_complex;

        c
-----------------
 (5.2,6.05)
 (133.42,144.95)
```

We've shown how to create a binary operator here. To create unary operators, just omit one of `leftarg` (for left unary) or `rightarg` (for right unary). The `procedure` clause and the argument clauses are the only required items in `CREATE OPERATOR`. The `commutator` clause shown in the example is an optional hint to the query optimizer. Further details about `commutator` and other optimizer hints appear below.

11.3. Operator Optimization Information

Author

Written by Tom Lane.

A PostgreSQL operator definition can include several optional clauses that tell the system useful things about how the operator behaves. These clauses should be provided whenever appropriate, because they can make for considerable speedups in execution of queries that use the operator. But if you provide them, you must be sure that they are right! Incorrect use of an optimization clause can result in backend crashes, subtly wrong output, or other Bad Things. You can always leave out an optimization clause if you are not sure about it; the only consequence is that queries might run slower than they need to.

Additional optimization clauses might be added in future versions of PostgreSQL. The ones described here are all the ones that release 7.3.21 understands.

11.3.1. COMMUTATOR

The `COMMUTATOR` clause, if provided, names an operator that is the commutator of the operator being defined. We say that operator A is the commutator of operator B if (x A y) equals (y B x) for all possible input values x, y. Notice that B is also the commutator of A. For example, operators < and > for a particular data type are usually each others' commutators, and operator + is usually commutative with itself. But operator − is usually not commutative with anything.

The left operand type of a commuted operator is the same as the right operand type of its commutator, and vice versa. So the name of the commutator operator is all that PostgreSQL needs to be given to look up the commutator, and that's all that needs to be provided in the `COMMUTATOR` clause.

When you are defining a self-commutative operator, you just do it. When you are defining a pair of commutative operators, things are a little trickier: how can the first one to be defined refer to the other one, which you haven't defined yet? There are two solutions to this problem:

- One way is to omit the `COMMUTATOR` clause in the first operator that you define, and then provide one in the second operator's definition. Since PostgreSQL knows that commutative operators come in pairs, when it sees the second definition it will automatically go back and fill in the missing `COMMUTATOR` clause in the first definition.

- The other, more straightforward way is just to include `COMMUTATOR` clauses in both definitions. When PostgreSQL processes the first definition and realizes that `COMMUTATOR` refers to a non-existent operator, the system will make a dummy entry for that operator in the system catalog. This dummy entry will have valid data only for the operator name, left and right operand types, and result type, since that's all that PostgreSQL can deduce at this point. The first operator's catalog entry will link to this dummy entry. Later, when you define the second operator, the system updates the dummy entry with the additional information from the second definition. If you try to use the dummy operator before it's been filled in, you'll just get an error message. (Note: This procedure did not work reliably in PostgreSQL versions before 6.5, but it is now the recommended way to do things.)

11.3.2. NEGATOR

The `NEGATOR` clause, if provided, names an operator that is the negator of the operator being defined. We say that operator A is the negator of operator B if both return Boolean results and (x A y) equals NOT (x B y) for all possible inputs x, y. Notice that B is also the negator of A. For example, < and >= are a negator pair for most data types. An operator can never validly be its own negator.

Unlike commutators, a pair of unary operators could validly be marked as each others' negators; that would mean (A x) equals NOT (B x) for all x, or the equivalent for right unary operators.

An operator's negator must have the same left and/or right operand types as the operator itself, so just as with `COMMUTATOR`, only the operator name need be given in the `NEGATOR` clause.

Providing a negator is very helpful to the query optimizer since it allows expressions like `NOT (x = y)` to be simplified into x <> y. This comes up more often than you might think, because `NOT` operations can be inserted as a consequence of other rearrangements.

Pairs of negator operators can be defined using the same methods explained above for commutator pairs.

11.3.3. RESTRICT

The `RESTRICT` clause, if provided, names a restriction selectivity estimation function for the operator (note that this is a function name, not an operator name). `RESTRICT` clauses only make sense for binary operators that return `boolean`. The idea behind a restriction selectivity estimator is to guess what fraction of the rows in a table will satisfy a `WHERE`-clause condition of the form

```
column OP constant
```

for the current operator and a particular constant value. This assists the optimizer by giving it some idea of how many rows will be eliminated by `WHERE` clauses that have this form. (What happens if the constant is on the left, you may be wondering? Well, that's one of the things that `COMMUTATOR` is for...)

Writing new restriction selectivity estimation functions is far beyond the scope of this chapter, but fortunately you can usually just use one of the system's standard estimators for many of your own operators. These are the standard restriction estimators:

`eqsel` for =
`neqsel` for <>
`scalarltsel` for < or <=
`scalargtsel` for > or >=
It might seem a little odd that these are the categories, but they make sense if you think about it. = will typically accept only a small fraction of the rows in a table; <> will typically reject only a small fraction. < will accept a fraction that depends on where the given constant falls in the range of values for that table column (which, it just so happens, is information collected by `ANALYZE` and made available to the selectivity estimator). <= will accept a slightly larger fraction than < for the same comparison constant, but they're close enough to not be worth distinguishing, especially since we're not likely to do better than a rough guess anyhow. Similar remarks apply to > and >=.

You can frequently get away with using either `eqsel` or `neqsel` for operators that have very high or very low selectivity, even if they aren't really equality or inequality. For example, the approximate-equality geometric operators use `eqsel` on the assumption that they'll usually only match a small fraction of the entries in a table.

You can use `scalarltsel` and `scalargtsel` for comparisons on data types that have some sensible means of being converted into numeric scalars for range comparisons. If possible, add the data type to those understood by the routine `convert_to_scalar()` in `src/backend/utils/adt/selfuncs.c`. (Eventually, this routine should be replaced by per-data-type functions identified through a column of the `pg_type` system catalog; but that hasn't happened yet.) If you do not do this, things will still work, but the optimizer's estimates won't be as good as they could be.

There are additional selectivity functions designed for geometric operators in `src/backend/utils/adt/geo_selfuncs.c`: `areasel`, `positionsel`, and `contsel`. At this writing these are just stubs, but you may want to use them (or even better, improve them) anyway.

11.3.4. JOIN

The `JOIN` clause, if provided, names a join selectivity estimation function for the operator (note that this is a function name, not an operator name). `JOIN` clauses only make sense for binary operators that return `boolean`. The idea behind a join selectivity estimator is to guess what fraction of the rows in a pair of tables will satisfy a `WHERE`-clause condition of the form

```
table1.column1 OP table2.column2
```

for the current operator. As with the `RESTRICT` clause, this helps the optimizer very substantially by letting it figure out which of several possible join sequences is likely to take the least work.

As before, this chapter will make no attempt to explain how to write a join selectivity estimator function, but will just suggest that you use one of the standard estimators if one is applicable:

`eqjoinsel` for =
`neqjoinsel` for <>
`scalarltjoinsel` for < or <=
`scalargtjoinsel` for > or >=
`areajoinsel` for 2D area-based comparisons
`positionjoinsel` for 2D position-based comparisons
`contjoinsel` for 2D containment-based comparisons

11.3.5. HASHES

The `HASHES` clause, if present, tells the system that it is permissible to use the hash join method for a join based on this operator. `HASHES` only makes sense for binary operators that return `boolean`, and in practice the operator had better be equality for some data type.

The assumption underlying hash join is that the join operator can only return true for pairs of left and right values that hash to the same hash code. If two values get put in different hash buckets, the join will never compare them at all, implicitly assuming that the result of the join operator must be false. So it never makes sense to specify `HASHES` for operators that do not represent equality.

In fact, logical equality is not good enough either; the operator had better represent pure bitwise equality, because the hash function will be computed on the memory representation of the values regardless of what the bits mean. For example, equality of time intervals is not bitwise equality; the interval equality operator considers two time intervals equal if they have the same duration, whether or not their endpoints are identical. What this means is that a join using = between interval fields would yield different results if implemented as a hash join than if implemented another way, because a large fraction of the pairs that should match will hash to different values and will never be compared by the hash join. But if the optimizer chose to use a different kind of join, all the pairs that the equality operator says are equal will be found. We don't want that kind of inconsistency, so we don't mark interval equality as hashable.

There are also machine-dependent ways in which a hash join might fail to do the right thing. For example, if your data type is a structure in which there may be uninteresting pad bits, it's unsafe to mark the equality operator `HASHES`. (Unless, perhaps, you write your other operators to ensure that the unused bits are always zero.) Another example is that the floating-point data types are unsafe for hash joins. On machines that meet the IEEE floating-point standard, minus zero and plus zero are different values (different bit patterns) but they are defined to compare equal. So, if the equality operator on floating-point data types were marked `HASHES`, a minus zero and a plus zero would probably not be matched up by a hash join, but they would be matched up by any other join process.

The bottom line is that you should probably only use `HASHES` for equality operators that are (or could be) implemented by `memcmp()`.

11.3.6. MERGES (SORT1, SORT2, LTCMP, GTCMP)

The `MERGES` clause, if present, tells the system that it is permissible to use the merge join method for a join based on this operator. `MERGES` only makes sense for binary operators that return `boolean`, and in practice the operator must represent equality for some data type or pair of data types.

Merge join is based on the idea of sorting the left- and right-hand tables into order and then scanning them in parallel. So, both data types must be capable of being fully ordered, and the join operator must be one that can only succeed for pairs of values that fall at the “same place” in the sort order. In practice this means that the join operator must behave like equality. But unlike hash join, where the left and right data types had better be the same (or at least bitwise equivalent), it is possible to merge-join two distinct data types so long as they are logically compatible. For example, the `int2`-versus-`int4` equality operator is merge-joinable. We only need sorting operators that will bring both data types into a logically compatible sequence.

Execution of a merge join requires that the system be able to identify four operators related to the merge-join equality operator: less-than comparison for the left input data type, less-than comparison for the right input data type, less-than comparison between the two data types, and greater-than comparison between the two data types. (These are actually four distinct operators if the merge-joinable operator has two different input data types; but when the input types are the same the three less-than operators are all the same operator.) It is possible to specify these operators individually by name, as the `SORT1`, `SORT2`, `LTCMP`, and `GTCMP` options respectively. The system will fill in the default names <, <, <, > respectively if any of these are omitted when `MERGES` is specified. Also, `MERGES` will be assumed to be implied if any of these four operator options appear, so it is possible to specify just some of them and let the system fill in the rest.

The input data types of the four comparison operators can be deduced from the input types of the merge-joinable operator, so just as with `COMMUTATOR`, only the operator names need be given in these clauses. Unless you are using peculiar choices of operator names, it's sufficient to write `MERGES` and let the system fill in the details. (As with `COMMUTATOR` and `NEGATOR`, the system is able to make dummy operator entries if you happen to define the equality operator before the other ones.)

There are additional restrictions on operators that you mark merge-joinable. These restrictions are not currently checked by `CREATE OPERATOR`, but errors may occur when the operator is used if any are not true:

- A merge-joinable equality operator must have a merge-joinable commutator (itself if the two data types are the same, or a related equality operator if they are different).
- If there is a merge-joinable operator relating any two data types A and B, and another merge-joinable operator relating B to any third data type C, then A and C must also have a merge-joinable operator; in other words, having a merge-joinable operator must be transitive.
- Bizarre results will ensue at runtime if the four comparison operators you name do not sort the data values compatibly.

Note

In PostgreSQL versions before 7.3, the `MERGES` shorthand was not available: to make a merge-joinable operator one had to write both `SORT1` and `SORT2` explicitly. Also, the `LTCMP` and `GTCMP` options did not exist; the names of those operators were hardwired as < and > respectively.

Chapter 12. Extending SQL: Aggregates

Aggregate functions in PostgreSQL are expressed as *state values* and *state transition functions*. That is, an aggregate can be defined in terms of state that is modified whenever an input item is processed. To define a new aggregate function, one selects a data type for the state value, an initial value for the state, and a state transition function. The state transition function is just an ordinary function that could also be used outside the context of the aggregate. A *final function* can also be specified, in case the desired output of the aggregate is different from the data that needs to be kept in the running state value.

Thus, in addition to the input and result data types seen by a user of the aggregate, there is an internal state-value data type that may be different from both the input and result types.

If we define an aggregate that does not use a final function, we have an aggregate that computes a running function of the column values from each row. `Sum` is an example of this kind of aggregate. `Sum` starts at zero and always adds the current row's value to its running total. For example, if we want to make a `sum` aggregate to work on a data type for complex numbers, we only need the addition function for that data type. The aggregate definition is:

```
CREATE AGGREGATE complex_sum (
    sfunc = complex_add,
    basetype = complex,
    stype = complex,
    initcond = '(0,0)'
);

SELECT complex_sum(a) FROM test_complex;

 complex_sum
-------------
 (34,53.9)
```

(In practice, we'd just name the aggregate `sum`, and rely on PostgreSQL to figure out which kind of sum to apply to a column of type `complex`.)

The above definition of `sum` will return zero (the initial state condition) if there are no non-null input values. Perhaps we want to return NULL in that case instead --- the SQL standard expects `sum` to behave that way. We can do this simply by omitting the `initcond` phrase, so that the initial state condition is NULL. Ordinarily this would mean that the `sfunc` would need to check for a NULL state-condition input, but for `sum` and some other simple aggregates like `max` and `min`, it's sufficient to insert the first non-null input value into the state variable and then start applying the transition function at the second non-null input value. PostgreSQL will do that automatically if the initial condition is NULL and the transition function is marked “strict” (i.e., not to be called for NULL inputs).

Another bit of default behavior for a “strict” transition function is that the previous state value is retained unchanged whenever a NULL input value is encountered. Thus, null values are ignored. If you need some other behavior for NULL inputs, just define your transition function as non-strict, and code it to test for NULL inputs and do whatever is needed.

`Avg` (average) is a more complex example of an aggregate. It requires two pieces of running state: the sum of the inputs and the count of the number of inputs. The final result is obtained by dividing these quantities. Average is typically implemented by using a two-element array as the transition state value. For example, the built-in implementation of `avg(float8)` looks like:

```
CREATE AGGREGATE avg (
    sfunc = float8_accum,
    basetype = float8,
```

```
    stype = float8[],
    finalfunc = float8_avg,
    initcond = '{0,0}'
);
```

For further details see the description of the `CREATE AGGREGATE` command in the *Reference Manual*.

Chapter 13. The Rule System

Author

Written by Jan Wieck. Updates for 7.1 by Tom Lane.

13.1. Introduction

Production rule systems are conceptually simple, but there are many subtle points involved in actually using them. Some of these points and the theoretical foundations of the PostgreSQL rule system can be found in [ston90b].

Some other database systems define active database rules. These are usually stored procedures and triggers and are implemented in PostgreSQL as functions and triggers.

The query rewrite rule system (the *rule system* from now on) is totally different from stored procedures and triggers. It modifies queries to take rules into consideration, and then passes the modified query to the query planner for planning and execution. It is very powerful, and can be used for many things such as query language procedures, views, and versions. The power of this rule system is discussed in [ong90] as well as [ston90b].

13.2. What is a Query Tree?

To understand how the rule system works it is necessary to know when it is invoked and what its input and results are.

The rule system is located between the query parser and the planner. It takes the output of the parser, one query tree, and the rewrite rules from the `pg_rewrite` catalog, which are query trees too with some extra information, and creates zero or many query trees as result. So its input and output are always things the parser itself could have produced and thus, anything it sees is basically representable as an SQL statement.

Now what is a query tree? It is an internal representation of an SQL statement where the single parts that built it are stored separately. These query trees are visible when starting the PostgreSQL backend with debug level 4 and typing queries into the interactive backend interface. The rule actions in the `pg_rewrite` system catalog are also stored as query trees. They are not formatted like the debug output, but they contain exactly the same information.

Reading a query tree requires some experience and it was a hard time when I started to work on the rule system. I can remember that I was standing at the coffee machine and I saw the cup in a target list, water and coffee powder in a range table and all the buttons in a qualification expression. Since SQL representations of query trees are sufficient to understand the rule system, this document will not teach how to read them. It might help to learn it and the naming conventions are required in the later following descriptions.

13.2.1. The Parts of a Query tree

When reading the SQL representations of the query trees in this document it is necessary to be able to identify the parts the statement is broken into when it is in the query tree structure. The parts of a query tree are

the command type

This is a simple value telling which command (SELECT, INSERT, UPDATE, DELETE) produced the parse tree.

the range table

The range table is a list of relations that are used in the query. In a SELECT statement these are the relations given after the FROM keyword.

Every range table entry identifies a table or view and tells by which name it is called in the other parts of the query. In the query tree the range table entries are referenced by index rather than by name, so here it doesn't matter if there are duplicate names as it would in an SQL statement. This can happen after the range tables of rules have been merged in. The examples in this document will not have this situation.

the result relation

This is an index into the range table that identifies the relation where the results of the query go.

SELECT queries normally don't have a result relation. The special case of a SELECT INTO is mostly identical to a CREATE TABLE, INSERT ... SELECT sequence and is not discussed separately here.

On INSERT, UPDATE and DELETE queries the result relation is the table (or view!) where the changes take effect.

the target list

The target list is a list of expressions that define the result of the query. In the case of a SELECT, the expressions are what builds the final output of the query. They are the expressions between the SELECT and the FROM keywords. (* is just an abbreviation for all the attribute names of a relation. It is expanded by the parser into the individual attributes, so the rule system never sees it.)

DELETE queries don't need a target list because they don't produce any result. In fact the planner will add a special CTID entry to the empty target list. But this is after the rule system and will be discussed later. For the rule system the target list is empty.

In INSERT queries the target list describes the new rows that should go into the result relation. It is the expressions in the VALUES clause or the ones from the SELECT clause in INSERT ... SELECT. The first step of the rewrite process adds target list entries for any columns that were not assigned to by the original query and have defaults. Any remaining columns (with neither a given value nor a default) will be filled in by the planner with a constant NULL expression.

In UPDATE queries, the target list describes the new rows that should replace the old ones. In the rule system, it contains just the expressions from the SET attribute = expression part of the query. The planner will handle missing columns by inserting expressions that copy the values from the old row into the new one. And it will add the special CTID entry just as for DELETE too.

Every entry in the target list contains an expression that can be a constant value, a variable pointing to an attribute of one of the relations in the range table, a parameter, or an expression tree made of function calls, constants, variables, operators etc.

the qualification

The query's qualification is an expression much like one of those contained in the target list entries. The result value of this expression is a Boolean that tells if the operation (INSERT, UPDATE, DELETE or SELECT) for the final result row should be executed or not. It is the WHERE clause of an SQL statement.

the join tree

The query's join tree shows the structure of the FROM clause. For a simple query like SELECT FROM a, b, c the join tree is just a list of the FROM items, because we are allowed to join them in any order. But when JOIN expressions --- particularly outer joins --- are used, we have to join in the order shown by the joins. The join tree shows the structure of the JOIN expressions. The restrictions associated with particular JOIN clauses (from ON or USING expressions) are stored

as qualification expressions attached to those join tree nodes. It turns out to be convenient to store the top-level WHERE expression as a qualification attached to the top-level join tree item, too. So really the join tree represents both the FROM and WHERE clauses of a SELECT.

the others

The other parts of the query tree like the ORDER BY clause aren't of interest here. The rule system substitutes entries there while applying rules, but that doesn't have much to do with the fundamentals of the rule system.

13.3. Views and the Rule System

13.3.1. Implementation of Views in PostgreSQL

Views in PostgreSQL are implemented using the rule system. In fact there is essentially no difference between

```
CREATE VIEW myview AS SELECT * FROM mytab;
```

compared against the two commands

```
CREATE TABLE myview (same attribute list as for mytab);
CREATE RULE "_RETURN" AS ON SELECT TO myview DO INSTEAD
    SELECT * FROM mytab;
```

because this is exactly what the CREATE VIEW command does internally. This has some side effects. One of them is that the information about a view in the PostgreSQL system catalogs is exactly the same as it is for a table. So for the query parser, there is absolutely no difference between a table and a view. They are the same thing - relations. That is the important one for now.

13.3.2. How SELECT Rules Work

Rules ON SELECT are applied to all queries as the last step, even if the command given is an INSERT, UPDATE or DELETE. And they have different semantics from the others in that they modify the parse tree in place instead of creating a new one. So SELECT rules are described first.

Currently, there can be only one action in an ON SELECT rule, and it must be an unconditional SELECT action that is INSTEAD. This restriction was required to make rules safe enough to open them for ordinary users and it restricts rules ON SELECT to real view rules.

The examples for this document are two join views that do some calculations and some more views using them in turn. One of the two first views is customized later by adding rules for INSERT, UPDATE and DELETE operations so that the final result will be a view that behaves like a real table with some magic functionality. It is not such a simple example to start from and this makes things harder to get into. But it's better to have one example that covers all the points discussed step by step rather than having many different ones that might mix up in mind.

The database needed to play with the examples is named `al_bundy`. You'll see soon why this is the database name. And it needs the procedural language PL/pgSQL installed, because we need a little min() function returning the lower of 2 integer values. We create that as

```
CREATE FUNCTION min(integer, integer) RETURNS integer AS '
    BEGIN
        IF $1 < $2 THEN
            RETURN $1;
        END IF;
        RETURN $2;
    END;
' LANGUAGE plpgsql;
```

The real tables we need in the first two rule system descriptions are these:

```
CREATE TABLE shoe_data (
    shoename   char(10),      -- primary key
    sh_avail   integer,       -- available # of pairs
    slcolor    char(10),      -- preferred shoelace color
    slminlen   float,         -- miminum shoelace length
    slmaxlen   float,         -- maximum shoelace length
    slunit     char(8)        -- length unit
);

CREATE TABLE shoelace_data (
    sl_name    char(10),      -- primary key
    sl_avail   integer,       -- available # of pairs
    sl_color   char(10),      -- shoelace color
    sl_len     float,         -- shoelace length
    sl_unit    char(8)        -- length unit
);

CREATE TABLE unit (
    un_name    char(8),       -- the primary key
    un_fact    float          -- factor to transform to cm
);
```

I think most of us wear shoes and can realize that this is really useful data. Well there are shoes out in the world that don't require shoelaces, but this doesn't make Al's life easier and so we ignore it.

The views are created as

```
CREATE VIEW shoe AS
    SELECT sh.shoename,
           sh.sh_avail,
           sh.slcolor,
           sh.slminlen,
           sh.slminlen * un.un_fact AS slminlen_cm,
           sh.slmaxlen,
           sh.slmaxlen * un.un_fact AS slmaxlen_cm,
           sh.slunit
      FROM shoe_data sh, unit un
     WHERE sh.slunit = un.un_name;

CREATE VIEW shoelace AS
    SELECT s.sl_name,
           s.sl_avail,
           s.sl_color,
           s.sl_len,
           s.sl_unit,
           s.sl_len * u.un_fact AS sl_len_cm
      FROM shoelace_data s, unit u
     WHERE s.sl_unit = u.un_name;

CREATE VIEW shoe_ready AS
    SELECT rsh.shoename,
           rsh.sh_avail,
           rsl.sl_name,
           rsl.sl_avail,
           min(rsh.sh_avail, rsl.sl_avail) AS total_avail
      FROM shoe rsh, shoelace rsl
     WHERE rsl.sl_color = rsh.slcolor
```

```
        AND rsl.sl_len_cm >= rsh.slminlen_cm
        AND rsl.sl_len_cm <= rsh.slmaxlen_cm;
```

The CREATE VIEW command for the `shoelace` view (which is the simplest one we have) will create a relation shoelace and an entry in `pg_rewrite` that tells that there is a rewrite rule that must be applied whenever the relation shoelace is referenced in a query's range table. The rule has no rule qualification (discussed later, with the non SELECT rules, since SELECT rules currently cannot have them) and it is INSTEAD. Note that rule qualifications are not the same as query qualifications! The rule's action has a query qualification.

The rule's action is one query tree that is a copy of the SELECT statement in the view creation command.

Note

The two extra range table entries for NEW and OLD (named *NEW* and *CURRENT* for historical reasons in the printed query tree) you can see in the `pg_rewrite` entry aren't of interest for SELECT rules.

Now we populate `unit`, `shoe_data` and `shoelace_data` and Al types the first SELECT in his life:

```
al_bundy=> INSERT INTO unit VALUES ('cm', 1.0);
al_bundy=> INSERT INTO unit VALUES ('m', 100.0);
al_bundy=> INSERT INTO unit VALUES ('inch', 2.54);
al_bundy=>
al_bundy=> INSERT INTO shoe_data VALUES
al_bundy->     ('sh1', 2, 'black', 70.0, 90.0, 'cm');
al_bundy=> INSERT INTO shoe_data VALUES
al_bundy->     ('sh2', 0, 'black', 30.0, 40.0, 'inch');
al_bundy=> INSERT INTO shoe_data VALUES
al_bundy->     ('sh3', 4, 'brown', 50.0, 65.0, 'cm');
al_bundy=> INSERT INTO shoe_data VALUES
al_bundy->     ('sh4', 3, 'brown', 40.0, 50.0, 'inch');
al_bundy=>
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl1', 5, 'black', 80.0, 'cm');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl2', 6, 'black', 100.0, 'cm');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl3', 0, 'black', 35.0 , 'inch');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl4', 8, 'black', 40.0 , 'inch');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl5', 4, 'brown', 1.0 , 'm');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl6', 0, 'brown', 0.9 , 'm');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl7', 7, 'brown', 60 , 'cm');
al_bundy=> INSERT INTO shoelace_data VALUES
al_bundy->     ('sl8', 1, 'brown', 40 , 'inch');
al_bundy=>
al_bundy=> SELECT * FROM shoelace;
sl_name   |sl_avail|sl_color  |sl_len|sl_unit |sl_len_cm
----------+--------+----------+------+--------+---------
sl1       |       5|black     |    80|cm      |       80
sl2       |       6|black     |   100|cm      |      100
sl7       |       7|brown     |    60|cm      |       60
sl3       |       0|black     |    35|inch    |     88.9
sl4       |       8|black     |    40|inch    |    101.6
```

```
sl8       |       1|brown     |    40|inch    |    101.6
sl5       |       4|brown     |     1|m       |      100
sl6       |       0|brown     |   0.9|m       |       90
(8 rows)
```

It's the simplest SELECT Al can do on our views, so we take this to explain the basics of view rules. The `SELECT * FROM shoelace` was interpreted by the parser and produced the parse tree

```
SELECT shoelace.sl_name, shoelace.sl_avail,
       shoelace.sl_color, shoelace.sl_len,
       shoelace.sl_unit, shoelace.sl_len_cm
  FROM shoelace shoelace;
```

and this is given to the rule system. The rule system walks through the range table and checks if there are rules in `pg_rewrite` for any relation. When processing the range table entry for `shoelace` (the only one up to now) it finds the `_RETURN` rule with the parse tree

```
SELECT s.sl_name, s.sl_avail,
       s.sl_color, s.sl_len, s.sl_unit,
       float8mul(s.sl_len, u.un_fact) AS sl_len_cm
  FROM shoelace *OLD*, shoelace *NEW*,
       shoelace_data s, unit u
 WHERE bpchareq(s.sl_unit, u.un_name);
```

Note that the parser changed the calculation and qualification into calls to the appropriate functions. But in fact this changes nothing.

To expand the view, the rewriter simply creates a subselect range-table entry containing the rule's action parse tree, and substitutes this range table entry for the original one that referenced the view. The resulting rewritten parse tree is almost the same as if Al had typed

```
SELECT shoelace.sl_name, shoelace.sl_avail,
       shoelace.sl_color, shoelace.sl_len,
       shoelace.sl_unit, shoelace.sl_len_cm
  FROM (SELECT s.sl_name,
               s.sl_avail,
               s.sl_color,
               s.sl_len,
               s.sl_unit,
               s.sl_len * u.un_fact AS sl_len_cm
          FROM shoelace_data s, unit u
         WHERE s.sl_unit = u.un_name) shoelace;
```

There is one difference however: the sub-query's range table has two extra entries shoelace *OLD*, shoelace *NEW*. These entries don't participate directly in the query, since they aren't referenced by the sub-query's join tree or target list. The rewriter uses them to store the access permission check info that was originally present in the range-table entry that referenced the view. In this way, the executor will still check that the user has proper permissions to access the view, even though there's no direct use of the view in the rewritten query.

That was the first rule applied. The rule system will continue checking the remaining range-table entries in the top query (in this example there are no more), and it will recursively check the range-table entries in the added sub-query to see if any of them reference views. (But it won't expand *OLD* or *NEW* --- otherwise we'd have infinite recursion!) In this example, there are no rewrite rules for shoelace_data or unit, so rewriting is complete and the above is the final result given to the planner.

Now we face Al with the problem that the Blues Brothers appear in his shop and want to buy some new shoes, and as the Blues Brothers are, they want to wear the same shoes. And they want to wear them immediately, so they need shoelaces too.

Al needs to know for which shoes currently in the store he has the matching shoelaces (color and size) and where the total number of exactly matching pairs is greater or equal to two. We teach him what to do and he asks his database:

```
al_bundy=> SELECT * FROM shoe_ready WHERE total_avail >= 2;
shoename  |sh_avail|sl_name   |sl_avail|total_avail
----------+--------+----------+--------+-----------
sh1       |       2|sl1       |       5|          2
sh3       |       4|sl7       |       7|          4
(2 rows)
```

Al is a shoe guru and so he knows that only shoes of type sh1 would fit (shoelace sl7 is brown and shoes that need brown shoelaces aren't shoes the Blues Brothers would ever wear).

The output of the parser this time is the parse tree

```
SELECT shoe_ready.shoename, shoe_ready.sh_avail,
       shoe_ready.sl_name, shoe_ready.sl_avail,
       shoe_ready.total_avail
  FROM shoe_ready shoe_ready
 WHERE int4ge(shoe_ready.total_avail, 2);
```

The first rule applied will be the one for the `shoe_ready` view and it results in the parse tree

```
SELECT shoe_ready.shoename, shoe_ready.sh_avail,
       shoe_ready.sl_name, shoe_ready.sl_avail,
       shoe_ready.total_avail
  FROM (SELECT rsh.shoename,
               rsh.sh_avail,
               rsl.sl_name,
               rsl.sl_avail,
               min(rsh.sh_avail, rsl.sl_avail) AS total_avail
          FROM shoe rsh, shoelace rsl
         WHERE rsl.sl_color = rsh.slcolor
           AND rsl.sl_len_cm >= rsh.slminlen_cm
           AND rsl.sl_len_cm <= rsh.slmaxlen_cm) shoe_ready
 WHERE int4ge(shoe_ready.total_avail, 2);
```

Similarly, the rules for `shoe` and `shoelace` are substituted into the range table of the sub-query, leading to a three-level final query tree:

```
SELECT shoe_ready.shoename, shoe_ready.sh_avail,
       shoe_ready.sl_name, shoe_ready.sl_avail,
       shoe_ready.total_avail
  FROM (SELECT rsh.shoename,
               rsh.sh_avail,
               rsl.sl_name,
               rsl.sl_avail,
               min(rsh.sh_avail, rsl.sl_avail) AS total_avail
          FROM (SELECT sh.shoename,
                       sh.sh_avail,
                       sh.slcolor,
                       sh.slminlen,
                       sh.slminlen * un.un_fact AS slminlen_cm,
                       sh.slmaxlen,
                       sh.slmaxlen * un.un_fact AS slmaxlen_cm,
                       sh.slunit
                  FROM shoe_data sh, unit un
                 WHERE sh.slunit = un.un_name) rsh,
```

```
                (SELECT s.sl_name,
                        s.sl_avail,
                        s.sl_color,
                        s.sl_len,
                        s.sl_unit,
                        s.sl_len * u.un_fact AS sl_len_cm
                   FROM shoelace_data s, unit u
                  WHERE s.sl_unit = u.un_name) rsl
          WHERE rsl.sl_color = rsh.slcolor
            AND rsl.sl_len_cm >= rsh.slminlen_cm
            AND rsl.sl_len_cm <= rsh.slmaxlen_cm) shoe_ready
 WHERE int4ge(shoe_ready.total_avail, 2);
```

It turns out that the planner will collapse this tree into a two-level query tree: the bottommost selects will be “pulled up” into the middle select since there's no need to process them separately. But the middle select will remain separate from the top, because it contains aggregate functions. If we pulled those up it would change the behavior of the topmost select, which we don't want. However, collapsing the query tree is an optimization that the rewrite system doesn't have to concern itself with.

Note

There is currently no recursion stopping mechanism for view rules in the rule system (only for the other kinds of rules). This doesn't hurt much, because the only way to push this into an endless loop (blowing up the backend until it reaches the memory limit) is to create tables and then setup the view rules by hand with CREATE RULE in such a way, that one selects from the other that selects from the one. This could never happen if CREATE VIEW is used because for the first CREATE VIEW, the second relation does not exist and thus the first view cannot select from the second.

13.3.3. View Rules in Non-SELECT Statements

Two details of the parse tree aren't touched in the description of view rules above. These are the command type and the result relation. In fact, view rules don't need this information.

There are only a few differences between a parse tree for a SELECT and one for any other command. Obviously they have another command type and this time the result relation points to the range table entry where the result should go. Everything else is absolutely the same. So having two tables t1 and t2 with attributes a and b, the parse trees for the two statements

```
SELECT t2.b FROM t1, t2 WHERE t1.a = t2.a;

UPDATE t1 SET b = t2.b WHERE t1.a = t2.a;
```

are nearly identical.

- The range tables contain entries for the tables t1 and t2.
- The target lists contain one variable that points to attribute b of the range table entry for table t2.
- The qualification expressions compare the attributes a of both ranges for equality.
- The join trees show a simple join between t1 and t2.

The consequence is, that both parse trees result in similar execution plans. They are both joins over the two tables. For the UPDATE the missing columns from t1 are added to the target list by the planner and the final parse tree will read as

```
UPDATE t1 SET a = t1.a, b = t2.b WHERE t1.a = t2.a;
```

and thus the executor run over the join will produce exactly the same result set as a

```
SELECT t1.a, t2.b FROM t1, t2 WHERE t1.a = t2.a;
```

will do. But there is a little problem in UPDATE. The executor does not care what the results from the join it is doing are meant for. It just produces a result set of rows. The difference that one is a SELECT command and the other is an UPDATE is handled in the caller of the executor. The caller still knows (looking at the parse tree) that this is an UPDATE, and he knows that this result should go into table t1. But which of the rows that are there has to be replaced by the new row?

To resolve this problem, another entry is added to the target list in UPDATE (and also in DELETE) statements: the current tuple ID (CTID). This is a system attribute containing the file block number and position in the block for the row. Knowing the table, the CTID can be used to retrieve the original t1 row to be updated. After adding the CTID to the target list, the query actually looks like

```
SELECT t1.a, t2.b, t1.ctid FROM t1, t2 WHERE t1.a = t2.a;
```

Now another detail of PostgreSQL enters the stage. At this moment, table rows aren't overwritten and this is why ABORT TRANSACTION is fast. In an UPDATE, the new result row is inserted into the table (after stripping CTID) and in the tuple header of the row that CTID pointed to the `cmax` and `xmax` entries are set to the current command counter and current transaction ID. Thus the old row is hidden and after the transaction committed the vacuum cleaner can really move it out.

Knowing all that, we can simply apply view rules in absolutely the same way to any command. There is no difference.

13.3.4. The Power of Views in PostgreSQL

The above demonstrates how the rule system incorporates view definitions into the original parse tree. In the second example a simple SELECT from one view created a final parse tree that is a join of 4 tables (unit is used twice with different names).

13.3.4.1. Benefits

The benefit of implementing views with the rule system is, that the planner has all the information about which tables have to be scanned plus the relationships between these tables plus the restrictive qualifications from the views plus the qualifications from the original query in one single parse tree. And this is still the situation when the original query is already a join over views. Now the planner has to decide which is the best path to execute the query. The more information the planner has, the better this decision can be. And the rule system as implemented in PostgreSQL ensures, that this is all information available about the query up to now.

13.3.5. What about updating a view?

What happens if a view is named as the target relation for an INSERT, UPDATE, or DELETE? After doing the substitutions described above, we will have a query tree in which the result relation points at a subquery range table entry. This will not work, so the rewriter throws an error if it sees it has produced such a thing.

To change this we can define rules that modify the behavior of non-SELECT queries. This is the topic of the next section.

13.4. Rules on INSERT, UPDATE and DELETE

13.4.1. Differences from View Rules

Rules that are defined ON INSERT, UPDATE and DELETE are totally different from the view rules described in the previous section. First, their CREATE RULE command allows more:

- They can have no action.

- They can have multiple actions.
- The keyword INSTEAD is optional.
- The pseudo relations NEW and OLD become useful.
- They can have rule qualifications.

Second, they don't modify the parse tree in place. Instead they create zero or many new parse trees and can throw away the original one.

13.4.2. How These Rules Work

Keep the syntax

```
CREATE RULE rule_name AS ON event
    TO object [WHERE rule_qualification]
    DO [INSTEAD] [action | (actions) | NOTHING];
```

in mind. In the following, *update rules* means rules that are defined ON INSERT, UPDATE or DELETE.

Update rules get applied by the rule system when the result relation and the command type of a parse tree are equal to the object and event given in the CREATE RULE command. For update rules, the rule system creates a list of parse trees. Initially the parse tree list is empty. There can be zero (NOTHING keyword), one or multiple actions. To simplify, we look at a rule with one action. This rule can have a qualification or not and it can be INSTEAD or not.

What is a rule qualification? It is a restriction that tells when the actions of the rule should be done and when not. This qualification can only reference the NEW and/or OLD pseudo relations which are basically the relation given as object (but with a special meaning).

So we have four cases that produce the following parse trees for a one-action rule.

- No qualification and not INSTEAD:
  - The parse tree from the rule action where the original parse tree's qualification has been added.
- No qualification but INSTEAD:
  - The parse tree from the rule action where the original parse tree's qualification has been added.
- Qualification given and not INSTEAD:
  - The parse tree from the rule action where the rule qualification and the original parse tree's qualification have been added.
- Qualification given and INSTEAD:
  - The parse tree from the rule action where the rule qualification and the original parse tree's qualification have been added.
  - The original parse tree where the negated rule qualification has been added.

Finally, if the rule is not INSTEAD, the unchanged original parse tree is added to the list. Since only qualified INSTEAD rules already add the original parse tree, we end up with either one or two output parse trees for a rule with one action.

For ON INSERT rules, the original query (if not suppressed by INSTEAD) is done before any actions added by rules. This allows the actions to see the inserted row(s). But for ON UPDATE and ON DELETE rules, the original query is done after the actions added by rules. This ensures that the actions

can see the to-be-updated or to-be-deleted rows; otherwise, the actions might do nothing because they find no rows matching their qualifications.

The parse trees generated from rule actions are thrown into the rewrite system again and maybe more rules get applied resulting in more or less parse trees. So the parse trees in the rule actions must have either another command type or another result relation. Otherwise this recursive process will end up in a loop. There is a compiled-in recursion limit of currently 100 iterations. If after 100 iterations there are still update rules to apply the rule system assumes a loop over multiple rule definitions and reports an error.

The parse trees found in the actions of the `pg_rewrite` system catalog are only templates. Since they can reference the range-table entries for NEW and OLD, some substitutions have to be made before they can be used. For any reference to NEW, the target list of the original query is searched for a corresponding entry. If found, that entry's expression replaces the reference. Otherwise NEW means the same as OLD (for an UPDATE) or is replaced by NULL (for an INSERT). Any reference to OLD is replaced by a reference to the range-table entry which is the result relation.

After we are done applying update rules, we apply view rules to the produced parse tree(s). Views cannot insert new update actions so there is no need to apply update rules to the output of view rewriting.

13.4.2.1. A First Rule Step by Step

We want to trace changes to the sl_avail column in the `shoelace_data` relation. So we setup a log table and a rule that conditionally writes a log entry when an UPDATE is performed on `shoelace_data`.

```
CREATE TABLE shoelace_log (
    sl_name    char(10),      -- shoelace changed
    sl_avail   integer,       -- new available value
    log_who    text,          -- who did it
    log_when   timestamp      -- when
);

CREATE RULE log_shoelace AS ON UPDATE TO shoelace_data
    WHERE NEW.sl_avail != OLD.sl_avail
    DO INSERT INTO shoelace_log VALUES (
                                    NEW.sl_name,
                                    NEW.sl_avail,
                                    current_user,
                                    current_timestamp
                                );
```

Now Al does

```
al_bundy=> UPDATE shoelace_data SET sl_avail = 6

al_bundy->     WHERE sl_name = 'sl7';
```

and we look at the log table.

```
al_bundy=> SELECT * FROM shoelace_log;
sl_name   |sl_avail|log_who|log_when
----------+--------+-------+--------------------------------
sl7       |       6|Al     |Tue Oct 20 16:14:45 1998 MET DST
(1 row)
```

That's what we expected. What happened in the background is the following. The parser created the parse tree (this time the parts of the original parse tree are highlighted because the base of operations is the rule action for update rules).

```
UPDATE shoelace_data SET sl_avail = 6
  FROM shoelace_data shoelace_data
 WHERE bpchareq(shoelace_data.sl_name, 'sl7');
```

There is a rule `log_shoelace` that is ON UPDATE with the rule qualification expression

```
int4ne(NEW.sl_avail, OLD.sl_avail)
```

and one action

```
INSERT INTO shoelace_log VALUES(
       *NEW*.sl_name, *NEW*.sl_avail,
       current_user, current_timestamp)
  FROM shoelace_data *NEW*, shoelace_data *OLD*;
```

This is a little strange-looking since you can't normally write INSERT ... VALUES ... FROM. The FROM clause here is just to indicate that there are range-table entries in the parse tree for *NEW* and *OLD*. These are needed so that they can be referenced by variables in the INSERT command's query tree.

The rule is a qualified non-INSTEAD rule, so the rule system has to return two parse trees: the modified rule action and the original parse tree. In the first step the range table of the original query is incorporated into the rule's action parse tree. This results in

```
INSERT INTO shoelace_log VALUES(
       *NEW*.sl_name, *NEW*.sl_avail,
       current_user, current_timestamp)
  FROM shoelace_data *NEW*, shoelace_data *OLD*,
       shoelace_data shoelace_data;
```

In step 2 the rule qualification is added to it, so the result set is restricted to rows where sl_avail changes.

```
INSERT INTO shoelace_log VALUES(
       *NEW*.sl_name, *NEW*.sl_avail,
       current_user, current_timestamp)
  FROM shoelace_data *NEW*, shoelace_data *OLD*,
       shoelace_data shoelace_data
 WHERE int4ne(*NEW*.sl_avail, *OLD*.sl_avail);
```

This is even stranger-looking, since INSERT ... VALUES doesn't have a WHERE clause either, but the planner and executor will have no difficulty with it. They need to support this same functionality anyway for INSERT ... SELECT.

In step 3 the original parse tree's qualification is added, restricting the result set further to only the rows touched by the original parse tree.

```
INSERT INTO shoelace_log VALUES(
       *NEW*.sl_name, *NEW*.sl_avail,
       current_user, current_timestamp)
  FROM shoelace_data *NEW*, shoelace_data *OLD*,
       shoelace_data shoelace_data
 WHERE int4ne(*NEW*.sl_avail, *OLD*.sl_avail)
   AND bpchareq(shoelace_data.sl_name, 'sl7');
```

Step 4 replaces NEW references by the target list entries from the original parse tree or by the matching variable references from the result relation.

```
INSERT INTO shoelace_log VALUES(
       shoelace_data.sl_name, 6,
       current_user, current_timestamp)
```

```
  FROM shoelace_data *NEW*, shoelace_data *OLD*,
       shoelace_data shoelace_data
 WHERE int4ne(6, *OLD*.sl_avail)
   AND bpchareq(shoelace_data.sl_name, 'sl7');
```

Step 5 changes OLD references into result relation references.

```
INSERT INTO shoelace_log VALUES(
       shoelace_data.sl_name, 6,
       current_user, current_timestamp)
  FROM shoelace_data *NEW*, shoelace_data *OLD*,
       shoelace_data shoelace_data
 WHERE int4ne(6, shoelace_data.sl_avail)
   AND bpchareq(shoelace_data.sl_name, 'sl7');
```

That's it. Since the rule is not INSTEAD, we also output the original parse tree. In short, the output from the rule system is a list of two parse trees that are the same as the statements:

```
INSERT INTO shoelace_log VALUES(
       shoelace_data.sl_name, 6,
       current_user, current_timestamp)
  FROM shoelace_data
 WHERE 6 != shoelace_data.sl_avail
   AND shoelace_data.sl_name = 'sl7';

UPDATE shoelace_data SET sl_avail = 6
 WHERE sl_name = 'sl7';
```

These are executed in this order and that is exactly what the rule defines. The substitutions and the qualifications added ensure that if the original query would be, say,

```
UPDATE shoelace_data SET sl_color = 'green'
 WHERE sl_name = 'sl7';
```

no log entry would get written. This time the original parse tree does not contain a target list entry for sl_avail, so NEW.sl_avail will get replaced by shoelace_data.sl_avail resulting in the extra query

```
INSERT INTO shoelace_log VALUES(
       shoelace_data.sl_name, shoelace_data.sl_avail,
       current_user, current_timestamp)
  FROM shoelace_data
 WHERE shoelace_data.sl_avail != shoelace_data.sl_avail
   AND shoelace_data.sl_name = 'sl7';
```

and that qualification will never be true. It will also work if the original query modifies multiple rows. So if Al would issue the command

```
UPDATE shoelace_data SET sl_avail = 0
 WHERE sl_color = 'black';
```

four rows in fact get updated (sl1, sl2, sl3 and sl4). But sl3 already has sl_avail = 0. This time, the original parse trees qualification is different and that results in the extra parse tree

```
INSERT INTO shoelace_log SELECT
       shoelace_data.sl_name, 0,
       current_user, current_timestamp
  FROM shoelace_data
 WHERE 0 != shoelace_data.sl_avail
   AND shoelace_data.sl_color = 'black';
```

This parse tree will surely insert three new log entries. And that's absolutely correct.

Here we can see why it is important that the original parse tree is executed last. If the UPDATE would have been executed first, all the rows are already set to zero, so the logging INSERT would not find any row where 0 != shoelace_data.sl_avail.

13.4.3. Cooperation with Views

A simple way to protect view relations from the mentioned possibility that someone can try to INSERT, UPDATE and DELETE on them is to let those parse trees get thrown away. We create the rules

```
CREATE RULE shoe_ins_protect AS ON INSERT TO shoe
    DO INSTEAD NOTHING;
CREATE RULE shoe_upd_protect AS ON UPDATE TO shoe
    DO INSTEAD NOTHING;
CREATE RULE shoe_del_protect AS ON DELETE TO shoe
    DO INSTEAD NOTHING;
```

If Al now tries to do any of these operations on the view relation `shoe`, the rule system will apply the rules. Since the rules have no actions and are INSTEAD, the resulting list of parse trees will be empty and the whole query will become nothing because there is nothing left to be optimized or executed after the rule system is done with it.

A more sophisticated way to use the rule system is to create rules that rewrite the parse tree into one that does the right operation on the real tables. To do that on the `shoelace` view, we create the following rules:

```
CREATE RULE shoelace_ins AS ON INSERT TO shoelace
    DO INSTEAD
    INSERT INTO shoelace_data VALUES (
           NEW.sl_name,
           NEW.sl_avail,
           NEW.sl_color,
           NEW.sl_len,
           NEW.sl_unit);

CREATE RULE shoelace_upd AS ON UPDATE TO shoelace
    DO INSTEAD
    UPDATE shoelace_data SET
           sl_name = NEW.sl_name,
           sl_avail = NEW.sl_avail,
           sl_color = NEW.sl_color,
           sl_len = NEW.sl_len,
           sl_unit = NEW.sl_unit
     WHERE sl_name = OLD.sl_name;

CREATE RULE shoelace_del AS ON DELETE TO shoelace
    DO INSTEAD
    DELETE FROM shoelace_data
     WHERE sl_name = OLD.sl_name;
```

Now there is a pack of shoelaces arriving in Al's shop and it has a big part list. Al is not that good in calculating and so we don't want him to manually update the shoelace view. Instead we setup two little tables, one where he can insert the items from the part list and one with a special trick. The create commands for these are:

```
CREATE TABLE shoelace_arrive (
    arr_name    char(10),
    arr_quant   integer
```

```
);

CREATE TABLE shoelace_ok (
    ok_name     char(10),
    ok_quant    integer
);

CREATE RULE shoelace_ok_ins AS ON INSERT TO shoelace_ok
    DO INSTEAD
    UPDATE shoelace SET
           sl_avail = sl_avail + NEW.ok_quant
     WHERE sl_name = NEW.ok_name;
```

Now Al can sit down and do whatever until

```
al_bundy=> SELECT * FROM shoelace_arrive;
arr_name  |arr_quant
----------+---------
sl3       |       10
sl6       |       20
sl8       |       20
(3 rows)
```

is exactly what's on the part list. We take a quick look at the current data,

```
al_bundy=> SELECT * FROM shoelace;
sl_name   |sl_avail|sl_color  |sl_len|sl_unit |sl_len_cm
----------+--------+----------+------+--------+---------
sl1       |       5|black     |    80|cm      |       80
sl2       |       6|black     |   100|cm      |      100
sl7       |       6|brown     |    60|cm      |       60
sl3       |       0|black     |    35|inch    |     88.9
sl4       |       8|black     |    40|inch    |    101.6
sl8       |       1|brown     |    40|inch    |    101.6
sl5       |       4|brown     |     1|m       |      100
sl6       |       0|brown     |   0.9|m       |       90
(8 rows)
```

move the arrived shoelaces in

```
al_bundy=> INSERT INTO shoelace_ok SELECT * FROM shoelace_arrive;
```

and check the results

```
al_bundy=> SELECT * FROM shoelace ORDER BY sl_name;
sl_name   |sl_avail|sl_color  |sl_len|sl_unit |sl_len_cm
----------+--------+----------+------+--------+---------
sl1       |       5|black     |    80|cm      |       80
sl2       |       6|black     |   100|cm      |      100
sl7       |       6|brown     |    60|cm      |       60
sl4       |       8|black     |    40|inch    |    101.6
sl3       |      10|black     |    35|inch    |     88.9
sl8       |      21|brown     |    40|inch    |    101.6
sl5       |       4|brown     |     1|m       |      100
sl6       |      20|brown     |   0.9|m       |       90
(8 rows)

al_bundy=> SELECT * FROM shoelace_log;
sl_name   |sl_avail|log_who|log_when
```

```
----------+--------+-------+--------------------------------
sl7       |       6|Al     |Tue Oct 20 19:14:45 1998 MET DST
sl3       |      10|Al     |Tue Oct 20 19:25:16 1998 MET DST
sl6       |      20|Al     |Tue Oct 20 19:25:16 1998 MET DST
sl8       |      21|Al     |Tue Oct 20 19:25:16 1998 MET DST
(4 rows)
```

It's a long way from the one INSERT ... SELECT to these results. And its description will be the last in this document (but not the last example :-). First there was the parser's output

```
INSERT INTO shoelace_ok SELECT
       shoelace_arrive.arr_name, shoelace_arrive.arr_quant
  FROM shoelace_arrive shoelace_arrive, shoelace_ok shoelace_ok;
```

Now the first rule `shoelace_ok_ins` is applied and turns it into

```
UPDATE shoelace SET
       sl_avail = int4pl(shoelace.sl_avail,
 shoelace_arrive.arr_quant)
  FROM shoelace_arrive shoelace_arrive, shoelace_ok shoelace_ok,
       shoelace_ok *OLD*, shoelace_ok *NEW*,
       shoelace shoelace
 WHERE bpchareq(shoelace.sl_name, showlace_arrive.arr_name);
```

and throws away the original INSERT on `shoelace_ok`. This rewritten query is passed to the rule system again and the second applied rule `shoelace_upd` produced

```
UPDATE shoelace_data SET
       sl_name = shoelace.sl_name,
       sl_avail = int4pl(shoelace.sl_avail,
 shoelace_arrive.arr_quant),
       sl_color = shoelace.sl_color,
       sl_len = shoelace.sl_len,
       sl_unit = shoelace.sl_unit
  FROM shoelace_arrive shoelace_arrive, shoelace_ok shoelace_ok,
       shoelace_ok *OLD*, shoelace_ok *NEW*,
       shoelace shoelace, shoelace *OLD*,
       shoelace *NEW*, shoelace_data showlace_data
 WHERE bpchareq(shoelace.sl_name, showlace_arrive.arr_name)
   AND bpchareq(shoelace_data.sl_name, shoelace.sl_name);
```

Again it's an INSTEAD rule and the previous parse tree is trashed. Note that this query still uses the view `shoelace`. But the rule system isn't finished with this loop so it continues and applies the `_RETURN` rule on it and we get

```
UPDATE shoelace_data SET
       sl_name = s.sl_name,
       sl_avail = int4pl(s.sl_avail, shoelace_arrive.arr_quant),
       sl_color = s.sl_color,
       sl_len = s.sl_len,
       sl_unit = s.sl_unit
  FROM shoelace_arrive shoelace_arrive, shoelace_ok shoelace_ok,
       shoelace_ok *OLD*, shoelace_ok *NEW*,
       shoelace shoelace, shoelace *OLD*,
       shoelace *NEW*, shoelace_data showlace_data,
       shoelace *OLD*, shoelace *NEW*,
       shoelace_data s, unit u
 WHERE bpchareq(s.sl_name, showlace_arrive.arr_name)
   AND bpchareq(shoelace_data.sl_name, s.sl_name);
```

Again an update rule has been applied and so the wheel turns on and we are in rewrite round 3. This time rule `log_shoelace` gets applied, producing the extra parse tree

```
INSERT INTO shoelace_log SELECT
       s.sl_name,
       int4pl(s.sl_avail, shoelace_arrive.arr_quant),
       current_user,
       current_timestamp
  FROM shoelace_arrive shoelace_arrive, shoelace_ok shoelace_ok,
       shoelace_ok *OLD*, shoelace_ok *NEW*,
       shoelace shoelace, shoelace *OLD*,
       shoelace *NEW*, shoelace_data showlace_data,
       shoelace *OLD*, shoelace *NEW*,
       shoelace_data s, unit u,
       shoelace_data *OLD*, shoelace_data *NEW*
       shoelace_log shoelace_log
 WHERE bpchareq(s.sl_name,  showlace_arrive.arr_name)
   AND bpchareq(shoelace_data.sl_name, s.sl_name);
   AND int4ne(int4pl(s.sl_avail, shoelace_arrive.arr_quant),
 s.sl_avail);
```

After that the rule system runs out of rules and returns the generated parse trees. So we end up with two final parse trees that are equal to the SQL statements

```
INSERT INTO shoelace_log SELECT
       s.sl_name,
       s.sl_avail + shoelace_arrive.arr_quant,
       current_user,
       current_timestamp
  FROM shoelace_arrive shoelace_arrive, shoelace_data
 shoelace_data,
       shoelace_data s
 WHERE s.sl_name = shoelace_arrive.arr_name
   AND shoelace_data.sl_name = s.sl_name
   AND s.sl_avail + shoelace_arrive.arr_quant != s.sl_avail;

UPDATE shoelace_data SET
       sl_avail = shoelace_data.sl_avail +
 shoelace_arrive.arr_quant
  FROM shoelace_arrive shoelace_arrive,
       shoelace_data shoelace_data,
       shoelace_data s
 WHERE s.sl_name = shoelace_arrive.sl_name
   AND shoelace_data.sl_name = s.sl_name;
```

The result is that data coming from one relation inserted into another, changed into updates on a third, changed into updating a fourth plus logging that final update in a fifth gets reduced into two queries.

There is a little detail that's a bit ugly. Looking at the two queries turns out, that the `shoelace_data` relation appears twice in the range table where it could definitely be reduced to one. The planner does not handle it and so the execution plan for the rule systems output of the INSERT will be

```
Nested Loop
  ->  Merge Join
        ->  Seq Scan
              ->  Sort
                    ->  Seq Scan on s
        ->  Seq Scan
              ->  Sort
```

```
                    ->  Seq Scan on shoelace_arrive
  ->  Seq Scan on shoelace_data
```

while omitting the extra range table entry would result in a

```
Merge Join
  ->  Seq Scan
        ->  Sort
              ->  Seq Scan on s
  ->  Seq Scan
        ->  Sort
              ->  Seq Scan on shoelace_arrive
```

that totally produces the same entries in the log relation. Thus, the rule system caused one extra scan on the `shoelace_data` relation that is absolutely not necessary. And the same obsolete scan is done once more in the UPDATE. But it was a really hard job to make that all possible at all.

A final demonstration of the PostgreSQL rule system and its power. There is a cute blonde that sells shoelaces. And what Al could never realize, she's not only cute, she's smart too - a little too smart. Thus, it happens from time to time that Al orders shoelaces that are absolutely not sellable. This time he ordered 1000 pairs of magenta shoelaces and since another kind is currently not available but he committed to buy some, he also prepared his database for pink ones.

```
al_bundy=> INSERT INTO shoelace VALUES
al_bundy->     ('sl9', 0, 'pink', 35.0, 'inch', 0.0);
al_bundy=> INSERT INTO shoelace VALUES
al_bundy->     ('sl10', 1000, 'magenta', 40.0, 'inch', 0.0);
```

Since this happens often, we must lookup for shoelace entries, that fit for absolutely no shoe sometimes. We could do that in a complicated statement every time, or we can setup a view for it. The view for this is

```
CREATE VIEW shoelace_obsolete AS
    SELECT * FROM shoelace WHERE NOT EXISTS
        (SELECT shoename FROM shoe WHERE slcolor = sl_color);
```

Its output is

```
al_bundy=> SELECT * FROM shoelace_obsolete;
sl_name   |sl_avail|sl_color  |sl_len|sl_unit |sl_len_cm
----------+--------+----------+------+--------+---------
sl9       |       0|pink      |    35|inch    |     88.9
sl10      |    1000|magenta   |    40|inch    |    101.6
```

For the 1000 magenta shoelaces we must debit Al before we can throw 'em away, but that's another problem. The pink entry we delete. To make it a little harder for PostgreSQL, we don't delete it directly. Instead we create one more view

```
CREATE VIEW shoelace_candelete AS
    SELECT * FROM shoelace_obsolete WHERE sl_avail = 0;
```

and do it this way:

```
DELETE FROM shoelace WHERE EXISTS
    (SELECT * FROM shoelace_candelete
             WHERE sl_name = shoelace.sl_name);
```

Voilà:

```
al_bundy=> SELECT * FROM shoelace;
sl_name   |sl_avail|sl_color  |sl_len|sl_unit |sl_len_cm
```

```
----------+--------+----------+------+--------+---------
sl1       |        5|black     |    80|cm      |        80
sl2       |        6|black     |   100|cm      |       100
sl7       |        6|brown     |    60|cm      |        60
sl4       |        8|black     |    40|inch    |     101.6
sl3       |       10|black     |    35|inch    |      88.9
sl8       |       21|brown     |    40|inch    |     101.6
sl10      |     1000|magenta   |    40|inch    |     101.6
sl5       |        4|brown     |     1|m       |       100
sl6       |       20|brown     |   0.9|m       |        90
(9 rows)
```

A DELETE on a view, with a subselect qualification that in total uses 4 nesting/joined views, where one of them itself has a subselect qualification containing a view and where calculated view columns are used, gets rewritten into one single parse tree that deletes the requested data from a real table.

I think there are only a few situations out in the real world, where such a construct is necessary. But it makes me feel comfortable that it works.

The truth is: Doing this I found one more bug while writing this document. But after fixing that I was a little amazed that it works at all.

13.5. Rules and Permissions

Due to rewriting of queries by the PostgreSQL rule system, other tables/views than those used in the original query get accessed. Using update rules, this can include write access to tables.

Rewrite rules don't have a separate owner. The owner of a relation (table or view) is automatically the owner of the rewrite rules that are defined for it. The PostgreSQL rule system changes the behavior of the default access control system. Relations that are used due to rules get checked against the permissions of the rule owner, not the user invoking the rule. This means, that a user does only need the required permissions for the tables/views he names in his queries.

For example: A user has a list of phone numbers where some of them are private, the others are of interest for the secretary of the office. He can construct the following:

```
CREATE TABLE phone_data (person text, phone text, private bool);
CREATE VIEW phone_number AS
    SELECT person, phone FROM phone_data WHERE NOT private;
GRANT SELECT ON phone_number TO secretary;
```

Nobody except him (and the database superusers) can access the phone_data table. But due to the GRANT, the secretary can SELECT from the phone_number view. The rule system will rewrite the SELECT from phone_number into a SELECT from phone_data and add the qualification that only entries where private is false are wanted. Since the user is the owner of phone_number, the read access to phone_data is now checked against his permissions and the query is considered granted. The check for accessing phone_number is also performed, but this is done against the invoking user, so nobody but the user and the secretary can use it.

The permissions are checked rule by rule. So the secretary is for now the only one who can see the public phone numbers. But the secretary can setup another view and grant access to that to public. Then, anyone can see the phone_number data through the secretaries view. What the secretary cannot do is to create a view that directly accesses phone_data (actually he can, but it will not work since every access aborts the transaction during the permission checks). And as soon as the user will notice, that the secretary opened his phone_number view, he can REVOKE his access. Immediately any access to the secretaries view will fail.

Someone might think that this rule by rule checking is a security hole, but in fact it isn't. If this would not work, the secretary could setup a table with the same columns as phone_number and copy the

data to there once per day. Then it's his own data and he can grant access to everyone he wants. A GRANT means “I trust you”. If someone you trust does the thing above, it's time to think it over and then REVOKE.

This mechanism does also work for update rules. In the examples of the previous section, the owner of the tables in Al's database could GRANT SELECT, INSERT, UPDATE and DELETE on the shoelace view to al. But only SELECT on shoelace_log. The rule action to write log entries will still be executed successfully. And Al could see the log entries. But he cannot create fake entries, nor could he manipulate or remove existing ones.

Warning

GRANT ALL currently includes RULE permission. This means the granted user could drop the rule, do the changes and reinstall it. I think this should get changed quickly.

13.6. Rules and Command Status

The PostgreSQL server returns a command status string, such as `INSERT 149592 1`, for each query it receives. This is simple enough when there are no rules involved, but what happens when the query is rewritten by rules?

As of PostgreSQL 7.3, rules affect the command status as follows:

1. If there is no unconditional INSTEAD rule for the query, then the originally given query will be executed, and its command status will be returned as usual. (But note that if there were any conditional INSTEAD rules, the negation of their qualifications will have been added to the original query. This may reduce the number of rows it processes, and if so the reported status will be affected.)

2. If there is any unconditional INSTEAD rule for the query, then the original query will not be executed at all. In this case, the server will return the command status for the last query that was inserted by an INSTEAD rule (conditional or unconditional) and is of the same type (INSERT, UPDATE, or DELETE) as the original query. If no query meeting those requirements is added by any rule, then the returned command status shows the original query type and zeroes for the tuple-count and OID fields.

The programmer can ensure that any desired INSTEAD rule is the one that sets the command status in the second case, by giving it the alphabetically last rule name among the active rules, so that it fires last.

13.7. Rules versus Triggers

Many things that can be done using triggers can also be implemented using the PostgreSQL rule system. What currently cannot be implemented by rules are some kinds of constraints. It is possible, to place a qualified rule that rewrites a query to NOTHING if the value of a column does not appear in another table. But then the data is silently thrown away and that's not a good idea. If checks for valid values are required, and in the case of an invalid value an error message should be generated, it must be done by a trigger for now.

On the other hand a trigger that is fired on INSERT on a view can do the same as a rule, put the data somewhere else and suppress the insert in the view. But it cannot do the same thing on UPDATE or DELETE, because there is no real data in the view relation that could be scanned and thus the trigger would never get called. Only a rule will help.

For the things that can be implemented by both, it depends on the usage of the database, which is the best. A trigger is fired for any row affected once. A rule manipulates the parse tree or generates an additional one. So if many rows are affected in one statement, a rule issuing one extra query would usually do a better job than a trigger that is called for any single row and must execute his operations this many times.

For example: There are two tables

```
CREATE TABLE computer (
    hostname        text,    -- indexed
    manufacturer    text     -- indexed
);

CREATE TABLE software (
    software        text,    -- indexed
    hostname        text     -- indexed
);
```

Both tables have many thousands of rows and the index on `hostname` is unique. The `hostname` column contains the full qualified domain name of the computer. The rule/trigger should constraint delete rows from software that reference the deleted host. Since the trigger is called for each individual row deleted from computer, it can use the statement

```
DELETE FROM software WHERE hostname = $1;
```

in a prepared and saved plan and pass the `hostname` in the parameter. The rule would be written as

```
CREATE RULE computer_del AS ON DELETE TO computer
    DO DELETE FROM software WHERE hostname = OLD.hostname;
```

Now we look at different types of deletes. In the case of a

```
DELETE FROM computer WHERE hostname = 'mypc.local.net';
```

the table computer is scanned by index (fast) and the query issued by the trigger would also be an index scan (fast too). The extra query from the rule would be a

```
DELETE FROM software WHERE computer.hostname = 'mypc.local.net'
                       AND software.hostname = computer.hostname;
```

Since there are appropriate indexes setup, the planner will create a plan of

```
Nestloop
  ->  Index Scan using comp_hostidx on computer
  ->  Index Scan using soft_hostidx on software
```

So there would be not that much difference in speed between the trigger and the rule implementation. With the next delete we want to get rid of all the 2000 computers where the `hostname` starts with 'old'. There are two possible queries to do that. One is

```
DELETE FROM computer WHERE hostname >= 'old'
                       AND hostname <  'ole'
```

Where the plan for the rule query will be a

```
Hash Join
  ->  Seq Scan on software
  ->  Hash
    ->  Index Scan using comp_hostidx on computer
```

The other possible query is a

```
DELETE FROM computer WHERE hostname ~ '^old';
```

with the execution plan

```
Nestloop
```

```
  ->  Index Scan using comp_hostidx on computer
  ->  Index Scan using soft_hostidx on software
```

This shows, that the planner does not realize that the qualification for the `hostname` on computer could also be used for an index scan on software when there are multiple qualification expressions combined with AND, what he does in the regexp version of the query. The trigger will get invoked once for any of the 2000 old computers that have to be deleted and that will result in one index scan over computer and 2000 index scans for the software. The rule implementation will do it with two queries over indexes. And it depends on the overall size of the software table if the rule will still be faster in the sequential scan situation. 2000 query executions over the SPI manager take some time, even if all the index blocks to look them up will soon appear in the cache.

The last query we look at is a

```
DELETE FROM computer WHERE manufacurer = 'bim';
```

Again this could result in many rows to be deleted from computer. So the trigger will again fire many queries into the executor. But the rule plan will again be the nested loop over two index scans. Only using another index on computer:

```
Nestloop
  ->  Index Scan using comp_manufidx on computer
  ->  Index Scan using soft_hostidx on software
```

resulting from the rules query

```
DELETE FROM software WHERE computer.manufacurer = 'bim'
                       AND software.hostname = computer.hostname;
```

In any of these cases, the extra queries from the rule system will be more or less independent from the number of affected rows in a query.

Another situation is cases on UPDATE where it depends on the change of an attribute if an action should be performed or not. In PostgreSQL version 6.4, the attribute specification for rule events is disabled (it will have its comeback latest in 6.5, maybe earlier - stay tuned). So for now the only way to create a rule as in the shoelace_log example is to do it with a rule qualification. That results in an extra query that is performed always, even if the attribute of interest cannot change at all because it does not appear in the target list of the initial query. When this is enabled again, it will be one more advantage of rules over triggers. Optimization of a trigger must fail by definition in this case, because the fact that its actions will only be done when a specific attribute is updated is hidden in its functionality. The definition of a trigger only allows to specify it on row level, so whenever a row is touched, the trigger must be called to make its decision. The rule system will know it by looking up the target list and will suppress the additional query completely if the attribute isn't touched. So the rule, qualified or not, will only do its scans if there ever could be something to do.

Rules will only be significantly slower than triggers if their actions result in large and bad qualified joins, a situation where the planner fails. They are a big hammer. Using a big hammer without caution can cause big damage. But used with the right touch, they can hit any nail on the head.

Chapter 14. Interfacing Extensions To Indexes

14.1. Introduction

The procedures described thus far let you define new types, new functions, and new operators. However, we cannot yet define a secondary index (such as a B-tree, R-tree, or hash access method) over a new type, nor associate operators of a new type with secondary indexes. To do these things, we must define an *operator class* for the new data type. We will describe operator classes in the context of a running example: a new operator class for the B-tree access method that stores and sorts complex numbers in ascending absolute value order.

Note

Prior to PostgreSQL release 7.3, it was necessary to make manual additions to `pg_amop`, `pg_amproc`, and `pg_opclass` in order to create a user-defined operator class. That approach is now deprecated in favor of using `CREATE OPERATOR CLASS`, which is a much simpler and less error-prone way of creating the necessary catalog entries.

14.2. Access Methods and Operator Classes

The `pg_am` table contains one row for every index access method. Support for access to regular tables is built into PostgreSQL, but all index access methods are described in `pg_am`. It is possible to add a new index access method by defining the required interface routines and then creating a row in `pg_am` --- but that is far beyond the scope of this chapter.

The routines for an index access method do not directly know anything about the data types the access method will operate on. Instead, an *operator class* identifies the set of operations that the access method needs to be able to use to work with a particular data type. Operator classes are so called because one thing they specify is the set of WHERE-clause operators that can be used with an index (ie, can be converted into an index scan qualification). An operator class may also specify some *support procedures* that are needed by the internal operations of the index access method, but do not directly correspond to any WHERE-clause operator that can be used with the index.

It is possible to define multiple operator classes for the same input data type and index access method. By doing this, multiple sets of indexing semantics can be defined for a single data type. For example, a B-tree index requires a sort ordering to be defined for each data type it works on. It might be useful for a complex-number data type to have one B-tree operator class that sorts the data by complex absolute value, another that sorts by real part, and so on. Typically one of the operator classes will be deemed most commonly useful and will be marked as the default operator class for that data type and index access method.

The same operator class name can be used for several different access methods (for example, both B-tree and hash access methods have operator classes named `oid_ops`), but each such class is an independent entity and must be defined separately.

14.3. Access Method Strategies

The operators associated with an operator class are identified by “strategy numbers”, which serve to identify the semantics of each operator within the context of its operator class. For example, B-trees impose a strict ordering on keys, lesser to greater, and so operators like “less than” and “greater than or equal to” are interesting with respect to a B-tree. Because PostgreSQL allows the user to define operators, PostgreSQL cannot look at the name of an operator (e.g., < or >=) and tell what kind of comparison it is. Instead, the index access method defines a set of “strategies”, which can be thought of

as generalized operators. Each operator class shows which actual operator corresponds to each strategy for a particular data type and interpretation of the index semantics.

B-tree indexes define 5 strategies, as shown in Table 14.1, “B-tree”.

Table 14.1. B-tree Strategies

Operation	Strategy Number
less than	1
less than or equal	2
equal	3
greater than or equal	4
greater than	5

Hash indexes express only bitwise similarity, and so they define only 1 strategy, as shown in Table 14.2, “Hash”.

Table 14.2. Hash Strategies

Operation	Strategy Number
equal	1

R-tree indexes express rectangle-containment relationships. They define 8 strategies, as shown in Table 14.3, “R-tree”.

Table 14.3. R-tree Strategies

Operation	Strategy Number
left of	1
left of or overlapping	2
overlapping	3
right of or overlapping	4
right of	5
same	6
contains	7
contained by	8

GiST indexes are even more flexible: they do not have a fixed set of strategies at all. Instead, the “consistency” support routine of a particular GiST operator class interprets the strategy numbers however it likes.

By the way, the `amorderstrategy` column in `pg_am` tells whether the access method supports ordered scan. Zero means it doesn't; if it does, `amorderstrategy` is the strategy number that corresponds to the ordering operator. For example, B-tree has `amorderstrategy` = 1, which is its “less than” strategy number.

In short, an operator class must specify a set of operators that express each of these semantic ideas for the operator class's data type.

14.4. Access Method Support Routines

Strategies aren't usually enough information for the system to figure out how to use an index. In practice, the access methods require additional support routines in order to work. For example, the B-tree access method must be able to compare two keys and determine whether one is greater than, equal

to, or less than the other. Similarly, the R-tree access method must be able to compute intersections, unions, and sizes of rectangles. These operations do not correspond to operators used in qualifications in SQL queries; they are administrative routines used by the access methods, internally.

Just as with operators, the operator class identifies which specific functions should play each of these roles for a given data type and semantic interpretation. The index access method specifies the set of functions it needs, and the operator class identifies the correct functions to use by assigning "support function numbers" to them.

B-trees require a single support function, as shown in Table 14.4, "B-tree".

Table 14.4. B-tree Support Functions

Function	Support Number
Compare two keys and return an integer less than zero, zero, or greater than zero, indicating whether the first key is less than, equal to, or greater than the second.	1

Hash indexes likewise require one support function, as shown in Table 14.5, "Hash".

Table 14.5. Hash Support Functions

Function	Support Number
Compute the hash value for a key	1

R-tree indexes require three support functions, as shown in Table 14.6, "R-tree".

Table 14.6. R-tree Support Functions

Function	Support Number
union	1
intersection	2
size	3

GiST indexes require seven support functions, as shown in Table 14.7, "GiST".

Table 14.7. GiST Support Functions

Function	Support Number
consistent	1
union	2
compress	3
decompress	4
penalty	5
picksplit	6
equal	7

14.5. Creating the Operators and Support Routines

Now that we have seen the ideas, here is the promised example of creating a new operator class. First, we need a set of operators. The procedure for defining operators was discussed in Chapter 11,

Extending SQL: Operators. For the `complex_abs_ops` operator class on B-trees, the operators we require are:

- absolute-value less-than (strategy 1)
- absolute-value less-than-or-equal (strategy 2)
- absolute-value equal (strategy 3)
- absolute-value greater-than-or-equal (strategy 4)
- absolute-value greater-than (strategy 5)

Suppose the code that implements these functions is stored in the file *PGROOT*`/src/tutorial/complex.c`, which we have compiled into *PGROOT*`/src/tutorial/complex.so`. Part of the C code looks like this:

```
#define Mag(c) ((c)->x*(c)->x + (c)->y*(c)->y)

          bool
          complex_abs_eq(Complex *a, Complex *b)
          {
              double amag = Mag(a), bmag = Mag(b);
              return (amag==bmag);
          }
```

(Note that we will only show the equality operator in this text. The other four operators are very similar. Refer to `complex.c` or `complex.source` for the details.)

We make the function known to PostgreSQL like this:

```
CREATE FUNCTION complex_abs_eq(complex, complex) RETURNS boolean
    AS 'PGROOT/src/tutorial/complex'
    LANGUAGE C;
```

There are some important things that are happening here:

- First, note that operators for less-than, less-than-or-equal, equal, greater-than-or-equal, and greater-than for `complex` are being defined. We can only have one operator named, say, = and taking type `complex` for both operands. In this case we don't have any other operator = for `complex`, but if we were building a practical data type we'd probably want = to be the ordinary equality operation for complex numbers. In that case, we'd need to use some other operator name for `complex_abs_eq`.

- Second, although PostgreSQL can cope with operators having the same name as long as they have different input data types, C can only cope with one global routine having a given name, period. So we shouldn't name the C function something simple like `abs_eq`. Usually it's a good practice to include the data type name in the C function name, so as not to conflict with functions for other data types.

- Third, we could have made the PostgreSQL name of the function `abs_eq`, relying on PostgreSQL to distinguish it by input data types from any other PostgreSQL function of the same name. To keep the example simple, we make the function have the same names at the C level and PostgreSQL level.

- Finally, note that these operator functions return Boolean values. In practice, all operators defined as index access method strategies must return type `boolean`, since they must appear at the top level of a `WHERE` clause to be used with an index. (On the other hand, support functions return whatever the particular access method expects -- in the case of the comparison function for B-trees, a signed integer.)

Now we are ready to define the operators:

```
CREATE OPERATOR = (
     leftarg = complex, rightarg = complex,
     procedure = complex_abs_eq,
```

```
    restrict = eqsel, join = eqjoinsel
        );
```

The important things here are the procedure names (which are the C functions defined above) and the restriction and join selectivity functions. You should just use the selectivity functions used in the example (see `complex.source`). Note that there are different such functions for the less-than, equal, and greater-than cases. These must be supplied or the optimizer will be unable to make effective use of the index.

The next step is the registration of the comparison "support routine" required by B-trees. The C code that implements this is in the same file that contains the operator procedures:

```
CREATE FUNCTION complex_abs_cmp(complex, complex)
    RETURNS integer
    AS 'PGROOT/src/tutorial/complex'
    LANGUAGE C;
```

14.6. Creating the Operator Class

Now that we have the required operators and support routine, we can finally create the operator class:

```
CREATE OPERATOR CLASS complex_abs_ops
    DEFAULT FOR TYPE complex USING btree AS
        OPERATOR        1       < ,
        OPERATOR        2       <= ,
        OPERATOR        3       = ,
        OPERATOR        4       >= ,
        OPERATOR        5       > ,
        FUNCTION        1       complex_abs_cmp(complex, complex);
```

And we're done! (Whew.) It should now be possible to create and use B-tree indexes on `complex` columns.

We could have written the operator entries more verbosely, as in

```
        OPERATOR        1       < (complex, complex) ,
```

but there is no need to do so when the operators take the same data type we are defining the operator class for.

The above example assumes that you want to make this new operator class the default B-tree operator class for the `complex` data type. If you don't, just leave out the word `DEFAULT`.

14.7. Special Features of Operator Classes

There are two special features of operator classes that we have not discussed yet, mainly because they are not very useful with the default B-tree index access method.

Normally, declaring an operator as a member of an operator class means that the index access method can retrieve exactly the set of rows that satisfy a WHERE condition using the operator. For example,

```
SELECT * FROM table WHERE integer_column < 4;
```

can be satisfied exactly by a B-tree index on the integer column. But there are cases where an index is useful as an inexact guide to the matching rows. For example, if an R-tree index stores only bounding boxes for objects, then it cannot exactly satisfy a WHERE condition that tests overlap between nonrectangular objects such as polygons. Yet we could use the index to find objects whose bounding box overlaps the bounding box of the target object, and then do the exact overlap test only on the objects found by the index. If this scenario applies, the index is said to be "lossy" for the operator, and we add

RECHECK to the OPERATOR clause in the CREATE OPERATOR CLASS command. RECHECK is valid if the index is guaranteed to return all the required tuples, plus perhaps some additional tuples, which can be eliminated by performing the original operator comparison.

Consider again the situation where we are storing in the index only the bounding box of a complex object such as a polygon. In this case there's not much value in storing the whole polygon in the index entry --- we may as well store just a simpler object of type box. This situation is expressed by the STORAGE option in CREATE OPERATOR CLASS: we'd write something like

```
CREATE OPERATOR CLASS polygon_ops
    DEFAULT FOR TYPE polygon USING gist AS
        ...
        STORAGE box;
```

At present, only the GiST access method supports a STORAGE type that's different from the column data type. The GiST compress and decompress support routines must deal with data-type conversion when STORAGE is used.

Chapter 15. Index Cost Estimation Functions

Author

Written by Tom Lane (<tgl@sss.pgh.pa.us>) on 2000-01-24

Note

This must eventually become part of a much larger chapter about writing new index access methods.

Every index access method must provide a cost estimation function for use by the planner/optimizer. The procedure OID of this function is given in the `amcostestimate` field of the access method's `pg_am` entry.

Note

Prior to PostgreSQL 7.0, a different scheme was used for registering index-specific cost estimation functions.

The amcostestimate function is given a list of WHERE clauses that have been determined to be usable with the index. It must return estimates of the cost of accessing the index and the selectivity of the WHERE clauses (that is, the fraction of main-table tuples that will be retrieved during the index scan). For simple cases, nearly all the work of the cost estimator can be done by calling standard routines in the optimizer; the point of having an amcostestimate function is to allow index access methods to provide index-type-specific knowledge, in case it is possible to improve on the standard estimates.

Each amcostestimate function must have the signature:

```
void
amcostestimate (Query *root,
                RelOptInfo *rel,
                IndexOptInfo *index,
                List *indexQuals,
                Cost *indexStartupCost,
                Cost *indexTotalCost,
                Selectivity *indexSelectivity,
                double *indexCorrelation);
```

The first four parameters are inputs:

root

The query being processed.

rel

The relation the index is on.

index

The index itself.

indexQuals

List of index qual clauses (implicitly ANDed); a NIL list indicates no qualifiers are available.

The last four parameters are pass-by-reference outputs:

*indexStartupCost

Set to cost of index start-up processing

*indexTotalCost

Set to total cost of index processing

*indexSelectivity

Set to index selectivity

*indexCorrelation

Set to correlation coefficient between index scan order and underlying table's order

Note that cost estimate functions must be written in C, not in SQL or any available procedural language, because they must access internal data structures of the planner/optimizer.

The index access costs should be computed in the units used by `src/backend/optimizer/path/costsize.c`: a sequential disk block fetch has cost 1.0, a nonsequential fetch has cost random_page_cost, and the cost of processing one index tuple should usually be taken as cpu_index_tuple_cost (which is a user-adjustable optimizer parameter). In addition, an appropriate multiple of cpu_operator_cost should be charged for any comparison operators invoked during index processing (especially evaluation of the indexQuals themselves).

The access costs should include all disk and CPU costs associated with scanning the index itself, but NOT the costs of retrieving or processing the main-table tuples that are identified by the index.

The “start-up cost” is the part of the total scan cost that must be expended before we can begin to fetch the first tuple. For most indexes this can be taken as zero, but an index type with a high start-up cost might want to set it nonzero.

The indexSelectivity should be set to the estimated fraction of the main table tuples that will be retrieved during the index scan. In the case of a lossy index, this will typically be higher than the fraction of tuples that actually pass the given qual conditions.

The indexCorrelation should be set to the correlation (ranging between -1.0 and 1.0) between the index order and the table order. This is used to adjust the estimate for the cost of fetching tuples from the main table.

Cost Estimation

A typical cost estimator will proceed as follows:

1. Estimate and return the fraction of main-table tuples that will be visited based on the given qual conditions. In the absence of any index-type-specific knowledge, use the standard optimizer function `clauselist_selectivity()`:

   ```
   *indexSelectivity = clauselist_selectivity(root, indexQuals,
                                              lfirsti(rel-
   >relids));
   ```

2. Estimate the number of index tuples that will be visited during the scan. For many index types this is the same as indexSelectivity times the number of tuples in the index, but it might be more. (Note that the index's size in pages and tuples is available from the IndexOptInfo struct.)

3. Estimate the number of index pages that will be retrieved during the scan. This might be just indexSelectivity times the index's size in pages.

4. Compute the index access cost. A generic estimator might do this:

```
    /*
     * Our generic assumption is that the index pages will be
read
     * sequentially, so they have cost 1.0 each, not
random_page_cost.
     * Also, we charge for evaluation of the indexquals at each
index tuple.
     * All the costs are assumed to be paid incrementally
during the scan.
     */
    *indexStartupCost = 0;
    *indexTotalCost = numIndexPages +
        (cpu_index_tuple_cost + cost_qual_eval(indexQuals)) *
numIndexTuples;
```

5. Estimate the index correlation. For a simple ordered index on a single field, this can be retrieved from pg_statistic. If the correlation is not known, the conservative estimate is zero (no correlation).

Examples of cost estimator functions can be found in `src/backend/utils/adt/selfuncs.c`.

By convention, the `pg_proc` entry for an `amcostestimate` function should show eight arguments all declared as `internal` (since none of them have types that are known to SQL), and the return type is `void`.

Chapter 16. Triggers

PostgreSQL has various server-side function interfaces. Server-side functions can be written in SQL, C, or any defined procedural language. Trigger functions can be written in C and most procedural languages, but not in SQL. Note that statement-level trigger events are not supported in the current version. You can currently specify BEFORE or AFTER on INSERT, DELETE or UPDATE of a tuple as a trigger event.

16.1. Trigger Definition

If a trigger event occurs, the trigger manager (called by the Executor) sets up a `TriggerData` information structure (described below) and calls the trigger function to handle the event.

The trigger function must be defined before the trigger itself can be created. The trigger function must be declared as a function taking no arguments and returning type `trigger`. (The trigger function receives its input through a `TriggerData` structure, not in the form of ordinary function arguments.) If the function is written in C, it must use the "version 1" function manager interface.

The syntax for creating triggers is:

```
CREATE TRIGGER trigger [ BEFORE | AFTER ] [ INSERT | DELETE |
 UPDATE [ OR ... ] ]
    ON relation FOR EACH [ ROW | STATEMENT ]
    EXECUTE PROCEDURE procedure
     (args);
```

where the arguments are:

trigger

The trigger must have a name distinct from all other triggers on the same table. The name is needed if you ever have to delete the trigger.

BEFORE
AFTER

Determines whether the function is called before or after the event.

INSERT
DELETE
UPDATE

The next element of the command determines what event(s) will trigger the function. Multiple events can be specified separated by OR.

relation

The relation name indicates which table the event applies to.

ROW
STATEMENT

The FOR EACH clause determines whether the trigger is fired for each affected row or before (or after) the entire statement has completed. Currently only the ROW case is supported.

procedure

The procedure name is the function to be called.

args

The arguments passed to the function in the `TriggerData` structure. This is either empty or a list of one or more simple literal constants (which will be passed to the function as strings).

The purpose of including arguments in the trigger definition is to allow different triggers with similar requirements to call the same function. As an example, there could be a generalized trigger function that takes as its arguments two field names and puts the current user in one and the current time stamp in the other. Properly written, this trigger function would be independent of the specific table it is triggering on. So the same function could be used for INSERT events on any table with suitable fields, to automatically track creation of records in a transaction table for example. It could also be used to track last-update events if defined as an UPDATE trigger.

Trigger functions return a `HeapTuple` to the calling executor. The return value is ignored for triggers fired AFTER an operation, but it allows BEFORE triggers to:

- Return a `NULL` pointer to skip the operation for the current tuple (and so the tuple will not be inserted/updated/deleted).
- For INSERT and UPDATE triggers only, the returned tuple becomes the tuple which will be inserted or will replace the tuple being updated. This allows the trigger function to modify the row being inserted or updated.

A BEFORE trigger that does not intend to cause either of these behaviors must be careful to return the same NEW tuple it is passed.

Note that there is no initialization performed by the CREATE TRIGGER handler. This may be changed in the future.

If more than one trigger is defined for the same event on the same relation, the triggers will be fired in alphabetical order by name. In the case of BEFORE triggers, the possibly-modified tuple returned by each trigger becomes the input to the next trigger. If any BEFORE trigger returns `NULL`, the operation is abandoned and subsequent triggers are not fired.

If a trigger function executes SQL-queries (using SPI) then these queries may fire triggers again. This is known as cascading triggers. There is no direct limitation on the number of cascade levels. It is possible for cascades to cause recursive invocation of the same trigger --- for example, an INSERT trigger might execute a query that inserts an additional tuple into the same table, causing the INSERT trigger to be fired again. It is the trigger programmer's responsibility to avoid infinite recursion in such scenarios.

16.2. Interaction with the Trigger Manager

This section describes the low-level details of the interface to a trigger function. This information is only needed when writing a trigger function in C. If you are using a higher-level function language then these details are handled for you.

Note

The interface described here applies for PostgreSQL 7.1 and later. Earlier versions passed the `TriggerData` pointer in a global variable `CurrentTriggerData`.

When a function is called by the trigger manager, it is not passed any normal parameters, but it is passed a “context” pointer pointing to a `TriggerData` structure. C functions can check whether they were called from the trigger manager or not by executing the macro `CALLED_AS_TRIGGER(fcinfo)`, which expands to

```
((fcinfo)->context != NULL && IsA((fcinfo)->context, TriggerData))
```

If this returns true, then it is safe to cast `fcinfo->context` to type `TriggerData *` and make use of the pointed-to `TriggerData` structure. The function must *not* alter the `TriggerData` structure or any of the data it points to.

`struct TriggerData` is defined in `commands/trigger.h`:

```
typedef struct TriggerData
{
    NodeTag       type;
    TriggerEvent  tg_event;
    Relation      tg_relation;
    HeapTuple     tg_trigtuple;
    HeapTuple     tg_newtuple;
    Trigger      *tg_trigger;
} TriggerData;
```

where the members are defined as follows:

`type`

Always `T_TriggerData` if this is a trigger event.

`tg_event`

describes the event for which the function is called. You may use the following macros to examine `tg_event`:

TRIGGER_FIRED_BEFORE(tg_event)

returns TRUE if trigger fired BEFORE.

TRIGGER_FIRED_AFTER(tg_event)

Returns TRUE if trigger fired AFTER.

TRIGGER_FIRED_FOR_ROW(event)

Returns TRUE if trigger fired for a ROW-level event.

TRIGGER_FIRED_FOR_STATEMENT(event)

Returns TRUE if trigger fired for STATEMENT-level event.

TRIGGER_FIRED_BY_INSERT(event)

Returns TRUE if trigger fired by INSERT.

TRIGGER_FIRED_BY_DELETE(event)

Returns TRUE if trigger fired by DELETE.

TRIGGER_FIRED_BY_UPDATE(event)

Returns TRUE if trigger fired by UPDATE.

`tg_relation`

is a pointer to structure describing the triggered relation. Look at `utils/rel.h` for details about this structure. The most interesting things are `tg_relation->rd_att` (descriptor of the relation tuples) and `tg_relation->rd_rel->relname` (relation's name. This is not

`char*`, but `NameData`. Use `SPI_getrelname(tg_relation)` to get `char*` if you need a copy of the name).

`tg_trigtuple`

is a pointer to the tuple for which the trigger is fired. This is the tuple being inserted (if INSERT), deleted (if DELETE) or updated (if UPDATE). If INSERT/DELETE then this is what you are to return to Executor if you don't want to replace tuple with another one (INSERT) or skip the operation.

`tg_newtuple`

is a pointer to the new version of tuple if UPDATE and `NULL` if this is for an INSERT or a DELETE. This is what you are to return to Executor if UPDATE and you don't want to replace this tuple with another one or skip the operation.

`tg_trigger`

is pointer to structure `Trigger` defined in `utils/rel.h`:

```
typedef struct Trigger
{
    Oid         tgoid;
    char       *tgname;
    Oid         tgfoid;
    int16       tgtype;
    bool        tgenabled;
    bool        tgisconstraint;
    Oid         tgconstrrelid;
    bool        tgdeferrable;
    bool        tginitdeferred;
    int16       tgnargs;
    int16       tgattr[FUNC_MAX_ARGS];
    char      **tgargs;
} Trigger;
```

where `tgname` is the trigger's name, `tgnargs` is number of arguments in `tgargs`, `tgargs` is an array of pointers to the arguments specified in the CREATE TRIGGER statement. Other members are for internal use only.

16.3. Visibility of Data Changes

PostgreSQL data changes visibility rule: during a query execution, data changes made by the query itself (via SQL-function, SPI-function, triggers) are invisible to the query scan. For example, in query

```
INSERT INTO a SELECT * FROM a;
```

tuples inserted are invisible for SELECT scan. In effect, this duplicates the database table within itself (subject to unique index rules, of course) without recursing.

But keep in mind this notice about visibility in the SPI documentation:

> Changes made by query Q are visible by queries that are started after query Q, no matter whether they are started inside Q (during the execution of Q) or after Q is done.

This is true for triggers as well so, though a tuple being inserted (`tg_trigtuple`) is not visible to queries in a BEFORE trigger, this tuple (just inserted) is visible to queries in an AFTER trigger, and to queries in BEFORE/AFTER triggers fired after this!

16.4. Examples

There are more complex examples in `src/test/regress/regress.c` and in `contrib/spi`.

Here is a very simple example of trigger usage. Function `trigf` reports the number of tuples in the triggered relation `ttest` and skips the operation if the query attempts to insert a null value into x (i.e - it acts as a not-null constraint but doesn't abort the transaction).

```
#include "executor/spi.h"       /* this is what you need to work
 with SPI */
#include "commands/trigger.h"   /* -"- and triggers */

extern Datum trigf(PG_FUNCTION_ARGS);

PG_FUNCTION_INFO_V1(trigf);

Datum
trigf(PG_FUNCTION_ARGS)
{
    TriggerData *trigdata = (TriggerData *) fcinfo->context;
    TupleDesc   tupdesc;
    HeapTuple   rettuple;
    char       *when;
    bool        checknull = false;
    bool        isnull;
    int         ret, i;

    /* Make sure trigdata is pointing at what I expect */
    if (!CALLED_AS_TRIGGER(fcinfo))
        elog(ERROR, "trigf: not fired by trigger manager");

    /* tuple to return to Executor */
    if (TRIGGER_FIRED_BY_UPDATE(trigdata->tg_event))
        rettuple = trigdata->tg_newtuple;
    else
        rettuple = trigdata->tg_trigtuple;

    /* check for null values */
    if (!TRIGGER_FIRED_BY_DELETE(trigdata->tg_event)
        && TRIGGER_FIRED_BEFORE(trigdata->tg_event))
        checknull = true;

    if (TRIGGER_FIRED_BEFORE(trigdata->tg_event))
        when = "before";
    else
        when = "after ";

    tupdesc = trigdata->tg_relation->rd_att;

    /* Connect to SPI manager */
    if ((ret = SPI_connect()) < 0)
        elog(INFO, "trigf (fired %s): SPI_connect returned %d",
 when, ret);

    /* Get number of tuples in relation */
    ret = SPI_exec("SELECT count(*) FROM ttest", 0);

    if (ret < 0)
```

```
        elog(NOTICE, "trigf (fired %s): SPI_exec returned %d",
 when, ret);

    /* count(*) returns int8 as of PG 7.2, so be careful to convert
 */
    i = (int) DatumGetInt64(SPI_getbinval(SPI_tuptable->vals[0],
                                          SPI_tuptable->tupdesc,
                                          1,
                                          &isnull));

    elog (NOTICE, "trigf (fired %s): there are %d tuples in ttest",
 when, i);

    SPI_finish();

    if (checknull)
    {
        (void) SPI_getbinval(rettuple, tupdesc, 1, &isnull);
        if (isnull)
            rettuple = NULL;
    }

    return PointerGetDatum(rettuple);
}
```

Now, compile and create the trigger function:

```
CREATE FUNCTION trigf () RETURNS TRIGGER AS
'...path_to_so' LANGUAGE C;

CREATE TABLE ttest (x int4);

vac=> CREATE TRIGGER tbefore BEFORE INSERT OR UPDATE OR DELETE ON
 ttest
FOR EACH ROW EXECUTE PROCEDURE trigf();
CREATE
vac=> CREATE TRIGGER tafter AFTER INSERT OR UPDATE OR DELETE ON
 ttest
FOR EACH ROW EXECUTE PROCEDURE trigf();
CREATE
vac=> INSERT INTO ttest VALUES (NULL);
WARNING:  trigf (fired before): there are 0 tuples in ttest
INSERT 0 0

-- Insertion skipped and AFTER trigger is not fired

vac=> SELECT * FROM ttest;
 x
---
(0 rows)

vac=> INSERT INTO ttest VALUES (1);
INFO:  trigf (fired before): there are 0 tuples in ttest
INFO:  trigf (fired after ): there are 1 tuples in ttest
                                       ^^^^^^^^
                               remember what we said about
 visibility.
INSERT 167793 1
vac=> SELECT * FROM ttest;
```

```
 x
---
 1
(1 row)

vac=> INSERT INTO ttest SELECT x * 2 FROM ttest;
INFO:  trigf (fired before): there are 1 tuples in ttest
INFO:  trigf (fired after ): there are 2 tuples in ttest
                                       ^^^^^^^^
                              remember what we said about
 visibility.
INSERT 167794 1
vac=> SELECT * FROM ttest;
 x
---
 1
 2
(2 rows)

vac=> UPDATE ttest SET x = NULL WHERE x = 2;
INFO:  trigf (fired before): there are 2 tuples in ttest
UPDATE 0
vac=> UPDATE ttest SET x = 4 WHERE x = 2;
INFO:  trigf (fired before): there are 2 tuples in ttest
INFO:  trigf (fired after ): there are 2 tuples in ttest
UPDATE 1
vac=> SELECT * FROM ttest;
 x
---
 1
 4
(2 rows)

vac=> DELETE FROM ttest;
INFO:  trigf (fired before): there are 2 tuples in ttest
INFO:  trigf (fired after ): there are 1 tuples in ttest
INFO:  trigf (fired before): there are 1 tuples in ttest
INFO:  trigf (fired after ): there are 0 tuples in ttest
                                       ^^^^^^^^
                              remember what we said about
 visibility.
DELETE 2
vac=> SELECT * FROM ttest;
 x
---
(0 rows)
```

Chapter 17. Server Programming Interface

Vadim Mikheev

The *Server Programming Interface* (SPI) gives users the ability to run SQL queries inside user-defined C functions.

Note

The available Procedural Languages (PL) give an alternate means to build functions that can execute queries.

In fact, SPI is just a set of native interface functions to simplify access to the Parser, Planner, Optimizer and Executor. SPI also does some memory management.

To avoid misunderstanding we'll use *function* to mean SPI interface functions and *procedure* for user-defined C-functions using SPI.

Procedures which use SPI are called by the Executor. The SPI calls recursively invoke the Executor in turn to run queries. When the Executor is invoked recursively, it may itself call procedures which may make SPI calls.

Note that if during execution of a query from a procedure the transaction is aborted, then control will not be returned to your procedure. Rather, all work will be rolled back and the server will wait for the next command from the client. This will probably be changed in future versions.

A related restriction is the inability to execute BEGIN, END and ABORT (transaction control statements). This will also be changed in the future.

If successful, SPI functions return a non-negative result (either via a returned integer value or in SPI_result global variable, as described below). On error, a negative or NULL result will be returned.

17.1. Interface Functions

Name

SPI_connect — Connects your procedure to the SPI manager.

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
int SPI_connect(void)
```

Inputs

None

Outputs

int

Return status

SPI_OK_CONNECT

if connected

SPI_ERROR_CONNECT

if not connected

Description

`SPI_connect` opens a connection from a procedure invocation to the SPI manager. You must call this function if you will need to execute queries. Some utility SPI functions may be called from un-connected procedures.

If your procedure is already connected, `SPI_connect` will return an SPI_ERROR_CONNECT error. Note that this may happen if a procedure which has called `SPI_connect` directly calls another procedure which itself calls `SPI_connect`. While recursive calls to the SPI manager are permitted when an SPI query invokes another function which uses SPI, directly nested calls to `SPI_connect` and `SPI_finish` are forbidden.

Usage

Algorithm

`SPI_connect` performs the following: Initializes the SPI internal structures for query execution and memory management.

Name

SPI_finish — Disconnects your procedure from the SPI manager.

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_finish(void)
```

Inputs

None

Outputs

int

SPI_OK_FINISH if properly disconnected
SPI_ERROR_UNCONNECTED if called from an un-connected procedure

Description

`SPI_finish` closes an existing connection to the SPI manager. You must call this function after completing the SPI operations needed during your procedure's current invocation.

You may get the error return SPI_ERROR_UNCONNECTED if `SPI_finish` is called without having a current valid connection. There is no fundamental problem with this; it means that nothing was done by the SPI manager.

Usage

`SPI_finish` *must* be called as a final step by a connected procedure, or you may get unpredictable results! However, you do not need to worry about making this happen if the transaction is aborted via elog(ERROR). In that case SPI will clean itself up.

Algorithm

`SPI_finish` performs the following: Disconnects your procedure from the SPI manager and frees all memory allocations made by your procedure via `palloc` since the `SPI_connect`. These allocations can't be used any more! See Memory management.

Name

SPI_exec — Creates an execution plan (parser+planner+optimizer) and executes a query.

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_exec(query, tcount)
```

Inputs

char *query

String containing query plan

int tcount

Maximum number of tuples to return

Outputs

int

SPI_ERROR_UNCONNECTED if called from an un-connected procedure
SPI_ERROR_ARGUMENT if query is NULL or tcount < 0.
SPI_ERROR_UNCONNECTED if procedure is unconnected.
SPI_ERROR_COPY if COPY TO/FROM stdin.
SPI_ERROR_CURSOR if DECLARE/CLOSE CURSOR, FETCH.
SPI_ERROR_TRANSACTION if BEGIN/ABORT/END.
SPI_ERROR_OPUNKNOWN if type of query is unknown (this shouldn't occur).

If execution of your query was successful then one of the following (non-negative) values will be returned:

SPI_OK_UTILITY if some utility (e.g. CREATE TABLE ...) was executed
SPI_OK_SELECT if SELECT (but not SELECT ... INTO!) was executed
SPI_OK_SELINTO if SELECT ... INTO was executed
SPI_OK_INSERT if INSERT (or INSERT ... SELECT) was executed
SPI_OK_DELETE if DELETE was executed
SPI_OK_UPDATE if UPDATE was executed

Description

SPI_exec creates an execution plan (parser+planner+optimizer) and executes the query for tcount tuples.

Usage

This should only be called from a connected procedure. If tcount is zero then it executes the query for all tuples returned by the query scan. Using tcount > 0 you may restrict the number of tuples for which the query will be executed (much like a LIMIT clause). For example,

```
SPI_exec ("INSERT INTO tab SELECT * FROM tab", 5);
```

will allow at most 5 tuples to be inserted into table. If execution of your query was successful then a non-negative value will be returned.

Note

You may pass multiple queries in one string or query string may be re-written by RULEs. SPI_exec returns the result for the last query executed.

The actual number of tuples for which the (last) query was executed is returned in the global variable SPI_processed (if not SPI_OK_UTILITY). If SPI_OK_SELECT is returned then you may use global pointer SPITupleTable *SPI_tuptable to access the result tuples.

`SPI_exec` may return one of the following (negative) values:

SPI_ERROR_ARGUMENT if query is NULL or *`tcount`* < 0.
SPI_ERROR_UNCONNECTED if procedure is unconnected.
SPI_ERROR_COPY if COPY TO/FROM stdin.
SPI_ERROR_CURSOR if DECLARE/CLOSE CURSOR, FETCH.
SPI_ERROR_TRANSACTION if BEGIN/ABORT/END.
SPI_ERROR_OPUNKNOWN if type of query is unknown (this shouldn't occur).

Structures

If SPI_OK_SELECT is returned then you may use the global pointer SPITupleTable *SPI_tuptable to access the selected tuples.

Structure SPITupleTable is defined in spi.h:

```
   typedef struct
   {
       MemoryContext tuptabcxt;    /* memory context of result
 table */
       uint32      alloced;        /* # of alloced vals */
       uint32      free;           /* # of free vals */
       TupleDesc   tupdesc;        /* tuple descriptor */
       HeapTuple  *vals;           /* tuples */
   } SPITupleTable;
```

`vals` is an array of pointers to tuples (the number of useful entries is given by SPI_processed). `tupdesc` is a tuple descriptor which you may pass to SPI functions dealing with tuples. `tuptabcxt`, `alloced`, and `free` are internal fields not intended for use by SPI callers.

Note

Functions `SPI_exec`, `SPI_execp` and `SPI_prepare` change both SPI_processed and SPI_tuptable (just the pointer, not the contents of the structure). Save these two global variables into local procedure variables if you need to access the result of one `SPI_exec` or `SPI_execp` across later calls.

`SPI_finish` frees all SPITupleTables allocated during the current procedure. You can free a particular result table earlier, if you are done with it, by calling `SPI_freetuptable`.

Name

SPI_prepare — Prepares a plan for a query, without executing it yet

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_prepare(query, nargs, argtypes)
```

Inputs

query

Query string

nargs

Number of input parameters ($1 ... $nargs - as in SQL-functions)

argtypes

Pointer to array of type OIDs for input parameter types

Outputs

void *

Pointer to an execution plan (parser+planner+optimizer)

Description

`SPI_prepare` creates and returns an execution plan (parser+planner+optimizer) but doesn't execute the query. Should only be called from a connected procedure.

Usage

When the same or similar query is to be executed repeatedly, it may be advantageous to perform query planning only once. `SPI_prepare` converts a query string into an execution plan that can be passed repeatedly to `SPI_execp`.

A prepared query can be generalized by writing parameters ($1, $2, etc) in place of what would be constants in a normal query. The values of the parameters are then specified when `SPI_execp` is called. This allows the prepared query to be used over a wider range of situations than would be possible without parameters.

Note

However, there is a disadvantage: since the planner does not know the values that will be supplied for the parameters, it may make worse query planning choices than it would make for a simple query with all constants visible.

If the query uses parameters, their number and data types must be specified in the call to `SPI_prepare`.

The plan returned by `SPI_prepare` may be used only in current invocation of the procedure since `SPI_finish` frees memory allocated for a plan. But see `SPI_saveplan` to save a plan for longer.

If successful, a non-null pointer will be returned. Otherwise, you'll get a NULL plan. In both cases SPI_result will be set like the value returned by SPI_exec, except that it is set to SPI_ERROR_ARGUMENT if query is NULL or nargs < 0 or nargs > 0 && argtypes is NULL.

Name

SPI_execp — Executes a plan from `SPI_prepare`

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_execp(plan,
values,
nulls,
tcount)
```

Inputs

void **plan*

Execution plan

Datum **values*

Actual parameter values

char **nulls*

Array describing which parameters are NULLs

`n` indicates NULL (values[] entry ignored)
space indicates not NULL (values[] entry is valid)

int *tcount*

Number of tuples for which plan is to be executed

Outputs

int

Returns the same value as `SPI_exec` as well as

SPI_ERROR_ARGUMENT if *plan* is NULL or *tcount* < 0
SPI_ERROR_PARAM if *values* is NULL and *plan* was prepared with some parameters.

SPI_tuptable

initialized as in `SPI_exec` if successful

SPI_processed

initialized as in `SPI_exec` if successful

Description

`SPI_execp` executes a plan prepared by `SPI_prepare`. *tcount* has the same interpretation as in `SPI_exec`.

Usage

If *nulls* is NULL then `SPI_execp` assumes that all parameters (if any) are NOT NULL.

Note

If one of the objects (a relation, function, etc.) referenced by the prepared plan is dropped during your session (by your backend or another process) then the results of `SPI_execp` for this plan will be unpredictable.

Name

SPI_cursor_open — Sets up a cursor using a plan created with `SPI_prepare`

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_cursor_open(name,
plan,
values,
nulls)
```

Inputs

char *`name`

Name for portal, or NULL to let the system select a name

void *`plan`

Execution plan

Datum *`values`

Actual parameter values

char *`nulls`

Array describing which parameters are NULLs

`n` indicates NULL (values[] entry ignored)
space indicates not NULL (values[] entry is valid)

Outputs

Portal

Pointer to Portal containing cursor, or NULL on error

Description

`SPI_cursor_open` sets up a cursor (internally, a Portal) that will execute a plan prepared by `SPI_prepare`.

Using a cursor instead of executing the plan directly has two benefits. First, the result rows can be retrieved a few at a time, avoiding memory overrun for queries that return many rows. Second, a Portal can outlive the current procedure (it can, in fact, live to the end of the current transaction). Returning the portal name to the procedure's caller provides a way of returning a rowset result.

Usage

If `nulls` is NULL then `SPI_cursor_open` assumes that all parameters (if any) are NOT NULL.

Name

SPI_cursor_find — Finds an existing cursor (Portal) by name

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_cursor_find(name)
```

Inputs

char *name

Name of portal

Outputs

Portal

Pointer to Portal with given name, or NULL if not found

Description

`SPI_cursor_find` finds a pre-existing Portal by name. This is primarily useful to resolve a cursor name returned as text by some other function.

Name

SPI_cursor_fetch — Fetches some rows from a cursor

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_cursor_fetch(portal,
forward,
count)
```

Inputs

Portal *portal*

Portal containing cursor

bool *forward*

True for fetch forward, false for fetch backward

int *count*

Maximum number of rows to fetch

Outputs

SPI_tuptable

initialized as in `SPI_exec` if successful

SPI_processed

initialized as in `SPI_exec` if successful

Description

`SPI_cursor_fetch` fetches some (more) rows from a cursor. This is equivalent to the SQL command `FETCH`.

Name

SPI_cursor_move — Moves a cursor

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_cursor_move(portal,
forward,
count)
```

Inputs

Portal *portal*

Portal containing cursor

bool *forward*

True for move forward, false for move backward

int *count*

Maximum number of rows to move

Outputs

None

Description

`SPI_cursor_move` skips over some number of rows in a cursor. This is equivalent to the SQL command `MOVE`.

Name

SPI_cursor_close — Closes a cursor

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_cursor_close(portal)
```

Inputs

Portal *portal*

Portal containing cursor

Outputs

None

Description

`SPI_cursor_close` closes a previously created cursor and releases its Portal storage.

Usage

All open cursors are closed implicitly at transaction end. `SPI_cursor_close` need only be invoked if it is desirable to release resources sooner.

Name

SPI_saveplan — Saves a passed plan

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_saveplan(plan)
```

Inputs

void *query

Passed plan

Outputs

void *

Execution plan location. NULL if unsuccessful.

SPI_result

SPI_ERROR_ARGUMENT if plan is NULL
SPI_ERROR_UNCONNECTED if procedure is un-connected

Description

`SPI_saveplan` stores a plan prepared by `SPI_prepare` in safe memory protected from freeing by `SPI_finish` or the transaction manager.

In the current version of PostgreSQL there is no ability to store prepared plans in the system catalog and fetch them from there for execution. This will be implemented in future versions. As an alternative, there is the ability to reuse prepared plans in the subsequent invocations of your procedure in the current session. Use `SPI_execp` to execute this saved plan.

Usage

`SPI_saveplan` saves a passed plan (prepared by `SPI_prepare`) in memory protected from freeing by `SPI_finish` and by the transaction manager and returns a pointer to the saved plan. You may save the pointer returned in a local variable. Always check if this pointer is NULL or not either when preparing a plan or using an already prepared plan in SPI_execp (see below).

Note

If one of the objects (a relation, function, etc.) referenced by the prepared plan is dropped during your session (by your backend or another process) then the results of `SPI_execp` for this plan will be unpredictable.

17.2. Interface Support Functions

The functions described here provide convenient interfaces for extracting information from tuple sets returned by `SPI_exec` and other SPI interface functions.

All functions described in this section may be used by both connected and unconnected procedures.

Name

SPI_fnumber — Finds the attribute number for specified attribute name

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_fnumber(tupdesc, fname)
```

Inputs

TupleDesc *tupdesc*

Input tuple description

char * *fname*

Field name

Outputs

int

Attribute number

Valid one-based index number of attribute
SPI_ERROR_NOATTRIBUTE if the named attribute is not found

Description

`SPI_fnumber` returns the attribute number for the attribute with name in fname.

Usage

Attribute numbers are 1 based.

If the given fname refers to a system attribute (eg, `oid`) then the appropriate negative attribute number will be returned. The caller should be careful to test for exact equality to SPI_ERROR_NOATTRIBUTE to detect error; testing for result <= 0 is not correct unless system attributes should be rejected.

Name

SPI_fname — Finds the attribute name for the specified attribute number

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_fname(tupdesc, fnumber)
```

Inputs

TupleDesc *tupdesc*

Input tuple description

int *fnumber*

Attribute number

Outputs

char *

Attribute name

NULL if fnumber is out of range
SPI_result set to SPI_ERROR_NOATTRIBUTE on error

Description

`SPI_fname` returns the attribute name for the specified attribute.

Usage

Attribute numbers are 1 based.

Algorithm

Returns a newly-allocated copy of the attribute name. (Use pfree() to release the copy when done with it.)

Name

SPI_getvalue — Returns the string value of the specified attribute

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_getvalue(tuple, tupdesc, fnumber)
```

Inputs

HeapTuple *tuple*

Input tuple to be examined

TupleDesc *tupdesc*

Input tuple description

int *fnumber*

Attribute number

Outputs

char *

Attribute value or NULL if

attribute is NULL
fnumber is out of range (SPI_result set to SPI_ERROR_NOATTRIBUTE)
no output function available (SPI_result set to SPI_ERROR_NOOUTFUNC)

Description

`SPI_getvalue` returns an external (string) representation of the value of the specified attribute.

Usage

Attribute numbers are 1 based.

Algorithm

The result is returned as a palloc'd string. (Use pfree() to release the string when done with it.)

Name

SPI_getbinval — Returns the binary value of the specified attribute

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_getbinval(tuple, tupdesc, fnumber, isnull)
```

Inputs

HeapTuple *tuple*

Input tuple to be examined

TupleDesc *tupdesc*

Input tuple description

int *fnumber*

Attribute number

Outputs

Datum

Attribute binary value

bool * *isnull*

flag for null value in attribute

SPI_result

SPI_ERROR_NOATTRIBUTE

Description

`SPI_getbinval` returns the specified attribute's value in internal form (as a Datum).

Usage

Attribute numbers are 1 based.

Algorithm

Does not allocate new space for the datum. In the case of a pass-by- reference data type, the Datum will be a pointer into the given tuple.

Name

SPI_gettype — Returns the type name of the specified attribute

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_gettype(tupdesc, fnumber)
```

Inputs

TupleDesc *tupdesc*

Input tuple description

int *fnumber*

Attribute number

Outputs

char *

The type name for the specified attribute number

SPI_result

SPI_ERROR_NOATTRIBUTE

Description

`SPI_gettype` returns a copy of the type name for the specified attribute, or NULL on error.

Usage

Attribute numbers are 1 based.

Algorithm

Returns a newly-allocated copy of the type name. (Use pfree() to release the copy when done with it.)

Name

SPI_gettypeid — Returns the type OID of the specified attribute

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_gettypeid(tupdesc, fnumber)
```

Inputs

TupleDesc *tupdesc*

Input tuple description

int *fnumber*

Attribute number

Outputs

OID

The type OID for the specified attribute number

SPI_result

SPI_ERROR_NOATTRIBUTE

Description

`SPI_gettypeid` returns the type OID for the specified attribute.

Usage

Attribute numbers are 1 based.

Name

SPI_getrelname — Returns the name of the specified relation

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_getrelname(rel)
```

Inputs

Relation *rel*

Input relation

Outputs

char *

The name of the specified relation

Description

`SPI_getrelname` returns the name of the specified relation.

Algorithm

Returns a newly-allocated copy of the rel name. (Use pfree() to release the copy when done with it.)

17.3. Memory Management

PostgreSQL allocates memory within memory *contexts*, which provide a convenient method of managing allocations made in many different places that need to live for differing amounts of time. Destroying a context releases all the memory that was allocated in it. Thus, it is not necessary to keep track of individual objects to avoid memory leaks --- only a relatively small number of contexts have to be managed. `palloc` and related functions allocate memory from the "current" context.

`SPI_connect` creates a new memory context and makes it current. `SPI_finish` restores the previous current memory context and destroys the context created by `SPI_connect`. These actions ensure that transient memory allocations made inside your procedure are reclaimed at procedure exit, avoiding memory leakage.

However, if your procedure needs to return an allocated memory object (such as a value of a pass-by-reference data type), you can't allocate the return object using `palloc`, at least not while you are connected to SPI. If you try, the object will be deallocated during `SPI_finish`, and your procedure will not work reliably!

To solve this problem, use `SPI_palloc` to allocate your return object. `SPI_palloc` allocates space from "upper Executor" memory --- that is, the memory context that was current when `SPI_connect` was called, which is precisely the right context for return values of your procedure.

If called while not connected to SPI, `SPI_palloc` acts the same as plain `palloc`.

Before a procedure connects to the SPI manager, the current memory context is the upper Executor context, so all allocations made by the procedure via `palloc` or by SPI utility functions are made in this context.

After `SPI_connect` is called, the current context is the procedure's private context made by `SPI_connect`. All allocations made via `palloc`/`repalloc` or by SPI utility

functions (except for `SPI_copytuple`, `SPI_copytupledesc`, `SPI_copytupleintoslot`, `SPI_modifytuple`, and `SPI_palloc`) are made in this context.

When a procedure disconnects from the SPI manager (via `SPI_finish`) the current context is restored to the upper Executor context, and all allocations made in the procedure memory context are freed and can't be used any more!

All functions described in this section may be used by both connected and unconnected procedures. In an unconnected procedure, they act the same as the underlying ordinary backend functions (`palloc` etc).

Name

SPI_copytuple — Makes copy of tuple in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_copytuple(tuple)
```

Inputs

HeapTuple *tuple*

Input tuple to be copied

Outputs

HeapTuple

Copied tuple

non-NULL if *tuple* is not NULL and the copy was successful
NULL only if *tuple* is NULL

Description

`SPI_copytuple` makes a copy of tuple in upper Executor context.

Usage

TBD

Name

SPI_copytupledesc — Makes copy of tuple descriptor in upper Executor context

Synopsis

<refsynopsisdivinfo>2001-08-02</refsynopsisdivinfo>

```
SPI_copytupledesc(tupdesc)
```

Inputs

TupleDesc *tupdesc*

Input tuple descriptor to be copied

Outputs

TupleDesc

Copied tuple descriptor

non-NULL if *tupdesc* is not NULL and the copy was successful
NULL only if *tupdesc* is NULL

Description

`SPI_copytupledesc` makes a copy of tupdesc in upper Executor context.

Usage

TBD

Name

SPI_copytupleintoslot — Makes copy of tuple and descriptor in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_copytupleintoslot(tuple, tupdesc)
```

Inputs

HeapTuple *tuple*

Input tuple to be copied

TupleDesc *tupdesc*

Input tuple descriptor to be copied

Outputs

TupleTableSlot *

Tuple slot containing copied tuple and descriptor

non-NULL if *tuple* and *tupdesc* are not NULL and the copy was successful
NULL only if *tuple* or *tupdesc* is NULL

Description

`SPI_copytupleintoslot` makes a copy of tuple in upper Executor context, returning it in the form of a filled-in TupleTableSlot.

Usage

TBD

Name

SPI_modifytuple — Creates a tuple by replacing selected fields of a given tuple

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_modifytuple(rel, tuple, nattrs, attnum, Values, Nulls)
```

Inputs

Relation *rel*

Used only as source of tuple descriptor for tuple. (Passing a relation rather than a tuple descriptor is a misfeature.)

HeapTuple *tuple*

Input tuple to be modified

int *nattrs*

Number of attribute numbers in attnum array

int * *attnum*

Array of numbers of the attributes that are to be changed

Datum * *Values*

New values for the attributes specified

char * *Nulls*

Which new values are NULL, if any

Outputs

HeapTuple

New tuple with modifications

non-NULL if *tuple* is not NULL and the modify was successful
NULL only if *tuple* is NULL

SPI_result

SPI_ERROR_ARGUMENT if rel is NULL or tuple is NULL or natts <= 0 or attnum is NULL or Values is NULL.
SPI_ERROR_NOATTRIBUTE if there is an invalid attribute number in attnum (attnum <= 0 or > number of attributes in tuple)

Description

`SPI_modifytuple` creates a new tuple by substituting new values for selected attributes, copying the original tuple's attributes at other positions. The input tuple is not modified.

Usage

If successful, a pointer to the new tuple is returned. The new tuple is allocated in upper Executor context.

Name

SPI_palloc — Allocates memory in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_palloc(size)
```

Inputs

Size *size*

Octet size of storage to allocate

Outputs

void *

New storage space of specified size

Description

`SPI_palloc` allocates memory in upper Executor context.

Usage

TBD

Name

SPI_repalloc — Re-allocates memory in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_repalloc(pointer, size)
```

Inputs

void * *pointer*

Pointer to existing storage

Size *size*

Octet size of storage to allocate

Outputs

void *

New storage space of specified size with contents copied from existing area

Description

`SPI_repalloc` re-allocates memory in upper Executor context.

Usage

This function is no longer different from plain `repalloc`. It's kept just for backward compatibility of existing code.

Name

SPI_pfree — Frees memory in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_pfree(pointer)
```

Inputs

void * *pointer*

Pointer to existing storage

Outputs

None

Description

`SPI_pfree` frees memory in upper Executor context.

Usage

This function is no longer different from plain `pfree`. It's kept just for backward compatibility of existing code.

Name

SPI_freetuple — Frees a tuple allocated in upper Executor context

Synopsis

<refsynopsisdivinfo>1997-12-24</refsynopsisdivinfo>

```
SPI_freetuple(pointer)
```

Inputs

HeapTuple *pointer*

Pointer to allocated tuple

Outputs

None

Description

`SPI_freetuple` frees a tuple previously allocated in upper Executor context.

Usage

This function is no longer different from plain `heap_freetuple`. It's kept just for backward compatibility of existing code.

Name

SPI_freetuptable — Frees a tuple set created by `SPI_exec` or similar function

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_freetuptable(tuptable)
```

Inputs

SPITupleTable * *`tuptable`*

Pointer to tuple table

Outputs

None

Description

`SPI_freetuptable` frees a tuple set created by a prior SPI query function, such as `SPI_exec`.

Usage

This function is useful if a SPI procedure needs to execute multiple queries and does not want to keep the results of earlier queries around until it ends. Note that any unfreed tuple sets will be freed anyway at `SPI_finish`.

Name

SPI_freeplan — Releases a previously saved plan

Synopsis

<refsynopsisdivinfo>2001-11-14</refsynopsisdivinfo>

```
SPI_freeplan(plan)
```

Inputs

void *plan

Passed plan

Outputs

int

SPI_ERROR_ARGUMENT if plan is NULL

Description

`SPI_freeplan` releases a query plan previously returned by `SPI_prepare` or saved by `SPI_saveplan`.

17.4. Visibility of Data Changes

PostgreSQL data changes visibility rule: during a query execution, data changes made by the query itself (via SQL-function, SPI-function, triggers) are invisible to the query scan. For example, in query

```
INSERT INTO a SELECT * FROM a
```

tuples inserted are invisible for SELECT's scan. In effect, this duplicates the database table within itself (subject to unique index rules, of course) without recursing.

Changes made by query Q are visible to queries that are started after query Q, no matter whether they are started inside Q (during the execution of Q) or after Q is done.

17.5. Examples

This example of SPI usage demonstrates the visibility rule. There are more complex examples in src/test/regress/regress.c and in contrib/spi.

This is a very simple example of SPI usage. The procedure execq accepts an SQL-query in its first argument and tcount in its second, executes the query using SPI_exec and returns the number of tuples for which the query executed:

```
#include "executor/spi.h"   /* this is what you need to work with
 SPI */

int execq(text *sql, int cnt);

int
execq(text *sql, int cnt)
{
    char *query;
    int ret;
    int proc;
```

```
    /* Convert given TEXT object to a C string */
    query = DatumGetCString(DirectFunctionCall1(textout,

 PointerGetDatum(sql)));

    SPI_connect();

    ret = SPI_exec(query, cnt);

    proc = SPI_processed;
    /*
     * If this is SELECT and some tuple(s) fetched -
     * returns tuples to the caller via elog (INFO).
     */
    if ( ret == SPI_OK_SELECT && SPI_processed > 0 )
    {
        TupleDesc tupdesc = SPI_tuptable->tupdesc;
        SPITupleTable *tuptable = SPI_tuptable;
        char buf[8192];
        int i,j;

        for (j = 0; j < proc; j++)
        {
            HeapTuple tuple = tuptable->vals[j];

            for (i = 1, buf[0] = 0; i <= tupdesc->natts; i++)
                snprintf(buf + strlen (buf), sizeof(buf) -
 strlen(buf)," %s%s",
                         SPI_getvalue(tuple, tupdesc, i),
                         (i == tupdesc->natts) ? " " : " |");
            elog (INFO, "EXECQ: %s", buf);
        }
    }

    SPI_finish();

    pfree(query);

    return (proc);
}
```

Now, compile and create the function:

```
CREATE FUNCTION execq (text, integer) RETURNS integer
    AS '...path_to_so'
    LANGUAGE C;

vac=> SELECT execq('CREATE TABLE a (x INTEGER)', 0);
execq
-----
    0
(1 row)

vac=> INSERT INTO a VALUES (execq('INSERT INTO a VALUES (0)',0));
INSERT 167631 1
vac=> SELECT execq('SELECT * FROM a',0);
INFO:  EXECQ:  0 <<< inserted by execq
```

```
INFO:  EXECQ:  1 <<< value returned by execq and inserted by upper
 INSERT

execq
-----
    2
(1 row)

vac=> SELECT execq('INSERT INTO a SELECT x + 2 FROM a',1);
execq
-----
    1
(1 row)

vac=> SELECT execq('SELECT * FROM a', 10);
INFO:  EXECQ:  0

INFO:  EXECQ:  1

INFO:  EXECQ:  2 <<< 0 + 2, only one tuple inserted - as specified

execq
-----
    3            <<< 10 is max value only, 3 is real # of tuples
(1 row)

vac=> DELETE FROM a;
DELETE 3
vac=> INSERT INTO a VALUES (execq('SELECT * FROM a', 0) + 1);
INSERT 167712 1
vac=> SELECT * FROM a;
x
-
1               <<< no tuples in a (0) + 1
(1 row)

vac=> INSERT INTO a VALUES (execq('SELECT * FROM a', 0) + 1);
INFO:  EXECQ:  0
INSERT 167713 1
vac=> SELECT * FROM a;
x
-
1
2               <<< there was single tuple in a + 1
(2 rows)

--   This demonstrates data changes visibility rule:

vac=> INSERT INTO a SELECT execq('SELECT * FROM a', 0) * x FROM a;
INFO:  EXECQ:  1
INFO:  EXECQ:  2
INFO:  EXECQ:  1
INFO:  EXECQ:  2
INFO:  EXECQ:  2
INSERT 0 2
vac=> SELECT * FROM a;
x
-
```

```
1
2
2               <<< 2 tuples * 1 (x in first tuple)
6               <<< 3 tuples (2 + 1 just inserted) * 2 (x in
 second tuple)
(4 rows)            ^^^^^^^^
                    tuples visible to execq() in different
 invocations
```

Part III. Procedural Languages

This part documents the procedural languages available in the PostgreSQL distribution as well as general issues concerning procedural languages.

Table of Contents

18. Procedural Languages 281
    18.1. Introduction 281
    18.2. Installing Procedural Languages 281
19. PL/pgSQL - SQL Procedural Language 283
    19.1. Overview 283
        19.1.1. Advantages of Using PL/pgSQL 284
        19.1.2. Developing in PL/pgSQL 284
    19.2. Structure of PL/pgSQL 285
        19.2.1. Lexical Details 286
    19.3. Declarations 286
        19.3.1. Aliases for Function Parameters 286
        19.3.2. Row Types 287
        19.3.3. Records 288
        19.3.4. Attributes 288
        19.3.5. RENAME 289
    19.4. Expressions 289
    19.5. Basic Statements 290
        19.5.1. Assignment 290
        19.5.2. SELECT INTO 290
        19.5.3. Executing an expression or query with no result 291
        19.5.4. Executing dynamic queries 292
        19.5.5. Obtaining result status 293
    19.6. Control Structures 294
        19.6.1. Returning from a function 294
        19.6.2. Conditionals 294
        19.6.3. Simple Loops 296
        19.6.4. Looping Through Query Results 298
    19.7. Cursors 299
        19.7.1. Declaring Cursor Variables 299
        19.7.2. Opening Cursors 299
        19.7.3. Using Cursors 300
    19.8. Errors and Messages 301
        19.8.1. Exceptions 302
    19.9. Trigger Procedures 302
    19.10. Examples 304
    19.11. Porting from Oracle PL/SQL 304
        19.11.1. Main Differences 305
        19.11.2. Porting Functions 306
        19.11.3. Procedures 310
        19.11.4. Packages 311
        19.11.5. Other Things to Watch For 312
        19.11.6. Appendix 313
20. PL/Tcl - Tcl Procedural Language 316
    20.1. Overview 316
    20.2. Description 316
        20.2.1. PL/Tcl Functions and Arguments 316
        20.2.2. Data Values in PL/Tcl 317
        20.2.3. Global Data in PL/Tcl 317
        20.2.4. Database Access from PL/Tcl 318
        20.2.5. Trigger Procedures in PL/Tcl 320
        20.2.6. Modules and the `unknown` command 321
        20.2.7. Tcl Procedure Names 322
21. PL/Perl - Perl Procedural Language 323
    21.1. PL/Perl Functions and Arguments 323
    21.2. Data Values in PL/Perl 324

21.3. Database Access from PL/Perl 324
21.4. Trusted and Untrusted PL/Perl 324
21.5. Missing Features 325
22. PL/Python - Python Procedural Language 326
22.1. PL/Python Functions 326
22.2. Trigger Functions 326
22.3. Database Access 327
22.4. Restricted Environment 328

Chapter 18. Procedural Languages

18.1. Introduction

PostgreSQL allows users to add new programming languages to be available for writing functions and procedures. These are called *procedural languages* (PL). In the case of a function or trigger procedure written in a procedural language, the database server has no built-in knowledge about how to interpret the function's source text. Instead, the task is passed to a special handler that knows the details of the language. The handler could either do all the work of parsing, syntax analysis, execution, etc. itself, or it could serve as "glue" between PostgreSQL and an existing implementation of a programming language. The handler itself is a special programming language function compiled into a shared object and loaded on demand.

Writing a handler for a new procedural language is described in Section 9.8, "Procedural Language Handlers". Several procedural languages are available in the standard PostgreSQL distribution, which can serve as examples.

18.2. Installing Procedural Languages

A procedural language must be "installed" into each database where it is to be used. But procedural languages installed in the template1 database are automatically available in all subsequently created databases. So the database administrator can decide which languages are available in which databases, and can make some languages available by default if he chooses.

For the languages supplied with the standard distribution, the shell script `createlang` may be used instead of carrying out the details by hand. For example, to install PL/pgSQL into the template1 database, use

```
createlang plpgsql template1
```

The manual procedure described below is only recommended for installing custom languages that `createlang` does not know about.

Manual Procedural Language Installation

A procedural language is installed in the database in three steps, which must be carried out by a database superuser.

1. The shared object for the language handler must be compiled and installed into an appropriate library directory. This works in the same way as building and installing modules with regular user-defined C functions does; see Section 9.5.8, "Compiling and Linking Dynamically-Loaded Functions".

2. The handler must be declared with the command

   ```
   CREATE FUNCTION handler_function_name ()
       RETURNS LANGUAGE_HANDLER AS
       'path-to-shared-object' LANGUAGE C;
   ```

   The special return type of `LANGUAGE_HANDLER` tells the database that this function does not return one of the defined SQL data types and is not directly usable in SQL statements.

3. The PL must be declared with the command

   ```
   CREATE [TRUSTED] [PROCEDURAL] LANGUAGE language-name
       HANDLER handler_function_name;
   ```

The optional key word `TRUSTED` tells whether ordinary database users that have no superuser privileges should be allowed to use this language to create functions and trigger procedures. Since PL functions are executed inside the database server, the `TRUSTED` flag should only be given for languages that do not allow access to database server internals or the file system. The languages PL/pgSQL, PL/Tcl, PL/Perl, and PL/Python are known to be trusted; the languages PL/TclU and PL/PerlU are designed to provide unlimited functionality should *not* be marked trusted.

In a default PostgreSQL installation, the handler for the PL/pgSQL language is built and installed into the "library" directory. If Tcl/Tk support is configured in, the handlers for PL/Tcl and PL/TclU are also built and installed in the same location. Likewise, the PL/Perl and PL/PerlU handlers are built and installed if Perl support is configured, and PL/Python is installed if Python support is configured. The `createlang` script automates Step 2 and Step 3 described above.

Example 18.1. Manual Installation of PL/pgSQL

The following command tells the database server where to find the shared object for the PL/pgSQL language's call handler function.

```
CREATE FUNCTION plpgsql_call_handler () RETURNS LANGUAGE_HANDLER AS
    '$libdir/plpgsql' LANGUAGE C;
```

The command

```
CREATE TRUSTED PROCEDURAL LANGUAGE plpgsql
    HANDLER plpgsql_call_handler;
```

then defines that the previously declared call handler function should be invoked for functions and trigger procedures where the language attribute is `plpgsql`.

Chapter 19. PL/pgSQL - SQL Procedural Language

PL/pgSQL is a loadable procedural language for the PostgreSQL database system.

This package was originally written by Jan Wieck. This documentation was in part written by Roberto Mello (<rmello@fslc.usu.edu>).

19.1. Overview

The design goals of PL/pgSQL were to create a loadable procedural language that

- can be used to create functions and trigger procedures,
- adds control structures to the SQL language,
- can perform complex computations,
- inherits all user defined types, functions and operators,
- can be defined to be trusted by the server,
- is easy to use.

The PL/pgSQL call handler parses the function's source text and produces an internal binary instruction tree the first time the function is called (within any one backend process). The instruction tree fully translates the PL/pgSQL statement structure, but individual SQL expressions and SQL queries used in the function are not translated immediately.

As each expression and SQL query is first used in the function, the PL/pgSQL interpreter creates a prepared execution plan (using the SPI manager's `SPI_prepare` and `SPI_saveplan` functions). Subsequent visits to that expression or query re-use the prepared plan. Thus, a function with conditional code that contains many statements for which execution plans might be required will only prepare and save those plans that are really used during the lifetime of the database connection. This can substantially reduce the total amount of time required to parse, and generate query plans for the statements in a procedural language function. A disadvantage is that errors in a specific expression or query may not be detected until that part of the function is reached in execution.

Once PL/pgSQL has made a query plan for a particular query in a function, it will re-use that plan for the life of the database connection. This is usually a win for performance, but it can cause some problems if you dynamically alter your database schema. For example:

```
CREATE FUNCTION populate() RETURNS INTEGER AS '
DECLARE
    -- Declarations
BEGIN
    PERFORM my_function();
END;
' LANGUAGE 'plpgsql';
```

If you execute the above function, it will reference the OID for `my_function()` in the query plan produced for the PERFORM statement. Later, if you drop and re-create `my_function()`, then `populate()` will not be able to find `my_function()` anymore. You would then have to re-create `populate()`, or at least start a new database session so that it will be compiled afresh.

Because PL/pgSQL saves execution plans in this way, queries that appear directly in a PL/pgSQL function must refer to the same tables and fields on every execution; that is, you cannot use a parameter as the name of a table or field in a query. To get around this restriction, you can construct dynamic

queries using the PL/pgSQL EXECUTE statement --- at the price of constructing a new query plan on every execution.

Note

The PL/pgSQL EXECUTE statement is not related to the EXECUTE statement supported by the PostgreSQL backend. The backend EXECUTE statement cannot be used within PL/pgSQL functions (and is not needed).

Except for input/output conversion and calculation functions for user defined types, anything that can be defined in C language functions can also be done with PL/pgSQL. It is possible to create complex conditional computation functions and later use them to define operators or use them in functional indexes.

19.1.1. Advantages of Using PL/pgSQL

- Better performance (see Section 19.1.1.1, “Better Performance”)
- SQL support (see Section 19.1.1.2, “SQL Support”)
- Portability (see Section 19.1.1.3, “Portability”)

19.1.1.1. Better Performance

SQL is the language PostgreSQL (and most other relational databases) use as query language. It's portable and easy to learn. But every SQL statement must be executed individually by the database server.

That means that your client application must send each query to the database server, wait for it to process it, receive the results, do some computation, then send other queries to the server. All this incurs inter-process communication and may also incur network overhead if your client is on a different machine than the database server.

With PL/pgSQL you can group a block of computation and a series of queries *inside* the database server, thus having the power of a procedural language and the ease of use of SQL, but saving lots of time because you don't have the whole client/server communication overhead. This can make for a considerable performance increase.

19.1.1.2. SQL Support

PL/pgSQL adds the power of a procedural language to the flexibility and ease of SQL. With PL/pgSQL you can use all the data types, columns, operators and functions of SQL.

19.1.1.3. Portability

Because PL/pgSQL functions run inside PostgreSQL, these functions will run on any platform where PostgreSQL runs. Thus you can reuse code and reduce development costs.

19.1.2. Developing in PL/pgSQL

Developing in PL/pgSQL is pretty straight forward, especially if you have developed in other database procedural languages, such as Oracle's PL/SQL. Two good ways of developing in PL/pgSQL are:

- Using a text editor and reloading the file with `psql`
- Using PostgreSQL's GUI Tool: PgAccess

One good way to develop in PL/pgSQL is to simply use the text editor of your choice to create your functions, and in another window, use `psql` (PostgreSQL's interactive monitor) to load those

functions. If you are doing it this way, it is a good idea to write the function using `CREATE OR REPLACE FUNCTION`. That way you can reload the file to update the function definition. For example:

```
CREATE OR REPLACE FUNCTION testfunc(INTEGER) RETURNS INTEGER AS '
    ....
end;
' LANGUAGE 'plpgsql';
```

While running `psql`, you can load or reload such a function definition file with

```
    \i filename.sql
```

and then immediately issue SQL commands to test the function.

Another good way to develop in PL/pgSQL is using PostgreSQL's GUI tool: PgAccess. It does some nice things for you, like escaping single-quotes, and making it easy to recreate and debug functions.

19.2. Structure of PL/pgSQL

PL/pgSQL is a *block structured* language. The complete text of a function definition must be a *block*. A block is defined as:

```
[ <<label>> ]
[ DECLARE
    declarations ]
BEGIN
    statements
END;
```

Any *statement* in the statement section of a block can be a *sub-block*. Sub-blocks can be used for logical grouping or to localize variables to a small group of statements.

The variables declared in the declarations section preceding a block are initialized to their default values every time the block is entered, not only once per function call. For example:

```
CREATE FUNCTION somefunc() RETURNS INTEGER AS '
DECLARE
   quantity INTEGER := 30;
BEGIN
   RAISE NOTICE ''Quantity here is %'',quantity;  -- Quantity here
 is 30
   quantity := 50;
   --
   -- Create a sub-block
   --
   DECLARE
      quantity INTEGER := 80;
   BEGIN
      RAISE NOTICE ''Quantity here is %'',quantity;  -- Quantity
 here is 80
   END;

   RAISE NOTICE ''Quantity here is %'',quantity;  -- Quantity here
 is 50

   RETURN quantity;
END;
' LANGUAGE 'plpgsql';
```

It is important not to confuse the use of BEGIN/END for grouping statements in PL/pgSQL with the database commands for transaction control. PL/pgSQL's BEGIN/END are only for grouping; they do not start or end a transaction. Functions and trigger procedures are always executed within a transaction established by an outer query --- they cannot start or commit transactions, since PostgreSQL does not have nested transactions.

19.2.1. Lexical Details

Each statement and declaration within a block is terminated by a semicolon.

All keywords and identifiers can be written in mixed upper- and lower-case. Identifiers are implicitly converted to lower-case unless double-quoted.

There are two types of comments in PL/pgSQL. A double dash `--` starts a comment that extends to the end of the line. A `/*` starts a block comment that extends to the next occurrence of `*/`. Block comments cannot be nested, but double dash comments can be enclosed into a block comment and a double dash can hide the block comment delimiters `/*` and `*/`.

19.3. Declarations

All variables, rows and records used in a block must be declared in the declarations section of the block. (The only exception is that the loop variable of a FOR loop iterating over a range of integer values is automatically declared as an integer variable.)

PL/pgSQL variables can have any SQL data type, such as `INTEGER`, `VARCHAR` and `CHAR`.

Here are some examples of variable declarations:

```
user_id INTEGER;
quantity NUMERIC(5);
url VARCHAR;
myrow tablename%ROWTYPE;
myfield tablename.fieldname%TYPE;
arow RECORD;
```

The general syntax of a variable declaration is:

```
name [ CONSTANT ] type [ NOT NULL ] [ { DEFAULT | := } expression
 ];
```

The DEFAULT clause, if given, specifies the initial value assigned to the variable when the block is entered. If the DEFAULT clause is not given then the variable is initialized to the SQL NULL value.

The CONSTANT option prevents the variable from being assigned to, so that its value remains constant for the duration of the block. If NOT NULL is specified, an assignment of a NULL value results in a run-time error. All variables declared as NOT NULL must have a non-NULL default value specified.

The default value is evaluated every time the block is entered. So, for example, assigning '`now`' to a variable of type `timestamp` causes the variable to have the time of the current function call, not when the function was precompiled.

Examples:

```
quantity INTEGER DEFAULT 32;
url varchar := ''http://mysite.com'';
user_id CONSTANT INTEGER := 10;
```

19.3.1. Aliases for Function Parameters

```
name ALIAS FOR $n;
```

Parameters passed to functions are named with the identifiers `$1`, `$2`, etc. Optionally, aliases can be declared for `$n` parameter names for increased readability. Either the alias or the numeric identifier can then be used to refer to the parameter value. Some examples:

```
CREATE FUNCTION sales_tax(REAL) RETURNS REAL AS '
DECLARE
    subtotal ALIAS FOR $1;
BEGIN
    return subtotal * 0.06;
END;
' LANGUAGE 'plpgsql';


CREATE FUNCTION instr(VARCHAR,INTEGER) RETURNS INTEGER AS '
DECLARE
    v_string ALIAS FOR $1;
    index ALIAS FOR $2;
BEGIN
    -- Some computations here
END;
' LANGUAGE 'plpgsql';


CREATE FUNCTION use_many_fields(tablename) RETURNS TEXT AS '
DECLARE
    in_t ALIAS FOR $1;
BEGIN
    RETURN in_t.f1 || in_t.f3 || in_t.f5 || in_t.f7;
END;
' LANGUAGE 'plpgsql';
```

19.3.2. Row Types

```
name tablename%ROWTYPE;
```

A variable of a composite type is called a *row* variable (or *row-type* variable). Such a variable can hold a whole row of a SELECT or FOR query result, so long as that query's column set matches the declared type of the variable. The individual fields of the row value are accessed using the usual dot notation, for example `rowvar.field`.

Presently, a row variable can only be declared using the `%ROWTYPE` notation; although one might expect a bare table name to work as a type declaration, it won't be accepted within PL/pgSQL functions.

Parameters to a function can be composite types (complete table rows). In that case, the corresponding identifier $n will be a row variable, and fields can be selected from it, for example `$1.user_id`.

Only the user-defined attributes of a table row are accessible in a row-type variable, not OID or other system attributes (because the row could be from a view). The fields of the row type inherit the table's field size or precision for data types such as `char(n)`.

```
CREATE FUNCTION use_two_tables(tablename) RETURNS TEXT AS '
DECLARE
    in_t ALIAS FOR $1;
    use_t table2name%ROWTYPE;
BEGIN
    SELECT * INTO use_t FROM table2name WHERE ... ;
    RETURN in_t.f1 || use_t.f3 || in_t.f5 || use_t.f7;
END;
```

```
' LANGUAGE 'plpgsql';
```

19.3.3. Records

name RECORD;

Record variables are similar to row-type variables, but they have no predefined structure. They take on the actual row structure of the row they are assigned during a SELECT or FOR command. The substructure of a record variable can change each time it is assigned to. A consequence of this is that until a record variable is first assigned to, *it has no* substructure, and any attempt to access a field in it will draw a run-time error.

Note that RECORD is not a true data type, only a placeholder.

19.3.4. Attributes

Using the %TYPE and %ROWTYPE attributes, you can declare variables with the same data type or structure as another database item (e.g: a table field).

variable%TYPE

%TYPE provides the data type of a variable or database column. You can use this to declare variables that will hold database values. For example, let's say you have a column named user_id in your users table. To declare a variable with the same data type as users.user_id you write:

```
user_id   users.user_id%TYPE;
```

By using %TYPE you don't need to know the data type of the structure you are referencing, and most important, if the data type of the referenced item changes in the future (e.g: you change your table definition of user_id from INTEGER to REAL), you may not need to change your function definition.

table%ROWTYPE

%ROWTYPE provides the composite data type corresponding to a whole row of the specified table. *table* must be an existing table or view name of the database.

```
DECLARE
    users_rec users%ROWTYPE;
    user_id users.user_id%TYPE;
BEGIN
    user_id := users_rec.user_id;
    ...
```

```
CREATE FUNCTION does_view_exist(INTEGER) RETURNS bool AS '
   DECLARE
        key ALIAS FOR $1;
        table_data cs_materialized_views%ROWTYPE;
   BEGIN
        SELECT INTO table_data * FROM cs_materialized_views
               WHERE sort_key=key;

        IF NOT FOUND THEN
           RETURN false;
        END IF;
        RETURN true;
   END;
' LANGUAGE 'plpgsql';
```

19.3.5. RENAME

```
RENAME oldname TO newname;
```

Using the RENAME declaration you can change the name of a variable, record or row. This is primarily useful if NEW or OLD should be referenced by another name inside a trigger procedure. See also ALIAS.

Examples:

```
RENAME id TO user_id;
RENAME this_var TO that_var;
```

Note

RENAME appears to be broken as of PostgreSQL 7.3. Fixing this is of low priority, since ALIAS covers most of the practical uses of RENAME.

19.4. Expressions

All expressions used in PL/pgSQL statements are processed using the server's regular SQL executor. Expressions that appear to contain constants may in fact require run-time evaluation (e.g. `'now'` for the `timestamp` type) so it is impossible for the PL/pgSQL parser to identify real constant values other than the NULL keyword. All expressions are evaluated internally by executing a query

```
SELECT expression
```

using the SPI manager. In the expression, occurrences of PL/pgSQL variable identifiers are replaced by parameters and the actual values from the variables are passed to the executor in the parameter array. This allows the query plan for the SELECT to be prepared just once and then re-used for subsequent evaluations.

The evaluation done by the PostgreSQL main parser has some side effects on the interpretation of constant values. In detail there is a difference between what these two functions do:

```
CREATE FUNCTION logfunc1 (TEXT) RETURNS TIMESTAMP AS '
    DECLARE
        logtxt ALIAS FOR $1;
    BEGIN
        INSERT INTO logtable VALUES (logtxt, ''now'');
        RETURN ''now'';
    END;
' LANGUAGE 'plpgsql';
```

and

```
CREATE FUNCTION logfunc2 (TEXT) RETURNS TIMESTAMP AS '
    DECLARE
        logtxt ALIAS FOR $1;
        curtime timestamp;
    BEGIN
        curtime := ''now'';
        INSERT INTO logtable VALUES (logtxt, curtime);
        RETURN curtime;
    END;
' LANGUAGE 'plpgsql';
```

In the case of `logfunc1()`, the PostgreSQL main parser knows when preparing the plan for the INSERT, that the string `'now'` should be interpreted as `timestamp` because the target field of `logtable` is of that type. Thus, it will make a constant from it at this time and this constant value

is then used in all invocations of `logfunc1()` during the lifetime of the backend. Needless to say that this isn't what the programmer wanted.

In the case of `logfunc2()`, the PostgreSQL main parser does not know what type `'now'` should become and therefore it returns a data value of type `text` containing the string `'now'`. During the ensuing assignment to the local variable `curtime`, the PL/pgSQL interpreter casts this string to the `timestamp` type by calling the `text_out()` and `timestamp_in()` functions for the conversion. So, the computed time stamp is updated on each execution as the programmer expects.

The mutable nature of record variables presents a problem in this connection. When fields of a record variable are used in expressions or statements, the data types of the fields must not change between calls of one and the same expression, since the expression will be planned using the data type that is present when the expression is first reached. Keep this in mind when writing trigger procedures that handle events for more than one table. (EXECUTE can be used to get around this problem when necessary.)

19.5. Basic Statements

In this section and the following ones, we describe all the statement types that are explicitly understood by PL/pgSQL. Anything not recognized as one of these statement types is presumed to be an SQL query, and is sent to the main database engine to execute (after substitution for any PL/pgSQL variables used in the statement). Thus, for example, SQL `INSERT`, `UPDATE`, and `DELETE` commands may be considered to be statements of PL/pgSQL. But they are not specifically listed here.

19.5.1. Assignment

An assignment of a value to a variable or row/record field is written as:

identifier := *expression*;

As explained above, the expression in such a statement is evaluated by means of an SQL `SELECT` command sent to the main database engine. The expression must yield a single value.

If the expression's result data type doesn't match the variable's data type, or the variable has a specific size/precision (like `char(20)`), the result value will be implicitly converted by the PL/pgSQL interpreter using the result type's output-function and the variable type's input-function. Note that this could potentially result in run-time errors generated by the input function, if the string form of the result value is not acceptable to the input function.

Examples:

```
user_id := 20;
tax := subtotal * 0.06;
```

19.5.2. SELECT INTO

The result of a SELECT command yielding multiple columns (but only one row) can be assigned to a record variable, row-type variable, or list of scalar variables. This is done by:

SELECT INTO *target expressions* FROM ...;

where *target* can be a record variable, a row variable, or a comma-separated list of simple variables and record/row fields. Note that this is quite different from PostgreSQL's normal interpretation of SELECT INTO, which is that the INTO target is a newly created table. (If you want to create a table from a SELECT result inside a PL/pgSQL function, use the syntax `CREATE TABLE ... AS SELECT`.)

If a row or a variable list is used as target, the selected values must exactly match the structure of the target(s), or a run-time error occurs. When a record variable is the target, it automatically configures itself to the row type of the query result columns.

Except for the INTO clause, the SELECT statement is the same as a normal SQL SELECT query and can use the full power of SELECT.

If the SELECT query returns zero rows, null values are assigned to the target(s). If the SELECT query returns multiple rows, the first row is assigned to the target(s) and the rest are discarded. (Note that "the first row" is not well-defined unless you've used ORDER BY.)

At present, the INTO clause can appear almost anywhere in the SELECT query, but it is recommended to place it immediately after the SELECT keyword as depicted above. Future versions of PL/pgSQL may be less forgiving about placement of the INTO clause.

You can use `FOUND` immediately after a SELECT INTO statement to determine whether the assignment was successful (that is, at least one row was was returned by the SELECT statement). For example:

```
SELECT INTO myrec * FROM EMP WHERE empname = myname;
IF NOT FOUND THEN
    RAISE EXCEPTION ''employee % not found'', myname;
END IF;
```

Alternatively, you can use the `IS NULL` (or `ISNULL`) conditional to test for whether a RECORD/ROW result is null. Note that there is no way to tell whether any additional rows might have been discarded.

```
DECLARE
    users_rec RECORD;
    full_name varchar;
BEGIN
    SELECT INTO users_rec * FROM users WHERE user_id=3;

    IF users_rec.homepage IS NULL THEN
        -- user entered no homepage, return "http://"

        RETURN ''http://'';
    END IF;
END;
```

19.5.3. Executing an expression or query with no result

Sometimes one wishes to evaluate an expression or query but discard the result (typically because one is calling a function that has useful side-effects but no useful result value). To do this in PL/pgSQL, use the PERFORM statement:

```
PERFORM query;
```

This executes a `SELECT` *`query`* and discards the result. PL/pgSQL variables are substituted in the query as usual. Also, the special variable `FOUND` is set to true if the query produced at least one row, or false if it produced no rows.

Note

One might expect that SELECT with no INTO clause would accomplish this result, but at present the only accepted way to do it is PERFORM.

An example:

```
PERFORM create_mv(''cs_session_page_requests_mv'', my_query);
```

19.5.4. Executing dynamic queries

Oftentimes you will want to generate dynamic queries inside your PL/pgSQL functions, that is, queries that will involve different tables or different data types each time they are executed. PL/pgSQL's normal attempts to cache plans for queries will not work in such scenarios. To handle this sort of problem, the EXECUTE statement is provided:

```
EXECUTE query-string;
```

where *query-string* is an expression yielding a string (of type `text`) containing the *query* to be executed. This string is fed literally to the SQL engine.

Note in particular that no substitution of PL/pgSQL variables is done on the query string. The values of variables must be inserted in the query string as it is constructed.

When working with dynamic queries you will have to face escaping of single quotes in PL/pgSQL. Please refer to the table in Section 19.11, “Porting from Oracle PL/SQL” for a detailed explanation that will save you some effort.

Unlike all other queries in PL/pgSQL, a *query* run by an EXECUTE statement is not prepared and saved just once during the life of the server. Instead, the *query* is prepared each time the statement is run. The *query-string* can be dynamically created within the procedure to perform actions on variable tables and fields.

The results from SELECT queries are discarded by EXECUTE, and SELECT INTO is not currently supported within EXECUTE. So, the only way to extract a result from a dynamically-created SELECT is to use the FOR-IN-EXECUTE form described later.

An example:

```
EXECUTE ''UPDATE tbl SET ''
        || quote_ident(fieldname)
        || '' = ''
        || quote_literal(newvalue)
        || '' WHERE ...'';
```

This example shows use of the functions `quote_ident(TEXT)` and `quote_literal(TEXT)`. Variables containing field and table identifiers should be passed to function `quote_ident()`. Variables containing literal elements of the dynamic query string should be passed to `quote_literal()`. Both take the appropriate steps to return the input text enclosed in single or double quotes and with any embedded special characters properly escaped.

Here is a much larger example of a dynamic query and EXECUTE:

```
CREATE FUNCTION cs_update_referrer_type_proc() RETURNS INTEGER AS '
DECLARE
    referrer_keys RECORD;  -- Declare a generic record to be used
 in a FOR
    a_output varchar(4000);
BEGIN
    a_output := ''CREATE FUNCTION
 cs_find_referrer_type(varchar,varchar,varchar)
                  RETURNS VARCHAR AS ''''
                     DECLARE
                         v_host ALIAS FOR $1;
                         v_domain ALIAS FOR $2;
                         v_url ALIAS FOR $3;
                     BEGIN '';

    --
```

```
   -- Notice how we scan through the results of a query in a FOR
loop
   -- using the FOR <record> construct.
   --

   FOR referrer_keys IN SELECT * FROM cs_referrer_keys ORDER BY
try_order LOOP
       a_output := a_output || '' IF v_'' || referrer_keys.kind ||
'' LIKE ''''''''''
                || referrer_keys.key_string || '''''''''' THEN
RETURN ''''''
                || referrer_keys.referrer_type || ''''''; END
IF;'';
   END LOOP;

   a_output := a_output || '' RETURN NULL; END; '''' LANGUAGE
''''plpgsql'''';'';

   -- This works because we are not substituting any variables
   -- Otherwise it would fail. Look at PERFORM for another way to
run functions

   EXECUTE a_output;
END;
' LANGUAGE 'plpgsql';
```

19.5.5. Obtaining result status

There are several ways to determine the effect of a command. The first method is to use the `GET DIAGNOSTICS`, which has the form:

```
GET DIAGNOSTICS variable = item [ , ... ] ;
```

This command allows retrieval of system status indicators. Each *`item`* is a keyword identifying a state value to be assigned to the specified variable (which should be of the right data type to receive it). The currently available status items are `ROW_COUNT`, the number of rows processed by the last SQL query sent down to the SQL engine; and `RESULT_OID`, the OID of the last row inserted by the most recent SQL query. Note that `RESULT_OID` is only useful after an INSERT query.

```
    GET DIAGNOSTICS var_integer = ROW_COUNT;
```

There is a special variable named `FOUND` of type `boolean`. `FOUND` starts out false within each PL/pgSQL function. It is set by each of the following types of statements:

- A SELECT INTO statement sets `FOUND` true if it returns a row, false if no row is returned.
- A PERFORM statement sets `FOUND` true if it produces (discards) a row, false if no row is produced.
- UPDATE, INSERT, and DELETE statements set `FOUND` true if at least one row is affected, false if no row is affected.
- A FETCH statement sets `FOUND` true if it returns a row, false if no row is returned.
- A FOR statement sets `FOUND` true if it iterates one or more times, else false. This applies to all three variants of the FOR statement (integer FOR loops, record-set FOR loops, and dynamic record-set FOR loops). `FOUND` is only set when the FOR loop exits: inside the execution of the loop, `FOUND` is not modified by the FOR statement, although it may be changed by the execution of other statements within the loop body.

`FOUND` is a local variable; any changes to it affect only the current PL/pgSQL function.

19.6. Control Structures

Control structures are probably the most useful (and important) part of PL/pgSQL. With PL/pgSQL's control structures, you can manipulate PostgreSQL data in a very flexible and powerful way.

19.6.1. Returning from a function

```
RETURN expression;
```

RETURN with an expression is used to return from a PL/pgSQL function that does not return a set. The function terminates and the value of *expression* is returned to the caller.

To return a composite (row) value, you must write a record or row variable as the *expression*. When returning a scalar type, any expression can be used. The expression's result will be automatically cast into the function's return type as described for assignments. (If you have declared the function to return `void`, then the expression can be omitted, and will be ignored in any case.)

The return value of a function cannot be left undefined. If control reaches the end of the top-level block of the function without hitting a RETURN statement, a run-time error will occur.

When a PL/pgSQL function is declared to return `SETOF` *sometype*, the procedure to follow is slightly different. In that case, the individual items to return are specified in RETURN NEXT commands, and then a final RETURN command with no arguments is used to indicate that the function has finished executing. RETURN NEXT can be used with both scalar and composite data types; in the later case, an entire "table" of results will be returned. Functions that use RETURN NEXT should be called in the following fashion:

```
SELECT * FROM some_func();
```

That is, the function is used as a table source in a FROM clause.

```
RETURN NEXT expression;
```

RETURN NEXT does not actually return from the function; it simply saves away the value of the expression (or record or row variable, as appropriate for the data type being returned). Execution then continues with the next statement in the PL/pgSQL function. As successive RETURN NEXT commands are executed, the result set is built up. A final RETURN, which need have no argument, causes control to exit the function.

Note

The current implementation of RETURN NEXT for PL/pgSQL stores the entire result set before returning from the function, as discussed above. That means that if a PL/pgSQL function produces a very large result set, performance may be poor: data will be written to disk to avoid memory exhaustion, but the function itself will not return until the entire result set has been generated. A future version of PL/pgSQL may allow users to allow users to define set-returning functions that do not have this limitation. Currently, the point at which data begins being written to disk is controlled by the `SORT_MEM` configuration variable. Administrators who have sufficient memory to store larger result sets in memory should consider increasing this parameter.

19.6.2. Conditionals

`IF` statements let you execute commands based on certain conditions. PL/pgSQL has four forms of `IF`:

- `IF ... THEN`
- `IF ... THEN ... ELSE`
- `IF ... THEN ... ELSE IF` and

- IF ... THEN ... ELSIF ... THEN ... ELSE

19.6.2.1. IF-THEN

```
IF boolean-expression THEN
    statements
END IF;
```

IF-THEN statements are the simplest form of IF. The statements between THEN and END IF will be executed if the condition is true. Otherwise, they are skipped.

```
IF v_user_id <> 0 THEN
    UPDATE users SET email = v_email WHERE user_id = v_user_id;
END IF;
```

19.6.2.2. IF-THEN-ELSE

```
IF boolean-expression THEN
    statements
ELSE
    statements
END IF;
```

IF-THEN-ELSE statements add to IF-THEN by letting you specify an alternative set of statements that should be executed if the condition evaluates to FALSE.

```
IF parentid IS NULL or parentid = ''''
THEN
    return fullname;
ELSE
    return hp_true_filename(parentid) || ''/'' || fullname;
END IF;


IF v_count > 0 THEN
    INSERT INTO users_count(count) VALUES(v_count);
    return ''t'';
ELSE
    return ''f'';
END IF;
```

19.6.2.3. IF-THEN-ELSE IF

IF statements can be nested, as in the following example:

```
IF demo_row.sex = ''m'' THEN
  pretty_sex := ''man'';
ELSE
  IF demo_row.sex = ''f'' THEN
    pretty_sex := ''woman'';
  END IF;
END IF;
```

When you use this form, you are actually nesting an IF statement inside the ELSE part of an outer IF statement. Thus you need one END IF statement for each nested IF and one for the parent IF-ELSE. This is workable but grows tedious when there are many alternatives to be checked.

19.6.2.4. IF-THEN-ELSIF-ELSE

```
IF boolean-expression THEN
```

```
    statements
[ ELSIF boolean-expression THEN
    statements
[ ELSIF boolean-expression THEN
    statements
    ...]]
[ ELSE
    statements ]
END IF;
```

`IF-THEN-ELSIF-ELSE` provides a more convenient method of checking many alternatives in one statement. Formally it is equivalent to nested `IF-THEN-ELSE-IF-THEN` commands, but only one `END IF` is needed.

Here is an example:

```
IF number = 0 THEN
    result := ''zero'';
ELSIF number > 0 THEN
    result := ''positive'';
ELSIF number < 0 THEN
    result := ''negative'';
ELSE
    -- hmm, the only other possibility is that number IS NULL
    result := ''NULL'';
END IF;
```

The final ELSE section is optional.

19.6.3. Simple Loops

With the LOOP, EXIT, WHILE and FOR statements, you can arrange for your PL/pgSQL function to repeat a series of commands.

19.6.3.1. LOOP

```
[<<label>>]
LOOP
    statements
END LOOP;
```

LOOP defines an unconditional loop that is repeated indefinitely until terminated by an EXIT or RETURN statement. The optional label can be used by EXIT statements in nested loops to specify which level of nesting should be terminated.

19.6.3.2. EXIT

```
EXIT [ label ] [ WHEN expression ];
```

If no *label* is given, the innermost loop is terminated and the statement following END LOOP is executed next. If *label* is given, it must be the label of the current or some outer level of nested loop or block. Then the named loop or block is terminated and control continues with the statement after the loop's/block's corresponding END.

If WHEN is present, loop exit occurs only if the specified condition is true, otherwise control passes to the statement after EXIT.

Examples:

```
LOOP
    -- some computations
```

```
    IF count > 0 THEN
        EXIT;  -- exit loop
    END IF;
END LOOP;

LOOP
    -- some computations
    EXIT WHEN count > 0;
END LOOP;

BEGIN
    -- some computations
    IF stocks > 100000 THEN
        EXIT;  -- illegal. Can't use EXIT outside of a LOOP
    END IF;
END;
```

19.6.3.3. WHILE

```
[<<label>>]
WHILE expression LOOP
    statements
END LOOP;
```

The WHILE statement repeats a sequence of statements so long as the condition expression evaluates to true. The condition is checked just before each entry to the loop body.

For example:

```
WHILE amount_owed > 0 AND gift_certificate_balance > 0 LOOP
    -- some computations here
END LOOP;

WHILE NOT boolean_expression LOOP
    -- some computations here
END LOOP;
```

19.6.3.4. FOR (integer for-loop)

```
[<<label>>]
FOR name IN [ REVERSE ] expression .. expression LOOP
    statements
END LOOP;
```

This form of FOR creates a loop that iterates over a range of integer values. The variable *name* is automatically defined as type integer and exists only inside the loop. The two expressions giving the lower and upper bound of the range are evaluated once when entering the loop. The iteration step is normally 1, but is -1 when REVERSE is specified.

Some examples of integer FOR loops:

```
FOR i IN 1..10 LOOP
  -- some expressions here

    RAISE NOTICE ''i is %'',i;
END LOOP;

FOR i IN REVERSE 10..1 LOOP
    -- some expressions here
END LOOP;
```

19.6.4. Looping Through Query Results

Using a different type of FOR loop, you can iterate through the results of a query and manipulate that data accordingly. The syntax is:

```
[<<label>>]
FOR record | row IN select_query LOOP
    statements
END LOOP;
```

The record or row variable is successively assigned all the rows resulting from the SELECT query and the loop body is executed for each row. Here is an example:

```
CREATE FUNCTION cs_refresh_mviews () RETURNS INTEGER AS '
DECLARE
     mviews RECORD;
BEGIN
     PERFORM cs_log(''Refreshing materialized views...'');

     FOR mviews IN SELECT * FROM cs_materialized_views ORDER BY
 sort_key LOOP

         -- Now "mviews" has one record from cs_materialized_views

         PERFORM cs_log(''Refreshing materialized view '' ||
 quote_ident(mviews.mv_name) || ''...'');
         EXECUTE ''TRUNCATE TABLE  '' ||
 quote_ident(mviews.mv_name);
         EXECUTE ''INSERT INTO '' || quote_ident(mviews.mv_name) ||
 '' '' || mviews.mv_query;
     END LOOP;

     PERFORM cs_log(''Done refreshing materialized views.'');
     RETURN 1;
end;
' LANGUAGE 'plpgsql';
```

If the loop is terminated by an EXIT statement, the last assigned row value is still accessible after the loop.

The FOR-IN-EXECUTE statement is another way to iterate over records:

```
[<<label>>]
FOR record | row IN EXECUTE text_expression LOOP
    statements
END LOOP;
```

This is like the previous form, except that the source SELECT statement is specified as a string expression, which is evaluated and re-planned on each entry to the FOR loop. This allows the programmer to choose the speed of a pre-planned query or the flexibility of a dynamic query, just as with a plain EXECUTE statement.

Note

The PL/pgSQL parser presently distinguishes the two kinds of FOR loops (integer or record-returning) by checking whether the target variable mentioned just after FOR has been declared as a record/row variable. If not, it's presumed to be an integer FOR loop. This can cause rather nonintuitive error messages when the true problem is, say, that one has misspelled the FOR variable name.

19.7. Cursors

Rather than executing a whole query at once, it is possible to set up a *cursor* that encapsulates the query, and then read the query result a few rows at a time. One reason for doing this is to avoid memory overrun when the result contains a large number of rows. (However, PL/pgSQL users don't normally need to worry about that, since FOR loops automatically use a cursor internally to avoid memory problems.) A more interesting usage is to return a reference to a cursor that it has created, allowing the caller to read the rows. This provides an efficient way to return large row sets from functions.

19.7.1. Declaring Cursor Variables

All access to cursors in PL/pgSQL goes through cursor variables, which are always of the special data type `refcursor`. One way to create a cursor variable is just to declare it as a variable of type `refcursor`. Another way is to use the cursor declaration syntax, which in general is:

```
name CURSOR [ ( arguments ) ] FOR select_query ;
```

(`FOR` may be replaced by `IS` for Oracle compatibility.) *`arguments`*, if any, are a comma-separated list of *`name datatype`* pairs that define names to be replaced by parameter values in the given query. The actual values to substitute for these names will be specified later, when the cursor is opened.

Some examples:

```
DECLARE
    curs1 refcursor;
    curs2 CURSOR FOR SELECT * from tenk1;
    curs3 CURSOR (key int) IS SELECT * from tenk1 where unique1 =
 key;
```

All three of these variables have the data type `refcursor`, but the first may be used with any query, while the second has a fully specified query already *bound* to it, and the last has a parameterized query bound to it. (`key` will be replaced by an integer parameter value when the cursor is opened.) The variable `curs1` is said to be *unbound* since it is not bound to any particular query.

19.7.2. Opening Cursors

Before a cursor can be used to retrieve rows, it must be *opened*. (This is the equivalent action to the SQL command `DECLARE CURSOR`.) PL/pgSQL has four forms of the OPEN statement, two of which use unbound cursor variables and the other two use bound cursor variables.

19.7.2.1. OPEN FOR SELECT

```
OPEN unbound-cursor FOR SELECT ...;
```

The cursor variable is opened and given the specified query to execute. The cursor cannot be open already, and it must have been declared as an unbound cursor (that is, as a simple `refcursor` variable). The SELECT query is treated in the same way as other SELECT statements in PL/pgSQL: PL/pgSQL variable names are substituted, and the query plan is cached for possible re-use.

```
OPEN curs1 FOR SELECT * FROM foo WHERE key = mykey;
```

19.7.2.2. OPEN FOR EXECUTE

```
OPEN unbound-cursor FOR EXECUTE query-string;
```

The cursor variable is opened and given the specified query to execute. The cursor cannot be open already, and it must have been declared as an unbound cursor (that is, as a simple `refcursor` variable). The query is specified as a string expression in the same way as in the EXECUTE command. As usual, this gives flexibility so the query can vary from one run to the next.

```
OPEN curs1 FOR EXECUTE ''SELECT * FROM '' || quote_ident($1);
```

19.7.2.3. Opening a bound cursor

```
OPEN bound-cursor [ ( argument_values ) ];
```

This form of OPEN is used to open a cursor variable whose query was bound to it when it was declared. The cursor cannot be open already. A list of actual argument value expressions must appear if and only if the cursor was declared to take arguments. These values will be substituted in the query. The query plan for a bound cursor is always considered cacheable --- there is no equivalent of EXECUTE in this case.

```
OPEN curs2;
OPEN curs3(42);
```

19.7.3. Using Cursors

Once a cursor has been opened, it can be manipulated with the statements described here.

These manipulations need not occur in the same function that opened the cursor to begin with. You can return a `refcursor` value out of a function and let the caller operate on the cursor. (Internally, a `refcursor` value is simply the string name of a Portal containing the active query for the cursor. This name can be passed around, assigned to other `refcursor` variables, and so on, without disturbing the Portal.)

All Portals are implicitly closed at transaction end. Therefore a `refcursor` value is useful to reference an open cursor only until the end of the transaction.

19.7.3.1. FETCH

```
FETCH cursor INTO target;
```

FETCH retrieves the next row from the cursor into a target, which may be a row variable, a record variable, or a comma-separated list of simple variables, just like SELECT INTO. As with SELECT INTO, the special variable `FOUND` may be checked to see whether a row was obtained or not.

```
FETCH curs1 INTO rowvar;
FETCH curs2 INTO foo,bar,baz;
```

19.7.3.2. CLOSE

```
CLOSE cursor;
```

CLOSE closes the Portal underlying an open cursor. This can be used to release resources earlier than end of transaction, or to free up the cursor variable to be opened again.

```
CLOSE curs1;
```

19.7.3.3. Returning Cursors

PL/pgSQL functions can return cursors to the caller. This is used to return multiple rows or columns from the function. The function opens the cursor and returns the cursor name to the caller. The caller can then FETCH rows from the cursor. The cursor can be closed by the caller, or it will be closed automatically when the transaction closes.

The cursor name returned by the function can be specified by the caller or automatically generated. The following example shows how a cursor name can be supplied by the caller:

```
CREATE TABLE test (col text);
INSERT INTO test VALUES ('123');
```

```
CREATE FUNCTION reffunc(refcursor) RETURNS refcursor AS '
BEGIN
        OPEN $1 FOR SELECT col FROM test;
        RETURN $1;
END;
' LANGUAGE 'plpgsql';

BEGIN;
SELECT reffunc('funccursor');
FETCH ALL IN funccursor;
COMMIT;
```

The following example uses automatic cursor name generation:

```
CREATE FUNCTION reffunc2() RETURNS refcursor AS '
DECLARE
        ref refcursor;
BEGIN
        OPEN ref FOR SELECT col FROM test;
        RETURN ref;
END;
' LANGUAGE 'plpgsql';

BEGIN;
SELECT reffunc2();

        reffunc2
  --------------------
   <unnamed cursor 1>
  (1 row)

FETCH ALL IN "<unnamed cursor 1>";
COMMIT;
```

19.8. Errors and Messages

Use the RAISE statement to report messages and raise errors.

```
RAISE level 'format' [, variable [...]];
```

Possible levels are DEBUG (write the message to the server log), LOG (write the message to the server log with a higher priority), INFO, NOTICE and WARNING (write the message to the server log and send it to the client, with respectively higher priorities), and EXCEPTION (raise an error and abort the current transaction). Whether error messages of a particular priority are reported to the client, written to the server log, or both is controlled by the SERVER_MIN_MESSAGES and CLIENT_MIN_MESSAGES configuration variables. See the *PostgreSQL Administrator's Guide* for more information.

Inside the format string, % is replaced by the next optional argument's external representation. Write %% to emit a literal %. Note that the optional arguments must presently be simple variables, not expressions, and the format must be a simple string literal.

Examples:

```
RAISE NOTICE ''Calling cs_create_job(%)'',v_job_id;
```

In this example, the value of v_job_id will replace the % in the string.

```
RAISE EXCEPTION ''Inexistent ID --> %'',user_id;
```

This will abort the transaction with the given error message.

19.8.1. Exceptions

PostgreSQL does not have a very smart exception handling model. Whenever the parser, planner/optimizer or executor decide that a statement cannot be processed any longer, the whole transaction gets aborted and the system jumps back into the main loop to get the next query from the client application.

It is possible to hook into the error mechanism to notice that this happens. But currently it is impossible to tell what really caused the abort (input/output conversion error, floating-point error, parse error). And it is possible that the database backend is in an inconsistent state at this point so returning to the upper executor or issuing more commands might corrupt the whole database.

Thus, the only thing PL/pgSQL currently does when it encounters an abort during execution of a function or trigger procedure is to write some additional `NOTICE` level log messages telling in which function and where (line number and type of statement) this happened. The error always stops execution of the function.

19.9. Trigger Procedures

PL/pgSQL can be used to define trigger procedures. A trigger procedure is created with the `CREATE FUNCTION` command as a function with no arguments and a return type of `TRIGGER`. Note that the function must be declared with no arguments even if it expects to receive arguments specified in `CREATE TRIGGER` --- trigger arguments are passed via `TG_ARGV`, as described below.

When a PL/pgSQL function is called as a trigger, several special variables are created automatically in the top-level block. They are:

`NEW`

Data type `RECORD`; variable holding the new database row for INSERT/UPDATE operations in ROW level triggers.

`OLD`

Data type `RECORD`; variable holding the old database row for UPDATE/DELETE operations in ROW level triggers.

`TG_NAME`

Data type `name`; variable that contains the name of the trigger actually fired.

`TG_WHEN`

Data type `text`; a string of either `BEFORE` or `AFTER` depending on the trigger's definition.

`TG_LEVEL`

Data type `text`; a string of either `ROW` or `STATEMENT` depending on the trigger's definition.

`TG_OP`

Data type `text`; a string of `INSERT`, `UPDATE` or `DELETE` telling for which operation the trigger is fired.

`TG_RELID`

Data type `oid`; the object ID of the table that caused the trigger invocation.

`TG_RELNAME`

Data type `name`; the name of the table that caused the trigger invocation.

`TG_NARGS`

Data type `integer`; the number of arguments given to the trigger procedure in the `CREATE TRIGGER` statement.

`TG_ARGV[]`

Data type array of `text`; the arguments from the `CREATE TRIGGER` statement. The index counts from 0 and can be given as an expression. Invalid indices (< 0 or >= `tg_nargs`) result in a null value.

A trigger function must return either NULL or a record/row value having exactly the structure of the table the trigger was fired for. Triggers fired BEFORE may return NULL to signal the trigger manager to skip the rest of the operation for this row (ie, subsequent triggers are not fired, and the INSERT/UPDATE/DELETE does not occur for this row). If a non-NULL value is returned then the operation proceeds with that row value. Note that returning a row value different from the original value of NEW alters the row that will be inserted or updated. It is possible to replace single values directly in NEW and return that, or to build a complete new record/row to return.

The return value of a trigger fired AFTER is ignored; it may as well always return a NULL value. But an AFTER trigger can still abort the operation by raising an error.

Example 19.1. A PL/pgSQL Trigger Procedure Example

This example trigger ensures that any time a row is inserted or updated in the table, the current user name and time are stamped into the row. And it ensures that an employee's name is given and that the salary is a positive value.

```
CREATE TABLE emp (
    empname text,
    salary integer,
    last_date timestamp,
    last_user text
);

CREATE FUNCTION emp_stamp () RETURNS TRIGGER AS '
    BEGIN
        -- Check that empname and salary are given
        IF NEW.empname ISNULL THEN
            RAISE EXCEPTION ''empname cannot be NULL value'';
        END IF;
        IF NEW.salary ISNULL THEN
            RAISE EXCEPTION ''% cannot have NULL salary'',
 NEW.empname;
        END IF;

        -- Who works for us when she must pay for?
        IF NEW.salary < 0 THEN
            RAISE EXCEPTION ''% cannot have a negative salary'',
 NEW.empname;
        END IF;

        -- Remember who changed the payroll when
        NEW.last_date := ''now'';
        NEW.last_user := current_user;
        RETURN NEW;
    END;
' LANGUAGE 'plpgsql';

CREATE TRIGGER emp_stamp BEFORE INSERT OR UPDATE ON emp
```

```
    FOR EACH ROW EXECUTE PROCEDURE emp_stamp();
```

19.10. Examples

Here are only a few functions to demonstrate how easy it is to write PL/pgSQL functions. For more complex examples the programmer might look at the regression test for PL/pgSQL.

One painful detail in writing functions in PL/pgSQL is the handling of single quotes. The function's source text in `CREATE FUNCTION` must be a literal string. Single quotes inside of literal strings must be either doubled or quoted with a backslash. We are still looking for an elegant alternative. In the meantime, doubling the single quotes as in the examples below should be used. Any solution for this in future versions of PostgreSQL will be forward compatible.

For a detailed explanation and examples of how to escape single quotes in different situations, please see Section 19.11.1.1, “Quote Me on That: Escaping Single Quotes”.

Example 19.2. A Simple PL/pgSQL Function to Increment an Integer

The following two PL/pgSQL functions are identical to their counterparts from the C language function discussion. This function receives an `integer` and increments it by one, returning the incremented value.

```
CREATE FUNCTION add_one (integer) RETURNS INTEGER AS '
    BEGIN
        RETURN $1 + 1;
    END;
' LANGUAGE 'plpgsql';
```

Example 19.3. A Simple PL/pgSQL Function to Concatenate Text

This function receives two `text` parameters and returns the result of concatenating them.

```
CREATE FUNCTION concat_text (TEXT, TEXT) RETURNS TEXT AS '
    BEGIN
        RETURN $1 || $2;
    END;
' LANGUAGE 'plpgsql';
```

Example 19.4. A PL/pgSQL Function on Composite Type

In this example, we take `EMP` (a table) and an `integer` as arguments to our function, which returns a `boolean`. If the `salary` field of the `EMP` table is `NULL`, we return `f`. Otherwise we compare with that field with the `integer` passed to the function and return the `boolean` result of the comparison (t or f). This is the PL/pgSQL equivalent to the example from the C functions.

```
CREATE FUNCTION c_overpaid (EMP, INTEGER) RETURNS BOOLEAN AS '
    DECLARE
        emprec ALIAS FOR $1;
        sallim ALIAS FOR $2;
    BEGIN
        IF emprec.salary ISNULL THEN
            RETURN ''f'';
        END IF;
        RETURN emprec.salary > sallim;
    END;
' LANGUAGE 'plpgsql';
```

19.11. Porting from Oracle PL/SQL

Roberto Mello <rmello@fslc.usu.edu>

Author

Roberto Mello (<rmello@fslc.usu.edu>)

This section explains differences between Oracle's PL/SQL and PostgreSQL's PL/pgSQL languages in the hopes of helping developers port applications from Oracle to PostgreSQL. Most of the code here is from the ArsDigita[1] Clickstream module[2] that I ported to PostgreSQL when I took an internship with OpenForce Inc.[3] in the Summer of 2000.

PL/pgSQL is similar to PL/SQL in many aspects. It is a block structured, imperative language (all variables have to be declared). PL/SQL has many more features than its PostgreSQL counterpart, but PL/pgSQL allows for a great deal of functionality and it is being improved constantly.

19.11.1. Main Differences

Some things you should keep in mind when porting from Oracle to PostgreSQL:

- No default parameters in PostgreSQL.
- You can overload functions in PostgreSQL. This is often used to work around the lack of default parameters.
- Assignments, loops and conditionals are similar.
- No need for cursors in PostgreSQL, just put the query in the FOR statement (see example below)
- In PostgreSQL you *need* to escape single quotes. See Section 19.11.1.1, “Quote Me on That: Escaping Single Quotes”.

19.11.1.1. Quote Me on That: Escaping Single Quotes

In PostgreSQL you need to escape single quotes inside your function definition. This can lead to quite amusing code at times, especially if you are creating a function that generates other function(s), as in Example 19.6, “ A Function that Creates Another Function ”. One thing to keep in mind when escaping lots of single quotes is that, except for the beginning/ending quotes, all the others will come in even quantity.

Table 19.1, “Single Quotes Escaping Chart” gives the scoop. (You'll love this little chart.)

Table 19.1. Single Quotes Escaping Chart

No. of Quotes	Usage	Example	Result
1	To begin/terminate function bodies	`CREATE FUNCTION foo() RETURNS INTEGER AS '...' LANGUAGE 'plpgsql';`	as is
2	In assignments, SELECT statements, to delimit strings, etc.	`a_output := ''Blah''; SELECT * FROM users WHERE f_name=''foobar'';`	`SELECT * FROM users WHERE f_name='foobar';`
4	When you need two single quotes in your	`a_output := a_output || '' AND name`	`AND name LIKE 'foobar' AND ...`

[1] http://www.arsdigita.com
[2] http://www.arsdigita.com/asj/clickstream
[3] http://www.openforce.net

No. of Quotes	Usage	Example	Result
	resulting string without terminating that string.	`LIKE '''foobar''' AND ...''`	
6	When you want double quotes in your resulting string *and* terminate that string.	`a_output := a_output || '' AND name LIKE ''''foobar''''''`	`AND name LIKE 'foobar'`
10	When you want two single quotes in the resulting string (which accounts for 8 quotes) *and* terminate that string (2 more). You will probably only need that if you were using a function to generate other functions (like in Example 19.6, " A Function that Creates Another Function ").	`a_output := a_output || '' if v_'' || referrer_keys.kind || '' like '''''''''' || referrer_keys.key_string || '''''''''' then return '''''' || referrer_keys.referrer_type || ''''''; end if;'';`	`if v_<...> like ''<...>'' then return ''<...>''; end if;`

19.11.2. Porting Functions

Example 19.5. A Simple Function

Here is an Oracle function:

```
CREATE OR REPLACE FUNCTION cs_fmt_browser_version(v_name IN
 varchar, v_version IN varchar)
RETURN varchar IS
BEGIN
    IF v_version IS NULL THEN
        RETURN v_name;
    END IF;
    RETURN v_name || '/' || v_version;
END;
/
SHOW ERRORS;
```

Let's go through this function and see the differences to PL/pgSQL:

- PostgreSQL does not have named parameters. You have to explicitly alias them inside your function.
- Oracle can have `IN`, `OUT`, and `INOUT` parameters passed to functions. The `INOUT`, for example, means that the parameter will receive a value and return another. PostgreSQL only has "IN" parameters and functions can return only a single value.
- The `RETURN` key word in the function prototype (not the function body) becomes `RETURNS` in PostgreSQL.
- On PostgreSQL functions are created using single quotes as delimiters, so you have to escape single quotes inside your functions (which can be quite annoying at times; see Section 19.11.1.1, "Quote Me on That: Escaping Single Quotes").

- The `/show errors` command does not exist in PostgreSQL.

So let's see how this function would look when ported to PostgreSQL:

```
CREATE OR REPLACE FUNCTION cs_fmt_browser_version(VARCHAR, VARCHAR)
RETURNS VARCHAR AS '
DECLARE
    v_name ALIAS FOR $1;
    v_version ALIAS FOR $2;
BEGIN
    IF v_version IS NULL THEN
        return v_name;
    END IF;
    RETURN v_name || ''/'' || v_version;
END;
' LANGUAGE 'plpgsql';
```

Example 19.6. A Function that Creates Another Function

The following procedure grabs rows from a `SELECT` statement and builds a large function with the results in `IF` statements, for the sake of efficiency. Notice particularly the differences in cursors, `FOR` loops, and the need to escape single quotes in PostgreSQL.

```
CREATE OR REPLACE PROCEDURE cs_update_referrer_type_proc IS
    CURSOR referrer_keys IS
        SELECT * FROM cs_referrer_keys
        ORDER BY try_order;

    a_output VARCHAR(4000);
BEGIN
    a_output := 'CREATE OR REPLACE FUNCTION
 cs_find_referrer_type(v_host IN VARCHAR, v_domain IN VARCHAR,
v_url IN VARCHAR) RETURN VARCHAR IS BEGIN';

    FOR referrer_key IN referrer_keys LOOP
        a_output := a_output || ' IF v_' || referrer_key.kind || '
 LIKE ''' ||
referrer_key.key_string || ''' THEN RETURN ''' ||
 referrer_key.referrer_type ||
'''; END IF;';
    END LOOP;

    a_output := a_output || ' RETURN NULL; END;';
    EXECUTE IMMEDIATE a_output;
END;
/
show errors
```

Here is how this function would end up in PostgreSQL:

```
CREATE FUNCTION cs_update_referrer_type_proc() RETURNS INTEGER AS '
DECLARE
    referrer_keys RECORD;  -- Declare a generic record to be used
 in a FOR
    a_output varchar(4000);
BEGIN
    a_output := ''CREATE FUNCTION
 cs_find_referrer_type(VARCHAR,VARCHAR,VARCHAR)
                  RETURNS VARCHAR AS ''''
```

```
                    DECLARE
                        v_host ALIAS FOR $1;
                        v_domain ALIAS FOR $2;
                        v_url ALIAS FOR $3;
                    BEGIN '';

    --
    -- Notice how we scan through the results of a query in a FOR
 loop
    -- using the FOR <record> construct.
    --

    FOR referrer_keys IN SELECT * FROM cs_referrer_keys ORDER BY
 try_order LOOP
        a_output := a_output || '' IF v_'' || referrer_keys.kind ||
 '' LIKE ''''''''''
                || referrer_keys.key_string || '''''''''' THEN
 RETURN ''''''
                || referrer_keys.referrer_type || ''''''; END
 IF;'';
    END LOOP;

    a_output := a_output || '' RETURN NULL; END; '''' LANGUAGE
 ''''plpgsql'''';'';

    -- This works because we are not substituting any variables
    -- Otherwise it would fail. Look at PERFORM for another way to
 run functions

    EXECUTE a_output;
END;
' LANGUAGE 'plpgsql';
```

Example 19.7. A Procedure with a lot of String Manipulation and OUT Parameters

The following Oracle PL/SQL procedure is used to parse a URL and return several elements (host, path and query). It is an procedure because in PL/pgSQL functions only one value can be returned (see Section 19.11.3, “ Procedures ”). In PostgreSQL, one way to work around this is to split the procedure in three different functions: one to return the host, another for the path and another for the query.

```
CREATE OR REPLACE PROCEDURE cs_parse_url(
    v_url IN VARCHAR,
    v_host OUT VARCHAR,  -- This will be passed back
    v_path OUT VARCHAR,  -- This one too
    v_query OUT VARCHAR) -- And this one
is
    a_pos1 INTEGER;
    a_pos2 INTEGER;
begin
    v_host := NULL;
    v_path := NULL;
    v_query := NULL;
    a_pos1 := instr(v_url, '//'); -- PostgreSQL doesn't have an
 instr function

    IF a_pos1 = 0 THEN
        RETURN;
```

```
    END IF;
    a_pos2 := instr(v_url, '/', a_pos1 + 2);
    IF a_pos2 = 0 THEN
        v_host := substr(v_url, a_pos1 + 2);
        v_path := '/';
        RETURN;
    END IF;

    v_host := substr(v_url, a_pos1 + 2, a_pos2 - a_pos1 - 2);
    a_pos1 := instr(v_url, '?', a_pos2 + 1);

    IF a_pos1 = 0 THEN
        v_path := substr(v_url, a_pos2);
        RETURN;
    END IF;

    v_path := substr(v_url, a_pos2, a_pos1 - a_pos2);
    v_query := substr(v_url, a_pos1 + 1);
END;
/
show errors;
```

Here is how this procedure could be translated for PostgreSQL:

```
CREATE OR REPLACE FUNCTION cs_parse_url_host(VARCHAR) RETURNS
 VARCHAR AS '
DECLARE
    v_url ALIAS FOR $1;
    v_host VARCHAR;
    v_path VARCHAR;
    a_pos1 INTEGER;
    a_pos2 INTEGER;
    a_pos3 INTEGER;
BEGIN
    v_host := NULL;
    a_pos1 := instr(v_url,''//'');

    IF a_pos1 = 0 THEN
        RETURN '''';  -- Return a blank
    END IF;

    a_pos2 := instr(v_url,''/'',a_pos1 + 2);
    IF a_pos2 = 0 THEN
        v_host := substr(v_url, a_pos1 + 2);
        v_path := ''/'';
        RETURN v_host;
    END IF;

    v_host := substr(v_url, a_pos1 + 2, a_pos2 - a_pos1 - 2 );
    RETURN v_host;
END;
' LANGUAGE 'plpgsql';
```

Note

PostgreSQL does not have an `instr` function, so you can work around it using a combination of other functions. I got tired of doing this and created my own `instr` functions that behave exactly like Oracle's (it makes life easier). See the Section 19.11.6, “ Appendix ” for the code.

19.11.3. Procedures

Oracle procedures give a little more flexibility to the developer because nothing needs to be explicitly returned, but it can be through the use of `INOUT` or `OUT` parameters.

An example:

```
CREATE OR REPLACE PROCEDURE cs_create_job(v_job_id IN INTEGER) IS
    a_running_job_count INTEGER;
    PRAGMA AUTONOMOUS_TRANSACTION;1
BEGIN
    LOCK TABLE cs_jobs IN EXCLUSIVE MODE;2

    SELECT count(*) INTO a_running_job_count
    FROM cs_jobs
    WHERE end_stamp IS NULL;

    IF a_running_job_count > 0 THEN
        COMMIT; -- free lock3
        raise_application_error(-20000, 'Unable to create a new
 job: a job is currently running.');
    END IF;

    DELETE FROM cs_active_job;
    INSERT INTO cs_active_job(job_id) VALUES (v_job_id);

    BEGIN
        INSERT INTO cs_jobs (job_id, start_stamp) VALUES (v_job_id,
 sysdate);
        EXCEPTION WHEN dup_val_on_index THEN NULL; -- don't worry
 if it already exists4
    END;
    COMMIT;
END;
/
show errors
```

Procedures like this can be easily converted into PostgreSQL functions returning an `INTEGER`. This procedure in particular is interesting because it can teach us some things:

1. There is no `pragma` statement in PostgreSQL.
2. If you do a `LOCK TABLE` in PL/pgSQL, the lock will not be released until the calling transaction is finished.
3. You also cannot have transactions in PL/pgSQL procedures. The entire function (and other functions called from therein) is executed in a transaction and PostgreSQL rolls back the results if something goes wrong. Therefore only one `BEGIN` statement is allowed.
4. The exception when would have to be replaced by an `IF` statement.

So let's see one of the ways we could port this procedure to PL/pgSQL:

```
CREATE OR REPLACE FUNCTION cs_create_job(INTEGER) RETURNS INTEGER
 AS '
DECLARE
    v_job_id ALIAS FOR $1;
    a_running_job_count INTEGER;
    a_num INTEGER;
    -- PRAGMA AUTONOMOUS_TRANSACTION;
BEGIN
```

```
    LOCK TABLE cs_jobs IN EXCLUSIVE MODE;
    SELECT count(*) INTO a_running_job_count
    FROM cs_jobs
    WHERE end_stamp IS NULL;

    IF a_running_job_count > 0
    THEN
        -- COMMIT; -- free lock
        RAISE EXCEPTION ''Unable to create a new job: a job is
 currently running.'';
    END IF;

    DELETE FROM cs_active_job;
    INSERT INTO cs_active_job(job_id) VALUES (v_job_id);

    SELECT count(*) into a_num
    FROM cs_jobs
    WHERE job_id=v_job_id;
    IF NOT FOUND THEN  -- If nothing was returned in the last query
        -- This job is not in the table so lets insert it.
        INSERT INTO cs_jobs(job_id, start_stamp) VALUES (v_job_id,
 sysdate());
        RETURN 1;
    ELSE
        RAISE NOTICE ''Job already running.'';1
    END IF;

    RETURN 0;
END;
' LANGUAGE 'plpgsql';
```

1 Notice how you can raise notices (or errors) in PL/pgSQL.

19.11.4. Packages

Note

I haven't done much with packages myself, so if there are mistakes here, please let me know.

Packages are a way Oracle gives you to encapsulate PL/SQL statements and functions into one entity, like Java classes, where you define methods and objects. You can access these objects/methods with a "." (dot). Here is an example of an Oracle package from ACS 4 (the ArsDigita Community System[4]):

```
CREATE OR REPLACE PACKAGE BODY acs
AS
  FUNCTION add_user (
    user_id     IN users.user_id%TYPE DEFAULT NULL,
    object_type     IN acs_objects.object_type%TYPE DEFAULT 'user',
    creation_date   IN acs_objects.creation_date%TYPE DEFAULT
 sysdate,
    creation_user   IN acs_objects.creation_user%TYPE DEFAULT NULL,
    creation_ip     IN acs_objects.creation_ip%TYPE DEFAULT NULL,
  ...
  ) RETURN users.user_id%TYPE
  IS
    v_user_id       users.user_id%TYPE;
```

[4] http://www.arsdigita.com/doc/

```
    v_rel_id        membership_rels.rel_id%TYPE;
  BEGIN
    v_user_id := acs_user.new (user_id, object_type, creation_date,
                 creation_user, creation_ip, email, ...
    RETURN v_user_id;
  END;
END acs;
/
show errors
```

We port this to PostgreSQL by creating the different objects of the Oracle package as functions with a standard naming convention. We have to pay attention to some other details, like the lack of default parameters in PostgreSQL functions. The above package would become something like this:

```
CREATE FUNCTION
 acs__add_user(INTEGER,INTEGER,VARCHAR,TIMESTAMP,INTEGER,INTEGER,...)
RETURNS INTEGER AS '
DECLARE
    user_id ALIAS FOR $1;
    object_type ALIAS FOR $2;
    creation_date ALIAS FOR $3;
    creation_user ALIAS FOR $4;
    creation_ip ALIAS FOR $5;
    ...
    v_user_id users.user_id%TYPE;
    v_rel_id membership_rels.rel_id%TYPE;
BEGIN
    v_user_id :=
 acs_user__new(user_id,object_type,creation_date,creation_user,creation_ip, ...
    ...

    RETURN v_user_id;
END;
' LANGUAGE 'plpgsql';
```

19.11.5. Other Things to Watch For

19.11.5.1. EXECUTE

The PostgreSQL version of `EXECUTE` works nicely, but you have to remember to use `quote_literal(TEXT)` and `quote_string(TEXT)` as described in Section 19.5.4, “Executing dynamic queries”. Constructs of the type `EXECUTE ''SELECT * from $1'';` will not work unless you use these functions.

19.11.5.2. Optimizing PL/pgSQL Functions

PostgreSQL gives you two function creation modifiers to optimize execution: `iscachable` (function always returns the same result when given the same arguments) and `isstrict` (function returns NULL if any argument is NULL). Consult the `CREATE FUNCTION` reference for details.

To make use of these optimization attributes, you have to use the `WITH` modifier in your `CREATE FUNCTION` statement. Something like:

```
CREATE FUNCTION foo(...) RETURNS INTEGER AS '
...
' LANGUAGE 'plpgsql'
WITH (isstrict, iscachable);
```

19.11.6. Appendix

19.11.6.1. Code for my `instr` functions

```
--
-- instr functions that mimic Oracle's counterpart
-- Syntax: instr(string1,string2,[n],[m]) where [] denotes optional
 params.
--
-- Searches string1 beginning at the nth character for the mth
-- occurrence of string2. If n is negative, search backwards. If m
 is
-- not passed, assume 1 (search starts at first character).
--
-- by Roberto Mello (rmello@fslc.usu.edu)
-- modified by Robert Gaszewski (graszew@poland.com)
-- Licensed under the GPL v2 or later.
--

CREATE FUNCTION instr(VARCHAR,VARCHAR) RETURNS INTEGER AS '
DECLARE
    pos integer;
BEGIN
    pos:= instr($1,$2,1);
    RETURN pos;
END;
' LANGUAGE 'plpgsql';


CREATE FUNCTION instr(VARCHAR,VARCHAR,INTEGER) RETURNS INTEGER AS '
DECLARE
    string ALIAS FOR $1;
    string_to_search ALIAS FOR $2;
    beg_index ALIAS FOR $3;
    pos integer NOT NULL DEFAULT 0;
    temp_str VARCHAR;
    beg INTEGER;
    length INTEGER;
    ss_length INTEGER;
BEGIN
    IF beg_index > 0 THEN

       temp_str := substring(string FROM beg_index);
       pos := position(string_to_search IN temp_str);

       IF pos = 0 THEN
          RETURN 0;
      ELSE
          RETURN pos + beg_index - 1;
      END IF;
    ELSE
       ss_length := char_length(string_to_search);
       length := char_length(string);
       beg := length + beg_index - ss_length + 2;

       WHILE beg > 0 LOOP
           temp_str := substring(string FROM beg FOR ss_length);
```

```
          pos := position(string_to_search IN temp_str);

          IF pos > 0 THEN
             RETURN beg;
          END IF;

          beg := beg - 1;
       END LOOP;
       RETURN 0;
    END IF;
END;
' LANGUAGE 'plpgsql';

--
-- Written by Robert Gaszewski (graszew@poland.com)
-- Licensed under the GPL v2 or later.
--
CREATE FUNCTION instr(VARCHAR,VARCHAR,INTEGER,INTEGER) RETURNS
 INTEGER AS '
DECLARE
    string ALIAS FOR $1;
    string_to_search ALIAS FOR $2;
    beg_index ALIAS FOR $3;
    occur_index ALIAS FOR $4;
    pos integer NOT NULL DEFAULT 0;
    occur_number INTEGER NOT NULL DEFAULT 0;
    temp_str VARCHAR;
    beg INTEGER;
    i INTEGER;
    length INTEGER;
    ss_length INTEGER;
BEGIN
    IF beg_index > 0 THEN
        beg := beg_index;
        temp_str := substring(string FROM beg_index);

        FOR i IN 1..occur_index LOOP
            pos := position(string_to_search IN temp_str);

            IF i = 1 THEN
                beg := beg + pos - 1;
            ELSE
                beg := beg + pos;
            END IF;

            temp_str := substring(string FROM beg + 1);
        END LOOP;

        IF pos = 0 THEN
            RETURN 0;
        ELSE
            RETURN beg;
        END IF;
    ELSE
        ss_length := char_length(string_to_search);
        length := char_length(string);
        beg := length + beg_index - ss_length + 2;
```

```
        WHILE beg > 0 LOOP
            temp_str := substring(string FROM beg FOR ss_length);
            pos := position(string_to_search IN temp_str);

            IF pos > 0 THEN
                occur_number := occur_number + 1;

                IF occur_number = occur_index THEN
                    RETURN beg;
                END IF;
            END IF;

            beg := beg - 1;
        END LOOP;

        RETURN 0;
    END IF;
END;
' LANGUAGE 'plpgsql';
```

Chapter 20. PL/Tcl - Tcl Procedural Language

PL/Tcl is a loadable procedural language for the PostgreSQL database system that enables the Tcl language to be used to write functions and trigger procedures.

This package was originally written by Jan Wieck.

20.1. Overview

PL/Tcl offers most of the capabilities a function writer has in the C language, except for some restrictions.

The good restriction is that everything is executed in a safe Tcl interpreter. In addition to the limited command set of safe Tcl, only a few commands are available to access the database via SPI and to raise messages via `elog()`. There is no way to access internals of the database backend or to gain OS-level access under the permissions of the PostgreSQL user ID, as a C function can do. Thus, any unprivileged database user may be permitted to use this language.

The other, implementation restriction is that Tcl procedures cannot be used to create input/output functions for new data types.

Sometimes it is desirable to write Tcl functions that are not restricted to safe Tcl --- for example, one might want a Tcl function that sends mail. To handle these cases, there is a variant of PL/Tcl called `PL/TclU` (for untrusted Tcl). This is the exact same language except that a full Tcl interpreter is used. *If PL/TclU is used, it must be installed as an untrusted procedural language* so that only database superusers can create functions in it. The writer of a PL/TclU function must take care that the function cannot be used to do anything unwanted, since it will be able to do anything that could be done by a user logged in as the database administrator.

The shared object for the PL/Tcl and PL/TclU call handlers is automatically built and installed in the PostgreSQL library directory if Tcl/Tk support is specified in the configuration step of the installation procedure. To install PL/Tcl and/or PL/TclU in a particular database, use the `createlang` script, for example `createlang pltcl` *`dbname`* or `createlang pltclu` *`dbname`*.

20.2. Description

20.2.1. PL/Tcl Functions and Arguments

To create a function in the PL/Tcl language, use the standard syntax

```
CREATE FUNCTION funcname (argument-types) RETURNS return-type AS '
    # PL/Tcl function body
' LANGUAGE 'pltcl';
```

PL/TclU is the same, except that the language should be specified as `pltclu`.

The body of the function is simply a piece of Tcl script. When the function is called, the argument values are passed as variables `$1` ... `$n` to the Tcl script. The result is returned from the Tcl code in the usual way, with a `return` statement. For example, a function returning the greater of two integer values could be defined as:

```
CREATE FUNCTION tcl_max (integer, integer) RETURNS integer AS '
    if {$1 > $2} {return $1}
    return $2
```

```
' LANGUAGE 'pltcl' WITH (isStrict);
```

Note the clause `WITH (isStrict)`, which saves us from having to think about NULL input values: if a NULL is passed, the function will not be called at all, but will just return a NULL result automatically.

In a non-strict function, if the actual value of an argument is NULL, the corresponding `$n` variable will be set to an empty string. To detect whether a particular argument is NULL, use the function `argisnull`. For example, suppose that we wanted `tcl_max` with one null and one non-null argument to return the non-null argument, rather than NULL:

```
CREATE FUNCTION tcl_max (integer, integer) RETURNS integer AS '
    if {[argisnull 1]} {
        if {[argisnull 2]} { return_null }
        return $2
    }
    if {[argisnull 2]} { return $1 }
    if {$1 > $2} {return $1}
    return $2
' LANGUAGE 'pltcl';
```

As shown above, to return a NULL value from a PL/Tcl function, execute `return_null`. This can be done whether the function is strict or not.

Composite-type arguments are passed to the procedure as Tcl arrays. The element names of the array are the attribute names of the composite type. If an attribute in the passed row has the NULL value, it will not appear in the array! Here is an example that defines the overpaid_2 function (as found in the older PostgreSQL documentation) in PL/Tcl:

```
CREATE FUNCTION overpaid_2 (EMP) RETURNS bool AS '
    if {200000.0 < $1(salary)} {
        return "t"
    }
    if {$1(age) < 30 && 100000.0 < $1(salary)} {
        return "t"
    }
    return "f"
' LANGUAGE 'pltcl';
```

There is not currently any support for returning a composite-type result value.

20.2.2. Data Values in PL/Tcl

The argument values supplied to a PL/Tcl function's script are simply the input arguments converted to text form (just as if they had been displayed by a SELECT statement). Conversely, the `return` command will accept any string that is acceptable input format for the function's declared return type. So, the PL/Tcl programmer can manipulate data values as if they were just text.

20.2.3. Global Data in PL/Tcl

Sometimes it is useful to have some global status data that is held between two calls to a procedure or is shared between different procedures. This is easily done since all PL/Tcl procedures executed in one backend share the same safe Tcl interpreter. So, any global Tcl variable is accessible to all PL/Tcl procedure calls, and will persist for the duration of the SQL client connection. (Note that PL/TclU functions likewise share global data, but they are in a different Tcl interpreter and cannot communicate with PL/Tcl functions.)

To help protect PL/Tcl procedures from unintentionally interfering with each other, a global array is made available to each procedure via the `upvar` command. The global name of this variable is the procedure's internal name and the local name is `GD`. It is recommended that `GD` be used for private status data of a procedure. Use regular Tcl global variables only for values that you specifically intend to be shared among multiple procedures.

An example of using `GD` appears in the `spi_execp` example below.

20.2.4. Database Access from PL/Tcl

The following commands are available to access the database from the body of a PL/Tcl procedure:

`spi_exec ?-count` *`n`*`? ?-array` *`name`*`? `*`query`*` ?`*`loop-body`*`?`

Execute an SQL query given as a string. An error in the query causes an error to be raised. Otherwise, the command's return value is the number of rows processed (selected, inserted, updated, or deleted) by the query, or zero if the query is a utility statement. In addition, if the query is a SELECT statement, the values of the selected columns are placed in Tcl variables as described below.

The optional `-count` value tells `spi_exec` the maximum number of rows to process in the query. The effect of this is comparable to setting up the query as a cursor and then saying `FETCH n`.

If the query is a `SELECT` statement, the values of the statement's result columns are placed into Tcl variables named after the columns. If the `-array` option is given, the column values are instead stored into the named associative array, with the SELECT column names used as array indexes.

If the query is a SELECT statement and no *`loop-body`* script is given, then only the first row of results are stored into Tcl variables; remaining rows, if any, are ignored. No store occurs if the SELECT returns no rows (this case can be detected by checking the result of `spi_exec`). For example,

```
spi_exec "SELECT count(*) AS cnt FROM pg_proc"
```

will set the Tcl variable `$cnt` to the number of rows in the `pg_proc` system catalog.

If the optional *`loop-body`* argument is given, it is a piece of Tcl script that is executed once for each row in the SELECT result (note: *`loop-body`* is ignored if the given query is not a SELECT). The values of the current row's fields are stored into Tcl variables before each iteration. For example,

```
spi_exec -array C "SELECT * FROM pg_class" {
    elog DEBUG "have table $C(relname)"
}
```

will print a DEBUG log message for every row of pg_class. This feature works similarly to other Tcl looping constructs; in particular `continue` and `break` work in the usual way inside the loop body.

If a field of a SELECT result is NULL, the target variable for it is “unset” rather than being set.

`spi_prepare` *`query typelist`*

Prepares and saves a query plan for later execution. The saved plan will be retained for the life of the current backend.

The query may use *arguments*, which are placeholders for values to be supplied whenever the plan is actually executed. In the query string, refer to arguments by the symbols `$1` ... `$n`. If the query

uses arguments, the names of the argument types must be given as a Tcl list. (Write an empty list for *typelist* if no arguments are used.) Presently, the argument types must be identified by the internal type names shown in pg_type; for example int4 not integer.

The return value from spi_prepare is a query ID to be used in subsequent calls to spi_execp. See spi_execp for an example.

spi_execp ?-count *n*? ?-array *name*? ?-nulls *string*? *queryid* ?*value-list*? ?*loop-body*?

Execute a query previously prepared with spi_prepare. *queryid* is the ID returned by spi_prepare. If the query references arguments, a *value-list* must be supplied: this is a Tcl list of actual values for the arguments. This must be the same length as the argument type list previously given to spi_prepare. Omit *value-list* if the query has no arguments.

The optional value for -nulls is a string of spaces and 'n' characters telling spi_execp which of the arguments are null values. If given, it must have exactly the same length as the *value-list*. If it is not given, all the argument values are non-NULL.

Except for the way in which the query and its arguments are specified, spi_execp works just like spi_exec. The -count, -array, and *loop-body* options are the same, and so is the result value.

Here's an example of a PL/Tcl function using a prepared plan:

```
CREATE FUNCTION t1_count(integer, integer) RETURNS integer AS '
    if {![ info exists GD(plan) ]} {
        # prepare the saved plan on the first call
        set GD(plan) [ spi_prepare \\
                "SELECT count(*) AS cnt FROM t1 WHERE num >= \\
$1 AND num <= \\$2" \\
                [ list int4 int4 ] ]
    }
    spi_execp -count 1 $GD(plan) [ list $1 $2 ]
    return $cnt
' LANGUAGE 'pltcl';
```

Note that each backslash that Tcl should see must be doubled when we type in the function, since the main parser processes backslashes too in CREATE FUNCTION. We need backslashes inside the query string given to spi_prepare to ensure that the $n markers will be passed through to spi_prepare as-is, and not replaced by Tcl variable substitution.

spi_lastoid

Returns the OID of the row inserted by the last spi_exec'd or spi_execp'd query, if that query was a single-row INSERT. (If not, you get zero.)

quote *string*

Duplicates all occurrences of single quote and backslash characters in the given string. This may be used to safely quote strings that are to be inserted into SQL queries given to spi_exec or spi_prepare. For example, think about a query string like

```
"SELECT '$val' AS ret"
```

where the Tcl variable val actually contains doesn't. This would result in the final query string

```
SELECT 'doesn't' AS ret
```

which would cause a parse error during spi_exec or spi_prepare. The submitted query should contain

```
SELECT 'doesn''t' AS ret
```

which can be formed in PL/Tcl as

```
"SELECT '[ quote $val ]' AS ret"
```

One advantage of `spi_execp` is that you don't have to quote argument values like this, since the arguments are never parsed as part of an SQL query string.

`elog` *`level msg`*

Emit a log or error message. Possible levels are `DEBUG`, `LOG`, `INFO`, `NOTICE`, `WARNING`, `ERROR`, and `FATAL`. Most simply emit the given message just like the `elog` backend C function. `ERROR` raises an error condition: further execution of the function is abandoned, and the current transaction is aborted. `FATAL` aborts the transaction and causes the current backend to shut down (there is probably no good reason to use this error level in PL/Tcl functions, but it's provided for completeness).

20.2.5. Trigger Procedures in PL/Tcl

Trigger procedures can be written in PL/Tcl. As is customary in PostgreSQL, a procedure that's to be called as a trigger must be declared as a function with no arguments and a return type of `trigger`.

The information from the trigger manager is passed to the procedure body in the following variables:

`$TG_name`

The name of the trigger from the CREATE TRIGGER statement.

`$TG_relid`

The object ID of the table that caused the trigger procedure to be invoked.

`$TG_relatts`

A Tcl list of the table field names, prefixed with an empty list element. So looking up an element name in the list with Tcl's `lsearch` command returns the element's number starting with 1 for the first column, the same way the fields are customarily numbered in PostgreSQL.

`$TG_when`

The string `BEFORE` or `AFTER` depending on the type of trigger call.

`$TG_level`

The string `ROW` or `STATEMENT` depending on the type of trigger call.

`$TG_op`

The string `INSERT`, `UPDATE` or `DELETE` depending on the type of trigger call.

`$NEW`

An associative array containing the values of the new table row for INSERT/UPDATE actions, or empty for DELETE. The array is indexed by field name. Fields that are NULL will not appear in the array!

`$OLD`

An associative array containing the values of the old table row for UPDATE/DELETE actions, or empty for INSERT. The array is indexed by field name. Fields that are NULL will not appear in the array!

$args

A Tcl list of the arguments to the procedure as given in the CREATE TRIGGER statement. These arguments are also accessible as $1 ... $n in the procedure body.

The return value from a trigger procedure can be one of the strings OK or SKIP, or a list as returned by the array get Tcl command. If the return value is OK, the operation (INSERT/UPDATE/DELETE) that fired the trigger will proceed normally. SKIP tells the trigger manager to silently suppress the operation for this row. If a list is returned, it tells PL/Tcl to return a modified row to the trigger manager that will be inserted instead of the one given in $NEW (this works for INSERT/UPDATE only). Needless to say that all this is only meaningful when the trigger is BEFORE and FOR EACH ROW; otherwise the return value is ignored.

Here's a little example trigger procedure that forces an integer value in a table to keep track of the number of updates that are performed on the row. For new rows inserted, the value is initialized to 0 and then incremented on every update operation:

```
CREATE FUNCTION trigfunc_modcount() RETURNS TRIGGER AS '
    switch $TG_op {
        INSERT {
            set NEW($1) 0
        }
        UPDATE {
            set NEW($1) $OLD($1)
            incr NEW($1)
        }
        default {
            return OK
        }
    }
    return [array get NEW]
' LANGUAGE 'pltcl';

CREATE TABLE mytab (num integer, description text, modcnt integer);

CREATE TRIGGER trig_mytab_modcount BEFORE INSERT OR UPDATE ON mytab
    FOR EACH ROW EXECUTE PROCEDURE trigfunc_modcount('modcnt');
```

Notice that the trigger procedure itself does not know the column name; that's supplied from the trigger arguments. This lets the trigger procedure be re-used with different tables.

20.2.6. Modules and the unknown command

PL/Tcl has support for auto-loading Tcl code when used. It recognizes a special table, pltcl_modules, which is presumed to contain modules of Tcl code. If this table exists, the module unknown is fetched from the table and loaded into the Tcl interpreter immediately after creating the interpreter.

While the unknown module could actually contain any initialization script you need, it normally defines a Tcl “unknown” procedure that is invoked whenever Tcl does not recognize an invoked procedure name. PL/Tcl's standard version of this procedure tries to find a module in pltcl_modules that will define the required procedure. If one is found, it is loaded into the interpreter, and then execution is allowed to proceed with the originally attempted procedure call. A secondary table pltcl_modfuncs provides an index of which functions are defined by which modules, so that the lookup is reasonably quick.

The PostgreSQL distribution includes support scripts to maintain these tables: pltcl_loadmod, pltcl_listmod, pltcl_delmod, as well as source for the standard unknown module share/

`unknown.pltcl`. This module must be loaded into each database initially to support the autoloading mechanism.

The tables `pltcl_modules` and `pltcl_modfuncs` must be readable by all, but it is wise to make them owned and writable only by the database administrator.

20.2.7. Tcl Procedure Names

In PostgreSQL, one and the same function name can be used for different functions as long as the number of arguments or their types differ. Tcl, however, requires all procedure names to be distinct. PL/Tcl deals with this by making the internal Tcl procedure names contain the object ID of the procedure's `pg_proc` row as part of their name. Thus, PostgreSQL functions with the same name and different argument types will be different Tcl procedures too. This is not normally a concern for a PL/Tcl programmer, but it might be visible when debugging.

Chapter 21. PL/Perl - Perl Procedural Language

PL/Perl is a loadable procedural language that enables you to write PostgreSQL functions in the Perl[1] programming language.

To install PL/Perl in a particular database, use `createlang plperl` *dbname*.

Tip

If a language is installed into `template1`, all subsequently created databases will have the language installed automatically.

Note

Users of source packages must specially enable the build of PL/Perl during the installation process (refer to the installation instructions for more information). Users of binary packages might find PL/Perl in a separate subpackage.

21.1. PL/Perl Functions and Arguments

To create a function in the PL/Perl language, use the standard syntax:

```
CREATE FUNCTION funcname (argument-types) RETURNS return-type AS '
    # PL/Perl function body
' LANGUAGE plperl;
```

The body of the function is ordinary Perl code.

Arguments and results are handled as in any other Perl subroutine: Arguments are passed in `@_`, and a result value is returned with `return` or as the last expression evaluated in the function. For example, a function returning the greater of two integer values could be defined as:

```
CREATE FUNCTION perl_max (integer, integer) RETURNS integer AS '
    if ($_[0] > $_[1]) { return $_[0]; }
    return $_[1];
' LANGUAGE plperl;
```

If an SQL null value is passed to a function, the argument value will appear as “undefined” in Perl. The above function definition will not behave very nicely with null inputs (in fact, it will act as though they are zeroes). We could add `STRICT` to the function definition to make PostgreSQL do something more reasonable: if a null value is passed, the function will not be called at all, but will just return a null result automatically. Alternatively, we could check for undefined inputs in the function body. For example, suppose that we wanted `perl_max` with one null and one non-null argument to return the non-null argument, rather than a null value:

```
CREATE FUNCTION perl_max (integer, integer) RETURNS integer AS '
    my ($a,$b) = @_;
    if (! defined $a) {
        if (! defined $b) { return undef; }
        return $b;
    }
    if (! defined $b) { return $a; }
    if ($a > $b) { return $a; }
    return $b;
```

[1] http://www.perl.com

```
' LANGUAGE plperl;
```

As shown above, to return an SQL null value from a PL/Perl function, return an undefined value. This can be done whether the function is strict or not.

Composite-type arguments are passed to the function as references to hashes. The keys of the hash are the attribute names of the composite type. Here is an example:

```
CREATE TABLE employee (
    name text,
    basesalary integer,
    bonus integer
);

CREATE FUNCTION empcomp(employee) RETURNS integer AS '
    my ($emp) = @_;
    return $emp->{''basesalary''} + $emp->{''bonus''};
' LANGUAGE plperl;

SELECT name, empcomp(employee) FROM employee;
```

There is currently no support for returning a composite-type result value.

Tip

Because the function body is passed as an SQL string literal to `CREATE FUNCTION`, you have to escape single quotes and backslashes within your Perl source, typically by doubling them as shown in the above example. Another possible approach is to avoid writing single quotes by using Perl's extended quoting operators (`q[]`, `qq[]`, `qw[]`).

21.2. Data Values in PL/Perl

The argument values supplied to a PL/Perl function's script are simply the input arguments converted to text form (just as if they had been displayed by a `SELECT` statement). Conversely, the `return` command will accept any string that is acceptable input format for the function's declared return type. So, the PL/Perl programmer can manipulate data values as if they were just text.

21.3. Database Access from PL/Perl

Access to the database itself from your Perl function can be done via an experimental module `DBD::PgSPI`[2] (also available at CPAN mirror sites[3]). This module makes available a DBI-compliant database-handle named `$pg_dbh` that can be used to perform queries with normal DBI syntax.

PL/Perl itself presently provides only one additional Perl command:

`elog` *`level`*, *`msg`*

Emit a log or error message. Possible levels are `DEBUG`, `LOG`, `INFO`, `NOTICE`, `WARNING`, and `ERROR`. `ERROR` raises an error condition: further execution of the function is abandoned, and the current transaction is aborted.

21.4. Trusted and Untrusted PL/Perl

Normally, PL/Perl is installed as a “trusted” programming language named `plperl`. In this setup, certain Perl operations are disabled to preserve security. In general, the operations that are restricted

[2] http://www.cpan.org/modules/by-module/DBD/APILOS/
[3] http://www.cpan.org/SITES.html

are those that interact with the environment. This includes file handle operations, `require`, and `use` (for external modules). There is no way to access internals of the database backend process or to gain OS-level access with the permissions of the PostgreSQL user ID, as a C function can do. Thus, any unprivileged database user may be permitted to use this language.

Here is an example of a function that will not work because file system operations are not allowed for security reasons:

```
CREATE FUNCTION badfunc() RETURNS integer AS '
    open(TEMP, ">/tmp/badfile");
    print TEMP "Gotcha!\n";
    return 1;
' LANGUAGE plperl;
```

The creation of the function will succeed, but executing it will not.

Sometimes it is desirable to write Perl functions that are not restricted --- for example, one might want a Perl function that sends mail. To handle these cases, PL/Perl can also be installed as an “untrusted” language (usually called PL/PerlU). In this case the full Perl language is available. If the `createlang` program is used to install the language, the language name `plperlu` will select the untrusted PL/Perl variant.

The writer of a PL/PerlU function must take care that the function cannot be used to do anything unwanted, since it will be able to do anything that could be done by a user logged in as the database administrator. Note that the database system allows only database superusers to create functions in untrusted languages.

If the above function was created by a superuser using the language `plperlu`, execution would succeed.

21.5. Missing Features

The following features are currently missing from PL/Perl, but they would make welcome contributions:

- PL/Perl functions cannot call each other directly (because they are anonymous subroutines inside Perl). There's presently no way for them to share global variables, either.
- PL/Perl cannot be used to write trigger functions.
- DBD::PgSPI or similar capability should be integrated into the standard PostgreSQL distribution.

Chapter 22. PL/Python - Python Procedural Language

The PL/Python procedural language allows PostgreSQL functions to be written in the Python[1] language.

To install PL/Python in a particular database, use `createlang plpython` *dbname*.

Note

Users of source packages must specially enable the build of PL/Python during the installation process (refer to the installation instructions for more information). Users of binary packages might find PL/Python in a separate subpackage.

22.1. PL/Python Functions

The Python code you write gets transformed into a function. E.g.,

```
CREATE FUNCTION myfunc(text) RETURNS text
    AS 'return args[0]'
    LANGUAGE 'plpython';
```

gets transformed into

```
def __plpython_procedure_myfunc_23456():
        return args[0]
```

where 23456 is the OID of the function.

If you do not provide a return value, Python returns the default `None` which may or may not be what you want. The language module translates Python's `None` into the SQL null value.

The PostgreSQL function parameters are available in the global `args` list. In the `myfunc` example, `args[0]` contains whatever was passed in as the text argument. For `myfunc2(text, integer)`, `args[0]` would contain the `text` variable and `args[1]` the `integer` variable.

The global dictionary `SD` is available to store data between function calls. This variable is private static data. The global dictionary `GD` is public data, available to all Python functions within a session. Use with care.

Each function gets its own restricted execution object in the Python interpreter, so that global data and function arguments from `myfunc` are not available to `myfunc2`. The exception is the data in the `GD` dictionary, as mentioned above.

22.2. Trigger Functions

When a function is used in a trigger, the dictionary `TD` contains trigger-related values. The trigger rows are in `TD["new"]` and/or `TD["old"]` depending on the trigger event. `TD["event"]` contains the event as a string (`INSERT`, `UPDATE`, `DELETE`, or `UNKNOWN`). `TD["when"]` contains one of `BEFORE`, `AFTER`, and `UNKNOWN`. `TD["level"]` contains one of `ROW`, `STATEMENT`, and `UNKNOWN`. `TD["name"]` contains the trigger name, and `TD["relid"]` contains the relation ID of the table on which the trigger occurred. If the trigger was called with arguments they are available in `TD["args"][0]` to `TD["args"][(n-1)]`.

[1] http://www.python.org

If the TD["when"] is BEFORE, you may return None or "OK" from the Python function to indicate the row is unmodified, "SKIP" to abort the event, or "MODIFY" to indicate you've modified the row.

22.3. Database Access

The PL/Python language module automatically imports a Python module called plpy. The functions and constants in this module are available to you in the Python code as plpy.*foo*. At present plpy implements the functions plpy.debug("msg"), plpy.log("msg"), plpy.info("msg"), plpy.notice("msg"), plpy.warning("msg"), plpy.error("msg"), and plpy.fatal("msg"). They are mostly equivalent to calling elog(*LEVEL*, "msg") from C code. plpy.error and plpy.fatal actually raise a Python exception which, if uncaught, causes the PL/Python module to call elog(ERROR, msg) when the function handler returns from the Python interpreter. Long-jumping out of the Python interpreter is probably not good. raise plpy.ERROR("msg") and raise plpy.FATAL("msg") are equivalent to calling plpy.error and plpy.fatal, respectively.

Additionally, the plpy module provides two functions called execute and prepare. Calling plpy.execute with a query string and an optional limit argument causes that query to be run and the result to be returned in a result object. The result object emulates a list or dictionary object. The result object can be accessed by row number and field name. It has these additional methods: nrows() which returns the number of rows returned by the query, and status which is the SPI_exec return variable. The result object can be modified.

For example,

```
rv = plpy.execute("SELECT * FROM my_table", 5)
```

returns up to 5 rows from my_table. If my_table has a column my_field, it would be accessed as

```
foo = rv[i]["my_field"]
```

The second function plpy.prepare is called with a query string and a list of argument types if you have bind variables in the query. For example:

```
plan = plpy.prepare("SELECT last_name FROM my_users WHERE
 first_name = $1", [ "text" ])
```

text is the type of the variable you will be passing as $1. After preparing a statement, you use the function plpy.execute to run it:

```
rv = plpy.execute(plan, [ "name" ], 5)
```

The limit argument is optional in the call to plpy.execute.

In the current version, any database error encountered while running a PL/Python function will result in the immediate termination of that function by the server; it is not possible to trap error conditions using Python try ... catch constructs. For example, a syntax error in an SQL statement passed to the plpy.execute() call will terminate the function. This behavior may be changed in a future release.

When you prepare a plan using the PL/Python module it is automatically saved. Read the SPI documentation (Chapter 17, *Server Programming Interface*) for a description of what this means.

In order to make effective use of this across function calls one needs to use one of the persistent storage dictionaries SD or GD, see Section 22.1, “PL/Python Functions”. For example:

```
CREATE FUNCTION usesavedplan ( ) RETURNS TRIGGER AS '
   if SD.has_key("plan"):
      plan = SD["plan"]
```

```
   else:
      plan = plpy.prepare("SELECT 1")
      SD["plan"] = plan
   # rest of function
' LANGUAGE 'plpython';
```

22.4. Restricted Environment

The current version of PL/Python functions as a trusted language only; access to the file system and other local resources is disabled. Specifically, PL/Python uses the Python restricted execution environment, further restricts it to prevent the use of the file `open` call, and allows only modules from a specific list to be imported. Presently, that list includes: `array`, `bisect`, `binascii`, `calendar`, `cmath`, `codecs`, `errno`, `marshal`, `math`, `md5`, `mpz`, `operator`, `pcre`, `pickle`, `random`, `re`, `regex`, `sre`, `sha`, `string`, `StringIO`, `struct`, `time`, `whrandom`, and `zlib`.

PostgreSQL 7.3.21 Reference Manual

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 Reference Manual

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

Preface cccxxxiii
I. SQL Commands 334
ABORT 336
ALTER DATABASE 337
ALTER GROUP 339
ALTER TABLE 340
ALTER TRIGGER 345
ALTER USER 346
ANALYZE 348
BEGIN 350
CHECKPOINT 352
CLOSE 353
CLUSTER 354
COMMENT 356
COMMIT 358
COPY 359
CREATE AGGREGATE 365
CREATE CAST 368
CREATE CONSTRAINT TRIGGER 371
CREATE CONVERSION 372
CREATE DATABASE 374
CREATE DOMAIN 377
CREATE FUNCTION 379
CREATE GROUP 384
CREATE INDEX 385
CREATE LANGUAGE 389
CREATE OPERATOR 392
CREATE OPERATOR CLASS 397
CREATE RULE 400
CREATE SCHEMA 403
CREATE SEQUENCE 405
CREATE TABLE 408
CREATE TABLE AS 416
CREATE TRIGGER 418
CREATE TYPE 421
CREATE USER 425
CREATE VIEW 428
DEALLOCATE 431
DECLARE 432
DELETE 435
DROP AGGREGATE 437
DROP CAST 438
DROP CONVERSION 439
DROP DATABASE 440
DROP DOMAIN 441
DROP FUNCTION 442
DROP GROUP 444
DROP INDEX 445
DROP LANGUAGE 446
DROP OPERATOR 447
DROP OPERATOR CLASS 449
DROP RULE 450
DROP SCHEMA 451
DROP SEQUENCE 452
DROP TABLE 453

DROP TRIGGER ... 454
DROP TYPE ... 456
DROP USER ... 457
DROP VIEW ... 458
END ... 459
EXECUTE ... 460
EXPLAIN ... 461
FETCH ... 463
GRANT ... 466
INSERT ... 470
LISTEN ... 472
LOAD ... 474
LOCK ... 475
MOVE ... 479
NOTIFY ... 480
PREPARE ... 482
REINDEX ... 484
RESET ... 486
REVOKE ... 487
ROLLBACK ... 489
SELECT ... 490
SELECT INTO ... 502
SET ... 503
SET CONSTRAINTS ... 507
SET SESSION AUTHORIZATION ... 508
SET TRANSACTION ... 510
SHOW ... 511
START TRANSACTION ... 513
TRUNCATE ... 514
UNLISTEN ... 515
UPDATE ... 517
VACUUM ... 519
II. PostgreSQL Client Applications ... 522
clusterdb ... 523
createdb ... 525
createlang ... 528
createuser ... 530
dropdb ... 533
droplang ... 535
dropuser ... 537
ecpg ... 539
pg_config ... 541
pg_dump ... 543
pg_dumpall ... 549
pg_restore ... 552
psql ... 558
pgtclsh ... 579
pgtksh ... 580
vacuumdb ... 581
III. PostgreSQL Server Applications ... 584
initdb ... 585
initlocation ... 587
ipcclean ... 588
pg_ctl ... 589
pg_controldata ... 592
pg_resetxlog ... 593
postgres ... 594
postmaster ... 597

Preface

The entries in this *Reference Manual* are meant to provide in reasonable length an authoritative, complete, and formal summary about their respective subjects. More information about the use of PostgreSQL, in narrative, tutorial, or example form, may be found in other parts of the PostgreSQL documentation set. See the cross-references listed on each reference page.

The *Reference Manual* entries are also available as traditional “man” pages.

SQL Commands

This part contains reference information for the SQL commands supported by PostgreSQL. By “SQL” the language in general is meant; information about the standards conformance and compatibility of each command can be found on the respective reference page.

Table of Contents

ABORT 336
ALTER DATABASE 337
ALTER GROUP 339
ALTER TABLE 340
ALTER TRIGGER 345
ALTER USER 346
ANALYZE 348
BEGIN 350
CHECKPOINT 352
CLOSE 353
CLUSTER 354
COMMENT 356
COMMIT 358
COPY 359
CREATE AGGREGATE 365
CREATE CAST 368
CREATE CONSTRAINT TRIGGER 371
CREATE CONVERSION 372
CREATE DATABASE 374
CREATE DOMAIN 377
CREATE FUNCTION 379
CREATE GROUP 384
CREATE INDEX 385
CREATE LANGUAGE 389
CREATE OPERATOR 392
CREATE OPERATOR CLASS 397
CREATE RULE 400
CREATE SCHEMA 403
CREATE SEQUENCE 405
CREATE TABLE 408
CREATE TABLE AS 416
CREATE TRIGGER 418
CREATE TYPE 421
CREATE USER 425
CREATE VIEW 428
DEALLOCATE 431
DECLARE 432
DELETE 435
DROP AGGREGATE 437
DROP CAST 438
DROP CONVERSION 439
DROP DATABASE 440
DROP DOMAIN 441
DROP FUNCTION 442
DROP GROUP 444
DROP INDEX 445
DROP LANGUAGE 446

DROP OPERATOR 447
DROP OPERATOR CLASS 449
DROP RULE 450
DROP SCHEMA 451
DROP SEQUENCE 452
DROP TABLE 453
DROP TRIGGER 454
DROP TYPE 456
DROP USER 457
DROP VIEW 458
END 459
EXECUTE 460
EXPLAIN 461
FETCH 463
GRANT 466
INSERT 470
LISTEN 472
LOAD 474
LOCK 475
MOVE 479
NOTIFY 480
PREPARE 482
REINDEX 484
RESET 486
REVOKE 487
ROLLBACK 489
SELECT 490
SELECT INTO 502
SET 503
SET CONSTRAINTS 507
SET SESSION AUTHORIZATION 508
SET TRANSACTION 510
SHOW 511
START TRANSACTION 513
TRUNCATE 514
UNLISTEN 515
UPDATE 517
VACUUM 519

Name

ABORT — abort the current transaction

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
ABORT [ WORK | TRANSACTION ]
```

Inputs

None.

Outputs

`ROLLBACK`

Message returned if successful.

`WARNING: ROLLBACK: no transaction in progress`

If there is not any transaction currently in progress.

Description

`ABORT` rolls back the current transaction and causes all the updates made by the transaction to be discarded. This command is identical in behavior to the SQL92 command `ROLLBACK`, and is present only for historical reasons.

Notes

Use `COMMIT` to successfully terminate a transaction.

Usage

To abort all changes:

```
ABORT WORK;
```

Compatibility

SQL92

This command is a PostgreSQL extension present for historical reasons. `ROLLBACK` is the SQL92 equivalent command.

Name

ALTER DATABASE — change a database

Synopsis

```
ALTER DATABASE name SET variable { TO | = } { value | DEFAULT }
ALTER DATABASE name RESET variable
```

Description

`ALTER DATABASE` is used to change the session default of a run-time configuration variable for a PostgreSQL database. Whenever a new session is subsequently started in that database, the specified value becomes the session default value. The database-specific default overrides whatever setting is present in `postgresql.conf` or has been received from the postmaster.

Only a superuser or the database owner can change the session defaults for a database.

Parameters

name

The name of the database whose session defaults are to be altered.

variable
value

Set the session default for this database of the specified configuration variable to the given value. If *value* is `DEFAULT` or, equivalently, `RESET` is used, the database-specific variable setting is removed and the system-wide default setting will be inherited in new sessions. Use `RESET ALL` to clear all settings.

See SET and the *Administrator's Guide* for more information about allowed variable names and values.

Diagnostics

`ALTER DATABASE`

Message returned if the alteration was successful.

`ERROR: database "dbname" does not exist`

Error message returned if the specified database is not known to the system.

Notes

Using ALTER USER, it is also possible to tie a session default to a specific user rather than a database. User-specific settings override database-specific ones if there is a conflict.

Examples

To disable index scans by default in the database `test`:

```
ALTER DATABASE test SET enable_indexscan TO off;
```

Compatibility

The `ALTER DATABASE` statement is a PostgreSQL extension.

See Also

ALTER USER, CREATE DATABASE, DROP DATABASE, SET

Name

ALTER GROUP — add users to a group or remove users from a group

Synopsis

<refsynopsisdivinfo>2000-01-14</refsynopsisdivinfo>

```
ALTER GROUP name ADD USER username [, ... ]
ALTER GROUP name DROP USER username [, ... ]
```

Inputs

name

The name of the group to modify.

username

Users which are to be added or removed from the group. The user names must exist.

Outputs

`ALTER GROUP`

Message returned if the alteration was successful.

Description

`ALTER GROUP` is used to add or remove users from a group. Only database superusers can use this command. Adding a user to a group does not create the user. Similarly, removing a user from a group does not drop the user itself.

Use CREATE GROUP to create a new group and DROP GROUP to remove a group.

Usage

Add users to a group:

```
ALTER GROUP staff ADD USER karl, john;
```

Remove a user from a group:

```
ALTER GROUP workers DROP USER beth;
```

Compatibility

SQL92

There is no `ALTER GROUP` statement in SQL92. The concept of roles is similar.

Name

ALTER TABLE — change the definition of a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
ALTER TABLE [ ONLY ] table [ * ]
    ADD [ COLUMN ] column type [ column_constraint [ ... ] ]
ALTER TABLE [ ONLY ] table [ * ]
    DROP [ COLUMN ] column [ RESTRICT | CASCADE ]
ALTER TABLE [ ONLY ] table [ * ]
    ALTER [ COLUMN ] column { SET DEFAULT value | DROP DEFAULT }
ALTER TABLE [ ONLY ] table [ * ]
    ALTER [ COLUMN ] column { SET | DROP } NOT NULL
ALTER TABLE [ ONLY ] table [ * ]
    ALTER [ COLUMN ] column SET STATISTICS integer
ALTER TABLE [ ONLY ] table [ * ]
    ALTER [ COLUMN ] column SET STORAGE { PLAIN | EXTERNAL |
 EXTENDED | MAIN }
ALTER TABLE [ ONLY ] table [ * ]
    RENAME [ COLUMN ] column TO new_column
ALTER TABLE table
    RENAME TO new_table
ALTER TABLE [ ONLY ] table [ * ]
    ADD table_constraint
ALTER TABLE [ ONLY ] table [ * ]
    DROP CONSTRAINT constraint_name [ RESTRICT | CASCADE ]
ALTER TABLE table
    OWNER TO new_owner
```

Inputs

table

The name (possibly schema-qualified) of an existing table to alter. If ONLY is specified, only that table is altered. If ONLY is not specified, the table and all its descendant tables (if any) are updated. * can be appended to the table name to indicate that descendant tables are to be scanned, but in the current version, this is the default behavior. (In releases before 7.1, ONLY was the default behavior.) The default can be altered by changing the SQL_INHERITANCE configuration option.

column

Name of a new or existing column.

type

Type of the new column.

new_column

New name for an existing column.

new_table

New name for the table.

table_constraint

New table constraint for the table.

constraint_name

Name of an existing constraint to drop.

new_owner

The user name of the new owner of the table.

CASCADE

Automatically drop objects that depend on the dropped column or constraint (for example, views referencing the column).

RESTRICT

Refuse to drop the column or constraint if there are any dependent objects. This is the default behavior.

Outputs

`ALTER TABLE`

Message returned from column or table renaming.

`ERROR`

Message returned if table or column is not available.

Description

`ALTER TABLE` changes the definition of an existing table. There are several sub-forms:

ADD COLUMN

This form adds a new column to the table using the same syntax as CREATE TABLE.

DROP COLUMN

This form drops a column from a table. Note that indexes and table constraints involving the column will be automatically dropped as well. You will need to say `CASCADE` if anything outside the table depends on the column --- for example, foreign key references, views, etc.

SET/DROP DEFAULT

These forms set or remove the default value for a column. Note that defaults only apply to subsequent `INSERT` commands; they do not cause rows already in the table to change. Defaults may also be created for views, in which case they are inserted into `INSERT` statements on the view before the view's ON INSERT rule is applied.

SET/DROP NOT NULL

These forms change whether a column is marked to allow NULL values or to reject NULL values. You may only `SET NOT NULL` when the table contains no null values in the column.

SET STATISTICS

This form sets the per-column statistics-gathering target for subsequent ANALYZE operations. The target can be set in the range 0 to 1000; alternatively, set it to -1 to revert to using the system default statistics target.

SET STORAGE

This form sets the storage mode for a column. This controls whether this column is held inline or in a supplementary table, and whether the data should be compressed or not. `PLAIN` must be used for fixed-length values such as `INTEGER` and is inline, uncompressed. `MAIN` is for inline, compressible data. `EXTERNAL` is for external, uncompressed data and `EXTENDED` is for external, compressed data. `EXTENDED` is the default for all data types that support it. The use of `EXTERNAL` will make substring operations on a TEXT column faster, at the penalty of increased storage space.

RENAME

The `RENAME` forms change the name of a table (or an index, sequence, or view) or the name of an individual column in a table. There is no effect on the stored data.

ADD *`table_constraint`*

This form adds a new constraint to a table using the same syntax as CREATE TABLE.

DROP CONSTRAINT

This form drops constraints on a table. Currently, constraints on tables are not required to have unique names, so there may be more than one constraint matching the specified name. All such constraints will be dropped.

OWNER

This form changes the owner of the table, index, sequence or view to the specified user.

You must own the table to use `ALTER TABLE`; except for `ALTER TABLE OWNER`, which may only be executed by a superuser.

Notes

The keyword `COLUMN` is noise and can be omitted.

In the current implementation of `ADD COLUMN`, default and NOT NULL clauses for the new column are not supported. The new column always comes into being with all values NULL. You can use the `SET DEFAULT` form of `ALTER TABLE` to set the default afterwards. (You may also want to update the already existing rows to the new default value, using UPDATE.) If you want to mark the column non-null, use the `SET NOT NULL` form after you've entered non-null values for the column in all rows.

The `DROP COLUMN` command does not physically remove the column, but simply makes it invisible to SQL operations. Subsequent inserts and updates of the table will store a NULL for the column. Thus, dropping a column is quick but it will not immediately reduce the on-disk size of your table, as the space occupied by the dropped column is not reclaimed. The space will be reclaimed over time as existing rows are updated. To reclaim the space at once, do a dummy `UPDATE` of all rows and then vacuum, as in:

```
UPDATE table SET col = col;
VACUUM FULL table;
```

If a table has any descendant tables, it is not permitted to ADD or RENAME a column in the parent table without doing the same to the descendants --- that is, ALTER TABLE ONLY will be rejected. This ensures that the descendants always have columns matching the parent.

A recursive DROP COLUMN operation will remove a descendant table's column only if the descendant does not inherit that column from any other parents and never had an independent definition of the column. A nonrecursive DROP COLUMN (i.e., ALTER TABLE ONLY ... DROP COLUMN) never removes any descendant columns, but instead marks them as independently defined rather than inherited.

Changing any part of the schema of a system catalog is not permitted.

Refer to `CREATE TABLE` for a further description of valid arguments. The *PostgreSQL User's Guide* has further information on inheritance.

Usage

To add a column of type `varchar` to a table:

```
ALTER TABLE distributors ADD COLUMN address VARCHAR(30);
```

To drop a column from a table:

```
ALTER TABLE distributors DROP COLUMN address RESTRICT;
```

To rename an existing column:

```
ALTER TABLE distributors RENAME COLUMN address TO city;
```

To rename an existing table:

```
ALTER TABLE distributors RENAME TO suppliers;
```

To add a NOT NULL constraint to a column:

```
ALTER TABLE distributors ALTER COLUMN street SET NOT NULL;
```

To remove a NOT NULL constraint from a column:

```
ALTER TABLE distributors ALTER COLUMN street DROP NOT NULL;
```

To add a check constraint to a table:

```
ALTER TABLE distributors ADD CONSTRAINT zipchk CHECK
 (char_length(zipcode) = 5);
```

To remove a check constraint from a table and all its children:

```
ALTER TABLE distributors DROP CONSTRAINT zipchk;
```

To add a foreign key constraint to a table:

```
ALTER TABLE distributors ADD CONSTRAINT distfk FOREIGN KEY
 (address) REFERENCES addresses(address) MATCH FULL;
```

To add a (multicolumn) unique constraint to a table:

```
ALTER TABLE distributors ADD CONSTRAINT dist_id_zipcode_key UNIQUE
 (dist_id, zipcode);
```

To add an automatically named primary key constraint to a table, noting that a table can only ever have one primary key:

```
ALTER TABLE distributors ADD PRIMARY KEY (dist_id);
```

Compatibility

SQL92

The `ADD COLUMN` form is compliant with the exception that it does not support defaults and NOT NULL constraints, as explained above. The `ALTER COLUMN` form is in full compliance.

The clauses to rename tables, columns, indexes, and sequences are PostgreSQL extensions from SQL92.

Name

ALTER TRIGGER — change the definition of a trigger

Synopsis

<refsynopsisdivinfo>2002-04-19</refsynopsisdivinfo>

```
ALTER TRIGGER trigger ON table
    RENAME TO newname
```

Inputs

trigger

The name of an existing trigger to alter.

table

The name of the table on which this trigger acts.

newname

New name for the existing trigger.

Outputs

`ALTER TRIGGER`

Message returned from trigger renaming.

`ERROR`

Message returned if trigger is not available, or new name is a duplicate of another existing trigger on the table.

Description

`ALTER TRIGGER` changes the definition of an existing trigger. The `RENAME` clause causes the name of a trigger on the given table to change without otherwise changing the trigger definition.

You must own the table on which the trigger acts in order to change its properties.

Notes

Refer to `CREATE TRIGGER` for a further description of valid arguments.

Usage

To rename an existing trigger:

```
ALTER TRIGGER emp_stamp ON emp RENAME TO emp_track_chgs;
```

Compatibility

SQL92

The clause to rename triggers is a PostgreSQL extension from SQL92.

Name

ALTER USER — change a database user account

Synopsis

```
ALTER USER username [ [ WITH ] option [ ... ] ]

where option can be:

      [ ENCRYPTED | UNENCRYPTED ] PASSWORD 'password'
    | CREATEDB | NOCREATEDB
    | CREATEUSER | NOCREATEUSER
    | VALID UNTIL 'abstime'

ALTER USER username SET variable { TO | = } { value | DEFAULT }
ALTER USER username RESET variable
```

Description

`ALTER USER` is used to change the attributes of a PostgreSQL user account. Attributes not mentioned in the command retain their previous settings.

The first variant of this command in the synopsis changes certain global user privileges and authentication settings. (See below for details.) Only a database superuser can change privileges and password expiration with this command. Ordinary users can only change their own password.

The second and the third variant change a user's session default for a specified configuration variable. Whenever the user subsequently starts a new session, the specified value becomes the session default, overriding whatever setting is present in `postgresql.conf` or has been received from the postmaster. Ordinary users can change their own session defaults. Superusers can change anyone's session defaults.

Parameters

username

The name of the user whose attributes are to be altered.

password

The new password to be used for this account.

`ENCRYPTED`
`UNENCRYPTED`

These key words control whether the password is stored encrypted in `pg_shadow`. (See CREATE USER for more information about this choice.)

`CREATEDB`
`NOCREATEDB`

These clauses define a user's ability to create databases. If `CREATEDB` is specified, the user being defined will be allowed to create his own databases. Using `NOCREATEDB` will deny a user the ability to create databases.

`CREATEUSER`
`NOCREATEUSER`

These clauses determine whether a user will be permitted to create new users himself. This option will also make the user a superuser who can override all access restrictions.

abstime

The date (and, optionally, the time) at which this user's password is to expire.

variable
value

Set this user's session default for the specified configuration variable to the given value. If *value* is DEFAULT or, equivalently, RESET is used, the user-specific variable setting is removed and the user will inherit the system-wide default setting in new sessions. Use RESET ALL to clear all settings.

See SET and the *Administrator's Guide* for more information about allowed variable names and values.

Diagnostics

ALTER USER

Message returned if the alteration was successful.

ERROR: ALTER USER: user "username" does not exist

Error message returned if the specified user is not known to the database.

Notes

Use CREATE USER to add new users, and DROP USER to remove a user.

ALTER USER cannot change a user's group memberships. Use ALTER GROUP to do that.

Using ALTER DATABASE, it is also possible to tie a session default to a specific database rather than a user.

Examples

Change a user password:

```
ALTER USER davide WITH PASSWORD 'hu8jmn3';
```

Change a user's valid until date:

```
ALTER USER manuel VALID UNTIL 'Jan 31 2030';
```

Change a user's valid until date, specifying that his authorization should expire at midday on 4th May 1998 using the time zone which is one hour ahead of UTC:

```
ALTER USER chris VALID UNTIL 'May 4 12:00:00 1998 +1';
```

Give a user the ability to create other users and new databases:

```
ALTER USER miriam CREATEUSER CREATEDB;
```

Compatibility

The ALTER USER statement is a PostgreSQL extension. The SQL standard leaves the definition of users to the implementation.

See Also

CREATE USER, DROP USER, SET

Name

ANALYZE — collect statistics about a database

Synopsis

<refsynopsisdivinfo>2001-05-04</refsynopsisdivinfo>

```
ANALYZE [ VERBOSE ] [ table [ (column [, ...] ) ] ]
```

Inputs

VERBOSE

Enables display of progress messages.

table

The name (possibly schema-qualified) of a specific table to analyze. Defaults to all tables in the current database.

column

The name of a specific column to analyze. Defaults to all columns.

Outputs

ANALYZE

The command is complete.

Description

ANALYZE collects statistics about the contents of PostgreSQL tables, and stores the results in the system table pg_statistic. Subsequently, the query planner uses the statistics to help determine the most efficient execution plans for queries.

With no parameter, ANALYZE examines every table in the current database. With a parameter, ANALYZE examines only that table. It is further possible to give a list of column names, in which case only the statistics for those columns are updated.

Notes

It is a good idea to run ANALYZE periodically, or just after making major changes in the contents of a table. Accurate statistics will help the planner to choose the most appropriate query plan, and thereby improve the speed of query processing. A common strategy is to run VACUUM and ANALYZE once a day during a low-usage time of day.

Unlike VACUUM FULL, ANALYZE requires only a read lock on the target table, so it can run in parallel with other activity on the table.

For large tables, ANALYZE takes a random sample of the table contents, rather than examining every row. This allows even very large tables to be analyzed in a small amount of time. Note however that the statistics are only approximate, and will change slightly each time ANALYZE is run, even if the actual table contents did not change. This may result in small changes in the planner's estimated costs shown by EXPLAIN.

The collected statistics usually include a list of some of the most common values in each column and a histogram showing the approximate data distribution in each column. One or both of these may be

omitted if ANALYZE deems them uninteresting (for example, in a unique-key column, there are no common values) or if the column data type does not support the appropriate operators. There is more information about the statistics in the *User's Guide*.

The extent of analysis can be controlled by adjusting the default_statistics_target parameter variable, or on a column-by-column basis by setting the per-column statistics target with ALTER TABLE ALTER COLUMN SET STATISTICS (see ALTER TABLE). The target value sets the maximum number of entries in the most-common-value list and the maximum number of bins in the histogram. The default target value is 10, but this can be adjusted up or down to trade off accuracy of planner estimates against the time taken for ANALYZE and the amount of space occupied in pg_statistic. In particular, setting the statistics target to zero disables collection of statistics for that column. It may be useful to do that for columns that are never used as part of the WHERE, GROUP BY, or ORDER BY clauses of queries, since the planner will have no use for statistics on such columns.

The largest statistics target among the columns being analyzed determines the number of table rows sampled to prepare the statistics. Increasing the target causes a proportional increase in the time and space needed to do ANALYZE.

Compatibility

SQL92

There is no ANALYZE statement in SQL92.

Name

BEGIN — start a transaction block

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
BEGIN [ WORK | TRANSACTION ]
```

Inputs

WORK
TRANSACTION

Optional keywords. They have no effect.

Outputs

`BEGIN`

This signifies that a new transaction has been started.

`WARNING: BEGIN: already a transaction in progress`

This indicates that a transaction was already in progress. The current transaction is not affected.

Description

By default, PostgreSQL executes transactions in *unchained mode* (also known as "autocommit" in other database systems). In other words, each user statement is executed in its own transaction and a commit is implicitly performed at the end of the statement (if execution was successful, otherwise a rollback is done). `BEGIN` initiates a user transaction in chained mode, i.e., all user statements after `BEGIN` command will be executed in a single transaction until an explicit COMMIT or ROLLBACK. Statements are executed more quickly in chained mode, because transaction start/commit requires significant CPU and disk activity. Execution of multiple statements inside a transaction is also useful to ensure consistency when changing several related tables: other clients will be unable to see the intermediate states wherein not all the related updates have been done.

The default transaction isolation level in PostgreSQL is READ COMMITTED, wherein each query inside the transaction sees changes committed before that query begins execution. So, you have to use `SET TRANSACTION ISOLATION LEVEL SERIALIZABLE` just after `BEGIN` if you need more rigorous transaction isolation. (Alternatively, you can change the default transaction isolation level; see the *PostgreSQL Administrator's Guide* for details.) In SERIALIZABLE mode queries will see only changes committed before the entire transaction began (actually, before execution of the first DML statement in the transaction).

Transactions have the standard ACID (atomic, consistent, isolatable, and durable) properties.

Notes

START TRANSACTION has the same functionality as `BEGIN`.

Use COMMIT or ROLLBACK to terminate a transaction.

Refer to LOCK for further information about locking tables inside a transaction.

If you turn `autocommit` mode off, then `BEGIN` is not required: any SQL command automatically starts a transaction.

Usage

To begin a user transaction:

```
BEGIN WORK;
```

Compatibility

SQL92

`BEGIN` is a PostgreSQL language extension. There is no explicit `BEGIN` command in SQL92; transaction initiation is always implicit and it terminates either with a `COMMIT` or `ROLLBACK` statement.

Note

Many relational database systems offer an autocommit feature as a convenience.

Incidentally, the `BEGIN` keyword is used for a different purpose in embedded SQL. You are advised to be careful about the transaction semantics when porting database applications.

SQL92 also requires SERIALIZABLE to be the default transaction isolation level.

Name

CHECKPOINT — force a transaction log checkpoint

Synopsis

```
CHECKPOINT
```

Description

Write-Ahead Logging (WAL) puts a checkpoint in the transaction log every so often. (To adjust the automatic checkpoint interval, see the run-time configuration options *CHECKPOINT_SEGMENTS* and *CHECKPOINT_TIMEOUT*.) The CHECKPOINT command forces an immediate checkpoint when the command is issued, without waiting for a scheduled checkpoint.

A checkpoint is a point in the transaction log sequence at which all data files have been updated to reflect the information in the log. All data files will be flushed to disk. Refer to the *PostgreSQL Administrator's Guide* for more information about the WAL system.

Only superusers may call CHECKPOINT. The command is not intended for use during normal operation.

See Also

PostgreSQL Administrator's Guide

Compatibility

The CHECKPOINT command is a PostgreSQL language extension.

Name

CLOSE — close a cursor

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
CLOSE cursor
```

Inputs

cursor

The name of an open cursor to close.

Outputs

`CLOSE CURSOR`

Message returned if the cursor is successfully closed.

`WARNING: PerformPortalClose: portal "`*cursor*`" not found`

This warning is given if *cursor* is not declared or has already been closed.

Description

`CLOSE` frees the resources associated with an open cursor. After the cursor is closed, no subsequent operations are allowed on it. A cursor should be closed when it is no longer needed.

An implicit close is executed for every open cursor when a transaction is terminated by `COMMIT` or `ROLLBACK`.

Notes

PostgreSQL does not have an explicit `OPEN` cursor statement; a cursor is considered open when it is declared. Use the `DECLARE` statement to declare a cursor.

Usage

Close the cursor `liahona`:

```
CLOSE liahona;
```

Compatibility

SQL92

`CLOSE` is fully compatible with SQL92.

Name

CLUSTER — cluster a table according to an index

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
CLUSTER indexname ON tablename
```

Inputs

indexname

The name of an index.

table

The name (possibly schema-qualified) of a table.

Outputs

CLUSTER

The clustering was done successfully.

Description

CLUSTER instructs PostgreSQL to cluster the table specified by *table* based on the index specified by *indexname*. The index must already have been defined on *tablename*.

When a table is clustered, it is physically reordered based on the index information. Clustering is a one-time operation: when the table is subsequently updated, the changes are not clustered. That is, no attempt is made to store new or updated tuples according to their index order. If one wishes, one can periodically re-cluster by issuing the command again.

Notes

In cases where you are accessing single rows randomly within a table, the actual order of the data in the heap table is unimportant. However, if you tend to access some data more than others, and there is an index that groups them together, you will benefit from using CLUSTER.

Another place where CLUSTER is helpful is in cases where you use an index to pull out several rows from a table. If you are requesting a range of indexed values from a table, or a single indexed value that has multiple rows that match, CLUSTER will help because once the index identifies the heap page for the first row that matches, all other rows that match are probably already on the same heap page, saving disk accesses and speeding up the query.

During the cluster operation, a temporary copy of the table is created that contains the table data in the index order. Temporary copies of each index on the table are created as well. Therefore, you need free space on disk at least equal to the sum of the table size and the index sizes.

CLUSTER preserves GRANT, inheritance, index, foreign key, and other ancillary information about the table.

Because the optimizer records statistics about the ordering of tables, it is advisable to run ANALYZE on the newly clustered table. Otherwise, the optimizer may make poor choices of query plans.

There is another way to cluster data. The `CLUSTER` command reorders the original table using the ordering of the index you specify. This can be slow on large tables because the rows are fetched from the heap in index order, and if the heap table is unordered, the entries are on random pages, so there is one disk page retrieved for every row moved. (PostgreSQL has a cache, but the majority of a big table will not fit in the cache.) The other way to cluster a table is to use

```
SELECT columnlist INTO TABLE newtable
     FROM table ORDER BY columnlist
```

which uses the PostgreSQL sorting code in the ORDER BY clause to create the desired order; this is usually much faster than an index scan for unordered data. You then drop the old table, use `ALTER TABLE...RENAME` to rename *`newtable`* to the old name, and recreate the table's indexes. However, this approach does not preserve OIDs, constraints, foreign key relationships, granted privileges, and other ancillary properties of the table --- all such items must be manually recreated.

Usage

Cluster the employees relation on the basis of its ID attribute:

```
CLUSTER emp_ind ON emp;
```

Compatibility

SQL92

There is no `CLUSTER` statement in SQL92.

Name

COMMENT — define or change the comment of an object

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
COMMENT ON
[
  TABLE object_name |
  COLUMN table_name.column_name |
  AGGREGATE agg_name (agg_type) |
  CONSTRAINT constraint_name ON table_name |
  DATABASE object_name |
  DOMAIN object_name |
  FUNCTION func_name (arg1_type, arg2_type, ...) |
  INDEX object_name |
  OPERATOR op (leftoperand_type, rightoperand_type) |
  RULE rule_name ON table_name |
  SCHEMA object_name |
  SEQUENCE object_name |
  TRIGGER trigger_name ON table_name |
  TYPE object_name |
  VIEW object_name
] IS 'text'
```

Inputs

object_name, *table_name.column_name*, *agg_name*, *constraint_name*, *func_name*, *op*, *rule_name*, *trigger_name*

The name of the object to be be commented. Names of tables, aggregates, domains, functions, indexes, operators, sequences, types, and views may be schema-qualified.

text

The comment to add.

Outputs

COMMENT

Message returned if the table is successfully commented.

Description

COMMENT stores a comment about a database object. Comments can be easily retrieved with psql's \dd, \d+, or \l+ commands. Other user interfaces to retrieve comments can be built atop the same built-in functions that psql uses, namely obj_description() and col_description().

To modify a comment, issue a new COMMENT command for the same object. Only one comment string is stored for each object. To remove a comment, write NULL in place of the text string. Comments are automatically dropped when the object is dropped.

Note

There is presently no security mechanism for comments: any user connected to a database can see all the comments for objects in that database (although only superusers can change

comments for objects that they don't own). Therefore, don't put security-critical information in comments.

Usage

Attach a comment to the table `mytable`:

```
COMMENT ON TABLE mytable IS 'This is my table.';
```

Remove it again:

```
COMMENT ON TABLE mytable IS NULL;
```

Some more examples:

```
COMMENT ON AGGREGATE my_aggregate (double precision) IS 'Computes
 sample variance';
COMMENT ON COLUMN my_table.my_field IS 'Employee ID number';
COMMENT ON DATABASE my_database IS 'Development Database';
COMMENT ON DOMAIN my_domain IS 'Email Address Domain';
COMMENT ON FUNCTION my_function (timestamp) IS 'Returns Roman
 Numeral';
COMMENT ON INDEX my_index IS 'Enforces uniqueness on employee id';
COMMENT ON OPERATOR ^ (text, text) IS 'Performs intersection of two
 texts';
COMMENT ON OPERATOR ^ (NONE, text) IS 'This is a prefix operator on
 text';
COMMENT ON RULE my_rule ON my_table IS 'Logs UPDATES of employee
 records';
COMMENT ON SCHEMA my_schema IS 'Departmental data';
COMMENT ON SEQUENCE my_sequence IS 'Used to generate primary keys';
COMMENT ON TABLE my_schema.my_table IS 'Employee Information';
COMMENT ON TRIGGER my_trigger ON my_table IS 'Used for R.I.';
COMMENT ON TYPE complex IS 'Complex Number datatype';
COMMENT ON VIEW my_view IS 'View of departmental costs';
```

Compatibility

SQL92

There is no `COMMENT` in SQL92.

Name

COMMIT — commit the current transaction

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
COMMIT [ WORK | TRANSACTION ]
```

Inputs

WORK
TRANSACTION

Optional keywords. They have no effect.

Outputs

`COMMIT`

Message returned if the transaction is successfully committed.

`WARNING: COMMIT: no transaction in progress`

If there is no transaction in progress.

Description

`COMMIT` commits the current transaction. All changes made by the transaction become visible to others and are guaranteed to be durable if a crash occurs.

Notes

The keywords WORK and TRANSACTION are noise and can be omitted.

Use ROLLBACK to abort a transaction.

Usage

To make all changes permanent:

```
COMMIT WORK;
```

Compatibility

SQL92

SQL92 only specifies the two forms `COMMIT` and `COMMIT WORK`. Otherwise full compatibility.

Name

COPY — copy data between files and tables

Synopsis

<refsynopsisdivinfo>1999-12-11</refsynopsisdivinfo>

```
COPY table [ ( column [, ...] ) ]
    FROM { 'filename' | stdin }
    [ [ WITH ]
          [ BINARY ]
          [ OIDS ]
          [ DELIMITER [ AS ] 'delimiter' ]
          [ NULL [ AS ] 'null string' ] ]
COPY table [ ( column [, ...] ) ]
    TO { 'filename' | stdout }
    [ [ WITH ]
          [ BINARY ]
          [ OIDS ]
          [ DELIMITER [ AS ] 'delimiter' ]
          [ NULL [ AS ] 'null string' ] ]
```

Inputs

table

The name (possibly schema-qualified) of an existing table.

column

An optional list of columns to be copied. If no column list is specified, all columns will be used.

filename

The absolute Unix path name of the input or output file.

stdin

Specifies that input comes from the client application.

stdout

Specifies that output goes to the client application.

BINARY

Changes the behavior of field formatting, forcing all data to be stored or read in binary format rather than as text. You can not specify DELIMITER or NULL in binary mode.

OIDS

Specifies copying the internal object id (OID) for each row.

delimiter

The single character that separates fields within each row (line) of the file.

null string

The string that represents a NULL value. The default is "\N" (backslash-N). You might prefer an empty string, for example.

Note

On a copy in, any data item that matches this string will be stored as a NULL value, so you should make sure that you use the same string as you used on copy out.

Outputs

`COPY`

The copy completed successfully.

`ERROR: reason`

The copy failed for the reason stated in the error message.

Description

`COPY` moves data between PostgreSQL tables and standard file-system files. `COPY TO` copies the contents of a table *to* a file, while `COPY FROM` copies data *from* a file to a table (appending the data to whatever is in the table already).

If a list of columns is specified, `COPY` will only copy the data in the specified columns to or from the file. If there are any columns in the table that are not in the column list, `COPY FROM` will insert the default values for those columns.

`COPY` with a file name instructs the PostgreSQL backend to directly read from or write to a file. The file must be accessible to the backend and the name must be specified from the viewpoint of the backend. When `stdin` or `stdout` is specified, data flows through the client frontend to the backend.

Tip

Do not confuse `COPY` with the psql instruction `\copy`. `\copy` invokes `COPY FROM stdin` or `COPY TO stdout`, and then fetches/stores the data in a file accessible to the psql client. Thus, file accessibility and access rights depend on the client rather than the backend when `\copy` is used.

Notes

`COPY` can only be used with plain tables, not with views.

The BINARY keyword will force all data to be stored/read as binary format rather than as text. It is somewhat faster than the normal copy command, but a binary copy file is not portable across machine architectures.

By default, a text copy uses a tab ("\t") character as a delimiter between fields. The field delimiter may be changed to any other single character with the keyword `DELIMITER`. Characters in data fields that happen to match the delimiter character will be backslash quoted.

You must have *select privilege* on any table whose values are read by `COPY TO`, and *insert privilege* on a table into which values are being inserted by `COPY FROM`. The backend also needs appropriate Unix permissions for any file read or written by `COPY`.

`COPY FROM` will invoke any triggers and check constraints on the destination table. However, it will not invoke rules.

`COPY` stops operation at the first error. This should not lead to problems in the event of a `COPY TO`, but the target relation will already have received earlier rows in a `COPY FROM`. These rows will not be visible or accessible, but they still occupy disk space. This may amount to a considerable amount of wasted disk space if the failure happened well into a large copy operation. You may wish to invoke `VACUUM` to recover the wasted space.

Files named in a COPY command are read or written directly by the backend, not by the client application. Therefore, they must reside on or be accessible to the database server machine, not the client. They must be accessible to and readable or writable by the PostgreSQL user (the user ID the server runs as), not the client. COPY naming a file is only allowed to database superusers, since it allows reading or writing any file that the backend has privileges to access.

Tip

The psql instruction \copy reads or writes files on the client machine with the client's permissions, so it is not restricted to superusers.

It is recommended that the file name used in COPY always be specified as an absolute path. This is enforced by the backend in the case of COPY TO, but for COPY FROM you do have the option of reading from a file specified by a relative path. The path will be interpreted relative to the backend's working directory (somewhere below $PGDATA), not the client's working directory.

File Formats

Text Format

When COPY is used without the BINARY option, the file read or written is a text file with one line per table row. Columns (attributes) in a row are separated by the delimiter character. The attribute values themselves are strings generated by the output function, or acceptable to the input function, of each attribute's data type. The specified null-value string is used in place of attributes that are NULL. COPY FROM will raise an error if any line of the input file contains more or fewer columns than are expected.

If OIDS is specified, the OID is read or written as the first column, preceding the user data columns. (An error is raised if OIDS is specified for a table that does not have OIDs.)

End of data can be represented by a single line containing just backslash-period (\.). An end-of-data marker is not necessary when reading from a Unix file, since the end of file serves perfectly well; but an end marker must be provided when copying data to or from a client application.

Backslash characters (\) may be used in the COPY data to quote data characters that might otherwise be taken as row or column delimiters. In particular, the following characters *must* be preceded by a backslash if they appear as part of an attribute value: backslash itself, newline, and the current delimiter character.

The following special backslash sequences are recognized by COPY FROM:

Sequence	Represents
\b	Backspace (ASCII 8)
\f	Form feed (ASCII 12)
\n	Newline (ASCII 10)
\r	Carriage return (ASCII 13)
\t	Tab (ASCII 9)
\v	Vertical tab (ASCII 11)
digits	Backslash followed by one to three octal digits specifies the character with that numeric code

Presently, COPY TO will never emit an octal-digits backslash sequence, but it does use the other sequences listed above for those control characters.

Never put a backslash before a data character N or period (.). Such pairs will be mistaken for the default null string or the end-of-data marker, respectively. Any other backslashed character that is not mentioned in the above table will be taken to represent itself.

It is strongly recommended that applications generating COPY data convert data newlines and carriage returns to the `\n` and `\r` sequences respectively. At present (PostgreSQL 7.2 and older versions) it is possible to represent a data carriage return without any special quoting, and to represent a data newline by a backslash and newline. However, these representations will not be accepted by default in future releases.

Note that the end of each row is marked by a Unix-style newline ("\n"). Presently, `COPY FROM` will not behave as desired if given a file containing DOS- or Mac-style newlines. This is expected to change in future releases.

Binary Format

The file format used for `COPY BINARY` changed in PostgreSQL v7.1. The new format consists of a file header, zero or more tuples, and a file trailer.

File Header

The file header consists of 24 bytes of fixed fields, followed by a variable-length header extension area. The fixed fields are:

Signature

12-byte sequence `PGBCOPY\n\377\r\n\0` --- note that the null is a required part of the signature. (The signature is designed to allow easy identification of files that have been munged by a non-8-bit-clean transfer. This signature will be changed by newline-translation filters, dropped nulls, dropped high bits, or parity changes.)

Integer layout field

int32 constant 0x01020304 in source's byte order. Potentially, a reader could engage in byte-flipping of subsequent fields if the wrong byte order is detected here.

Flags field

int32 bit mask to denote important aspects of the file format. Bits are numbered from 0 (LSB) to 31 (MSB) --- note that this field is stored with source's endianness, as are all subsequent integer fields. Bits 16-31 are reserved to denote critical file format issues; a reader should abort if it finds an unexpected bit set in this range. Bits 0-15 are reserved to signal backwards-compatible format issues; a reader should simply ignore any unexpected bits set in this range. Currently only one flag bit is defined, and the rest must be zero:

Bit 16

if 1, OIDs are included in the dump; if 0, not

Header extension area length

int32 length in bytes of remainder of header, not including self. In the initial version this will be zero, and the first tuple follows immediately. Future changes to the format might allow additional data to be present in the header. A reader should silently skip over any header extension data it does not know what to do with.

The header extension area is envisioned to contain a sequence of self-identifying chunks. The flags field is not intended to tell readers what is in the extension area. Specific design of header extension contents is left for a later release.

This design allows for both backwards-compatible header additions (add header extension chunks, or set low-order flag bits) and non-backwards-compatible changes (set high-order flag bits to signal such changes, and add supporting data to the extension area if needed).

Tuples

Each tuple begins with an int16 count of the number of fields in the tuple. (Presently, all tuples in a table will have the same count, but that might not always be true.) Then, repeated for each field in the tuple, there is an int16 `typlen` word possibly followed by field data. The `typlen` field is interpreted thus:

Zero

Field is NULL. No data follows.

> 0

Field is a fixed-length data type. Exactly N bytes of data follow the `typlen` word.

-1

Field is a `varlena` data type. The next four bytes are the `varlena` header, which contains the total value length including itself.

< -1

Reserved for future use.

For non-NULL fields, the reader can check that the `typlen` matches the expected `typlen` for the destination column. This provides a simple but very useful check that the data is as expected.

There is no alignment padding or any other extra data between fields. Note also that the format does not distinguish whether a data type is pass-by-reference or pass-by-value. Both of these provisions are deliberate: they might help improve portability of the files (although of course endianness and floating-point-format issues can still keep you from moving a binary file across machines).

If OIDs are included in the dump, the OID field immediately follows the field-count word. It is a normal field except that it's not included in the field-count. In particular it has a `typlen` --- this will allow handling of 4-byte vs 8-byte OIDs without too much pain, and will allow OIDs to be shown as NULL if that ever proves desirable.

File Trailer

The file trailer consists of an int16 word containing -1. This is easily distinguished from a tuple's field-count word.

A reader should report an error if a field-count word is neither -1 nor the expected number of columns. This provides an extra check against somehow getting out of sync with the data.

Usage

The following example copies a table to standard output, using a vertical bar (|) as the field delimiter:

```
COPY country TO stdout WITH DELIMITER '|';
```

To copy data from a Unix file into the `country` table:

```
COPY country FROM '/usr1/proj/bray/sql/country_data';
```

Here is a sample of data suitable for copying into a table from `stdin` (so it has the termination sequence on the last line):

```
AF      AFGHANISTAN
AL      ALBANIA
```

```
DZ      ALGERIA
ZM      ZAMBIA
ZW      ZIMBABWE
\.
```

Note that the white space on each line is actually a TAB.

The following is the same data, output in binary format on a Linux/i586 machine. The data is shown after filtering through the Unix utility `od -c`. The table has three fields; the first is `char(2)`, the second is `text`, and the third is `integer`. All the rows have a null value in the third field.

```
0000000   P   G   B   C   O   P   Y  \n 377  \r  \n  \0 004 003 002
 001
0000020  \0  \0  \0  \0  \0  \0  \0  \0 003  \0 377 377 006  \0  \0
  \0
0000040   A   F 377 377 017  \0  \0  \0   A   F   G   H   A   N   I
   S
0000060   T   A   N  \0  \0 003  \0 377 377 006  \0  \0  \0   A   L
 377
0000100 377  \v  \0  \0  \0   A   L   B   A   N   I   A  \0  \0 003
  \0
0000120 377 377 006  \0  \0  \0   D   Z 377 377  \v  \0  \0  \0   A
   L
0000140   G   E   R   I   A  \0  \0 003  \0 377 377 006  \0  \0  \0
   Z
0000160   M 377 377  \n  \0  \0  \0   Z   A   M   B   I   A  \0  \0
 003
0000200  \0 377 377 006  \0  \0  \0   Z   W 377 377  \f  \0  \0  \0
   Z
0000220   I   M   B   A   B   W   E  \0  \0 377 377
```

Compatibility

SQL92

There is no `COPY` statement in SQL92.

The following syntax was used by pre-7.3 applications and is still supported:

```
COPY [ BINARY ] table [ WITH OIDS ]
    FROM { 'filename' | stdin }
    [ [USING] DELIMITERS 'delimiter' ]
    [ WITH NULL AS 'null string' ]
COPY [ BINARY ] table [ WITH OIDS ]
    TO { 'filename' | stdout }
    [ [USING] DELIMITERS 'delimiter' ]
    [ WITH NULL AS 'null string' ]
```

Name

CREATE AGGREGATE — define a new aggregate function

Synopsis

<refsynopsisdivinfo>2000-07-16</refsynopsisdivinfo>

```
CREATE AGGREGATE name ( BASETYPE = input_data_type,
    SFUNC = sfunc, STYPE = state_type
    [ , FINALFUNC = ffunc ]
    [ , INITCOND = initial_condition ] )
```

Inputs

name

The name (optionally schema-qualified) of an aggregate function to create.

input_data_type

The input data type on which this aggregate function operates. This can be specified as "ANY" for an aggregate that does not examine its input values (an example is `count(*)`).

sfunc

The name of the state transition function to be called for each input data value. This is normally a function of two arguments, the first being of type *state_type* and the second of type *input_data_type*. Alternatively, for an aggregate that does not examine its input values, the function takes just one argument of type *state_type*. In either case the function must return a value of type *state_type*. This function takes the current state value and the current input data item, and returns the next state value.

state_type

The data type for the aggregate's state value.

ffunc

The name of the final function called to compute the aggregate's result after all input data has been traversed. The function must take a single argument of type *state_type*. The output data type of the aggregate is defined as the return type of this function. If *ffunc* is not specified, then the ending state value is used as the aggregate's result, and the output type is *state_type*.

initial_condition

The initial setting for the state value. This must be a literal constant in the form accepted for the data type *state_type*. If not specified, the state value starts out NULL.

Outputs

CREATE AGGREGATE

Message returned if the command completes successfully.

Description

CREATE AGGREGATE allows a user or programmer to extend PostgreSQL functionality by defining new aggregate functions. Some aggregate functions for base types such as `min(integer)` and

`avg(double precision)` are already provided in the base distribution. If one defines new types or needs an aggregate function not already provided, then `CREATE AGGREGATE` can be used to provide the desired features.

If a schema name is given (for example, `CREATE AGGREGATE myschema.myagg ...`) then the aggregate function is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`).

An aggregate function is identified by its name and input data type. Two aggregates in the same schema can have the same name if they operate on different input types. The name and input data type of an aggregate must also be distinct from the name and input data type(s) of every ordinary function in the same schema.

An aggregate function is made from one or two ordinary functions: a state transition function *`sfunc`*, and an optional final calculation function *`ffunc`*. These are used as follows:

```
sfunc( internal-state, next-data-item ) ---> next-internal-state
ffunc( internal-state ) ---> aggregate-value
```

PostgreSQL creates a temporary variable of data type *`stype`* to hold the current internal state of the aggregate. At each input data item, the state transition function is invoked to calculate a new internal state value. After all the data has been processed, the final function is invoked once to calculate the aggregate's output value. If there is no final function then the ending state value is returned as-is.

An aggregate function may provide an initial condition, that is, an initial value for the internal state value. This is specified and stored in the database as a field of type `text`, but it must be a valid external representation of a constant of the state value data type. If it is not supplied then the state value starts out NULL.

If the state transition function is declared “strict”, then it cannot be called with NULL inputs. With such a transition function, aggregate execution behaves as follows. NULL input values are ignored (the function is not called and the previous state value is retained). If the initial state value is NULL, then the first non-NULL input value replaces the state value, and the transition function is invoked beginning with the second non-NULL input value. This is handy for implementing aggregates like `max`. Note that this behavior is only available when *`state_type`* is the same as *`input_data_type`*. When these types are different, you must supply a non-NULL initial condition or use a non-strict transition function.

If the state transition function is not strict, then it will be called unconditionally at each input value, and must deal with NULL inputs and NULL transition values for itself. This allows the aggregate author to have full control over the aggregate's handling of null values.

If the final function is declared “strict”, then it will not be called when the ending state value is NULL; instead a NULL result will be output automatically. (Of course this is just the normal behavior of strict functions.) In any case the final function has the option of returning NULL. For example, the final function for `avg` returns NULL when it sees there were zero input tuples.

Notes

Use `DROP AGGREGATE` to drop aggregate functions.

The parameters of `CREATE AGGREGATE` can be written in any order, not just the order illustrated above.

Usage

Refer to the chapter on aggregate functions in the *PostgreSQL Programmer's Guide* for complete examples of usage.

Compatibility

SQL92

`CREATE AGGREGATE` is a PostgreSQL language extension. There is no `CREATE AGGREGATE` in SQL92.

Name

CREATE CAST — define a user-defined cast

Synopsis

```
CREATE CAST (sourcetype AS targettype)
    WITH FUNCTION funcname (argtype)
    [ AS ASSIGNMENT | AS IMPLICIT ]

CREATE CAST (sourcetype AS targettype)
    WITHOUT FUNCTION
    [ AS ASSIGNMENT | AS IMPLICIT ]
```

Description

`CREATE CAST` defines a new cast. A cast specifies how to perform a conversion between two data types. For example,

```
SELECT CAST(42 AS text);
```

converts the integer constant 42 to type `text` by invoking a previously specified function, in this case `text(int4)`. (If no suitable cast has been defined, the conversion fails.)

Two types may be *binary compatible*, which means that they can be converted into one another "for free" without invoking any function. This requires that corresponding values use the same internal representation. For instance, the types `text` and `varchar` are binary compatible.

By default, a cast can be invoked only by an explicit cast request, that is an explicit `CAST(`*`x`* `AS` *`typename`*`)`, *`x`*`::`*`typename`*, or *`typename`*`(`*`x`*`)` construct.

If the cast is marked `AS ASSIGNMENT` then it can be invoked implicitly when assigning to a column of the target data type. For example, supposing that `foo.f1` is a column of type `text`, then

```
INSERT INTO foo(f1) VALUES(42);
```

will be allowed if the cast from type `integer` to type `text` is marked `AS ASSIGNMENT`, otherwise not. (We generally use the term *assignment cast* to describe this kind of cast.)

If the cast is marked `AS IMPLICIT` then it can be invoked implicitly in any context, whether assignment or internally in an expression. For example, since `||` takes `text` arguments,

```
SELECT 'The time is ' || now();
```

will be allowed only if the cast from type `timestamp` to `text` is marked `AS IMPLICIT`. Otherwise it will be necessary to write the cast explicitly, for example

```
SELECT 'The time is ' || CAST(now() AS text);
```

(We generally use the term *implicit cast* to describe this kind of cast.)

It is wise to be conservative about marking casts as implicit. An overabundance of implicit casting paths can cause PostgreSQL to choose surprising interpretations of commands, or to be unable to resolve commands at all because there are multiple possible interpretations. A good rule of thumb is to make a cast implicitly invokable only for information-preserving transformations between types in the same general type category. For example, the cast from `int2` to `int4` can reasonably be implicit, but the cast from `float8` to `int4` should probably be assignment-only. Cross-type-category casts, such as `text` to `int4`, are best made explicit-only.

To be able to create a cast, you must own the source or the target data type. To create a binary-compatible cast, you must be superuser (this restriction is made because an erroneous binary-compatible cast conversion can easily crash the server).

Parameters

sourcetype

The name of the source data type of the cast.

targettype

The name of the target data type of the cast.

funcname(*argtype*)

The function used to perform the cast. The function name may be schema-qualified. If it is not, the function will be looked up in the path. The argument type must be identical to the source type, the result data type must match the target type of the cast.

`WITHOUT FUNCTION`

Indicates that the source type and the target type are binary compatible, so no function is required to perform the cast.

`AS ASSIGNMENT`

Indicates that the cast may be invoked implicitly in assignment contexts.

`AS IMPLICIT`

Indicates that the cast may be invoked implicitly in any context.

Notes

Use `DROP CAST` to remove user-defined casts.

Remember that if you want to be able to convert types both ways you need to declare casts both ways explicitly.

Prior to PostgreSQL 7.3, every function that had the same name as a data type, returned that data type, and took one argument of a different type was automatically a cast function. This convention has been abandoned in face of the introduction of schemas and to be able to represent binary compatible casts in the catalogs. (The built-in cast functions still follow this naming scheme, but they have to be shown as casts in `pg_cast` now.)

Examples

To create a cast from type `text` to type `int4` using the function `int4(text)`:

```
CREATE CAST (text AS int4) WITH FUNCTION int4(text);
```

(This cast is already predefined in the system.)

Compatibility

The `CREATE CAST` command conforms to SQL99, except that SQL99 does not make provisions for binary compatible types. `AS IMPLICIT` is a PostgreSQL extension, too.

See Also

CREATE FUNCTION, CREATE TYPE, DROP CAST, *PostgreSQL Programmer's Guide*

Name

CREATE CONSTRAINT TRIGGER — define a new constraint trigger

Synopsis

<refsynopsisdivinfo>2000-04-13</refsynopsisdivinfo>

```
CREATE CONSTRAINT TRIGGER name
    AFTER events ON
    relation constraint attributes
    FOR EACH ROW EXECUTE PROCEDURE func '(' args ')'
```

Inputs

name

The name of the constraint trigger.

events

The event categories for which this trigger should be fired.

relation

The name (possibly schema-qualified) of the relation in which the triggering events occur.

constraint

Actual constraint specification.

attributes

Constraint attributes.

func(*args*)

Function to call as part of the trigger processing.

Outputs

CREATE TRIGGER

Message returned if successful.

Description

CREATE CONSTRAINT TRIGGER is used within CREATE/ALTER TABLE and by pg_dump to create the special triggers for referential integrity.

It is not intended for general use.

Name

CREATE CONVERSION — define a user-defined encoding conversion

Synopsis

```
CREATE [DEFAULT] CONVERSION conversion_name
    FOR source_encoding TO dest_encoding FROM funcname
```

Description

`CREATE CONVERSION` defines a new encoding conversion. Conversion names may be used in the CONVERT() function to specify a particular encoding conversion. Also, conversions that are marked DEFAULT can be used for automatic encoding conversion between frontend and backend. For this purpose, two conversions, from encoding A to B AND from encoding B to A, must be defined.

To be able to create a conversion, you must have the execute right on the function and the create right on the destination schema.

Parameters

`DEFAULT`

The `DEFAULT` clause indicates that this conversion is the default for this particular source to destination encoding. There should be only one default encoding in a schema for the encoding pair.

`conversion_name`

The name of the conversion. The conversion name may be schema-qualified. If it is not, the conversion is defined in the current schema. The conversion name must be unique within a schema.

`source_encoding`

The source encoding name.

`source_encoding`

The destination encoding name.

`funcname`

The function used to perform the conversion. The function name may be schema-qualified. If it is not, the function will be looked up in the path.

The function must have the following signature:

```
conv_proc(
INTEGER, -- source encoding id
INTEGER, -- destination encoding id
CSTRING, -- source string (null terminated C string)
INTERNAL, -- destination (fill with a null terminated C string)
INTEGER  -- source string length
) returns VOID;
```

Notes

Use `DROP CONVERSION` to remove user-defined conversions.

The privileges required to create a conversion may be changed in a future release.

Examples

To create a conversion from encoding UNICODE to LATIN1 using `myfunc`:

```
CREATE CONVERSION myconv FOR 'UNICODE' TO 'LATIN1' FROM myfunc;
```

Compatibility

`CREATE CONVERSION` is a PostgreSQL extension. There is no `CREATE CONVERSION` statement in SQL99.

See Also

CREATE FUNCTION, DROP CONVERSION, *PostgreSQL Programmer's Guide*

Name

CREATE DATABASE — create a new database

Synopsis

<refsynopsisdivinfo>1999-12-11</refsynopsisdivinfo>

```
CREATE DATABASE name
    [ [ WITH ] [ OWNER [=] dbowner ]
           [ LOCATION [=] 'dbpath' ]
           [ TEMPLATE [=] template ]
           [ ENCODING [=] encoding ] ]
```

Inputs

name

The name of a database to create.

dbowner

Name of the database user who will own the new database, or DEFAULT to use the default (namely, the user executing the command).

dbpath

An alternate file-system location in which to store the new database, specified as a string literal; or DEFAULT to use the default location.

template

Name of template from which to create the new database, or DEFAULT to use the default template (template1).

encoding

Multibyte encoding method to use in the new database. Specify a string literal name (e.g., 'SQL_ASCII'), or an integer encoding number, or DEFAULT to use the default encoding.

Outputs

CREATE DATABASE

Message returned if the command completes successfully.

ERROR: user '*username*' is not allowed to create/drop databases

You must have the special CREATEDB privilege to create databases. See CREATE USER.

ERROR: createdb: database "*name*" already exists

This occurs if a database with the *name* specified already exists.

ERROR: database path may not contain single quotes

The database location *dbpath* cannot contain single quotes. This is required so that the shell commands that create the database directory can execute safely.

ERROR: CREATE DATABASE: may not be called in a transaction block

If you have an explicit transaction block in progress you cannot call CREATE DATABASE. You must finish the transaction first.

```
ERROR: Unable to create database directory 'path'.
ERROR: Could not initialize database directory.
```

These are most likely related to insufficient permissions on the data directory, a full disk, or other file system problems. The user under which the database server is running must have access to the location.

Description

`CREATE DATABASE` creates a new PostgreSQL database.

Normally, the creator becomes the owner of the new database. Superusers can create databases owned by other users using the `OWNER` clause. They can even create databases owned by users with no special privileges. Non-superusers with `CREATEDB` privilege can only create databases owned by themselves.

An alternate location can be specified in order to, for example, store the database on a different disk. The path must have been prepared with the initlocation command.

If the path name does not contain a slash, it is interpreted as an environment variable name, which must be known to the server process. This way the database administrator can exercise control over locations in which databases can be created. (A customary choice is, e.g., `PGDATA2`.) If the server is compiled with `ALLOW_ABSOLUTE_DBPATHS` (not so by default), absolute path names, as identified by a leading slash (e.g., `/usr/local/pgsql/data`), are allowed as well.

By default, the new database will be created by cloning the standard system database `template1`. A different template can be specified by writing `TEMPLATE = name`. In particular, by writing `TEMPLATE = template0`, you can create a virgin database containing only the standard objects predefined by your version of PostgreSQL. This is useful if you wish to avoid copying any installation-local objects that may have been added to `template1`.

The optional encoding parameter allows selection of the database encoding, if your server was compiled with multibyte encoding support. When not specified, it defaults to the encoding used by the selected template database.

Optional parameters can be written in any order, not only the order illustrated above.

Notes

`CREATE DATABASE` is a PostgreSQL language extension.

Use DROP DATABASE to remove a database.

The program createdb is a shell script wrapper around this command, provided for convenience.

There are security and data integrity issues involved with using alternate database locations specified with absolute path names, and by default only an environment variable known to the backend may be specified for an alternate location. See the Administrator's Guide for more information.

Although it is possible to copy a database other than `template1` by specifying its name as the template, this is not (yet) intended as a general-purpose COPY DATABASE facility. We recommend that databases used as templates be treated as read-only. See the *Administrator's Guide* for more information.

Usage

To create a new database:

```
olly=> create database lusiadas;
```

To create a new database in an alternate area ~/private_db:

```
$ mkdir private_db
$ initlocation ~/private_db
    The location will be initialized with username "olly".
This user will own all the files and must also own the server
 process.
Creating directory /home/olly/private_db
Creating directory /home/olly/private_db/base

initlocation is complete.


$ psql olly
Welcome to psql, the PostgreSQL interactive terminal.

Type:  \copyright for distribution terms
       \h for help with SQL commands
       \? for help on internal slash commands
       \g or terminate with semicolon to execute query
       \q to quit

olly=> CREATE DATABASE elsewhere WITH LOCATION = '/home/olly/
private_db';
CREATE DATABASE
```

Compatibility

SQL92

There is no CREATE DATABASE statement in SQL92. Databases are equivalent to catalogs, whose creation is implementation-defined.

Name

CREATE DOMAIN — define a new domain

Synopsis

<refsynopsisdivinfo>2002-02-24</refsynopsisdivinfo>

```
CREATE DOMAIN domainname [AS] data_type
    [ DEFAULT default_expr ]
    [ constraint [ ... ] ]

where constraint is:

[ CONSTRAINT constraint_name ]
{ NOT NULL | NULL }
```

Parameters

domainname

The name (optionally schema-qualified) of a domain to be created.

data_type

The underlying data type of the domain. This may include array specifiers. Refer to the *User's Guide* for further information about data types and arrays.

DEFAULT *default_expr*

The DEFAULT clause specifies a default value for columns of the domain data type. The value is any variable-free expression (but subselects are not allowed). The data type of the default expression must match the data type of the domain.

The default expression will be used in any insert operation that does not specify a value for the column. If there is no default for a domain, then the default is NULL.

Note

If a default value is specified for a particular column, it overrides any default associated with the domain. In turn, the domain default overrides any default value associated with the underlying data type.

CONSTRAINT *constraint_name*

An optional name for a constraint. If not specified, the system generates a name.

NOT NULL

Values of this domain are not allowed to be NULL.

NULL

Values of this domain are allowed to be NULL. This is the default.

This clause is only available for compatibility with non-standard SQL databases. Its use is discouraged in new applications.

Outputs

CREATE DOMAIN

Message returned if the domain is successfully created.

Description

`CREATE DOMAIN` allows the user to register a new data domain with PostgreSQL for use in the current data base. The user who defines a domain becomes its owner.

If a schema name is given (for example, `CREATE DOMAIN myschema.mydomain ...`) then the domain is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`). The domain name must be unique among the types and domains existing in its schema.

Domains are useful for abstracting common fields between tables into a single location for maintenance. An email address column may be used in several tables, all with the same properties. Define a domain and use that rather than setting up each table's constraints individually.

Examples

This example creates the `country_code` data type and then uses the type in a table definition:

```
CREATE DOMAIN country_code char(2) NOT NULL;
CREATE TABLE countrylist (id INT4, country country_code);
```

Compatibility

SQL99 defines CREATE DOMAIN, but says that the only allowed constraint type is CHECK constraints. CHECK constraints for domains are not yet supported by PostgreSQL.

See Also

DROP DOMAIN , *PostgreSQL Programmer's Guide*

Name

CREATE FUNCTION — define a new function

Synopsis

```
CREATE [ OR REPLACE ] FUNCTION name ( [ argtype [, ...] ] )
    RETURNS rettype
  { LANGUAGE langname
    | IMMUTABLE | STABLE | VOLATILE
    | CALLED ON NULL INPUT | RETURNS NULL ON NULL INPUT | STRICT
    | [EXTERNAL] SECURITY INVOKER | [EXTERNAL] SECURITY DEFINER
    | AS 'definition'
    | AS 'obj_file', 'link_symbol'
  } ...
    [ WITH ( attribute [, ...] ) ]
```

Description

`CREATE FUNCTION` defines a new function. `CREATE OR REPLACE FUNCTION` will either create a new function, or replace an existing definition.

The user that creates the function becomes the owner of the function.

Parameters

name

The name of a function to create. If a schema name is included, then the function is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`). The name of the new function must not match any existing function with the same argument types in the same schema. However, functions of different argument types may share a name (this is called *overloading*).

argtype

The data type(s) of the function's arguments, if any. The input types may be base, complex, or domain types, or the same as the type of an existing column. The type of a column is referenced by writing *tablename.columnname*`%TYPE`; using this can sometimes help make a function independent from changes to the definition of a table. Depending on the implementation language it may also be allowed to specify “pseudo-types” such as `cstring`. Pseudo-types indicate that the actual argument type is either incompletely specified, or outside the set of ordinary SQL data types.

rettype

The return data type. The return type may be specified as a base, complex, or domain type, or the same as the type of an existing column. Depending on the implementation language it may also be allowed to specify “pseudo-types” such as `cstring`. The `setof` modifier indicates that the function will return a set of items, rather than a single item.

langname

The name of the language that the function is implemented in. May be `SQL`, `C`, `internal`, or the name of a user-defined procedural language. (See also createlang.) For backward compatibility, the name may be enclosed by single quotes.

IMMUTABLE
STABLE
VOLATILE

These attributes inform the system whether it is safe to replace multiple evaluations of the function with a single evaluation, for run-time optimization. At most one choice should be specified. If none of these appear, `VOLATILE` is the default assumption.

`IMMUTABLE` indicates that the function always returns the same result when given the same argument values; that is, it does not do database lookups or otherwise use information not directly present in its parameter list. If this option is given, any call of the function with all-constant arguments can be immediately replaced with the function value.

`STABLE` indicates that within a single table scan the function will consistently return the same result for the same argument values, but that its result could change across SQL statements. This is the appropriate selection for functions whose results depend on database lookups, parameter variables (such as the current time zone), etc. Also note that the `CURRENT_TIMESTAMP` family of functions qualify as stable, since their values do not change within a transaction.

`VOLATILE` indicates that the function value can change even within a single table scan, so no optimizations can be made. Relatively few database functions are volatile in this sense; some examples are `random()`, `currval()`, `timeofday()`. Note that any function that has side-effects must be classified volatile, even if its result is quite predictable, to prevent calls from being optimized away; an example is `setval()`.

CALLED ON NULL INPUT
RETURNS NULL ON NULL INPUT
STRICT

`CALLED ON NULL INPUT` (the default) indicates that the function will be called normally when some of its arguments are null. It is then the function author's responsibility to check for null values if necessary and respond appropriately.

`RETURNS NULL ON NULL INPUT` or `STRICT` indicates that the function always returns NULL whenever any of its arguments are NULL. If this parameter is specified, the function is not executed when there are NULL arguments; instead a NULL result is assumed automatically.

[EXTERNAL] SECURITY INVOKER
[EXTERNAL] SECURITY DEFINER

`SECURITY INVOKER` indicates that the function is to be executed with the privileges of the user that calls it. That is the default. `SECURITY DEFINER` specifies that the function is to be executed with the privileges of the user that created it.

The key word `EXTERNAL` is present for SQL compatibility but is optional since, unlike in SQL, this feature does not only apply to external functions.

`definition`

A string defining the function; the meaning depends on the language. It may be an internal function name, the path to an object file, an SQL query, or text in a procedural language.

`obj_file`, *`link_symbol`*

This form of the `AS` clause is used for dynamically linked C language functions when the function name in the C language source code is not the same as the name of the SQL function. The string *`obj_file`* is the name of the file containing the dynamically loadable object, and *`link_symbol`* is the object's link symbol, that is, the name of the function in the C language source code.

attribute

The historical way to specify optional pieces of information about the function. The following attributes may appear here:

`isStrict`

Equivalent to `STRICT` or `RETURNS NULL ON NULL INPUT`

`isCachable`

`isCachable` is an obsolete equivalent of `IMMUTABLE`; it's still accepted for backwards-compatibility reasons.

Attribute names are not case-sensitive.

Notes

Refer to the chapter in the *PostgreSQL Programmer's Guide* on the topic of extending PostgreSQL via functions for further information on writing external functions.

The full SQL type syntax is allowed for input arguments and return value. However, some details of the type specification (e.g., the precision field for `numeric` types) are the responsibility of the underlying function implementation and are silently swallowed (i.e., not recognized or enforced) by the `CREATE FUNCTION` command.

PostgreSQL allows function *overloading*; that is, the same name can be used for several different functions so long as they have distinct argument types. This facility must be used with caution for internal and C-language functions, however.

Two `internal` functions cannot have the same C name without causing errors at link time. To get around that, give them different C names (for example, use the argument types as part of the C names), then specify those names in the AS clause of `CREATE FUNCTION`. If the AS clause is left empty, then `CREATE FUNCTION` assumes the C name of the function is the same as the SQL name.

Similarly, when overloading SQL function names with multiple C-language functions, give each C-language instance of the function a distinct name, then use the alternative form of the `AS` clause in the `CREATE FUNCTION` syntax to select the appropriate C-language implementation of each overloaded SQL function.

When repeated `CREATE FUNCTION` calls refer to the same object file, the file is only loaded once. To unload and reload the file (perhaps during development), use the LOAD command.

Use `DROP FUNCTION` to remove user-defined functions.

To update the definition of an existing function, use `CREATE OR REPLACE FUNCTION`. Note that it is not possible to change the name or argument types of a function this way (if you tried, you'd just be creating a new, distinct function). Also, `CREATE OR REPLACE FUNCTION` will not let you change the return type of an existing function. To do that, you must drop and re-create the function.

If you drop and then re-create a function, the new function is not the same entity as the old; you will break existing rules, views, triggers, etc that referred to the old function. Use `CREATE OR REPLACE FUNCTION` to change a function definition without breaking objects that refer to the function.

To be able to define a function, the user must have the `USAGE` privilege on the language.

By default, only the owner (creator) of the function has the right to execute it. Other users must be granted the `EXECUTE` privilege on the function to be able to use it.

Examples

To create a simple SQL function:

```
CREATE FUNCTION one() RETURNS integer
    AS 'SELECT 1 AS RESULT;'
    LANGUAGE SQL;

SELECT one() AS answer;
 answer
--------
      1
```

The next example creates a C function by calling a routine from a user-created shared library named `funcs.so` (the extension may vary across platforms). The shared library file is sought in the server's dynamic library search path. This particular routine calculates a check digit and returns true if the check digit in the function parameters is correct. It is intended for use in a CHECK constraint.

```
CREATE FUNCTION ean_checkdigit(char, char) RETURNS boolean
    AS 'funcs' LANGUAGE C;

CREATE TABLE product (
    id        char(8) PRIMARY KEY,
    eanprefix char(8) CHECK (eanprefix ~ '[0-9]{2}-[0-9]{5}')
                      REFERENCES brandname(ean_prefix),
    eancode   char(6) CHECK (eancode ~ '[0-9]{6}'),
    CONSTRAINT ean    CHECK (ean_checkdigit(eanprefix, eancode))
);
```

The next example creates a function that does type conversion from the user-defined type complex to the built-in type point. The function is implemented by a dynamically loaded object that was compiled from C source (we illustrate the now-deprecated alternative of specifying the absolute file name to the shared object file). For PostgreSQL to find a type conversion function automatically, the SQL function has to have the same name as the return type, and so overloading is unavoidable. The function name is overloaded by using the second form of the `AS` clause in the SQL definition:

```
CREATE FUNCTION point(complex) RETURNS point
    AS '/home/bernie/pgsql/lib/complex.so', 'complex_to_point'
    LANGUAGE C STRICT;
```

The C declaration of the function could be:

```
Point * complex_to_point (Complex *z)
{
 Point *p;

 p = (Point *) palloc(sizeof(Point));
 p->x = z->x;
 p->y = z->y;

 return p;
}
```

Note that the function is marked “strict”; this allows us to skip checking for NULL input in the function body.

Writing `SECURITY DEFINER` Functions Safely

Because a `SECURITY DEFINER` function is executed with the privileges of the user that created it, care is needed to ensure that the function cannot be misused. For security, `search_path` should be set to exclude any schemas writable by untrusted users. This prevents malicious users from creating objects that mask objects used by the function. Particularly important in this regard is the temporary-table schema, which is searched first by default, and is normally writable by anyone. A

secure arrangement can be had by forcing the temporary schema to be searched last. To do this, write `pg_temp` as the last entry in `search_path`. This function illustrates safe usage:

```
CREATE FUNCTION check_password(TEXT, TEXT)
RETURNS BOOLEAN AS '
DECLARE passed BOOLEAN;
        old_path TEXT;
BEGIN
        -- Save old search_path; notice we must qualify
 current_setting
        -- to ensure we invoke the right function
        old_path := pg_catalog.current_setting(''search_path'');

        -- Set a secure search_path: trusted schemas, then
 ''pg_temp''.
        -- We set is_local = true so that the old value will be
 restored
        -- in event of an error before we reach the function end.
        PERFORM pg_catalog.set_config(''search_path'', ''admin,
 pg_temp'', true);

        -- Do whatever secure work we came for.
        SELECT  (pwd = $2) INTO passed
        FROM    pwds
        WHERE   username = $1;

        -- Restore caller''s search_path
        PERFORM pg_catalog.set_config(''search_path'', old_path,
 true);

        RETURN passed;
END;
' LANGUAGE plpgsql SECURITY DEFINER;
```

Compatibility

A `CREATE FUNCTION` command is defined in SQL99. The PostgreSQL version is similar but not fully compatible. The attributes are not portable, neither are the different available languages.

See Also

DROP FUNCTION, GRANT, LOAD, REVOKE, createlang, *PostgreSQL Programmer's Guide*

Name

CREATE GROUP — define a new user group

Synopsis

<refsynopsisdivinfo>2000-01-14</refsynopsisdivinfo>

```
CREATE GROUP name [ [ WITH ] option [ ... ] ]

where option can be:

      SYSID gid
    | USER  username [, ...]
```

Inputs

name

The name of the group.

gid

The SYSID clause can be used to choose the PostgreSQL group id of the new group. It is not necessary to do so, however.

If this is not specified, the highest assigned group id plus one, starting at 1, will be used as default.

username

A list of users to include in the group. The users must already exist.

Outputs

CREATE GROUP

Message returned if the command completes successfully.

Description

CREATE GROUP will create a new group in the database installation. Refer to the *Administrator's Guide* for information about using groups for authentication. You must be a database superuser to use this command.

Use ALTER GROUP to change a group's membership, and DROP GROUP to remove a group.

Usage

Create an empty group:

```
CREATE GROUP staff;
```

Create a group with members:

```
CREATE GROUP marketing WITH USER jonathan, david;
```

Compatibility

SQL92

There is no CREATE GROUP statement in SQL92. Roles are similar in concept to groups.

Name

CREATE INDEX — define a new index

Synopsis

<refsynopsisdivinfo>2001-07-15</refsynopsisdivinfo>

```
CREATE [ UNIQUE ] INDEX index_name ON table
    [ USING acc_method ] ( column [ ops_name ] [, ...] )
    [ WHERE predicate ]
CREATE [ UNIQUE ] INDEX index_name ON table
    [ USING acc_method ] ( func_name( column [, ... ]) [ ops_name
 ] )
    [ WHERE predicate ]
```

Inputs

UNIQUE

Causes the system to check for duplicate values in the table when the index is created (if data already exist) and each time data is added. Attempts to insert or update data which would result in duplicate entries will generate an error.

index_name

The name of the index to be created. No schema name can be included here; the index is always created in the same schema as its parent table.

table

The name (possibly schema-qualified) of the table to be indexed.

acc_method

The name of the access method to be used for the index. The default access method is `BTREE`. PostgreSQL provides four access methods for indexes:

`BTREE`

an implementation of Lehman-Yao high-concurrency B-trees.

`RTREE`

implements standard R-trees using Guttman's quadratic split algorithm.

`HASH`

an implementation of Litwin's linear hashing.

`GIST`

Generalized Index Search Trees.

column

The name of a column of the table.

ops_name

An associated operator class. See below for details.

func_name

A function, which returns a value that can be indexed.

predicate

Defines the constraint expression for a partial index.

Outputs

CREATE INDEX

The message returned if the index is successfully created.

ERROR: Cannot create index: 'index_name' already exists.

This error occurs if it is impossible to create the index.

Description

CREATE INDEX constructs an index *index_name* on the specified *table*.

Tip

Indexes are primarily used to enhance database performance. But inappropriate use will result in slower performance.

In the first syntax shown above, the key field(s) for the index are specified as column names. Multiple fields can be specified if the index access method supports multicolumn indexes.

In the second syntax shown above, an index is defined on the result of a user-specified function *func_name* applied to one or more columns of a single table. These *functional indexes* can be used to obtain fast access to data based on operators that would normally require some transformation to apply them to the base data. For example, a functional index on upper(col) would allow the clause WHERE upper(col) = 'JIM' to use an index.

PostgreSQL provides B-tree, R-tree, hash, and GiST access methods for indexes. The B-tree access method is an implementation of Lehman-Yao high-concurrency B-trees. The R-tree access method implements standard R-trees using Guttman's quadratic split algorithm. The hash access method is an implementation of Litwin's linear hashing. We mention the algorithms used solely to indicate that all of these access methods are fully dynamic and do not have to be optimized periodically (as is the case with, for example, static hash access methods).

When the WHERE clause is present, a *partial index* is created. A partial index is an index that contains entries for only a portion of a table, usually a portion that is somehow more interesting than the rest of the table. For example, if you have a table that contains both billed and unbilled orders where the unbilled orders take up a small fraction of the total table and yet that is an often used section, you can improve performance by creating an index on just that portion. Another possible application is to use WHERE with UNIQUE to enforce uniqueness over a subset of a table.

The expression used in the WHERE clause may refer only to columns of the underlying table (but it can use all columns, not only the one(s) being indexed). Presently, subqueries and aggregate expressions are also forbidden in WHERE.

All functions and operators used in an index definition must be *immutable*, that is, their results must depend only on their input arguments and never on any outside influence (such as the contents of another table or the current time). This restriction ensures that the behavior of the index is well-defined. To use a user-defined function in an index, remember to mark the function immutable when you create it.

Use DROP INDEX to remove an index.

Notes

The PostgreSQL query optimizer will consider using a B-tree index whenever an indexed attribute is involved in a comparison using one of: <, <=, =, >=, >

The PostgreSQL query optimizer will consider using an R-tree index whenever an indexed attribute is involved in a comparison using one of: <<, &<, &>, >>, @, ~=, &&

The PostgreSQL query optimizer will consider using a hash index whenever an indexed attribute is involved in a comparison using the = operator.

Testing has shown PostgreSQL's hash indexes to be similar or slower than B-tree indexes, and the index size and build time for hash indexes is much worse. Hash indexes also suffer poor performance under high concurrency. For these reasons, hash index use is discouraged.

Currently, only the B-tree and gist access methods support multicolumn indexes. Up to 32 keys may be specified by default (this limit can be altered when building PostgreSQL). Only B-tree currently supports unique indexes.

An *operator class* can be specified for each column of an index. The operator class identifies the operators to be used by the index for that column. For example, a B-tree index on four-byte integers would use the `int4_ops` class; this operator class includes comparison functions for four-byte integers. In practice the default operator class for the field's data type is usually sufficient. The main point of having operator classes is that for some data types, there could be more than one meaningful ordering. For example, we might want to sort a complex-number data type either by absolute value or by real part. We could do this by defining two operator classes for the data type and then selecting the proper class when making an index. There are also some operator classes with special purposes:

- The operator classes `box_ops` and `bigbox_ops` both support R-tree indexes on the `box` data type. The difference between them is that `bigbox_ops` scales box coordinates down, to avoid floating-point exceptions from doing multiplication, addition, and subtraction on very large floating-point coordinates. (Note: this was true some time ago, but currently the two operator classes both use floating point and are effectively identical.)

The following query shows all defined operator classes:

```
SELECT am.amname AS acc_method,
       opc.opcname AS ops_name
    FROM pg_am am, pg_opclass opc
    WHERE opc.opcamid = am.oid
    ORDER BY acc_method, ops_name;
```

Usage

To create a B-tree index on the field `title` in the table `films`:

```
CREATE UNIQUE INDEX title_idx
    ON films (title);
```

Compatibility

SQL92

CREATE INDEX is a PostgreSQL language extension.

There is no `CREATE INDEX` command in SQL92.

Name

CREATE LANGUAGE — define a new procedural language

Synopsis

```
CREATE [ TRUSTED ] [ PROCEDURAL ] LANGUAGE langname
    HANDLER call_handler [ VALIDATOR valfunction ]
```

Description

Using `CREATE LANGUAGE`, a PostgreSQL user can register a new procedural language with a PostgreSQL database. Subsequently, functions and trigger procedures can be defined in this new language. The user must have the PostgreSQL superuser privilege to register a new language.

`CREATE LANGUAGE` effectively associates the language name with a call handler that is responsible for executing functions written in the language. Refer to the *Programmer's Guide* for more information about language call handlers.

Note that procedural languages are local to individual databases. To make a language available in all databases by default, it should be installed into the `template1` database.

Parameters

`TRUSTED`

`TRUSTED` specifies that the call handler for the language is safe, that is, it does not offer an unprivileged user any functionality to bypass access restrictions. If this keyword is omitted when registering the language, only users with the PostgreSQL superuser privilege can use this language to create new functions.

`PROCEDURAL`

This is a noise word.

`langname`

The name of the new procedural language. The language name is case insensitive. A procedural language cannot override one of the built-in languages of PostgreSQL.

For backward compatibility, the name may be enclosed by single quotes.

`HANDLER` *`call_handler`*

`call_handler` is the name of a previously registered function that will be called to execute the procedural language functions. The call handler for a procedural language must be written in a compiled language such as C with version 1 call convention and registered with PostgreSQL as a function taking no arguments and returning the `language_handler` type, a placeholder type that is simply used to identify the function as a call handler.

`VALIDATOR` *`valfunction`*

`valfunction` is the name of a previously registered function that will be called when a new function in the language is created, to validate the new function. If no validator function is specified, then a new function will not be checked when it is created. The validator function must take one argument of type `oid`, which will be the OID of the to-be-created function, and will typically return `void`.

A validator function would typically inspect the function body for syntactical correctness, but it can also look at other properties of the function, for example if the language cannot handle certain

argument types. To signal an error, the validator function should use the `elog()` function. The return value of the function is ignored.

Diagnostics

`CREATE LANGUAGE`

This message is returned if the language is successfully created.

`ERROR:  PL handler function` *`funcname`*`() doesn't exist`

This error is returned if the function *`funcname`*() is not found.

Notes

This command normally should not be executed directly by users. For the procedural languages supplied in the PostgreSQL distribution, the createlang script should be used, which will also install the correct call handler. (`createlang` will call `CREATE LANGUAGE` internally.)

In PostgreSQL versions before 7.3, it was necessary to declare handler functions as returning the placeholder type `opaque`, rather than `language_handler`. To support loading of old dump files, `CREATE LANGUAGE` will accept a function declared as returning `opaque`, but it will issue a NOTICE and change the function's declared return type to `language_handler`.

Use the CREATE FUNCTION command to create a new function.

Use DROP LANGUAGE, or better yet the droplang script, to drop procedural languages.

The system catalog `pg_language` records information about the currently installed procedural languages.

```
        Table "pg_language"
   Attribute   |   Type    | Modifier
---------------+-----------+----------
 lanname       | name      |
 lanispl       | boolean   |
 lanpltrusted  | boolean   |
 lanplcallfoid | oid       |
 lanvalidator  | oid       |
 lanacl        | aclitem[] |

   lanname   | lanispl | lanpltrusted | lanplcallfoid |
 lanvalidator | lanacl
-------------+---------+--------------+---------------
+--------------+--------
 internal    | f       | f            |             0 |
 2246 |
 c           | f       | f            |             0 |
 2247 |
 sql         | f       | t            |             0 |
 2248 | {=U}
```

At present, with the exception of the permissions, the definition of a procedural language cannot be changed once it has been created.

To be able to use a procedural language, a user must be granted the `USAGE` privilege. The `createlang` program automatically grants permissions to everyone if the language is known to be trusted.

Examples

The following two commands executed in sequence will register a new procedural language and the associated call handler.

```
CREATE FUNCTION plsample_call_handler () RETURNS language_handler
    AS '$libdir/plsample'
    LANGUAGE C;
CREATE LANGUAGE plsample
    HANDLER plsample_call_handler;
```

Compatibility

`CREATE LANGUAGE` is a PostgreSQL extension.

History

The `CREATE LANGUAGE` command first appeared in PostgreSQL 6.3.

See Also

createlang, CREATE FUNCTION, droplang, DROP LANGUAGE, GRANT, REVOKE, *PostgreSQL Programmer's Guide*

Name

CREATE OPERATOR — define a new operator

Synopsis

<refsynopsisdivinfo>2000-03-25</refsynopsisdivinfo>

```
CREATE OPERATOR name ( PROCEDURE = func_name
     [, LEFTARG = lefttype
     ] [, RIGHTARG = righttype ]
     [, COMMUTATOR = com_op ] [, NEGATOR = neg_op ]
     [, RESTRICT = res_proc ] [, JOIN = join_proc ]
     [, HASHES ] [, MERGES ]
     [, SORT1 = left_sort_op ] [, SORT2 = right_sort_op ]
     [, LTCMP = less_than_op ] [, GTCMP = greater_than_op ] )
```

Inputs

name

The operator to be defined. See below for allowable characters. The name may be schema-qualified, for example `CREATE OPERATOR myschema.+ (...)`.

func_name

The function used to implement this operator.

lefttype

The type of the left-hand argument of the operator, if any. This option would be omitted for a left-unary operator.

righttype

The type of the right-hand argument of the operator, if any. This option would be omitted for a right-unary operator.

com_op

The commutator of this operator.

neg_op

The negator of this operator.

res_proc

The restriction selectivity estimator function for this operator.

join_proc

The join selectivity estimator function for this operator.

HASHES

Indicates this operator can support a hash join.

MERGES

Indicates this operator can support a merge join.

left_sort_op

If this operator can support a merge join, the less-than operator that sorts the left-hand data type of this operator.

right_sort_op

If this operator can support a merge join, the less-than operator that sorts the right-hand data type of this operator.

less_than_op

If this operator can support a merge join, the less-than operator that compares the input data types of this operator.

greater_than_op

If this operator can support a merge join, the greater-than operator that compares the input data types of this operator.

Outputs

CREATE OPERATOR

Message returned if the operator is successfully created.

Description

CREATE OPERATOR defines a new operator, *name*. The user who defines an operator becomes its owner.

If a schema name is given then the operator is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see CURRENT_SCHEMA()).

Two operators in the same schema can have the same name if they operate on different data types. This is called *overloading*. The system will attempt to pick the intended operator based on the actual input data types when there is ambiguity.

The operator *name* is a sequence of up to NAMEDATALEN-1 (63 by default) characters from the following list:

+ - * / < > = ~ ! @ # % ^ & | ` ? $

There are a few restrictions on your choice of name:

- $ cannot be defined as a single-character operator, although it can be part of a multicharacter operator name.
- -- and /* cannot appear anywhere in an operator name, since they will be taken as the start of a comment.
- A multicharacter operator name cannot end in + or -, unless the name also contains at least one of these characters:

  ~ ! @ # % ^ & | ` ? $

  For example, @- is an allowed operator name, but *- is not. This restriction allows PostgreSQL to parse SQL-compliant queries without requiring spaces between tokens.

Note

When working with non-SQL-standard operator names, you will usually need to separate adjacent operators with spaces to avoid ambiguity. For example, if you have defined a left-unary operator named `@`, you cannot write `X*@Y`; you must write `X* @Y` to ensure that PostgreSQL reads it as two operator names not one.

The operator `!=` is mapped to `<>` on input, so these two names are always equivalent.

At least one of `LEFTARG` and `RIGHTARG` must be defined. For binary operators, both should be defined. For right unary operators, only `LEFTARG` should be defined, while for left unary operators only `RIGHTARG` should be defined.

The *`func_name`* procedure must have been previously defined using `CREATE FUNCTION` and must be defined to accept the correct number of arguments (either one or two) of the indicated types.

The commutator operator should be identified if one exists, so that PostgreSQL can reverse the order of the operands if it wishes. For example, the operator area-less-than, <<<, would probably have a commutator operator, area-greater-than, >>>. Hence, the query optimizer could freely convert:

```
box '((0,0), (1,1))'  >>> MYBOXES.description
```

to

```
MYBOXES.description <<< box '((0,0), (1,1))'
```

This allows the execution code to always use the latter representation and simplifies the query optimizer somewhat.

Similarly, if there is a negator operator then it should be identified. Suppose that an operator, area-equal, ===, exists, as well as an area not equal, !==. The negator link allows the query optimizer to simplify

```
NOT MYBOXES.description === box '((0,0), (1,1))'
```

to

```
MYBOXES.description !== box '((0,0), (1,1))'
```

If a commutator operator name is supplied, PostgreSQL searches for it in the catalog. If it is found and it does not yet have a commutator itself, then the commutator's entry is updated to have the newly created operator as its commutator. This applies to the negator, as well. This is to allow the definition of two operators that are the commutators or the negators of each other. The first operator should be defined without a commutator or negator (as appropriate). When the second operator is defined, name the first as the commutator or negator. The first will be updated as a side effect. (As of PostgreSQL `6.5`, it also works to just have both operators refer to each other.)

The `HASHES`, `MERGES`, `SORT1`, `SORT2`, `LTCMP`, and `GTCMP` options are present to support the query optimizer in performing joins. PostgreSQL can always evaluate a join (i.e., processing a clause with two tuple variables separated by an operator that returns a `boolean`) by iterative substitution . In addition, PostgreSQL can use a hash-join algorithm ; however, it must know whether this strategy is applicable. The current hash-join algorithm is only correct for operators that represent equality tests; furthermore, equality of the data type must mean bitwise equality of the representation of the type. (For example, a data type that contains unused bits that don't matter for equality tests could not be hash-joined.) The `HASHES` flag indicates to the query optimizer that a hash join may safely be used with this operator.

Similarly, the MERGES flag indicates whether merge-sort is a usable join strategy for this operator. A merge join requires that the two input data types have consistent orderings, and that the merge-join operator behave like equality with respect to that ordering. For example, it is possible to merge-join equality between an integer and a float variable by sorting both inputs in ordinary numeric order. Execution of a merge join requires that the system be able to identify four operators related to the merge-join equality operator: less-than comparison for the left input data type, less-than comparison for the right input data type, less-than comparison between the two data types, and greater-than comparison between the two data types. It is possible to specify these by name, as the SORT1, SORT2, LTCMP, and GTCMP options respectively. The system will fill in the default names <, <, <, > respectively if any of these are omitted when MERGES is specified. Also, MERGES will be assumed to be implied if any of these four operator options appear.

If other join strategies are found to be practical, PostgreSQL will change the optimizer and run-time system to use them and will require additional specification when an operator is defined. Fortunately, the research community invents new join strategies infrequently, and the added generality of user-defined join strategies was not felt to be worth the complexity involved.

The RESTRICT and JOIN options assist the query optimizer in estimating result sizes. If a clause of the form:

```
myboxes.description <<< box '((0,0), (1,1))'
```

is present in the qualification, then PostgreSQL may have to estimate the fraction of the instances in myboxes that satisfy the clause. The function *res_proc* must be a registered function (meaning it is already defined using CREATE FUNCTION) which accepts arguments of the correct data types and returns a floating-point number. The query optimizer simply calls this function, passing the parameter ((0,0), (1,1)) and multiplies the result by the relation size to get the expected number of instances.

Similarly, when the operands of the operator both contain instance variables, the query optimizer must estimate the size of the resulting join. The function join_proc will return another floating-point number which will be multiplied by the cardinalities of the two tables involved to compute the expected result size.

The difference between the function

```
my_procedure_1 (MYBOXES.description, box '((0,0), (1,1))')
```

and the operator

```
MYBOXES.description === box '((0,0), (1,1))'
```

is that PostgreSQL attempts to optimize operators and can decide to use an index to restrict the search space when operators are involved. However, there is no attempt to optimize functions, and they are performed by brute force. Moreover, functions can have any number of arguments while operators are restricted to one or two.

Notes

Refer to the chapter on operators in the *PostgreSQL User's Guide* for further information. Refer to DROP OPERATOR to delete user-defined operators from a database.

To give a schema-qualified operator name in *com_op* or the other optional arguments, use the OPERATOR() syntax, for example

```
   COMMUTATOR = OPERATOR(myschema.===) ,
```

Usage

The following command defines a new operator, area-equality, for the BOX data type:

```
CREATE OPERATOR === (
   LEFTARG = box,
   RIGHTARG = box,
   PROCEDURE = area_equal_procedure,
   COMMUTATOR = ===,
   NEGATOR = !==,
   RESTRICT = area_restriction_procedure,
   JOIN = area_join_procedure,
   HASHES,
   SORT1 = <<<,
   SORT2 = <<<
   -- Since sort operators were given, MERGES is implied.
   -- LTCMP and GTCMP are assumed to be < and > respectively
);
```

Compatibility

SQL92

`CREATE OPERATOR` is a PostgreSQL extension. There is no `CREATE OPERATOR` statement in SQL92.

Name

CREATE OPERATOR CLASS — define a new operator class for indexes

Synopsis

<refsynopsisdivinfo>2002-07-28</refsynopsisdivinfo>

```
CREATE OPERATOR CLASS name [ DEFAULT ] FOR TYPE data_type
 USING access_method AS
  {  OPERATOR strategy_number operator_id [ ( type, type ) ]
 [ RECHECK ]
   | FUNCTION support_number func_name ( parameter_types )
   | STORAGE storage_type
  } [, ... ]
```

Inputs

name

The name of the operator class to be created. The name may be schema-qualified.

DEFAULT

If present, the operator class will become the default index operator class for its data type. At most one operator class can be the default for a specific data type and access method.

data_type

The column data type that this operator class is for.

access_method

The name of the index access method this operator class is for.

strategy_number

The index access method's strategy number for an operator associated with the operator class.

operator_id

The identifier (optionally schema-qualified) of an operator associated with the operator class.

type

The input data type(s) of an operator, or NONE to signify a left-unary or right-unary operator. The input data types may be omitted in the normal case where they are the same as the operator class's data type.

RECHECK

If present, the index is “lossy” for this operator, and so the tuples retrieved using the index must be rechecked to verify that they actually satisfy the qualification clause involving this operator.

support_number

The index access method's support procedure number for a function associated with the operator class.

func_name

The name (optionally schema-qualified) of a function that is an index access method support procedure for the operator class.

parameter_types

The parameter data type(s) of the function.

storage_type

The data type actually stored in the index. Normally this is the same as the column data type, but some index access methods (only GIST at this writing) allow it to be different. The STORAGE clause must be omitted unless the index access method allows a different type to be used.

Outputs

CREATE OPERATOR CLASS

Message returned if the operator class is successfully created.

Description

CREATE OPERATOR CLASS defines a new operator class, *name*.

An operator class defines how a particular data type can be used with an index. The operator class specifies that certain operators will fill particular roles or "strategies" for this data type and this access method. The operator class also specifies the support procedures to be used by the index access method when the operator class is selected for an index column. All the operators and functions used by an operator class must be defined before the operator class is created.

If a schema name is given then the operator class is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see CURRENT_SCHEMA()). Two operator classes in the same schema can have the same name only if they are for different index access methods.

The user who defines an operator class becomes its owner. Presently, the creating user must be a superuser. (This restriction is made because an erroneous operator class definition could confuse or even crash the server.)

CREATE OPERATOR CLASS does not presently check whether the class definition includes all the operators and functions required by the index access method. It is the user's responsibility to define a valid operator class.

Refer to the chapter on interfacing extensions to indexes in the *PostgreSQL Programmer's Guide* for further information.

Notes

Refer to DROP OPERATOR CLASS to delete user-defined operator classes from a database.

Usage

The following example command defines a GiST index operator class for data type _int4 (array of int4). See contrib/intarray/ for the complete example.

```
CREATE OPERATOR CLASS gist__int_ops
    DEFAULT FOR TYPE _int4 USING gist AS
        OPERATOR        3       &&,
        OPERATOR        6       =       RECHECK,
        OPERATOR        7       @,
        OPERATOR        8       ~,
        OPERATOR        20      @@ (_int4, query_int),
```

```
        FUNCTION        1       g_int_consistent (internal, _int4,
int4),
        FUNCTION        2       g_int_union (bytea, internal),
        FUNCTION        3       g_int_compress (internal),
        FUNCTION        4       g_int_decompress (internal),
        FUNCTION        5       g_int_penalty (internal, internal,
internal),
        FUNCTION        6       g_int_picksplit (internal,
internal),
        FUNCTION        7       g_int_same (_int4, _int4,
internal);
```

The `OPERATOR`, `FUNCTION`, and `STORAGE` clauses may appear in any order.

Compatibility

SQL92

`CREATE OPERATOR CLASS` is a PostgreSQL extension. There is no `CREATE OPERATOR CLASS` statement in SQL92.

Name

CREATE RULE — define a new rewrite rule

Synopsis

<refsynopsisdivinfo>2001-01-05</refsynopsisdivinfo>

```
CREATE [ OR REPLACE ] RULE name AS ON event
    TO table [ WHERE condition ]
    DO [ INSTEAD ] action

where action can be:

NOTHING
| query
| ( query ; query ... )
```

Inputs

name

The name of a rule to create. This must be distinct from the name of any other rule for the same table.

event

Event is one of `SELECT`, `UPDATE`, `DELETE` or `INSERT`.

table

The name (optionally schema-qualified) of the table or view the rule applies to.

condition

Any SQL conditional expression (returning `boolean`). The condition expression may not refer to any tables except `new` and `old`, and may not contain aggregate functions.

query

The query or queries making up the *action* can be any SQL `SELECT`, `INSERT`, `UPDATE`, `DELETE`, or `NOTIFY` statement.

Within the *condition* and *action*, the special table names `new` and `old` may be used to refer to values in the referenced table. `new` is valid in ON INSERT and ON UPDATE rules to refer to the new row being inserted or updated. `old` is valid in ON UPDATE and ON DELETE rules to refer to the existing row being updated or deleted.

Outputs

`CREATE RULE`

Message returned if the rule is successfully created.

Description

`CREATE RULE` defines a new rule applying to a specified table or view. `CREATE OR REPLACE RULE` will either create a new rule, or replace an existing rule of the same name for the same table.

The PostgreSQL *rule system* allows one to define an alternate action to be performed on inserts, updates, or deletions from database tables. Rules are used to implement table views as well.

The semantics of a rule is that at the time an individual instance (row) is accessed, inserted, updated, or deleted, there is an old instance (for selects, updates and deletes) and a new instance (for inserts and updates). All the rules for the given event type and the given target table are examined successively (in order by name). If the *condition* specified in the WHERE clause (if any) is true, the *action* part of the rule is executed. The *action* is done instead of the original query if INSTEAD is specified; otherwise it is done after the original query in the case of ON INSERT, or before the original query in the case of ON UPDATE or ON DELETE. Within both the *condition* and *action*, values from fields in the old instance and/or the new instance are substituted for `old.`*attribute-name* and `new.`*attribute-name*.

The *action* part of the rule can consist of one or more queries. To write multiple queries, surround them with parentheses. Such queries will be performed in the specified order. The *action* can also be NOTHING indicating no action. Thus, a DO INSTEAD NOTHING rule suppresses the original query from executing (when its condition is true); a DO NOTHING rule is useless.

The *action* part of the rule executes with the same command and transaction identifier as the user command that caused activation.

It is important to realize that a rule is really a query transformation mechanism, or query macro. The entire query is processed to convert it into a series of queries that include the rule actions. This occurs before evaluation of the query starts. So, conditional rules are handled by adding the rule condition to the WHERE clause of the action(s) derived from the rule. The above description of a rule as an operation that executes for each row is thus somewhat misleading. If you actually want an operation that fires independently for each physical row, you probably want to use a trigger not a rule. Rules are most useful for situations that call for transforming entire queries independently of the specific data being handled.

Rules and Views

Presently, ON SELECT rules must be unconditional INSTEAD rules and must have actions that consist of a single SELECT query. Thus, an ON SELECT rule effectively turns the table into a view, whose visible contents are the rows returned by the rule's SELECT query rather than whatever had been stored in the table (if anything). It is considered better style to write a CREATE VIEW command than to create a real table and define an ON SELECT rule for it.

CREATE VIEW creates a dummy table (with no underlying storage) and associates an ON SELECT rule with it. The system will not allow updates to the view, since it knows there is no real table there. You can create the illusion of an updatable view by defining ON INSERT, ON UPDATE, and ON DELETE rules (or any subset of those that's sufficient for your purposes) to replace update actions on the view with appropriate updates on other tables.

There is a catch if you try to use conditional rules for view updates: there *must* be an unconditional INSTEAD rule for each action you wish to allow on the view. If the rule is conditional, or is not INSTEAD, then the system will still reject attempts to perform the update action, because it thinks it might end up trying to perform the action on the dummy table in some cases. If you want to handle all the useful cases in conditional rules, you can; just add an unconditional DO INSTEAD NOTHING rule to ensure that the system understands it will never be called on to update the dummy table. Then make the conditional rules non-INSTEAD; in the cases where they fire, they add to the default INSTEAD NOTHING action.

Notes

You must have rule definition access to a table in order to define a rule on it. Use `GRANT` and `REVOKE` to change permissions.

It is very important to take care to avoid circular rules. For example, though each of the following two rule definitions are accepted by PostgreSQL, the select command will cause PostgreSQL to report an error because the query cycled too many times:

```
CREATE RULE "_RETURN" AS
```

```
    ON SELECT TO emp
    DO INSTEAD
 SELECT * FROM toyemp;

CREATE RULE "_RETURN" AS
    ON SELECT TO toyemp
    DO INSTEAD
 SELECT * FROM emp;
```

This attempt to select from EMP will cause PostgreSQL to issue an error because the queries cycled too many times:

```
SELECT * FROM emp;
```

Presently, if a rule contains a NOTIFY query, the NOTIFY will be executed unconditionally --- that is, the NOTIFY will be issued even if there are not any rows that the rule should apply to. For example, in

```
CREATE RULE notify_me AS ON UPDATE TO mytable DO NOTIFY mytable;

UPDATE mytable SET name = 'foo' WHERE id = 42;
```

one NOTIFY event will be sent during the UPDATE, whether or not there are any rows with id = 42. This is an implementation restriction that may be fixed in future releases.

Compatibility

SQL92

CREATE RULE is a PostgreSQL language extension. There is no CREATE RULE statement in SQL92.

Name

CREATE SCHEMA — define a new schema

Synopsis

```
CREATE SCHEMA schemaname [ AUTHORIZATION username ]
 [ schema_element [ ... ] ]
CREATE SCHEMA AUTHORIZATION username [ schema_element [ ... ] ]
```

Inputs

schemaname

The name of a schema to be created. If this is omitted, the user name is used as the schema name.

username

The name of the user who will own the schema. If omitted, defaults to the user executing the command. Only superusers may create schemas owned by users other than themselves.

schema_element

An SQL statement defining an object to be created within the schema. Currently, only CREATE TABLE, CREATE VIEW, and GRANT are accepted as clauses within CREATE SCHEMA. Other kinds of objects may be created in separate commands after the schema is created.

Outputs

CREATE SCHEMA

Message returned if the command is successful.

ERROR: namespace "*schemaname*" already exists

If the schema specified already exists.

Description

CREATE SCHEMA will enter a new schema into the current database. The schema name must be distinct from the name of any existing schema in the current database.

A schema is essentially a namespace: it contains named objects (tables, data types, functions, and operators) whose names may duplicate those of other objects existing in other schemas. Named objects are accessed either by "qualifying" their names with the schema name as a prefix, or by setting a search path that includes the desired schema(s). Unqualified objects are created in the current schema (the one at the front of the search path; see CURRENT_SCHEMA()).

Optionally, CREATE SCHEMA can include subcommands to create objects within the new schema. The subcommands are treated essentially the same as separate commands issued after creating the schema, except that if the AUTHORIZATION clause is used, all the created objects will be owned by that user.

Notes

To create a schema, the invoking user must have CREATE privilege for the current database. (Of course, superusers bypass this check.)

Use DROP SCHEMA to remove a schema.

Examples

Create a schema:

```
CREATE SCHEMA myschema;
```

Create a schema for user `joe` --- the schema will also be named `joe`:

```
CREATE SCHEMA AUTHORIZATION joe;
```

Create a schema and create a table and view within it:

```
CREATE SCHEMA hollywood
    CREATE TABLE films (title text, release date, awards text[])
    CREATE VIEW winners AS
        SELECT title, release FROM films WHERE awards IS NOT NULL;
```

Notice that the individual subcommands do not end with semicolons.

The following is an equivalent way of accomplishing the same result:

```
CREATE SCHEMA hollywood;
CREATE TABLE hollywood.films (title text, release date, awards
 text[]);
CREATE VIEW hollywood.winners AS
    SELECT title, release FROM hollywood.films WHERE awards IS NOT
 NULL;
```

Compatibility

SQL92

SQL92 allows a `DEFAULT CHARACTER SET` clause in `CREATE SCHEMA`, as well as more subcommand types than are presently accepted by PostgreSQL.

SQL92 specifies that the subcommands in `CREATE SCHEMA` may appear in any order. The present PostgreSQL implementation does not handle all cases of forward references in subcommands; it may sometimes be necessary to reorder the subcommands to avoid forward references.

In SQL92, the owner of a schema always owns all objects within it. PostgreSQL allows schemas to contain objects owned by users other than the schema owner. This can happen only if the schema owner grants `CREATE` rights on his schema to someone else.

Name

CREATE SEQUENCE — define a new sequence generator

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
CREATE [ TEMPORARY | TEMP ] SEQUENCE seqname [ INCREMENT increment
 ]
    [ MINVALUE minvalue ] [ MAXVALUE maxvalue ]
    [ START start ] [ CACHE cache ] [ CYCLE ]
```

Inputs

TEMPORARY or TEMP

If specified, the sequence object is created only for this session, and is automatically dropped on session exit. Existing permanent sequences with the same name are not visible (in this session) while the temporary sequence exists, unless they are referenced with schema-qualified names.

seqname

The name (optionally schema-qualified) of a sequence to be created.

increment

The `INCREMENT` *increment* clause is optional. A positive value will make an ascending sequence, a negative one a descending sequence. The default value is one (1).

minvalue

The optional clause `MINVALUE` *minvalue* determines the minimum value a sequence can generate. The defaults are 1 and -2^63-1 for ascending and descending sequences, respectively.

maxvalue

The optional clause `MAXVALUE` *maxvalue* determines the maximum value for the sequence. The defaults are 2^63-1 and -1 for ascending and descending sequences, respectively.

start

The optional `START` *start* `clause` enables the sequence to begin anywhere. The default starting value is *minvalue* for ascending sequences and *maxvalue* for descending ones.

cache

The `CACHE` *cache* option enables sequence numbers to be preallocated and stored in memory for faster access. The minimum value is 1 (only one value can be generated at a time, i.e., no cache) and this is also the default.

CYCLE

The optional CYCLE keyword may be used to enable the sequence to wrap around when the *maxvalue* or *minvalue* has been reached by an ascending or descending sequence respectively. If the limit is reached, the next number generated will be the *minvalue* or *maxvalue*, respectively. Without CYCLE, after the limit is reached `nextval` calls will return an error.

Outputs

`CREATE SEQUENCE`

Message returned if the command is successful.

`ERROR: Relation '`*`seqname`*`' already exists`

If the sequence specified already exists.

`ERROR: DefineSequence: MINVALUE (`*`start`*`) can't be >= MAXVALUE (`*`max`*`)`

If the specified starting value is out of range.

`ERROR: DefineSequence: START value (`*`start`*`) can't be < MINVALUE (`*`min`*`)`

If the specified starting value is out of range.

`ERROR: DefineSequence: MINVALUE (`*`min`*`) can't be >= MAXVALUE (`*`max`*`)`

If the minimum and maximum values are inconsistent.

Description

`CREATE SEQUENCE` will enter a new sequence number generator into the current database. This involves creating and initializing a new single-row table with the name *`seqname`*. The generator will be owned by the user issuing the command.

If a schema name is given then the sequence is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`). TEMP sequences exist in a special schema, so a schema name may not be given when creating a TEMP sequence. The sequence name must be distinct from the name of any other sequence, table, index, or view in the same schema.

After a sequence is created, you use the functions `nextval`, `currval` and `setval` to operate on the sequence. These functions are documented in the *User's Guide*.

Although you cannot update a sequence directly, you can use a query like

```
SELECT * FROM seqname;
```

to examine the parameters and current state of a sequence. In particular, the `last_value` field of the sequence shows the last value allocated by any backend process. (Of course, this value may be obsolete by the time it's printed, if other processes are actively doing `nextval` calls.)

Caution

Unexpected results may be obtained if a *`cache`* setting greater than one is used for a sequence object that will be used concurrently by multiple backends. Each backend will allocate and cache successive sequence values during one access to the sequence object and increase the sequence object's `last_value` accordingly. Then, the next *`cache`*-1 uses of `nextval` within that backend simply return the preallocated values without touching the shared object. So, any numbers allocated but not used within a session will be lost when that session ends. Furthermore, although multiple backends are guaranteed to allocate distinct sequence values, the values may be generated out of sequence when all the backends are considered. (For example, with a *`cache`* setting of 10, backend A might reserve values 1..10 and return `nextval`=1, then backend B might reserve values 11..20 and return `nextval`=11 before backend A has generated `nextval`=2.) Thus, with a *`cache`* setting of one it is safe to assume that `nextval` values are generated sequentially; with a *`cache`* setting greater than

one you should only assume that the `nextval` values are all distinct, not that they are generated purely sequentially. Also, `last_value` will reflect the latest value reserved by any backend, whether or not it has yet been returned by `nextval`. Another consideration is that a `setval` executed on such a sequence will not be noticed by other backends until they have used up any preallocated values they have cached.

Notes

Use `DROP SEQUENCE` to remove a sequence.

Sequences are based on `bigint` arithmetic, so the range cannot exceed the range of an eight-byte integer (-9223372036854775808 to 9223372036854775807). On some older platforms, there may be no compiler support for eight-byte integers, in which case sequences use regular `integer` arithmetic (range -2147483648 to +2147483647).

When *`cache`* is greater than one, each backend uses its own cache to store preallocated numbers. Numbers that are cached but not used in the current session will be lost, resulting in “holes” in the sequence.

Usage

Create an ascending sequence called `serial`, starting at 101:

```
CREATE SEQUENCE serial START 101;
```

Select the next number from this sequence:

```
SELECT nextval('serial');

nextval
-------
    114
```

Use this sequence in an INSERT:

```
INSERT INTO distributors VALUES (nextval('serial'), 'nothing');
```

Update the sequence value after a COPY FROM:

```
BEGIN;
    COPY distributors FROM 'input_file';
    SELECT setval('serial', max(id)) FROM distributors;
END;
```

Compatibility

SQL92

`CREATE SEQUENCE` is a PostgreSQL language extension. There is no `CREATE SEQUENCE` statement in SQL92.

Name

CREATE TABLE — define a new table

Synopsis

```
CREATE [ [ LOCAL ] { TEMPORARY | TEMP } ] TABLE table_name (
    { column_name data_type [ DEFAULT default_expr ]
  [ column_constraint [, ... ] ]
    | table_constraint }  [, ... ]
)
[ INHERITS ( parent_table [, ... ] ) ]
[ WITH OIDS | WITHOUT OIDS ]

where column_constraint is:

[ CONSTRAINT constraint_name ]
{ NOT NULL | NULL | UNIQUE | PRIMARY KEY |
  CHECK (expression) |
  REFERENCES reftable [ ( refcolumn ) ] [ MATCH FULL | MATCH
 PARTIAL ]
    [ ON DELETE action ] [ ON UPDATE action ] }
[ DEFERRABLE | NOT DEFERRABLE ] [ INITIALLY DEFERRED | INITIALLY
 IMMEDIATE ]

and table_constraint is:

[ CONSTRAINT constraint_name ]
{ UNIQUE ( column_name [, ... ] ) |
  PRIMARY KEY ( column_name [, ... ] ) |
  CHECK ( expression ) |
  FOREIGN KEY ( column_name [, ... ] ) REFERENCES reftable
 [ ( refcolumn [, ... ] ) ]
    [ MATCH FULL | MATCH PARTIAL ] [ ON DELETE action ] [ ON
 UPDATE action ] }
[ DEFERRABLE | NOT DEFERRABLE ] [ INITIALLY DEFERRED | INITIALLY
 IMMEDIATE ]
```

Description

`CREATE TABLE` will create a new, initially empty table in the current database. The table will be owned by the user issuing the command.

If a schema name is given (for example, `CREATE TABLE myschema.mytable ...`) then the table is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`). TEMP tables exist in a special schema, so a schema name may not be given when creating a TEMP table. The table name must be distinct from the name of any other table, sequence, index, or view in the same schema.

`CREATE TABLE` also automatically creates a data type that represents the tuple type (structure type) corresponding to one row of the table. Therefore, tables cannot have the same name as any existing data type in the same schema.

A table cannot have more than 1600 columns. (In practice, the effective limit is lower because of tuple-length constraints).

The optional constraint clauses specify constraints (or tests) that new or updated rows must satisfy for an insert or update operation to succeed. A constraint is a named rule: an SQL object which helps define

valid sets of values by putting limits on the results of insert, update, or delete operations performed on a table.

There are two ways to define constraints: table constraints and column constraints. A column constraint is defined as part of a column definition. A table constraint definition is not tied to a particular column, and it can encompass more than one column. Every column constraint can also be written as a table constraint; a column constraint is only a notational convenience if the constraint only affects one column.

Parameters

`[LOCAL] TEMPORARY` or `[LOCAL] TEMP`

If specified, the table is created as a temporary table. Temporary tables are automatically dropped at the end of a session. Existing permanent tables with the same name are not visible to the current session while the temporary table exists, unless they are referenced with schema-qualified names. Any indexes created on a temporary table are automatically temporary as well.

The `LOCAL` word is optional. But see under Compatibility.

`table_name`

The name (optionally schema-qualified) of the table to be created.

`column_name`

The name of a column to be created in the new table.

`data_type`

The data type of the column. This may include array specifiers. Refer to the *User's Guide* for further information about data types and arrays.

`DEFAULT` *`default_expr`*

The `DEFAULT` clause assigns a default data value for the column whose column definition it appears within. The value is any variable-free expression (subselects and cross-references to other columns in the current table are not allowed). The data type of the default expression must match the data type of the column.

The default expression will be used in any insert operation that does not specify a value for the column. If there is no default for a column, then the default is NULL.

`INHERITS ( parent_table [, ... ] )`

The optional `INHERITS` clause specifies a list of tables from which the new table automatically inherits all columns. If the same column name exists in more than one parent table, an error is reported unless the data types of the columns match in each of the parent tables. If there is no conflict, then the duplicate columns are merged to form a single column in the new table. If the column name list of the new table contains a column that is also inherited, the data type must likewise match the inherited column(s), and the column definitions are merged into one. However, inherited and new column declarations of the same name need not specify identical constraints: all constraints provided from any declaration are merged together and all are applied to the new table. If the new table explicitly specifies a default value for the column, this default overrides any defaults from inherited declarations of the column. Otherwise, any parents that specify default values for the column must all specify the same default, or an error will be reported.

`WITH OIDS` or `WITHOUT OIDS`

This optional clause specifies whether rows of the new table should have OIDs (object identifiers) assigned to them. The default is to have OIDs. (If the new table inherits from any tables that have OIDs, then `WITH OIDS` is forced even if the command says `WITHOUT OIDS`.)

Specifying WITHOUT OIDS allows the user to suppress generation of OIDs for rows of a table. This may be worthwhile for large tables, since it will reduce OID consumption and thereby postpone wraparound of the 32-bit OID counter. Once the counter wraps around, uniqueness of OIDs can no longer be assumed, which considerably reduces their usefulness.

CONSTRAINT *constraint_name*

An optional name for a column or table constraint. If not specified, the system generates a name.

NOT NULL

The column is not allowed to contain NULL values.

NULL

The column is allowed to contain NULL values. This is the default.

This clause is only available for compatibility with non-standard SQL databases. Its use is discouraged in new applications.

UNIQUE (column constraint)
UNIQUE (*column_name* [, ...]) (table constraint)

The UNIQUE constraint specifies a rule that a group of one or more distinct columns of a table may contain only unique values. The behavior of the unique table constraint is the same as that for column constraints, with the additional capability to span multiple columns.

For the purpose of a unique constraint, NULL values are not considered equal.

Each unique table constraint must name a set of columns that is different from the set of columns named by any other unique or primary key constraint defined for the table. (Otherwise it would just be the same constraint listed twice.)

PRIMARY KEY (column constraint)
PRIMARY KEY (*column_name* [, ...]) (table constraint)

The primary key constraint specifies that a column or columns of a table may contain only unique (non-duplicate), non-NULL values. Technically, PRIMARY KEY is merely a combination of UNIQUE and NOT NULL, but identifying a set of columns as primary key also provides meta-data about the design of the schema, as a primary key implies that other tables may rely on this set of columns as a unique identifier for rows.

Only one primary key can be specified for a table, whether as a column constraint or a table constraint.

The primary key constraint should name a set of columns that is different from other sets of columns named by any unique constraint defined for the same table.

CHECK (*expression*)

CHECK clauses specify integrity constraints or tests which new or updated rows must satisfy for an insert or update operation to succeed. Each constraint must be an expression producing a Boolean result. A condition appearing within a column definition should reference that column's value only, while a condition appearing as a table constraint may reference multiple columns.

Currently, CHECK expressions cannot contain subselects nor refer to variables other than columns of the current row.

`REFERENCES` *`reftable`* `[ ( ` *`refcolumn`* ` ) ] [ MATCH` *`matchtype`* `] [ ON DELETE` *`action`* `] [ ON UPDATE` *`action`* `]` (column constraint)
`FOREIGN KEY ( ` *`column`* `[, ... ] ) REFERENCES` *`reftable`* `[ ( ` *`refcolumn`* `[, ... ] ) ] [ MATCH` *`matchtype`* `] [ ON DELETE` *`action`* `] [ ON UPDATE` *`action`* `]` (table constraint)

The `REFERENCES` column constraint specifies that a group of one or more columns of the new table must only contain values which match against values in the referenced column(s) *`refcolumn`* of the referenced table *`reftable`*. If *`refcolumn`* is omitted, the primary key of the *`reftable`* is used. The referenced columns must be the columns of a unique or primary key constraint in the referenced table.

A value added to these columns is matched against the values of the referenced table and referenced columns using the given match type. There are three match types: `MATCH FULL`, `MATCH PARTIAL`, and a default match type if none is specified. `MATCH FULL` will not allow one column of a multicolumn foreign key to be NULL unless all foreign key columns are NULL. The default match type allows some foreign key columns to be NULL while other parts of the foreign key are not NULL. `MATCH PARTIAL` is not yet implemented.

In addition, when the data in the referenced columns is changed, certain actions are performed on the data in this table's columns. The `ON DELETE` clause specifies the action to do when a referenced row in the referenced table is being deleted. Likewise, the `ON UPDATE` clause specifies the action to perform when a referenced column in the referenced table is being updated to a new value. If the row is updated, but the referenced column is not actually changed, no action is done. There are the following possible actions for each clause:

`NO ACTION`

Produce an error indicating that the deletion or update would create a foreign key constraint violation. This is the default action.

`RESTRICT`

Same as `NO ACTION`.

`CASCADE`

Delete any rows referencing the deleted row, or update the value of the referencing column to the new value of the referenced column, respectively.

`SET NULL`

Set the referencing column values to NULL.

`SET DEFAULT`

Set the referencing column values to their default value.

If primary key column is updated frequently, it may be wise to add an index to the `REFERENCES` column so that `NO ACTION` and `CASCADE` actions associated with the `REFERENCES` column can be more efficiently performed.

`DEFERRABLE` or `NOT DEFERRABLE`

This controls whether the constraint can be deferred. A constraint that is not deferrable will be checked immediately after every command. Checking of constraints that are deferrable may be postponed until the end of the transaction (using the SET CONSTRAINTS command). `NOT DEFERRABLE` is the default. Only foreign key constraints currently accept this clause. All other constraint types are not deferrable.

`INITIALLY IMMEDIATE` or `INITIALLY DEFERRED`

If a constraint is deferrable, this clause specifies the default time to check the constraint. If the constraint is `INITIALLY IMMEDIATE`, it is checked after each statement. This is the default. If the constraint is `INITIALLY DEFERRED`, it is checked only at the end of the transaction. The constraint check time can be altered with the SET CONSTRAINTS command.

Diagnostics

`CREATE TABLE`

Message returned if table is successfully created.

`ERROR`

Message returned if table creation failed. This is usually accompanied by some descriptive text, such as: `ERROR: Relation 'table' already exists`, which occurs at run time if the table specified already exists in the database.

Notes

- Whenever an application makes use of OIDs to identify specific rows of a table, it is recommended to create a unique constraint on the `oid` column of that table, to ensure that OIDs in the table will indeed uniquely identify rows even after counter wraparound. Avoid assuming that OIDs are unique across tables; if you need a database-wide unique identifier, use the combination of `tableoid` and row OID for the purpose. (It is likely that future PostgreSQL releases will use a separate OID counter for each table, so that it will be *necessary*, not optional, to include `tableoid` to have a unique identifier database-wide.)

  ## Tip

  The use of `WITHOUT OIDS` is not recommended for tables with no primary key, since without either an OID or a unique data key, it is difficult to identify specific rows.

- PostgreSQL automatically creates an index for each unique constraint and primary key constraint to enforce the uniqueness. Thus, it is not necessary to create an explicit index for primary key columns. (See CREATE INDEX for more information.)

- The SQL92 standard says that `CHECK` column constraints may only refer to the column they apply to; only `CHECK` table constraints may refer to multiple columns. PostgreSQL does not enforce this restriction; it treats column and table check constraints alike.

- Unique constraints and primary keys are not inherited in the current implementation. This makes the combination of inheritance and unique constraints rather dysfunctional.

Examples

Create table `films` and table `distributors`:

```
CREATE TABLE films (
    code        CHARACTER(5) CONSTRAINT firstkey PRIMARY KEY,
    title       CHARACTER VARYING(40) NOT NULL,
    did         DECIMAL(3) NOT NULL,
    date_prod   DATE,
    kind        CHAR(10),
    len         INTERVAL HOUR TO MINUTE
);
```

```
CREATE TABLE distributors (
     did    DECIMAL(3) PRIMARY KEY DEFAULT NEXTVAL('serial'),
     name   VARCHAR(40) NOT NULL CHECK (name <> '')
);
```

Create a table with a 2-dimensional array:

```
CREATE TABLE array (
    vector  INT[][]
);
```

Define a unique table constraint for the table films. Unique table constraints can be defined on one or more columns of the table:

```
CREATE TABLE films (
    code        CHAR(5),
    title       VARCHAR(40),
    did         DECIMAL(3),
    date_prod   DATE,
    kind        VARCHAR(10),
    len         INTERVAL HOUR TO MINUTE,
    CONSTRAINT production UNIQUE(date_prod)
);
```

Define a check column constraint:

```
CREATE TABLE distributors (
    did     DECIMAL(3) CHECK (did > 100),
    name    VARCHAR(40)
);
```

Define a check table constraint:

```
CREATE TABLE distributors (
    did     DECIMAL(3),
    name    VARCHAR(40)
    CONSTRAINT con1 CHECK (did > 100 AND name <> '')
);
```

Define a primary key table constraint for the table `films`. Primary key table constraints can be defined on one or more columns of the table.

```
CREATE TABLE films (
    code        CHAR(5),
    title       VARCHAR(40),
    did         DECIMAL(3),
    date_prod   DATE,
    kind        VARCHAR(10),
    len         INTERVAL HOUR TO MINUTE,
    CONSTRAINT code_title PRIMARY KEY(code,title)
);
```

Define a primary key constraint for table `distributors`. The following two examples are equivalent, the first using the table constraint syntax, the second the column constraint notation.

```
CREATE TABLE distributors (
    did     DECIMAL(3),
    name    CHAR VARYING(40),
    PRIMARY KEY(did)
```

```
);

CREATE TABLE distributors (
    did     DECIMAL(3) PRIMARY KEY,
    name    VARCHAR(40)
);
```

This assigns a literal constant default value for the column `name`, and arranges for the default value of column `did` to be generated by selecting the next value of a sequence object. The default value of `modtime` will be the time at which the row is inserted.

```
CREATE TABLE distributors (
    name      VARCHAR(40) DEFAULT 'luso films',
    did       INTEGER DEFAULT NEXTVAL('distributors_serial'),
    modtime   TIMESTAMP DEFAULT CURRENT_TIMESTAMP
);
```

Define two `NOT NULL` column constraints on the table `distributors`, one of which is explicitly given a name:

```
CREATE TABLE distributors (
    did     DECIMAL(3) CONSTRAINT no_null NOT NULL,
    name    VARCHAR(40) NOT NULL
);
```

Define a unique constraint for the `name` column:

```
CREATE TABLE distributors (
    did     DECIMAL(3),
    name    VARCHAR(40) UNIQUE
);
```

The above is equivalent to the following specified as a table constraint:

```
CREATE TABLE distributors (
    did     DECIMAL(3),
    name    VARCHAR(40),
    UNIQUE(name)
);
```

Compatibility

The `CREATE TABLE` conforms to SQL92 Intermediate and to a subset of SQL99, with exceptions listed below and in the descriptions above.

Temporary Tables

In addition to the local temporary table, SQL92 also defines a `CREATE GLOBAL TEMPORARY TABLE` statement. Global temporary tables are also visible to other sessions.

For temporary tables, there is an optional `ON COMMIT` clause:

```
CREATE { GLOBAL | LOCAL } TEMPORARY TABLE table ( ... ) [ ON COMMIT
 { DELETE | PRESERVE } ROWS ]
```

The `ON COMMIT` clause specifies whether or not the temporary table should be emptied of rows whenever `COMMIT` is executed. If the `ON COMMIT` clause is omitted, SQL92 specifies that the default is `ON COMMIT DELETE ROWS`. However, the behavior of PostgreSQL is always like `ON COMMIT PRESERVE ROWS`.

`NULL` "Constraint"

The `NULL` "constraint" (actually a non-constraint) is a PostgreSQL extension to SQL92 that is included for compatibility with some other RDBMS (and for symmetry with the `NOT NULL` constraint). Since it is the default for any column, its presence is simply noise.

Assertions

An assertion is a special type of integrity constraint and shares the same namespace as other constraints. However, an assertion is not necessarily dependent on one particular table as constraints are, so SQL92 provides the `CREATE ASSERTION` statement as an alternate method for defining a constraint:

```
CREATE ASSERTION name CHECK ( condition )
```

PostgreSQL does not implement assertions at present.

Inheritance

Multiple inheritance via the `INHERITS` clause is a PostgreSQL language extension. SQL99 (but not SQL92) defines single inheritance using a different syntax and different semantics. SQL99-style inheritance is not yet supported by PostgreSQL.

Object IDs

The PostgreSQL concept of OIDs is not standard.

See Also

ALTER TABLE, DROP TABLE

Name

CREATE TABLE AS — create a new table from the results of a query

Synopsis

```
CREATE [ [ LOCAL ] { TEMPORARY | TEMP } ] TABLE table_name
 [ (column_name [, ...] ) ]
    AS query
```

Description

`CREATE TABLE AS` creates a table and fills it with data computed by a `SELECT` command. The table columns have the names and data types associated with the output columns of the `SELECT` (except that you can override the column names by giving an explicit list of new column names).

`CREATE TABLE AS` bears some resemblance to creating a view, but it is really quite different: it creates a new table and evaluates the query just once to fill the new table initially. The new table will not track subsequent changes to the source tables of the query. In contrast, a view re-evaluates its defining `SELECT` statement whenever it is queried.

Parameters

`[LOCAL] TEMPORARY` or `[LOCAL] TEMP`

If specified, the table is created as a temporary table. Refer to CREATE TABLE for details.

`table_name`

The name (optionally schema-qualified) of the table to be created.

`column_name`

The name of a column in the new table. Multiple column names can be specified using a comma-delimited list of column names. If column names are not provided, they are taken from the output column names of the query.

`query`

A query statement (that is, a `SELECT` command). Refer to SELECT for a description of the allowed syntax.

Diagnostics

Refer to CREATE TABLE and SELECT for a summary of possible output messages.

Notes

This command is functionally equivalent to SELECT INTO, but it is preferred since it is less likely to be confused with other uses of the `SELECT ... INTO` syntax.

Compatibility

This command is modeled after an Oracle feature. There is no command with equivalent functionality in SQL92 or SQL99. However, a combination of `CREATE TABLE` and `INSERT ... SELECT` can accomplish the same thing with little more effort.

History

The `CREATE TABLE AS` command has been available since PostgreSQL 6.3.

See Also

CREATE TABLE, CREATE VIEW, SELECT, SELECT INTO

Name

CREATE TRIGGER — define a new trigger

Synopsis

<refsynopsisdivinfo>2000-03-25</refsynopsisdivinfo>

```
CREATE TRIGGER name { BEFORE | AFTER } { event [OR ...] }
    ON table FOR EACH { ROW | STATEMENT }
    EXECUTE PROCEDURE func ( arguments )
```

Inputs

name

The name to give the new trigger. This must be distinct from the name of any other trigger for the same table.

event

One of INSERT, DELETE or UPDATE.

table

The name (optionally schema-qualified) of the table the trigger is for.

func

A user-supplied function that is declared as taking no arguments and returning type `trigger`.

arguments

An optional comma-separated list of arguments to be provided to the function when the trigger is executed, along with the standard trigger data such as old and new tuple contents. The arguments are literal string constants. Simple names and numeric constants may be written here too, but they will all be converted to strings.

Outputs

`CREATE TRIGGER`

This message is returned if the trigger is successfully created.

Description

`CREATE TRIGGER` will enter a new trigger into the current data base. The trigger will be associated with the relation *table* and will execute the specified function *func*.

The trigger can be specified to fire either before BEFORE the operation is attempted on a tuple (before constraints are checked and the `INSERT`, `UPDATE` or `DELETE` is attempted) or AFTER the operation has been attempted (e.g., after constraints are checked and the `INSERT`, `UPDATE` or `DELETE` has completed). If the trigger fires before the event, the trigger may skip the operation for the current tuple, or change the tuple being inserted (for `INSERT` and `UPDATE` operations only). If the trigger fires after the event, all changes, including the last insertion, update, or deletion, are "visible" to the trigger.

If multiple triggers of the same kind are defined for the same event, they will be fired in alphabetical order by name.

`SELECT` does not modify any rows so you can not create `SELECT` triggers. Rules and views are more appropriate in such cases.

Refer to the chapters on SPI and Triggers in the *PostgreSQL Programmer's Guide* for more information.

Notes

To create a trigger on a table, the user must have the `TRIGGER` privilege on the table.

In PostgreSQL versions before 7.3, it was necessary to declare trigger functions as returning the placeholder type `opaque`, rather than `trigger`. To support loading of old dump files, `CREATE TRIGGER` will accept a function declared as returning `opaque`, but it will issue a NOTICE and change the function's declared return type to `trigger`.

As of the current release, `STATEMENT` triggers are not implemented.

Refer to the DROP TRIGGER command for information on how to remove triggers.

Examples

Check if the specified distributor code exists in the distributors table before appending or updating a row in the table films:

```
CREATE TRIGGER if_dist_exists
    BEFORE INSERT OR UPDATE ON films FOR EACH ROW
    EXECUTE PROCEDURE check_primary_key ('did', 'distributors',
 'did');
```

Before cancelling a distributor or updating its code, remove every reference to the table films:

```
CREATE TRIGGER if_film_exists
    BEFORE DELETE OR UPDATE ON distributors FOR EACH ROW
    EXECUTE PROCEDURE check_foreign_key (1, 'CASCADE', 'did',
 'films', 'did');
```

The second example can also be done by using a foreign key, constraint as in:

```
CREATE TABLE distributors (
    did      DECIMAL(3),
    name     VARCHAR(40),
    CONSTRAINT if_film_exists
    FOREIGN KEY(did) REFERENCES films
    ON UPDATE CASCADE ON DELETE CASCADE
);
```

Compatibility

SQL92

There is no `CREATE TRIGGER` statement in SQL92.

SQL99

The `CREATE TRIGGER` statement in PostgreSQL implements a subset of the SQL99 standard. The following functionality is missing:

- SQL99 allows triggers to fire on updates to specific columns (e.g., `AFTER UPDATE OF col1, col2`).
- SQL99 allows you to define aliases for the “old” and “new” rows or tables for use in the definition of the triggered action (e.g., `CREATE TRIGGER ... ON tablename`

`REFERENCING OLD ROW AS somename NEW ROW AS othername ...`). Since PostgreSQL allows trigger procedures to be written in any number of user-defined languages, access to the data is handled in a language-specific way.

- PostgreSQL only has row-level triggers, no statement-level triggers.
- PostgreSQL only allows the execution of a stored procedure for the triggered action. SQL99 allows the execution of a number of other SQL commands, such as `CREATE TABLE` as triggered action. This limitation is not hard to work around by creating a stored procedure that executes these commands.

SQL99 specifies that multiple triggers should be fired in time-of-creation order. PostgreSQL uses name order, which was judged more convenient to work with.

See Also

CREATE FUNCTION, ALTER TRIGGER , DROP TRIGGER, *PostgreSQL Programmer's Guide*

Name

CREATE TYPE — define a new data type

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
CREATE TYPE typename ( INPUT = input_function, OUTPUT
 = output_function
      , INTERNALLENGTH = { internallength | VARIABLE }
    [ , DEFAULT = default ]
    [ , ELEMENT = element ] [ , DELIMITER = delimiter ]
    [ , PASSEDBYVALUE ]
    [ , ALIGNMENT = alignment ]
    [ , STORAGE = storage ]
)

CREATE TYPE typename AS
    ( column_name data_type [, ... ] )
```

Inputs

typename

The name (optionally schema-qualified) of a type to be created.

internallength

A literal value, which specifies the internal length of the new type.

input_function

The name of a function, created by `CREATE FUNCTION`, which converts data from its external form to the type's internal form.

output_function

The name of a function, created by `CREATE FUNCTION`, which converts data from its internal form to a form suitable for display.

element

The type being created is an array; this specifies the type of the array elements.

delimiter

The delimiter character to be used between values in arrays made of this type.

default

The default value for the data type. Usually this is omitted, so that the default is NULL.

alignment

Storage alignment requirement of the data type. If specified, must be `char`, `int2`, `int4`, or `double`; the default is `int4`.

storage

Storage technique for the data type. If specified, must be `plain`, `external`, `extended`, or `main`; the default is `plain`.

column_name

The name of a column of the composite type.

data_type

The name of an existing data type.

Outputs

CREATE TYPE

Message returned if the type is successfully created.

Description

CREATE TYPE allows the user to register a new data type with PostgreSQL for use in the current data base. The user who defines a type becomes its owner.

If a schema name is given then the type is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see CURRENT_SCHEMA()). The type name must be distinct from the name of any existing type or domain in the same schema. (Because tables have associated data types, type names also must not conflict with table names in the same schema.)

Base Types

The first form of CREATE TYPE creates a new base type (scalar type). It requires the registration of two functions (using CREATE FUNCTION) before defining the type. The representation of a new base type is determined by *input_function*, which converts the type's external representation to an internal representation usable by the operators and functions defined for the type. Naturally, *output_function* performs the reverse transformation. The input function may be declared as taking one argument of type cstring, or as taking three arguments of types cstring, OID, int4. (The first argument is the input text as a C string, the second argument is the element type in case this is an array type, and the third is the typmod of the destination column, if known.) It should return a value of the data type itself. The output function may be declared as taking one argument of the new data type, or as taking two arguments of which the second is type OID. (The second argument is again the array element type for array types.) The output function should return type cstring.

You should at this point be wondering how the input and output functions can be declared to have results or inputs of the new type, when they have to be created before the new type can be created. The answer is that the input function must be created first, then the output function, then the data type. PostgreSQL will first see the name of the new data type as the return type of the input function. It will create a “shell” type, which is simply a placeholder entry in pg_type, and link the input function definition to the shell type. Similarly the output function will be linked to the (now already existing) shell type. Finally, CREATE TYPE replaces the shell entry with a complete type definition, and the new type can be used.

Note

In PostgreSQL versions before 7.3, it was customary to avoid creating a shell type by replacing the functions' forward references to the type name with the placeholder pseudo-type OPAQUE. The cstring inputs and results also had to be declared as OPAQUE before 7.3. To support loading of old dump files, CREATE TYPE will accept functions declared using opaque, but it will issue a NOTICE and change the function's declaration to use the correct types.

New base data types can be fixed length, in which case *internallength* is a positive integer, or variable length, indicated by setting *internallength* to VARIABLE. (Internally, this is

represented by setting `typlen` to -1.) The internal representation of all variable-length types must start with an integer giving the total length of this value of the type.

To indicate that a type is an array, specify the type of the array elements using the `ELEMENT` keyword. For example, to define an array of 4-byte integers ("int4"), specify

```
ELEMENT = int4
```

More details about array types appear below.

To indicate the delimiter to be used between values in the external representation of arrays of this type, *`delimiter`* can be set to a specific character. The default delimiter is the comma (`,`). Note that the delimiter is associated with the array element type, not the array type itself.

A default value may be specified, in case a user wants columns of the data type to default to something other than NULL. Specify the default with the `DEFAULT` keyword. (Such a default may be overridden by an explicit `DEFAULT` clause attached to a particular column.)

The optional flag, `PASSEDBYVALUE`, indicates that values of this data type are passed by value rather than by reference. Note that you may not pass by value types whose internal representation is longer than the width of the `Datum` type (four bytes on most machines, eight bytes on a few).

The *`alignment`* keyword specifies the storage alignment required for the data type. The allowed values equate to alignment on 1, 2, 4, or 8 byte boundaries. Note that variable-length types must have an alignment of at least 4, since they necessarily contain an `int4` as their first component.

The *`storage`* keyword allows selection of storage strategies for variable-length data types (only `plain` is allowed for fixed-length types). `plain` disables TOAST for the data type: it will always be stored in-line and not compressed. `extended` gives full TOAST capability: the system will first try to compress a long data value, and will move the value out of the main table row if it's still too long. `external` allows the value to be moved out of the main table, but the system will not try to compress it. `main` allows compression, but discourages moving the value out of the main table. (Data items with this storage method may still be moved out of the main table if there is no other way to make a row fit, but they will be kept in the main table preferentially over `extended` and `external` items.)

Composite Types

The second form of `CREATE TYPE` creates a composite type. The composite type is specified by a list of column names and data types. This is essentially the same as the row type of a table, but using `CREATE TYPE` avoids the need to create an actual table when all that is wanted is to define a type. A stand-alone composite type is useful as the return type of a function.

Array Types

Whenever a user-defined base data type is created, PostgreSQL automatically creates an associated array type, whose name consists of the base type's name prepended with an underscore. The parser understands this naming convention, and translates requests for columns of type `foo[]` into requests for type `_foo`. The implicitly-created array type is variable length and uses the built-in input and output functions `array_in` and `array_out`.

You might reasonably ask “why is there an `ELEMENT` option, if the system makes the correct array type automatically?” The only case where it's useful to use `ELEMENT` is when you are making a fixed-length type that happens to be internally an array of N identical things, and you want to allow the N things to be accessed directly by subscripting, in addition to whatever operations you plan to provide for the type as a whole. For example, type `name` allows its constituent `chars` to be accessed this way. A 2-D `point` type could allow its two component floats to be accessed like `point[0]` and `point[1]`. Note that this facility only works for fixed-length types whose internal form is exactly a sequence of N identical fixed-length fields. A subscriptable variable-length type must have the generalized internal representation used by `array_in` and `array_out`. For historical reasons (i.e., this is clearly wrong

but it's far too late to change it), subscripting of fixed-length array types starts from zero, rather than from one as for variable-length arrays.

Notes

User-defined type names cannot begin with the underscore character ("_") and can only be 62 characters long (or in general `NAMEDATALEN-2`, rather than the `NAMEDATALEN-1` characters allowed for other names). Type names beginning with underscore are reserved for internally-created array type names.

Examples

This example creates the `box` data type and then uses the type in a table definition:

```
CREATE TYPE box (INTERNALLENGTH = 16,
    INPUT = my_procedure_1, OUTPUT = my_procedure_2);
CREATE TABLE myboxes (id INT4, description box);
```

If `box`'s internal structure were an array of four `float4`s, we might instead say

```
CREATE TYPE box (INTERNALLENGTH = 16,
    INPUT = my_procedure_1, OUTPUT = my_procedure_2,
    ELEMENT = float4);
```

which would allow a box value's component floats to be accessed by subscripting. Otherwise the type behaves the same as before.

This example creates a large object type and uses it in a table definition:

```
CREATE TYPE bigobj (INPUT = lo_filein, OUTPUT = lo_fileout,
    INTERNALLENGTH = VARIABLE);
CREATE TABLE big_objs (id int4, obj bigobj);
```

This example creates a composite type and uses it in a table function definition:

```
CREATE TYPE compfoo AS (f1 int, f2 text);
CREATE FUNCTION getfoo() RETURNS SETOF compfoo AS 'SELECT fooid,
 fooname FROM foo' LANGUAGE SQL;
```

Compatibility

This `CREATE TYPE` command is a PostgreSQL extension. There is a `CREATE TYPE` statement in SQL99 that is rather different in detail.

See Also

CREATE FUNCTION, DROP TYPE, *PostgreSQL Programmer's Guide*

Name

CREATE USER — define a new database user account

Synopsis

```
CREATE USER username [ [ WITH ] option [ ... ] ]

where option can be:

      SYSID uid
    | [ ENCRYPTED | UNENCRYPTED ] PASSWORD 'password'
    | CREATEDB | NOCREATEDB
    | CREATEUSER | NOCREATEUSER
    | IN GROUP groupname [, ...]
    | VALID UNTIL 'abstime'
```

Description

`CREATE USER` will add a new user to an instance of PostgreSQL. Refer to the *Administrator's Guide* for information about managing users and authentication. You must be a database superuser to use this command.

Parameters

username

The name of the user.

uid

The `SYSID` clause can be used to choose the PostgreSQL user ID of the user that is being created. It is not at all necessary that those match the Unix user IDs, but some people choose to keep the numbers the same.

If this is not specified, the highest assigned user ID plus one (with a minimum of 100) will be used as default.

password

Sets the user's password. If you do not plan to use password authentication you can omit this option, but the user won't be able to connect to a password-authenticated server. The password can be set or changed later, using ALTER USER.

`ENCRYPTED`
`UNENCRYPTED`

These keywords control whether the password is stored encrypted in `pg_shadow`. (If neither is specified, the default behavior is determined by the `PASSWORD_ENCRYPTION` server parameter.) If the presented string is already in MD5-encrypted format, then it is stored as-is, regardless of whether `ENCRYPTED` or `UNENCRYPTED` is specified. This allows reloading of encrypted passwords during dump/restore.

See the chapter on client authentication in the *Administrator's Guide* for details on how to set up authentication mechanisms. Note that older clients may lack support for the MD5 authentication mechanism that is needed to work with passwords that are stored encrypted.

`CREATEDB`
`NOCREATEDB`

These clauses define a user's ability to create databases. If `CREATEDB` is specified, the user being defined will be allowed to create his own databases. Using `NOCREATEDB` will deny a user the ability to create databases. If this clause is omitted, `NOCREATEDB` is used by default.

`CREATEUSER`
`NOCREATEUSER`

These clauses determine whether a user will be permitted to create new users himself. This option will also make the user a superuser who can override all access restrictions. Omitting this clause will set the user's value of this attribute to be `NOCREATEUSER`.

`groupname`

A name of a group into which to insert the user as a new member. Multiple group names may be listed.

`abstime`

The `VALID UNTIL` clause sets an absolute time after which the user's password is no longer valid. If this clause is omitted the login will be valid for all time.

Diagnostics

`CREATE USER`

Message returned if the command completes successfully.

Notes

Use ALTER USER to change the attributes of a user, and DROP USER to remove a user. Use ALTER GROUP to add the user to groups or remove the user from groups. PostgreSQL includes a program createuser that has the same functionality as this command (in fact, it calls this command) but can be run from the command shell.

Examples

Create a user with no password:

```
CREATE USER jonathan;
```

Create a user with a password:

```
CREATE USER davide WITH PASSWORD 'jw8s0F4';
```

Create a user with a password, whose account is valid until the end of 2001. Note that after one second has ticked in 2002, the account is not valid:

```
CREATE USER miriam WITH PASSWORD 'jw8s0F4' VALID UNTIL 'Jan 1
 2002';
```

Create an account where the user can create databases:

```
CREATE USER manuel WITH PASSWORD 'jw8s0F4' CREATEDB;
```

Compatibility

The `CREATE USER` statement is a PostgreSQL extension. The SQL standard leaves the definition of users to the implementation.

See Also

ALTER USER, DROP USER, createuser

Name

CREATE VIEW — define a new view

Synopsis

<refsynopsisdivinfo>2000-03-25</refsynopsisdivinfo>

```
CREATE [ OR REPLACE ] VIEW view [ ( column name list ) ] AS
 SELECT query
```

Inputs

view

The name (optionally schema-qualified) of a view to be created.

column name list

An optional list of names to be used for columns of the view. If given, these names override the column names that would be deduced from the SQL query.

query

An SQL query (that is, a SELECT statement) which will provide the columns and rows of the view.

Refer to SELECT for more information about valid arguments.

Outputs

CREATE VIEW

The message returned if the view is successfully created.

ERROR: Relation '*view*' already exists

This error occurs if the view specified already exists in the database.

WARNING: Attribute '*column*' has an unknown type

The view will be created having a column with an unknown type if you do not specify it. For example, the following command gives a warning:

```
CREATE VIEW vista AS SELECT 'Hello World'
```

whereas this command does not:

```
CREATE VIEW vista AS SELECT text 'Hello World'
```

Description

CREATE VIEW defines a view of a query. The view is not physically materialized. Instead, a query rewrite rule (an ON SELECT rule) is automatically generated to support SELECT operations on views.

CREATE OR REPLACE VIEW is similar, but if a view of the same name already exists, it is replaced. You can only replace a view with a new query that generates the identical set of columns (i.e., same column names and data types).

If a schema name is given (for example, `CREATE VIEW myschema.myview ...`) then the view is created in the specified schema. Otherwise it is created in the current schema (the one at the front of the search path; see `CURRENT_SCHEMA()`). The view name must be distinct from the name of any other view, table, sequence, or index in the same schema.

Notes

Currently, views are read only: the system will not allow an insert, update, or delete on a view. You can get the effect of an updatable view by creating rules that rewrite inserts, etc. on the view into appropriate actions on other tables. For more information see CREATE RULE.

Use the `DROP VIEW` statement to drop views.

Usage

Create a view consisting of all Comedy films:

```
CREATE VIEW kinds AS
    SELECT *
    FROM films
    WHERE kind = 'Comedy';

SELECT * FROM kinds;

 code  |           title           | did | date_prod  |  kind  |
 len
-------+---------------------------+-----+------------+--------
+-------
 UA502 | Bananas                   | 105 | 1971-07-13 | Comedy |
 01:22
 C_701 | There's a Girl in my Soup | 107 | 1970-06-11 | Comedy |
 01:36
(2 rows)
```

Compatibility

SQL92

SQL92 specifies some additional capabilities for the `CREATE VIEW` statement:

```
CREATE VIEW view [ column [, ...] ]
    AS SELECT expression [ AS colname ] [, ...]
    FROM table [ WHERE condition ]
    [ WITH [ CASCADE | LOCAL ] CHECK OPTION ]
```

The optional clauses for the full SQL92 command are:

CHECK OPTION

This option is to do with updatable views. All `INSERT` and `UPDATE` commands on the view will be checked to ensure data satisfy the view-defining condition. If they do not, the update will be rejected.

LOCAL

Check for integrity on this view.

CASCADE

Check for integrity on this view and on any dependent view. CASCADE is assumed if neither CASCADE nor LOCAL is specified.

`CREATE OR REPLACE VIEW` is a PostgreSQL language extension.

Name

DEALLOCATE — remove a prepared query

Synopsis

<refsynopsisdivinfo>2002-08-12</refsynopsisdivinfo>

```
DEALLOCATE [ PREPARE ] plan_name
```

Inputs

PREPARE

This keyword is ignored.

plan_name

The name of the prepared query to remove.

Outputs

DEALLOCATE

The prepared query was removed successfully.

Description

DEALLOCATE is used to remove a previously prepared query. If you do not explicitly DEALLOCATE a prepared query, it is removed when the session ends.

For more information on prepared queries, see PREPARE.

Compatibility

SQL92

SQL92 includes a DEALLOCATE statement, but it is only for use in embedded SQL clients.

Name

DECLARE — define a cursor

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DECLARE cursorname [ BINARY ] [ INSENSITIVE ] [ SCROLL ]
    CURSOR FOR query
    [ FOR { READ ONLY | UPDATE [ OF column [, ...] ] ]
```

Inputs

cursorname

The name of the cursor to be used in subsequent FETCH operations.

BINARY

Causes the cursor to fetch data in binary rather than in text format.

INSENSITIVE

SQL92 keyword indicating that data retrieved from the cursor should be unaffected by updates from other processes or cursors. Since cursor operations occur within transactions in PostgreSQL this is always the case. This keyword has no effect.

SCROLL

SQL92 keyword indicating that data may be retrieved in multiple rows per FETCH operation. Since this is allowed at all times by PostgreSQL this keyword has no effect.

query

An SQL query which will provide the rows to be governed by the cursor. Refer to the SELECT statement for further information about valid arguments.

READ ONLY

SQL92 keyword indicating that the cursor will be used in a read only mode. Since this is the only cursor access mode available in PostgreSQL this keyword has no effect.

UPDATE

SQL92 keyword indicating that the cursor will be used to update tables. Since cursor updates are not currently supported in PostgreSQL this keyword provokes an informational error message.

column

Column(s) to be updated. Since cursor updates are not currently supported in PostgreSQL the UPDATE clause provokes an informational error message.

Outputs

DECLARE CURSOR

The message returned if the SELECT is run successfully.

`WARNING: Closing pre-existing portal "`*`cursorname`*`"`

This message is reported if the same cursor name was already declared in the current transaction block. The previous definition is discarded.

`ERROR: DECLARE CURSOR may only be used in begin/end transaction blocks`

This error occurs if the cursor is not declared within a transaction block.

Description

`DECLARE` allows a user to create cursors, which can be used to retrieve a small number of rows at a time out of a larger query. Cursors can return data either in text or in binary format using FETCH.

Normal cursors return data in text format, either ASCII or another encoding scheme depending on how the PostgreSQL backend was built. Since data is stored natively in binary format, the system must do a conversion to produce the text format. In addition, text formats are often larger in size than the corresponding binary format. Once the information comes back in text form, the client application may need to convert it to a binary format to manipulate it. BINARY cursors give you back the data in the native binary representation.

As an example, if a query returns a value of one from an integer column, you would get a string of `1` with a default cursor whereas with a binary cursor you would get a 4-byte value equal to control-A (`^A`).

BINARY cursors should be used carefully. User applications such as psql are not aware of binary cursors and expect data to come back in a text format.

String representation is architecture-neutral whereas binary representation can differ between different machine architectures. *PostgreSQL does not resolve byte ordering or representation issues for binary cursors*. Therefore, if your client machine and server machine use different representations (e.g., “big-endian” versus “little-endian”), you will probably not want your data returned in binary format. However, binary cursors may be a little more efficient since there is less conversion overhead in the server to client data transfer.

Tip

If you intend to display the data in ASCII, getting it back in ASCII will save you some effort on the client side.

Notes

Cursors are only available in transactions. Use to BEGIN, COMMIT and ROLLBACK to define a transaction block.

In SQL92 cursors are only available in embedded SQL (ESQL) applications. The PostgreSQL backend does not implement an explicit `OPEN cursor` statement; a cursor is considered to be open when it is declared. However, ecpg, the embedded SQL preprocessor for PostgreSQL, supports the SQL92 cursor conventions, including those involving DECLARE and OPEN statements.

Usage

To declare a cursor:

```
DECLARE liahona CURSOR
    FOR SELECT * FROM films;
```

Compatibility

SQL92

SQL92 allows cursors only in embedded SQL and in modules. PostgreSQL permits cursors to be used interactively. SQL92 allows embedded or modular cursors to update database information. All PostgreSQL cursors are read only. The BINARY keyword is a PostgreSQL extension.

Name

DELETE — delete rows of a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DELETE FROM [ ONLY ] table [ WHERE condition ]
```

Inputs

table

The name (optionally schema-qualified) of an existing table.

condition

This is an SQL selection query which returns the rows which are to be deleted.

Refer to the SELECT statement for further description of the WHERE clause.

Outputs

DELETE *count*

Message returned if items are successfully deleted. The *count* is the number of rows deleted.

If *count* is 0, no rows were deleted.

Description

DELETE removes rows which satisfy the WHERE clause from the specified table.

If the *condition* (WHERE clause) is absent, the effect is to delete all rows in the table. The result is a valid, but empty table.

Tip

TRUNCATE is a PostgreSQL extension which provides a faster mechanism to remove all rows from a table.

By default DELETE will delete tuples in the table specified and all its sub-tables. If you wish to only update the specific table mentioned, you should use the ONLY clause.

You must have write access to the table in order to modify it, as well as read access to any table whose values are read in the *condition*.

Usage

Remove all films but musicals:

```
DELETE FROM films WHERE kind <> 'Musical';
SELECT * FROM films;

 code  |           title           | did | date_prod  |  kind   |
 len
-------+---------------------------+-----+------------+---------
+-------
```

```
 UA501 | West Side Story           | 105 | 1961-01-03 | Musical |
 02:32
 TC901 | The King and I            | 109 | 1956-08-11 | Musical |
 02:13
 WD101 | Bed Knobs and Broomsticks | 111 |            | Musical |
 01:57
(3 rows)
```

Clear the table `films`:

```
DELETE FROM films;
SELECT * FROM films;

 code | title | did | date_prod | kind | len
------+-------+-----+-----------+------+-----
(0 rows)
```

Compatibility

SQL92

SQL92 allows a positioned DELETE statement:

```
DELETE FROM table WHERE
    CURRENT OF cursor
```

where *cursor* identifies an open cursor. Interactive cursors in PostgreSQL are read-only.

Name

DROP AGGREGATE — remove a user-defined aggregate function

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP AGGREGATE name ( type ) [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of an existing aggregate function.

type

The input data type of the aggregate function, or * if the function accepts any input type. (Refer to the *PostgreSQL User's Guide* for further information about data types.)

CASCADE

Automatically drop objects that depend on the aggregate.

RESTRICT

Refuse to drop the aggregate if there are any dependent objects. This is the default.

Outputs

`DROP AGGREGATE`

Message returned if the command is successful.

`ERROR: RemoveAggregate: aggregate '`*name*`' for type `*type*` does not exist`

This message occurs if the aggregate function specified does not exist in the database.

Description

`DROP AGGREGATE` will delete an existing aggregate definition. To execute this command the current user must be the owner of the aggregate.

Notes

Use CREATE AGGREGATE to create aggregate functions.

Usage

To remove the `myavg` aggregate for type `int4`:

```
DROP AGGREGATE myavg(int4);
```

Compatibility

SQL92

There is no `DROP AGGREGATE` statement in SQL92; the statement is a PostgreSQL language extension.

Name

DROP CAST — remove a user-defined cast

Synopsis

```
DROP CAST (sourcetype AS targettype)
    [ CASCADE | RESTRICT ]
```

Description

`DROP CAST` removes a previously defined cast.

To be able to drop a cast, you must own the source or the target data type. These are the same privileges that are required to create a cast.

Parameters

sourcetype

The name of the source data type of the cast.

targettype

The name of the target data type of the cast.

`CASCADE`
`RESTRICT`

These key words do not have any effect, since there are no dependencies on casts.

Notes

Use `CREATE CAST` to create user-defined casts.

Examples

To drop the cast from type `text` to type `int`:

```
DROP CAST (text AS int4);
```

Compatibility

The `DROP CAST` command conforms to SQL99.

See Also

CREATE CAST

Name

DROP CONVERSION — remove a user-defined conversion

Synopsis

```
DROP CONVERSION conversion_name
    [ CASCADE | RESTRICT ]
```

Description

`DROP CONVERSION` removes a previously defined conversion.

To be able to drop a conversion, you must own the conversion.

Parameters

`conversion_name`

The name of the conversion. The conversion name may be schema-qualified.

`CASCADE`
`RESTRICT`

These key words do not have any effect, since there are no dependencies on conversions.

Notes

Use `CREATE CONVERSION` to create user-defined conversions.

The privileges required to drop a conversion may be changed in a future release.

Examples

To drop the conversion named `myname`:

```
DROP CONVERSION myname;
```

Compatibility

`DROP CONVERSION` is a PostgreSQL extension. There is no `DROP CONVERSION` statement in SQL99.

See Also

CREATE CONVERSION

Name

DROP DATABASE — remove a database

Synopsis

<refsynopsisdivinfo>1999-12-11</refsynopsisdivinfo>

```
DROP DATABASE name
```

Inputs

name

The name of an existing database to remove.

Outputs

`DROP DATABASE`

This message is returned if the command is successful.

`DROP DATABASE: cannot be executed on the currently open database`

You cannot be connected to the database you are about to remove. Instead, connect to `template1` or any other database and run this command again.

`DROP DATABASE: may not be called in a transaction block`

You must finish the transaction in progress before you can call this command.

Description

`DROP DATABASE` removes the catalog entries for an existing database and deletes the directory containing the data. It can only be executed by the database owner (usually the user that created it).

`DROP DATABASE` cannot be undone. Use it with care!

Notes

This command cannot be executed while connected to the target database. Thus, it might be more convenient to use the shell script dropdb, which is a wrapper around this command, instead.

Refer to CREATE DATABASE for information on how to create a database.

Compatibility

SQL92

`DROP DATABASE` statement is a PostgreSQL language extension; there is no such command in SQL92.

Name

DROP DOMAIN — remove a user-defined domain

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP DOMAIN domainname [, ...]  [ CASCADE | RESTRICT ]
```

Inputs

domainname

The name (optionally schema-qualified) of an existing domain.

CASCADE

Automatically drop objects that depend on the domain (such as table columns).

RESTRICT

Refuse to drop the domain if there are any dependent objects. This is the default.

Outputs

DROP DOMAIN

The message returned if the command is successful.

ERROR: RemoveDomain: type '*domainname*' does not exist

This message occurs if the specified domain (or type) is not found.

Description

DROP DOMAIN will remove a user domain from the system catalogs.

Only the owner of a domain can remove it.

Examples

To remove the box domain:

```
DROP DOMAIN box;
```

Compatibility

SQL92

See Also

CREATE DOMAIN

Name

DROP FUNCTION — remove a user-defined function

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP FUNCTION name ( [ type [, ...] ] ) [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of an existing function.

type

The type of a parameter of the function.

CASCADE

Automatically drop objects that depend on the function (such as operators or triggers).

RESTRICT

Refuse to drop the function if there are any dependent objects. This is the default.

Outputs

`DROP FUNCTION`

Message returned if the command completes successfully.

`WARNING: RemoveFunction: Function "`*name*`" ("`*types*`") does not exist`

This message is given if the function specified does not exist in the current database.

Description

DROP FUNCTION will remove the definition of an existing function. To execute this command the user must be the owner of the function. The input argument types to the function must be specified, since several different functions may exist with the same name and different argument lists.

Notes

Refer to CREATE FUNCTION for information on creating functions.

Examples

This command removes the square root function:

```
DROP FUNCTION sqrt(integer);
```

Compatibility

A `DROP FUNCTION` statement is defined in SQL99. One of its syntax forms is similar to PostgreSQL's.

See Also

CREATE FUNCTION

Name

DROP GROUP — remove a user group

Synopsis

<refsynopsisdivinfo>2000-01-14</refsynopsisdivinfo>

```
DROP GROUP name
```

Inputs

name

The name of an existing group.

Outputs

`DROP GROUP`

The message returned if the group is successfully deleted.

Description

`DROP GROUP` removes the specified group from the database. The users in the group are not deleted.

Use CREATE GROUP to add new groups, and ALTER GROUP to change a group's membership.

Usage

To drop a group:

```
DROP GROUP staff;
```

Compatibility

SQL92

There is no `DROP GROUP` in SQL92.

Name

DROP INDEX — remove an index

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP INDEX index_name [, ...] [ CASCADE | RESTRICT ]
```

Inputs

index_name

The name (optionally schema-qualified) of an index to remove.

CASCADE

Automatically drop objects that depend on the index.

RESTRICT

Refuse to drop the index if there are any dependent objects. This is the default.

Outputs

`DROP INDEX`

The message returned if the command completes successfully.

`ERROR: index "index_name" does not exist`

This message occurs if *index_name* is not an index in the database.

Description

`DROP INDEX` drops an existing index from the database system. To execute this command you must be the owner of the index.

Notes

`DROP INDEX` is a PostgreSQL language extension.

Refer to CREATE INDEX for information on how to create indexes.

Usage

This command will remove the `title_idx` index:

```
DROP INDEX title_idx;
```

Compatibility

SQL92

SQL92 defines commands by which to access a generic relational database. Indexes are an implementation-dependent feature and hence there are no index-specific commands or definitions in the SQL92 language.

Name

DROP LANGUAGE — remove a user-defined procedural language

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP [ PROCEDURAL ] LANGUAGE name [ CASCADE | RESTRICT ]
```

Inputs

name

The name of an existing procedural language. For backward compatibility, the name may be enclosed by single quotes.

CASCADE

Automatically drop objects that depend on the language (such as functions in the language).

RESTRICT

Refuse to drop the language if there are any dependent objects. This is the default.

Outputs

`DROP LANGUAGE`

This message is returned if the language is successfully dropped.

`ERROR: Language "name" doesn't exist`

This message occurs if a language called *name* is not found in the database.

Description

`DROP PROCEDURAL LANGUAGE` will remove the definition of the previously registered procedural language called *name*.

Notes

The `DROP PROCEDURAL LANGUAGE` statement is a PostgreSQL language extension.

Refer to CREATE LANGUAGE for information on how to create procedural languages.

Usage

This command removes the PL/Sample language:

```
DROP LANGUAGE plsample;
```

Compatibility

SQL92

There is no `DROP PROCEDURAL LANGUAGE` in SQL92.

Name

DROP OPERATOR — remove a user-defined operator

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP OPERATOR id ( lefttype | NONE , righttype | NONE ) [ CASCADE |
 RESTRICT ]
```

Inputs

id

The identifier (optionally schema-qualified) of an existing operator.

lefttype

The type of the operator's left argument; write NONE if the operator has no left argument.

righttype

The type of the operator's right argument; write NONE if the operator has no right argument.

CASCADE

Automatically drop objects that depend on the operator.

RESTRICT

Refuse to drop the operator if there are any dependent objects. This is the default.

Outputs

DROP OPERATOR

The message returned if the command is successful.

ERROR: RemoveOperator: binary operator '*oper*' taking '*lefttype*' and '*righttype*' does not exist

This message occurs if the specified binary operator does not exist.

ERROR: RemoveOperator: left unary operator '*oper*' taking '*lefttype*' does not exist

This message occurs if the left unary operator specified does not exist.

ERROR: RemoveOperator: right unary operator '*oper*' taking '*righttype*' does not exist

This message occurs if the right unary operator specified does not exist.

Description

DROP OPERATOR drops an existing operator from the database. To execute this command you must be the owner of the operator.

The left or right type of a left or right unary operator, respectively, must be specified as NONE.

Notes

The `DROP OPERATOR` statement is a PostgreSQL language extension.

Refer to CREATE OPERATOR for information on how to create operators.

Usage

Remove power operator `a^n` for `int4`:

```
DROP OPERATOR ^ (int4, int4);
```

Remove left unary negation operator (`! b`) for `boolean`:

```
DROP OPERATOR ! (none, bool);
```

Remove right unary factorial operator (`i !`) for `int4`:

```
DROP OPERATOR ! (int4, none);
```

Compatibility

SQL92

There is no `DROP OPERATOR` in SQL92.

Name

DROP OPERATOR CLASS — remove a user-defined operator class

Synopsis

<refsynopsisdivinfo>2002-07-28</refsynopsisdivinfo>

```
DROP OPERATOR CLASS name USING access_method [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of an existing operator class.

access_method

The name of the index access method the operator class is for.

CASCADE

Automatically drop objects that depend on the operator class.

RESTRICT

Refuse to drop the operator class if there are any dependent objects. This is the default.

Outputs

`DROP OPERATOR CLASS`

The message returned if the command is successful.

Description

`DROP OPERATOR CLASS` drops an existing operator class from the database. To execute this command you must be the owner of the operator class.

Notes

The `DROP OPERATOR CLASS` statement is a PostgreSQL language extension.

Refer to CREATE OPERATOR CLASS for information on how to create operator classes.

Usage

Remove B-tree operator class `widget_ops`:

```
DROP OPERATOR CLASS widget_ops USING btree;
```

This command will not execute if there are any existing indexes that use the operator class. Add `CASCADE` to drop such indexes along with the operator class.

Compatibility

SQL92

There is no `DROP OPERATOR CLASS` in SQL92.

Name

DROP RULE — remove a rewrite rule

Synopsis

<refsynopsisdivinfo>1998-09-22</refsynopsisdivinfo>

```
DROP RULE name ON relation [ CASCADE | RESTRICT ]
```

Inputs

name

The name of an existing rule to drop.

relation

The name (optionally schema-qualified) of the relation the rule applies to.

CASCADE

Automatically drop objects that depend on the rule.

RESTRICT

Refuse to drop the rule if there are any dependent objects. This is the default.

Outputs

`DROP RULE`

Message returned if successful.

`ERROR: Rule "name" not found`

This message occurs if the specified rule does not exist.

Description

`DROP RULE` drops a rule from the specified PostgreSQL rule system. PostgreSQL will immediately cease enforcing it and will purge its definition from the system catalogs.

Notes

The `DROP RULE` statement is a PostgreSQL language extension.

Refer to `CREATE RULE` for information on how to create rules.

Usage

To drop the rewrite rule `newrule`:

```
DROP RULE newrule ON mytable;
```

Compatibility

SQL92

There is no `DROP RULE` in SQL92.

Name

DROP SCHEMA — remove a schema

Synopsis

<refsynopsisdivinfo>2002-07-18</refsynopsisdivinfo>

```
DROP SCHEMA name [, ...] [ CASCADE | RESTRICT ]
```

Inputs

name

The name of a schema.

CASCADE

Automatically drop objects (tables, functions, etc) that are contained in the schema.

RESTRICT

Refuse to drop the schema if it contains any objects. This is the default.

Outputs

`DROP SCHEMA`

The message returned if the schema is successfully dropped.

`ERROR: Schema "name" does not exist`

This message occurs if the specified schema does not exist.

Description

`DROP SCHEMA` removes schemas from the data base.

A schema can only be dropped by its owner or a superuser. Note that the owner can drop the schema (and thereby all contained objects) even if he does not own some of the objects within the schema.

Notes

Refer to the `CREATE SCHEMA` statement for information on how to create a schema.

Usage

To remove schema `mystuff` from the database, along with everything it contains:

```
DROP SCHEMA mystuff CASCADE;
```

Compatibility

SQL92

`DROP SCHEMA` is fully compatible with SQL92, except that the standard only allows one schema to be dropped per command.

Name

DROP SEQUENCE — remove a sequence

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP SEQUENCE name [, ...] [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of a sequence.

CASCADE

Automatically drop objects that depend on the sequence.

RESTRICT

Refuse to drop the sequence if there are any dependent objects. This is the default.

Outputs

`DROP SEQUENCE`

The message returned if the sequence is successfully dropped.

`ERROR: sequence "name" does not exist`

This message occurs if the specified sequence does not exist.

Description

`DROP SEQUENCE` removes sequence number generators from the data base. With the current implementation of sequences as special tables it works just like the `DROP TABLE` statement.

Notes

The `DROP SEQUENCE` statement is a PostgreSQL language extension.

Refer to the `CREATE SEQUENCE` statement for information on how to create a sequence.

Usage

To remove sequence `serial` from database:

```
DROP SEQUENCE serial;
```

Compatibility

SQL92

There is no `DROP SEQUENCE` in SQL92.

Name

DROP TABLE — remove a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP TABLE name [, ...] [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of an existing table to drop.

CASCADE

Automatically drop objects that depend on the table (such as views).

RESTRICT

Refuse to drop the table if there are any dependent objects. This is the default.

Outputs

`DROP TABLE`

The message returned if the command completes successfully.

`ERROR: table "name" does not exist`

If the specified table does not exist in the database.

Description

`DROP TABLE` removes tables from the database. Only its owner may destroy a table. A table may be emptied of rows, but not destroyed, by using `DELETE`.

`DROP TABLE` always removes any indexes, rules, triggers, and constraints that exist for the target table. However, to drop a table that is referenced by a foreign-key constraint of another table, CASCADE must be specified. (CASCADE will remove the foreign-key constraint, not the other table itself.)

Notes

Refer to `CREATE TABLE` and `ALTER TABLE` for information on how to create or modify tables.

Usage

To destroy two tables, `films` and `distributors`:

```
DROP TABLE films, distributors;
```

Compatibility

SQL92

Name

DROP TRIGGER — remove a trigger

Synopsis

<refsynopsisdivinfo>1998-09-22</refsynopsisdivinfo>

```
DROP TRIGGER name ON table [ CASCADE | RESTRICT ]
```

Inputs

name

The name of an existing trigger.

table

The name (optionally schema-qualified) of a table.

CASCADE

Automatically drop objects that depend on the trigger.

RESTRICT

Refuse to drop the trigger if there are any dependent objects. This is the default.

Outputs

`DROP TRIGGER`

The message returned if the trigger is successfully dropped.

`ERROR: DropTrigger: there is no trigger name on relation "table"`

This message occurs if the trigger specified does not exist.

Description

`DROP TRIGGER` will remove an existing trigger definition. To execute this command the current user must be the owner of the table for which the trigger is defined.

Examples

Destroy the `if_dist_exists` trigger on table `films`:

```
DROP TRIGGER if_dist_exists ON films;
```

Compatibility

SQL92

There is no `DROP TRIGGER` statement in SQL92.

SQL99

The `DROP TRIGGER` statement in PostgreSQL is incompatible with SQL99. In SQL99, trigger names are not local to tables, so the command is simply `DROP TRIGGER name`.

See Also

CREATE TRIGGER

Name

DROP TYPE — remove a user-defined data type

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP TYPE typename [, ...] [ CASCADE | RESTRICT ]
```

Inputs

typename

The name (optionally schema-qualified) of an existing type.

CASCADE

Automatically drop objects that depend on the type (such as table columns, functions, operators, etc).

RESTRICT

Refuse to drop the type if there are any dependent objects. This is the default.

Outputs

`DROP TYPE`

The message returned if the command is successful.

`ERROR: RemoveType: type '`*typename*`' does not exist`

This message occurs if the specified type is not found.

Description

`DROP TYPE` will remove a user type from the system catalogs.

Only the owner of a type can remove it.

Examples

To remove the `box` type:

```
DROP TYPE box;
```

Compatibility

Note that the `CREATE TYPE` command and the data type extension mechanisms in PostgreSQL differ from SQL99.

See Also

CREATE TYPE

Name

DROP USER — remove a database user account

Synopsis

```
DROP USER name
```

Description

`DROP USER` removes the specified user from the database. It does not remove tables, views, or other objects owned by the user. If the user owns any database, an error is raised.

Parameters

name

The name of an existing user.

Diagnostics

`DROP USER`

The message returned if the user is successfully deleted.

`ERROR: DROP USER: user "name" does not exist`

This message occurs if the user name is not found.

`DROP USER: user "name" owns database "name", cannot be removed`

You must drop the database first or change its ownership.

Notes

Use CREATE USER to add new users, and ALTER USER to change a user's attributes. PostgreSQL includes a program dropuser that has the same functionality as this command (in fact, it calls this command) but can be run from the command shell.

Examples

To drop a user account:

```
DROP USER jonathan;
```

Compatibility

The `DROP USER` statement is a PostgreSQL extension. The SQL standard leaves the definition of users to the implementation.

See Also

CREATE USER, ALTER USER, dropuser

Name

DROP VIEW — remove a view

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
DROP VIEW name [, ...] [ CASCADE | RESTRICT ]
```

Inputs

name

The name (optionally schema-qualified) of an existing view.

CASCADE

Automatically drop objects that depend on the view (such as other views).

RESTRICT

Refuse to drop the view if there are any dependent objects. This is the default.

Outputs

`DROP VIEW`

The message returned if the command is successful.

`ERROR: view name does not exist`

This message occurs if the specified view does not exist in the database.

Description

`DROP VIEW` drops an existing view from the database. To execute this command you must be the owner of the view.

Notes

Refer to CREATE VIEW for information on how to create views.

Usage

This command will remove the view called `kinds`:

```
DROP VIEW kinds;
```

Compatibility

SQL92

Name

END — commit the current transaction

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
END [ WORK | TRANSACTION ]
```

Inputs

WORK
TRANSACTION

Optional keywords. They have no effect.

Outputs

`COMMIT`

Message returned if the transaction is successfully committed.

`WARNING: COMMIT: no transaction in progress`

If there is no transaction in progress.

Description

`END` is a PostgreSQL extension, and is a synonym for the SQL92-compatible COMMIT.

Notes

The keywords WORK and TRANSACTION are noise and can be omitted.

Use ROLLBACK to abort a transaction.

Usage

To make all changes permanent:

```
END WORK;
```

Compatibility

SQL92

`END` is a PostgreSQL extension which provides functionality equivalent to COMMIT.

Name

EXECUTE — execute a prepared query

Synopsis

<refsynopsisdivinfo>2002-08-12</refsynopsisdivinfo>

```
EXECUTE plan_name [ (parameter [, ...] ) ]
```

Inputs

plan_name

The name of the prepared query to execute.

parameter

The actual value of a parameter to the prepared query. This must be an expression yielding a value of a type compatible with the data-type specified for this parameter position in the PREPARE statement that created the prepared query.

Description

EXECUTE is used to execute a previously prepared query. Since prepared queries only exist for the duration of a session, the prepared query must have been created by a PREPARE statement executed earlier in the current session.

If the PREPARE statement that created the query specified some parameters, a compatible set of parameters must be passed to the EXECUTE statement, or else an error is raised. Note that (unlike functions) prepared queries are not overloaded based on the type or number of their parameters: the name of a prepared query must be unique within a database session.

For more information on the creation and usage of prepared queries, see PREPARE.

Compatibility

SQL92

SQL92 includes an EXECUTE statement, but it is only for use in embedded SQL clients. The EXECUTE statement implemented by PostgreSQL also uses a somewhat different syntax.

Name

EXPLAIN — show the execution plan of a statement

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
EXPLAIN [ ANALYZE ] [ VERBOSE ] query
```

Inputs

ANALYZE

Flag to carry out the query and show actual run times.

VERBOSE

Flag to show detailed query plan dump.

query

Any *query*.

Outputs

Query plan

Explicit query plan from the PostgreSQL planner.

Note

Prior to PostgreSQL 7.3, the query plan was emitted in the form of a NOTICE message. Now it appears as a query result (formatted like a table with a single text column).

Description

This command displays the execution plan that the PostgreSQL planner generates for the supplied query. The execution plan shows how the table(s) referenced by the query will be scanned---by plain sequential scan, index scan, etc.---and if multiple tables are referenced, what join algorithms will be used to bring together the required tuples from each input table.

The most critical part of the display is the estimated query execution cost, which is the planner's guess at how long it will take to run the query (measured in units of disk page fetches). Actually two numbers are shown: the start-up time before the first tuple can be returned, and the total time to return all the tuples. For most queries the total time is what matters, but in contexts such as an EXISTS sub-query the planner will choose the smallest start-up time instead of the smallest total time (since the executor will stop after getting one tuple, anyway). Also, if you limit the number of tuples to return with a LIMIT clause, the planner makes an appropriate interpolation between the endpoint costs to estimate which plan is really the cheapest.

The ANALYZE option causes the query to be actually executed, not only planned. The total elapsed time expended within each plan node (in milliseconds) and total number of rows it actually returned are added to the display. This is useful for seeing whether the planner's estimates are close to reality.

Caution

Keep in mind that the query is actually executed when ANALYZE is used. Although `EXPLAIN` will discard any output that a SELECT would return, other side-effects of the query will happen as usual. If you wish to use `EXPLAIN ANALYZE` on an INSERT, UPDATE, or DELETE query without letting the query affect your data, use this approach:

```
BEGIN;
EXPLAIN ANALYZE ...;
ROLLBACK;
```

The VERBOSE option emits the full internal representation of the plan tree, rather than just a summary. Usually this option is only useful for debugging PostgreSQL. The VERBOSE dump is either pretty-printed or not, depending on the setting of the `EXPLAIN_PRETTY_PRINT` configuration parameter.

Notes

There is only sparse documentation on the optimizer's use of cost information in PostgreSQL. Refer to the *User's Guide* and *Programmer's Guide* for more information.

Usage

To show a query plan for a simple query on a table with a single `int4` column and 10000 rows:

```
EXPLAIN SELECT * FROM foo;
                           QUERY PLAN
-----------------------------------------------------------
 Seq Scan on foo  (cost=0.00..155.00 rows=10000 width=4)
(1 row)
```

If there is an index and we use a query with an indexable WHERE condition, `EXPLAIN` will show a different plan:

```
EXPLAIN SELECT * FROM foo WHERE i = 4;
                             QUERY PLAN
-------------------------------------------------------------
 Index Scan using fi on foo  (cost=0.00..5.98 rows=1 width=4)
   Index Cond: (i = 4)
(2 rows)
```

And here is an example of a query plan for a query using an aggregate function:

```
EXPLAIN SELECT sum(i) FROM foo WHERE i < 10;
                                QUERY PLAN
-------------------------------------------------------------------------
 Aggregate  (cost=23.93..23.93 rows=1 width=4)
   ->  Index Scan using fi on foo  (cost=0.00..23.92 rows=6
 width=4)
         Index Cond: (i < 10)
(3 rows)
```

Note that the specific numbers shown, and even the selected query strategy, may vary between PostgreSQL releases due to planner improvements.

Compatibility

SQL92

There is no `EXPLAIN` statement defined in SQL92.

Name

FETCH — retrieve rows from a table using a cursor

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
FETCH [ direction ] [ count ] { IN | FROM } cursor
FETCH [ FORWARD | BACKWARD | RELATIVE ] [ # | ALL | NEXT | PRIOR ]
    { IN | FROM } cursor
```

Inputs

direction

selector defines the fetch direction. It can be one of the following:

FORWARD

fetch next row(s). This is the default if *selector* is omitted.

BACKWARD

fetch previous row(s).

RELATIVE

Noise word for SQL92 compatibility.

count

count determines how many rows to fetch. It can be one of the following:

#

A signed integer that specifies how many rows to fetch. Note that a negative integer is equivalent to changing the sense of FORWARD and BACKWARD.

ALL

Retrieve all remaining rows.

NEXT

Equivalent to specifying a count of `1`.

PRIOR

Equivalent to specifying a count of `-1`.

cursor

An open cursor's name.

Outputs

`FETCH` returns the results of the query defined by the specified cursor. The following messages will be returned if the query fails:

`WARNING: PerformPortalFetch: portal "`*cursor*`" not found`

If *cursor* is not previously declared. The cursor must be declared within a transaction block.

```
WARNING: FETCH/ABSOLUTE not supported, using RELATIVE
```

PostgreSQL does not support absolute positioning of cursors.

```
ERROR: FETCH/RELATIVE at current position is not supported
```

SQL92 allows one to repetitively retrieve the cursor at its "current position" using the syntax

`FETCH RELATIVE 0 FROM cursor.`

PostgreSQL does not currently support this notion; in fact the value zero is reserved to indicate that all rows should be retrieved and is equivalent to specifying the ALL keyword. If the RELATIVE keyword has been used, PostgreSQL assumes that the user intended SQL92 behavior and returns this error message.

Description

`FETCH` allows a user to retrieve rows using a cursor. The number of rows retrieved is specified by `#`. If the number of rows remaining in the cursor is less than `#`, then only those available are fetched. Substituting the keyword ALL in place of a number will cause all remaining rows in the cursor to be retrieved. Instances may be fetched in both FORWARD and BACKWARD directions. The default direction is FORWARD.

Tip

Negative numbers are allowed to be specified for the row count. A negative number is equivalent to reversing the sense of the FORWARD and BACKWARD keywords. For example, `FORWARD -1` is the same as `BACKWARD 1`.

Notes

Note that the FORWARD and BACKWARD keywords are PostgreSQL extensions. The SQL92 syntax is also supported, specified in the second form of the command. See below for details on compatibility issues.

Updating data in a cursor is not supported by PostgreSQL, because mapping cursor updates back to base tables is not generally possible, as is also the case with VIEW updates. Consequently, users must issue explicit UPDATE commands to replace data.

Cursors may only be used inside of transactions because the data that they store spans multiple user queries.

Use MOVE to change cursor position. DECLARE will define a cursor. Refer to BEGIN, COMMIT, and ROLLBACK for further information about transactions.

Usage

The following examples traverses a table using a cursor.

```
-- Set up and use a cursor:

BEGIN WORK;
DECLARE liahona CURSOR FOR SELECT * FROM films;

-- Fetch first 5 rows in the cursor liahona:
FETCH FORWARD 5 IN liahona;
```

```
 code  |          title          | did | date_prod  |  kind    |
 len
-------+-------------------------+-----+------------+----------
+-------
 BL101 | The Third Man           | 101 | 1949-12-23 | Drama    |
 01:44
 BL102 | The African Queen       | 101 | 1951-08-11 | Romantic |
 01:43
 JL201 | Une Femme est une Femme | 102 | 1961-03-12 | Romantic |
 01:25
 P_301 | Vertigo                 | 103 | 1958-11-14 | Action   |
 02:08
 P_302 | Becket                  | 103 | 1964-02-03 | Drama    |
 02:28

-- Fetch previous row:
FETCH BACKWARD 1 IN liahona;

 code  | title   | did | date_prod  | kind   | len
-------+---------+-----+------------+--------+-------
 P_301 | Vertigo | 103 | 1958-11-14 | Action | 02:08

-- close the cursor and commit work:

CLOSE liahona;
COMMIT WORK;
```

Compatibility

SQL92

Note

The non-embedded use of cursors is a PostgreSQL extension. The syntax and usage of cursors is being compared against the embedded form of cursors defined in SQL92.

SQL92 allows absolute positioning of the cursor for FETCH, and allows placing the results into explicit variables:

```
FETCH ABSOLUTE #
    FROM cursor
    INTO :variable [, ...]
```

ABSOLUTE

The cursor should be positioned to the specified absolute row number. All row numbers in PostgreSQL are relative numbers so this capability is not supported.

:*variable*

Target host variable(s).

Name

GRANT — define access privileges

Synopsis

```
GRANT { { SELECT | INSERT | UPDATE | DELETE | RULE | REFERENCES |
 TRIGGER }
    [,...] | ALL [ PRIVILEGES ] }
    ON [ TABLE ] tablename [, ...]
    TO { username | GROUP groupname | PUBLIC } [, ...]

GRANT { { CREATE | TEMPORARY | TEMP } [,...] | ALL [ PRIVILEGES ] }
    ON DATABASE dbname [, ...]
    TO { username | GROUP groupname | PUBLIC } [, ...]

GRANT { EXECUTE | ALL [ PRIVILEGES ] }
    ON FUNCTION funcname ([type, ...]) [, ...]
    TO { username | GROUP groupname | PUBLIC } [, ...]

GRANT { USAGE | ALL [ PRIVILEGES ] }
    ON LANGUAGE langname [, ...]
    TO { username | GROUP groupname | PUBLIC } [, ...]

GRANT { { CREATE | USAGE } [,...] | ALL [ PRIVILEGES ] }
    ON SCHEMA schemaname [, ...]
    TO { username | GROUP groupname | PUBLIC } [, ...]
```

Description

The `GRANT` command gives specific permissions on an object (table, view, sequence, database, function, procedural language, or schema) to one or more users or groups of users. These permissions are added to those already granted, if any.

The key word `PUBLIC` indicates that the privileges are to be granted to all users, including those that may be created later. `PUBLIC` may be thought of as an implicitly defined group that always includes all users. Note that any particular user will have the sum of privileges granted directly to him, privileges granted to any group he is presently a member of, and privileges granted to `PUBLIC`.

There is no need to grant privileges to the creator of an object, as the creator has all privileges by default. (The creator could, however, choose to revoke some of his own privileges for safety.) Note that the ability to grant and revoke privileges is inherent in the creator and cannot be lost. The right to drop an object, or to alter it in any way not described by a grantable right, is likewise inherent in the creator, and cannot be granted or revoked.

Depending on the type of object, the initial default privileges may include granting some privileges to `PUBLIC`. The default is no public access for tables and schemas; `TEMP` table creation privilege for databases; `EXECUTE` privilege for functions; and `USAGE` privilege for languages. The object creator may of course revoke these privileges. (For maximum security, issue the `REVOKE` in the same transaction that creates the object; then there is no window in which another user may use the object.)

The possible privileges are:

SELECT

Allows SELECT from any column of the specified table, view, or sequence. Also allows the use of COPY TO. For sequences, this privilege also allows the use of the `currval` function.

INSERT

Allows INSERT of a new row into the specified table. Also allows COPY FROM.

UPDATE

Allows UPDATE of any column of the specified table. `SELECT ... FOR UPDATE` also requires this privilege (besides the `SELECT` privilege). For sequences, this privilege allows the use of the `nextval` and `setval` functions.

DELETE

Allows DELETE of a row from the specified table.

RULE

Allows the creation of a rule on the table/view. (See CREATE RULE statement.)

REFERENCES

To create a foreign key constraint, it is necessary to have this privilege on both the referencing and referenced tables.

TRIGGER

Allows the creation of a trigger on the specified table. (See CREATE TRIGGER statement.)

CREATE

For databases, allows new schemas to be created within the database.

For schemas, allows new objects to be created within the schema. To rename an existing object, you must own the object *and* have this privilege for the containing schema.

TEMPORARY
TEMP

Allows temporary tables to be created while using the database.

EXECUTE

Allows the use of the specified function and the use of any operators that are implemented on top of the function. This is the only type of privilege that is applicable to functions. (This syntax works for aggregate functions, as well.)

USAGE

For procedural languages, allows the use of the specified language for the creation of functions in that language. This is the only type of privilege that is applicable to procedural languages.

For schemas, allows access to objects contained in the specified schema (assuming that the objects' own privilege requirements are also met). Essentially this allows the grantee to “look up” objects within the schema.

ALL PRIVILEGES

Grant all of the privileges applicable to the object at once. The `PRIVILEGES` key word is optional in PostgreSQL, though it is required by strict SQL.

The privileges required by other commands are listed on the reference page of the respective command.

Notes

The REVOKE command is used to revoke access privileges.

It should be noted that database *superusers* can access all objects regardless of object privilege settings. This is comparable to the rights of `root` in a Unix system. As with `root`, it's unwise to operate as a superuser except when absolutely necessary.

Currently, to grant privileges in PostgreSQL to only a few columns, you must create a view having the desired columns and then grant privileges to that view.

Use psql's `\dp` command to obtain information about existing privileges, for example:

```
lusitania=> \dp mytable
        Access privileges for database "lusitania"
 Schema |  Table  |           Access privileges
--------+---------+---------------------------------------
 public | mytable | {=r,miriam=arwdRxt,"group todos=arw"}
(1 row)
```

The entries shown by `\dp` are interpreted thus:

```
              =xxxx -- privileges granted to PUBLIC
          uname=xxxx -- privileges granted to a user
   group gname=xxxx -- privileges granted to a group

                 r -- SELECT ("read")
                 w -- UPDATE ("write")
                 a -- INSERT ("append")
                 d -- DELETE
                 R -- RULE
                 x -- REFERENCES
                 t -- TRIGGER
                 X -- EXECUTE
                 U -- USAGE
                 C -- CREATE
                 T -- TEMPORARY
            arwdRxt -- ALL PRIVILEGES (for tables)
```

The above example display would be seen by user `miriam` after creating table `mytable` and doing

```
GRANT SELECT ON mytable TO PUBLIC;
GRANT SELECT,UPDATE,INSERT ON mytable TO GROUP todos;
```

If the “Access privileges” column is empty for a given object, it means the object has default privileges (that is, its privileges field is NULL). Default privileges always include all privileges for the owner, and may include some privileges for `PUBLIC` depending on the object type, as explained above. The first `GRANT` or `REVOKE` on an object will instantiate the default privileges (producing, for example, `{=,miriam=arwdRxt}`) and then modify them per the specified request.

Examples

Grant insert privilege to all users on table films:

```
GRANT INSERT ON films TO PUBLIC;
```

Grant all privileges to user `manuel` on view `kinds`:

```
GRANT ALL PRIVILEGES ON kinds TO manuel;
```

Compatibility

SQL92

The `PRIVILEGES` key word in `ALL PRIVILEGES` is required. SQL does not support setting the privileges on more than one table per command.

The SQL92 syntax for GRANT allows setting privileges for individual columns within a table, and allows setting a privilege to grant the same privileges to others:

```
GRANT privilege [, ...]
    ON object [ ( column [, ...] ) ] [, ...]
    TO { PUBLIC | username [, ...] } [ WITH GRANT OPTION ]
```

SQL allows to grant the USAGE privilege on other kinds of objects: CHARACTER SET, COLLATION, TRANSLATION, DOMAIN.

The TRIGGER privilege was introduced in SQL99. The RULE privilege is a PostgreSQL extension.

See Also

REVOKE

Name

INSERT — create new rows in a table

Synopsis

<refsynopsisdivinfo>2000-08-08</refsynopsisdivinfo>

```
INSERT INTO table [ ( column [, ...] ) ]
    { DEFAULT VALUES | VALUES ( { expression | DEFAULT } [, ...] )
 | SELECT query }
```

Inputs

table

The name (optionally schema-qualified) of an existing table.

column

The name of a column in *table*.

DEFAULT VALUES

All columns will be filled by null values or by values specified when the table was created using DEFAULT clauses.

expression

A valid expression or value to assign to *column*.

DEFAULT

This column will be filled in by the column DEFAULT clause, or NULL if a default is not available.

query

A valid query. Refer to the SELECT statement for a further description of valid arguments.

Outputs

INSERT *oid* 1

Message returned if only one row was inserted. *oid* is the numeric OID of the inserted row.

INSERT 0 #

Message returned if more than one rows were inserted. # is the number of rows inserted.

Description

INSERT allows one to insert new rows into a table. One can insert a single row at a time or several rows as a result of a query. The columns in the target list may be listed in any order.

Each column not present in the target list will be inserted using a default value, either a declared DEFAULT value or NULL. PostgreSQL will reject the new column if a NULL is inserted into a column declared NOT NULL.

If the expression for each column is not of the correct data type, automatic type coercion will be attempted.

You must have insert privilege to a table in order to append to it, as well as select privilege on any table specified in a WHERE clause.

Usage

Insert a single row into table `films`:

```
INSERT INTO films VALUES
    ('UA502','Bananas',105,'1971-07-13','Comedy',INTERVAL '82
 minute');
```

In this second example the last column `len` is omitted and therefore it will have the default value of NULL:

```
INSERT INTO films (code, title, did, date_prod, kind)
    VALUES ('T_601', 'Yojimbo', 106, DATE '1961-06-16', 'Drama');
```

In the third example, we use the DEFAULT values for the date columns rather than specifying an entry.

```
INSERT INTO films VALUES
    ('UA502','Bananas',105,DEFAULT,'Comedy',INTERVAL '82 minute');
INSERT INTO films (code, title, did, date_prod, kind)
    VALUES ('T_601', 'Yojimbo', 106, DEFAULT, 'Drama');
```

Insert a single row into table distributors; note that only column `name` is specified, so the omitted column `did` will be assigned its default value:

```
INSERT INTO distributors (name) VALUES ('British Lion');
```

Insert several rows into table films from table `tmp`:

```
INSERT INTO films SELECT * FROM tmp;
```

Insert into arrays (refer to the *PostgreSQL User's Guide* for further information about arrays):

```
-- Create an empty 3x3 gameboard for noughts-and-crosses
-- (all of these queries create the same board attribute)
INSERT INTO tictactoe (game, board[1:3][1:3])
    VALUES (1,'{{"","",""},{},{"",""}}');
INSERT INTO tictactoe (game, board[3][3])
    VALUES (2,'{}');
INSERT INTO tictactoe (game, board)
    VALUES (3,'{{,,},{,,},{,,}}');
```

Compatibility

SQL92

`INSERT` is fully compatible with SQL92. Possible limitations in features of the *`query`* clause are documented for SELECT.

Name

LISTEN — listen for a notification

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
LISTEN name
```

Inputs

name

Name of notify condition.

Outputs

`LISTEN`

Message returned upon successful completion of registration.

`WARNING: Async_Listen: We are already listening on name`

If this backend is already registered for that notify condition.

Description

`LISTEN` registers the current PostgreSQL backend as a listener on the notify condition *name*.

Whenever the command `NOTIFY` *name* is invoked, either by this backend or another one connected to the same database, all the backends currently listening on that notify condition are notified, and each will in turn notify its connected frontend application. See the discussion of `NOTIFY` for more information.

A backend can be unregistered for a given notify condition with the `UNLISTEN` command. Also, a backend's listen registrations are automatically cleared when the backend process exits.

The method a frontend application must use to detect notify events depends on which PostgreSQL application programming interface it uses. With the libpq library, the application issues `LISTEN` as an ordinary SQL command, and then must periodically call the routine `PQnotifies` to find out whether any notify events have been received. Other interfaces such as libpgtcl provide higher-level methods for handling notify events; indeed, with libpgtcl the application programmer should not even issue `LISTEN` or `UNLISTEN` directly. See the documentation for the library you are using for more details.

NOTIFY contains a more extensive discussion of the use of `LISTEN` and `NOTIFY`.

Notes

name can be any string valid as a name; it need not correspond to the name of any actual table. If *notifyname* is enclosed in double-quotes, it need not even be a syntactically valid name, but can be any string up to 63 characters long.

In some previous releases of PostgreSQL, *name* had to be enclosed in double-quotes when it did not correspond to any existing table name, even if syntactically valid as a name. That is no longer required.

Usage

Configure and execute a listen/notify sequence from psql:

```
LISTEN virtual;
NOTIFY virtual;

Asynchronous NOTIFY 'virtual' from backend with pid '8448'
 received.
```

Compatibility

SQL92

There is no `LISTEN` in SQL92.

Name

LOAD — load or reload a shared library file

Synopsis

```
LOAD 'filename'
```

Description

Loads a shared library file into the PostgreSQL backend's address space. If the file had been loaded previously, it is first unloaded. This command is primarily useful to unload and reload a shared library file that has been changed since the backend first loaded it. To make use of the shared library, function(s) in it need to be declared using the CREATE FUNCTION command.

The file name is specified in the same way as for shared library names in CREATE FUNCTION; in particular, one may rely on a search path and automatic addition of the system's standard shared library file name extension. See the *Programmer's Guide* for more detail.

Compatibility

`LOAD` is a PostgreSQL extension.

See Also

CREATE FUNCTION, *PostgreSQL Programmer's Guide*

Name

LOCK — explicitly lock a table

Synopsis

<refsynopsisdivinfo>2001-07-09</refsynopsisdivinfo>

```
LOCK [ TABLE ] name [, ...]
LOCK [ TABLE ] name [, ...] IN lockmode MODE

where lockmode is one of:

 ACCESS SHARE | ROW SHARE | ROW EXCLUSIVE | SHARE UPDATE EXCLUSIVE
 |
 SHARE | SHARE ROW EXCLUSIVE | EXCLUSIVE | ACCESS EXCLUSIVE
```

Inputs

name

The name (optionally schema-qualified) of an existing table to lock.

ACCESS SHARE MODE

This is the least restrictive lock mode. It conflicts only with ACCESS EXCLUSIVE mode. It is used to protect a table from being modified by concurrent `ALTER TABLE`, `DROP TABLE` and `VACUUM FULL` commands.

Note

The `SELECT` command acquires a lock of this mode on referenced tables. In general, any query that only reads a table and does not modify it will acquire this lock mode.

ROW SHARE MODE

Conflicts with EXCLUSIVE and ACCESS EXCLUSIVE lock modes.

Note

The `SELECT FOR UPDATE` command acquires a lock of this mode on the target table(s) (in addition to `ACCESS SHARE` locks on any other tables that are referenced but not selected `FOR UPDATE`).

ROW EXCLUSIVE MODE

Conflicts with SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE and ACCESS EXCLUSIVE modes.

Note

The commands `UPDATE`, `DELETE`, and `INSERT` acquire this lock mode on the target table (in addition to `ACCESS SHARE` locks on any other referenced tables). In general, this lock mode will be acquired by any query that modifies the data in a table.

SHARE UPDATE EXCLUSIVE MODE

Conflicts with SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE and ACCESS EXCLUSIVE modes. This mode protects a table against concurrent schema changes and `VACUUM` runs.

Note

Acquired by `VACUUM` (without `FULL`).

SHARE MODE

Conflicts with ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE ROW EXCLUSIVE, EXCLUSIVE and ACCESS EXCLUSIVE modes. This mode protects a table against concurrent data changes.

Note

Acquired by `CREATE INDEX`.

SHARE ROW EXCLUSIVE MODE

Conflicts with ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE and ACCESS EXCLUSIVE modes.

Note

This lock mode is not automatically acquired by any PostgreSQL command.

EXCLUSIVE MODE

Conflicts with ROW SHARE, ROW EXCLUSIVE, SHARE UPDATE EXCLUSIVE, SHARE, SHARE ROW EXCLUSIVE, EXCLUSIVE and ACCESS EXCLUSIVE modes. This mode allows only concurrent ACCESS SHARE, i.e., only reads from the table can proceed in parallel with a transaction holding this lock mode.

Note

This lock mode is not automatically acquired by any PostgreSQL command.

ACCESS EXCLUSIVE MODE

Conflicts with all lock modes. This mode guarantees that the holder is the only transaction accessing the table in any way.

Note

Acquired by `ALTER TABLE`, `DROP TABLE`, and `VACUUM FULL` statements. This is also the default lock mode for `LOCK TABLE` statements that do not specify a mode explicitly.

Outputs

`LOCK TABLE`

The lock was successfully acquired.

`ERROR` *`name`*`: Table does not exist.`

Message returned if *`name`* does not exist.

Description

`LOCK TABLE` obtains a table-level lock, waiting if necessary for any conflicting locks to be released. Once obtained, the lock is held for the remainder of the current transaction. (There is no `UNLOCK TABLE` command; locks are always released at transaction end.)

When acquiring locks automatically for commands that reference tables, PostgreSQL always uses the least restrictive lock mode possible. `LOCK TABLE` provides for cases when you might need more restrictive locking.

For example, suppose an application runs a transaction at READ COMMITTED isolation level and needs to ensure that data in a table remains stable for the duration of the transaction. To achieve this you could obtain SHARE lock mode over the table before querying. This will prevent concurrent data changes and ensure subsequent reads of the table see a stable view of committed data, because SHARE lock mode conflicts with the ROW EXCLUSIVE lock acquired by writers, and your `LOCK TABLE` *`name`* `IN SHARE MODE` statement will wait until any concurrent holders of ROW EXCLUSIVE mode commit or roll back. Thus, once you obtain the lock, there are no uncommitted writes outstanding; furthermore none can begin until you release the lock.

Note

To achieve a similar effect when running a transaction at the SERIALIZABLE isolation level, you have to execute the `LOCK TABLE` statement before executing any DML statement. A serializable transaction's view of data will be frozen when its first DML statement begins. A later `LOCK` will still prevent concurrent writes --- but it won't ensure that what the transaction reads corresponds to the latest committed values.

If a transaction of this sort is going to change the data in the table, then it should use SHARE ROW EXCLUSIVE lock mode instead of SHARE mode. This ensures that only one transaction of this type runs at a time. Without this, a deadlock is possible: two transactions might both acquire SHARE mode, and then be unable to also acquire ROW EXCLUSIVE mode to actually perform their updates. (Note that a transaction's own locks never conflict, so a transaction can acquire ROW EXCLUSIVE mode when it holds SHARE mode --- but not if anyone else holds SHARE mode.)

Two general rules may be followed to prevent deadlock conditions:

- Transactions have to acquire locks on the same objects in the same order.

  For example, if one application updates row R1 and than updates row R2 (in the same transaction) then the second application shouldn't update row R2 if it's going to update row R1 later (in a single transaction). Instead, it should update rows R1 and R2 in the same order as the first application.

- If multiple lock modes are involved for a single object, then transactions should always acquire the most restrictive mode first.

  An example for this rule was given previously when discussing the use of SHARE ROW EXCLUSIVE mode rather than SHARE mode.

PostgreSQL does detect deadlocks and will rollback at least one waiting transaction to resolve the deadlock. If it is not practical to code an application to follow the above rules strictly, an alternative solution is to be prepared to retry transactions when they are aborted by deadlocks.

When locking multiple tables, the command `LOCK a, b;` is equivalent to `LOCK a; LOCK b;`. The tables are locked one-by-one in the order specified in the `LOCK` command.

Notes

`LOCK ... IN ACCESS SHARE MODE` requires `SELECT` privileges on the target table. All other forms of `LOCK` require `UPDATE` and/or `DELETE` privileges.

`LOCK` is useful only inside a transaction block (`BEGIN...COMMIT`), since the lock is dropped as soon as the transaction ends. A `LOCK` command appearing outside any transaction block forms a self-contained transaction, so the lock will be dropped as soon as it is obtained.

RDBMS locking uses the following standard terminology:

EXCLUSIVE

An exclusive lock prevents other locks of the same type from being granted.

SHARE

A shared lock allows others to also hold the same type of lock, but prevents the corresponding EXCLUSIVE lock from being granted.

ACCESS

Locks table schema.

ROW

Locks individual rows.

PostgreSQL does not follow this terminology exactly. `LOCK TABLE` only deals with table-level locks, and so the mode names involving ROW are all misnomers. These mode names should generally be read as indicating the intention of the user to acquire row-level locks within the locked table. Also, ROW EXCLUSIVE mode does not follow this naming convention accurately, since it is a sharable table lock. Keep in mind that all the lock modes have identical semantics so far as `LOCK TABLE` is concerned, differing only in the rules about which modes conflict with which.

Usage

Obtain a SHARE lock on a primary key table when going to perform inserts into a foreign key table:

```
BEGIN WORK;
LOCK TABLE films IN SHARE MODE;
SELECT id FROM films
    WHERE name = 'Star Wars: Episode I - The Phantom Menace';
-- Do ROLLBACK if record was not returned
INSERT INTO films_user_comments VALUES
    (_id_, 'GREAT! I was waiting for it for so long!');
COMMIT WORK;
```

Take a SHARE ROW EXCLUSIVE lock on a primary key table when going to perform a delete operation:

```
BEGIN WORK;
LOCK TABLE films IN SHARE ROW EXCLUSIVE MODE;
DELETE FROM films_user_comments WHERE id IN
    (SELECT id FROM films WHERE rating < 5);
DELETE FROM films WHERE rating < 5;
COMMIT WORK;
```

Compatibility

SQL92

There is no `LOCK TABLE` in SQL92, which instead uses `SET TRANSACTION` to specify concurrency levels on transactions. We support that too; see SET TRANSACTION for details.

Except for ACCESS SHARE, ACCESS EXCLUSIVE, and SHARE UPDATE EXCLUSIVE lock modes, the PostgreSQL lock modes and the `LOCK TABLE` syntax are compatible with those present in Oracle(TM).

Name

MOVE — position a cursor on a specified row of a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
MOVE [ direction ] [ count ]
    { IN | FROM } cursor
```

Description

`MOVE` allows a user to move cursor position a specified number of rows. `MOVE` works like the `FETCH` command, but only positions the cursor and does not return rows.

Refer to FETCH for details on syntax and usage.

Notes

`MOVE` is a PostgreSQL language extension.

Refer to FETCH for a description of valid arguments. Refer to DECLARE to define a cursor. Refer to BEGIN, COMMIT, and ROLLBACK for further information about transactions.

Usage

Set up and use a cursor:

```
BEGIN WORK;
DECLARE liahona CURSOR  FOR SELECT * FROM films;
-- Skip first 5 rows:
MOVE FORWARD 5 IN liahona;
MOVE
-- Fetch 6th row in the cursor liahona:
FETCH 1 IN liahona;
FETCH

 code  | title  | did | date_prod | kind   | len
-------+--------+-----+-----------+--------+-------
 P_303 | 48 Hrs | 103 | 1982-10-22| Action | 01:37
(1 row)
-- close the cursor liahona and commit work:
CLOSE liahona;
COMMIT WORK;
```

Compatibility

SQL92

There is no SQL92 `MOVE` statement. Instead, SQL92 allows one to `FETCH` rows from an absolute cursor position, implicitly moving the cursor to the correct position.

Name

NOTIFY — generate a notification

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
NOTIFY name
```

Inputs

notifyname

Notify condition to be signaled.

Outputs

NOTIFY

Acknowledgement that notify command has executed.

Notify events

Events are delivered to listening frontends; whether and how each frontend application reacts depends on its programming.

Description

The NOTIFY command sends a notify event to each frontend application that has previously executed LISTEN *notifyname* for the specified notify condition in the current database.

The information passed to the frontend for a notify event includes the notify condition name and the notifying backend process's PID. It is up to the database designer to define the condition names that will be used in a given database and what each one means.

Commonly, the notify condition name is the same as the name of some table in the database, and the notify event essentially means “I changed this table, take a look at it to see what's new”. But no such association is enforced by the NOTIFY and LISTEN commands. For example, a database designer could use several different condition names to signal different sorts of changes to a single table.

NOTIFY provides a simple form of signal or IPC (interprocess communication) mechanism for a collection of processes accessing the same PostgreSQL database. Higher-level mechanisms can be built by using tables in the database to pass additional data (beyond a mere condition name) from notifier to listener(s).

When NOTIFY is used to signal the occurrence of changes to a particular table, a useful programming technique is to put the NOTIFY in a rule that is triggered by table updates. In this way, notification happens automatically when the table is changed, and the application programmer can't accidentally forget to do it.

NOTIFY interacts with SQL transactions in some important ways. Firstly, if a NOTIFY is executed inside a transaction, the notify events are not delivered until and unless the transaction is committed. This is appropriate, since if the transaction is aborted we would like all the commands within it to have had no effect, including NOTIFY. But it can be disconcerting if one is expecting the notify events to be delivered immediately. Secondly, if a listening backend receives a notify signal while it is within a transaction, the notify event will not be delivered to its connected frontend until just after the transaction is completed (either committed or aborted). Again, the reasoning is that if a notify were delivered within a transaction that was later aborted, one would want the notification to be undone

somehow---but the backend cannot “take back” a notify once it has sent it to the frontend. So notify events are only delivered between transactions. The upshot of this is that applications using NOTIFY for real-time signaling should try to keep their transactions short.

NOTIFY behaves like Unix signals in one important respect: if the same condition name is signaled multiple times in quick succession, recipients may get only one notify event for several executions of NOTIFY. So it is a bad idea to depend on the number of notifies received. Instead, use NOTIFY to wake up applications that need to pay attention to something, and use a database object (such as a sequence) to keep track of what happened or how many times it happened.

It is common for a frontend that sends NOTIFY to be listening on the same notify name itself. In that case it will get back a notify event, just like all the other listening frontends. Depending on the application logic, this could result in useless work---for example, re-reading a database table to find the same updates that that frontend just wrote out. In PostgreSQL 6.4 and later, it is possible to avoid such extra work by noticing whether the notifying backend process's PID (supplied in the notify event message) is the same as one's own backend's PID (available from libpq). When they are the same, the notify event is one's own work bouncing back, and can be ignored. (Despite what was said in the preceding paragraph, this is a safe technique. PostgreSQL keeps self-notifies separate from notifies arriving from other backends, so you cannot miss an outside notify by ignoring your own notifies.)

Notes

name can be any string valid as a name; it need not correspond to the name of any actual table. If *name* is enclosed in double-quotes, it need not even be a syntactically valid name, but can be any string up to 63 characters long.

In some previous releases of PostgreSQL, *name* had to be enclosed in double-quotes when it did not correspond to any existing table name, even if syntactically valid as a name. That is no longer required.

In PostgreSQL releases prior to 6.4, the backend PID delivered in a notify message was always the PID of the frontend's own backend. So it was not possible to distinguish one's own notifies from other clients' notifies in those earlier releases.

Usage

Configure and execute a listen/notify sequence from psql:

```
LISTEN virtual;
NOTIFY virtual;
Asynchronous NOTIFY 'virtual' from backend with pid '8448'
 received.
```

Compatibility

SQL92

There is no NOTIFY statement in SQL92.

Name

PREPARE — create a prepared query

Synopsis

<refsynopsisdivinfo>2002-08-12</refsynopsisdivinfo>

```
PREPARE plan_name [ (datatype [, ...] ) ] AS query
```

Inputs

plan_name

An arbitrary name given to this particular prepared query. It must be unique within a single session, and is used to execute or remove a previously prepared query.

datatype

The data-type of a parameter to the prepared query. To refer to the parameters in the prepared query itself, use `$1`, `$2`, etc.

Outputs

`PREPARE`

The query has been prepared successfully.

Description

`PREPARE` creates a prepared query. A prepared query is a server-side object that can be used to optimize performance. When the `PREPARE` statement is executed, the specified query is parsed, rewritten, and planned. When a subsequent `EXECUTE` statement is issued, the prepared query need only be executed. Thus, the parsing, rewriting, and planning stages are only performed once, instead of every time the query is executed.

Prepared queries can take parameters: values that are substituted into the query when it is executed. To specify the parameters to a prepared query, include a list of data-types with the `PREPARE` statement. In the query itself, you can refer to the parameters by position using `$1`, `$2`, etc. When executing the query, specify the actual values for these parameters in the `EXECUTE` statement -- refer to EXECUTE for more information.

Prepared queries are stored locally (in the current backend), and only exist for the duration of the current database session. When the client exits, the prepared query is forgotten, and so it must be re-created before being used again. This also means that a single prepared query cannot be used by multiple simultaneous database clients; however, each client can create their own prepared query to use.

Prepared queries have the largest performance advantage when a single backend is being used to execute a large number of similar queries. The performance difference will be particularly significant if the queries are complex to plan or rewrite. For example, if the query involves a join of many tables or requires the application of several rules. If the query is relatively simple to plan and rewrite but relatively expensive to execute, the performance advantage of prepared queries will be less noticeable.

Notes

In some situations, the query plan produced by PostgreSQL for a prepared query may be inferior to the plan produced if the query were submitted and executed normally. This is because when the query

is planned (and the optimizer attempts to determine the optimal query plan), the actual values of any parameters specified in the query are unavailable. PostgreSQL collects statistics on the distribution of data in the table, and can use constant values in a query to make guesses about the likely result of executing the query. Since this data is unavailable when planning prepared queries with parameters, the chosen plan may be sub-optimal.

For more information on query planning and the statistics collected by PostgreSQL for query optimization purposes, see the ANALYZE documentation.

Compatibility

SQL92

SQL92 includes a `PREPARE` statement, but it is only for use in embedded SQL clients. The `PREPARE` statement implemented by PostgreSQL also uses a somewhat different syntax.

Name

REINDEX — rebuild corrupted indexes

Synopsis

<refsynopsisdivinfo>2000-03-30</refsynopsisdivinfo>

```
REINDEX { TABLE | DATABASE | INDEX } name [ FORCE ]
```

Inputs

TABLE

Recreate all indexes of a specified table.

DATABASE

Recreate all system indexes of a specified database. (User-table indexes are not included.)

INDEX

Recreate a specified index.

name

The name of the specific table/database/index to be reindexed. Table and index names may be schema-qualified.

FORCE

Force rebuild of system indexes. Without this keyword `REINDEX` skips system indexes that are not marked invalid. FORCE is irrelevant for `REINDEX INDEX`, or when reindexing user indexes.

Outputs

`REINDEX`

Message returned if the table is successfully reindexed.

Description

`REINDEX` is used to rebuild corrupted indexes. Although in theory this should never be necessary, in practice indexes may become corrupted due to software bugs or hardware failures. `REINDEX` provides a recovery method.

`REINDEX` also removes certain dead index pages that can't be reclaimed any other way. See the "Routine Reindexing" section in the manual for more information.

If you suspect corruption of an index on a user table, you can simply rebuild that index, or all indexes on the table, using `REINDEX INDEX` or `REINDEX TABLE`.

Note

Another approach to dealing with a corrupted user-table index is just to drop and recreate it. This may in fact be preferable if you would like to maintain some semblance of normal operation on the table meanwhile. `REINDEX` acquires exclusive lock on the table, while `CREATE INDEX` only locks out writes not reads of the table.

Things are more difficult if you need to recover from corruption of an index on a system table. In this case it's important for the backend doing the recovery to not have used any of the suspect indexes itself. (Indeed, in this sort of scenario you may find that backends are crashing immediately at start-up, due to reliance on the corrupted indexes.) To recover safely, the postmaster must be shut down and a stand-alone PostgreSQL backend must be started instead, giving it the command-line options -O and -P (these options allow system table modifications and prevent use of system indexes, respectively). Then issue `REINDEX INDEX`, `REINDEX TABLE`, or `REINDEX DATABASE` depending on how much you want to reconstruct. If in doubt, use `REINDEX DATABASE FORCE` to force reconstruction of all system indexes in the database. Then quit the standalone backend and restart the postmaster.

Since this is likely the only situation when most people will ever use a standalone backend, some usage notes might be in order:

- Start the backend with a command like

  `postgres -D $PGDATA -O -P my_database`

  Provide the correct path to the database area with `-D`, or make sure that the environment variable `PGDATA` is set. Also specify the name of the particular database you want to work in.

- You can issue any SQL command, not only `REINDEX`.

- Be aware that the standalone backend treats newline as the command entry terminator; there is no intelligence about semicolons, as there is in psql. To continue a command across multiple lines, you must type backslash just before each newline except the last one. Also, you won't have any of the conveniences of command-line editing (no command history, for example).

- To quit the backend, type EOF (**Control**+**D**, usually).

See the postgres reference page for more information.

Usage

Recreate the indexes on the table `mytable`:

```
REINDEX TABLE mytable;
```

Rebuild a single index:

```
REINDEX INDEX my_index;
```

Rebuild all system indexes (this will only work in a standalone backend):

```
REINDEX DATABASE my_database FORCE;
```

Compatibility

SQL92

There is no `REINDEX` in SQL92.

Name

RESET — restore the value of a run-time parameter to a default value

Synopsis

```
RESET variable

RESET ALL
```

Inputs

variable

The name of a run-time parameter. See SET for a list.

ALL

Resets all settable run-time parameters to default values.

Description

`RESET` restores run-time parameters to their default values. Refer to SET for details. `RESET` is an alternate spelling for

```
SET variable TO DEFAULT
```

The default value is defined as the value that the variable would have had, had no `SET` ever been issued for it in the current session. The actual source of this value might be a compiled-in default, the postmaster's configuration file or command-line switches, or per-database or per-user default settings. See the *Administrator's Guide* for details.

See the `SET` manual page for details on the transaction behavior of `RESET`.

Diagnostics

See under the SET command.

Examples

Set `DateStyle` to its default value:

```
RESET DateStyle;
```

Set `geqo` to its default value:

```
RESET GEQO;
```

Compatibility

`RESET` is a PostgreSQL extension.

Name

REVOKE — remove access privileges

Synopsis

```
REVOKE { { SELECT | INSERT | UPDATE | DELETE | RULE | REFERENCES |
 TRIGGER }
    [,...] | ALL [ PRIVILEGES ] }
    ON [ TABLE ] tablename [, ...]
    FROM { username | GROUP groupname | PUBLIC } [, ...]

REVOKE { { CREATE | TEMPORARY | TEMP } [,...] | ALL
 [ PRIVILEGES ] }
    ON DATABASE dbname [, ...]
    FROM { username | GROUP groupname | PUBLIC } [, ...]

REVOKE { EXECUTE | ALL [ PRIVILEGES ] }
    ON FUNCTION funcname ([type, ...]) [, ...]
    FROM { username | GROUP groupname | PUBLIC } [, ...]

REVOKE { USAGE | ALL [ PRIVILEGES ] }
    ON LANGUAGE langname [, ...]
    FROM { username | GROUP groupname | PUBLIC } [, ...]

REVOKE { { CREATE | USAGE } [,...] | ALL [ PRIVILEGES ] }
    ON SCHEMA schemaname [, ...]
    FROM { username | GROUP groupname | PUBLIC } [, ...]
```

Description

`REVOKE` allows the creator of an object to revoke previously granted permissions from one or more users or groups of users. The key word `PUBLIC` refers to the implicitly defined group of all users.

Note that any particular user will have the sum of privileges granted directly to him, privileges granted to any group he is presently a member of, and privileges granted to `PUBLIC`. Thus, for example, revoking SELECT privilege from `PUBLIC` does not necessarily mean that all users have lost SELECT privilege on the object: those who have it granted directly or via a group will still have it.

See the description of the GRANT command for the meaning of the privilege types.

Notes

Use psql's `\z` command to display the privileges granted on existing objects. See also GRANT for information about the format.

Examples

Revoke insert privilege for the public on table `films`:

```
REVOKE INSERT ON films FROM PUBLIC;
```

Revoke all privileges from user `manuel` on view `kinds`:

```
REVOKE ALL PRIVILEGES ON kinds FROM manuel;
```

Compatibility

SQL92

The compatibility notes of the GRANT command apply analogously to `REVOKE`. The syntax summary is:

```
REVOKE [ GRANT OPTION FOR ] { SELECT | INSERT | UPDATE | DELETE |
 REFERENCES }
    ON object [ ( column [, ...] ) ]
    FROM { PUBLIC | username [, ...] }
    { RESTRICT | CASCADE }
```

If user1 gives a privilege WITH GRANT OPTION to user2, and user2 gives it to user3 then user1 can revoke this privilege in cascade using the CASCADE keyword. If user1 gives a privilege WITH GRANT OPTION to user2, and user2 gives it to user3, then if user1 tries to revoke this privilege it fails if he specifies the RESTRICT keyword.

See Also

GRANT

Name

ROLLBACK — abort the current transaction

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
ROLLBACK [ WORK | TRANSACTION ]
```

Inputs

None.

Outputs

`ROLLBACK`

Message returned if successful.

`WARNING: ROLLBACK: no transaction in progress`

If there is not any transaction currently in progress.

Description

`ROLLBACK` rolls back the current transaction and causes all the updates made by the transaction to be discarded.

Notes

Use COMMIT to successfully terminate a transaction. ABORT is a synonym for `ROLLBACK`.

Usage

To abort all changes:

```
ROLLBACK WORK;
```

Compatibility

SQL92

SQL92 only specifies the two forms `ROLLBACK` and `ROLLBACK WORK`. Otherwise full compatibility.

Name

SELECT — retrieve rows from a table or view

Synopsis

<refsynopsisdivinfo>2000-12-11</refsynopsisdivinfo>

```
SELECT [ ALL | DISTINCT [ ON ( expression [, ...] ) ] ]
    * | expression [ AS output_name ] [, ...]
    [ FROM from_item [, ...] ]
    [ WHERE condition ]
    [ GROUP BY expression [, ...] ]
    [ HAVING condition [, ...] ]
    [ { UNION | INTERSECT | EXCEPT } [ ALL ] select ]
    [ ORDER BY expression [ ASC | DESC | USING operator ] [, ...] ]
    [ LIMIT { count | ALL } ]
    [ OFFSET start ]
    [ FOR UPDATE [ OF tablename [, ...] ] ]

where from_item can be:

[ ONLY ] table_name [ * ]
    [ [ AS ] alias [ ( column_alias_list ) ] ]
|
( select )
    [ AS ] alias [ ( column_alias_list ) ]
|
table_function_name ( [ argument [, ...] ] )
    [ AS ] alias [ ( column_alias_list | column_definition_list ) ]
|
table_function_name ( [ argument [, ...] ] )
    AS ( column_definition_list )
|
from_item [ NATURAL ] join_type from_item
    [ ON join_condition | USING ( join_column_list ) ]
```

Inputs

expression

The name of a table's column or an expression.

output_name

Specifies another name for an output column using the AS clause. This name is primarily used to label the column for display. It can also be used to refer to the column's value in ORDER BY and GROUP BY clauses. But the *output_name* cannot be used in the WHERE or HAVING clauses; write out the expression instead.

from_item

A table reference, sub-SELECT, table function, or JOIN clause. See below for details.

condition

A Boolean expression giving a result of true or false. See the WHERE and HAVING clause descriptions below.

select

A select statement with all features except the ORDER BY, LIMIT/OFFSET, and FOR UPDATE clauses (even those can be used when the select is parenthesized).

FROM items can contain:

table_name

The name (optionally schema-qualified) of an existing table or view. If `ONLY` is specified, only that table is scanned. If `ONLY` is not specified, the table and all its descendant tables (if any) are scanned. `*` can be appended to the table name to indicate that descendant tables are to be scanned, but in the current version, this is the default behavior. (In releases before 7.1, `ONLY` was the default behavior.) The default behavior can be modified by changing the `SQL_INHERITANCE` configuration option.

alias

A substitute name for the FROM item containing the alias. An alias is used for brevity or to eliminate ambiguity for self-joins (where the same table is scanned multiple times). When an alias is provided, it completely hides the actual name of the table or table function; for example given `FROM foo AS f`, the remainder of the SELECT must refer to this FROM item as `f` not `foo`. If an alias is written, a column alias list can also be written to provide substitute names for one or more columns of the table.

select

A sub-SELECT can appear in the FROM clause. This acts as though its output were created as a temporary table for the duration of this single SELECT command. Note that the sub-SELECT must be surrounded by parentheses, and an alias *must* be provided for it.

table function

A table function can appear in the FROM clause. This acts as though its output were created as a temporary table for the duration of this single SELECT command. An alias may also be used. If an alias is written, a column alias list can also be written to provide substitute names for one or more columns of the table function. If the table function has been defined as returning the `record` data type, an alias, or the keyword `AS`, must be present, followed by a column definition list in the form (*column_name data_type* [, ...]). The column definition list must match the actual number and types of columns returned by the function.

join_type

One of `[ INNER ] JOIN`, `LEFT [ OUTER ] JOIN`, `RIGHT [ OUTER ] JOIN`, `FULL [ OUTER ] JOIN`, or `CROSS JOIN`. For INNER and OUTER join types, exactly one of NATURAL, ON *join_condition*, or USING (*join_column_list*) must appear. For CROSS JOIN, none of these items may appear.

join_condition

A qualification condition. This is similar to the WHERE condition except that it only applies to the two from_items being joined in this JOIN clause.

join_column_list

A USING column list (a, b, ...) is shorthand for the ON condition left_table.a = right_table.a AND left_table.b = right_table.b ...

Outputs

Rows

The complete set of rows resulting from the query specification.

count

The count of rows returned by the query.

Description

SELECT will return rows from one or more tables. Candidates for selection are rows which satisfy the WHERE condition; if WHERE is omitted, all rows are candidates. (See WHERE Clause .)

Actually, the returned rows are not directly the rows produced by the FROM/WHERE/GROUP BY/HAVING clauses; rather, the output rows are formed by computing the SELECT output expressions for each selected row. * can be written in the output list as a shorthand for all the columns of the selected rows. Also, one can write *table_name*.* as a shorthand for the columns coming from just that table.

DISTINCT will eliminate duplicate rows from the result. ALL (the default) will return all candidate rows, including duplicates.

DISTINCT ON eliminates rows that match on all the specified expressions, keeping only the first row of each set of duplicates. The DISTINCT ON expressions are interpreted using the same rules as for ORDER BY items; see below. Note that the “first row” of each set is unpredictable unless ORDER BY is used to ensure that the desired row appears first. For example,

```
SELECT DISTINCT ON (location) location, time, report
FROM weatherReports
ORDER BY location, time DESC;
```

retrieves the most recent weather report for each location. But if we had not used ORDER BY to force descending order of time values for each location, we'd have gotten a report of unpredictable age for each location.

The GROUP BY clause allows a user to divide a table into groups of rows that match on one or more values. (See GROUP BY Clause .)

The HAVING clause allows selection of only those groups of rows meeting the specified condition. (See HAVING Clause .)

The ORDER BY clause causes the returned rows to be sorted in a specified order. If ORDER BY is not given, the rows are returned in whatever order the system finds cheapest to produce. (See ORDER BY Clause .)

SELECT queries can be combined using UNION, INTERSECT, and EXCEPT operators. Use parentheses if necessary to determine the ordering of these operators.

The UNION operator computes the collection of rows returned by the queries involved. Duplicate rows are eliminated unless ALL is specified. (See UNION Clause .)

The INTERSECT operator computes the rows that are common to both queries. Duplicate rows are eliminated unless ALL is specified. (See INTERSECT Clause .)

The EXCEPT operator computes the rows returned by the first query but not the second query. Duplicate rows are eliminated unless ALL is specified. (See EXCEPT Clause .)

The LIMIT clause allows a subset of the rows produced by the query to be returned to the user. (See LIMIT Clause .)

The FOR UPDATE clause causes the SELECT statement to lock the selected rows against concurrent updates.

You must have SELECT privilege to a table to read its values (See the GRANT/REVOKE statements). Use of FOR UPDATE requires UPDATE privilege as well.

FROM Clause

The FROM clause specifies one or more source tables for the SELECT. If multiple sources are specified, the result is conceptually the Cartesian product of all the rows in all the sources --- but usually qualification conditions are added to restrict the returned rows to a small subset of the Cartesian product.

When a FROM item is a simple table name, it implicitly includes rows from sub-tables (inheritance children) of the table. ONLY will suppress rows from sub-tables of the table. Before PostgreSQL 7.1, this was the default result, and adding sub-tables was done by appending * to the table name. This old behavior is available via the command SET SQL_Inheritance TO OFF.

A FROM item can also be a parenthesized sub-SELECT (note that an alias clause is required for a sub-SELECT!). This is an extremely handy feature since it's the only way to get multiple levels of grouping, aggregation, or sorting in a single query.

A FROM item can be a table function (typically, a function that returns multiple rows and/or columns, though actually any function can be used). The function is invoked with the given argument value(s), and then its output is scanned as though it were a table.

In some cases it is useful to define table functions that can return different column sets depending on how they are invoked. To support this, the table function can be declared as returning the pseudo-type record. When such a function is used in FROM, it must be followed by an alias, or the keyword AS alone, and then by a parenthesized list of column names and types. This provides a query-time composite type definition. The composite type definition must match the actual composite type returned from the function, or an error will be reported at run-time.

Finally, a FROM item can be a JOIN clause, which combines two simpler FROM items. (Use parentheses if necessary to determine the order of nesting.)

A CROSS JOIN or INNER JOIN is a simple Cartesian product, the same as you get from listing the two items at the top level of FROM. CROSS JOIN is equivalent to INNER JOIN ON (TRUE), that is, no rows are removed by qualification. These join types are just a notational convenience, since they do nothing you couldn't do with plain FROM and WHERE.

LEFT OUTER JOIN returns all rows in the qualified Cartesian product (i.e., all combined rows that pass its ON condition), plus one copy of each row in the left-hand table for which there was no right-hand row that passed the ON condition. This left-hand row is extended to the full width of the joined table by inserting null values for the right-hand columns. Note that only the JOIN's own ON or USING condition is considered while deciding which rows have matches. Outer ON or WHERE conditions are applied afterwards.

Conversely, RIGHT OUTER JOIN returns all the joined rows, plus one row for each unmatched right-hand row (extended with nulls on the left). This is just a notational convenience, since you could convert it to a LEFT OUTER JOIN by switching the left and right inputs.

FULL OUTER JOIN returns all the joined rows, plus one row for each unmatched left-hand row (extended with nulls on the right), plus one row for each unmatched right-hand row (extended with nulls on the left).

For all the JOIN types except CROSS JOIN, you must write exactly one of ON *join_condition*, USING (*join_column_list*), or NATURAL. ON is the most general case: you can write any qualification expression involving the two tables to be joined. A USING column list (a, b, ...) is shorthand for the ON condition left_table.a = right_table.a AND left_table.b = right_table.b ... Also, USING implies that only one of each pair of equivalent columns will be included in the JOIN output, not both. NATURAL is shorthand for a USING list that mentions all similarly-named columns in the tables.

WHERE Clause

The optional WHERE condition has the general form:

```
WHERE boolean_expr
```

boolean_expr can consist of any expression which evaluates to a Boolean value. In many cases, this expression will be:

```
expr cond_op expr
```

or

```
log_op expr
```

where *cond_op* can be one of: =, <, <=, >, >= or <>, a conditional operator like ALL, ANY, IN, LIKE, or a locally defined operator, and *log_op* can be one of: AND, OR, NOT. SELECT will ignore all rows for which the WHERE condition does not return TRUE.

GROUP BY Clause

GROUP BY specifies a grouped table derived by the application of this clause:

```
GROUP BY expression [, ...]
```

GROUP BY will condense into a single row all selected rows that share the same values for the grouped columns. Aggregate functions, if any, are computed across all rows making up each group, producing a separate value for each group (whereas without GROUP BY, an aggregate produces a single value computed across all the selected rows). When GROUP BY is present, it is not valid for the SELECT output expression(s) to refer to ungrouped columns except within aggregate functions, since there would be more than one possible value to return for an ungrouped column.

A GROUP BY item can be an input column name, or the name or ordinal number of an output column (SELECT expression), or it can be an arbitrary expression formed from input-column values. In case of ambiguity, a GROUP BY name will be interpreted as an input-column name rather than an output column name.

HAVING Clause

The optional HAVING condition has the general form:

```
HAVING boolean_expr
```

where *boolean_expr* is the same as specified for the WHERE clause.

HAVING specifies a grouped table derived by the elimination of group rows that do not satisfy the *boolean_expr*. HAVING is different from WHERE: WHERE filters individual rows before application of GROUP BY, while HAVING filters group rows created by GROUP BY.

Each column referenced in *boolean_expr* shall unambiguously reference a grouping column, unless the reference appears within an aggregate function.

ORDER BY Clause

```
ORDER BY expression [ ASC | DESC | USING operator ] [, ...]
```

An ORDER BY item can be the name or ordinal number of an output column (SELECT expression), or it can be an arbitrary expression formed from input-column values. In case of ambiguity, an ORDER BY name will be interpreted as an output-column name.

The ordinal number refers to the ordinal (left-to-right) position of the result column. This feature makes it possible to define an ordering on the basis of a column that does not have a unique name. This is never absolutely necessary because it is always possible to assign a name to a result column using the AS clause, e.g.:

```
SELECT title, date_prod + 1 AS newlen FROM films ORDER BY newlen;
```

It is also possible to ORDER BY arbitrary expressions (an extension to SQL92), including fields that do not appear in the SELECT result list. Thus the following statement is legal:

```
SELECT name FROM distributors ORDER BY code;
```

A limitation of this feature is that an ORDER BY clause applying to the result of a UNION, INTERSECT, or EXCEPT query may only specify an output column name or number, not an expression.

Note that if an ORDER BY item is a simple name that matches both a result column name and an input column name, ORDER BY will interpret it as the result column name. This is the opposite of the choice that GROUP BY will make in the same situation. This inconsistency is mandated by the SQL92 standard.

Optionally one may add the key word `DESC` (descending) or `ASC` (ascending) after each column name in the `ORDER BY` clause. If not specified, `ASC` is assumed by default. Alternatively, a specific ordering operator name may be specified. `ASC` is equivalent to `USING <` and `DESC` is equivalent to `USING >`.

The null value sorts higher than any other value in a domain. In other words, with ascending sort order nulls sort at the end and with descending sort order nulls sort at the beginning.

Data of character types is sorted according to the locale-specific collation order that was established when the database cluster was initialized.

UNION Clause

```
table_query UNION [ ALL ] table_query
    [ ORDER BY expression [ ASC | DESC | USING operator ] [, ...] ]
    [ LIMIT { count | ALL } ]
    [ OFFSET start ]
```

where *table_query* specifies any select expression without an ORDER BY, LIMIT, or FOR UPDATE clause. (ORDER BY and LIMIT can be attached to a sub-expression if it is enclosed in parentheses. Without parentheses, these clauses will be taken to apply to the result of the UNION, not to its right-hand input expression.)

The UNION operator computes the collection (set union) of the rows returned by the queries involved. The two SELECT statements that represent the direct operands of the UNION must produce the same number of columns, and corresponding columns must be of compatible data types.

The result of UNION does not contain any duplicate rows unless the ALL option is specified. ALL prevents elimination of duplicates.

Multiple UNION operators in the same SELECT statement are evaluated left to right, unless otherwise indicated by parentheses.

Currently, FOR UPDATE may not be specified either for a UNION result or for the inputs of a UNION.

INTERSECT Clause

```
table_query INTERSECT [ ALL ] table_query
    [ ORDER BY expression [ ASC | DESC | USING operator ] [, ...] ]
    [ LIMIT { count | ALL } ]
    [ OFFSET start ]
```

where *table_query* specifies any select expression without an ORDER BY, LIMIT, or FOR UPDATE clause.

INTERSECT is similar to UNION, except that it produces only rows that appear in both query outputs, rather than rows that appear in either.

The result of INTERSECT does not contain any duplicate rows unless the ALL option is specified. With ALL, a row that has m duplicates in L and n duplicates in R will appear min(m,n) times.

Multiple INTERSECT operators in the same SELECT statement are evaluated left to right, unless parentheses dictate otherwise. INTERSECT binds more tightly than UNION --- that is, A UNION B INTERSECT C will be read as A UNION (B INTERSECT C) unless otherwise specified by parentheses.

EXCEPT Clause

```
table_query EXCEPT [ ALL ] table_query
    [ ORDER BY expression [ ASC | DESC | USING operator ] [, ...] ]
    [ LIMIT { count | ALL } ]
    [ OFFSET start ]
```

where *table_query* specifies any select expression without an ORDER BY, LIMIT, or FOR UPDATE clause.

EXCEPT is similar to UNION, except that it produces only rows that appear in the left query's output but not in the right query's output.

The result of EXCEPT does not contain any duplicate rows unless the ALL option is specified. With ALL, a row that has m duplicates in L and n duplicates in R will appear max(m-n,0) times.

Multiple EXCEPT operators in the same SELECT statement are evaluated left to right, unless parentheses dictate otherwise. EXCEPT binds at the same level as UNION.

LIMIT Clause

```
LIMIT { count | ALL }
OFFSET start
```

where *count* specifies the maximum number of rows to return, and *start* specifies the number of rows to skip before starting to return rows.

LIMIT allows you to retrieve just a portion of the rows that are generated by the rest of the query. If a limit count is given, no more than that many rows will be returned. If an offset is given, that many rows will be skipped before starting to return rows.

When using LIMIT, it is a good idea to use an ORDER BY clause that constrains the result rows into a unique order. Otherwise you will get an unpredictable subset of the query's rows---you may be asking

for the tenth through twentieth rows, but tenth through twentieth in what ordering? You don't know what ordering unless you specify ORDER BY.

As of PostgreSQL 7.0, the query optimizer takes LIMIT into account when generating a query plan, so you are very likely to get different plans (yielding different row orders) depending on what you use for LIMIT and OFFSET. Thus, using different LIMIT/OFFSET values to select different subsets of a query result *will give inconsistent results* unless you enforce a predictable result ordering with ORDER BY. This is not a bug; it is an inherent consequence of the fact that SQL does not promise to deliver the results of a query in any particular order unless ORDER BY is used to constrain the order.

FOR UPDATE Clause

```
FOR UPDATE [ OF tablename [, ...] ]
```

FOR UPDATE causes the rows retrieved by the query to be locked as though for update. This prevents them from being modified or deleted by other transactions until the current transaction ends; that is, other transactions that attempt UPDATE, DELETE, or SELECT FOR UPDATE of these rows will be blocked until the current transaction ends. Also, if an UPDATE, DELETE, or SELECT FOR UPDATE from another transaction has already locked a selected row or rows, SELECT FOR UPDATE will wait for the other transaction to complete, and will then lock and return the updated row (or no row, if the row was deleted). For further discussion see the concurrency chapter of the *User's Guide*.

If specific tables are named in FOR UPDATE, then only rows coming from those tables are locked; any other tables used in the SELECT are simply read as usual.

FOR UPDATE cannot be used in contexts where returned rows can't be clearly identified with individual table rows; for example it can't be used with aggregation.

FOR UPDATE may appear before LIMIT for compatibility with pre-7.3 applications. However, it effectively executes after LIMIT, and so that is the recommended place to write it.

Usage

To join the table `films` with the table `distributors`:

```
SELECT f.title, f.did, d.name, f.date_prod, f.kind
    FROM distributors d, films f
    WHERE f.did = d.did

           title           | did |   name           | date_prod  |
 kind
---------------------------+-----+------------------+------------
+----------
 The Third Man             | 101 | British Lion     | 1949-12-23 |
 Drama
 The African Queen         | 101 | British Lion     | 1951-08-11 |
 Romantic
 Une Femme est une Femme   | 102 | Jean Luc Godard  | 1961-03-12 |
 Romantic
 Vertigo                   | 103 | Paramount        | 1958-11-14 |
 Action
 Becket                    | 103 | Paramount        | 1964-02-03 |
 Drama
 48 Hrs                    | 103 | Paramount        | 1982-10-22 |
 Action
 War and Peace             | 104 | Mosfilm          | 1967-02-12 |
 Drama
```

```
 West Side Story           | 105 | United Artists   | 1961-01-03 |
 Musical
 Bananas                   | 105 | United Artists   | 1971-07-13 |
 Comedy
 Yojimbo                   | 106 | Toho             | 1961-06-16 |
 Drama
 There's a Girl in my Soup | 107 | Columbia         | 1970-06-11 |
 Comedy
 Taxi Driver               | 107 | Columbia         | 1975-05-15 |
 Action
 Absence of Malice         | 107 | Columbia         | 1981-11-15 |
 Action
 Storia di una donna       | 108 | Westward         | 1970-08-15 |
 Romantic
 The King and I            | 109 | 20th Century Fox | 1956-08-11 |
 Musical
 Das Boot                  | 110 | Bavaria Atelier  | 1981-11-11 |
 Drama
 Bed Knobs and Broomsticks | 111 | Walt Disney      |            |
 Musical
(17 rows)
```

To sum the column `len` of all films and group the results by `kind`:

```
SELECT kind, SUM(len) AS total FROM films GROUP BY kind;
```

```
   kind   | total
----------+-------
 Action   | 07:34
 Comedy   | 02:58
 Drama    | 14:28
 Musical  | 06:42
 Romantic | 04:38
(5 rows)
```

To sum the column `len` of all films, group the results by `kind` and show those group totals that are less than 5 hours:

```
SELECT kind, SUM(len) AS total
    FROM films
    GROUP BY kind
    HAVING SUM(len) < INTERVAL '5 hour';
```

```
 kind     | total
----------+-------
 Comedy   | 02:58
 Romantic | 04:38
(2 rows)
```

The following two examples are identical ways of sorting the individual results according to the contents of the second column (`name`):

```
SELECT * FROM distributors ORDER BY name;
SELECT * FROM distributors ORDER BY 2;
```

```
 did |       name
-----+------------------
 109 | 20th Century Fox
 110 | Bavaria Atelier
```

```
 101 | British Lion
 107 | Columbia
 102 | Jean Luc Godard
 113 | Luso films
 104 | Mosfilm
 103 | Paramount
 106 | Toho
 105 | United Artists
 111 | Walt Disney
 112 | Warner Bros.
 108 | Westward
(13 rows)
```

This example shows how to obtain the union of the tables `distributors` and `actors`, restricting the results to those that begin with letter W in each table. Only distinct rows are wanted, so the ALL keyword is omitted:

```
distributors:               actors:
 did |     name              id |     name
-----+--------------        ----+----------------
 108 | Westward               1 | Woody Allen
 111 | Walt Disney            2 | Warren Beatty
 112 | Warner Bros.           3 | Walter Matthau
 ...                          ...

SELECT distributors.name
    FROM   distributors
    WHERE  distributors.name LIKE 'W%'
UNION
SELECT actors.name
    FROM   actors
    WHERE  actors.name LIKE 'W%';

      name
----------------
 Walt Disney
 Walter Matthau
 Warner Bros.
 Warren Beatty
 Westward
 Woody Allen
```

This example shows how to use a table function, both with and without a column definition list.

```
distributors:
 did |     name
-----+--------------
 108 | Westward
 111 | Walt Disney
 112 | Warner Bros.
 ...

CREATE FUNCTION distributors(int)
  RETURNS SETOF distributors AS '
  SELECT * FROM distributors WHERE did = $1;
  ' LANGUAGE SQL;

SELECT * FROM distributors(111);
 did |    name
```

```
-----+-------------
 111 | Walt Disney
(1 row)

CREATE FUNCTION distributors_2(int)
  RETURNS SETOF RECORD AS '
  SELECT * FROM distributors WHERE did = $1;
  ' LANGUAGE SQL;

SELECT * FROM distributors_2(111) AS (f1 int, f2 text);
 f1  |     f2
-----+-------------
 111 | Walt Disney
(1 row)
```

Compatibility

Extensions

PostgreSQL allows one to omit the `FROM` clause from a query. This feature was retained from the original PostQUEL query language. It has a straightforward use to compute the results of simple expressions:

```
SELECT 2+2;

 ?column?
----------
        4
```

Some other SQL databases cannot do this except by introducing a dummy one-row table to do the select from. A less obvious use is to abbreviate a normal select from one or more tables:

```
SELECT distributors.* WHERE distributors.name = 'Westward';

 did | name
-----+----------
 108 | Westward
```

This works because an implicit FROM item is added for each table that is referenced in the query but not mentioned in FROM. While this is a convenient shorthand, it's easy to misuse. For example, the query

```
SELECT distributors.* FROM distributors d;
```

is probably a mistake; most likely the user meant

```
SELECT d.* FROM distributors d;
```

rather than the unconstrained join

```
SELECT distributors.* FROM distributors d, distributors
 distributors;
```

that he will actually get. To help detect this sort of mistake, PostgreSQL 7.1 and later will warn if the implicit-FROM feature is used in a query that also contains an explicit FROM clause.

The table-function feature is a PostgreSQL extension.

SQL92

SELECT Clause

In the SQL92 standard, the optional keyword `AS` is just noise and can be omitted without affecting the meaning. The PostgreSQL parser requires this keyword when renaming output columns because the type extensibility features lead to parsing ambiguities in this context. `AS` is optional in FROM items, however.

The DISTINCT ON phrase is not part of SQL92. Nor are LIMIT and OFFSET.

In SQL92, an ORDER BY clause may only use result column names or numbers, while a GROUP BY clause may only use input column names. PostgreSQL extends each of these clauses to allow the other choice as well (but it uses the standard's interpretation if there is ambiguity). PostgreSQL also allows both clauses to specify arbitrary expressions. Note that names appearing in an expression will always be taken as input-column names, not as result-column names.

UNION/INTERSECT/EXCEPT Clause

The SQL92 syntax for UNION/INTERSECT/EXCEPT allows an additional CORRESPONDING BY option:

```
table_query UNION [ALL]
    [CORRESPONDING [BY (column [,...])]]
    table_query
```

The CORRESPONDING BY clause is not supported by PostgreSQL.

Name

SELECT INTO — create a new table from the results of a query

Synopsis

<refsynopsisdivinfo>2000-12-11</refsynopsisdivinfo>

```
SELECT [ ALL | DISTINCT [ ON ( expression [, ...] ) ] ]
    * | expression [ AS output_name ] [, ...]
    INTO [ TEMPORARY | TEMP ] [ TABLE ] new_table
    [ FROM from_item [, ...] ]
    [ WHERE condition ]
    [ GROUP BY expression [, ...] ]
    [ HAVING condition [, ...] ]
    [ { UNION | INTERSECT | EXCEPT } [ ALL ] select ]
    [ ORDER BY expression [ ASC | DESC | USING operator ] [, ...] ]
    [ LIMIT { count | ALL } ]
    [ OFFSET start ]
    [ FOR UPDATE [ OF tablename [, ...] ] ]
```

Inputs

TEMPORARY
TEMP

If specified, the table is created as a temporary table. Refer to CREATE TABLE for details.

new_table

The name (optionally schema-qualified) of the table to be created.

All other inputs are described in detail for SELECT.

Outputs

Refer to CREATE TABLE and SELECT for a summary of possible output messages.

Description

`SELECT INTO` creates a new table and fills it with data computed by a query. The data is not returned to the client, as it is with a normal `SELECT`. The new table's columns have the names and data types associated with the output columns of the `SELECT`.

Note

CREATE TABLE AS is functionally equivalent to `SELECT INTO`. `CREATE TABLE AS` is the recommended syntax, since `SELECT INTO` is not standard. In fact, this form of `SELECT INTO` is not available in PL/pgSQL or ecpg, because they interpret the INTO clause differently.

Compatibility

SQL92 uses `SELECT ... INTO` to represent selecting values into scalar variables of a host program, rather than creating a new table. This indeed is the usage found in PL/pgSQL and ecpg. The PostgreSQL usage of `SELECT INTO` to represent table creation is historical. It's best to use `CREATE TABLE AS` for this purpose in new code. (`CREATE TABLE AS` isn't standard either, but it's less likely to cause confusion.)

Name

SET — change a run-time parameter

Synopsis

```
SET [ SESSION | LOCAL ] variable { TO | = } { value | 'value' |
 DEFAULT }
SET [ SESSION | LOCAL ] TIME ZONE { timezone | LOCAL | DEFAULT }
```

Inputs

`SESSION`

Specifies that the command takes effect for the current session. (This is the default if neither `SESSION` nor `LOCAL` appears.)

`LOCAL`

Specifies that the command takes effect for only the current transaction. After `COMMIT` or `ROLLBACK`, the session-level setting takes effect again. Note that `SET LOCAL` will appear to have no effect if it's executed outside a `BEGIN` block, since the transaction will end immediately.

`variable`

A settable run-time parameter.

`value`

New value of parameter. `DEFAULT` can be used to specify resetting the parameter to its default value. Lists of strings are allowed, but more complex constructs may need to be single or double quoted.

Description

The `SET` command changes run-time configuration parameters. Many of the run-time parameters listed in the *Administrator's Guide* can be changed on-the-fly with `SET`. (But some require superuser privileges to change, and others cannot be changed after server or session start.) Note that `SET` only affects the value used by the current session.

If `SET` or `SET SESSION` is issued within a transaction that is later aborted, the effects of the `SET` command disappear when the transaction is rolled back. (This behavior represents a change from PostgreSQL versions prior to 7.3, where the effects of `SET` would not roll back after a later error.) Once the surrounding transaction is committed, the effects will persist until the end of the session, unless overridden by another `SET`.

The effects of `SET LOCAL` last only till the end of the current transaction, whether committed or not. A special case is `SET` followed by `SET LOCAL` within a single transaction: the `SET LOCAL` value will be seen until the end of the transaction, but afterwards (if the transaction is committed) the `SET` value will take effect.

Even with `autocommit` set to `off`, `SET` does not start a new transaction block. See the `autocommit` section of the *Administrator's Guide* for details.

Here are additional details about a few of the parameters that can be set:

`DATESTYLE`

Choose the date/time representation style. Two separate settings are involved: the default date/time output and the interpretation of ambiguous input.

The following are date/time output styles:

`ISO`

Use ISO 8601-style dates and times (`YYYY-MM-DD HH:MM:SS`). This is the default.

`SQL`

Use Oracle/Ingres-style dates and times. Note that this style has nothing to do with SQL (which mandates ISO 8601 style), the naming of this option is a historical accident.

`PostgreSQL`

Use traditional PostgreSQL format.

`German`

Use `dd.mm.yyyy` for numeric date representations.

The following two options determine both a substyle of the "SQL" and "PostgreSQL" output formats and the preferred interpretation of ambiguous date input.

`European`

Use `dd/mm/yyyy` for numeric date representations.

`NonEuropean`
`US`

Use `mm/dd/yyyy` for numeric date representations.

A value for `SET DATESTYLE` can be one from the first list (output styles), or one from the second list (substyles), or one from each separated by a comma.

`SET DATESTYLE` affects interpretation of input and provides several standard output formats. For applications needing different variations or tighter control over input or output, consider using the `to_char` family of functions.

There are several now-deprecated means for setting the date style in addition to the normal methods of setting it via `SET` or a configuration-file entry:

Setting the postmaster's `PGDATESTYLE` environment variable. (This will be overridden by any of the other methods.)
Running postmaster using the option `-o -e` to set dates to the `European` convention. (This overrides environment variables and configuration-file entries.)
Setting the client's `PGDATESTYLE` environment variable. If `PGDATESTYLE` is set in the frontend environment of a client based on libpq, libpq will automatically set `DATESTYLE` to the value of `PGDATESTYLE` during connection start-up. This is equivalent to a manually issued `SET DATESTYLE`.

NAMES

`SET NAMES` is an alias for `SET CLIENT_ENCODING`.

SEED

Sets the internal seed for the random number generator.

value

The value for the seed to be used by the `random` function. Allowed values are floating-point numbers between 0 and 1, which are then multiplied by 2^{31}-1.

The seed can also be set by invoking the `setseed` SQL function:

```
SELECT setseed(value);
```

SERVER_ENCODING

Shows the server-side multibyte encoding. (At present, this parameter can be shown but not set, because the encoding is determined at initdb time.)

TIME ZONE
TIMEZONE

Sets the default time zone for your session. Arguments can be an SQL time interval constant, an integer or double precision constant, or a string representing a time zone name recognized by the host operating system.

Here are some typical values for time zone settings:

'PST8PDT'

Set the time zone for Berkeley, California.

'Portugal'

Set the time zone for Portugal.

'Europe/Rome'

Set the time zone for Italy.

7

Set the time zone to 7 hours offset west from GMT (equivalent to PDT).

INTERVAL '08:00' HOUR TO MINUTE

Set the time zone to 8 hours offset west from GMT (equivalent to PST).

LOCAL
DEFAULT

Set the time zone to your local time zone (the one that your operating system defaults to).

The available time zone names depend on your operating system. For example, on Linux `/usr/share/zoneinfo` contains the database of time zones; the names of the files in that directory can be used as parameters to this command.

If an invalid time zone is specified, the time zone becomes GMT (on most systems anyway).

If the `PGTZ` environment variable is set in the frontend environment of a client based on libpq, libpq will automatically `SET TIMEZONE` to the value of `PGTZ` during connection start-up.

Use SHOW to show the current setting of a parameter.

Diagnostics

`SET`

Message returned if successful.

```
ERROR: 'name is not a valid option name
```

The parameter you tried to set does not exist.

```
ERROR: 'name': permission denied
```

You must be a superuser to alter certain settings.

```
ERROR: 'name' cannot be changed after server start
```

Some parameters are fixed once the server is started.

Examples

Set the style of date to traditional PostgreSQL with European conventions:

```
SET DATESTYLE TO PostgreSQL,European;
```

Set the time zone for Berkeley, California, using quotes to preserve the uppercase spelling of the time zone name (note that the date style is `PostgreSQL` for this example):

```
SET TIME ZONE 'PST8PDT';
SELECT CURRENT_TIMESTAMP AS today;
               today
-----------------------------------
 Tue Feb 26 07:32:21.42834 2002 PST
```

Set the time zone for Italy (note the required single quotes to handle the special characters):

```
SET TIME ZONE 'Europe/Rome';
SELECT CURRENT_TIMESTAMP AS today;

             today
-------------------------------
 2002-10-08 05:39:35.008271+02
```

Compatibility

SQL92

`SET TIME ZONE` extends syntax defined in SQL9x. SQL9x allows only numeric time zone offsets while PostgreSQL allows full time zone specifier strings as well. All other `SET` features are PostgreSQL extensions.

See Also

The function `set_config` provides the equivalent capability. See *Miscellaneous Functions* in the *PostgreSQL User's Guide*.

Name

SET CONSTRAINTS — set the constraint mode of the current transaction

Synopsis

<refsynopsisdivinfo>2000-06-01</refsynopsisdivinfo>

```
SET CONSTRAINTS { ALL | constraint [, ...] } { DEFERRED |
 IMMEDIATE }
```

Description

`SET CONSTRAINTS` sets the behavior of constraint evaluation in the current transaction. In `IMMEDIATE` mode, constraints are checked at the end of each statement. In `DEFERRED` mode, constraints are not checked until transaction commit.

Note

This command only alters the behavior of constraints within the current transaction. Thus, if you execute this command outside of an explicit transaction block (such as one started with `BEGIN`), it will not appear to have any effect. If you wish to change the behavior of a constraint without needing to issue a `SET CONSTRAINTS` command in every transaction, specify `INITIALLY DEFERRED` or `INITIALLY IMMEDIATE` when you create the constraint.

When you change the mode of a constraint to be `IMMEDIATE` , the new constraint mode takes effect retroactively: any outstanding data modifications that would have been checked at the end of the transaction (when using `DEFERRED`) are instead checked during the execution of the `SET CONSTRAINTS` command.

Upon creation, a constraint is always give one of three characteristics: `INITIALLY DEFERRED`, `INITIALLY IMMEDIATE DEFERRABLE`, or `INITIALLY IMMEDIATE NOT DEFERRABLE`. The third class is not affected by the `SET CONSTRAINTS` command.

Currently, only foreign key constraints are affected by this setting. Check and unique constraints are always effectively initially immediate not deferrable.

Compatibility

SQL92, SQL99

`SET CONSTRAINTS` is defined in SQL92 and SQL99. The implementation in PostgreSQL complies with the behavior defined in the standard, except for the PostgreSQL limitation that `SET CONSTRAINTS` cannot be applied to check or unique constraints.

<docinfo>2001-04-21</docinfo>

Name

SET SESSION AUTHORIZATION — set the session user identifier and the current user identifier of the current session

Synopsis

```
SET [ SESSION | LOCAL ] SESSION AUTHORIZATION username
SET [ SESSION | LOCAL ] SESSION AUTHORIZATION DEFAULT
RESET SESSION AUTHORIZATION
```

Description

This command sets the session user identifier and the current user identifier of the current SQL session to be *username*. The user name may be written as either an identifier or a string literal. The session user identifier is valid for the duration of a connection; for example, it is possible to temporarily become an unprivileged user and later switch back to become a superuser.

The session user identifier is initially set to be the (possibly authenticated) user name provided by the client. The current user identifier is normally equal to the session user identifier, but might change temporarily in the context of SECURITY DEFINER functions and similar mechanisms. The current user identifier is relevant for permission checking.

The session user identifier may be changed only if the initial session user (the *authenticated user*) had the superuser privilege. Otherwise, the command is accepted only if it specifies the authenticated user name.

The SESSION and LOCAL modifiers act the same as for the regular SET command.

The DEFAULT and RESET forms reset the session and current user identifiers to be the originally authenticated user name. These forms are always accepted.

Notes

SET SESSION AUTHORIZATION cannot be used within a SECURITY DEFINER function.

Examples

```
SELECT SESSION_USER, CURRENT_USER;
 current_user | session_user
--------------+--------------
 peter        | peter

SET SESSION AUTHORIZATION 'paul';

SELECT SESSION_USER, CURRENT_USER;
 current_user | session_user
--------------+--------------
 paul         | paul
```

Compatibility

SQL99

SQL99 allows some other expressions to appear in place of the literal *username* which are not important in practice. PostgreSQL allows identifier syntax ("username"), which SQL does not. SQL

does not allow this command during a transaction; PostgreSQL does not make this restriction because there is no reason to. The privileges necessary to execute this command are left implementation-defined by the standard.

<docinfo>2000-11-24</docinfo>

Name

SET TRANSACTION — set the characteristics of the current transaction

Synopsis

```
SET TRANSACTION ISOLATION LEVEL { READ COMMITTED | SERIALIZABLE }
SET SESSION CHARACTERISTICS AS TRANSACTION ISOLATION LEVEL
    { READ COMMITTED | SERIALIZABLE }
```

Description

This command sets the transaction isolation level. The `SET TRANSACTION` command sets the characteristics for the current SQL-transaction. It has no effect on any subsequent transactions. This command cannot be used after the first query or data-modification statement (`SELECT`, `INSERT`, `DELETE`, `UPDATE`, `FETCH`, `COPY`) of a transaction has been executed. `SET SESSION CHARACTERISTICS` sets the default transaction isolation level for each transaction for a session. `SET TRANSACTION` can override it for an individual transaction.

The isolation level of a transaction determines what data the transaction can see when other transactions are running concurrently.

READ COMMITTED

A statement can only see rows committed before it began. This is the default.

SERIALIZABLE

The current transaction can only see rows committed before first query or data-modification statement was executed in this transaction.

Tip

Intuitively, serializable means that two concurrent transactions will leave the database in the same state as if the two has been executed strictly after one another in either order.

Notes

The session default transaction isolation level can also be set with the command

```
SET default_transaction_isolation = 'value'
```

and in the configuration file. Consult the *Administrator's Guide* for more information.

Compatibility

SQL92, SQL99

`SERIALIZABLE` is the default level in SQL. PostgreSQL does not provide the isolation levels `READ UNCOMMITTED` and `REPEATABLE READ`. Because of multiversion concurrency control, the `SERIALIZABLE` level is not truly serializable. See the *User's Guide* for details.

In SQL there are two other transaction characteristics that can be set with these commands: whether the transaction is read-only and the size of the diagnostics area. Neither of these concepts are supported in PostgreSQL.

Name

SHOW — show the value of a run-time parameter

Synopsis

```
SHOW name

SHOW ALL
```

Inputs

name

The name of a run-time parameter. See SET for a list.

ALL

Show all current session parameters.

Description

SHOW will display the current setting of a run-time parameter. These variables can be set using the SET statement, by editing the postgresql.conf, through the PGOPTIONS environmental variable, or through a command-line flag when starting the postmaster.

Even with autocommit set to off, SHOW does not start a new transaction block. See the autocommit section of the *Administrator's Guide* for details.

Diagnostics

ERROR: Option '*name*' is not recognized

Message returned if *name* does not stand for an existing parameter.

Examples

Show the current DateStyle setting:

```
SHOW DateStyle;
               DateStyle
-------------------------------------
 ISO with US (NonEuropean) conventions
(1 row)
```

Show the current genetic optimizer (geqo) setting:

```
SHOW GEQO;
 geqo
------
 on
(1 row)
```

Show all settings:

```
SHOW ALL;
             name               |                setting
```

```
-------------------------------
+--------------------------------------
 australian_timezones           | off
 authentication_timeout         | 60
 checkpoint_segments            | 3
    .
    .
    .
 wal_debug                      | 0
 wal_sync_method                | fdatasync
(94 rows)
```

Compatibility

The `SHOW` command is a PostgreSQL extension.

See Also

The function `current_setting` produces equivalent output. See *Miscellaneous Functions* in the *PostgreSQL User's Guide*.

<docinfo>2002-07-26</docinfo>

Name

START TRANSACTION — start a transaction block

Synopsis

```
START TRANSACTION [ ISOLATION LEVEL { READ COMMITTED |
 SERIALIZABLE } ]
```

Inputs

None.

Outputs

`START TRANSACTION`

Message returned if successful.

`WARNING: BEGIN: already a transaction in progress`

If there is already a transaction in progress when the command is issued.

Description

This command begins a new transaction. If the isolation level is specified, the new transaction has that isolation level. In all other respects, the behavior of this command is identical to the BEGIN command.

Notes

The isolation level of a transaction can also be set with the SET TRANSACTION command. If no isolation level is specified, the default isolation level is used.

Compatibility

SQL99

`SERIALIZABLE` is the default isolation level in SQL99, but it is not the usual default in PostgreSQL: the factory default setting is READ COMMITTED. PostgreSQL does not provide the isolation levels `READ UNCOMMITTED` and `REPEATABLE READ`. Because of lack of predicate locking, the `SERIALIZABLE` level is not truly serializable. See the *User's Guide* for details.

In SQL99 this statement can specify two other properties of the new transaction: whether the transaction is read-only and the size of the diagnostics area. Neither of these concepts are currently supported in PostgreSQL.

Name

TRUNCATE — empty a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
TRUNCATE [ TABLE ] name
```

Inputs

name

The name (optionally schema-qualified) of the table to be truncated.

Outputs

`TRUNCATE TABLE`

Message returned if the table is successfully truncated.

Description

`TRUNCATE` quickly removes all rows from a table. It has the same effect as an unqualified `DELETE` but since it does not actually scan the table it is faster. This is most useful on large tables.

`TRUNCATE` cannot be executed inside a transaction block (`BEGIN`/`COMMIT` pair), because there is no way to roll it back.

Usage

Truncate the table `bigtable`:

```
TRUNCATE TABLE bigtable;
```

Compatibility

SQL92

There is no `TRUNCATE` in SQL92.

Name

UNLISTEN — stop listening for a notification

Synopsis

<refsynopsisdivinfo>1998-10-19</refsynopsisdivinfo>

```
UNLISTEN { notifyname | * }
```

Inputs

notifyname

Name of previously registered notify condition.

*

All current listen registrations for this backend are cleared.

Outputs

UNLISTEN

Acknowledgment that statement has executed.

Description

UNLISTEN is used to remove an existing NOTIFY registration. UNLISTEN cancels any existing registration of the current PostgreSQL session as a listener on the notify condition *notifyname*. The special condition wildcard * cancels all listener registrations for the current session.

NOTIFY contains a more extensive discussion of the use of LISTEN and NOTIFY.

Notes

notifyname need not be a valid class name but can be any string valid as a name up to 64 characters long.

The backend does not complain if you unlisten something you were not listening for. Each backend will automatically execute UNLISTEN * when exiting.

Usage

To subscribe to an existing registration:

```
LISTEN virtual;
LISTEN
NOTIFY virtual;
NOTIFY
Asynchronous NOTIFY 'virtual' from backend with pid '8448' received
```

Once UNLISTEN has been executed, further NOTIFY commands will be ignored:

```
UNLISTEN virtual;
UNLISTEN
NOTIFY virtual;
NOTIFY
```

```
-- notice no NOTIFY event is received
```

Compatibility

SQL92

There is no `UNLISTEN` in SQL92.

Name

UPDATE — update rows of a table

Synopsis

<refsynopsisdivinfo>1999-07-20</refsynopsisdivinfo>

```
UPDATE [ ONLY ] table SET col = expression [, ...]
    [ FROM fromlist ]
    [ WHERE condition ]
```

Inputs

table

The name (optionally schema-qualified) of an existing table. If ONLY is specified, only that table is updated. If ONLY is not specified, the table and all its descendant tables (if any) are updated. * can be appended to the table name to indicate that descendant tables are to be scanned, but in the current version, this is the default behavior. (In releases before 7.1, ONLY was the default behavior.) The default can be altered by changing the SQL_INHERITANCE configuration option.

column

The name of a column in *table*.

expression

A valid expression or value to assign to column.

fromlist

A PostgreSQL non-standard extension to allow columns from other tables to appear in the WHERE condition.

condition

Refer to the SELECT statement for a further description of the WHERE clause.

Outputs

UPDATE #

Message returned if successful. The # means the number of rows updated. If # is 0 no rows are updated.

Description

UPDATE changes the values of the columns specified for all rows which satisfy condition. Only the columns to be modified need appear as columns in the statement.

Array references use the same syntax found in SELECT. That is, either single array elements, a range of array elements or the entire array may be replaced with a single query.

You must have write access to the table in order to modify it, as well as read access to any table whose values are mentioned in the WHERE condition.

By default UPDATE will update tuples in the table specified and all its sub-tables. If you wish to only update the specific table mentioned, you should use the ONLY clause.

Usage

Change word `Drama` with `Dramatic` on column `kind`:

```
UPDATE films
SET kind = 'Dramatic'
WHERE kind = 'Drama';
SELECT *
FROM films
WHERE kind = 'Dramatic' OR kind = 'Drama';
```

```
 code  |     title     | did | date_prod  |   kind   | len
-------+---------------+-----+------------+----------+-------
 BL101 | The Third Man | 101 | 1949-12-23 | Dramatic | 01:44
 P_302 | Becket        | 103 | 1964-02-03 | Dramatic | 02:28
 M_401 | War and Peace | 104 | 1967-02-12 | Dramatic | 05:57
 T_601 | Yojimbo       | 106 | 1961-06-16 | Dramatic | 01:50
 DA101 | Das Boot      | 110 | 1981-11-11 | Dramatic | 02:29
```

Compatibility

SQL92

SQL92 defines a different syntax for the positioned UPDATE statement:

```
UPDATE table SET column = expression [, ...]
    WHERE CURRENT OF cursor
```

where *`cursor`* identifies an open cursor.

Name

VACUUM — garbage-collect and optionally analyze a database

Synopsis

<refsynopsisdivinfo>2001-08-26</refsynopsisdivinfo>

```
VACUUM [ FULL ] [ FREEZE ] [ VERBOSE ] [ table ]
VACUUM [ FULL ] [ FREEZE ] [ VERBOSE ] ANALYZE [ table [ (column
 [, ...] ) ] ]
```

Inputs

FULL

Selects “full” vacuum, which may reclaim more space, but takes much longer and exclusively locks the table.

FREEZE

Selects aggressive “freezing” of tuples.

VERBOSE

Prints a detailed vacuum activity report for each table.

ANALYZE

Updates statistics used by the optimizer to determine the most efficient way to execute a query.

table

The name (optionally schema-qualified) of a specific table to vacuum. Defaults to all tables in the current database.

column

The name of a specific column to analyze. Defaults to all columns.

Outputs

VACUUM

The command is complete.

INFO: --Relation *table*--

The report header for *table*.

```
INFO: Pages 98: Changed 25, Reapped 74, Empty 0, New 0; Tup 1000: Vac
3000, Crash 0, UnUsed 0, MinLen 188, MaxLen 188; Re-using: Free/Avail.
Space 586952/586952; EndEmpty/Avail. Pages 0/74. Elapsed 0/0 sec.
```

The analysis for *table* itself.

```
INFO: Index index: Pages 28; Tuples 1000: Deleted 3000. Elapsed 0/0
sec.
```

The analysis for an index on the target table.

Description

VACUUM reclaims storage occupied by deleted tuples. In normal PostgreSQL operation, tuples that are deleted or obsoleted by UPDATE are not physically removed from their table; they remain present until a VACUUM is done. Therefore it's necessary to do VACUUM periodically, especially on frequently-updated tables.

With no parameter, VACUUM processes every table in the current database. With a parameter, VACUUM processes only that table.

VACUUM ANALYZE performs a VACUUM and then an ANALYZE for each selected table. This is a handy combination form for routine maintenance scripts. See ANALYZE for more details about its processing.

Plain VACUUM (without FULL) simply reclaims space and makes it available for re-use. This form of the command can operate in parallel with normal reading and writing of the table, as an exclusive lock is not obtained. VACUUM FULL does more extensive processing, including moving of tuples across blocks to try to compact the table to the minimum number of disk blocks. This form is much slower and requires an exclusive lock on each table while it is being processed.

FREEZE is a special-purpose option that causes tuples to be marked “frozen” as soon as possible, rather than waiting until they are quite old. If this is done when there are no other open transactions in the same database, then it is guaranteed that all tuples in the database are “frozen” and will not be subject to transaction ID wraparound problems, no matter how long the database is left un-vacuumed. FREEZE is not recommended for routine use. Its only intended usage is in connection with preparation of user-defined template databases, or other databases that are completely read-only and will not receive routine maintenance VACUUM operations. See the *Administrator's Guide* for details.

Notes

We recommend that active production databases be VACUUM-ed frequently (at least nightly), in order to remove expired rows. After adding or deleting a large number of records, it may be a good idea to issue a VACUUM ANALYZE command for the affected table. This will update the system catalogs with the results of all recent changes, and allow the PostgreSQL query optimizer to make better choices in planning user queries.

The FULL option is not recommended for routine use, but may be useful in special cases. An example is when you have deleted most of the rows in a table and would like the table to physically shrink to occupy less disk space. VACUUM FULL will usually shrink the table more than a plain VACUUM would.

Usage

The following is an example from running VACUUM on a table in the regression database:

```
regression=> VACUUM VERBOSE ANALYZE onek;
INFO:  --Relation onek--
INFO:  Index onek_unique1: Pages 14; Tuples 1000: Deleted 3000.
        CPU 0.00s/0.11u sec elapsed 0.12 sec.
INFO:  Index onek_unique2: Pages 16; Tuples 1000: Deleted 3000.
        CPU 0.00s/0.10u sec elapsed 0.10 sec.
INFO:  Index onek_hundred: Pages 13; Tuples 1000: Deleted 3000.
        CPU 0.00s/0.10u sec elapsed 0.10 sec.
INFO:  Index onek_stringu1: Pages 31; Tuples 1000: Deleted 3000.
        CPU 0.01s/0.09u sec elapsed 0.10 sec.
INFO:  Removed 3000 tuples in 70 pages.
        CPU 0.02s/0.04u sec elapsed 0.07 sec.
INFO:  Pages 94: Changed 0, Empty 0; Tup 1000: Vac 3000, Keep 0,
 UnUsed 0.
```

```
        Total CPU 0.05s/0.45u sec elapsed 0.59 sec.
INFO:  Analyzing onek
VACUUM
```

Compatibility

SQL92

There is no VACUUM statement in SQL92.

PostgreSQL Client Applications

This part contains reference information for PostgreSQL client applications and utilities. Not all of these commands are of general utility, some may require special privileges. The common feature of these applications is that they can be run on any host, independent of where the database server resides.

Table of Contents

clusterdb 523
createdb 525
createlang 528
createuser 530
dropdb 533
droplang 535
dropuser 537
ecpg 539
pg_config 541
pg_dump 543
pg_dumpall 549
pg_restore 552
psql 558
pgtclsh 579
pgtksh 580
vacuumdb 581

Name

clusterdb — cluster a PostgreSQL database

Synopsis

`clusterdb` [*connection-options*...] [--table | -t *table*] [*dbname*]
`clusterdb` [*connection-options*...] [[--all] | [-a]]

Description

clusterdb is a utility for reclustering tables in a PostgreSQL database. It finds tables that have previously been clustered, and clusters them again on the same index that was last used. Tables that have never been clustered are not touched.

clusterdb is a shell script wrapper around the backend command CLUSTER via the PostgreSQL interactive terminal psql. There is no effective difference between clustering databases via this or other methods. psql must be found by the script and a database server must be running at the targeted host. Also, any default settings and environment variables available to psql and the libpq front-end library do apply.

clusterdb might need to connect several times to the PostgreSQL server, asking for a password each time. It is convenient to have a `$HOME/.pgpass` file in such cases.

Options

clusterdb accepts the following command-line arguments:

`-a`
`--all`

Cluster all databases.

`[-d]` *dbname*
`[--dbname]` *dbname*

Specifies the name of the database to be clustered. If this is not specified and `-a` (or `--all`) is not used, the database name is read from the environment variable `PGDATABASE`. If that is not set, the user name specified for the connection is used.

`-e`
`--echo`

Echo the commands that clusterdb generates and sends to the server.

`-q`
`--quiet`

Do not display a response.

`-t` *table*
`--table` *table*

Clusters *table* only.

clusterdb also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Diagnostics

`CLUSTER`

Everything went well.

`clusterdb: Cluster failed.`

Something went wrong. clusterdb is only a wrapper script. See CLUSTER and psql for a detailed discussion of error messages and potential problems. Note that this message may appear once per table to be clustered.

Environment

`PGDATABASE`
`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Examples

To cluster the database `test`:

```
$ clusterdb test
```

To cluster a single table `foo` in a database named `xyzzy`:

```
$ clusterdb --table foo xyzzy
```

See Also

CLUSTER

Name

createdb — create a new PostgreSQL database

Synopsis

`createdb` [*options*...] [*dbname*] [*description*]

Description

createdb creates a new PostgreSQL database.

Normally, the database user who executes this command becomes the owner of the new database. However a different owner can be specified via the `-O` option, if the executing user has appropriate privileges.

createdb is a shell script wrapper around the SQL command CREATE DATABASE via the PostgreSQL interactive terminal psql. Thus, there is nothing special about creating databases via this or other methods. This means that the psql program must be found by the script and that a database server must be running at the targeted port. Also, any default settings and environment variables available to psql and the libpq front-end library will apply.

Options

createdb accepts the following command-line arguments:

dbname

Specifies the name of the database to be created. The name must be unique among all PostgreSQL databases in this installation. The default is to create a database with the same name as the current system user.

description

This optionally specifies a comment to be associated with the newly created database.

`-D` *location*
`--location` *location*

Specifies the alternative location for the database. See also initlocation.

`-e`
`--echo`

Echo the queries that createdb generates and sends to the server.

`-E` *encoding*
`--encoding` *encoding*

Specifies the character encoding scheme to be used in this database.

`-O` *owner*
`--owner` *owner*

Specifies the database user who will own the new database.

`-q`
`--quiet`

Do not display a response.

`-T` *template*
`--template` *template*

Specifies the template database from which to build this database.

The options `-D`, `-E`, `-O`, and `-T` correspond to options of the underlying SQL command CREATE DATABASE; see there for more information about them.

createdb also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or the local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Diagnostics

`CREATE DATABASE`

The database was successfully created.

`createdb: Database creation failed.`

(Says it all.)

`createdb: Comment creation failed. (Database was created.)`

The comment/description for the database could not be created. The database itself will have been created already. You can use the SQL command `COMMENT ON DATABASE` to create the comment later on.

If there is an error condition, the backend error message will be displayed. See CREATE DATABASE and psql for possibilities.

Environment

`PGDATABASE`

If set, the name of the database to create, unless overridden on the command line.

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters. `PGUSER` also determines the name of the database to create, if it is not specified on the command line or by `PGDATABASE`.

Examples

To create the database `demo` using the default database server:

```
$ createdb demo
CREATE DATABASE
```

The response is the same as you would have gotten from running the `CREATE DATABASE` SQL command.

To create the database `demo` using the server on host `eden`, port 5000, using the `LATIN1` encoding scheme with a look at the underlying query:

```
$ createdb -p 5000 -h eden -E LATIN1 -e demo
CREATE DATABASE "demo" WITH ENCODING = 'LATIN1'
CREATE DATABASE
```

See Also

dropdb, CREATE DATABASE

Name

createlang — define a new PostgreSQL procedural language

Synopsis

```
createlang [connection-options...] langname [dbname]
createlang [connection-options...] [--list] | [-l] dbname
```

Description

createlang is a utility for adding a new programming language to a PostgreSQL database. createlang can handle all the languages supplied in the default PostgreSQL distribution, but not languages provided by other parties.

Although backend programming languages can be added directly using several SQL commands, it is recommended to use createlang because it performs a number of checks and is much easier to use. See CREATE LANGUAGE for additional information.

Options

createlang accepts the following command-line arguments:

langname

Specifies the name of the procedural programming language to be defined.

[-d] *dbname*
[--dbname] *dbname*

Specifies to which database the language should be added. The default is to use the database with the same name as the current system user.

-e
--echo

Displays SQL commands as they are executed.

-l
--list

Shows a list of already installed languages in the target database (which must be specified).

-L *directory*

Specifies the directory in which the language interpreter is to be found. The directory is normally found automatically; this option is primarily for debugging purposes.

createlang also accepts the following command-line arguments for connection parameters:

-h *host*
--host *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

-p *port*
--port *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Environment

`PGDATABASE`
`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Diagnostics

Most error messages are self-explanatory. If not, run createlang with the `--echo` option and see under the respective SQL command for details. Check also under psql for more possibilities.

Notes

Use droplang to remove a language.

createlang is a shell script that invokes psql several times. If you have things arranged so that a password prompt is required to connect, you will be prompted for a password several times.

Examples

To install `pltcl` into the database `template1`:

```
$ createlang pltcl template1
```

See Also

droplang, CREATE LANGUAGE

Name

createuser — define a new PostgreSQL user account

Synopsis

`createuser` [*options*...] [*username*]

Description

createuser creates a new PostgreSQL user. Only superusers (users with `usesuper` set in the `pg_shadow` table) can create new PostgreSQL users, so createuser must be invoked by someone who can connect as a PostgreSQL superuser.

Being a superuser also implies the ability to bypass access permission checks within the database, so superuserdom should not be granted lightly.

createuser is a shell script wrapper around the SQL command CREATE USER via the PostgreSQL interactive terminal psql. Thus, there is nothing special about creating users via this or other methods. This means that the psql application must be found by the script and that a database server must be running at the targeted host. Also, any default settings and environment variables used by psql and the libpq front-end library will apply.

Options

createuser accepts the following command-line arguments:

username

Specifies the name of the PostgreSQL user to be created. This name must be unique among all PostgreSQL users.

`-a`
`--adduser`

The new user is allowed to create other users. (Note: Actually, this makes the new user a *superuser*. The option is poorly named.)

`-A`
`--no-adduser`

The new user is not allowed to create other users (i.e., the new user is a regular user, not a superuser).

`-d`
`--createdb`

The new user is allowed to create databases.

`-D`
`--no-createdb`

The new user is not allowed to create databases.

`-e`
`--echo`

Echo the queries that createuser generates and sends to the server.

`-E`
`--encrypted`

Encrypts the user's password stored in the database. If not specified, the default is used.

`-i` *uid*
`--sysid` *uid*

Allows you to pick a non-default user ID for the new user. This is not necessary, but some people like it.

`-N`
`--unencrypted`

Does not encrypt the user's password stored in the database. If not specified, the default is used.

`-P`
`--pwprompt`

If given, createuser will issue a prompt for the password of the new user. This is not necessary if you do not plan on using password authentication.

`-q`
`--quiet`

Do not display a response.

You will be prompted for a name and other missing information if it is not specified on the command line.

createuser also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as (not the user name to create)

`-W`
`--password`

Force password prompt (to connect to the server, not for the password of the new user).

Environment

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters

Diagnostics

`CREATE USER`

All is well.

`createuser: creation of user "`*`username`*`" failed`

Something went wrong. The user was not created.

If there is an error condition, the backend error message will be displayed. See CREATE USER and psql for possibilities.

Examples

To create a user `joe` on the default database server:

```
$ createuser joe
Is the new user allowed to create databases? (y/n) n
Shall the new user be allowed to create more new users? (y/n) n
CREATE USER
```

To create the same user `joe` using the server on host `eden`, port 5000, avoiding the prompts and taking a look at the underlying query:

```
$ createuser -p 5000 -h eden -D -A -e joe
CREATE USER "joe" NOCREATEDB NOCREATEUSER
CREATE USER
```

See Also

dropuser, CREATE USER

Name

dropdb — remove a PostgreSQL database

Synopsis

`dropdb` [*options*...] *dbname*

Description

dropdb destroys an existing PostgreSQL database. The user who executes this command must be a database superuser or the owner of the database.

dropdb is a shell script wrapper around the SQL command DROP DATABASE via the PostgreSQL interactive terminal psql. Thus, there is nothing special about dropping databases via this or other methods. This means that the psql must be found by the script and that a database server is running at the targeted host. Also, any default settings and environment variables available to psql and the libpq front-end library do apply.

Options

dropdb accepts the following command-line arguments:

dbname

Specifies the name of the database to be removed. The database must be one of the existing PostgreSQL databases in this installation.

`-e`
`--echo`

Echo the queries that dropdb generates and sends to the server.

`-i`
`--interactive`

Issues a verification prompt before doing anything destructive.

`-q`
`--quiet`

Do not display a response.

createdb also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Diagnostics

`DROP DATABASE`

The database was successfully removed.

`dropdb: Database removal failed.`

Something didn't work out.

If there is an error condition, the backend error message will be displayed. See DROP DATABASE and psql for possibilities.

Environment

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters

Examples

To destroy the database `demo` on the default database server:

```
$ dropdb demo
DROP DATABASE
```

To destroy the database `demo` using the server on host `eden`, port 5000, with verification and a peek at the underlying query:

```
$ dropdb -p 5000 -h eden -i -e demo
Database "demo" will be permanently deleted.
Are you sure? (y/n) y
DROP DATABASE "demo"
DROP DATABASE
```

See Also

createdb, DROP DATABASE

Name

droplang — remove a PostgreSQL procedural language

Synopsis

```
droplang [connection-options...] langname [dbname]
droplang [connection-options...] [--list] | [-l] dbname
```

Description

droplang is a utility for removing an existing programming language from a PostgreSQL database. droplang can drop any procedural language, even those not supplied by the PostgreSQL distribution.

Although backend programming languages can be removed directly using several SQL commands, it is recommended to use droplang because it performs a number of checks and is much easier to use. See DROP LANGUAGE for more.

Options

droplang accepts the following command line arguments:

langname

Specifies the name of the backend programming language to be removed.

[-d] *dbname*
[--dbname] *dbname*

Specifies from which database the language should be removed. The default is to use the database with the same name as the current system user.

-e
--echo

Displays SQL commands as they are executed.

-l
--list

Shows a list of already installed languages in the target database (which must be specified).

droplang also accepts the following command line arguments for connection parameters:

-h *host*
--host *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

-p *port*
--port *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

-U *username*
--username *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Environment

`PGDATABASE`
`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Diagnostics

Most error messages are self-explanatory. If not, run droplang with the `--echo` option and see under the respective SQL command for details. Check also under psql for more possibilities.

Notes

Use createlang to add a language.

Examples

To remove `pltcl`:

```
$ droplang pltcl dbname
```

See Also

createlang, DROP LANGUAGE

Name

dropuser — remove a PostgreSQL user account

Synopsis

`dropuser` [*options*...] [*username*]

Description

dropuser removes an existing PostgreSQL user *and* the databases which that user owned. Only users with `usesuper` set in the `pg_shadow` table can destroy PostgreSQL users.

dropuser is a shell script wrapper around the SQL command DROP USER via the PostgreSQL interactive terminal psql. Thus, there is nothing special about removing users via this or other methods. This means that the psql must be found by the script and that a database server is running at the targeted host. Also, any default settings and environment variables available to psql and the libpq front-end library do apply.

Options

dropuser accepts the following command-line arguments:

username

Specifies the name of the PostgreSQL user to be removed. This name must exist in the PostgreSQL installation. You will be prompted for a name if none is specified on the command line.

`-e`
`--echo`

Echo the queries that dropuser generates and sends to the server.

`-i`
`--interactive`

Prompt for confirmation before actually removing the user.

`-q`
`--quiet`

Do not display a response.

createuser also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as (not the user name to drop)

`-W`
`--password`

Force password prompt (to connect to the server, not for the password of the user to be dropped).

Environment

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters

Diagnostics

`DROP USER`

All is well.

`dropuser: deletion of user "`*`username`*`" failed`

Something went wrong. The user was not removed.

If there is an error condition, the backend error message will be displayed. See DROP USER and psql for possibilities.

Examples

To remove user `joe` from the default database server:

```
$ dropuser joe
DROP USER
```

To remove user `joe` using the postmaster on host `eden`, port 5000, with verification and a peek at the underlying query:

```
$ dropuser -p 5000 -h eden -i -e joe
User "joe" and any owned databases will be permanently deleted.
Are you sure? (y/n) y
DROP USER "joe"
DROP USER
```

See Also

createuser, DROP USER

Name

ecpg — embedded SQL C preprocessor

Synopsis

`ecpg` [*option*...] *file*...

Description

`ecpg` is the embedded SQL preprocessor for C programs. It converts C programs with embedded SQL statements to normal C code by replacing the SQL invocations with special function calls. The output files can then be processed with any C compiler tool chain.

`ecpg` will convert each input file given on the command line to the corresponding C output file. Input files preferrably have the extension `.pgc`, in which case the extension will be replaced by `.c` to determine the output file name. If the extension of the input file is not `.pgc`, then the output file name is computed by appending `.c` to the full file name. The output file name can also be overridden using the `-o` option.

This reference page does not describe the embedded SQL language. See the PostgreSQL 7.3.21 Programmer's Guide for that.

Options

`ecpg` accepts the following command-line arguments:

`-c`

Automatically generate C code from SQL code. Currently, this works for `EXEC SQL TYPE`.

`-D` *symbol*

Define a C preprocessor symbol.

`-I` *directory*

Specify an additional include path, used to find files included via `EXEC SQL INCLUDE`. Defaults are `.` (current directory), `/usr/local/include`, the PostgreSQL include directory which is defined at compile time (default: `/usr/local/pgsql/include`), and `/usr/include`, in that order.

`-o` *filename*

Specifies that ecpg should write all its output to the given *filename*.

`-t`

Turn on autocommit of transactions. In this mode, each query is automatically committed unless it is inside an explicit transaction block. In the default mode, queries are committed only when `EXEC SQL COMMIT` is issued.

`-v`

Print additional information including the version and the include path.

`---help`

Show a brief summary of the command usage, then exit.

`--version`

Output version information, then exit.

Notes

When compiling the preprocessed C code files, the compiler needs to be able to find the ECPG header files in the PostgreSQL include directory. Therefore, one might have to use the `-I` option when invoking the compiler (e.g., `-I/usr/local/pgsql/include`).

Programs using C code with embedded SQL have to be linked against the `libecpg` library, for example using the flags `-L/usr/local/pgsql/lib -lecpg`.

The value of either of these directories that is appropriate for the installation can be found out using pg_config.

Examples

If you have an embedded SQL C source file named `prog1.pgc`, you can create an executable program using the following sequence of commands:

```
ecpg prog1.pgc
cc -I/usr/local/pgsql/include -c prog1.c
cc -o prog1 prog1.o -L/usr/local/pgsql/lib -lecpg
```

See Also

PostgreSQL Programmer's Guide for a more detailed description of the embedded SQL interface

Name

pg_config — retrieve information about the installed version of PostgreSQL

Synopsis

`pg_config` {[--bindir] | [--includedir] | [--includedir-server] | [--libdir] | [--pkglibdir] | [--configure] | [--version]...}

Description

The pg_config utility prints configuration parameters of the currently installed version of PostgreSQL. It is intended, for example, to be used by software packages that want to interface to PostgreSQL to facilitate finding the required header files and libraries.

Options

To use pg_config, supply one or more of the following options:

`--bindir`

Print the location of user executables. Use this, for example, to find the psql program. This is normally also the location where the `pg_config` program resides.

`--includedir`

Print the location of C header files of the client interfaces.

`--includedir-server`

Print the location of C header files for server programming.

`--libdir`

Print the location of object code libraries.

`--pkglibdir`

Print the location of dynamically loadable modules, or where the server would search for them. (Other architecture-dependent data files may also be installed in this directory.)

`--configure`

Print the options that were given to the `configure` script when PostgreSQL was configured for building. This can be used to reproduce the identical configuration, or to find out with what options a binary package was built. (Note however that binary packages often contain vendor-specific custom patches.)

`--version`

Print the version of PostgreSQL and exit.

If more than one option (except for `--version`) is given, the information is printed in that order, one item per line.

Notes

The option `--includedir-server` is new in PostgreSQL 7.2. In prior releases, the server include files were installed in the same location as the client headers, which could be queried with the `--`

`includedir`. To make your package handle both cases, try the newer option first and test the exit status to see whether it succeeded.

In releases prior to PostgreSQL 7.1, before the `pg_config` came to be, a method for finding the equivalent configuration information did not exist.

History

The `pg_config` utility first appeared in PostgreSQL 7.1.

See Also

PostgreSQL Programmer's Guide

Name

pg_dump — extract a PostgreSQL database into a script file or other archive file

Synopsis

```
pg_dump [options...] [dbname]
```

Description

pg_dump is a utility for saving a PostgreSQL database into a script or an archive file. The script files are in plain-text format and contain the SQL commands required to reconstruct the database to the state it was in at the time it was saved. To restore these scripts, use psql. They can be used to reconstruct the database even on other machines and other architectures, with some modifications even on other SQL database products.

Furthermore, there are alternative archive file formats that are meant to be used with pg_restore to rebuild the database, and they also allow pg_restore to be selective about what is restored, or even to reorder the items prior to being restored. The archive files are also designed to be portable across architectures.

pg_dump will save the information necessary to re-generate all user-defined types, functions, tables, indexes, aggregates, and operators. In addition, all the data is copied out in text format so that it can be readily copied in again, as well as imported into tools for editing.

When used with one of the archive file formats and combined with pg_restore, pg_dump provides a flexible archival and transfer mechanism. pg_dump can be used to backup an entire database, then pg_restore can be used to examine the archive and/or select which parts of the database are to be restored. The most flexible output file format is the "custom" format (`-Fc`). It allows for selection and reordering of all archived items, and is compressed by default. The `tar` format (`-Ft`) is not compressed and it is not possible to reorder data when loading, but it is otherwise quite flexible; moreover, it can be manipulated with other tools such as `tar`.

While running `pg_dump`, one should examine the output for any warnings (printed on standard error), especially in light of the limitations listed below.

pg_dump makes consistent backups even if the database is being used concurrently. pg_dump does not block other users accessing the database (readers or writers).

Options

The following command-line options are used to control the output format.

dbname

Specifies the name of the database to be dumped. If this is not specified, the environment variable `PGDATABASE` is used. If that is not set, the user name specified for the connection is used.

`-a`
`--data-only`

Dump only the data, not the schema (data definitions).

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-b`
`--blobs`

Include large objects in dump.

`-c`
`--clean`

Output commands to clean (drop) database objects prior to (the commands for) creating them.

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-C`
`--create`

Begin the output with a command to create the database itself and reconnect to the created database. (With a script of this form, it doesn't matter which database you connect to before running the script.)

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-d`
`--inserts`

Dump data as `INSERT` commands (rather than `COPY`). This will make restoration very slow, but it makes the archives more portable to other SQL database packages.

`-D`
`--column-inserts`
`--attribute-inserts`

Dump data as `INSERT` commands with explicit column names (`INSERT INTO` *`table`* `(`*`column`*`, ...) VALUES ...`). This will make restoration very slow, but it is necessary if you desire to rearrange column ordering.

`-f` *`file`*
`--file=`*`file`*

Send output to the specified file. If this is omitted, the standard output is used.

`-F` *`format`*
`--format=`*`format`*

Selects the format of the output. *`format`* can be one of the following:

p

Output a plain-text SQL script file (default)

t

Output a `tar` archive suitable for input into pg_restore. Using this archive format allows reordering and/or exclusion of schema elements at the time the database is restored. It is also possible to limit which data is reloaded at restore time.

c

Output a custom archive suitable for input into pg_restore. This is the most flexible format in that it allows reordering of data load as well as schema elements. This format is also compressed by default.

`-i`
`--ignore-version`

Ignore version mismatch between pg_dump and the database server.

pg_dump can handle databases from previous releases of PostgreSQL, but very old versions are not supported anymore (currently prior to 7.0). Use this option if you need to override the version check (and if pg_dump then fails, don't say you weren't warned).

`-o`
`--oids`

Dump object identifiers (OIDs) for every table. Use this option if your application references the OID columns in some way (e.g., in a foreign key constraint). Otherwise, this option should not be used.

`-O`
`--no-owner`

Do not output commands to set the object ownership to match the original database. Typically, pg_dump issues (psql-specific) `\connect` statements to set ownership of schema elements. See also under `-R` and `-X use-set-session-authorization`. Note that `-O` does not prevent all reconnections to the database, only the ones that are exclusively used for ownership adjustments.

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-R`
`--no-reconnect`

Prohibit pg_dump from outputting a script that would require reconnections to the database while being restored. An average restoration script usually has to reconnect several times as different users to set the original ownerships of the objects. This option is a rather blunt instrument because it makes pg_dump lose this ownership information, *unless* you use the `-X use-set-session-authorization` option.

One possible reason why reconnections during restore might not be desired is if the access to the database requires manual interaction (e.g., passwords).

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-s`
`--schema-only`

Dump only the schema (data definitions), no data.

`-S` *`username`*
`--superuser=`*`username`*

Specify the superuser user name to use when disabling triggers. This is only relevant if `--disable-triggers` is used. (Usually, it's better to specify `--use-set-session-authorization`, and then start the resulting script as superuser.)

`-t` *`table`*
`--table=`*`table`*

Dump data for *`table`* only.

`-v`
`--verbose`

Specifies verbose mode. This will cause pg_dump to print progress messages to standard error.

`-x`
`--no-privileges`
`--no-acl`

Prevent dumping of access privileges (grant/revoke commands).

`-X use-set-session-authorization`
`--use-set-session-authorization`

Normally, if a (plain-text mode) script generated by pg_dump must alter the current database user (e.g., to set correct object ownerships), it uses the psql `\connect` command. This command actually opens a new connection, which might require manual interaction (e.g., passwords). If you use the `-X use-set-session-authorization` option, then pg_dump will instead output SET SESSION AUTHORIZATION commands. This has the same effect, but it requires that the user restoring the database from the generated script be a database superuser. This option effectively overrides the `-R` option.

Since SET SESSION AUTHORIZATION is a standard SQL command, whereas `\connect` only works in psql, this option also enhances the theoretical portability of the output script.

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-X disable-triggers`
`--disable-triggers`

This option is only relevant when creating a data-only dump. It instructs pg_dump to include commands to temporarily disable triggers on the target tables while the data is reloaded. Use this if you have referential integrity checks or other triggers on the tables that you do not want to invoke during data reload.

Presently, the commands emitted for `--disable-triggers` must be done as superuser. So, you should also specify a superuser name with `-S`, or preferably specify `--use-set-session-authorization` and then be careful to start the resulting script as a superuser. If you give neither option, the entire script must be run as superuser.

This option is only meaningful for the plain-text format. For the other formats, you may specify the option when you call `pg_restore`.

`-Z` *`0..9`*
`--compress=`*`0..9`*

Specify the compression level to use in archive formats that support compression (currently only the custom archive format supports compression).

The following command-line options control the database connection parameters.

`-h` *`host`*
`--host=`*`host`*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *`port`*
`--port=`*`port`*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections. The port number defaults to 5432, or the value of the `PGPORT` environment variable (if set).

`-U` *`username`*

Connect as the given user

`-W`

Force a password prompt. This should happen automatically if the server requires password authentication.

Long option forms are only available on some platforms.

Environment

```
PGDATABASE
PGHOST
PGPORT
PGUSER
```

Default connection parameters

Diagnostics

```
Connection to database 'template1' failed.
connectDBStart() -- connect() failed: No such file or directory
        Is the postmaster running locally
        and accepting connections on Unix socket '/
tmp/.s.PGSQL.5432'?
```

pg_dump could not attach to the PostgreSQL server on the specified host and port. If you see this message, ensure that the server is running on the proper host and that you have specified the proper port.

Note

pg_dump internally executes `SELECT` statements. If you have problems running pg_dump, make sure you are able to select information from the database using, for example, psql.

Notes

If your installation has any local additions to the template1 database, be careful to restore the output of pg_dump into a truly empty database; otherwise you are likely to get errors due to duplicate definitions of the added objects. To make an empty database without any local additions, copy from template0 not template1, for example:

```
CREATE DATABASE foo WITH TEMPLATE template0;
```

pg_dump has a few limitations:

- When dumping a single table or as plain text, pg_dump does not handle large objects. Large objects must be dumped in their entirety using one of the binary archive formats.
- When doing a data only dump, pg_dump emits queries to disable triggers on user tables before inserting the data and queries to re-enable them after the data has been inserted. If the restore is stopped in the middle, the system catalogs may be left in the wrong state.

Members of tar archives are limited to a size less than 8 GB. (This is an inherent limitation of the tar file format.) Therefore this format cannot be used if the textual representation of a table exceeds that size. The total size of a tar archive and any of the other output formats is not limited, except possibly by the operating system.

Examples

To dump a database:

```
$ pg_dump mydb > db.out
```

To reload this database:

```
$ psql -d database -f db.out
```

To dump a database called `mydb` that contains large objects to a `tar` file:

```
$ pg_dump -Ft -b mydb > db.tar
```

To reload this database (with large objects) to an existing database called `newdb`:

```
$ pg_restore -d newdb db.tar
```

History

The pg_dump utility first appeared in Postgres95 release `0.02`. The non-plain-text output formats were introduced in PostgreSQL release `7.1`.

See Also

pg_dumpall, pg_restore, psql, *PostgreSQL Administrator's Guide*

Name

pg_dumpall — extract a PostgreSQL database cluster into a script file

Synopsis

```
pg_dumpall [options...]
```

Description

pg_dumpall is a utility for writing out ("dumping") all PostgreSQL databases of a cluster into one script file. The script file contains SQL commands that can be used as input to psql to restore the databases. It does this by calling pg_dump for each database in a cluster. pg_dumpall also dumps global objects that are common to all databases. (pg_dump does not save these objects.) This currently includes the information about database users and groups.

Thus, pg_dumpall is an integrated solution for backing up your databases. But note a limitation: it cannot dump "large objects", since pg_dump cannot dump such objects into text files. If you have databases containing large objects, they should be dumped using one of pg_dump's non-text output modes.

Since pg_dumpall reads tables from all databases you will most likely have to connect as a database superuser in order to produce a complete dump. Also you will need superuser privileges to execute the saved script in order to be allowed to add users and groups, and to create databases.

The SQL script will be written to the standard output. Shell operators should be used to redirect it into a file.

pg_dumpall might need to connect several times to the PostgreSQL server, asking for a password each time. It is convenient to have a `$HOME/.pgpass` file in such cases.

Options

The following command-line options are used to control the output format.

`-c`
`--clean`

Include SQL commands to clean (drop) the databases before recreating them.

`-d`
`--inserts`

Dump data as `INSERT` commands (rather than `COPY`). This will make restoration very slow, but it makes the output more portable to other RDBMS packages.

`-D`
`--column-inserts`
`--attribute-inserts`

Dump data as `INSERT` commands with explicit column names (`INSERT INTO` *table* `(`*column*`, ...) VALUES ...`). This will make restoration very slow, but it is necessary if you desire to rearrange column ordering.

`-g`
`--globals-only`

Dump only global objects (users and groups), no databases.

`-i`
`--ignore-version`

Ignore version mismatch between pg_dumpall and the database server.

pg_dumpall can handle databases from previous releases of PostgreSQL, but very old versions are not supported anymore (currently prior to 7.0). Use this option if you need to override the version check (and if pg_dumpall then fails, don't say you weren't warned).

`-o`
`--oids`

Dump object identifiers (OIDs) for every table. Use this option if your application references the OID columns in some way (e.g., in a foreign key constraint). Otherwise, this option should not be used.

`-v`
`--verbose`

Specifies verbose mode. This will cause pg_dumpall to print progress messages to standard error.

The following command-line options control the database connection parameters.

-h *host*

Specifies the host name of the machine on which the database server is running. If host begins with a slash, it is used as the directory for the Unix domain socket. The default is taken from the `PGHOST` environment variable, if set, else a Unix domain socket connection is attempted.

-p *port*

The port number on which the server is listening. Defaults to the `PGPORT` environment variable, if set, or a compiled-in default.

-U *username*

Connect as the given user.

-W

Force a password prompt. This should happen automatically if the server requires password authentication.

Long options are only available on some platforms.

Environment

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Notes

Since pg_dumpall calls pg_dump internally, some diagnostic messages will refer to pg_dump.

pg_dumpall will need to connect several times to the PostgreSQL server. If password authentication is configured, it will ask for a password each time. In that case it would be convenient to set up a password file.

Examples

To dump all databases:

```
$ pg_dumpall > db.out
```

To reload this database use, for example:

```
$ psql -f db.out template1
```

(It is not important to which database you connect here since the script file created by pg_dumpall will contain the appropriate commands to create and connect to the saved databases.)

See Also

pg_dump, psql. Check there for details on possible error conditions.

<docinfo>2001-03-06</docinfo>

Name

pg_restore — restore a PostgreSQL database from an archive file created by pg_dump

Synopsis

```
pg_restore [options...]
```

Description

pg_restore is a utility for restoring a PostgreSQL database from an archive created by pg_dump in one of the non-plain-text formats. It will issue the commands necessary to re-generate all user-defined types, functions, tables, indexes, aggregates, and operators, as well as the data in the tables.

The archive files contain information for pg_restore to rebuild the database, but also allow pg_restore to be selective about what is restored, or even to reorder the items prior to being restored. The archive files are designed to be portable across architectures.

pg_restore can operate in two modes: If a database name is specified, the archive is restored directly into the database. Otherwise, a script containing the SQL commands necessary to rebuild the database is created (and written to a file or standard output), similar to the ones created by the pg_dump plain text format. Some of the options controlling the script output are therefore analogous to pg_dump options.

Obviously, pg_restore cannot restore information that is not present in the archive file; for instance, if the archive was made using the "dump data as `INSERT`s" option, pg_restore will not be able to load the data using `COPY` statements.

Options

`pg_restore` accepts the following command line arguments. (Long option forms are only available on some platforms.)

`archive-name`

Specifies the location of the archive file to be restored. If not specified, the standard input is used.

`-a`
`--data-only`

Restore only the data, no schema (definitions).

`-c`
`--clean`

Clean (drop) database objects before recreating them.

`-C`
`--create`

Create the database before restoring into it. (When this switch appears, the database named with `-d` is used only to issue the initial `CREATE DATABASE` command. All data is restored into the database name that appears in the archive.)

`-d` *`dbname`*
`--dbname=`*`dbname`*

Connect to database *`dbname`* and restore directly into the database. Large objects can only be restored by using a direct database connection.

`-f` *filename*
`--file=`*filename*

Specify output file for generated script, or for the listing when used with `-l`. Default is the standard output.

`-F` *format*
`--format=`*format*

Specify format of the archive. It is not necessary to specify the format, since pg_restore will determine the format automatically. If specified, it can be one of the following:

t

Archive is a `tar` archive. Using this archive format allows reordering and/or exclusion of schema elements at the time the database is restored. It is also possible to limit which data is reloaded at restore time.

c

Archive is in the custom format of pg_dump. This is the most flexible format in that it allows reordering of data load as well as schema elements. This format is also compressed by default.

`-i`
`--ignore-version`

Ignore database version checks.

`-I` *index*
`--index=`*index*

Restore definition for named *index* only.

`-l`
`--list`

List the contents of the archive. The output of this command can be used with the `-L` option to restrict and reorder the items that are restored.

`-L` *list-file*
`--use-list=`*list-file*

Restore elements in *list-file* only, and in the order they appear in the file. Lines can be moved and may also be commented out by placing a `;` at the start of the line.

`-N`
`--orig-order`

Restore items in the original dump order. By default pg_dump will dump items in an order convenient to pg_dump, then save the archive in a modified OID order. This option overrides the OID ordering.

`-o`
`--oid-order`

Restore items in the OID order. By default pg_dump will dump items in an order convenient to pg_dump, then save the archive in a modified OID order. This option enforces strict OID ordering.

`-O`
`--no-owner`

Prevent any attempt to restore original object ownership. Objects will be owned by the user name used to attach to the database.

`-P` *`function-name(argtype [, ...])`*
`--function=`*`function-name(argtype [, ...])`*

Specify a procedure or function to be restored.

`-r`
`--rearrange`

Restore items in modified OID order. By default pg_dump will dump items in an order convenient to pg_dump, then save the archive in a modified OID order. Most objects will be restored in OID order, but some things (e.g., rules and indexes) will be restored at the end of the process irrespective of their OIDs. This option is the default.

`-R`
`--no-reconnect`

While restoring an archive, pg_restore typically has to reconnect to the database several times with different user names to set the correct ownership of the created objects. If this is undesirable (e.g., because manual interaction (passwords) would be necessary for each reconnection), this option prevents pg_restore from issuing any reconnection requests. (A connection request while in plain text mode, not connected to a database, is made by putting out a psql `\connect` command.) However, this option is a rather blunt instrument because it makes pg_restore lose all object ownership information, *unless* you use the `-X use-set-session-authorization` option.

`-s`
`--schema-only`

Restore the schema (definitions), no data. Sequence values will be reset.

`-S` *`username`*
`--superuser=`*`username`*

Specify the superuser user name to use when disabling triggers. This is only relevant if `--disable-triggers` is used.

`-t` *`table`*
`--table=`*`table`*

Restore schema/data for *`table`* only.

`-T` *`trigger`*
`--trigger=`*`trigger`*

Restore definition of *`trigger`* only.

`-v`
`--verbose`

Specifies verbose mode.

`-x`
`--no-privileges`
`--no-acl`

Prevent restoration of access privileges (grant/revoke commands).

`-X use-set-session-authorization`
`--use-set-session-authorization`

Normally, if restoring an archive requires altering the current database user (e.g., to set correct object ownerships), a new connection to the database must be opened, which might require manual

interaction (e.g., passwords). If you use the `-X use-set-session-authorization` option, then pg_restore will instead use the SET SESSION AUTHORIZATION command. This has the same effect, but it requires that the user restoring the archive is a database superuser. This option effectively overrides the `-R` option.

`-X disable-triggers`
`--disable-triggers`

This option is only relevant when performing a data-only restore. It instructs pg_restore to execute commands to temporarily disable triggers on the target tables while the data is reloaded. Use this if you have referential integrity checks or other triggers on the tables that you do not want to invoke during data reload.

Presently, the commands emitted for `--disable-triggers` must be done as superuser. So, you should also specify a superuser name with `-S`, or preferably specify `--use-set-session-authorization` and run pg_restore as a PostgreSQL superuser.

`pg_restore` also accepts the following command line arguments for connection parameters:

`-h` *host*
`--host=`*host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port=`*port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections. The port number defaults to 5432, or the value of the `PGPORT` environment variable (if set).

`-U` *username*

Connect as the given user

`-W`

Force a password prompt. This should happen automatically if the server requires password authentication.

Environment

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Diagnostics

```
Connection to database 'template1' failed.
connectDBStart() -- connect() failed: No such file or directory
        Is the postmaster running locally
        and accepting connections on Unix socket '/
tmp/.s.PGSQL.5432'?
```

pg_restore could not attach to the PostgreSQL server process on the specified host and port. If you see this message, ensure that the server is running on the proper host and that you have specified the

proper port. If your site uses an authentication system, ensure that you have obtained the required authentication credentials.

Note

When a direct database connection is specified using the -d option, pg_restore internally executes SQL statements. If you have problems running pg_restore, make sure you are able to select information from the database using, for example, psql.

Notes

If your installation has any local additions to the `template1` database, be careful to load the output of pg_restore into a truly empty database; otherwise you are likely to get errors due to duplicate definitions of the added objects. To make an empty database without any local additions, copy from template0 not template1, for example:

```
CREATE DATABASE foo WITH TEMPLATE = template0;
```

The limitations of pg_restore are detailed below.

- When restoring data to a pre-existing table, pg_restore emits queries to disable triggers on user tables before inserting the data then emits queries to re-enable them after the data has been inserted. If the restore is stopped in the middle, the system catalogs may be left in the wrong state.
- pg_restore will not restore large objects for a single table. If an archive contains large objects, then all large objects will be restored.

See also the pg_dump documentation for details on limitations of pg_dump.

Examples

To dump a database:

```
$ pg_dump mydb > db.out
```

To reload this database:

```
$ psql -d database -f db.out
```

To dump a database called `mydb` that contains large objects to a `tar` file:

```
$ pg_dump -Ft -b mydb > db.tar
```

To reload this database (with large objects) to an existing database called `newdb`:

```
$ pg_restore -d newdb db.tar
```

To reorder database items, it is first necessary to dump the table of contents of the archive:

```
$ pg_restore -l archive.file > archive.list
```

The listing file consists of a header and one line for each item, e.g.,

```
;
; Archive created at Fri Jul 28 22:28:36 2000
;     dbname: birds
;     TOC Entries: 74
;     Compression: 0
;     Dump Version: 1.4-0
;     Format: CUSTOM
```

```
;
;
; Selected TOC Entries:
;
2; 145344 TABLE species postgres
3; 145344 ACL species
4; 145359 TABLE nt_header postgres
5; 145359 ACL nt_header
6; 145402 TABLE species_records postgres
7; 145402 ACL species_records
8; 145416 TABLE ss_old postgres
9; 145416 ACL ss_old
10; 145433 TABLE map_resolutions postgres
11; 145433 ACL map_resolutions
12; 145443 TABLE hs_old postgres
13; 145443 ACL hs_old
```

Semi-colons are comment delimiters, and the numbers at the start of lines refer to the internal archive ID assigned to each item.

Lines in the file can be commented out, deleted, and reordered. For example,

```
10; 145433 TABLE map_resolutions postgres
;2; 145344 TABLE species postgres
;4; 145359 TABLE nt_header postgres
6; 145402 TABLE species_records postgres
;8; 145416 TABLE ss_old postgres
```

could be used as input to `pg_restore` and would only restore items 10 and 6, in that order.

```
$ pg_restore -L archive.list archive.file
```

History

The pg_restore utility first appeared in PostgreSQL 7.1.

See Also

pg_dump, pg_dumpall, psql, *PostgreSQL Administrator's Guide*

Name

psql — PostgreSQL interactive terminal

Synopsis

`psql` [*options*] [*dbname* [*user*]]

Description

psql is a terminal-based front-end to PostgreSQL. It enables you to type in queries interactively, issue them to PostgreSQL, and see the query results. Alternatively, input can be from a file. In addition, it provides a number of meta-commands and various shell-like features to facilitate writing scripts and automating a wide variety of tasks.

Options

`-a`
`--echo-all`

Print all the lines to the screen as they are read. This is more useful for script processing rather than interactive mode. This is equivalent to setting the variable `ECHO` to `all`.

`-A`
`--no-align`

Switches to unaligned output mode. (The default output mode is otherwise aligned.)

`-c` *query*
`--command` *query*

Specifies that psql is to execute one query string, *query*, and then exit. This is useful in shell scripts.

query must be either a query string that is completely parsable by the backend (i.e., it contains no psql specific features), or it is a single backslash command. Thus you cannot mix SQL and psql meta-commands. To achieve that, you could pipe the string into psql, like this: `echo "\x \\ select * from foo;" | psql`.

`-d` *dbname*
`--dbname` *dbname*

Specifies the name of the database to connect to. This is equivalent to specifying *dbname* as the first non-option argument on the command line.

`-e`
`--echo-queries`

Show all queries that are sent to the backend. This is equivalent to setting the variable `ECHO` to `queries`.

`-E`
`--echo-hidden`

Echoes the actual queries generated by \d and other backslash commands. You can use this if you wish to include similar functionality into your own programs. This is equivalent to setting the variable `ECHO_HIDDEN` from within psql.

`-f` *`filename`*
`--file` *`filename`*

Use the file *`filename`* as the source of queries instead of reading queries interactively. After the file is processed, psql terminates. This is in many ways equivalent to the internal command `\i`.

If *`filename`* is `-` (hyphen), then standard input is read.

Using this option is subtly different from writing `psql < `*`filename`*. In general, both will do what you expect, but using `-f` enables some nice features such as error messages with line numbers. There is also a slight chance that using this option will reduce the start-up overhead. On the other hand, the variant using the shell's input redirection is (in theory) guaranteed to yield exactly the same output that you would have gotten had you entered everything by hand.

`-F` *`separator`*
`--field-separator` *`separator`*

Use *`separator`* as the field separator. This is equivalent to `\pset fieldsep` or `\f`.

`-h` *`hostname`*
`--host` *`hostname`*

Specifies the host name of the machine on which the postmaster is running. If host begins with a slash, it is used as the directory for the Unix-domain socket.

`-H`
`--html`

Turns on HTML tabular output. This is equivalent to `\pset format html` or the `\H` command.

`-l`
`--list`

Lists all available databases, then exits. Other non-connection options are ignored. This is similar to the internal command `\list`.

`-o` *`filename`*
`--output` *`filename`*

Put all query output into file *`filename`*. This is equivalent to the command `\o`.

`-p` *`port`*
`--port` *`port`*

Specifies the TCP/IP port or, by omission, the local Unix domain socket file extension on which the postmaster is listening for connections. Defaults to the value of the `PGPORT` environment variable or, if not set, to the port specified at compile time, usually 5432.

`-P` *`assignment`*
`--pset` *`assignment`*

Allows you to specify printing options in the style of `\pset` on the command line. Note that here you have to separate name and value with an equal sign instead of a space. Thus to set the output format to LaTeX, you could write `-P format=latex`.

`-q`
`--quiet`

Specifies that psql should do its work quietly. By default, it prints welcome messages and various informational output. If this option is used, none of this happens. This is useful with the `-c` option. Within psql you can also set the `QUIET` variable to achieve the same effect.

`-R` *separator*
`--record-separator` *separator*

Use *separator* as the record separator. This is equivalent to the `\pset recordsep` command.

`-s`
`--single-step`

Run in single-step mode. That means the user is prompted before each query is sent to the backend, with the option to cancel execution as well. Use this to debug scripts.

`-S`
`--single-line`

Runs in single-line mode where a newline terminates a query, as a semicolon does.

Note

This mode is provided for those who insist on it, but you are not necessarily encouraged to use it. In particular, if you mix SQL and meta-commands on a line the order of execution might not always be clear to the inexperienced user.

`-t`
`--tuples-only`

Turn off printing of column names and result row count footers, etc. It is completely equivalent to the `\t` meta-command.

`-T` *table_options*
`--table-attr` *table_options*

Allows you to specify options to be placed within the HTML `table` tag. See `\pset` for details.

`-u`

Makes psql prompt for the user name and password before connecting to the database.

This option is deprecated, as it is conceptually flawed. (Prompting for a non-default user name and prompting for a password because the backend requires it are really two different things.) You are encouraged to look at the `-U` and `-W` options instead.

`-U` *username*
`--username` *username*

Connects to the database as the user *username* instead of the default. (You must have permission to do so, of course.)

`-v` *assignment*
`--set` *assignment*
`--variable` *assignment*

Performs a variable assignment, like the `\set` internal command. Note that you must separate name and value, if any, by an equal sign on the command line. To unset a variable, leave off the equal sign. To just set a variable without a value, use the equal sign but leave off the value. These assignments are done during a very early stage of start-up, so variables reserved for internal purposes might get overwritten later.

`-V`
`--version`

Shows the psql version.

`-W`
`--password`

Requests that psql should prompt for a password before connecting to a database. This will remain set for the entire session, even if you change the database connection with the meta-command `\connect`.

In the current version, psql automatically issues a password prompt whenever the backend requests password authentication. Because this is currently based on a hack, the automatic recognition might mysteriously fail, hence this option to force a prompt. If no password prompt is issued and the backend requires password authentication the connection attempt will fail.

`-x`
`--expanded`

Turns on extended row format mode. This is equivalent to the command `\x`.

`-X,`
`--no-psqlrc`

Do not read the start-up file `~/.psqlrc`.

`-?`
`--help`

Shows help about psql command line arguments.

Long options are not available on all platforms.

Exit Status

psql returns 0 to the shell if it finished normally, 1 if a fatal error of its own (out of memory, file not found) occurs, 2 if the connection to the backend went bad and the session is not interactive, and 3 if an error occurred in a script and the variable `ON_ERROR_STOP` was set.

Usage

Connecting To A Database

psql is a regular PostgreSQL client application. In order to connect to a database you need to know the name of your target database, the host name and port number of the server and what user name you want to connect as. psql can be told about those parameters via command line options, namely `-d`, `-h`, `-p`, and `-U` respectively. If an argument is found that does not belong to any option it will be interpreted as the database name (or the user name, if the database name is also given). Not all these options are required, defaults do apply. If you omit the host name, psql will connect via a Unix domain socket to a server on the local host. The default port number is compile-time determined. Since the database server uses the same default, you will not have to specify the port in most cases. The default user name is your Unix user name, as is the default database name. Note that you can't just connect to any database under any user name. Your database administrator should have informed you about your access rights. To save you some typing you can also set the environment variables `PGDATABASE`, `PGHOST`, `PGPORT` and `PGUSER` to appropriate values.

If the connection could not be made for any reason (e.g., insufficient privileges, postmaster is not running on the server, etc.), psql will return an error and terminate.

Entering Queries

In normal operation, psql provides a prompt with the name of the database to which psql is currently connected, followed by the string =>. For example,

```
$ psql testdb
Welcome to psql 7.3.21, the PostgreSQL interactive terminal.

Type:  \copyright for distribution terms
       \h for help with SQL commands
       \? for help on internal slash commands
       \g or terminate with semicolon to execute query
       \q to quit

testdb=>
```

At the prompt, the user may type in SQL queries. Ordinarily, input lines are sent to the backend when a query-terminating semicolon is reached. An end of line does not terminate a query! Thus queries can be spread over several lines for clarity. If the query was sent and without error, the query results are displayed on the screen.

Whenever a query is executed, psql also polls for asynchronous notification events generated by LISTEN and NOTIFY.

Meta-Commands

Anything you enter in psql that begins with an unquoted backslash is a psql meta-command that is processed by psql itself. These commands are what makes psql interesting for administration or scripting. Meta-commands are more commonly called slash or backslash commands.

The format of a psql command is the backslash, followed immediately by a command verb, then any arguments. The arguments are separated from the command verb and each other by any number of whitespace characters.

To include whitespace into an argument you may quote it with a single quote. To include a single quote into such an argument, precede it by a backslash. Anything contained in single quotes is furthermore subject to C-like substitutions for `\n` (new line), `\t` (tab), `\`*`digits`*, `\0`*`digits`*, and `\0x`*`digits`* (the character with the given decimal, octal, or hexadecimal code).

If an unquoted argument begins with a colon (`:`), it is taken as a psql variable and the value of the variable is used as the argument instead.

Arguments that are enclosed in backquotes (`` ` ``) are taken as a command line that is passed to the shell. The output of the command (with any trailing newline removed) is taken as the argument value. The above escape sequences also apply in backquotes.

Some commands take an SQL identifier (such as a table name) as argument. These arguments follow the syntax rules of SQL regarding double quotes: an identifier without double quotes is coerced to lower-case, while whitespace within double quotes is included in the argument.

Parsing for arguments stops when another unquoted backslash occurs. This is taken as the beginning of a new meta-command. The special sequence `\\` (two backslashes) marks the end of arguments and continues parsing SQL queries, if any. That way SQL and psql commands can be freely mixed on a line. But in any case, the arguments of a meta-command cannot continue beyond the end of the line.

The following meta-commands are defined:

`\a`

If the current table output format is unaligned, switch to aligned. If it is not unaligned, set it to unaligned. This command is kept for backwards compatibility. See `\pset` for a general solution.

`\cd [`*`directory`*`]`

Change the current working directory to *`directory`*. Without argument, change to the current user's home directory.

Tip

To print your current working directory, use `\!pwd`.

`\C [ title ]`

Set the title of any tables being printed as the result of a query or unset any such title. This command is equivalent to `\pset title title`. (The name of this command derives from "caption", as it was previously only used to set the caption in an HTML table.)

`\connect` (or `\c`) [*dbname* [*username*]]

Establishes a connection to a new database and/or under a user name. The previous connection is closed. If *dbname* is - the current database name is assumed.

If *username* is omitted the current user name is assumed.

As a special rule, `\connect` without any arguments will connect to the default database as the default user (as you would have gotten by starting psql without any arguments).

If the connection attempt failed (wrong user name, access denied, etc.), the previous connection will be kept if and only if psql is in interactive mode. When executing a non-interactive script, processing will immediately stop with an error. This distinction was chosen as a user convenience against typos on the one hand, and a safety mechanism that scripts are not accidentally acting on the wrong database on the other hand.

`\copy table [ ( column_list ) ] { from | to } filename | stdin | stdout [ with ] [ oids ] [ delimiter [as] 'character' ] [ null [as] 'string' ]`

Performs a frontend (client) copy. This is an operation that runs an SQL COPY command, but instead of the backend's reading or writing the specified file, psql reads or writes the file and routes the data between the backend and the local file system. This means that file accessibility and privileges are those of the local user, not the server, and no SQL superuser privileges are required.

The syntax of the command is similar to that of the SQL `COPY` command (see its description for the details). Note that, because of this, special parsing rules apply to the `\copy` command. In particular, the variable substitution rules and backslash escapes do not apply.

Tip

This operation is not as efficient as the SQL `COPY` command because all data must pass through the client/server IP or socket connection. For large amounts of data the other technique may be preferable.

Note

Note the difference in interpretation of `stdin` and `stdout` between frontend and backend copies: in a frontend copy these always refer to psql's input and output stream. On a backend copy `stdin` comes from wherever the `COPY` itself came from (for example, a script run with the `-f` option), and `stdout` refers to the query output stream (see `\o` meta-command below).

`\copyright`

Shows the copyright and distribution terms of PostgreSQL.

`\d [ pattern ]`

For each relation (table, view, index, or sequence) matching the *pattern*, show all columns, their types, and any special attributes such as `NOT NULL` or defaults, if any. Associated indexes,

constraints, rules, and triggers are also shown, as is the view definition if the relation is a view. ("Matching the pattern" is defined below.)

The command form `\d+` is identical, but any comments associated with the table columns are shown as well.

Note

If `\d` is used without a *`pattern`* argument, it is equivalent to `\dtvs` which will show a list of all tables, views, and sequences. This is purely a convenience measure.

`\da [ pattern ]`

Lists all available aggregate functions, together with the data type they operate on. If *`pattern`* (a regular expression) is specified, only matching aggregates are shown.

`\dd [ pattern ]`

Shows the descriptions of objects matching the *`pattern`*, or of all visible objects if no argument is given. But in either case, only objects that have a description are listed. ("Object" covers aggregates, functions, operators, types, relations (tables, views, indexes, sequences, large objects), rules, and triggers.) For example:

```
=> \dd version
                      Object descriptions
   Schema   |  Name   |  Object  |        Description
------------+---------+----------+---------------------------
 pg_catalog | version | function | PostgreSQL version string
(1 row)
```

Descriptions for objects can be created with the `COMMENT ON` SQL command.

Note

PostgreSQL stores the object descriptions in the `pg_description` system table.

`\dD [ pattern ]`

Lists all available domains (derived types). If *`pattern`* is specified, only matching domains are shown.

`\df [ pattern ]`

Lists available functions, together with their argument and return types. If *`pattern`* is specified, only matching functions are shown. If the form `\df+` is used, additional information about each function, including language and description, is shown.

Note

To reduce clutter, `\df` does not show data type I/O functions. This is implemented by ignoring functions that accept or return type `cstring`.

`\distvS [ pattern ]`

This is not the actual command name: the letters i, s, t, v, S stand for index, sequence, table, view, and system table, respectively. You can specify any or all of these letters, in any order, to obtain a listing of all the matching objects. The letter S restricts the listing to system objects; without S, only non-system objects are shown. If "+" is appended to the command name, each object is listed with its associated description, if any.

If a *`pattern`* is specified, only objects whose name matches the pattern are listed.

`\dl`

This is an alias for `\lo_list`, which shows a list of large objects.

`\do [ pattern ]`

Lists available operators with their operand and return types. If a *pattern* is specified, only operators whose name matches the pattern are listed.

`\dp [ pattern ]`

Produces a list of all available tables with their associated access permissions. If a *pattern* is specified, only tables whose name matches the pattern are listed.

The commands GRANT and REVOKE are used to set access permissions. See GRANT for more information.

`\dT [ pattern ]`

Lists all data types or only those that match *pattern*. The command form `\dT+` shows extra information.

`\du [ pattern ]`

Lists all database users, or only those that match *pattern*.

`\edit` (or `\e`) [*filename*]

If *filename* is specified, the file is edited; after the editor exits, its content is copied back to the query buffer. If no argument is given, the current query buffer is copied to a temporary file which is then edited in the same fashion.

The new query buffer is then re-parsed according to the normal rules of psql, where the whole buffer is treated as a single line. (Thus you cannot make scripts this way. Use `\i` for that.) This means also that if the query ends with (or rather contains) a semicolon, it is immediately executed. In other cases it will merely wait in the query buffer.

Tip

psql searches the environment variables `PSQL_EDITOR`, `EDITOR`, and `VISUAL` (in that order) for an editor to use. If all of them are unset, `/bin/vi` is run.

`\echo text [ ... ]`

Prints the arguments to the standard output, separated by one space and followed by a newline. This can be useful to intersperse information in the output of scripts. For example:

```
=> \echo `date`
Tue Oct 26 21:40:57 CEST 1999
```

If the first argument is an unquoted `-n` the the trailing newline is not written.

Tip

If you use the `\o` command to redirect your query output you may wish to use `\qecho` instead of this command.

`\encoding [ encoding ]`

Sets the client encoding, if you are using multibyte encodings. Without an argument, this command shows the current encoding.

`\f` [*string*]

Sets the field separator for unaligned query output. The default is pipe (`|`). See also `\pset` for a generic way of setting output options.

`\g` [{ *filename* | `|` *command* }]

Sends the current query input buffer to the backend and optionally saves the output in *filename* or pipes the output into a separate Unix shell to execute *command*. A bare `\g` is virtually equivalent to a semicolon. A `\g` with argument is a "one-shot" alternative to the `\o` command.

`\help` (or `\h`) [*command*]

Give syntax help on the specified SQL command. If *command* is not specified, then psql will list all the commands for which syntax help is available. If *command* is an asterisk ("*"), then syntax help on all SQL commands is shown.

Note

To simplify typing, commands that consists of several words do not have to be quoted. Thus it is fine to type **`\help alter table`**.

`\H`

Turns on HTML query output format. If the HTML format is already on, it is switched back to the default aligned text format. This command is for compatibility and convenience, but see `\pset` about setting other output options.

`\i` *filename*

Reads input from the file *filename* and executes it as though it had been typed on the keyboard.

Note

If you want to see the lines on the screen as they are read you must set the variable `ECHO` to `all`.

`\l` (or `\list`)

List all the databases in the server as well as their owners. Append a "+" to the command name to see any descriptions for the databases as well. If your PostgreSQL installation was compiled with multibyte encoding support, the encoding scheme of each database is shown as well.

`\lo_export` *loid filename*

Reads the large object with OID *loid* from the database and writes it to *filename*. Note that this is subtly different from the server function `lo_export`, which acts with the permissions of the user that the database server runs as and on the server's file system.

Tip

Use `\lo_list` to find out the large object's OID.

Note

See the description of the `LO_TRANSACTION` variable for important information concerning all large object operations.

`\lo_import` *filename* [*comment*]

Stores the file into a PostgreSQL "large object". Optionally, it associates the given comment with the object. Example:

```
foo=> \lo_import '/home/peter/pictures/photo.xcf' 'a picture of
 me'
lo_import 152801
```

The response indicates that the large object received object id 152801 which one ought to remember if one wants to access the object ever again. For that reason it is recommended to always associate a human-readable comment with every object. Those can then be seen with the `\lo_list` command.

Note that this command is subtly different from the server-side `lo_import` because it acts as the local user on the local file system, rather than the server's user and file system.

Note

See the description of the `LO_TRANSACTION` variable for important information concerning all large object operations.

`\lo_list`

Shows a list of all PostgreSQL "large objects" currently stored in the database, along with any comments provided for them.

`\lo_unlink` *`loid`*

Deletes the large object with OID *`loid`* from the database.

Tip

Use `\lo_list` to find out the large object's OID.

Note

See the description of the `LO_TRANSACTION` variable for important information concerning all large object operations.

`\o` [{*`filename`* | `|` *`command`*}]

Saves future query results to the file *`filename`* or pipes future results into a separate Unix shell to execute *`command`*. If no arguments are specified, the query output will be reset to `stdout`.

"Query results" includes all tables, command responses, and notices obtained from the database server, as well as output of various backslash commands that query the database (such as `\d`), but not error messages.

Tip

To intersperse text output in between query results, use `\qecho`.

`\p`

Print the current query buffer to the standard output.

`\pset` *`parameter`* [*`value`*]

This command sets options affecting the output of query result tables. *`parameter`* describes which option is to be set. The semantics of *`value`* depend thereon.

Adjustable printing options are:

`format`

Sets the output format to one of `unaligned`, `aligned`, `html`, or `latex`. Unique abbreviations are allowed. (That would mean one letter is enough.)

"Unaligned" writes all fields of a tuple on a line, separated by the currently active field separator. This is intended to create output that might be intended to be read in by other programs (tab-separated, comma-separated). "Aligned" mode is the standard, human-readable, nicely formatted text output that is default. The "HTML" and "LaTeX" modes put out tables that are intended to be included in documents using the respective mark-up language. They are not complete documents! (This might not be so dramatic in HTML, but in LaTeX you must have a complete document wrapper.)

`border`

The second argument must be a number. In general, the higher the number the more borders and lines the tables will have, but this depends on the particular format. In HTML mode, this will translate directly into the `border=...` attribute, in the others only values 0 (no border), 1 (internal dividing lines), and 2 (table frame) make sense.

`expanded` (or `x`)

Toggles between regular and expanded format. When expanded format is enabled, all output has two columns with the field name on the left and the data on the right. This mode is useful if the data wouldn't fit on the screen in the normal "horizontal" mode.

Expanded mode is supported by all four output modes.

`null`

The second argument is a string that should be printed whenever a field is null. The default is not to print anything, which can easily be mistaken for, say, an empty string. Thus, one might choose to write `\pset null '(null)'`.

`fieldsep`

Specifies the field separator to be used in unaligned output mode. That way one can create, for example, tab- or comma-separated output, which other programs might prefer. To set a tab as field separator, type `\pset fieldsep '\t'`. The default field separator is `'|'` (a "pipe" symbol).

`footer`

Toggles the display of the default footer `(x rows)`.

`recordsep`

Specifies the record (line) separator to use in unaligned output mode. The default is a newline character.

`tuples_only` (or `t`)

Toggles between tuples only and full display. Full display may show extra information such as column headers, titles, and various footers. In tuples only mode, only actual table data is shown.

`title` [*`text`*]

Sets the table title for any subsequently printed tables. This can be used to give your output descriptive tags. If no argument is given, the title is unset.

Note

This formerly only affected HTML mode. You can now set titles in any output format.

`tableattr` (or `T`) [*`text`*]

Allows you to specify any attributes to be placed inside the HTML `table` tag. This could for example be `cellpadding` or `bgcolor`. Note that you probably don't want to specify `border` here, as that is already taken care of by `\pset border`.

`pager`

Toggles the use of a pager for query and psql help output. If the environment variable `PAGER` is set, the output is piped to the specified program. Otherwise a platform-dependent default (such as `more`) is used.

In any case, psql only uses the pager if it seems appropriate. That means among other things that the output is to a terminal and that the table would normally not fit on the screen. Because of the modular nature of the printing routines it is not always possible to predict the number of lines that will actually be printed. For that reason psql might not appear very discriminating about when to use the pager.

Illustrations on how these different formats look can be seen in the Examples section.

Tip

There are various shortcut commands for `\pset`. See `\a`, `\C`, `\H`, `\t`, `\T`, and `\x`.

Note

It is an error to call `\pset` without arguments. In the future this call might show the current status of all printing options.

`\q`

Quit the psql program.

`\qecho` *`text`* [...]

This command is identical to `\echo` except that all output will be written to the query output channel, as set by `\o`.

`\r`

Resets (clears) the query buffer.

`\s` [*`filename`*]

Print or save the command line history to *`filename`*. If *`filename`* is omitted, the history is written to the standard output. This option is only available if psql is configured to use the GNU history library.

Note

In the current version, it is no longer necessary to save the command history, since that will be done automatically on program termination. The history is also loaded automatically every time psql starts up.

`\set` [*`name`* [*`value`* [...]]]

Sets the internal variable *`name`* to *`value`* or, if more than one value is given, to the concatenation of all of them. If no second argument is given, the variable is just set with no value. To unset a variable, use the `\unset` command.

Valid variable names can contain characters, digits, and underscores. See the section about psql variables for details.

Although you are welcome to set any variable to anything you want, psql treats several variables as special. They are documented in the section about variables.

Note

This command is totally separate from the SQL command SET.

`\t`

Toggles the display of output column name headings and row count footer. This command is equivalent to `\pset tuples_only` and is provided for convenience.

`\T` *table_options*

Allows you to specify options to be placed within the `table` tag in HTML tabular output mode. This command is equivalent to `\pset tableattr` *table_options*.

`\timing`

Toggles a display of how long each SQL statement takes, in milliseconds.

`\w` {*filename* | | *command*}

Outputs the current query buffer to the file *filename* or pipes it to the Unix command *command*.

`\x`

Toggles extended row format mode. As such it is equivalent to `\pset expanded`.

`\z` [*pattern*]

Produces a list of all available tables with their associated access permissions. If a *pattern* is specified, only tables whose name matches the pattern are listed.

The commands GRANT and REVOKE are used to set access permissions. See GRANT for more information.

This is an alias for `\dp` (“display permissions”).

`\!` [*command*]

Escapes to a separate Unix shell or executes the Unix command *command*. The arguments are not further interpreted, the shell will see them as is.

`\?`

Get help information about the backslash (“\”) commands.

The various `\d` commands accept a *pattern* parameter to specify the object name(s) to be displayed. Patterns are interpreted similarly to SQL identifiers, in that unquoted letters are forced to lowercase, while double quotes (`"`) protect letters from case conversion and allow incorporation of whitespace into the identifier. Within double quotes, paired double quotes reduce to a single double quote in the resulting name. For example, `FOO"BAR"BAZ` is interpreted as `fooBARbaz`, and `"A weird"" name"` becomes `A weird" name`.

More interestingly, `\d` patterns allow the use of `*` to mean “any sequence of characters”, and `?` to mean “any single character”. (This notation is comparable to Unix shell filename patterns.) Advanced users can also use regular-expression notations such as character classes, for example `[0-9]` to match “any digit”. To make any of these pattern-matching characters be interpreted literally, surround it with double quotes.

A pattern that contains an (unquoted) dot is interpreted as a schema name pattern followed by an object name pattern. For example, `\dt foo*.bar*` displays all tables in schemas whose name starts with `foo` and whose table name starts with `bar`. If no dot appears, then the pattern matches only objects that are visible in the current schema search path.

Whenever the *`pattern`* parameter is omitted completely, the `\d` commands display all objects that are visible in the current schema search path. To see all objects in the database, use the pattern `*.*`.

Advanced features

Variables

psql provides variable substitution features similar to common Unix command shells. This feature is new and not very sophisticated, yet, but there are plans to expand it in the future. Variables are simply name/value pairs, where the value can be any string of any length. To set variables, use the psql meta-command `\set`:

```
testdb=> \set foo bar
```

sets the variable “foo” to the value “bar”. To retrieve the content of the variable, precede the name with a colon and use it as the argument of any slash command:

```
testdb=> \echo :foo
bar
```

Note

The arguments of `\set` are subject to the same substitution rules as with other commands. Thus you can construct interesting references such as `\set :foo 'something'` and get “soft links” or “variable variables” of Perl or PHP fame, respectively. Unfortunately (or fortunately?), there is no way to do anything useful with these constructs. On the other hand, `\set bar :foo` is a perfectly valid way to copy a variable.

If you call `\set` without a second argument, the variable is simply set, but has no value. To unset (or delete) a variable, use the command `\unset`.

psql's internal variable names can consist of letters, numbers, and underscores in any order and any number of them. A number of regular variables are treated specially by psql. They indicate certain option settings that can be changed at run time by altering the value of the variable or represent some state of the application. Although you can use these variables for any other purpose, this is not recommended, as the program behavior might grow really strange really quickly. By convention, all specially treated variables consist of all upper-case letters (and possibly numbers and underscores). To ensure maximum compatibility in the future, avoid such variables. A list of all specially treated variables follows.

`DBNAME`

The name of the database you are currently connected to. This is set every time you connect to a database (including program start-up), but can be unset.

`ECHO`

If set to “`all`”, all lines entered or from a script are written to the standard output before they are parsed or executed. To specify this on program start-up, use the switch `-a`. If set to “`queries`”, psql merely prints all queries as they are sent to the backend. The option for this is `-e`.

`ECHO_HIDDEN`

When this variable is set and a backslash command queries the database, the query is first shown. This way you can study the PostgreSQL internals and provide similar functionality in your own

programs. If you set the variable to the value `noexec`, the queries are just shown but are not actually sent to the backend and executed.

`ENCODING`

The current client multibyte encoding. If you are not set up to use multibyte characters, this variable will always contain "SQL_ASCII".

`HISTCONTROL`

If this variable is set to `ignorespace`, lines which begin with a space are not entered into the history list. If set to a value of `ignoredups`, lines matching the previous history line are not entered. A value of `ignoreboth` combines the two options. If unset, or if set to any other value than those above, all lines read in interactive mode are saved on the history list.

Note

This feature was shamelessly plagiarized from bash.

`HISTSIZE`

The number of commands to store in the command history. The default value is 500.

Note

This feature was shamelessly plagiarized from bash.

`HOST`

The database server host you are currently connected to. This is set every time you connect to a database (including program start-up), but can be unset.

`IGNOREEOF`

If unset, sending an EOF character (usually **Control**+**D**) to an interactive session of psql will terminate the application. If set to a numeric value, that many EOF characters are ignored before the application terminates. If the variable is set but has no numeric value, the default is 10.

Note

This feature was shamelessly plagiarized from bash.

`LASTOID`

The value of the last affected OID, as returned from an `INSERT` or `lo_insert` command. This variable is only guaranteed to be valid until after the result of the next SQL command has been displayed.

`LO_TRANSACTION`

If you use the PostgreSQL large object interface to specially store data that does not fit into one tuple, all the operations must be contained in a transaction block. (See the documentation of the large object interface for more information.) Since psql has no way to tell if you already have a transaction in progress when you call one of its internal commands (`\lo_export`, `\lo_import`, `\lo_unlink`) it must take some arbitrary action. This action could either be to roll back any transaction that might already be in progress, or to commit any such transaction, or to do nothing at all. In the last case you must provide your own `BEGIN TRANSACTION`/`COMMIT` block or the results will be unpredictable (usually resulting in the desired action's not being performed in any case).

To choose what you want to do you set this variable to one of "rollback", "commit", or "nothing". The default is to roll back the transaction. If you just want to load one or a few objects this is fine. However, if you intend to transfer many large objects, it might be advisable to provide one explicit transaction block around all commands.

`ON_ERROR_STOP`

By default, if non-interactive scripts encounter an error, such as a malformed SQL query or internal meta-command, processing continues. This has been the traditional behavior of psql but it is sometimes not desirable. If this variable is set, script processing will immediately terminate. If the script was called from another script it will terminate in the same fashion. If the outermost script was not called from an interactive psql session but rather using the `-f` option, psql will return error code 3, to distinguish this case from fatal error conditions (error code 1).

`PORT`

The database server port to which you are currently connected. This is set every time you connect to a database (including program start-up), but can be unset.

`PROMPT1`
`PROMPT2`
`PROMPT3`

These specify what the prompt psql issues is supposed to look like. See "Prompting" below.

`QUIET`

This variable is equivalent to the command line option `-q`. It is probably not too useful in interactive mode.

`SINGLELINE`

This variable is set by the command line option `-S`. You can unset or reset it at run time.

`SINGLESTEP`

This variable is equivalent to the command line option `-s`.

`USER`

The database user you are currently connected as. This is set every time you connect to a database (including program start-up), but can be unset.

SQL Interpolation

An additional useful feature of psql variables is that you can substitute ("interpolate") them into regular SQL statements. The syntax for this is again to prepend the variable name with a colon (`:`).

```
testdb=> \set foo 'my_table'
testdb=> SELECT * FROM :foo;
```

would then query the table `my_table`. The value of the variable is copied literally, so it can even contain unbalanced quotes or backslash commands. You must make sure that it makes sense where you put it. Variable interpolation will not be performed into quoted SQL entities.

A popular application of this facility is to refer to the last inserted OID in subsequent statements to build a foreign key scenario. Another possible use of this mechanism is to copy the contents of a file into a field. First load the file into a variable and then proceed as above.

```
testdb=> \set content '\'' `cat my_file.txt` '\''
testdb=> INSERT INTO my_table VALUES (:content);
```

One possible problem with this approach is that `my_file.txt` might contain single quotes. These need to be escaped so that they don't cause a syntax error when the third line is processed. This could be done with the program sed:

```
testdb=> \set content '\'' `sed -e "s/'/\\\\\\'/g" < my_file.txt`
 '\''
```

Observe the correct number of backslashes (6)! You can resolve it this way: After psql has parsed this line, it passes `sed -e "s/'/\\\'/g" < my_file.txt` to the shell. The shell will do its own thing inside the double quotes and execute `sed` with the arguments `-e` and `s/'/\\'/g`. When sed parses this it will replace the two backslashes with a single one and then do the substitution. Perhaps at one point you thought it was great that all Unix commands use the same escape character. And this is ignoring the fact that you might have to escape all backslashes as well because SQL text constants are also subject to certain interpretations. In that case you might be better off preparing the file externally.

Since colons may legally appear in queries, the following rule applies: If the variable is not set, the character sequence "colon+name" is not changed. In any case you can escape a colon with a backslash to protect it from interpretation. (The colon syntax for variables is standard SQL for embedded query languages, such as ecpg. The colon syntax for array slices and type casts are PostgreSQL extensions, hence the conflict.)

Prompting

The prompts psql issues can be customized to your preference. The three variables `PROMPT1`, `PROMPT2`, and `PROMPT3` contain strings and special escape sequences that describe the appearance of the prompt. Prompt 1 is the normal prompt that is issued when psql requests a new query. Prompt 2 is issued when more input is expected during query input because the query was not terminated with a semicolon or a quote was not closed. Prompt 3 is issued when you run an SQL `COPY` command and you are expected to type in the tuples on the terminal.

The value of the respective prompt variable is printed literally, except where a percent sign ("%") is encountered. Depending on the next character, certain other text is substituted instead. Defined substitutions are:

`%M`

The full host name (with domain name) of the database server, or `[local]` if the connection is over a Unix domain socket, or `[local:`*`/dir/name`*`]`, if the Unix domain socket is not at the compiled in default location.

`%m`

The host name of the database server, truncated after the first dot, or `[local]` if the connection is over a Unix domain socket.

`%>`

The port number at which the database server is listening.

`%n`

The user name you are connected as (not your local system user name).

`%/`

The name of the current database.

`%~`

Like `%/`, but the output is "~" (tilde) if the database is your default database.

`%#`

If the current user is a database superuser, then a "#", otherwise a ">".

`%R`

In prompt 1 normally "=", but "^" if in single-line mode, and "!" if the session is disconnected from the database (which can happen if `\connect` fails). In prompt 2 the sequence is replaced by "-", "*", a single quote, or a double quote, depending on whether psql expects more input because the query wasn't terminated yet, because you are inside a `/* ... */` comment, or because you are inside a quote. In prompt 3 the sequence doesn't resolve to anything.

`%`*`digits`*

If *`digits`* starts with `0x` the rest of the characters are interpreted as a hexadecimal digit and the character with the corresponding code is substituted. If the first digit is `0` the characters are interpreted as on octal number and the corresponding character is substituted. Otherwise a decimal number is assumed.

`%:`*`name`*`:`

The value of the psql, variable *`name`*. See the section "Variables" for details.

`` %`command` ``

The output of *`command`*, similar to ordinary "back-tick" substitution.

To insert a percent sign into your prompt, write `%%`. The default prompts are equivalent to `'%/%R%# '` for prompts 1 and 2, and `'>> '` for prompt 3.

Note

This feature was shamelessly plagiarized from tcsh.

Command-Line Editing

psql supports the Readline library for convenient line editing and retrieval. The command history is stored in a file named `.psql_history` in your home directory and is reloaded when psql starts up. Tab-completion is also supported, although the completion logic makes no claim to be an SQL parser. When available, psql is automatically built to use these features. If for some reason you do not like the tab completion, you can turn if off by putting this in a file named `.inputrc` in your home directory:

```
$if psql
set disable-completion on
$endif
```

(This is not a psql but a readline feature. Read its documentation for further details.)

Environment

`HOME`

Directory for initialization file (`.psqlrc`) and command history file (`.psql_history`).

`PAGER`

If the query results do not fit on the screen, they are piped through this command. Typical values are `more` or `less`. The default is platform-dependent. The use of the pager can be disabled by using the `\pset` command.

`PGDATABASE`

Default database to connect to

`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters

`PSQL_EDITOR`
`EDITOR`
`VISUAL`

Editor used by the `\e` command. The variables are examined in the order listed; the first that is set is used.

`SHELL`

Command executed by the `\!` command.

`TMPDIR`

Directory for storing temporary files. The default is `/tmp`.

Files

- Before starting up, psql attempts to read and execute commands from the file `$HOME/.psqlrc`. It could be used to set up the client or the server to taste (using the `\set` and `SET` commands).
- The command-line history is stored in the file `$HOME/.psql_history`.

Notes

- In an earlier life psql allowed the first argument of a single-letter backslash command to start directly after the command, without intervening whitespace. For compatibility this is still supported to some extent, but I am not going to explain the details here as this use is discouraged. If you get strange messages, keep this in mind. For example

```
testdb=> \foo
Field separator is "oo",
```

which is perhaps not what one would expect.

- psql only works smoothly with servers of the same version. That does not mean other combinations will fail outright, but subtle and not-so-subtle problems might come up. Backslash commands are particularly likely to fail if the server is of a different version.
- Pressing Control-C during a “copy in” (data sent to the server) doesn't show the most ideal of behaviors. If you get a message such as “COPY state must be terminated first”, simply reset the connection by entering `\c - -`.

Examples

Note

This section only shows a few examples specific to psql. If you want to learn SQL or get familiar with PostgreSQL, you might wish to read the Tutorial that is included in the distribution.

The first example shows how to spread a query over several lines of input. Notice the changing prompt:

```
testdb=> CREATE TABLE my_table (
testdb(>  first integer not null default 0,
testdb(>  second text
testdb-> );
CREATE
```

Now look at the table definition again:

```
testdb=> \d my_table
             Table "my_table"
 Attribute |  Type   |      Modifier
-----------+---------+--------------------
 first     | integer | not null default 0
 second    | text    |
```

At this point you decide to change the prompt to something more interesting:

```
testdb=> \set PROMPT1 '%n@%m %~%R%# '
peter@localhost testdb=>
```

Let's assume you have filled the table with data and want to take a look at it:

```
peter@localhost testdb=> SELECT * FROM my_table;
 first | second
-------+--------
     1 | one
     2 | two
     3 | three
     4 | four
(4 rows)
```

You can make this table look differently by using the `\pset` command:

```
peter@localhost testdb=> \pset border 2
Border style is 2.
peter@localhost testdb=> SELECT * FROM my_table;
+-------+--------+
| first | second |
+-------+--------+
|     1 | one    |
|     2 | two    |
|     3 | three  |
|     4 | four   |
+-------+--------+
(4 rows)

peter@localhost testdb=> \pset border 0
Border style is 0.
peter@localhost testdb=> SELECT * FROM my_table;
first second
----- ------
    1 one
    2 two
    3 three
    4 four
(4 rows)
```

```
peter@localhost testdb=> \pset border 1
Border style is 1.
peter@localhost testdb=> \pset format unaligned
Output format is unaligned.
peter@localhost testdb=> \pset fieldsep ","
Field separator is ",".
peter@localhost testdb=> \pset tuples_only
Showing only tuples.
peter@localhost testdb=> SELECT second, first FROM my_table;
one,1
two,2
three,3
four,4
```

Alternatively, use the short commands:

```
peter@localhost testdb=> \a \t \x
Output format is aligned.
Tuples only is off.
Expanded display is on.
peter@localhost testdb=> SELECT * FROM my_table;
-[ RECORD 1 ]-
first  | 1
second | one
-[ RECORD 2 ]-
first  | 2
second | two
-[ RECORD 3 ]-
first  | 3
second | three
-[ RECORD 4 ]-
first  | 4
second | four
```

Name

pgtclsh — PostgreSQL Tcl shell client

Synopsis

`pgtclsh` [*`filename`* [*`arguments`*...]]

Description

`pgtclsh` is a Tcl shell interface extended with PostgreSQL database access functions. (Essentially, it is `tclsh` with `libpgtcl` loaded.) Like with the regular Tcl shell, the first command line argument is a script file, any remaining arguments are passed to the script. If no script file is named, the shell is interactive.

A Tcl shell with Tk and PostgreSQL functions is available as pgtksh.

See Also

pgtksh, *PostgreSQL Programmer's Guide* (description of `libpgtcl`) , tclsh

Name

pgtksh — PostgreSQL Tcl/Tk shell client

Synopsis

`pgtksh` [*`filename`* [*`arguments`*...]]

Description

`pgtksh` is a Tcl/Tk shell interface extended with PostgreSQL database access functions. (Essentially, it is `wish` with `libpgtcl` loaded.) Like with `wish`, the regular Tcl/Tk shell, the first command line argument is a script file, any remaining arguments are passed to the script. Special options may be processed by the X Window System libraries instead. If no script file is named, the shell is interactive.

A plain Tcl shell with PostgreSQL functions is available as pgtclsh.

See Also

pgtclsh, *PostgreSQL Programmer's Guide* (description of `libpgtcl`) , tclsh , wish

Name

vacuumdb — garbage-collect and analyze a PostgreSQL database

Synopsis

`vacuumdb` [*connection-options*...] [[--full] | [-f]] [[--verbose] | [-v]] [[--analyze] | [-z]] [--table | -t '*table* [(*column* [,...])]'] [*dbname*]
`vacuumdb` [*connection-options*...] [[--all] | [-a]] [[--full] | [-f]] [[--verbose] | [-v]] [[--analyze] | [-z]]

Description

vacuumdb is a utility for cleaning a PostgreSQL database. vacuumdb will also generate internal statistics used by the PostgreSQL query optimizer.

vacuumdb is a shell script wrapper around the backend command VACUUM via the PostgreSQL interactive terminal psql. There is no effective difference between vacuuming databases via this or other methods. psql must be found by the script and a database server must be running at the targeted host. Also, any default settings and environment variables available to psql and the libpq front-end library do apply.

vacuumdb might need to connect several times to the PostgreSQL server, asking for a password each time. It is convenient to have a `$HOME/.pgpass` file in such cases.

Options

vacuumdb accepts the following command-line arguments:

`[-d] dbname`
`[--dbname] dbname`

Specifies the name of the database to be cleaned or analyzed. If this is not specified and `-a` (or `--all`) is not used, the database name is read from the environment variable `PGDATABASE`. If that is not set, the user name specified for the connection is used.

`-a`
`--all`

Vacuum all databases.

`-e`
`--echo`

Echo the commands that vacuumdb generates and sends to the server.

`-f`
`--full`

Perform “full” vacuuming.

`-q`
`--quiet`

Do not display a response.

`-t table [ (column [,...]) ]`
`--table table [ (column [,...]) ]`

Clean or analyze *table* only. Column names may be specified only in conjunction with the `--analyze` option.

Tip

If you specify columns to vacuum, you probably have to escape the parentheses from the shell.

`-v`
`--verbose`

Print detailed information during processing.

`-z`
`--analyze`

Calculate statistics for use by the optimizer.

vacuumdb also accepts the following command-line arguments for connection parameters:

`-h` *host*
`--host` *host*

Specifies the host name of the machine on which the server is running. If host begins with a slash, it is used as the directory for the Unix domain socket.

`-p` *port*
`--port` *port*

Specifies the Internet TCP/IP port or local Unix domain socket file extension on which the server is listening for connections.

`-U` *username*
`--username` *username*

User name to connect as

`-W`
`--password`

Force password prompt.

Diagnostics

`VACUUM`

Everything went well.

`vacuumdb: Vacuum failed.`

Something went wrong. vacuumdb is only a wrapper script. See VACUUM and psql for a detailed discussion of error messages and potential problems.

Environment

`PGDATABASE`
`PGHOST`
`PGPORT`
`PGUSER`

Default connection parameters.

Examples

To clean the database `test`:

```
$ vacuumdb test
```

To clean and analyze for the optimizer a database named `bigdb`:

```
$ vacuumdb --analyze bigdb
```

To clean a single table `foo` in a database named `xyzzy`, and analyze a single column `bar` of the table for the optimizer:

```
$ vacuumdb --analyze --verbose --table 'foo(bar)' xyzzy
```

See Also

VACUUM

PostgreSQL Server Applications

This part contains reference information for PostgreSQL server applications and support utilities. These commands can only be run usefully on the host where the database server resides. Other utility programs are listed in PostgreSQL Client Applications.

Table of Contents

initdb 585
initlocation 587
ipcclean 588
pg_ctl 589
pg_controldata 592
pg_resetxlog 593
postgres 594
postmaster 597

Name

initdb — create a new PostgreSQL database cluster

Synopsis

`initdb` [options...] [--pgdata] | [-D]*`directory`*

Description

`initdb` creates a new PostgreSQL database cluster (or database system). A database cluster is a collection of databases that are managed by a single server instance.

Creating a database system consists of creating the directories in which the database data will live, generating the shared catalog tables (tables that belong to the whole cluster rather than to any particular database), and creating the `template1` database. When you create a new database, everything in the `template1` database is copied. It contains catalog tables filled in for things like the built-in types.

`initdb` initializes the database cluster's default locale and character set encoding. Some locale categories are fixed for the lifetime of the cluster, so it is important to make the right choice when running `initdb`. Other locale categories can be changed later when the server is started. `initdb` will write those locale settings into the `postgresql.conf` configuration file so they are the default, but they can be changed by editing that file. To set the locale that `initdb` uses, see the description of the `--locale` option. The character set encoding can be set separately for each database as it is created. `initdb` determines the encoding for the `template1` database, which will serve as the default for all other databases. To alter the default encoding use the `--encoding` option.

`initdb` must be run as the user that will own the server process, because the server needs to have access to the files and directories that `initdb` creates. Since the server may not be run as root, you must not run `initdb` as root either. (It will in fact refuse to do so.)

Although `initdb` will attempt to create the specified data directory, often it won't have permission to do so, since the parent of the desired data directory is often a root-owned directory. To set up an arrangement like this, create an empty data directory as root, then use `chown` to hand over ownership of that directory to the database user account, then `su` to become the database user, and finally run `initdb` as the database user.

Options

`-D` *`directory`*
`--pgdata=`*`directory`*

This option specifies the directory where the database system should be stored. This is the only information required by `initdb`, but you can avoid writing it by setting the `PGDATA` environment variable, which can be convenient since the database server (`postmaster`) can find the database directory later by the same variable.

`-E` *`encoding`*
`--encoding=`*`encoding`*

Selects the encoding of the template database. This will also be the default encoding of any database you create later, unless you override it there. To use the encoding feature, you must have enabled it at build time, at which time you also select the default for this option.

`--locale=`*`locale`*

Sets the default locale for the database cluster. If this option is not specified, the locale is inherited from the environment that `initdb` runs in.

```
--lc-collate=locale
--lc-ctype=locale
--lc-messages=locale
--lc-monetary=locale
--lc-numeric=locale
--lc-time=locale
```

Like `--locale`, but only sets the locale in the specified category.

```
-U username
--username=username
```

Selects the user name of the database superuser. This defaults to the name of the effective user running `initdb`. It is really not important what the superuser's name is, but one might choose to keep the customary name postgres, even if the operating system user's name is different.

```
-W
--pwprompt
```

Makes `initdb` prompt for a password to give the database superuser. If you don't plan on using password authentication, this is not important. Otherwise you won't be able to use password authentication until you have a password set up.

Other, less commonly used, parameters are also available:

```
-d
--debug
```

Print debugging output from the bootstrap backend and a few other messages of lesser interest for the general public. The bootstrap backend is the program `initdb` uses to create the catalog tables. This option generates a tremendous amount of extremely boring output.

```
-L directory
```

Specifies where `initdb` should find its input files to initialize the database system. This is normally not necessary. You will be told if you need to specify their location explicitly.

```
-n
--noclean
```

By default, when `initdb` determines that an error prevented it from completely creating the database system, it removes any files it may have created before discovering that it can't finish the job. This option inhibits tidying-up and is thus useful for debugging.

Environment

`PGDATA`

Specifies the directory where the database system is to be stored; may be overridden using the `-D` option.

See Also

postgres, postmaster, *PostgreSQL Administrator's Guide*

Name

initlocation — create a secondary PostgreSQL database storage area

Synopsis

```
initlocation directory
```

Description

initlocation creates a new PostgreSQL secondary database storage area. See the discussion under CREATE DATABASE about how to manage and use secondary storage areas. If the argument does not contain a slash and is not valid as a path, it is assumed to be an environment variable, which is referenced. See the examples at the end.

In order to use this command you must be logged in (using `su`, for example) as the database superuser.

Examples

To create a database in an alternate location, using an environment variable:

```
$ export PGDATA2=/opt/postgres/data
```

Stop and start postmaster so it sees the `PGDATA2` environment variable. The system must be configured so the postmaster sees `PGDATA2` every time it starts. Finally:

```
$ initlocation PGDATA2
$ createdb -D PGDATA2 testdb
```

Alternatively, if you allow absolute paths you could write:

```
$ initlocation /opt/postgres/data
$ createdb -D /opt/postgres/data/testdb testdb
```

See Also

PostgreSQL Administrator's Guide

Name

ipcclean — remove shared memory and semaphores from an aborted PostgreSQL server

Synopsis

```
ipcclean
```

Description

`ipcclean` removes all shared memory segments and semaphore sets owned by the current user. It is intended to be used for cleaning up after a crashed PostgreSQL server (postmaster). Note that immediately restarting the server will also clean up shared memory and semaphores, so this command is of little real utility.

Only the database administrator should execute this program as it can cause bizarre behavior (i.e., crashes) if run during multiuser execution. If this command is executed while a postmaster is running, the shared memory and semaphores allocated by the postmaster will be deleted. This will result in a general failure of the backend servers started by that postmaster.

Notes

This script is a hack, but in the many years since it was written, no one has come up with an equally effective and portable solution. Since the postmaster can now clean up by itself, it is unlikely that `ipcclean` will be improved upon in the future.

The script makes assumption about the format of output of the ipcs utility which may not be true across different operating systems. Therefore, it may not work on your particular OS.

Name

pg_ctl — start, stop, or restart a PostgreSQL server

Synopsis

`pg_ctl` start [-w] [-s] [-D *`datadir`*] [-l *`filename`*] [-o *`options`*] [-p *`path`*]
`pg_ctl` stop [-W] [-s] [-D *`datadir`*] [-m [s[mart]] | [f[ast]] | [i[mmediate]]]
`pg_ctl` restart [-w] [-s] [-D *`datadir`*] [-m [s[mart]] | [f[ast]] | [i[mmediate]]] [-o *`options`*]
`pg_ctl` reload [-s] [-D *`datadir`*]
`pg_ctl` status [-D *`datadir`*]

Description

pg_ctl is a utility for starting, stopping, or restarting postmaster, the PostgreSQL backend server, or displaying the status of a running postmaster. Although the postmaster can be started manually, pg_ctl encapsulates tasks such as redirecting log output, properly detaching from the terminal and process group, and it provides convenient options for controlled shutdown.

In `start` mode, a new postmaster is launched. The server is started in the background, the standard input attached to `/dev/null`. The standard output and standard error are either appended to a log file, if the `-l` option is used, or are redirected to pg_ctl's standard output (not standard error). If no log file is chosen, the standard output of pg_ctl should be redirected to a file or piped to another process, for example a log rotating program, otherwise the postmaster will write its output the the controlling terminal (from the background) and will not leave the shell's process group.

In `stop` mode, the postmaster that is running in the specified data directory is shut down. Three different shutdown methods can be selected with the `-m` option: “Smart” mode waits for all the clients to disconnect. This is the default. “Fast” mode does not wait for clients to disconnect. All active transactions are rolled back and clients are forcibly disconnected, then the database is shut down. “Immediate” mode will abort all server processes without clean shutdown. This will lead to a recovery run on restart.

`restart` mode effectively executes a stop followed by a start. This allows the changing of postmaster command line options.

`reload` mode simply sends the postmaster a SIGHUP signal, causing it to reread its configuration files (`postgresql.conf`, `pg_hba.conf`, etc.). This allows changing of configuration-file options that do not require a complete restart to take effect.

`status` mode checks whether a postmaster is running and if so displays the PID and the command line options that were used to invoke it.

Options

-D *`datadir`*

Specifies the file system location of the database files. If this is omitted, the environment variable `PGDATA` is used.

-l *`filename`*

Append the server log output to *`filename`*. If the file does not exist, it is created. The umask is set to 077, so access to the log file from other users is disallowed by default.

-m *`mode`*

Specifies the shutdown mode. *`mode`* may be `smart`, `fast`, or `immediate`, or the first letter of one of these three.

-o *options*

Specifies options to be passed directly to postmaster.

The parameters are usually surrounded by single or double quotes to ensure that they are passed through as a group.

-p *path*

Specifies the location of the `postmaster` executable. By default the postmaster is taken from the same directory as `pg_ctl`, or failing that, the hard-wired installation directory. It is not necessary to use this option unless you are doing something unusual and get errors that the postmaster was not found.

-s

Only print errors, no informational messages.

-w

Wait for the start or shutdown to complete. Times out after 60 seconds. This is the default for shutdowns.

-W

Do not wait for start or shutdown to complete. This is the default for starts and restarts.

Environment

`PGDATA`

Default data direction location

For others, see postmaster.

Files

If the file `postmaster.opts.default` exists in the data directory, the contents of the file will be passed as options to the postmaster, unless overridden by the `-o` option.

Notes

Waiting for complete start is not a well-defined operation and may fail if access control is set up so that a local client cannot connect without manual interaction. It should be avoided.

Examples

Starting the postmaster

To start up a postmaster:

```
$ pg_ctl start
```

An example of starting the postmaster, blocking until the postmaster comes up is:

```
$ pg_ctl -w start
```

For a postmaster using port 5433, and running without `fsync`, use:

```
$ pg_ctl -o "-F -p 5433" start
```

Stopping the postmaster

```
$ pg_ctl stop
```

stops the postmaster. Using the `-m` switch allows one to control *how* the backend shuts down.

Restarting the postmaster

This is almost equivalent to stopping the postmaster and starting it again except that `pg_ctl` saves and reuses the command line options that were passed to the previously running instance. To restart the postmaster in the simplest form:

```
$ pg_ctl restart
```

To restart postmaster, waiting for it to shut down and to come up:

```
$ pg_ctl -w restart
```

To restart using port 5433 and disabling `fsync` after restarting:

```
$ pg_ctl -o "-F -p 5433" restart
```

Showing postmaster status

Here is a sample status output from pg_ctl:

```
$ pg_ctl status
pg_ctl: postmaster is running (pid: 13718)
Command line was:
/usr/local/pgsql/bin/postmaster '-D' '/usr/local/pgsql/data' '-p'
 '5433' '-B' '128'
```

This is the command line that would be invoked in restart mode.

See Also

postmaster, *PostgreSQL Administrator's Guide*

Name

pg_controldata — display server-wide control information

Synopsis

`pg_controldata` [*datadir*]

Description

`pg_controldata` returns information initialized during initdb, such as the catalog version and server locale. It also shows information about write-ahead logging and checkpoint processing. This information is server-wide, and not specific to any one database.

This utility may only be run by the user who installed the server because it requires read access to the `datadir`. You can specify the data directory on the command line, or use the environment variable `PGDATA`.

Environment

`PGDATA`

Default data directory location

Name

pg_resetxlog — reset write-ahead log and pg_control contents

Synopsis

`pg_resetxlog` [-f] [-n] [-o *oid*] [-x *xid*] [-l *fileid*,*seg*] *datadir*

Description

`pg_resetxlog` clears the write-ahead log and optionally resets some fields in the `pg_control` file. This function is sometimes needed if these files have become corrupted. It should be used only as a last resort, when the server will not start due to such corruption.

After running this command, it should be possible to start the server, but bear in mind that the database may contain inconsistent data due to partially-committed transactions. You should immediately dump your data, run initdb, and reload. After reload, check for inconsistencies and repair as needed.

This utility can only be run by the user who installed the server, because it requires read/write access to the `datadir`. For safety reasons, you must specify the data directory on the command line. `pg_resetxlog` does not use the environment variable `PGDATA`.

If `pg_resetxlog` complains that it cannot determine valid data for `pg_control`, you can force it to proceed anyway by specifying the `-f` (force) switch. In this case plausible values will be substituted for the missing data. Most of the fields can be expected to match, but manual assistance may be needed for the next OID, next transaction ID, WAL starting address, and database locale fields. The first three of these can be set using the switches discussed below. `pg_resetxlog`'s own environment is the source for its guess at the locale fields; take care that `LANG` and so forth match the environment that initdb was run in. If you are not able to determine correct values for all these fields, `-f` can still be used, but the recovered database must be treated with even more suspicion than usual --- an immediate dump and reload is imperative. *Do not* execute any data-modifying operations in the database before you dump, as any such action is likely to make the corruption worse.

The `-o`, `-x`, and `-l` switches allow the next OID, next transaction ID, and WAL starting address values to be set manually. These are only needed when `pg_resetxlog` is unable to determine appropriate values by reading `pg_control`. A safe value for the next transaction ID may be determined by looking for the largest file name in `$PGDATA/pg_clog`, adding one, and then multiplying by 1048576. Note that the file names are in hexadecimal. It is usually easiest to specify the switch value in hexadecimal too. For example, if `0011` is the largest entry in `pg_clog`, `-x 0x1200000` will work (five trailing zeroes provide the proper multiplier). The WAL starting address should be larger than any file number currently existing in `$PGDATA/pg_xlog`. These also are in hex, and have two parts. For example, if `000000FF0000003A` is the largest entry in `pg_xlog`, `-l 0xFF,0x3B` will work. There is no comparably easy way to determine a next OID that's beyond the largest one in the database, but fortunately it is not critical to get the next-OID setting right.

The `-n` (no operation) switch instructs `pg_resetxlog` to print the values reconstructed from `pg_control` and then exit without modifying anything. This is mainly a debugging tool, but may be useful as a sanity check before allowing `pg_resetxlog` to proceed for real.

Notes

This command must not be used when the postmaster is running. `pg_resetxlog` will refuse to start up if it finds a postmaster lock file in the `datadir`. If the postmaster crashed then a lock file may have been left behind; in that case you can remove the lock file to allow `pg_resetxlog` to run. But before you do so, make doubly certain that there is no postmaster nor any backend server process still alive.

Name

postgres — run a PostgreSQL server in single-user mode

Synopsis

`postgres` [-A [0] | [1]] [-B *nbuffers*] [-c *name*=*value*] [-d *debug-level*] [-D *datadir*] [-e] [-E] [-f [s] | [i] | [t] | [n] | [m] | [h]] [-F] [-i] [-N] [-o *filename*] [-O] [-P] [[-s] | [-t [pa] | [pl] | [ex]]] [-S *sort-mem*] [-W *seconds*] [--*name*=*value*] *database*
`postgres` [-A [0] | [1]] [-B *nbuffers*] [-c *name*=*value*] [-d *debug-level*] [-D *datadir*] [-e] [-f [s] | [i] | [t] | [n] | [m] | [h]] [-F] [-i] [-o *filename*] [-O] [-p *database*] [-P] [[-s] | [-t [pa] | [pl] | [ex]]] [-S *sort-mem*] [-v *protocol-version*] [-W *seconds*] [--*name*=*value*]

Description

The `postgres` executable is the actual PostgreSQL server process that processes queries. It is normally not called directly; instead a postmaster multiuser server is started.

The second form above is how postgres is invoked by the postmaster (only conceptually, since both `postmaster` and `postgres` are in fact the same program); it should not be invoked directly this way. The first form invokes the server directly in interactive single-user mode. The primary use for this mode is during bootstrapping by initdb. Sometimes it is used for debugging or disaster recovery.

When invoked in interactive mode from the shell, the user can enter queries and the results will be printed to the screen, but in a form that is more useful for developers than end users. But note that running a single-user backend is not truly suitable for debugging the server since no realistic interprocess communication and locking will happen.

When running a stand-alone backend, the session user will be set to the user with ID 1. This user does not actually have to exist, so a stand-alone backend can be used to manually recover from certain kinds of accidental damage to the system catalogs. Implicit superuser powers are granted to the user with ID 1 in stand-alone mode.

Options

When postgres is started by a postmaster then it inherits all options set by the latter. Additionally, postgres-specific options can be passed from the postmaster with the `-o` switch.

You can avoid having to type these options by setting up a configuration file. See the *Administrator's Guide* for details. Some (safe) options can also be set from the connecting client in an application-dependent way. For example, if the environment variable `PGOPTIONS` is set, then libpq-based clients will pass that string to the server, which will interpret it as postgres command-line options.

General Purpose

The options `-A`, `-B`, `-c`, `-d`, `-D`, `-F`, and `--name` have the same meanings as the postmaster except that `-d 0` prevents the debugging level of the postmaster from being propagated to the backend.

`-e`

Sets the default date style to “European”, which means that the “day before month” (rather than month before day) rule is used to interpret ambiguous date input, and that the day is printed before the month in certain date output formats. See the *PostgreSQL User's Guide* for more information.

`-o` *filename*

Sends all debugging and error output to *filename*. If the backend is running under the postmaster, this option is ignored, and the stderr inherited from the postmaster is used.

`-P`

Ignore system indexes while scanning/updating system tuples. The `REINDEX` command for system tables/indexes requires this option to be used.

`-s`

Print time information and other statistics at the end of each query. This is useful for benchmarking or for use in tuning the number of buffers.

`-S` *`sort-mem`*

Specifies the amount of memory to be used by internal sorts and hashes before resorting to temporary disk files. The value is specified in kilobytes, and defaults to 512 kilobytes. Note that for a complex query, several sorts and/or hashes might be running in parallel, and each one will be allowed to use as much as *`sort-mem`* kilobytes before it starts to put data into temporary files.

Options for stand-alone mode

`database`

Specifies the name of the database to be accessed. If it is omitted it defaults to the user name.

`-E`

Echo all queries.

`-N`

Disables use of newline as a query delimiter.

Semi-internal Options

There are several other options that may be specified, used mainly for debugging purposes. These are listed here only for the use by PostgreSQL system developers. *Use of any of these options is highly discouraged.* Furthermore, any of these options may disappear or change in a future release without notice.

`-f { s | i | m | n | h }`

Forbids the use of particular scan and join methods: `s` and `i` disable sequential and index scans respectively, while `n`, `m`, and `h` disable nested-loop, merge and hash joins respectively.

Note

Neither sequential scans nor nested-loop joins can be disabled completely; the `-fs` and `-fn` options simply discourage the optimizer from using those plan types if it has any other alternative.

`-i`

Prevents query execution, but shows the plan tree.

`-O`

Allows the structure of system tables to be modified. This is used by initdb.

`-p` *`database`*

Indicates that this server has been started by a postmaster and makes different assumptions about buffer pool management, file descriptors, etc.

`-t pa[rser] | pl[anner] | e[xecutor]`

Print timing statistics for each query relating to each of the major system modules. This option cannot be used together with the `-s` option.

`-v` *`protocol`*

Specifies the version number of the frontend/backend protocol to be used for this particular session.

`-W` *`seconds`*

As soon as this option is encountered, the process sleeps for the specified amount of seconds. This gives developers time to attach a debugger to the backend process.

Environment

`PGDATA`

Default data direction location

For others, which have little influence during single-user mode, see postmaster.

Notes

To stop a running query use the `SIGINT` signal. To tell postgres to reread the config file, use a `SIGHUP` signal. The postmaster uses `SIGTERM` to tell a postgres process to quit normally and `SIGQUIT` to terminate without the normal cleanup. These *should not* be used by users.

Usage

Start a stand-alone backend with a command like

`postgres -D $PGDATA` ***`other-options`*** **`my_database`**

Provide the correct path to the database area with `-D`, or make sure that the environment variable `PGDATA` is set. Also specify the name of the particular database you want to work in.

Normally, the stand-alone backend treats newline as the command entry terminator; there is no intelligence about semicolons, as there is in psql. To continue a command across multiple lines, you must type backslash just before each newline except the last one.

But if you use the `-N` command line switch, then newline does not terminate command entry. The backend will read the standard input until the end-of-file (EOF) marker, then process the input as a single query string. Backslash-newline is not treated specially in this case.

To quit the session, type EOF (**Control**+**D**, usually). If you've used `-N`, two consecutive EOFs are needed to exit.

Note that the stand-alone backend does not provide sophisticated line-editing features (no command history, for example).

See Also

initdb, ipcclean, postmaster

Name

postmaster — PostgreSQL multiuser database server

Synopsis

`postmaster` [-A [0] | [1]] [-B *nbuffers*] [-c *name*=*value*] [-d *debug-level*] [-D *datadir*] [-F] [-h *hostname*] [-i] [-k *directory*] [-l] [-N *max-connections*] [-o *extra-options*] [-p *port*] [-S] [--*name*=*value*] [[-n] | [-s]]

Description

postmaster is the PostgreSQL multiuser database server. In order for a client application to access a database it connects (over a network or locally) to a running postmaster. The postmaster then starts a separate server process ("postgres") to handle the connection. The postmaster also manages the communication among server processes.

By default the postmaster starts in the foreground and prints log messages to the standard output. In practical applications the postmaster should be started as a background process, perhaps at boot time.

One postmaster always manages the data from exactly one database cluster. A database cluster is a collection of databases that is stored at a common file system location. When the postmaster starts it needs to know the location of the database cluster files ("data area"). This is done with the `-D` invocation option or the `PGDATA` environment variable; there is no default. More than one postmaster process can run on a system at one time, as long as they use different data areas and different communication ports (see below). A data area is created with initdb.

Options

postmaster accepts the following command line arguments. For a detailed discussion of the options consult the *Administrator's Guide*. You can also save typing most of these options by setting up a configuration file.

-A 0|1

Enables run-time assert checks, which is a debugging aid to detect programming mistakes. This is only available if it was enabled during compilation. If so, the default is on.

-B *nbuffers*

Sets the number of shared buffers for use by the server processes. This value defaults to 64 buffers, where each buffer is 8 kB.

-c *name*=*value*

Sets a named run-time parameter. Consult the *Administrator's Guide* for a list and descriptions. Most of the other command line options are in fact short forms of such a parameter assignment. `-c` can appear multiple times to set multiple parameters.

-d *debug-level*

Sets the debug level. The higher this value is set, the more debugging output is written to the server log. Values are from 1 to 5.

-D *datadir*

Specifies the file system location of the data directory. See discussion above.

-F

Disables `fsync` calls for performance improvement, at the risk of data corruption in event of a system crash. This parameter corresponds to setting `fsync=false` in `postgresql.conf`. Read the detailed documentation before using this!

`--fsync=true` has the opposite effect of this option.

-h *hostname*

Specifies the TCP/IP host name or address on which the postmaster is to listen for connections from client applications. Defaults to listening on all configured addresses (including localhost).

-i

Allows clients to connect via TCP/IP (Internet domain) connections. Without this option, only local Unix domain socket connections are accepted. This option corresponds to setting `tcpip_socket=true` in `postgresql.conf`.

`--tcpip_socket=false` has the opposite effect of this option.

-k *directory*

Specifies the directory of the Unix-domain socket on which the postmaster is to listen for connections from client applications. The default is normally `/tmp`, but can be changed at build time.

-l

Enables secure connections using SSL. The `-i` option is also required. You must have compiled with SSL enabled to use this option.

-N *max-connections*

Sets the maximum number of client connections that this postmaster will accept. By default, this value is 32, but it can be set as high as your system will support. (Note that `-B` is required to be at least twice `-N`. See the *Administrator's Guide* for a discussion of system resource requirements for large numbers of client connections.)

-o *extra-options*

The command line-style options specified in *extra-options* are passed to all backend server processes started by this postmaster. See postgres for possibilities. If the option string contains any spaces, the entire string must be quoted.

-p *port*

Specifies the TCP/IP port or local Unix domain socket file extension on which the postmaster is to listen for connections from client applications. Defaults to the value of the `PGPORT` environment variable, or if `PGPORT` is not set, then defaults to the value established during compilation (normally 5432). If you specify a port other than the default port, then all client applications must specify the same port using either command-line options or `PGPORT`.

-S

Specifies that the postmaster process should start up in silent mode. That is, it will disassociate from the user's (controlling) terminal, start its own process group, and redirect its standard output and standard error to `/dev/null`.

Using this switch discards all logging output, which is probably not what you want, since it makes it very difficult to troubleshoot problems. See below for a better way to start the postmaster in the background.

`--silent_mode=false` has the opposite effect of this option.

--name=value

Sets a named run-time parameter; a shorter form of `-c`.

Two additional command line options are available for debugging problems that cause a backend to die abnormally. These options control the behavior of the postmaster in this situation, and *neither option is intended for use in ordinary operation*.

The ordinary strategy for this situation is to notify all other backends that they must terminate and then reinitialize the shared memory and semaphores. This is because an errant backend could have corrupted some shared state before terminating.

These special-case options are:

-n

postmaster will not reinitialize shared data structures. A knowledgeable system programmer can then use a debugger to examine shared memory and semaphore state.

-s

postmaster will stop all other backend processes by sending the signal `SIGSTOP`, but will not cause them to terminate. This permits system programmers to collect core dumps from all backend processes by hand.

Environment

`PGCLIENTENCODING`

Default character encoding used by clients. (The clients may override this individually.) This value can also be set in the configuration file.

`PGDATA`

Default data direction location

`PGDATASTYLE`

Default value of the `datestyle` run-time parameter. (The use of this environment variable is deprecated.)

`PGPORT`

Default port (preferably set in the configuration file)

`TZ`

Server time zone

others

Other environment variables may be used to designate alternative data storage locations. See the *Administrator's Guide* for more information.

Diagnostics

`semget: No space left on device`

If you see this message, you should run the ipcclean command. After doing so, try starting postmaster again. If this still doesn't work, you probably need to configure your kernel for shared

memory and semaphores as described in the installation notes. If you run multiple instances of postmaster on a single host, or have a kernel with particularly small shared memory and/or semaphore limits, you may have to reconfigure your kernel to increase its shared memory or semaphore parameters.

Tip

You may be able to postpone reconfiguring your kernel by decreasing `-B` to reduce the shared memory consumption of PostgreSQL, and/or by reducing `-N` to reduce the semaphore consumption.

`StreamServerPort: cannot bind to port`

If you see this message, you should make certain that there is no other postmaster process already running on the same port number. The easiest way to determine this is by using the command

```
$ ps ax | grep postmaster
```

or

```
$ ps -e | grep postmaster
```

depending on your system.

If you are sure that no other postmaster processes are running and you still get this error, try specifying a different port using the `-p` option. You may also get this error if you terminate the postmaster and immediately restart it using the same port; in this case, you must simply wait a few seconds until the operating system closes the port before trying again. Finally, you may get this error if you specify a port number that your operating system considers to be reserved. For example, many versions of Unix consider port numbers under 1024 to be *trusted* and only permit the Unix superuser to access them.

Notes

If at all possible, *do not* use `SIGKILL` to kill the postmaster. This will prevent postmaster from freeing the system resources (e.g., shared memory and semaphores) that it holds before terminating.

To terminate the postmaster normally, the signals `SIGTERM`, `SIGINT`, or `SIGQUIT` can be used. The first will wait for all clients to terminate before quitting, the second will forcefully disconnect all clients, and the third will quit immediately without proper shutdown, resulting in a recovery run during restart.

The utility command pg_ctl can be used to start and shut down the postmaster safely and comfortably.

The `--` options will not work on FreeBSD or OpenBSD. Use `-c` instead. This is a bug in the affected operating systems; a future release of PostgreSQL will provide a workaround if this is not fixed.

Examples

To start postmaster in the background using default values, type:

```
$ nohup postmaster >logfile 2>&1 </dev/null &
```

To start postmaster with a specific port:

```
$ postmaster -p 1234
```

This command will start up postmaster communicating through the port 1234. In order to connect to this postmaster using psql, you would need to run it as

```
$ psql -p 1234
```

or set the environment variable `PGPORT`:

```
$ export PGPORT=1234
$ psql
```

Named run-time parameters can be set in either of these styles:

```
$ postmaster -c sort_mem=1234
$ postmaster --sort-mem=1234
```

Either form overrides whatever setting might exist for `sort_mem` in `postgresql.conf`. Notice that underscores in parameter names can be written as either underscore or dash on the command line.

Tip

Except for short-term experiments, it's probably better practice to edit the setting in `postgresql.conf` than to rely on a command-line switch to set a parameter.

See Also

initdb, pg_ctl

PostgreSQL 7.3.21 Developer's Guide

The PostgreSQL Global Development Group

PostgreSQL 7.3.21 Developer's Guide

The PostgreSQL Global Development Group
Copyright © 1996-2002 The PostgreSQL Global Development Group

Abstract

This document contains assorted information that can be of use to PostgreSQL developers.

Legal Notice

PostgreSQL is Copyright © 1996-2002 by the PostgreSQL Global Development Group and is distributed under the terms of the license of the University of California below.

Postgres95 is Copyright © 1994-5 by the Regents of the University of California.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose, without fee, and without a written agreement is hereby granted, provided that the above copyright notice and this paragraph and the following two paragraphs appear in all copies.

IN NO EVENT SHALL THE UNIVERSITY OF CALIFORNIA BE LIABLE TO ANY PARTY FOR DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING LOST PROFITS, ARISING OUT OF THE USE OF THIS SOFTWARE AND ITS DOCUMENTATION, EVEN IF THE UNIVERSITY OF CALIFORNIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

THE UNIVERSITY OF CALIFORNIA SPECIFICALLY DISCLAIMS ANY WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE SOFTWARE PROVIDED HEREUNDER IS ON AN “AS-IS” BASIS, AND THE UNIVERSITY OF CALIFORNIA HAS NO OBLIGATIONS TO PROVIDE MAINTENANCE, SUPPORT, UPDATES, ENHANCEMENTS, OR MODIFICATIONS.

Table of Contents

1. PostgreSQL Source Code 1
    1.1. Formatting 1
2. Overview of PostgreSQL Internals 2
    2.1. The Path of a Query 2
    2.2. How Connections are Established 2
    2.3. The Parser Stage 3
        2.3.1. Parser 3
        2.3.2. Transformation Process 4
    2.4. The PostgreSQL Rule System 4
        2.4.1. The Rewrite System 5
    2.5. Planner/Optimizer 6
        2.5.1. Generating Possible Plans 6
        2.5.2. Data Structure of the Plan 6
    2.6. Executor 7
3. System Catalogs 8
    3.1. Overview 8
    3.2. pg_aggregate 9
    3.3. pg_am 9
    3.4. pg_amop 11
    3.5. pg_amproc 11
    3.6. pg_attrdef 11
    3.7. pg_attribute 12
    3.8. pg_cast 14
    3.9. pg_class 15
    3.10. pg_constraint 17
    3.11. pg_conversion 18
    3.12. pg_database 19
    3.13. pg_depend 20
    3.14. pg_description 21
    3.15. pg_group 22
    3.16. pg_index 22
    3.17. pg_inherits 23
    3.18. pg_language 23
    3.19. pg_largeobject 24
    3.20. pg_listener 25
    3.21. pg_namespace 25
    3.22. pg_opclass 26
    3.23. pg_operator 26
    3.24. pg_proc 27
    3.25. pg_rewrite 29
    3.26. pg_shadow 30
    3.27. pg_statistic 30
    3.28. pg_trigger 32
    3.29. pg_type 33
4. Frontend/Backend Protocol 39
    4.1. Overview 39
    4.2. Protocol 39
        4.2.1. Start-up 39
        4.2.2. Query 41
        4.2.3. Function Call 42
        4.2.4. Notification Responses 43
        4.2.5. Cancelling Requests in Progress 43
        4.2.6. Termination 44
        4.2.7. SSL Session Encryption 44
    4.3. Message Data Types 44

4.4. Message Formats ... 45
5. gcc Default Optimizations ... 52
6. BKI Backend Interface ... 53
6.1. BKI File Format ... 53
6.2. BKI Commands ... 53
6.3. Example ... 54
7. Page Files ... 55
8. Genetic Query Optimization ... 58
8.1. Query Handling as a Complex Optimization Problem ... 58
8.2. Genetic Algorithms ... 58
8.3. Genetic Query Optimization (GEQO) in PostgreSQL ... 59
8.3.1. Future Implementation Tasks for PostgreSQL GEQO ... 60
8.4. Further Readings ... 60
9. GiST Indexes ... 61
10. Native Language Support ... 63
10.1. For the Translator ... 63
10.1.1. Requirements ... 63
10.1.2. Concepts ... 63
10.1.3. Creating and maintaining message catalogs ... 64
10.1.4. Editing the PO files ... 65
10.2. For the Programmer ... 65
A. The CVS Repository ... 68
A.1. Getting The Source Via Anonymous CVS ... 68
A.2. CVS Tree Organization ... 69
A.3. Getting The Source Via CVSup ... 70
A.3.1. Preparing A CVSup Client System ... 70
A.3.2. Running a CVSup Client ... 71
A.3.3. Installing CVSup ... 72
A.3.4. Installation from Sources ... 73
B. Documentation ... 75
B.1. DocBook ... 75
B.2. Tool Sets ... 75
B.2.1. Linux RPM Installation ... 76
B.2.2. FreeBSD Installation ... 76
B.2.3. Debian Packages ... 77
B.2.4. Manual Installation from Source ... 77
B.3. Building The Documentation ... 79
B.3.1. HTML ... 80
B.3.2. Manpages ... 80
B.3.3. Hardcopy Generation ... 80
B.3.4. Plain Text Files ... 82
B.4. Documentation Authoring ... 82
B.4.1. Emacs/PSGML ... 82
B.4.2. Other Emacs modes ... 84
B.5. Style Guide ... 84
B.5.1. Reference Pages ... 84

List of Figures

8.1. Structured Diagram of a Genetic Algorithm 59

List of Tables

3.1. System Catalogs 8
3.2. pg_aggregate Columns 9
3.3. pg_am Columns 9
3.4. pg_amop Columns 11
3.5. pg_amproc Columns 11
3.6. pg_attrdef Columns 11
3.7. pg_attribute Columns 12
3.8. pg_cast Columns 14
3.9. pg_class Columns 15
3.10. pg_constraint Columns 17
3.11. pg_conversion Columns 18
3.12. pg_database Columns 19
3.13. pg_depend Columns 20
3.14. pg_description Columns 21
3.15. pg_group Columns 22
3.16. pg_index Columns 22
3.17. pg_inherits Columns 23
3.18. pg_language Columns 23
3.19. pg_largeobject Columns 24
3.20. pg_listener Columns 25
3.21. pg_namespace Columns 25
3.22. pg_opclass Columns 26
3.23. pg_operator Columns 26
3.24. pg_proc Columns 28
3.25. pg_rewrite Columns 29
3.26. pg_shadow Columns 30
3.27. pg_statistic Columns 31
3.28. pg_trigger Columns 32
3.29. pg_type Columns 33
7.1. Page Layout 55
7.2. PageHeaderData Layout 55
7.3. HeapTupleHeaderData Layout 56
B.1. Indent Formatting for Table of Contents 81

List of Examples

2.1. A Simple Select 3

Chapter 1. PostgreSQL Source Code

1.1. Formatting

Source code formatting uses a 4 column tab spacing, currently with tabs preserved (i.e. tabs are not expanded to spaces).

For Emacs, add the following (or something similar) to your `~/.emacs` initialization file:

```
;; check for files with a path containing "postgres" or "pgsql"
(setq auto-mode-alist
  (cons '("\\(postgres\\|pgsql\\).*\\.[ch]\\'" . pgsql-c-mode)
        auto-mode-alist))
(setq auto-mode-alist
  (cons '("\\(postgres\\|pgsql\\).*\\.cc\\'" . pgsql-c-mode)
        auto-mode-alist))

(defun pgsql-c-mode ()
  ;; sets up formatting for PostgreSQL C code
  (interactive)
  (c-mode)
  (setq-default tab-width 4)
  (c-set-style "bsd")             ; set c-basic-offset to 4, plus
 other stuff
  (c-set-offset 'case-label '+)   ; tweak case indent to match PG
 custom
  (setq indent-tabs-mode t))      ; make sure we keep tabs when
 indenting
```

For vi, your `~/.vimrc` or equivalent file should contain the following:

```
set tabstop=4
```

or equivalently from within vi, try

```
:set ts=4
```

The text browsing tools more and less can be invoked as

```
more -x4
less -x4
```

Chapter 2. Overview of PostgreSQL Internals

Author

This chapter originally appeared as a part of [sim98], Stefan Simkovics' Master's Thesis prepared at Vienna University of Technology under the direction of O.Univ.Prof.Dr. Georg Gottlob and Univ.Ass. Mag. Katrin Seyr.

This chapter gives an overview of the internal structure of the backend of PostgreSQL. After having read the following sections you should have an idea of how a query is processed. Don't expect a detailed description here (I think such a description dealing with all data structures and functions used within PostgreSQL would exceed 1000 pages!). This chapter is intended to help understanding the general control and data flow within the backend from receiving a query to sending the results.

2.1. The Path of a Query

Here we give a short overview of the stages a query has to pass in order to obtain a result.

1. A connection from an application program to the PostgreSQL server has to be established. The application program transmits a query to the server and receives the results sent back by the server.

2. The *parser stage* checks the query transmitted by the application program (client) for correct syntax and creates a *query tree*.

3. The *rewrite system* takes the query tree created by the parser stage and looks for any *rules* (stored in the *system catalogs*) to apply to the *querytree* and performs the transformations given in the *rule bodies*. One application of the rewrite system is given in the realization of *views*.

   Whenever a query against a view (i.e. a *virtual table*) is made, the rewrite system rewrites the user's query to a query that accesses the *base tables* given in the *view definition* instead.

4. The *planner/optimizer* takes the (rewritten) querytree and creates a *queryplan* that will be the input to the *executor*.

   It does so by first creating all possible *paths* leading to the same result. For example if there is an index on a relation to be scanned, there are two paths for the scan. One possibility is a simple sequential scan and the other possibility is to use the index. Next the cost for the execution of each plan is estimated and the cheapest plan is chosen and handed back.

5. The executor recursively steps through the *plan tree* and retrieves tuples in the way represented by the plan. The executor makes use of the *storage system* while scanning relations, performs *sorts* and *joins*, evaluates *qualifications* and finally hands back the tuples derived.

In the following sections we will cover every of the above listed items in more detail to give a better understanding on PostgreSQL's internal control and data structures.

2.2. How Connections are Established

PostgreSQL is implemented using a simple "process per-user" client/server model. In this model there is one *client process* connected to exactly one *server process*. As we don't know *per se* how many connections will be made, we have to use a *master process* that spawns a new server process every time a connection is requested. This master process is called `postmaster` and listens at a specified TCP/IP port for incoming connections. Whenever a request for a connection is detected the `postmaster` process spawns a new server process called `postgres`. The server tasks (`postgres` processes) communicate with each other using *semaphores* and *shared memory* to ensure data integrity

throughout concurrent data access. Figure \ref{connection} illustrates the interaction of the master process `postmaster` the server process `postgres` and a client application.

The client process can either be the psql frontend (for interactive SQL queries) or any user application implemented using the `libpg` library. Note that applications implemented using ecpg (the PostgreSQL embedded SQL preprocessor for C) also use this library.

Once a connection is established the client process can send a query to the *backend* (server). The query is transmitted using plain text, i.e. there is no parsing done in the *frontend* (client). The server parses the query, creates an *execution plan*, executes the plan and returns the retrieved tuples to the client by transmitting them over the established connection.

2.3. The Parser Stage

The *parser stage* consists of two parts:

- The *parser* defined in `gram.y` and `scan.l` is built using the Unix tools yacc and lex.
- The *transformation process* does modifications and augmentations to the data structures returned by the parser.

2.3.1. Parser

The parser has to check the query string (which arrives as plain ASCII text) for valid syntax. If the syntax is correct a *parse tree* is built up and handed back otherwise an error is returned. For the implementation the well known Unix tools lex and yacc are used.

The *lexer* is defined in the file `scan.l` and is responsible for recognizing *identifiers*, the *SQL keywords* etc. For every keyword or identifier that is found, a *token* is generated and handed to the parser.

The parser is defined in the file `gram.y` and consists of a set of *grammar rules* and *actions* that are executed whenever a rule is fired. The code of the actions (which is actually C-code) is used to build up the parse tree.

The file `scan.l` is transformed to the C-source file `scan.c` using the program lex and `gram.y` is transformed to `gram.c` using yacc. After these transformations have taken place a normal C-compiler can be used to create the parser. Never make any changes to the generated C-files as they will be overwritten the next time lex or yacc is called.

Note

The mentioned transformations and compilations are normally done automatically using the *makefiles* shipped with the PostgreSQL source distribution.

A detailed description of yacc or the grammar rules given in `gram.y` would be beyond the scope of this paper. There are many books and documents dealing with lex and yacc. You should be familiar with yacc before you start to study the grammar given in `gram.y` otherwise you won't understand what happens there.

For a better understanding of the data structures used in PostgreSQL for the processing of a query we use an example to illustrate the changes made to these data structures in every stage. This example contains the following simple query that will be used in various descriptions and figures throughout the following sections. The query assumes that the tables given in *The Supplier Database* have already been defined.

Example 2.1. A Simple Select

```
select s.sname, se.pno
```

```
from supplier s, sells se
where s.sno > 2 and s.sno = se.sno;
```

Figure \ref{parsetree} shows the *parse tree* built by the grammar rules and actions given in `gram.y` for the query given in Example 2.1, “A Simple Select” (without the *operator tree* for the *where clause* which is shown in figure \ref{where_clause} because there was not enough space to show both data structures in one figure).

The top node of the tree is a `SelectStmt` node. For every entry appearing in the *from clause* of the SQL query a `RangeVar` node is created holding the name of the *alias* and a pointer to a `RelExpr` node holding the name of the *relation*. All `RangeVar` nodes are collected in a list which is attached to the field `fromClause` of the `SelectStmt` node.

For every entry appearing in the *select list* of the SQL query a `ResTarget` node is created holding a pointer to an `Attr` node. The `Attr` node holds the *relation name* of the entry and a pointer to a `Value` node holding the name of the *attribute*. All `ResTarget` nodes are collected to a list which is connected to the field `targetList` of the `SelectStmt` node.

Figure \ref{where_clause} shows the operator tree built for the where clause of the SQL query given in Example 2.1, “A Simple Select” which is attached to the field `qual` of the `SelectStmt` node. The top node of the operator tree is an `A_Expr` node representing an `AND` operation. This node has two successors called `lexpr` and `rexpr` pointing to two *subtrees*. The subtree attached to `lexpr` represents the qualification `s.sno > 2` and the one attached to `rexpr` represents `s.sno = se.sno`. For every attribute an `Attr` node is created holding the name of the relation and a pointer to a `Value` node holding the name of the attribute. For the constant term appearing in the query a `Const` node is created holding the value.

2.3.2. Transformation Process

The *transformation process* takes the tree handed back by the parser as input and steps recursively through it. If a `SelectStmt` node is found, it is transformed to a `Query` node that will be the top most node of the new data structure. Figure \ref{transformed} shows the transformed data structure (the part for the transformed *where clause* is given in figure \ref{transformed_where} because there was not enough space to show all parts in one figure).

Now a check is made, if the *relation names* in the *FROM clause* are known to the system. For every relation name that is present in the *system catalogs* a RTE node is created containing the relation name, the *alias name* and the *relation id*. From now on the relation ids are used to refer to the *relations* given in the query. All RTE nodes are collected in the *range table entry list* that is connected to the field `rtable` of the `Query` node. If a name of a relation that is not known to the system is detected in the query an error will be returned and the query processing will be aborted.

Next it is checked if the *attribute names* used are contained in the relations given in the query. For every attribute} that is found a TLE node is created holding a pointer to a `Resdom` node (which holds the name of the column) and a pointer to a `VAR` node. There are two important numbers in the `VAR` node. The field `varno` gives the position of the relation containing the current attribute} in the range table entry list created above. The field `varattno` gives the position of the attribute within the relation. If the name of an attribute cannot be found an error will be returned and the query processing will be aborted.

2.4. The PostgreSQL Rule System

PostgreSQL supports a powerful *rule system* for the specification of *views* and ambiguous *view updates*. Originally the PostgreSQL rule system consisted of two implementations:

- The first one worked using *tuple level* processing and was implemented deep in the *executor*. The rule system was called whenever an individual tuple had been accessed. This implementation was

removed in 1995 when the last official release of the PostgreSQL project was transformed into Postgres95.

- The second implementation of the rule system is a technique called *query rewriting*. The *rewrite system*} is a module that exists between the *parser stage* and the *planner/optimizer*. This technique is still implemented.

For information on the syntax and creation of rules in the PostgreSQL system refer to *The PostgreSQL User's Guide*.

2.4.1. The Rewrite System

The *query rewrite system* is a module between the parser stage and the planner/optimizer. It processes the tree handed back by the parser stage (which represents a user query) and if there is a rule present that has to be applied to the query it rewrites the tree to an alternate form.

2.4.1.1. Techniques To Implement Views

Now we will sketch the algorithm of the query rewrite system. For better illustration we show how to implement views using rules as an example.

Let the following rule be given:

```
create rule view_rule
as on select
to test_view
do instead
   select s.sname, p.pname
   from supplier s, sells se, part p
   where s.sno = se.sno and
         p.pno = se.pno;
```

The given rule will be *fired* whenever a select against the relation `test_view` is detected. Instead of selecting the tuples from `test_view` the select statement given in the *action part* of the rule is executed.

Let the following user-query against `test_view` be given:

```
select sname
from test_view
where sname <> 'Smith';
```

Here is a list of the steps performed by the query rewrite system whenever a user-query against `test_view` appears. (The following listing is a very informal description of the algorithm just intended for basic understanding. For a detailed description refer to [ston89]).

`test_view` Rewrite

1. Take the query given in the action part of the rule.
2. Adapt the targetlist to meet the number and order of attributes given in the user-query.
3. Add the qualification given in the where clause of the user-query to the qualification of the query given in the action part of the rule.

Given the rule definition above, the user-query will be rewritten to the following form (Note that the rewriting is done on the internal representation of the user-query handed back by the parser stage but the derived new data structure will represent the following query):

```
select s.sname
from supplier s, sells se, part p
where s.sno = se.sno and
      p.pno = se.pno and
      s.sname <> 'Smith';
```

2.5. Planner/Optimizer

The task of the *planner/optimizer* is to create an optimal execution plan. It first combines all possible ways of *scanning* and *joining* the relations that appear in a query. All the created paths lead to the same result and it's the task of the optimizer to estimate the cost of executing each path and find out which one is the cheapest.

2.5.1. Generating Possible Plans

The planner/optimizer decides which plans should be generated based upon the types of indexes defined on the relations appearing in a query. There is always the possibility of performing a sequential scan on a relation, so a plan using only sequential scans is always created. Assume an index is defined on a relation (for example a B-tree index) and a query contains the restriction `relation.attribute OPR constant`. If `relation.attribute` happens to match the key of the B-tree index and `OPR` is anything but '<>' another plan is created using the B-tree index to scan the relation. If there are further indexes present and the restrictions in the query happen to match a key of an index further plans will be considered.

After all feasible plans have been found for scanning single relations, plans for joining relations are created. The planner/optimizer considers only joins between every two relations for which there exists a corresponding join clause (i.e. for which a restriction like `where rel1.attr1=rel2.attr2` exists) in the where qualification. All possible plans are generated for every join pair considered by the planner/optimizer. The three possible join strategies are:

- *nested iteration join*: The right relation is scanned once for every tuple found in the left relation. This strategy is easy to implement but can be very time consuming.

- *merge sort join*: Each relation is sorted on the join attributes before the join starts. Then the two relations are merged together taking into account that both relations are ordered on the join attributes. This kind of join is more attractive because every relation has to be scanned only once.

- *hash join*: the right relation is first hashed on its join attributes. Next the left relation is scanned and the appropriate values of every tuple found are used as hash keys to locate the tuples in the right relation.

2.5.2. Data Structure of the Plan

Here we will give a little description of the nodes appearing in the plan. Figure \ref{plan} shows the plan produced for the query in example \ref{simple_select}.

The top node of the plan is a `MergeJoin` node that has two successors, one attached to the field `lefttree` and the second attached to the field `righttree`. Each of the subnodes represents one relation of the join. As mentioned above a merge sort join requires each relation to be sorted. That's why we find a `Sort` node in each subplan. The additional qualification given in the query (`s.sno > 2`) is pushed down as far as possible and is attached to the `qpqual` field of the leaf `SeqScan` node of the corresponding subplan.

The list attached to the field `mergeclauses` of the `MergeJoin` node contains information about the join attributes. The values `65000` and `65001` for the `varno` fields in the `VAR` nodes appearing in the `mergeclauses` list (and also in the `targetlist`) mean that not the tuples of the current

node should be considered but the tuples of the next "deeper" nodes (i.e. the top nodes of the subplans) should be used instead.

Note that every `Sort` and `SeqScan` node appearing in figure \ref{plan} has got a `targetlist` but because there was not enough space only the one for the `MergeJoin` node could be drawn.

Another task performed by the planner/optimizer is fixing the *operator ids* in the `Expr` and `Oper` nodes. As mentioned earlier, PostgreSQL supports a variety of different data types and even user defined types can be used. To be able to maintain the huge amount of functions and operators it is necessary to store them in a system table. Each function and operator gets a unique operator id. According to the types of the attributes used within the qualifications etc., the appropriate operator ids have to be used.

2.6. Executor

The *executor* takes the plan handed back by the planner/optimizer and starts processing the top node. In the case of our example (the query given in example \ref{simple_select}) the top node is a `MergeJoin` node.

Before any merge can be done two tuples have to be fetched (one from each subplan). So the executor recursively calls itself to process the subplans (it starts with the subplan attached to `lefttree`). The new top node (the top node of the left subplan) is a `SeqScan` node and again a tuple has to be fetched before the node itself can be processed. The executor calls itself recursively another time for the subplan attached to `lefttree` of the `SeqScan` node.

Now the new top node is a `Sort` node. As a sort has to be done on the whole relation, the executor starts fetching tuples from the `Sort` node's subplan and sorts them into a temporary relation (in memory or a file) when the `Sort` node is visited for the first time. (Further examinations of the `Sort` node will always return just one tuple from the sorted temporary relation.)

Every time the processing of the `Sort` node needs a new tuple the executor is recursively called for the `SeqScan` node attached as subplan. The relation (internally referenced by the value given in the `scanrelid` field) is scanned for the next tuple. If the tuple satisfies the qualification given by the tree attached to `qpqual` it is handed back, otherwise the next tuple is fetched until the qualification is satisfied. If the last tuple of the relation has been processed a `NULL` pointer is returned.

After a tuple has been handed back by the `lefttree` of the `MergeJoin` the `righttree` is processed in the same way. If both tuples are present the executor processes the `MergeJoin` node. Whenever a new tuple from one of the subplans is needed a recursive call to the executor is performed to obtain it. If a joined tuple could be created it is handed back and one complete processing of the plan tree has finished.

Now the described steps are performed once for every tuple, until a `NULL` pointer is returned for the processing of the `MergeJoin` node, indicating that we are finished.

Chapter 3. System Catalogs

3.1. Overview

The system catalogs are the place where a relational database management system stores schema metadata, such as information about tables and columns, and internal bookkeeping information. PostgreSQL's system catalogs are regular tables. You can drop and recreate the tables, add columns, insert and update values, and severely mess up your system that way. Normally one should not change the system catalogs by hand, there are always SQL commands to do that. (For example, `CREATE DATABASE` inserts a row into the `pg_database` catalog -- and actually creates the database on disk.) There are some exceptions for especially esoteric operations, such as adding index access methods.

Most system catalogs are copied from the template database during database creation, and are thereafter database-specific. A few catalogs are physically shared across all databases in an installation; these are marked in the descriptions of the individual catalogs.

Table 3.1. System Catalogs

Catalog Name	Purpose
pg_aggregate	aggregate functions
pg_am	index access methods
pg_amop	access method operators
pg_amproc	access method support procedures
pg_attrdef	column default values
pg_attribute	table columns (“attributes”, “fields”)
pg_cast	casts (data type conversions)
pg_class	tables, indexes, sequences (“relations”)
pg_constraint	check constraints, unique / primary key constraints, foreign key constraints
pg_conversion	encoding conversion information
pg_database	databases within this database cluster
pg_depend	dependencies between database objects
pg_description	descriptions or comments on database objects
pg_group	groups of database users
pg_index	additional index information
pg_inherits	table inheritance hierarchy
pg_language	languages for writing functions
pg_largeobject	large objects
pg_listener	asynchronous notification
pg_namespace	namespaces (schemas)
pg_opclass	index access method operator classes
pg_operator	operators
pg_proc	functions and procedures
pg_rewrite	query rewriter rules
pg_shadow	database users
pg_statistic	optimizer statistics

Catalog Name	Purpose
pg_trigger	triggers
pg_type	data types

More detailed documentation of each catalog follows below.

3.2. pg_aggregate

`pg_aggregate` stores information about aggregate functions. An aggregate function is a function that operates on a set of values (typically one column from each row that matches a query condition) and returns a single value computed from all these values. Typical aggregate functions are `sum`, `count`, and `max`. Each entry in `pg_aggregate` is an extension of an entry in `pg_proc`. The `pg_proc` entry carries the aggregate's name, input and output datatypes, and other information that is similar to ordinary functions.

Table 3.2. pg_aggregate Columns

Name	Type	References	Description
aggfnoid	`regproc`	pg_proc.oid	pg_proc OID of the aggregate function
aggtransfn	`regproc`	pg_proc.oid	Transition function
aggfinalfn	`regproc`	pg_proc.oid	Final function (zero if none)
aggtranstype	`oid`	pg_type.oid	The type of the aggregate function's internal transition (state) data
agginitval	`text`		The initial value of the transition state. This is a text field containing the initial value in its external string representation. If the field is NULL, the transition state value starts out NULL.

New aggregate functions are registered with the `CREATE AGGREGATE` command. See the *Programmer's Guide* for more information about writing aggregate functions and the meaning of the transition functions, etc.

3.3. pg_am

`pg_am` stores information about index access methods. There is one row for each index access method supported by the system.

Table 3.3. pg_am Columns

Name	Type	References	Description
amname	`name`		name of the access method
amowner	`int4`	pg_shadow.usesysid	user ID of the owner (currently not used)

Name	Type	References	Description
amstrategies	int2		number of operator strategies for this access method
amsupport	int2		number of support routines for this access method
amorderstrategy	int2		zero if the index offers no sort order, otherwise the strategy number of the strategy operator that describes the sort order
amcanunique	bool		does AM support unique indexes?
amcanmulticol	bool		does AM support multicolumn indexes?
amindexnulls	bool		does AM support NULL index entries?
amconcurrent	bool		does AM support concurrent updates?
amgettuple	regproc	pg_proc.oid	“next valid tuple” function
aminsert	regproc	pg_proc.oid	“insert this tuple” function
ambeginscan	regproc	pg_proc.oid	“start new scan” function
amrescan	regproc	pg_proc.oid	“restart this scan” function
amendscan	regproc	pg_proc.oid	“end this scan” function
ammarkpos	regproc	pg_proc.oid	“mark current scan position” function
amrestrpos	regproc	pg_proc.oid	“restore marked scan position” function
ambuild	regproc	pg_proc.oid	“build new index” function
ambulkdelete	regproc	pg_proc.oid	bulk-delete function
amcostestimate	regproc	pg_proc.oid	estimate cost of an indexscan

An index AM that supports multiple columns (has amcanmulticol true) *must* support indexing nulls in columns after the first, because the planner will assume the index can be used for queries on just the first column(s). For example, consider an index on (a,b) and a query WHERE a = 4. The system will assume the index can be used to scan for rows with a = 4, which is wrong if the index omits rows where b is null. However it is okay to omit rows where the first indexed column is null. (GiST currently does so.) amindexnulls should be set true only if the index AM indexes all rows, including arbitrary combinations of nulls.

3.4. pg_amop

pg_amop stores information about operators associated with index access method operator classes. There is one row for each operator that is a member of an operator class.

Table 3.4. pg_amop Columns

Name	Type	References	Description
amopclaid	oid	pg_opclass.oid	the index opclass this entry is for
amopstrategy	int2		operator strategy number
amopreqcheck	bool		index hit must be rechecked
amopopr	oid	pg_operator.oid	the operator's pg_operator OID

3.5. pg_amproc

pg_amproc stores information about support procedures associated with index access method operator classes. There is one row for each support procedure belonging to an operator class.

Table 3.5. pg_amproc Columns

Name	Type	References	Description
amopclaid	oid	pg_opclass.oid	the index opclass this entry is for
amprocnum	int2		support procedure index
amproc	regproc	pg_proc.oid	OID of the proc

3.6. pg_attrdef

This catalog stores column default values. The main information about columns is stored in pg_attribute (see below). Only columns that explicitly specify a default value (when the table is created or the column is added) will have an entry here.

Table 3.6. pg_attrdef Columns

Name	Type	References	Description
adrelid	oid	pg_class.oid	The table this column belongs to
adnum	int2	pg_attribute.attnum	The number of the column
adbin	text		An internal representation of the column default value
adsrc	text		A human-readable representation of the default value

3.7. pg_attribute

`pg_attribute` stores information about table columns. There will be exactly one `pg_attribute` row for every column in every table in the database. (There will also be attribute entries for indexes and other objects. See `pg_class`.)

The term attribute is equivalent to column and is used for historical reasons.

Table 3.7. pg_attribute Columns

Name	Type	References	Description
attrelid	`oid`	pg_class.oid	The table this column belongs to
attname	`name`		Column name
atttypid	`oid`	pg_type.oid	The data type of this column
attstattarget	`int4`		`attstattarget` controls the level of detail of statistics accumulated for this column by `ANALYZE`. A zero value indicates that no statistics should be collected. A negative value says to use the system default statistics target. The exact meaning of positive values is datatype-dependent. For scalar datatypes, `attstattarget` is both the target number of "most common values" to collect, and the target number of histogram bins to create.
attlen	`int2`		This is a copy of `pg_type.typlen` of this column's type.
attnum	`int2`		The number of the column. Ordinary columns are numbered from 1 up. System columns, such as `oid`, have (arbitrary) negative numbers.
attndims	`int4`		Number of dimensions, if the column is an array type; otherwise 0. (Presently, the number of dimensions of an array is not enforced, so any nonzero value

Name	Type	References	Description
			effectively means “it's an array”.)
attcacheoff	int4		Always -1 in storage, but when loaded into a tuple descriptor in memory this may be updated to cache the offset of the attribute within the tuple.
atttypmod	int4		atttypmod records type-specific data supplied at table creation time (for example, the maximum length of a varchar column). It is passed to type-specific input functions and length coercion functions. The value will generally be -1 for types that do not need typmod.
attbyval	bool		A copy of pg_type.typbyval of this column's type
attstorage	char		Normally a copy of pg_type.typstorage of this column's type. For TOASTable datatypes, this can be altered after column creation to control storage policy.
attisset	bool		If true, this attribute is a set. In that case, what is really stored in the attribute is the OID of a tuple in the pg_proc catalog. The pg_proc tuple contains the query string that defines this set - i.e., the query to run to get the set. So the atttypid (see above) refers to the type returned by this query, but the actual length of this attribute is the length (size) of an oid. --- At least this is the theory. All this is probably quite broken these days.

Name	Type	References	Description
attalign	char		A copy of pg_type.typalign of this column's type
attnotnull	bool		This represents a NOT NULL constraint. It is possible to change this field to enable or disable the constraint.
atthasdef	bool		This column has a default value, in which case there will be a corresponding entry in the pg_attrdef catalog that actually defines the value.
attisdropped	bool		This column has been dropped and is no longer valid. A dropped column is still physically present in the table, but is ignored by the parser and so cannot be accessed via SQL.
attislocal	bool		This column is defined locally in the relation. Note that a column may be locally defined and inherited simultaneously.
attinhcount	int4		The number of direct ancestors this column has. A column with a nonzero number of ancestors cannot be dropped nor renamed.

3.8. pg_cast

pg_cast stores data type conversion paths, both built-in paths and those defined with CREATE CAST.

Table 3.8. pg_cast Columns

Name	Type	References	Description
castsource	oid	pg_type.oid	OID of the source data type
casttarget	oid	pg_type.oid	OID of the target data type
castfunc	oid	pg_proc.oid	The OID of the function to use to perform this cast. Zero is stored if the data types are binary coercible (that is, no

Name	Type	References	Description
			run-time operation is needed to perform the cast).
castcontext	char		Indicates what contexts the cast may be invoked in. e means only as an explicit cast (using CAST, ::, or function-call syntax). a means implicitly in assignment to a target column, as well as explicitly. i means implicitly in expressions, as well as the other cases.

3.9. pg_class

pg_class catalogs tables and most everything else that has columns or is otherwise similar to a table. This includes indexes (but see also pg_index), sequences, views, and some kinds of special relation; see relkind. Below, when we mean all of these kinds of objects we speak of "relations". Not all fields are meaningful for all relation types.

Table 3.9. pg_class Columns

Name	Type	References	Description
relname	name		Name of the table, index, view, etc.
relnamespace	oid	pg_namespace.oid	The OID of the namespace that contains this relation
reltype	oid	pg_type.oid	The OID of the data type that corresponds to this table, if any (zero for indexes, which have no pg_type entry)
relowner	int4	pg_shadow.usesysid	Owner of the relation
relam	oid	pg_am.oid	If this is an index, the access method used (B-tree, hash, etc.)
relfilenode	oid		Name of the on-disk file of this relation; 0 if none
relpages	int4		Size of the on-disk representation of this table in pages (size BLCKSZ). This is only an estimate used by the planner. It is updated by VACUUM, ANALYZE, and CREATE INDEX.
reltuples	float4		Number of tuples in the table. This is only an estimate used by the

Name	Type	References	Description
			planner. It is updated by VACUUM, ANALYZE, and CREATE INDEX.
reltoastrelid	oid	pg_class.oid	OID of the TOAST table associated with this table, 0 if none. The TOAST table stores large attributes “out of line” in a secondary table.
reltoastidxid	oid	pg_class.oid	For a TOAST table, the OID of its index. 0 if not a TOAST table.
relhasindex	bool		True if this is a table and it has (or recently had) any indexes. This is set by CREATE INDEX, but not cleared immediately by DROP INDEX. VACUUM clears relhasindex if it finds the table has no indexes.
relisshared	bool		True if this table is shared across all databases in the cluster. Only certain system catalogs (such as pg_database) are shared.
relkind	char		'r' = ordinary table, 'i' = index, 'S' = sequence, 'v' = view, 'c' = composite type, 's' = special, 't' = TOAST table
relnatts	int2		Number of user columns in the relation (system columns not counted). There must be this many corresponding entries in pg_attribute. See also pg_attribute.attnum.
relchecks	int2		Number of check constraints on the table; see pg_constraint catalog
reltriggers	int2		Number of triggers on the table; see pg_trigger catalog
relukeys	int2		unused (*Not* the number of unique keys)

Name	Type	References	Description
relfkeys	int2		unused (*Not* the number of foreign keys on the table)
relrefs	int2		unused
relhasoids	bool		True if we generate an OID for each row of the relation.
relhaspkey	bool		True if the table has (or once had) a primary key.
relhasrules	bool		Table has rules; see pg_rewrite catalog
relhassubclass	bool		At least one table inherits from this one
relacl	aclitem[]		Access permissions. See the descriptions of GRANT and REVOKE for details.

3.10. pg_constraint

This system catalog stores CHECK, PRIMARY KEY, UNIQUE, and FOREIGN KEY constraints on tables. (Column constraints are not treated specially. Every column constraint is equivalent to some table constraint.) See under CREATE TABLE for more information.

Note

NOT NULL constraints are represented in the pg_attribute catalog.

CHECK constraints on domains are stored here, too. Global ASSERTIONS (a currently-unsupported SQL feature) may someday appear here as well.

Table 3.10. pg_constraint Columns

Name	Type	References	Description
conname	name		Constraint name (not necessarily unique!)
connamespace	oid	pg_namespace.oid	The OID of the namespace that contains this constraint
contype	char		'c' = check constraint, 'f' = foreign key constraint, 'p' = primary key constraint, 'u' = unique constraint
condeferrable	boolean		Is the constraint deferrable?
condeferred	boolean		Is the constraint deferred by default?
conrelid	oid	pg_class.oid	The table this constraint is on; 0 if not a table constraint

Name	Type	References	Description
contypid	oid	pg_type.oid	The domain this constraint is on; 0 if not a domain constraint
confrelid	oid	pg_class.oid	If a foreign key, the referenced table; else 0
confupdtype	char		Foreign key update action code
confdeltype	char		Foreign key deletion action code
confmatchtype	char		Foreign key match type
conkey	int2[]	pg_attribute.attnum	If a table constraint, list of columns which the constraint constrains
confkey	int2[]	pg_attribute.attnum	If a foreign key, list of the referenced columns
conbin	text		If a check constraint, an internal representation of the expression
consrc	text		If a check constraint, a human-readable representation of the expression

Note

`pg_class.relchecks` needs to agree with the number of check-constraint entries found in this table for the given relation.

3.11. pg_conversion

This system catalog stores encoding conversion information. See `CREATE CONVERSION` for more information.

Table 3.11. pg_conversion Columns

Name	Type	References	Description
conname	name		Conversion name (unique within a namespace)
connamespace	oid	pg_namespace.oid	The OID of the namespace that contains this conversion
conowner	int4	pg_shadow.usesysid	Owner (creator) of the namespace
conforencoding	int4		Source(for) encoding ID
contoencoding	int4		Destination(to) encoding ID
conproc	regproc	pg_proc.oid	Conversion procedure

Name	Type	References	Description
condefault	boolean		true if this is the default conversion

3.12. pg_database

The pg_database catalog stores information about the available databases. Databases are created with the CREATE DATABASE command. Consult the *Administrator's Guide* for details about the meaning of some of the parameters.

Unlike most system catalogs, pg_database is shared across all databases of a cluster: there is only one copy of pg_database per cluster, not one per database.

Table 3.12. pg_database Columns

Name	Type	References	Description
datname	name		Database name
datdba	int4	pg_shadow.usesysid	Owner of the database, usually the user who created it
encoding	int4		Character/multibyte encoding for this database
datistemplate	bool		If true then this database can be used in the "TEMPLATE" clause of CREATE DATABASE to create a new database as a clone of this one.
datallowconn	bool		If false then no one can connect to this database. This is used to protect the template0 database from being altered.
datlastsysoid	oid		Last system OID in the database; useful particularly to pg_dump
datvacuumxid	xid		All tuples inserted or deleted by transaction IDs before this one have been marked as known committed or known aborted in this database. This is used to determine when commit-log space can be recycled.
datfrozenxid	xid		All tuples inserted by transaction IDs before this one have been relabeled with a permanent ("frozen") transaction ID in this

Name	Type	References	Description
			database. This is useful to check whether a database must be vacuumed soon to avoid transaction ID wraparound problems.
datpath	text		If the database is stored at an alternative location then this records the location. It's either an environment variable name or an absolute path, depending how it was entered.
datconfig	text[]		Session defaults for run-time configuration variables
datacl	aclitem[]		Access permissions

3.13. pg_depend

The pg_depend table records the dependency relationships between database objects. This information allows DROP commands to find which other objects must be dropped by DROP CASCADE, or prevent dropping in the DROP RESTRICT case.

Table 3.13. pg_depend Columns

Name	Type	References	Description
classid	oid	pg_class.oid	The oid of the system catalog the dependent object is in
objid	oid	any oid attribute	The oid of the specific dependent object
objsubid	int4		For a table attribute, this is the attribute's column number (the objid and classid refer to the table itself). For all other object types, this field is presently zero.
refclassid	oid	pg_class.oid	The oid of the system catalog the referenced object is in
refobjid	oid	any oid attribute	The oid of the specific referenced object
refobjsubid	int4		For a table attribute, this is the attribute's column number (the refobjid and refclassid refer to the table itself). For all other object types, this field is presently zero.

Name	Type	References	Description
deptype	char		A code defining the specific semantics of this dependency relationship.

In all cases, a pg_depend entry indicates that the referenced object may not be dropped without also dropping the dependent object. However, there are several subflavors identified by deptype:

- DEPENDENCY_NORMAL ('n'): normal relationship between separately-created objects. The dependent object may be dropped without affecting the referenced object. The referenced object may only be dropped by specifying CASCADE, in which case the dependent object is dropped too. Example: a table column has a normal dependency on its datatype.
- DEPENDENCY_AUTO ('a'): the dependent object can be dropped separately from the referenced object, and should be automatically dropped (regardless of RESTRICT or CASCADE mode) if the referenced object is dropped. Example: a named constraint on a table is made auto-dependent on the table, so that it will go away if the table is dropped.
- DEPENDENCY_INTERNAL ('i'): the dependent object was created as part of creation of the referenced object, and is really just a part of its internal implementation. A DROP of the dependent object will be disallowed outright (we'll tell the user to issue a DROP against the referenced object, instead). A DROP of the referenced object will be propagated through to drop the dependent object whether CASCADE is specified or not. Example: a trigger that's created to enforce a foreign-key constraint is made internally dependent on the constraint's pg_constraint entry.
- DEPENDENCY_PIN ('p'): there is no dependent object; this type of entry is a signal that the system itself depends on the referenced object, and so that object must never be deleted. Entries of this type are created only during initdb. The fields for the dependent object contain zeroes.

Other dependency flavors may be needed in future.

3.14. pg_description

The pg_description table can store an optional description or comment for each database object. Descriptions can be manipulated with the COMMENT command and viewed with psql's \d commands. Descriptions of many built-in system objects are provided in the initial contents of pg_description.

Table 3.14. pg_description Columns

Name	Type	References	Description
objoid	oid	any oid attribute	The oid of the object this description pertains to
classoid	oid	pg_class.oid	The oid of the system catalog this object appears in
objsubid	int4		For a comment on a table attribute, this is the attribute's column number (the objoid and classoid refer to the table itself). For all other object types, this field is presently zero.
description	text		Arbitrary text that serves as the description of this object.

3.15. pg_group

This catalog defines groups and stores what users belong to what groups. Groups are created with the `CREATE GROUP` command. Consult the *Administrator's Guide* for information about user permission management.

Because user and group identities are cluster-wide, `pg_group` is shared across all databases of a cluster: there is only one copy of `pg_group` per cluster, not one per database.

Table 3.15. pg_group Columns

Name	Type	References	Description
groname	`name`		Name of the group
grosysid	`int4`		An arbitrary number to identify this group
grolist	`int4[]`	pg_shadow.usesysid	An array containing the ids of the users in this group

3.16. pg_index

`pg_index` contains part of the information about indexes. The rest is mostly in `pg_class`.

Table 3.16. pg_index Columns

Name	Type	References	Description
indexrelid	`oid`	pg_class.oid	The OID of the pg_class entry for this index
indrelid	`oid`	pg_class.oid	The OID of the pg_class entry for the table this index is for
indproc	`regproc`	pg_proc.oid	The function's OID if this is a functional index, else zero
indkey	`int2vector`	pg_attribute.attnum	This is a vector (array) of up to `INDEX_MAX_KEYS` values that indicate which table columns this index pertains to. For example a value of `1 3` would mean that the first and the third column make up the index key. For a functional index, these columns are the inputs to the function, and the function's return value is the index key.
indclass	`oidvector`	pg_opclass.oid	For each column in the index key this contains a reference to the “operator class” to

Name	Type	References	Description
			use. See `pg_opclass` for details.
indisclustered	`bool`		If true, the table was last clustered on this index.
indisunique	`bool`		If true, this is a unique index.
indisprimary	`bool`		If true, this index represents the primary key of the table. (indisunique should always be true when this is true.)
indreference	`oid`		unused
indpred	`text`		Expression tree (in the form of a nodeToString representation) for partial index predicate. Empty string if not a partial index.

3.17. pg_inherits

This catalog records information about table inheritance hierarchies.

Table 3.17. pg_inherits Columns

Name	Type	References	Description
inhrelid	`oid`	pg_class.oid	The OID of the child table.
inhparent	`oid`	pg_class.oid	The OID of the parent table.
inhseqno	`int4`		If there is more than one parent for a child table (multiple inheritance), this number tells the order in which the inherited columns are to be arranged. The count starts at 1.

3.18. pg_language

`pg_language` registers call interfaces or languages in which you can write functions or stored procedures. See under `CREATE LANGUAGE` and in the *Programmer's Guide* for more information about language handlers.

Table 3.18. pg_language Columns

Name	Type	References	Description
lanname	`name`		Name of the language (to be specified when creating a function)

Name	Type	References	Description
lanispl	bool		This is false for internal languages (such as SQL) and true for user-defined languages. Currently, pg_dump still uses this to determine which languages need to be dumped, but this may be replaced by a different mechanism sometime.
lanpltrusted	bool		This is a trusted language. See under CREATE LANGUAGE what this means. If this is an internal language (lanispl is false) then this field is meaningless.
lanplcallfoid	oid	pg_proc.oid	For non-internal languages this references the language handler, which is a special function that is responsible for executing all functions that are written in the particular language.
lanvalidator	oid	pg_proc.oid	This references a language validator function that is responsible for checking the syntax and validity of new functions when they are created. See under CREATE LANGUAGE for further information about validators.
lanacl	aclitem[]		Access permissions

3.19. pg_largeobject

pg_largeobject holds the data making up “large objects”. A large object is identified by an OID assigned when it is created. Each large object is broken into segments or “pages” small enough to be conveniently stored as rows in pg_largeobject. The amount of data per page is defined to be LOBLKSIZE (which is currently BLCKSZ/4, or typically 2Kbytes).

Table 3.19. pg_largeobject Columns

Name	Type	References	Description
loid	oid		Identifier of the large object that includes this page

Name	Type	References	Description
pageno	int4		Page number of this page within its large object (counting from zero)
data	bytea		Actual data stored in the large object. This will never be more than LOBLKSIZE bytes, and may be less.

Each row of pg_largeobject holds data for one page of a large object, beginning at byte offset (pageno * LOBLKSIZE) within the object. The implementation allows sparse storage: pages may be missing, and may be shorter than LOBLKSIZE bytes even if they are not the last page of the object. Missing regions within a large object read as zeroes.

3.20. pg_listener

pg_listener supports the LISTEN and NOTIFY commands. A listener creates an entry in pg_listener for each notification name it is listening for. A notifier scans pg_listener and updates each matching entry to show that a notification has occurred. The notifier also sends a signal (using the PID recorded in the table) to awaken the listener from sleep.

Table 3.20. pg_listener Columns

Name	Type	References	Description
relname	name		Notify condition name. (The name need not match any actual relation in the database; the term “relname” is historical.)
listenerpid	int4		PID of the backend process that created this entry.
notification	int4		Zero if no event is pending for this listener. If an event is pending, the PID of the backend that sent the notification.

3.21. pg_namespace

A namespace is the structure underlying SQL92 schemas: each namespace can have a separate collection of relations, types, etc without name conflicts.

Table 3.21. pg_namespace Columns

Name	Type	References	Description
nspname	name		Name of the namespace
nspowner	int4	pg_shadow.usesysid	Owner (creator) of the namespace

Name	Type	References	Description
nspacl	aclitem[]		Access permissions

3.22. pg_opclass

pg_opclass defines index access method operator classes. Each operator class defines semantics for index columns of a particular datatype and a particular index access method. Note that there can be multiple operator classes for a given datatype/access method combination, thus supporting multiple behaviors.

Operator classes are described at length in the *Programmer's Guide*.

Table 3.22. pg_opclass Columns

Name	Type	References	Description
opcamid	oid	pg_am.oid	index access method opclass is for
opcname	name		name of this opclass
opcnamespace	oid	pg_namespace.oid	namespace of this opclass
opcowner	int4	pg_shadow.usesysid	opclass owner
opcintype	oid	pg_type.oid	type of input data for opclass
opcdefault	bool		true if opclass is default for opcintype
opckeytype	oid	pg_type.oid	type of index data, or zero if same as opcintype

The majority of the information defining an operator class is actually not in its pg_opclass row, but in the associated rows in pg_amop and pg_amproc. Those rows are considered to be part of the operator class definition --- this is not unlike the way that a relation is defined by a single pg_class row, plus associated rows in pg_attribute and other tables.

3.23. pg_operator

See CREATE OPERATOR and the *Programmer's Guide* for details on these operator parameters.

Table 3.23. pg_operator Columns

Name	Type	References	Description
oprname	name		Name of the operator
oprnamespace	oid	pg_namespace.oid	The OID of the namespace that contains this operator
oprowner	int4	pg_shadow.usesysid	Owner (creator) of the operator
oprkind	char		'b' = infix (“both”), 'l' = prefix (“left”), 'r' = postfix (“right”)

Name	Type	References	Description
oprcanhash	bool		This operator supports hash joins.
oprleft	oid	pg_type.oid	Type of the left operand
oprright	oid	pg_type.oid	Type of the right operand
oprresult	oid	pg_type.oid	Type of the result
oprcom	oid	pg_operator.oid	Commutator of this operator, if any
oprnegate	oid	pg_operator.oid	Negator of this operator, if any
oprlsortop	oid	pg_operator.oid	If this operator supports merge joins, the operator that sorts the type of the left-hand operand (L<L)
oprrsortop	oid	pg_operator.oid	If this operator supports merge joins, the operator that sorts the type of the right-hand operand (R<R)
oprltcmpop	oid	pg_operator.oid	If this operator supports merge joins, the less-than operator that compares the left and right operand types (L<R)
oprgtcmpop	oid	pg_operator.oid	If this operator supports merge joins, the greater-than operator that compares the left and right operand types (L>R)
oprcode	regproc	pg_proc.oid	Function that implements this operator
oprrest	regproc	pg_proc.oid	Restriction selectivity estimation function for this operator
oprjoin	regproc	pg_proc.oid	Join selectivity estimation function for this operator

Unused fields contain zeroes, for example oprleft is zero for a prefix operator.

3.24. pg_proc

This catalog stores information about functions (or procedures). The description of CREATE FUNCTION and the *Programmer's Guide* contain more information about the meaning of some fields.

The table contains data for aggregate functions as well as plain functions. If proisagg is true, there should be a matching row in pg_aggregate.

Table 3.24. pg_proc Columns

Name	Type	References	Description
proname	name		Name of the function
pronamespace	oid	pg_namespace.oid	The OID of the namespace that contains this function
proowner	int4	pg_shadow.usesysid	Owner (creator) of the function
prolang	oid	pg_language.oid	Implementation language or call interface of this function
proisagg	bool		Function is an aggregate function
prosecdef	bool		Function is a security definer (i.e., a “setuid” function)
proisstrict	bool		Function returns null if any call argument is null. In that case the function won't actually be called at all. Functions that are not “strict” must be prepared to handle null inputs.
proretset	bool		Function returns a set (ie, multiple values of the specified data type)
provolatile	char		provolatile tells whether the function's result depends only on its input arguments, or is affected by outside factors. It is i for “immutable” functions, which always deliver the same result for the same inputs. It is s for “stable” functions, whose results (for fixed inputs) do not change within a scan. It is v for “volatile” functions, whose results may change at any time. (Use v also for functions with side-effects, so that calls to them cannot get optimized away.)
pronargs	int2		Number of arguments
prorettype	oid	pg_type.oid	Data type of the return value

Name	Type	References	Description
proargtypes	oidvector	pg_type.oid	A vector with the data types of the function arguments
prosrc	text		This tells the function handler how to invoke the function. It might be the actual source code of the function for interpreted languages, a link symbol, a file name, or just about anything else, depending on the implementation language/call convention.
probin	bytea		Additional information about how to invoke the function. Again, the interpretation is language-specific.
proacl	aclitem[]		Access permissions

Currently, prosrc contains the function's C-language name (link symbol) for compiled functions, both built-in and dynamically loaded. For all other language types, prosrc contains the function's source text.

Currently, probin is unused except for dynamically-loaded C functions, for which it gives the name of the shared library file containing the function.

3.25. pg_rewrite

This system catalog stores rewrite rules for tables and views.

Table 3.25. pg_rewrite Columns

Name	Type	References	Description
rulename	name		Rule name
ev_class	oid	pg_class.oid	The table this rule is for
ev_attr	int2		The column this rule is for (currently, always zero to indicate the whole table)
ev_type	char		Event type that the rule is for: '1' = SELECT, '2' = UPDATE, '3' = INSERT, '4' = DELETE
is_instead	bool		True if the rule is an INSTEAD rule
ev_qual	text		Expression tree (in the form of a nodeToString representation) for the rule's qualifying condition

Name	Type	References	Description
ev_action	text		Query tree (in the form of a nodeToString representation) for the rule's action

Note

pg_class.relhasrules must be true if a table has any rules in this catalog.

3.26. pg_shadow

pg_shadow contains information about database users. The name stems from the fact that this table should not be readable by the public since it contains passwords. pg_user is a publicly readable view on pg_shadow that blanks out the password field.

The *Administrator's Guide* contains detailed information about user and permission management.

Because user identities are cluster-wide, pg_shadow is shared across all databases of a cluster: there is only one copy of pg_shadow per cluster, not one per database.

Table 3.26. pg_shadow Columns

Name	Type	References	Description
usename	name		User name
usesysid	int4		User id (arbitrary number used to reference this user)
usecreatedb	bool		User may create databases
usesuper	bool		User is a superuser
usecatupd	bool		User may update system catalogs. (Even a superuser may not do this unless this attribute is true.)
passwd	text		Password
valuntil	abstime		Account expiry time (only used for password authentication)
useconfig	text[]		Session defaults for run-time configuration variables

3.27. pg_statistic

pg_statistic stores statistical data about the contents of the database. Entries are created by ANALYZE and subsequently used by the query planner. There is one entry for each table column that has been analyzed. Note that all the statistical data is inherently approximate, even assuming that it is up-to-date.

Since different kinds of statistics may be appropriate for different kinds of data, pg_statistic is designed not to assume very much about what sort of statistics it stores. Only extremely general statistics (such as NULL-ness) are given dedicated columns in pg_statistic. Everything else

is stored in “slots”, which are groups of associated columns whose content is identified by a code number in one of the slot's columns. For more information see `src/include/catalog/pg_statistic.h`.

`pg_statistic` should not be readable by the public, since even statistical information about a table's contents may be considered sensitive. (Example: minimum and maximum values of a salary column might be quite interesting.) `pg_stats` is a publicly readable view on `pg_statistic` that only exposes information about those tables that are readable by the current user. `pg_stats` is also designed to present the information in a more readable format than the underlying `pg_statistic` table --- at the cost that its schema must be extended whenever new slot types are added.

Table 3.27. pg_statistic Columns

Name	Type	References	Description
starelid	`oid`	pg_class.oid	The table that the described column belongs to
staattnum	`int2`	pg_attribute.attnum	The number of the described column
stanullfrac	`float4`		The fraction of the column's entries that are NULL
stawidth	`int4`		The average stored width, in bytes, of non-NULL entries
stadistinct	`float4`		The number of distinct non-NULL data values in the column. A value greater than zero is the actual number of distinct values. A value less than zero is the negative of a fraction of the number of rows in the table (for example, a column in which values appear about twice on the average could be represented by stadistinct = -0.5). A zero value means the number of distinct values is unknown.
stakindN	`int2`		A code number indicating the kind of statistics stored in the Nth “slot” of the `pg_statistic` row.
staopN	`oid`	pg_operator.oid	An operator used to derive the statistics stored in the Nth “slot”. For example, a histogram slot would show the < operator that defines the sort order of the data.

Name	Type	References	Description
stanumbersN	`float4[]`		Numerical statistics of the appropriate kind for the Nth “slot”, or NULL if the slot kind does not involve numerical values.
stavaluesN	`text[]`		Column data values of the appropriate kind for the Nth “slot”, or NULL if the slot kind does not store any data values. For data-type independence, all column data values are converted to external textual form and stored as TEXT datums.

3.28. pg_trigger

This system catalog stores triggers on tables. See under `CREATE TRIGGER` for more information.

Table 3.28. pg_trigger Columns

Name	Type	References	Description
tgrelid	`oid`	pg_class.oid	The table this trigger is on
tgname	`name`		Trigger name (must be unique among triggers of same table)
tgfoid	`oid`	pg_proc.oid	The function to be called
tgtype	`int2`		Bitmask identifying trigger conditions
tgenabled	`bool`		True if trigger is enabled (not presently checked everywhere it should be, so disabling a trigger by setting this false does not work reliably)
tgisconstraint	`bool`		True if trigger implements an RI constraint
tgconstrname	`name`		RI constraint name
tgconstrrelid	`oid`	pg_class.oid	The table referenced by an RI constraint
tgdeferrable	`bool`		True if deferrable
tginitdeferred	`bool`		True if initially deferred
tgnargs	`int2`		Number of argument strings passed to trigger function

Name	Type	References	Description
tgattr	int2vector		Currently unused
tgargs	bytea		Argument strings to pass to trigger, each null-terminated

Note

pg_class.reltriggers needs to match up with the entries in this table.

3.29. pg_type

This catalog stores information about data types. Scalar types ("base types") are created with CREATE TYPE. A complex type is automatically created for each table in the database, to represent the row structure of the table. It is also possible to create complex types with CREATE TYPE AS, and derived types with CREATE DOMAIN.

Table 3.29. pg_type Columns

Name	Type	References	Description
typname	name		Data type name
typnamespace	oid	pg_namespace.oid	The OID of the namespace that contains this type
typowner	int4	pg_shadow.usesysid	Owner (creator) of the type
typlen	int2		For a fixed-size type, typlen is the number of bytes in the internal representation of the type. But for a variable-length type, typlen is negative. -1 indicates a "varlena" type (one that has a length word), -2 indicates a null-terminated C string.
typbyval	bool		typbyval determines whether internal routines pass a value of this type by value or by reference. Only char, short, and int equivalent items can be passed by value, so if the type is not 1, 2, or 4 bytes long, PostgreSQL does not have the option of passing by value and so typbyval had better be false. Variable-length types are always passed by reference. Note that typbyval can be false

Name	Type	References	Description
			even if the length would allow pass-by-value; this is currently true for type `float4`, for example.
typtype	`char`		`typtype` is `b` for a base type, `c` for a complex type (i.e., a table's row type), `d` for a derived type (i.e., a domain), or `p` for a pseudo-type. See also `typrelid` and `typbasetype`.
typisdefined	`bool`		True if the type is defined, false if this is a placeholder entry for a not-yet-defined type. When typisdefined is false, nothing except the type name, namespace, and OID can be relied on.
typdelim	`char`		Character that separates two values of this type when parsing array input. Note that the delimiter is associated with the array element data type, not the array data type.
typrelid	`oid`	pg_class.oid	If this is a complex type (see `typtype`), then this field points to the `pg_class` entry that defines the corresponding table. (For a free-standing composite type, the `pg_class` entry doesn't really represent a table, but it is needed anyway for the type's `pg_attribute` entries to link to.) Zero for non-complex types.
typelem	`oid`	pg_type.oid	If `typelem` is not 0 then it identifies another row in `pg_type`. The current type can then be subscripted like an array yielding values of type `typelem`. A “true”

Name	Type	References	Description
			array type is variable length (`typlen` = -1), but some fixed-length (`typlen` > 0) types also have nonzero `typelem`, for example `name` and `oidvector`. If a fixed-length type has a `typelem` then its internal representation must be N values of the `typelem` data type with no other data. Variable-length array types have a header defined by the array subroutines.
typinput	`regproc`	pg_proc.oid	Input conversion function
typoutput	`regproc`	pg_proc.oid	Output conversion function
typalign	`char`		`typalign` is the alignment required when storing a value of this type. It applies to storage on disk as well as most representations of the value inside PostgreSQL. When multiple values are stored consecutively, such as in the representation of a complete row on disk, padding is inserted before a datum of this type so that it begins on the specified boundary. The alignment reference is the beginning of the first datum in the sequence. Possible values are: • 'c' = CHAR alignment, i.e., no alignment needed. • 's' = SHORT alignment (2 bytes on most machines).

Name	Type	References	Description
			• 'i' = INT alignment (4 bytes on most machines). • 'd' = DOUBLE alignment (8 bytes on many machines, but by no means all). **Note** For types used in system tables, it is critical that the size and alignment defined in `pg_type` agree with the way that the compiler will lay out the field in a struct representing a table row.
typstorage	`char`		`typstorage` tells for varlena types (those with `typlen = -1`) if the type is prepared for toasting and what the default strategy for attributes of this type should be. Possible values are • 'p': Value must always be stored plain. • 'e': Value can be stored in a "secondary" relation (if relation has one, see `pg_class.reltoastrelid`). • 'm': Value can be stored compressed inline. • 'x': Value can be stored compressed inline or in "secondary". Note that 'm' fields can also be moved out to

Name	Type	References	Description
			secondary storage, but only as a last resort ('e' and 'x' fields are moved first).
typnotnull	`bool`		`typnotnull` represents a NOT NULL constraint on a type. Presently used for domains only.
typbasetype	`oid`	pg_type.oid	If this is a derived type (see `typtype`), then `typbasetype` identifies the type that this one is based on. Zero if not a derived type.
typtypmod	`int4`		Domains use `typtypmod` to record the typmod to be applied to their base type (-1 if base type does not use a typmod). -1 if this type is not a domain.
typndims	`int4`		`typndims` is the number of array dimensions for a domain that is an array (that is, typbasetype is an array type; the domain's typelem will match the base type's typelem). Zero for non-domains and non-array domains.
typdefaultbin	`text`		If `typdefaultbin` is not NULL, it is the nodeToString representation of a default expression for the type. Currently this is only used for domains.
typdefault	`text`		`typdefault` is NULL if the type has no associated default value. If `typdefaultbin` is not NULL, `typdefault` must contain a human-readable version of the default expression represented by `typdefaultbin`. If `typdefaultbin` is

Name	Type	References	Description
			NULL and `typdefault` is not, then `typdefault` is the external representation of the type's default value, which may be fed to the type's input converter to produce a constant.

Chapter 4. Frontend/Backend Protocol

Note

Written by Phil Thompson (<phil@river-bank.demon.co.uk>). Updates for protocol 2.0 by Tom Lane (<tgl@sss.pgh.pa.us>).

PostgreSQL uses a message-based protocol for communication between frontends and backends. The protocol is implemented over TCP/IP and also on Unix domain sockets. PostgreSQL 6.3 introduced version numbers into the protocol. This was done in such a way as to still allow connections from earlier versions of frontends, but this document does not cover the protocol used by those earlier versions.

This document describes version 2.0 of the protocol, implemented in PostgreSQL 6.4 and later.

Higher level features built on this protocol (for example, how libpq passes certain environment variables after the connection is established) are covered elsewhere.

4.1. Overview

A frontend opens a connection to the server and sends a start-up packet. This includes the names of the user and of the database the user wants to connect to. The server then uses this, and the information in the `pg_hba.conf` file to determine what further authentication information it requires the frontend to send (if any) and responds to the frontend accordingly.

The frontend then sends any required authentication information. Once the server validates this it responds to the frontend that it is authenticated and sends a message indicating successful start-up (normal case) or failure (for example, an invalid database name).

In order to serve multiple clients efficiently, the server launches a new "backend" process for each client. This is transparent to the protocol, however. In the current implementation, a new child process is created immediately after an incoming connection is detected.

When the frontend wishes to disconnect it sends an appropriate packet and closes the connection without waiting for a response from the backend.

Packets are sent as a data stream. The first byte determines what should be expected in the rest of the packet. The exceptions are packets sent as part of the start-up and authentication exchange, which comprise a packet length followed by the packet itself. The difference is historical.

4.2. Protocol

This section describes the message flow. There are four different types of flows depending on the state of the connection: start-up, query, function call, and termination. There are also special provisions for notification responses and command cancellation, which can occur at any time after the start-up phase.

4.2.1. Start-up

Initially, the frontend sends a StartupPacket. The server uses this info and the contents of the `pg_hba.conf` file to determine what authentication method the frontend must use. The server then responds with one of the following messages:

ErrorResponse

The server then immediately closes the connection.

AuthenticationOk

The authentication exchange is completed.

AuthenticationKerberosV4

The frontend must then take part in a Kerberos V4 authentication dialog (not described here, part of the Kerberos specification) with the server. If this is successful, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

AuthenticationKerberosV5

The frontend must then take part in a Kerberos V5 authentication dialog (not described here, part of the Kerberos specification) with the server. If this is successful, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

AuthenticationCleartextPassword

The frontend must then send a PasswordPacket containing the password in clear-text form. If this is the correct password, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

AuthenticationCryptPassword

The frontend must then send a PasswordPacket containing the password encrypted via crypt(3), using the 2-character salt specified in the AuthenticationCryptPassword packet. If this is the correct password, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

AuthenticationMD5Password

The frontend must then send a PasswordPacket containing the password encrypted via MD5, using the 4-character salt specified in the AuthenticationMD5Password packet. If this is the correct password, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

AuthenticationSCMCredential

This method is only possible for local Unix-domain connections on platforms that support SCM credential messages. The frontend must issue an SCM credential message and then send a single data byte. (The contents of the data byte are uninteresting; it's only used to ensure that the server waits long enough to receive the credential message.) If the credential is acceptable, the server responds with an AuthenticationOk, otherwise it responds with an ErrorResponse.

If the frontend does not support the authentication method requested by the server, then it should immediately close the connection.

After having received AuthenticationOk, the frontend should wait for further messages from the server. The possible messages from the backend in this phase are:

BackendKeyData

This message provides secret-key data that the frontend must save if it wants to be able to issue cancel requests later. The frontend should not respond to this message, but should continue listening for a ReadyForQuery message.

ReadyForQuery

Start-up is completed. The frontend may now issue query or function call messages.

ErrorResponse

Start-up failed. The connection is closed after sending this message.

NoticeResponse

A warning message has been issued. The frontend should display the message but continue listening for ReadyForQuery or ErrorResponse.

The ReadyForQuery message is the same one that the backend will issue after each query cycle. Depending on the coding needs of the frontend, it is reasonable to consider ReadyForQuery as starting a query cycle (and then BackendKeyData indicates successful conclusion of the start-up phase), or to consider ReadyForQuery as ending the start-up phase and each subsequent query cycle.

4.2.2. Query

A Query cycle is initiated by the frontend sending a Query message to the backend. The backend then sends one or more response messages depending on the contents of the query command string, and finally a ReadyForQuery response message. ReadyForQuery informs the frontend that it may safely send a new query or function call.

The possible response messages from the backend are:

CompletedResponse

An SQL command completed normally.

CopyInResponse

The backend is ready to copy data from the frontend to a table. The frontend should then send a CopyDataRows message. The backend will then respond with a CompletedResponse message with a tag of `COPY`.

CopyOutResponse

The backend is ready to copy data from a table to the frontend. It then sends a CopyDataRows message, and then a CompletedResponse message with a tag of `COPY`.

CursorResponse

Beginning of the response to a `SELECT`, `FETCH`, `INSERT`, `UPDATE`, or `DELETE` query. In the `FETCH` case the name of the cursor being fetched from is included in the message. Otherwise the message always mentions the “blank” cursor.

RowDescription

Indicates that rows are about to be returned in response to a `SELECT` or `FETCH` query. The message contents describe the layout of the rows. This will be followed by an AsciiRow or BinaryRow message (depending on whether a binary cursor was specified) for each row being returned to the frontend.

EmptyQueryResponse

An empty query string was recognized.

ErrorResponse

An error has occurred.

ReadyForQuery

Processing of the query string is complete. A separate message is sent to indicate this because the query string may contain multiple SQL commands. (CompletedResponse marks the end of processing one SQL command, not the whole string.) ReadyForQuery will always be sent, whether processing terminates successfully or with an error.

NoticeResponse

A warning message has been issued in relation to the query. Notices are in addition to other responses, i.e., the backend will continue processing the command.

The response to a `SELECT` or `FETCH` query normally consists of CursorResponse, RowDescription, zero or more AsciiRow or BinaryRow messages, and finally CompletedResponse. `INSERT`, `UPDATE`, and `DELETE` queries produce CursorResponse followed by CompletedResponse. `COPY` to or from the frontend invokes special protocol as mentioned above. All other query types normally produce only a CompletedResponse message.

Since a query string could contain several queries (separated by semicolons), there might be several such response sequences before the backend finishes processing the query string. ReadyForQuery is issued when the entire string has been processed and the backend is ready to accept a new query string.

If a completely empty (no contents other than whitespace) query string is received, the response is EmptyQueryResponse followed by ReadyForQuery. (The need to specially distinguish this case is historical.)

In the event of an error, ErrorResponse is issued followed by ReadyForQuery. All further processing of the query string is aborted by ErrorResponse (even if more queries remained in it). Note that this may occur partway through the sequence of messages generated by an individual query.

A frontend must be prepared to accept ErrorResponse and NoticeResponse messages whenever it is expecting any other type of message.

Actually, it is possible for NoticeResponse to arrive even when the frontend is not expecting any kind of message, that is, the backend is nominally idle. (In particular, the backend can be commanded to terminate by its parent process. In that case it will send a NoticeResponse before closing the connection.) It is recommended that the frontend check for such asynchronous notices just before issuing any new command.

Also, if the frontend issues any `LISTEN` commands then it must be prepared to accept NotificationResponse messages at any time; see below.

Recommended practice is to code frontends in a state-machine style that will accept any message type at any time that it could make sense, rather than wiring in assumptions about the exact sequence of messages.

4.2.3. Function Call

A Function Call cycle is initiated by the frontend sending a FunctionCall message to the backend. The backend then sends one or more response messages depending on the results of the function call, and finally a ReadyForQuery response message. ReadyForQuery informs the frontend that it may safely send a new query or function call.

The possible response messages from the backend are:

ErrorResponse

An error has occurred.

FunctionResultResponse

The function call was executed and returned a result.

FunctionVoidResponse

The function call was executed and returned no result.

ReadyForQuery

Processing of the function call is complete. ReadyForQuery will always be sent, whether processing terminates successfully or with an error.

NoticeResponse

A warning message has been issued in relation to the function call. Notices are in addition to other responses, i.e., the backend will continue processing the command.

A frontend must be prepared to accept ErrorResponse and NoticeResponse messages whenever it is expecting any other type of message. Also, if it issues any `LISTEN` commands then it must be prepared to accept NotificationResponse messages at any time; see below.

4.2.4. Notification Responses

If a frontend issues a `LISTEN` command, then the backend will send a NotificationResponse message (not to be confused with NoticeResponse!) whenever a `NOTIFY` command is executed for the same notification name.

Notification responses are permitted at any point in the protocol (after start-up), except within another backend message. Thus, the frontend must be prepared to recognize a NotificationResponse message whenever it is expecting any message. Indeed, it should be able to handle NotificationResponse messages even when it is not engaged in a query.

NotificationResponse

A `NOTIFY` command has been executed for a name for which a previous `LISTEN` command was executed. Notifications may be sent at any time.

It may be worth pointing out that the names used in listen and notify commands need not have anything to do with names of relations (tables) in the SQL database. Notification names are simply arbitrarily chosen condition names.

4.2.5. Cancelling Requests in Progress

During the processing of a query, the frontend may request cancellation of the query. The cancel request is not sent directly on the open connection to the backend for reasons of implementation efficiency: we don't want to have the backend constantly checking for new input from the frontend during query processing. Cancel requests should be relatively infrequent, so we make them slightly cumbersome in order to avoid a penalty in the normal case.

To issue a cancel request, the frontend opens a new connection to the server and sends a CancelRequest message, rather than the StartupPacket message that would ordinarily be sent across a new connection. The server will process this request and then close the connection. For security reasons, no direct reply is made to the cancel request message.

A CancelRequest message will be ignored unless it contains the same key data (PID and secret key) passed to the frontend during connection start-up. If the request matches the PID and secret key for a currently executing backend, the processing of the current query is aborted. (In the existing implementation, this is done by sending a special signal to the backend process that is processing the query.)

The cancellation signal may or may not have any effect --- for example, if it arrives after the backend has finished processing the query, then it will have no effect. If the cancellation is effective, it results in the current command being terminated early with an error message.

The upshot of all this is that for reasons of both security and efficiency, the frontend has no direct way to tell whether a cancel request has succeeded. It must continue to wait for the backend to respond to the query. Issuing a cancel simply improves the odds that the current query will finish soon, and improves the odds that it will fail with an error message instead of succeeding.

Since the cancel request is sent across a new connection to the server and not across the regular frontend/backend communication link, it is possible for the cancel request to be issued by any process, not just the frontend whose query is to be canceled. This may have some benefits of flexibility in building multiple-process applications. It also introduces a security risk, in that unauthorized persons might try to cancel queries. The security risk is addressed by requiring a dynamically generated secret key to be supplied in cancel requests.

4.2.6. Termination

The normal, graceful termination procedure is that the frontend sends a Terminate message and immediately closes the connection. On receipt of the message, the backend immediately closes the connection and terminates.

An ungraceful termination may occur due to software failure (i.e., core dump) at either end. If either frontend or backend sees an unexpected closure of the connection, it should clean up and terminate. The frontend has the option of launching a new backend by recontacting the server if it doesn't want to terminate itself.

For either normal or abnormal termination, any open transaction is rolled back, not committed. One should note however that if a frontend disconnects while a query is being processed, the backend will probably finish the query before noticing the disconnection. If the query is outside any transaction block (`BEGIN` ... `COMMIT` sequence) then its results may be committed before the disconnection is recognized.

4.2.7. SSL Session Encryption

Recent releases of PostgreSQL allow frontend/backend communication to be encrypted using SSL. This provides communication security in environments where attackers might be able to capture the session traffic.

To initiate an SSL-encrypted connection, the frontend initially sends an SSLRequest message rather than a StartupPacket. The server then responds with a single byte containing `Y` or `N`, indicating that it is willing or unwilling to perform SSL, respectively. The frontend may close the connection at this point if it is dissatisfied with the response. To continue after `Y`, perform an SSL startup handshake (not described here, part of the SSL specification) with the server. If this is successful, continue with sending the usual StartupPacket. In this case the StartupPacket and all subsequent data will be SSL-encrypted. To continue after `N`, send the usual StartupPacket and proceed without encryption.

The frontend should also be prepared to handle an ErrorMessage response to SSLRequest from the server. This would only occur if the server predates the addition of SSL support to PostgreSQL. In this case the connection must be closed, but the frontend may choose to open a fresh connection and proceed without requesting SSL.

An initial SSLRequest may also be used in a connection that is being opened to send a CancelRequest message.

While the protocol itself does not provide a way for the server to force SSL encryption, the administrator may configure the server to reject unencrypted sessions as a byproduct of authentication checking.

4.3. Message Data Types

This section describes the base data types used in messages.

Int*n*(*i*)

An *n* bit integer in network byte order. If *i* is specified it is the literal value. Eg. Int16, Int32(42).

LimString*n*(*s*)

A character array of exactly *n* bytes interpreted as a null-terminated string. The zero-byte is omitted if there is insufficient room. If *s* is specified it is the literal value. Eg. LimString32, LimString64("user").

String(*s*)

A conventional C null-terminated string with no length limitation. If *s* is specified it is the literal value. Eg. String, String("user").

Note

There is no predefined limit on the length of a string that can be returned by the backend. Good coding strategy for a frontend is to use an expandable buffer so that anything that fits in memory can be accepted. If that's not feasible, read the full string and discard trailing characters that don't fit into your fixed-size buffer.

Byte*n*(*c*)

Exactly *n* bytes. If *c* is specified it is the literal value. Eg. Byte, Byte1('\n').

4.4. Message Formats

This section describes the detailed format of each message. Each can be sent by either a frontend (F), a backend (B), or both (F & B).

AsciiRow (B)

Byte1('D')

Identifies the message as an ASCII data row. (A prior RowDescription message defines the number of fields in the row and their data types.)

Byte*n*

A bit map with one bit for each field in the row. The 1st field corresponds to bit 7 (MSB) of the 1st byte, the 2nd field corresponds to bit 6 of the 1st byte, the 8th field corresponds to bit 0 (LSB) of the 1st byte, the 9th field corresponds to bit 7 of the 2nd byte, and so on. Each bit is set if the value of the corresponding field is not NULL. If the number of fields is not a multiple of 8, the remainder of the last byte in the bit map is wasted.

Then, for each field with a non-NULL value, there is the following:

Int32

Specifies the size of the value of the field, including this size.

Byte*n*

Specifies the value of the field itself in ASCII characters. *n* is the above size minus 4. There is no trailing zero-byte in the field data; the front end must add one if it wants one.

AuthenticationOk (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(0)

Specifies that the authentication was successful.

AuthenticationKerberosV4 (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(1)

Specifies that Kerberos V4 authentication is required.

AuthenticationKerberosV5 (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(2)

Specifies that Kerberos V5 authentication is required.

AuthenticationCleartextPassword (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(3)

Specifies that a cleartext password is required.

AuthenticationCryptPassword (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(4)

Specifies that a crypt()-encrypted password is required.

Byte2

The salt to use when encrypting the password.

AuthenticationMD5Password (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(5)

Specifies that an MD5-encrypted password is required.

Byte4

The salt to use when encrypting the password.

AuthenticationSCMCredential (B)

Byte1('R')

Identifies the message as an authentication request.

Int32(6)

Specifies that an SCM credentials message is required.

BackendKeyData (B)

Byte1('K')

Identifies the message as cancellation key data. The frontend must save these values if it wishes to be able to issue CancelRequest messages later.

Int32

The process ID of this backend.

Int32

The secret key of this backend.

BinaryRow (B)

Byte1('B')

Identifies the message as a binary data row. (A prior RowDescription message defines the number of fields in the row and their data types.)

Byte*n*

A bit map with one bit for each field in the row. The 1st field corresponds to bit 7 (MSB) of the 1st byte, the 2nd field corresponds to bit 6 of the 1st byte, the 8th field corresponds to bit 0 (LSB) of the 1st byte, the 9th field corresponds to bit 7 of the 2nd byte, and so on. Each bit is set if the value of the corresponding field is not NULL. If the number of fields is not a multiple of 8, the remainder of the last byte in the bit map is wasted.

Then, for each field with a non-NULL value, there is the following:

Int32

Specifies the size of the value of the field, excluding this size.

Byte*n*

Specifies the value of the field itself in binary format. *n* is the above size.

CancelRequest (F)

Int32(16)

The size of the packet in bytes.

Int32(80877102)

The cancel request code. The value is chosen to contain `1234` in the most significant 16 bits, and `5678` in the least 16 significant bits. (To avoid confusion, this code must not be the same as any protocol version number.)

Int32

The process ID of the target backend.

Int32

The secret key for the target backend.

CompletedResponse (B)

Byte1('C')

Identifies the message as a completed response.

String

The command tag. This is usually a single word that identifies which SQL command was completed.

For an `INSERT` command, the tag is `INSERT` *`oid rows`*, where *`rows`* is the number of rows inserted, and *`oid`* is the object ID of the inserted row if *`rows`* is 1, otherwise *`oid`* is 0.

For a `DELETE` command, the tag is `DELETE` *`rows`* where *`rows`* is the number of rows deleted.

For an `UPDATE` command, the tag is `UPDATE` *`rows`* where *`rows`* is the number of rows updated.

CopyDataRows (B & F)

This is a stream of rows where each row is terminated by a Byte1('\n'). This is then followed by the sequence Byte1('\\'), Byte1('.'), Byte1('\n').

CopyInResponse (B)

Byte1('G')

Identifies the message as a Start Copy In response. The frontend must now send a CopyDataRows message.

CopyOutResponse (B)

Byte1('H')

Identifies the message as a Start Copy Out response. This message will be followed by a CopyDataRows message.

CursorResponse (B)

Byte1('P')

Identifies the message as a cursor response.

String

The name of the cursor. This will be “blank” if the cursor is implicit.

EmptyQueryResponse (B)

Byte1('I')

Identifies the message as a response to an empty query string.

String("")

Unused.

ErrorResponse (B)

Byte1('E')

Identifies the message as an error.

String

The error message itself.

FunctionCall (F)

Byte1('F')

Identifies the message as a function call.

String("")

Unused.

Int32

Specifies the object ID of the function to call.

Int32

Specifies the number of arguments being supplied to the function.

Then, for each argument, there is the following:

Int32

Specifies the size of the value of the argument, excluding this size.

Byte*n*

Specifies the value of the field itself in binary format. *n* is the above size.

FunctionResultResponse (B)

Byte1('V')

Identifies the message as a function call result.

Byte1('G')

Specifies that a nonempty result was returned.

Int32

Specifies the size of the value of the result, excluding this size.

Byte*n*

Specifies the value of the result itself in binary format. *n* is the above size.

Byte1('0')

Unused. (Strictly speaking, FunctionResultResponse and FunctionVoidResponse are the same thing but with some optional parts to the message.)

FunctionVoidResponse (B)

Byte1('V')

Identifies the message as a function call result.

Byte1('0')

Specifies that an empty result was returned.

NoticeResponse (B)

Byte1('N')

Identifies the message as a notice.

String

The notice message itself.

NotificationResponse (B)

Byte1('A')

Identifies the message as a notification response.

Int32

The process ID of the notifying backend process.

String

The name of the condition that the notify has been raised on.

PasswordPacket (F)

Int32

The size of the packet in bytes.

String

The password (encrypted, if requested).

Query (F)

Byte1('Q')

Identifies the message as a query.

String

The query string itself.

ReadyForQuery (B)

Byte1('Z')

Identifies the message type. ReadyForQuery is sent whenever the backend is ready for a new query cycle.

RowDescription (B)

Byte1('T')

Identifies the message as a row description.

Int16

Specifies the number of fields in a row (may be zero).

Then, for each field, there is the following:

String

Specifies the field name.

Int32

Specifies the object ID of the field type.

Int16

Specifies the type size.

Int32

Specifies the type modifier.

SSLRequest (F)

Int32(8)

The size of the packet in bytes.

Int32(80877103)

The SSL request code. The value is chosen to contain `1234` in the most significant 16 bits, and `5679` in the least 16 significant bits. (To avoid confusion, this code must not be the same as any protocol version number.)

StartupPacket (F)

Int32(296)

The size of the packet in bytes.

Int32

The protocol version number. The most significant 16 bits are the major version number. The least 16 significant bits are the minor version number.

LimString64

The database name, defaults to the user name if empty.

LimString32

The user name.

LimString64

Any additional command line arguments to be passed to the backend child process by the server.

LimString64

Unused.

LimString64

The optional tty the backend should use for debugging messages. (Currently, this field is unsupported and ignored.)

Terminate (F)

Byte1('X')

Identifies the message as a termination.

Chapter 5. gcc Default Optimizations

Brian Gallew

Note

Contributed by Brian Gallew (<geek+@cmu.edu>)

Configuring gcc to use certain flags by default is a simple matter of editing the /usr/local/lib/gcc-lib/*platform*/*version*/specs file. The format of this file pretty simple. The file is broken into sections, each of which is three lines long. The first line is "**section_name*:" (e.g. "*asm:"). The second line is a list of flags, and the third line is blank.

The easiest change to make is to append the desired default flags to the list in the appropriate section. As an example, let's suppose that I have linux running on a '486 with gcc 2.7.2 installed in the default location. In the file /usr/local/lib/gcc-lib/i486-linux/2.7.2/specs, 13 lines down I find the following section:

```
- ----------SECTION----------
*cc1:


- ----------SECTION----------
```

As you can see, there aren't any default flags. If I always wanted compiles of C code to use "-m486 -fomit-frame-pointer", I would change it to look like:

```
- ----------SECTION----------
*cc1:
- -m486 -fomit-frame-pointer

- ----------SECTION----------
```

If I wanted to be able to generate 386 code for another, older linux box lying around, I'd have to make it look like this:

```
- ----------SECTION----------
*cc1:
%{!m386:-m486} -fomit-frame-pointer

- ----------SECTION----------
```

This will always omit frame pointers, any will build 486-optimized code unless -m386 is specified on the command line.

You can actually do quite a lot of customization with the specs file. Always remember, however, that these changes are global, and affect all users of the system.

Chapter 6. BKI Backend Interface

Backend Interface (BKI) files are scripts in a special language that are input to the PostgreSQL backend running in the special "bootstrap" mode that allows it to perform database functions without a database system already existing. BKI files can therefore be used to create the database system in the first place. (And they are probably not useful for anything else.)

initdb uses a BKI file to do part of its job when creating a new database cluster. The input file used by initdb is created as part of building and installing PostgreSQL by a program named `genbki.sh` from some specially formatted C header files in the source tree. The created BKI file is called `postgres.bki` and is normally installed in the `share` subdirectory of the installation tree.

Related information may be found in the documentation for initdb.

6.1. BKI File Format

This section describes how the PostgreSQL backend interprets BKI files. This description will be easier to understand if the `postgres.bki` file is at hand as an example. You should also study the source code of initdb to get an idea of how the backend is invoked.

BKI input consists of a sequence of commands. Commands are made up of a number of tokens, depending on the syntax of the command. Tokens are usually separated by whitespace, but need not be if there is no ambiguity. There is no special command separator; the next token that syntactically cannot belong to the preceding command starts a new one. (Usually you would put a new command on a new line, for clarity.) Tokens can be certain key words, special characters (parentheses, commas, etc.), numbers, or double-quoted strings. Everything is case sensitive.

Lines starting with a `#` are ignored.

6.2. BKI Commands

open *`tablename`*

Open the table called *`tablename`* for further manipulation.

close [*`tablename`*]

Close the open table called *`tablename`*. It is an error if *`tablename`* is not already opened. If no *`tablename`* is given, then the currently open table is closed.

create *`tablename`* (*`name1`* = *`type1`* [, *`name2`* = *`type2`*, ...])

Create a table named *`tablename`* with the columns given in parentheses.

The *`type`* is not necessarily the data type that the column will have in the SQL environment; that is determined by the `pg_attribute` system catalog. The type here is essentially only used to allocate storage. The following types are allowed: `bool`, `bytea`, `char` (1 byte), `name`, `int2`, `int2vector`, `int4`, `regproc`, `regclass`, `regtype`, `text`, `oid`, `tid`, `xid`, `cid`, `oidvector`, `smgr`, `_int4` (array), `_aclitem` (array). Array types can also be indicated by writing `[]` after the name of the element type.

Note

The table will only be created on disk, it will not automatically be registered in the system catalogs and will therefore not be accessible unless appropriate rows are inserted in `pg_class`, `pg_attribute`, etc.

insert [OID = *oid_value*] (*value1 value2* ...)

Insert a new row into the open table using *value1*, *value2*, etc., for its column values and *oid_value* for its OID. If *oid_value* is zero (0) or the clause is omitted, then the next available OID is used.

NULL values can be specified using the special key word `_null_`. Values containing spaces must be double quoted.

declare [unique] index *indexname* on *tablename* using *amname* (*opclass1 name1* [, ...])

Create an index named *indexname* on the table named *tablename* using the *amname* access method. The fields to index are called *name1*, *name2* etc., and the operator classes to use are *opclass1*, *opclass2* etc., respectively.

build indices

Build the indices that have previously been declared.

6.3. Example

The following sequence of commands will create the `test_table` table with the two columns `cola` and `colb` of type `int4` and `text`, respectively, and insert two rows into the table.

```
create test_table (cola = int4, colb = text)
open test_table
insert OID=421 ( 1 "value1" )
insert OID=422 ( 2 _null_ )
close test_table
```

Chapter 7. Page Files

A description of the database file page format.

This section provides an overview of the page format used by PostgreSQL tables and indexes. (Index access methods need not use this page format. At present, all index methods do use this basic format, but the data kept on index metapages usually doesn't follow the item layout rules exactly.) TOAST tables and sequences are formatted just like a regular table.

In the following explanation, a *byte* is assumed to contain 8 bits. In addition, the term *item* refers to an individual data value that is stored on a page. In a table, an item is a tuple (row); in an index, an item is an index entry.

Table 7.1, “Page Layout” shows the basic layout of a page. There are five parts to each page.

Table 7.1. Sample Page Layout

Item	Description
PageHeaderData	20 bytes long. Contains general information about the page, including free space pointers.
ItemIdData	Array of (offset,length) pairs pointing to the actual items.
Free space	The unallocated space. All new tuples are allocated from here, generally from the end.
Items	The actual items themselves.
Special Space	Index access method specific data. Different methods store different data. Empty in ordinary tables.

The first 20 bytes of each page consists of a page header (PageHeaderData). Its format is detailed in Table 7.2, “PageHeaderData Layout”. The first two fields deal with WAL related stuff. This is followed by three 2-byte integer fields (`pd_lower`, `pd_upper`, and `pd_special`). These represent byte offsets to the start of unallocated space, to the end of unallocated space, and to the start of the special space.

Table 7.2. PageHeaderData Layout

Field	Type	Length	Description
pd_lsn	XLogRecPtr	8 bytes	LSN: next byte after last byte of xlog
pd_sui	StartUpID	4 bytes	SUI of last changes (currently it's used by heap AM only)
pd_lower	LocationIndex	2 bytes	Offset to start of free space.
pd_upper	LocationIndex	2 bytes	Offset to end of free space.
pd_special	LocationIndex	2 bytes	Offset to start of special space.
pd_pagesize_version	uint16	2 bytes	Page size and layout version number information.

All the details may be found in src/include/storage/bufpage.h.

Special space is a region at the end of the page that is allocated at page initialization time and contains information specific to an access method. The last 2 bytes of the page header, `pd_pagesize_version`, store both the page size and a version indicator. Beginning with PostgreSQL 7.3 the version number is 1; prior releases used version number 0. (The basic page layout and header format has not changed, but the layout of heap tuple headers has.) The page size is basically only present as a cross-check; there is no support for having more than one page size in an installation.

Following the page header are item identifiers (`ItemIdData`), each requiring four bytes. An item identifier contains a byte-offset to the start of an item, its length in bytes, and a set of attribute bits which affect its interpretation. New item identifiers are allocated as needed from the beginning of the unallocated space. The number of item identifiers present can be determined by looking at `pd_lower`, which is increased to allocate a new identifier. Because an item identifier is never moved until it is freed, its index may be used on a long-term basis to reference an item, even when the item itself is moved around on the page to compact free space. In fact, every pointer to an item (`ItemPointer`, also known as `CTID`) created by PostgreSQL consists of a page number and the index of an item identifier.

The items themselves are stored in space allocated backwards from the end of unallocated space. The exact structure varies depending on what the table is to contain. Tables and sequences both use a structure named `HeapTupleHeaderData`, described below.

The final section is the "special section" which may contain anything the access method wishes to store. Ordinary tables do not use this at all (indicated by setting `pd_special` to equal the pagesize).

All table tuples are structured the same way. There is a fixed-size header (occupying 23 bytes on most machines), followed by an optional null bitmap, an optional object ID field, and the user data. The header is detailed in Table 7.3, “HeapTupleHeaderData Layout”. The actual user data (fields of the tuple) begins at the offset indicated by `t_hoff`, which must always be a multiple of the MAXALIGN distance for the platform. The null bitmap is only present if the *HEAP_HASNULL* bit is set in `t_infomask`. If it is present it begins just after the fixed header and occupies enough bytes to have one bit per data column (that is, `t_natts` bits altogether). In this list of bits, a 1 bit indicates not-null, a 0 bit is a null. When the bitmap is not present, all columns are assumed not-null. The object ID is only present if the *HEAP_HASOID* bit is set in `t_infomask`. If present, it appears just before the `t_hoff` boundary. Any padding needed to make `t_hoff` a MAXALIGN multiple will appear between the null bitmap and the object ID. (This in turn ensures that the object ID is suitably aligned.)

Table 7.3. HeapTupleHeaderData Layout

Field	Type	Length	Description
t_xmin	TransactionId	4 bytes	insert XID stamp
t_cmin	CommandId	4 bytes	insert CID stamp (overlays with t_xmax)
t_xmax	TransactionId	4 bytes	delete XID stamp
t_cmax	CommandId	4 bytes	delete CID stamp (overlays with t_xvac)
t_xvac	TransactionId	4 bytes	XID for VACUUM operation moving tuple
t_ctid	ItemPointerData	6 bytes	current TID of this or newer tuple
t_natts	int16	2 bytes	number of attributes
t_infomask	uint16	2 bytes	various flags
t_hoff	uint8	1 byte	offset to user data

All the details may be found in src/include/access/htup.h.

Interpreting the actual data can only be done with information obtained from other tables, mostly *pg_attribute*. The particular fields are `attlen` and `attalign`. There is no way to directly get a particular attribute, except when there are only fixed width fields and no NULLs. All this trickery is wrapped up in the functions *heap_getattr*, *fastgetattr* and *heap_getsysattr*.

To read the data you need to examine each attribute in turn. First check whether the field is NULL according to the null bitmap. If it is, go to the next. Then make sure you have the right alignment. If the field is a fixed width field, then all the bytes are simply placed. If it's a variable length field (attlen == -1) then it's a bit more complicated, using the variable length structure `varattrib`. Depending on the flags, the data may be either inline, compressed or in another table (TOAST).

Chapter 8. Genetic Query Optimization

Martin Utesch, University of Mining and Technology

Author

Written by Martin Utesch (<utesch@aut.tu-freiberg.de>) for the Institute of Automatic Control at the University of Mining and Technology in Freiberg, Germany.

8.1. Query Handling as a Complex Optimization Problem

Among all relational operators the most difficult one to process and optimize is the *join*. The number of alternative plans to answer a query grows exponentially with the number of joins included in it. Further optimization effort is caused by the support of a variety of *join methods* (e.g., nested loop, hash join, merge join in PostgreSQL) to process individual joins and a diversity of *indexes* (e.g., R-tree, B-tree, hash in PostgreSQL) as access paths for relations.

The current PostgreSQL optimizer implementation performs a *near-exhaustive search* over the space of alternative strategies. This query optimization technique is inadequate to support database application domains that involve the need for extensive queries, such as artificial intelligence.

The Institute of Automatic Control at the University of Mining and Technology, in Freiberg, Germany, encountered the described problems as its folks wanted to take the PostgreSQL DBMS as the backend for a decision support knowledge based system for the maintenance of an electrical power grid. The DBMS needed to handle large join queries for the inference machine of the knowledge based system.

Performance difficulties in exploring the space of possible query plans created the demand for a new optimization technique being developed.

In the following we propose the implementation of a *Genetic Algorithm* as an option for the database query optimization problem.

8.2. Genetic Algorithms

The genetic algorithm (GA) is a heuristic optimization method which operates through determined, randomized search. The set of possible solutions for the optimization problem is considered as a *population* of *individuals*. The degree of adaptation of an individual to its environment is specified by its *fitness*.

The coordinates of an individual in the search space are represented by *chromosomes*, in essence a set of character strings. A *gene* is a subsection of a chromosome which encodes the value of a single parameter being optimized. Typical encodings for a gene could be *binary* or *integer*.

Through simulation of the evolutionary operations *recombination*, *mutation*, and *selection* new generations of search points are found that show a higher average fitness than their ancestors.

According to the comp.ai.genetic FAQ it cannot be stressed too strongly that a GA is not a pure random search for a solution to a problem. A GA uses stochastic processes, but the result is distinctly non-random (better than random).

Figure 8.1. Structured Diagram of a Genetic Algorithm

P(t)	generation of ancestors at a time t
P"(t)	generation of descendants at a time t



8.3. Genetic Query Optimization (GEQO) in PostgreSQL

The GEQO module is intended for the solution of the query optimization problem similar to a traveling salesman problem (TSP). Possible query plans are encoded as integer strings. Each string represents the join order from one relation of the query to the next. E. g., the query tree

```
   /\
  /\ 2
 /\ 3
4  1
```

is encoded by the integer string '4-1-3-2', which means, first join relation '4' and '1', then '3', and then '2', where 1, 2, 3, 4 are relation IDs within the PostgreSQL optimizer.

Parts of the GEQO module are adapted from D. Whitley's Genitor algorithm.

Specific characteristics of the GEQO implementation in PostgreSQL are:

- Usage of a *steady state* GA (replacement of the least fit individuals in a population, not whole-generational replacement) allows fast convergence towards improved query plans. This is essential for query handling with reasonable time;
- Usage of *edge recombination crossover* which is especially suited to keep edge losses low for the solution of the TSP by means of a GA;
- Mutation as genetic operator is deprecated so that no repair mechanisms are needed to generate legal TSP tours.

The GEQO module allows the PostgreSQL query optimizer to support large join queries effectively through non-exhaustive search.

8.3.1. Future Implementation Tasks for PostgreSQL GEQO

Work is still needed to improve the genetic algorithm parameter settings. In file `backend/optimizer/geqo/geqo_params.c`, routines `gimme_pool_size` and `gimme_number_generations`, we have to find a compromise for the parameter settings to satisfy two competing demands:

- Optimality of the query plan
- Computing time

8.4. Further Readings

The following resources contain additional information about genetic algorithms:

- The Hitch-Hiker's Guide to Evolutionary Computation[1] (FAQ for comp.ai.genetic[2])
- Evolutionary Computation and its application to art and design[3] by Craig Reynolds
- [elma99]
- [fong]

[1] http://surf.de.uu.net/encore/www/
[2] news://comp.ai.genetic
[3] http://www.red3d.com/cwr/evolve.html

Chapter 9. GiST Indexes

Gene Selkov

The information about GIST is at http://GiST.CS.Berkeley.EDU:8000/gist/ with more on different indexing and sorting schemes at http://s2k-ftp.CS.Berkeley.EDU:8000/personal/jmh/. And there is more interesting reading at http://epoch.cs.berkeley.edu:8000/ and http://www.sai.msu.su/~megera/postgres/gist/.

Author

This extraction from an email sent by Eugene Selkov, Jr. (<selkovjr@mcs.anl.gov>) contains good information on GiST. Hopefully we will learn more in the future and update this information. - thomas 1998-03-01

Well, I can't say I quite understand what's going on, but at least I (almost) succeeded in porting GiST examples to linux. The GiST access method is already in the postgres tree (`src/backend/access/gist`).

Examples at Berkeley[1] come with an overview of the methods and demonstrate spatial index mechanisms for 2D boxes, polygons, integer intervals and text (see also GiST at Berkeley[2]). In the box example, we are supposed to see a performance gain when using the GiST index; it did work for me but I do not have a reasonably large collection of boxes to check that. Other examples also worked, except polygons: I got an error doing

```
test=> CREATE INDEX pix ON polytmp
test-> USING GIST (p:box gist_poly_ops) WITH (ISLOSSY);
ERROR:  cannot open pix

(PostgreSQL 6.3              Sun Feb  1 14:57:30 EST 1998)
```

I could not get sense of this error message; it appears to be something we'd rather ask the developers about (see also Note 4 below). What I would suggest here is that someone of you linux guys (linux==gcc?) fetch the original sources quoted above and apply my patch (see attachment) and tell us what you feel about it. Looks cool to me, but I would not like to hold it up while there are so many competent people around.

A few notes on the sources:

1. I failed to make use of the original (HP-UX) Makefile and rearranged the Makefile from the ancient postgres95 tutorial to do the job. I tried to keep it generic, but I am a very poor makefile writer -- just did some monkey work. Sorry about that, but I guess it is now a little more portable that the original makefile.

2. I built the example sources right under pgsql/src (just extracted the tar file there). The aforementioned Makefile assumes it is one level below pgsql/src (in our case, in pgsql/src/pggist).

3. The changes I made to the *.c files were all about #include's, function prototypes and typecasting. Other than that, I just threw away a bunch of unused vars and added a couple parentheses to please gcc. I hope I did not screw up too much :)

4. There is a comment in polyproc.sql:

```
-- -- there's a memory leak in rtree poly_ops!!
-- -- CREATE INDEX pix2 ON polytmp USING RTREE (p poly_ops);
```

[1] ftp://s2k-ftp.cs.berkeley.edu/pub/gist/pggist/pggist.tgz
[2] http://gist.cs.berkeley.edu:8000/gist/

Roger that!! I thought it could be related to a number of PostgreSQL versions back and tried the query. My system went nuts and I had to shoot down the postmaster in about ten minutes.

I will continue to look into GiST for a while, but I would also appreciate more examples of R-tree usage.

Chapter 10. Native Language Support

Peter Eisentraut

10.1. For the Translator

PostgreSQL programs (server and client) can issue their messages in your favorite language -- if the messages have been translated. Creating and maintaining translated message sets needs the help of people who speak their own language well and want to contribute to the PostgreSQL effort. You do not have to be a programmer at all to do this. This section explains how to help.

10.1.1. Requirements

We won't judge your language skills -- this section is about software tools. Theoretically, you only need a text editor. But this is only in the unlikely event that you do not want to try out your translated messages. When you configure your source tree, be sure to use the `--enable-nls` option. This will also check for the libintl library and the `msgfmt` program, which all end users will need anyway. To try out your work, follow the applicable portions of the installation instructions.

If you want to start a new translation effort or want to do a message catalog merge (described later), you will need the programs `xgettext` and `msgmerge`, respectively, in a GNU-compatible implementation. Later, we will try to arrange it so that if you use a packaged source distribution, you won't need `xgettext`. (From CVS, you will still need it.) GNU gettext 0.10.36 or later is currently recommended.

Your local gettext implementation should come with its own documentation. Some of that is probably duplicated in what follows, but for additional details you should look there.

10.1.2. Concepts

The pairs of original (English) messages and their (possibly) translated equivalents are kept in *message catalogs*, one for each program (although related programs can share a message catalog) and for each target language. There are two file formats for message catalogs: The first is the “PO” file (for Portable Object), which is a plain text file with special syntax that translators edit. The second is the “MO” file (for Machine Object), which is a binary file generated from the respective PO file and is used while the internationalized program is run. Translators do not deal with MO files; in fact hardly anyone does.

The extension of the message catalog file is to no surprise either `.po` or `.mo`. The base name is either the name of the program it accompanies, or the language the file is for, depending on the situation. This is a bit confusing. Examples are `psql.po` (PO file for psql) or `fr.mo` (MO file in French).

The file format of the PO files is illustrated here:

```
# comment

msgid "original string"
msgstr "translated string"

msgid "more original"
msgstr "another translated"
"string can be broken up like this"

...
```

The msgid's are extracted from the program source. (They need not be, but this is the most common way.) The msgstr lines are initially empty and are filled in with useful strings by the translator. The

strings can contain C-style escape characters and can be continued across lines as illustrated. (The next line must start at the beginning of the line.)

The # character introduces a comment. If whitespace immediately follows the # character, then this is a comment maintained by the translator. There may also be automatic comments, which have a non-whitespace character immediately following the #. These are maintained by the various tools that operate on the PO files and are intended to aid the translator.

```
#. automatic comment
#: filename.c:1023
#, flags, flags
```

The #. style comments are extracted from the source file where the message is used. Possibly the programmer has inserted information for the translator, such as about expected alignment. The #: comment indicates the exact location(s) where the message is used in the source. The translator need not look at the program source, but he can if there is doubt about the correct translation. The #, comments contain flags that describe the message in some way. There are currently two flags: `fuzzy` is set if the message has possibly been outdated because of changes in the program source. The translator can then verify this and possibly remove the fuzzy flag. Note that fuzzy messages are not made available to the end user. The other flag is `c-format`, which indicates that the message is a `printf`-style format template. This means that the translation should also be a format string with the same number and type of placeholders. There are tools that can verify this, which key off the c-format flag.

10.1.3. Creating and maintaining message catalogs

OK, so how does one create a “blank” message catalog? First, go into the directory that contains the program whose messages you want to translate. If there is a file `nls.mk`, then this program has been prepared for translation.

If there are already some `.po` files, then someone has already done some translation work. The files are named *`language`*`.po`, where *`language`* is the ISO 639-1[1] two-letter language code (in lower case), e.g., `fr.po` for French. If there is really a need for more than one translation effort per language then the files may also be named *`language_region`*`.po` where *`region`* is the ISO 3166-1[2] two-letter country code (in upper case), e.g., `pt_BR.po` for Portuguese in Brazil. If you find the language you wanted you can just start working on that file.

If you need to start a new translation effort, then first run the command

```
gmake init-po
```

This will create a file *`progname`*`.pot`. (`.pot` to distinguish it from PO files that are “in production”. The `T` stands for “template”.) Copy this file to *`language`*`.po` and edit it. To make it known that the new language is available, also edit the file `nls.mk` and add the language (or language and country) code to the line that looks like:

```
AVAIL_LANGUAGES := de fr
```

(Other languages may appear, of course.)

As the underlying program or library changes, messages may be changed or added by the programmers. In this case you do not need to start from scratch. Instead, run the command

```
gmake update-po
```

which will create a new blank message catalog file (the pot file you started with) and will merge it with the existing PO files. If the merge algorithm is not sure about a particular message it marks it

[1] http://lcweb.loc.gov/standards/iso639-2/englangn.html
[2] http://www.din.de/gremien/nas/nabd/iso3166ma/codlstp1/en_listp1.html

"fuzzy" as explained above. For the case where something went really wrong, the old PO file is saved with a `.po.old` extension.

10.1.4. Editing the PO files

The PO files can be edited with a regular text editor. The translator should only change the area between the quotes after the msgstr directive, may add comments and alter the fuzzy flag. There is (unsurprisingly) a PO mode for Emacs, which I find quite useful.

The PO files need not be completely filled in. The software will automatically fall back to the original string if no translation (or an empty translation) is available. It is no problem to submit incomplete translations for inclusions in the source tree; that gives room for other people to pick up your work. However, you are encouraged to give priority to removing fuzzy entries after doing a merge. Remember that fuzzy entries will not be installed; they only serve as reference what might be the right translation.

Here are some things to keep in mind while editing the translations:

- Make sure that if the original ends with a newline, the translation does, too. Similarly for tabs, etc.
- If the original is a printf format string, the translation also needs to be. The translation also needs to have the same format specifiers in the same order. Sometimes the natural rules of the language make this impossible or at least awkward. In this case you can use this format:

  ```
  msgstr "Die Datei %2$s hat %1$u Zeichen."
  ```

  Then the first placeholder will actually use the second argument from the list. The *`digits`*`$` needs to follow the % and come before any other format manipulators. (This feature really exists in the `printf` family of functions. You may not have heard of it because there is little use for it outside of message internationalization.)
- If the original string contains a linguistic mistake, report that (or fix it yourself in the program source) and translate normally. The corrected string can be merged in when the program sources have been updated. If the original string contains a factual mistake, report that (or fix it yourself) and do not translate it. Instead, you may mark the string with a comment in the PO file.
- Maintain the style and tone of the original string. Specifically, messages that are not sentences (`cannot open file %s`) should probably not start with a capital letter (if your language distinguishes letter case) or end with a period (if your language uses punctuation marks).
- If you don't know what a message means, or if it is ambiguous, ask on the developers' mailing list. Chances are that English speaking end users might also not understand it or find it ambiguous, so it's best to improve the message.

10.2. For the Programmer

This section describes how to support native language support in a program or library that is part of the PostgreSQL distribution. Currently, it only applies to C programs.

Adding NLS support to a program

1. Insert this code into the start-up sequence of the program:

   ```
   #ifdef ENABLE_NLS
   #include <locale.h>
   #endif

   ...
   ```

```
#ifdef ENABLE_NLS
setlocale(LC_ALL, "");
bindtextdomain("progname", LOCALEDIR);
textdomain("progname");
#endif
```

(The *progname* can actually be chosen freely.)

2. Wherever a message that is a candidate for translation is found, a call to `gettext()` needs to be inserted. E.g.,

   ```
   fprintf(stderr, "panic level %d\n", lvl);
   ```

   would be changed to

   ```
   fprintf(stderr, gettext("panic level %d\n"), lvl);
   ```

   (`gettext` is defined as a no-op if no NLS is configured.)

   This may tend to add a lot of clutter. One common shortcut is to

   ```
   #define _(x) gettext((x))
   ```

   Another solution is feasible if the program does much of its communication through one or a few functions, such as `elog()` in the backend. Then you make this function call `gettext` internally on all input values.

3. Add a file `nls.mk` in the directory with the program sources. This file will be read as a makefile. The following variable assignments need to be made here:

   CATALOG_NAME

   The program name, as provided in the `textdomain()` call.

   AVAIL_LANGUAGES

   List of provided translations -- empty in the beginning.

   GETTEXT_FILES

   List of files that contain translatable strings, i.e., those marked with `gettext` or an alternative solution. Eventually, this will include nearly all source files of the program. If this list gets too long you can make the first “file” be a + and the second word be a file that contains one file name per line.

   GETTEXT_TRIGGERS

   The tools that generate message catalogs for the translators to work on need to know what function calls contain translatable strings. By default, only `gettext()` calls are known. If you used _ or other identifiers you need to list them here. If the translatable string is not the first argument, the item needs to be of the form `func:2` (for the second argument).

The build system will automatically take care of building and installing the message catalogs.

To ease the translation of messages, here are some guidelines:

- Do not construct sentences at run-time out of laziness, like

  ```
  printf("Files where %s.\n", flag ? "copied" : "removed");
  ```

  The word order within the sentence may be different in other languages.

- For similar reasons, this won't work:

  ```
  printf("copied %d file%s", n, n!=1 ? "s" : "");
  ```

  because it assumes how the plural is formed. If you figured you could solve it like this

  ```
  if (n==1)
      printf("copied 1 file");
  else
      printf("copied %d files", n):
  ```

  then be disappointed. Some languages have more than two forms, with some peculiar rules. We may have a solution for this in the future, but for now this is best avoided altogether. You could write:

  ```
  printf("number of copied files: %d", n);
  ```

- If you want to communicate something to the translator, such as about how a message is intended to line up with other output, precede the occurrence of the string with a comment that starts with `translator`, e.g.,

  ```
  /* translator: This message is not what it seems to be. */
  ```

  These comments are copied to the message catalog files so that the translators can see them.

Appendix A. The CVS Repository

Marc Fournier
Tom Lane
Thomas Lockhart

The PostgreSQL source code is stored and managed using the CVS code management system.

At least two methods, anonymous CVS and CVSup, are available to pull the CVS code tree from the PostgreSQL server to your local machine.

A.1. Getting The Source Via Anonymous CVS

If you would like to keep up with the current sources on a regular basis, you can fetch them from our CVS server and then use CVS to retrieve updates from time to time.

Anonymous CVS

1. You will need a local copy of CVS (Concurrent Version Control System), which you can get from http://www.cyclic.com/ or any GNU software archive site. We currently recommend version 1.10 (the most recent at the time of writing). Many systems have a recent version of cvs installed by default.

2. Do an initial login to the CVS server:

   ```
   $ cvs -d :pserver:anoncvs@anoncvs.postgresql.org:/projects/
   cvsroot login
   ```

   You will be prompted for a password; just press `ENTER`. You should only need to do this once, since the password will be saved in `.cvspass` in your home directory.

3. Fetch the PostgreSQL sources:

   ```
   cvs -z3 -d :pserver:anoncvs@anoncvs.postgresql.org:/projects/
   cvsroot co -P pgsql
   ```

   which installs the PostgreSQL sources into a subdirectory `pgsql` of the directory you are currently in.

   > **Note**
   >
   > If you have a fast link to the Internet, you may not need `-z3`, which instructs CVS to use gzip compression for transferred data. But on a modem-speed link, it's a very substantial win.

   This initial checkout is a little slower than simply downloading a `tar.gz` file; expect it to take 40 minutes or so if you have a 28.8K modem. The advantage of CVS doesn't show up until you want to update the file set later on.

4. Whenever you want to update to the latest CVS sources, `cd` into the `pgsql` subdirectory, and issue

   ```
   $ cvs -z3 update -d -P
   ```

   This will fetch only the changes since the last time you updated. You can update in just a couple of minutes, typically, even over a modem-speed line.

5. You can save yourself some typing by making a file `.cvsrc` in your home directory that contains

```
cvs -z3
update -d -P
```

This supplies the `-z3` option to all cvs commands, and the `-d` and `-P` options to cvs update. Then you just have to say

```
$ cvs update
```

to update your files.

Caution

Some older versions of CVS have a bug that causes all checked-out files to be stored world-writable in your directory. If you see that this has happened, you can do something like

```
$ chmod -R go-w pgsql
```

to set the permissions properly. This bug is fixed as of CVS version 1.9.28.

CVS can do a lot of other things, such as fetching prior revisions of the PostgreSQL sources rather than the latest development version. For more info consult the manual that comes with CVS, or see the online documentation at http://www.cyclic.com/.

A.2. CVS Tree Organization

Author

Written by Marc G. Fournier (<scrappy@hub.org>) on 1998-11-05

The command `cvs checkout` has a flag, `-r`, that lets you check out a certain revision of a module. This flag makes it easy to, for example, retrieve the sources that make up release 6_4 of the module `tc' at any time in the future:

```
$ cvs checkout -r REL6_4 tc
```

This is useful, for instance, if someone claims that there is a bug in that release, but you cannot find the bug in the current working copy.

Tip

You can also check out a module as it was at any given date using the `-D` option.

When you tag more than one file with the same tag you can think about the tag as “a curve drawn through a matrix of filename vs. revision number”. Say we have 5 files with the following revisions:

```
file1   file2   file3   file4   file5

1.1     1.1     1.1     1.1  /--1.1*      <-*-  TAG
1.2*-   1.2     1.2    -1.2*-
1.3  \- 1.3*-   1.3   / 1.3
1.4          \  1.4  /  1.4
              \-1.5*-   1.5
                1.6
```

then the tag `TAG` will reference file1-1.2, file2-1.3, etc.

Note

For creating a release branch, other then a -b option added to the command, it's the same thing.

So, to create the 6.4 release I did the following:

```
$ cd pgsql
$ cvs tag -b REL6_4
```

which will create the tag and the branch for the RELEASE tree.

For those with CVS access, it's simple to create directories for different versions. First, create two subdirectories, RELEASE and CURRENT, so that you don't mix up the two. Then do:

```
cd RELEASE
cvs checkout -P -r REL6_4 pgsql
cd ../CURRENT
cvs checkout -P pgsql
```

which results in two directory trees, `RELEASE/pgsql` and `CURRENT/pgsql`. From that point on, CVS will keep track of which repository branch is in which directory tree, and will allow independent updates of either tree.

If you are *only* working on the `CURRENT` source tree, you just do everything as before we started tagging release branches.

After you've done the initial checkout on a branch

```
$ cvs checkout -r REL6_4
```

anything you do within that directory structure is restricted to that branch. If you apply a patch to that directory structure and do a

```
cvs commit
```

while inside of it, the patch is applied to the branch and *only* the branch.

A.3. Getting The Source Via CVSup

An alternative to using anonymous CVS for retrieving the PostgreSQL source tree is CVSup. CVSup was developed by John Polstra (<jdp@polstra.com>) to distribute CVS repositories and other file trees for the FreeBSD project[1].

A major advantage to using CVSup is that it can reliably replicate the *entire* CVS repository on your local system, allowing fast local access to cvs operations such as `log` and `diff`. Other advantages include fast synchronization to the PostgreSQL server due to an efficient streaming transfer protocol which only sends the changes since the last update.

A.3.1. Preparing A CVSup Client System

Two directory areas are required for CVSup to do it's job: a local CVS repository (or simply a directory area if you are fetching a snapshot rather than a repository; see below) and a local CVSup bookkeeping area. These can coexist in the same directory tree.

[1] http://www.freebsd.org

Decide where you want to keep your local copy of the CVS repository. On one of our systems we recently set up a repository in `/home/cvs/`, but had formerly kept it under a PostgreSQL development tree in `/opt/postgres/cvs/`. If you intend to keep your repository in `/home/cvs/`, then put

```
setenv CVSROOT /home/cvs
```

in your `.cshrc` file, or a similar line in your `.bashrc` or `.profile` file, depending on your shell.

The cvs repository area must be initialized. Once `CVSROOT` is set, then this can be done with a single command:

```
$ cvs init
```

after which you should see at least a directory named `CVSROOT` when listing the `CVSROOT` directory:

```
$ ls $CVSROOT
CVSROOT/
```

A.3.2. Running a CVSup Client

Verify that cvsup is in your path; on most systems you can do this by typing

```
which cvsup
```

Then, simply run cvsup using:

```
$ cvsup -L 2 postgres.cvsup
```

where `-L 2` enables some status messages so you can monitor the progress of the update, and *`postgres.cvsup`* is the path and name you have given to your CVSup configuration file.

Here is a CVSup configuration file modified for a specific installation, and which maintains a full local CVS repository:

```
# This file represents the standard CVSup distribution file
# for the PostgreSQL ORDBMS project
# Modified by lockhart@fourpalms.org 1997-08-28
# - Point to my local snapshot source tree
# - Pull the full CVS repository, not just the latest snapshot
#
# Defaults that apply to all the collections
*default host=cvsup.postgresql.org
*default compress
*default release=cvs
*default delete use-rel-suffix
# enable the following line to get the latest snapshot
#*default tag=.
# enable the following line to get whatever was specified above or
 by default
# at the date specified below
#*default date=97.08.29.00.00.00

# base directory where CVSup will store its 'bookmarks' file(s)
# will create subdirectory sup/
#*default base=/opt/postgres # /usr/local/pgsql
```

```
*default base=/home/cvs

# prefix directory where CVSup will store the actual
 distribution(s)
*default prefix=/home/cvs

# complete distribution, including all below
pgsql

# individual distributions vs 'the whole thing'
# pgsql-doc
# pgsql-perl5
# pgsql-src
```

The following is a suggested CVSup config file from the PostgreSQL ftp site[2] which will fetch the current snapshot only:

```
# This file represents the standard CVSup distribution file
# for the PostgreSQL ORDBMS project
#
# Defaults that apply to all the collections
*default host=cvsup.postgresql.org
*default compress
*default release=cvs
*default delete use-rel-suffix
*default tag=.

# base directory where CVSup will store its 'bookmarks' file(s)
*default base=/usr/local/pgsql

# prefix directory where CVSup will store the actual
 distribution(s)
*default prefix=/usr/local/pgsql

# complete distribution, including all below
pgsql

# individual distributions vs 'the whole thing'
# pgsql-doc
# pgsql-perl5
# pgsql-src
```

A.3.3. Installing CVSup

CVSup is available as source, pre-built binaries, or Linux RPMs. It is far easier to use a binary than to build from source, primarily because the very capable, but voluminous, Modula-3 compiler is required for the build.

CVSup Installation from Binaries

You can use pre-built binaries if you have a platform for which binaries are posted on the PostgreSQL ftp site[3], or if you are running FreeBSD, for which CVSup is available as a port.

[2] ftp://ftp.postgresql.org/pub/CVSup/README.cvsup
[3] ftp://ftp.postgresql.org/pub

Note

CVSup was originally developed as a tool for distributing the FreeBSD source tree. It is available as a "port", and for those running FreeBSD, if this is not sufficient to tell how to obtain and install it then please contribute a procedure here.

At the time of writing, binaries are available for Alpha/Tru64, ix86/xBSD, HPPA/HP-UX 10.20, MIPS/IRIX, ix86/linux-libc5, ix86/linux-glibc, Sparc/Solaris, and Sparc/SunOS.

1. Retrieve the binary tar file for cvsup (cvsupd is not required to be a client) appropriate for your platform.

   a. (Optional) If you are running FreeBSD, install the CVSup port.

   b. (Optional) If you have another platform, check for and download the appropriate binary from the PostgreSQL ftp site[4].

2. Check the tar file to verify the contents and directory structure, if any. For the linux tar file at least, the static binary and man page is included without any directory packaging.

   a. If the binary is in the top level of the tar file, then simply unpack the tar file into your target directory:

   ```
   $ cd /usr/local/bin
   $ tar zxvf /usr/local/src/cvsup-16.0-linux-i386.tar.gz
   $ mv cvsup.1 ../doc/man/man1/
   ```

   b. If there is a directory structure in the tar file, then unpack the tar file within /usr/local/src and move the binaries into the appropriate location as above.

3. Ensure that the new binaries are in your path.

   ```
   $ rehash
   $ which cvsup
   $ set path=(path to cvsup $path)
   $ which cvsup
   /usr/local/bin/cvsup
   ```

A.3.4. Installation from Sources

Installing CVSup from sources is not entirely trivial, primarily because most systems will need to install a Modula-3 compiler first. This compiler is available as Linux RPM, FreeBSD package, or source code.

Note

A clean-source installation of Modula-3 takes roughly 200MB of disk space, which shrinks to roughly 50MB of space when the sources are removed.

Linux installation

1. Install Modula-3.

   a. Pick up the Modula-3 distribution from Polytechnique Montréal[5], who are actively maintaining the code base originally developed by the DEC Systems Research Center[6]. The

[4] ftp://ftp.postgresql.org/pub
[5] http://m3.polymtl.ca/m3
[6] http://www.research.digital.com/SRC/modula-3/html/home.html

PM3 RPM distribution is roughly 30MB compressed. At the time of writing, the 1.1.10-1 release installed cleanly on RH-5.2, whereas the 1.1.11-1 release is apparently built for another release (RH-6.0?) and does not run on RH-5.2.

Tip

This particular rpm packaging has *many* RPM files, so you will likely want to place them into a separate directory.

b. Install the Modula-3 rpms:

```
# rpm -Uvh pm3*.rpm
```

2. Unpack the cvsup distribution:

```
# cd /usr/local/src
# tar zxf cvsup-16.0.tar.gz
```

3. Build the cvsup distribution, suppressing the GUI interface feature to avoid requiring X11 libraries:

```
# make M3FLAGS="-DNOGUI"
```

and if you want to build a static binary to move to systems that may not have Modula-3 installed, try:

```
# make M3FLAGS="-DNOGUI -DSTATIC"
```

4. Install the built binary:

```
# make M3FLAGS="-DNOGUI -DSTATIC" install
```

Appendix B. Documentation

PostgreSQL has four primary documentation formats:

- Plain text, for pre-installation information
- HTML, for on-line browsing and reference
- Postscript, for printing
- man pages, for quick reference.

Additionally, a number of plain-text README-type files can be found throughout the PostgreSQL source tree, documenting various implementation issues.

The documentation is organized into several “books”:

- *Tutorial*: introduction for new users
- *User's Guide*: documents the SQL implementation
- *Reference Manual*: reference pages for programs and SQL commands
- *Administrator's Guide*: installation and server maintenance
- *Programmer's Guide*: programming client applications and server extensions
- *Developer's Guide*: assorted information for developers of PostgreSQL proper

All books are available as HTML and Postscript. The *Reference Manual* contains reference entries which are also shipped as man pages.

HTML documentation and man pages are part of a standard distribution and are installed by default. Postscript format documentation is available separately for download.

B.1. DocBook

The documentation sources are written in *DocBook*, which is a markup language superficially similar to HTML. Both of these languages are applications of the *Standard Generalized Markup Language*, SGML, which is essentially a language for describing other languages. In what follows, the terms DocBook and SGML are both used, but technically they are not interchangeable.

DocBook allows an author to specify the structure and content of a technical document without worrying about presentation details. A document style defines how that content is rendered into one of several final forms. DocBook is maintained by the OASIS[1] group. The official DocBook site[2] has good introductory and reference documentation and a complete O'Reilly book for your online reading pleasure. The FreeBSD Documentation Project[3] also uses DocBook and has some good information, including a number of style guidelines that might be worth considering.

B.2. Tool Sets

The following tools are used to process the documentation. Some may be optional, as noted.

[1] http://www.oasis-open.org
[2] http://www.oasis-open.org/docbook
[3] http://www.freebsd.org/docproj/docproj.html

DocBook DTD[4]

This is the definition of DocBook itself. We currently use version 3.1; you cannot use later or earlier versions. Note that there is also an XML version of DocBook -- do not use that.

ISO 8879 character entities[5]

These are required by DocBook but are distributed separately because they are maintained by ISO.

OpenJade[6]

This is the base package of SGML processing. It contains an SGML parser, a DSSSL processor (that is, a program to convert SGML to other formats using DSSSL stylesheets), as well as a number of related tools. Jade is now being maintained by the OpenJade group, no longer by James Clark.

DocBook DSSSL Stylesheets[7]

These contain the processing instructions for converting the DocBook sources to other formats, such as HTML.

DocBook2X tools[8]

This optional package is used to create man pages. It has a number of prerequisite packages of its own. Check the web site.

JadeTeX[9]

If you want to, you can also install JadeTeX to use TeX as a formatting backend for Jade. JadeTeX can create Postscript or PDF files (the latter with bookmarks).

However, the output from JadeTeX is inferior to what you get from the RTF backend. Particular problem areas are tables and various artifacts of vertical and horizontal spacing. Also, there is no opportunity to manually polish the results.

We have documented experience with several installation methods for the various tools that are needed to process the documentation. These will be described below. There may be some other packaged distributions for these tools. Please report package status to the docs mailing list and we will include that information here.

B.2.1. Linux RPM Installation

Many vendors provide a complete RPM set for DocBook processing in their distribution, which is usually based on the docbook-tools[10] effort at Red Hat Software. Look for an “SGML” option while installing, or the following packages: `sgml-common`, `docbook`, `stylesheets`, `openjade` (or `jade`). Possibly `sgml-tools` will be needed as well. If your distributor does not provide these then you should be able to make use of the packages from some other, reasonably compatible vendor.

B.2.2. FreeBSD Installation

The FreeBSD Documentation Project is itself a heavy user of DocBook, so it comes as no surprise that there is a full set of “ports” of the documentation tools available on FreeBSD. The following ports need to be installed to build the documentation on FreeBSD.

[4] http://www.oasis-open.org/docbook/sgml/
[5] http://www.oasis-open.org/cover/ISOEnts.zip
[6] http://openjade.sourceforge.net
[7] http://docbook.sourceforge.net/projects/dsssl/index.html
[8] http://docbook2x.sourceforge.net
[9] http://jadetex.sourceforge.net
[10] http://sources.redhat.com/docbook-tools/

- textproc/sp
- textproc/openjade
- textproc/docbook-310
- textproc/iso8879
- textproc/dsssl-docbook-modular

A number of things from /usr/ports/print (tex, jadetex) might also be of interest.

It's possible that the ports do not update the main catalog file in /usr/local/share/sgml/catalog. Be sure to have the following line in there:

```
CATALOG "/usr/local/share/sgml/docbook/3.1/catalog"
```

If you do not want to edit the file you can also set the environment variable SGML_CATALOG_FILES to a colon-separated list of catalog files (such as the one above).

More information about the FreeBSD documentation tools can be found in the FreeBSD Documentation Project's instructions[11].

B.2.3. Debian Packages

There is a full set of packages of the documentation tools available for Debian GNU/Linux. To install, simply use:

```
apt-get install jade
apt-get install docbook
apt-get install docbook-stylesheets
```

B.2.4. Manual Installation from Source

The manual installation process of the DocBook tools is somewhat complex, so if you have pre-built packages available, use them. We describe here only a standard setup, with reasonably standard installation paths, and no “fancy” features. For details, you should study the documentation of the respective package, and read SGML introductory material.

B.2.4.1. Installing OpenJade

1. The installation of OpenJade offers a GNU-style ./configure; make; make install build process. Details can be found in the OpenJade source distribution. In a nutshell:

   ```
   ./configure --enable-default-catalog=/usr/local/share/sgml/
   catalog
   make
   make install
   ```

   Be sure to remember where you put the “default catalog”; you will need it below. You can also leave it off, but then you will have to set the environment variable SGML_CATALOG_FILES to point to the file whenever you use jade later on. (This method is also an option if OpenJade is already installed and you want to install the rest of the toolchain locally.)

2. Additionally, you should install the files dsssl.dtd, fot.dtd, style-sheet.dtd, and catalog from the dsssl directory somewhere, perhaps into /usr/local/share/sgml/dsssl. It's probably easiest to copy the entire directory:

[11] http://www.freebsd.org/doc/en_US.ISO8859-1/books/fdp-primer/tools.html

```
cp -R dsssl /usr/local/share/sgml
```

3. Finally, create the file `/usr/local/share/sgml/catalog` and add this line to it:

   ```
   CATALOG "dsssl/catalog"
   ```

   (This is a relative path reference to the file installed in Step 2. Be sure to adjust it if you chose your installation layout differently.)

B.2.4.2. Installing the DocBook DTD Kit

1. Obtain the DocBook V3.1[12] distribution.

2. Create the directory `/usr/local/share/sgml/docbook31` and change to it. (The exact location is irrelevant, but this one is reasonable within the layout we are following here.)

   ```
   $ mkdir /usr/local/share/sgml/docbook31
   $ cd /usr/local/share/sgml/docbook31
   ```

3. Unpack the archive.

   ```
   $ unzip -a ...../docbk31.zip
   ```

   (The archive will unpack its files into the current directory.)

4. Edit the file `/usr/local/share/sgml/catalog` (or whatever you told jade during installation) and put a line like this into it:

   ```
   CATALOG "docbook31/docbook.cat"
   ```

5. Optionally, you can edit the file `docbook.cat` and comment out or remove the line containing `DTDDECL`. If you do not then you will get warnings from jade, but there is no further harm.

6. Download the ISO 8879 character entities[13] archive, unpack it, and put the files in the same directory you put the DocBook files in.

   ```
   $ cd /usr/local/share/sgml/docbook31
   $ unzip ...../ISOEnts.zip
   ```

7. Run the following command in the directory with the DocBook and ISO files:

   ```
   perl -pi -e 's/iso-(.*).gml/ISO\1/g' docbook.cat
   ```

   (This fixes a mixup between the names used in the DocBook catalog file and the actual names of the ISO character entity files.)

B.2.4.3. Installing the DocBook DSSSL Style Sheets

To install the style sheets, unzip and untar the distribution and move it to a suitable place, for example `/usr/local/share/sgml`. (The archive will automatically create a subdirectory.)

```
$ gunzip docbook-dsssl-1.xx.tar.gz
$ tar -C /usr/local/share/sgml -xf docbook-dsssl-1.xx.tar
```

The usual catalog entry in `/usr/local/share/sgml/catalog` can also be made:

```
CATALOG "docbook-dsssl--1.xx/catalog
```

[12] http://www.oasis-open.org/docbook/sgml/3.1/docbk31.zip
[13] http://www.oasis-open.org/cover/ISOEnts.zip

Because stylesheets change rather often, and it's sometimes beneficial to try out alternative versions, PostgreSQL doesn't use this catalog entry. See Section B.3, “Building The Documentation” for information about how to select the stylesheets instead.

B.2.4.4. Installing JadeTeX

To install and use JadeTeX, you will need a working installation of TeX and LaTeX2e, including the supported tools and graphics packages, Babel, AMS fonts and AMS-LaTeX, the PSNFSS extension and companion kit of “the 35 fonts”, the dvips program for generating PostScript, the macro packages fancyhdr, hyperref, minitoc, url and ot2enc. All of these can be found on your friendly neighborhood CTAN[14] site. The installation of the TeX base system is far beyond the scope of this introduction. Binary packages should be available for any system that can run TeX.

Before you can use JadeTeX with the PostgreSQL documentation sources, you will need to increase the size of TeX's internal data structures. Details on this can be found in the JadeTeX installation instructions.

Once that is finished you can install JadeTeX:

```
$ gunzip jadetex-xxx.tar.gz
$ tar xf jadetex-xxx.tar
$ cd jadetex
$ make install
$ mktexlsr
```

The last two need to be done as root.

B.3. Building The Documentation

Before you can build the documentation you need to run the `configure` script as you would when building the programs themselves. Check the output near the end of the run, it should look something like this:

```
checking for onsgmls... onsgmls
checking for openjade... openjade
checking for DocBook V3.1... yes
checking for DocBook stylesheets... /usr/lib/sgml/stylesheets/
nwalsh-modular
checking for sgmlspl... sgmlspl
```

If neither `onsgmls` nor `nsgmls` were found then you will not see the remaining 4 lines. `nsgmls` is part of the Jade package. If “DocBook V3.1” was not found then you did not install the DocBook DTD kit in a place where jade can find it, or you have not set up the catalog files correctly. See the installation hints above. The DocBook stylesheets are looked for in a number of relatively standard places, but if you have them some other place then you should set the environment variable `DOCBOOKSTYLE` to the location and rerun `configure` afterwards.

Once you have everything set up, change to the directory `doc/src/sgml` and run one of the following commands: (Remember to use GNU make.)

- To build the HTML version of the *Administrator's Guide*:

  ```
  doc/src/sgml$ gmake admin.html
  ```

- For the RTF version of the same:

[14] http://www.ctan.org

```
doc/src/sgml$ gmake admin.rtf
```

- To get a DVI version via JadeTeX:

```
doc/src/sgml$ gmake admin.dvi
```

- And Postscript from the DVI:

```
doc/src/sgml$ gmake admin.ps
```

> **Note**
>
> The official Postscript format documentation is generated differently. See Section B.3.3, "Hardcopy Generation" below.

The other books can be built with analogous commands by replacing `admin` with one of `developer`, `programmer`, `tutorial`, or `user`. Using `postgres` builds an integrated version of all 5 books, which is practical since the browser interface makes it easy to move around all of the documentation by just clicking.

B.3.1. HTML

When building HTML documentation in `doc/src/sgml`, some of the resulting files will possibly (or quite certainly) have conflicting names between books. Therefore the files are not in that directory in the regular distribution. Instead, the files belonging to each book are stored in a tar archive that is unpacked at installation time. To create a set of HTML documentation packages use the commands

```
cd doc/src
gmake tutorial.tar.gz
gmake user.tar.gz
gmake admin.tar.gz
gmake programmer.tar.gz
gmake postgres.tar.gz
gmake install
```

In the distribution, these archives live in the `doc` directory and are installed by default with `gmake install`.

B.3.2. Manpages

We use the docbook2man utility to convert DocBook `REFENTRY` pages to *roff output suitable for man pages. The man pages are also distributed as a tar archive, similar to the HTML version. To create the man page package, use the commands

```
cd doc/src
gmake man
```

which will result in a tar file being generated in the `doc/src` directory.

The man build leaves a lot of confusing output, and special care must be taken to produce quality results. There is still room for improvement in this area.

B.3.3. Hardcopy Generation

The hardcopy Postscript documentation is generated by converting the SGML source code to RTF, then importing into Applixware. After a little cleanup (see the following section) the output is "printed" to a postscript file.

Several areas are addressed while generating Postscript hardcopy, including RTF repair, ToC generation, and page break adjustments.

Applixware RTF Cleanup

jade, an integral part of the hardcopy procedure, omits specifying a default style for body text. In the past, this undiagnosed problem led to a long process of Table of Contents (ToC) generation. However, with great help from the Applixware folks the symptom was diagnosed and a workaround is available.

1. Generate the RTF input by typing (for example):

   ```
   % cd doc/src/sgml
   % make tutorial.rtf
   ```

2. Repair the RTF file to correctly specify all styles, in particular the default style. If the document contains `REFENTRY` sections, one must also replace formatting hints which tie a *preceding* paragraph to the current paragraph, and instead tie the current paragraph to the following one. A utility, fixrtf is available in `doc/src/sgml` to accomplish these repairs:

   ```
   % cd doc/src/sgml
   % fixrtf tutorial.rtf
   ```

   or

   ```
   % cd doc/src/sgml
   % fixrtf --refentry reference.rtf
   ```

   The script adds `{\s0 Normal;}` as the zero-th style in the document. According to Applixware, the RTF standard would prohibit adding an implicit zero-th style, though M$Word happens to handle this case. For repairing `REFENTRY` sections, the script replaces `\keepn` tags with `\keep`.

3. Open a new document in Applixware Words and then import the RTF file.

4. Generate a new ToC using Applixware.

   a. Select the existing ToC lines, from the beginning of the first character on the first line to the last character of the last line.

   b. Build a new ToC using `Tools.BookBuilding.CreateToC`. Select the first three levels of headers for inclusion in the ToC. This will replace the existing lines imported in the RTF with a native Applixware ToC.

   c. Adjust the ToC formatting by using `Format.Style`, selecting each of the three ToC styles, and adjusting the indents for `First` and `Left`. Use the following values:

   Table B.1. Indent Formatting for Table of Contents

Style	First Indent (inches)	Left Indent (inches)
TOC-Heading 1	0.4	0.4
TOC-Heading 2	0.8	0.8
TOC-Heading 3	1.2	1.2

5. Work through the document to:

   - Adjust page breaks.

- Adjust table column widths.
- Insert figures into the document. Center each figure on the page using the centering margins button on the Applixware toolbar.

  Note

  Not all documents have figures. You can grep the SGML source files for the string `graphic` to identify those parts of the documentation that may have figures. A few figures are replicated in various parts of the documentation.

6. Replace the right-justified page numbers in the Examples and Figures portions of the ToC with correct values. This only takes a few minutes per document.
7. (Optional) Delete the index section from the document if it is empty.
8. Regenerate and adjust the table of contents.
   a. Select the ToC field.
   b. Select `Tools->Book Building->Create Table of Contents`.
   c. Unbind the ToC by selecting `Tools->Field Editing->Unprotect`.
   d. Delete the first line in the ToC, which is an entry for the ToC itself.
9. Save the document as native Applixware Words format to allow easier last minute editing later.
10. “Print” the document to a file in Postscript format.
11. Compress the Postscript file using gzip. Place the compressed file into the `doc` directory.

B.3.4. Plain Text Files

Several files are distributed as plain text, for reading during the installation process. The `INSTALL` file corresponds to the chapter in the *Administrator's Guide*, with some minor changes to account for the different context. To recreate the file, change to the directory `doc/src/sgml` and enter **`gmake INSTALL`**. This will create a file `INSTALL.html` that can be saved as text with Netscape Navigator and put into the place of the existing file. Netscape seems to offer the best quality for HTML to text conversions (over lynx and w3m).

The file `HISTORY` can be created similarly, using the command **`gmake HISTORY`**. For the file `src/test/regress/README` the command is **`gmake regress_README`**.

B.4. Documentation Authoring

SGML and DocBook do not suffer from an oversupply of open-source authoring tools. The most common tool set is the Emacs/XEmacs editor with appropriate editing mode. On some systems these tools are provided in a typical full installation.

B.4.1. Emacs/PSGML

PSGML is the most common and most powerful mode for editing SGML documents. When properly configured, it will allow you to use Emacs to insert tags and check markup consistency. You could use it for HTML as well. Check the PSGML web site[15] for downloads, installation instructions, and detailed documentation.

[15] http://www.lysator.liu.se/projects/about_psgml.html

There is one important thing to note with PSGML: its author assumed that your main SGML DTD directory would be `/usr/local/lib/sgml`. If, as in the examples in this chapter, you use `/usr/local/share/sgml`, you have to compensate for this, either by setting `SGML_CATALOG_FILES` environment variable, or you can customize your PSGML installation (its manual tells you how).

Put the following in your `~/.emacs` environment file (adjusting the path names to be appropriate for your system):

```
; ********** for SGML mode (psgml)

(setq sgml-omittag t)
(setq sgml-shorttag t)
(setq sgml-minimize-attributes nil)
(setq sgml-always-quote-attributes t)
(setq sgml-indent-step 1)
(setq sgml-indent-data t)
(setq sgml-parent-document nil)
(setq sgml-default-dtd-file "./reference.ced")
(setq sgml-exposed-tags nil)
(setq sgml-catalog-files '("/usr/local/share/sgml/catalog"))
(setq sgml-ecat-files nil)

(autoload 'sgml-mode "psgml" "Major mode to edit SGML files." t )
```

and in the same file add an entry for SGML into the (existing) definition for `auto-mode-alist`:

```
(setq
  auto-mode-alist
  '(("\\.sgml$" . sgml-mode)
   ))
```

Currently, each SGML source file has the following block at the end of the file:

```
<!-- Keep this comment at the end of the file
Local variables:
mode: sgml
sgml-omittag:t
sgml-shorttag:t
sgml-minimize-attributes:nil
sgml-always-quote-attributes:t
sgml-indent-step:1
sgml-indent-data:t
sgml-parent-document:nil
sgml-default-dtd-file:"./reference.ced"
sgml-exposed-tags:nil
sgml-local-catalogs:("/usr/lib/sgml/catalog")
sgml-local-ecat-files:nil
End:
-->
```

This will set up a number of editing mode parameters even if you do not set up your `~/.emacs` file, but it is a bit unfortunate, since if you followed the installation instructions above, then the catalog path will not match your location. Hence you might need to turn off local variables:

```
(setq inhibit-local-variables t)
```

The PostgreSQL distribution includes a parsed DTD definitions file `reference.ced`. You may find that when using PSGML, a comfortable way of working with these separate files of book parts is to insert a proper `DOCTYPE` declaration while you're editing them. If you are working on this source, for

instance, it is an appendix chapter, so you would specify the document as an “appendix” instance of a DocBook document by making the first line look like this:

```
<!doctype appendix PUBLIC "-//OASIS//DTD DocBook V3.1//EN">
```

This means that anything and everything that reads SGML will get it right, and I can verify the document with `nsgmls -s docguide.sgml`. (But you need to take out that line before building the entire documentation set.)

B.4.2. Other Emacs modes

GNU Emacs ships with a different SGML mode, which is not quite as powerful as PSGML, but it's less confusing and lighter weight. Also, it offers syntax highlighting (font lock), which can be very helpful.

Norm Walsh offers a major mode specifically for DocBook[16] which also has font-lock and a number of features to reduce typing.

B.5. Style Guide

B.5.1. Reference Pages

Reference pages should follow a standard layout. This allows users to find the desired information more quickly, and it also encourages writers to document all relevant aspects of a command. Consistency is not only desired among PostgreSQL reference pages, but also with reference pages provided by the operating system and other packages. Hence the following guidelines have been developed. They are for the most part consistent with similar guidelines established by various operating systems.

Reference pages that describe executable commands should contain the following sections, in this order. Sections that do not apply may be omitted. Additional top-level sections should only be used in special circumstances; often that information belongs in the “Usage” section.

Name

This section is generated automatically. It contains the command name and a half-sentence summary of its functionality.

Synopsis

This section contains the syntax diagram of the command. The synopsis should normally not list each command-line option; that is done below. Instead, list the major components of the command line, such as where input and output files go.

Description

Several paragraphs explaining what the command does.

Options

A list describing each command-line option. If there are a lot of options, subsections may be used.

Exit Status

If the program uses 0 for success and non-zero for failure, then you don't need to document it. If there is a meaning behind the different non-zero exit codes, list them here.

[16] http://nwalsh.com/emacs/docbookide/index.html

Usage

Describe any sublanguage or run-time interface of the program. If the program is not interactive, this section can usually be omitted. Otherwise, this section is a catch-all for describing run-time features. Use subsections if appropriate.

Environment

List all environment variables that the program might use. Try to be complete; even seemingly trivial variables like `SHELL` might be of interest to the user.

Files

List any files that the program might access implicitly. That is, do not list input and output files that were specified on the command line, but list configuration files, etc.

Diagnostics

Explain any unusual output that the program might create. Refrain from listing every possible error message. This is a lot of work and has little use in practice. But if, say, the error messages have a standard format that the user can parse, this would be the place to explain it.

Notes

Anything that doesn't fit elsewhere, but in particular bugs, implementation flaws, security considerations, compatibility issues.

Examples

Examples

History

If there were some major milestones in the history of the program, they might be listed here. Usually, this section can be omitted.

See Also

Cross-references, listed in the following order: other PostgreSQL command reference pages, PostgreSQL SQL command reference pages, citation of PostgreSQL manuals, other reference pages (e.g., operating system, other packages), other documentation. Items in the same group are listed alphabetically.

Reference pages describing SQL commands should contain the following sections: Name, Synopsis, Description, Parameters, Usage, Diagnostics, Notes, Examples, Compatibility, History, See Also. The Parameters section is like the Options section, but there is more freedom about which clauses of the command can be listed. The Compatibility section should explain to what extent this command conforms to the SQL standard(s), or to which other database system it is compatible. The See Also section of SQL commands should list SQL commands before cross-references to programs.